



CITY OF YPSILANTI
REGULAR COUNCIL MEETING
Tuesday, January 5, 2021 @ 7:00 PM
Zoom Meeting
<https://us02web.zoom.us/j/83437350616>
One South Huron, Ypsilanti, MI 48197

Page

I. CALL TO ORDER

II. ROLL CALL

III. AGENDA APPROVAL

IV. PUBLIC COMMENT (3 MINUTES)

V. RESOLUTIONS/MOTIONS/DISCUSSIONS

- 3 - 11** A. Resolution No. 2021-001, approving the minutes of December 15, 2020.
 [2021-001 - Pdf](#)
- 12 - 18** B. Resolution No. 2021-002, adopting rules governing operations of the parking
 bureau per 102-81.
 [2021-002 - Pdf](#)
- 19 - 244** C. Resolution No. 2021-003, approving the community distribution of the Master
 Plan.
 [2021-003 - Pdf](#)
- 245 - 276** D. Resolution No. 2021-004, approving the Metro Act Permit from Great Lakes
 Comnet dated April 4, 2014 to Everstream GLC Holding Company LLC.
 [2021-004 - Pdf](#)
- 277 - 315** E. Resolution No. 2021-005, approving remainder of locations for small cell
 wireless applications 2020-002.
 [2021-005 - Pdf](#)
- 316 - 347** F. Resolution No. 2021-006, approving the Recycling and Organics Infrastructure
 Grant Agreement between the Michigan Department of Environment, Great
 Lakes , and Energy and City of Ypsilanti.
 [2021-006 - Pdf](#)
- 348 - 352** G. Resolution No. 2021-007, approving the new collective bargaining agreement
 between the City of Ypsilanti and the COAM.
 [2021-007 - Pdf](#)
- H. Discussion regarding Employee Reviews of the City Manager and City Clerk.

VI. BOARD AND COMMISSION - NOMINATIONS

A. Historic District Commission

Erika Lindsay (Reappointment Exp. 1/31/2024)
317 Prospect
Ypsilanti, MI 48198

~~Ron Rupert (Reappointment Exp. 1/31/2024) (Removed)~~
~~421 N Huron #1~~
~~Ypsilanti, MI 48197~~

VII. LIAISON REPORTS

1. SEMCOG Update
2. Washtenaw Area Transportation Study
3. Urban County
4. Ypsilanti Downtown Development Authority
5. Friends of Rutherford Pool

VIII. COUNCIL PROPOSED BUSINESS

IX. COMMUNICATIONS FROM THE MAYOR

X. COMMUNICATIONS FROM THE CITY MANAGER

XI. COMMUNICATIONS

- A. Goal Sessions - January 12th and 19th.

XII. ADJOURNMENT

353

- A. Resolution No. 2021-008, adjourning the City Council Meeting.
[2021-008 - Pdf](#)
- B. Please click [here](#) to access the City Council Contact Form. This form can be used to submit any comments/concerns you might have about this agenda.



Resolution No. 2021-001
January 5, 2021

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

THAT the minutes of December 15, 2020 be approved.

OFFERED BY: _____

SECONDED BY: _____

YES:

NO:

ABSENT:

VOTE:

This resolution is adopted by the Council of the City of Ypsilanti and approved by the Mayor this
5 day of January 2021

#Resolution No. 2021-001



MINUTES REGULAR COUNCIL Meeting

6:00 PM - Tuesday, December 15, 2020
Zoom Meeting

The REGULAR COUNCIL of the City of Ypsilanti was called to order on Tuesday, December 15, 2020, at 6:00 PM, in the Zoom Meeting, with the following members present:

PRESENT: Council Member Jennifer Symanns, Council Member Steven Wilcoxon, Mayor Pro-Tem Nicole Brown, Mayor Lois Richardson, Council Member Anthony Morgan, Council Member Annie Somerville, and Council Member Brian Jones-Chance

ABSENT:

I. CALL TO ORDER

The meeting was called to order at 6:00 p.m.

II. ROLL CALL

Council Member Morgan, seconded by Council Member Wilcoxon moved to excuse Jennifer Symanns. On a voice vote, the motion carried.

III. AGENDA APPROVAL

The agenda was approved as submitted.

IV. WORK SESSION - 6:00 - 7:00 PM

a) Water Street Development - Costs associated with remediation.

Renovare Development and Nathan Vought from the Washtenaw County Brownfield Authority provided brief presentations regarding

V. PUBLIC COMMENT (3 MINUTES)

One person spoke.

VI. CONSENT AGENDA

a) Resolution No. 2020-265, approving the Consent Agenda.

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

That the following items be approved:

1. Resolution No. 2020-266, approving the minutes of November 24, December 1, December 8, 2020.
2. Resolution No. 2020-267, approving appointments to Boards and Commissions
3. Resolution No. 2020-268, amending Resolution 2020-134 to add the City Manager as the Authorized Representative of the EDA Grant for the Ann Arbor - Ypsilanti Fiber and Conduit Network Backbone.

Council Member Anthony Morgan moved, seconded by Mayor Pro-Tem Nicole Brown, to approve Resolution No. 2020-265.

RESULT:	CARRIED.
MOVER:	Council Member Anthony Morgan
SECONDER:	Mayor Pro-Tem Nicole Brown
AYES:	Jennifer Symanns, Steven Wilcoxon, Nicole Brown, Lois Richardson, Anthony Morgan, Annie Somerville, and Brian Jones-Chance

- b) Resolutions No. 2020-266, approving the minutes from November 24, December 1, & December 8, 2020.

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

THAT the minutes of November 24, December 1, and December 8, 2020 be approved.

- c) Resolution No. 2020-267, approving appointments to Boards and Commissions.

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

THAT, the following residents be appointed to the City of Ypsilanti Boards and Commissions as indicated below:

<u>NAME</u>	<u>BOARD</u>	<u>EXPIRATION</u>
Brian Coffey 1807 Roosevelt Ypsilanti, MI 48197 (New Appointment)	Ethics Commission	2/1/2024
James Ratzlaff 12/31/2023 305 S Washington Ypsilanti, MI 48197 (New Appointment)	Historic District Commission	

- d) Resolution No. 2020-268, amending Resolution 2020-134 to add the City Manager as the Authorized Representative of the EDA Grant for the Ann Arbor - Ypsilanti Fiber and Conduit Network Backbone.

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

WHEREAS, the Economic Development Administration's (EDA's) mission is to lead the federal economic development agenda by promoting innovation and competitiveness, preparing American regions for economic growth and success in the worldwide economy, and

WHEREAS, the EDA solicits applications from applicants in order to provide investments that support construction, non-construction, planning, technical assistance, and revolving loan fund projects under EDA's Public Works program and EAA program, and

WHEREAS, The LDFA has a goal to establish a connected high-tech ecosystem with infrastructure;

WHEREAS, An integral part of this goal is the connection of the Ann Arbor downtown Tech Park with the City of Ypsilanti and the American Center for Mobility;

WHEREAS, The City of Ann Arbor has already installed conduit and fiber in the downtown area which could be leveraged, but with little exception the system is full and cannot handle additional needs,

WHEREAS, the installation of a robust conduit and fiber system linking Downtown Ann Arbor to Ypsilanti, running through Ypsilanti Township and Pittsfield Township will leverage existing infrastructure investments and make it easier for company to innovate and grow, and

WHEREAS, Ann Arbor SPARK, in partnership with its local partners in the City of Ann Arbor, City of Ypsilanti, Ypsilanti Township, Pittsfield Township will file an application for the ANN ARBOR -YPSILANTI FIBER AND CONDUIT NETWORK BACKBONE , with the EDA under Funding Opportunity number PWEAA2020 requesting \$3,000,000, and

WHEREAS, the Ann Arbor/Ypsilanti Smartzone will provide a match of \$600,000 to construct the ANN ARBOR -YPSILANTI FIBER AND CONDUIT NETWORK BACKBONE which will be used as a matching grant funds that are a cash match that is readily available and unencumbered, and

WHEREAS, Ann Arbor SPARK will be the lead applicant, with City of Ann Arbor, City of Ypsilanti, Ypsilanti Township and Pittsfield Township as the co-applicants, and

WHEREAS, Ann Arbor SPARK will administer the grant, and

WHEREAS, City of Ypsilanti will not incur any costs associated with construction of the Fiber and Conduit Network Backbone

WHEREAS, Ypsilanti representatives of the effected taxing units will be given an opportunity for public comment at an informational meeting held on a date yet to be determined, and

NOW THEREFORE BE IT RESOLVED THAT, the City Manager, Frances McMullan, is the authorized representative on behalf of the EDA Grant, and is authorized to sign any and all documentation related to the grant.

VII. RESOLUTIONS/MOTIONS/DISCUSSIONS

- a) Resolution No. 2020-269, awarding the bid to Clean Air Concepts to replace the vehicle exhaust system on the YFD's apparatus floor.

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

Whereas, The YFD was awarded the Fiscal Year (FY) 2019 Assistance to Firefighters Grant (AFG) to include the installation of a direct source capture exhaust system. The amount of the grant awarded was \$69, 943.64. The YFD's 10% share is \$6,994.36; and

WHEREAS, Clean Air Concepts provided the lowest bid at \$57, 207.00; and

WHEREAS, YFD is requesting approval to award the bid to Clean Air Concepts to start the process of replacing the vehicle exhaust system on the YFD's apparatus floor; and

WHEREAS, This new exhaust capture system will essentially eliminate 100 percent of the diesel and automotive exhaust gases currently emitted presenting danger to fire personnel and the community; and

Whereas, Clean Air Concepts will provide the associated labor, materials, and equipment needed to complete the exhaust capture system including but not limited to all things related to removing diesel and automotive exhaust gases within the confines of the Ypsilanti Fire Station; and

Whereas, The entire project will include the purchase, delivery, installation of the direct source capture exhaust system and complete repair to the existing manual ventilation system. Per the AFG, the funds will cover all associated permit fees, all electrical modifications, a 5-year warranty for parts and labor, basic system training, and any modifications that must be made to the current exhaust systems on the apparatus. Remaining funds will be used to repair the existing manual ventilation system.

Now therefore be it resolved that the Ypsilanti City Council approves awarding the bid to Clean Air Concepts, to start the process of replacing the vehicle exhaust system on the YFD's apparatus floor.

Council Member Steven Wilcoxon moved, seconded by Mayor Pro-Tem Nicole Brown, to approve Resolution No. 2020-269.

RESULT:	CARRIED.
MOVER:	Council Member Steven Wilcoxon
SECONDER:	Mayor Pro-Tem Nicole Brown
AYES:	Jennifer Symanns, Steven Wilcoxon, Nicole Brown, Lois Richardson, Anthony Morgan, Annie Somerville, and Brian Jones-Chance

- b) Resolution No. 2020-270, approving the proposal from OHM for design engineering services for the Forest Street Bridge.

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

Whereas, the City of Ypsilanti have been allocated funds by the Michigan Department of Transportation to perform rehabilitation work on the Forest Street Bridge; and,

Whereas, the City engineer OHM has prepared a proposal to provide design engineering services for the project; and,

Whereas, design engineering is necessary to begin the project in the 2022 construction season;

Now therefore be it resolved that that the City of Ypsilanti approves the proposal from OHM for design engineering services for an amount of \$79,500.

THAT the City Clerk is authorized to sign this proposal and any change orders may be approved by the City Manager, to facilitate the completion of this work.

Council Member Jennifer Symanns moved, seconded by Council Member Annie Somerville, to approve Resolution No. 2020-270.

RESULT:	CARRIED.
MOVER:	Council Member Jennifer Symanns
SECONDER:	Council Member Annie Somerville
AYES:	Jennifer Symanns, Steven Wilcoxon, Nicole Brown, Lois Richardson, Anthony Morgan, Annie Somerville, and Brian Jones-Chance

- c) Resolution No. 2020-271, approving funding for the Huron River Road Diet and Conceptual Engineering Study.

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

Whereas, the City of Ypsilanti have been allocated Federal funds through the Washtenaw Area Transportation Study to reconstruct Huron River Drive between Cornell and Leforge; and,

Whereas, the City engineer OHM has prepared a proposal to provide a road diet study and conceptual engineering design for the project; and,

Whereas, the road diet study and conceptual design is necessary to identify necessary improvements to make the road safe for motorized and non-motorized users;

Now therefore be it resolved that that the City of Ypsilanti approves the proposal from OHM for the road diet study and conceptual engineering design for an amount of \$95,910.

THAT the Mayor is authorized to sign this proposal and any change orders may be approved by the City Manager, to facilitate the completion of this work.

Council Member Jennifer Symanns moved, seconded by Mayor Pro-Tem Nicole Brown, to approve Resolution 2020-271.

RESULT:	CARRIED.
MOVER:	Council Member Jennifer Symanns
SECONDER:	Mayor Pro-Tem Nicole Brown
AYES:	Jennifer Symanns, Steven Wilcoxon, Nicole Brown, Lois Richardson, Anthony Morgan, Annie Somerville, and Brian Jones-Chance

- d) Resolution No. 2020-272, authorizing the City Manager to adjust the budget to pay invoices for the Rutherford Pool.

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

WHEREAS, The City of Ypsilanti approved \$25,000 in support of the Rutherford Pool Renovations in 2019; and

WHEREAS, the remainder of funding will be paid from Friends of Rutherford Pool and a Michigan Department of Natural Resources Land and Water Conservation Fund Grant awarded in November 2018; and

WHEREAS, The City must be reimbursed the grant award of \$300,000 and make the capital improvement funds available by budget amendment.

NOW THEREFORE BE IT RESOLVED THAT the Ypsilanti City Council authorizes the City Manager to adjust the budget to pay invoices for the Rutherford Pool Renovations.

Council Member Anthony Morgan moved, seconded by Council Member Steven Wilcoxon, to approve Resolution No. 2020-272.

RESULT:	CARRIED.
MOVER:	Council Member Anthony Morgan
SECONDER:	Council Member Steven Wilcoxon
AYES:	Jennifer Symanns, Steven Wilcoxon, Nicole Brown, Lois Richardson, Anthony Morgan, Annie Somerville, and Brian Jones-Chance

e) Resolution No. 2020-273, awarding Educate Youth a mini-grant. (Added)

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

WHEREAS, In the recently concluded FY 2020-2021, the City Council approved a \$25,000 grant to organizations that serve the youth in the City; and

WHEREAS, Educate Youth is an organization currently serving the youth in the City of Ypsilanti; and

WHEREAS, Educate Youth has submitted a grant application for \$5,000; and

NOW THEREFORE BE IT RESOLVED that the Ypsilanti City Council approves a mini grant to Educate Youth in the amount of \$5,000 to support youth programing.

Council Member Annie Somerville moved, seconded by Council Member Jennifer Symanns, to approve Resolution No. 2020-273.

RESULT:	CARRIED.
MOVER:	Council Member Annie Somerville
SECONDER:	Council Member Jennifer Symanns
AYES:	Jennifer Symanns, Nicole Brown, Lois Richardson, Anthony Morgan, Annie Somerville, and Brian Jones-Chance
ABSTAINED:	Steven Wilcoxon

VIII. LIAISON REPORTS

1. SEMCOG Update - General Assembly Meeting in January. Program offers free videos for businesses.
2. Washtenaw Area Transportation Study - None
3. Urban County - None
4. Ypsilanti Downtown Development Authority - Virtual pub crawl and gift card drawings. Thanked Director Akers and DPS for the holiday lights.
5. Friends of Rutherford Pool - Roof construction and solar panel update.

IX. COUNCIL PROPOSED BUSINESS

Symanns

- City Manager and City Clerk review format will be on the next agenda.

Brown

- Tree trimming is ongoing on the South Side.

Somerville

- Thanked staff for the holiday lights.

Jones-Chance

- Stated that we need to keep the affordable housing conversation going.

Morgan

- YPAC meeting is this Thursday.
- CIVIC program to engage law enforcement.
- 100 Families 100 Homes Program
- Cream Inc's Covid Relief Tour event on December 21st.
- Everybody Eating for families to pick up meals 21-23.
- Thanked Ron Akers, fire department, and staff.

Wilcoxon

- Thanked Mr. Akers for helping a resident.
- Sustainability Commission is going through their goals.
- Penn Dam removal bids are under review. Public engagement will begin.

X. COMMUNICATIONS FROM THE MAYOR

Richardson

- Received a request from Supervisor Stumbo asking the City to support a Representative Peterson's Bill to get a sickle cell license plate.

Council Member Somerville, seconded by Council member Wilcoxon moved to support Representative Peterson's Bill and forward the letter to the senate majority leader to hold a hearing.

- Asked to be notified of action against the City when it occurs.
- Asked for recommendations to the HRC.
- Women and Men Working for Change will be serving dinner on December 23rd.
- Parkridge Center will open virtual learning labs when school reopens.
- Excited that the vaccine is beginning to be distributed but masks and distancing are still important.
- Wished everyone a safe and prosperous holiday season and new year.

XI. COMMUNICATIONS FROM THE CITY MANAGER

- Goal setting is tentatively scheduled for January 12th and 19th.

XII. COMMUNICATIONS

XIII. REMARKS FROM THE MAYOR

XIV. ADJOURNMENT

- a) Resolution No. 2020-274, adjourning the City Council Meeting.

The meeting was adjourned at 8:57 p.m.

Council Member Anthony Morgan moved, seconded by Council Member Steven Wilcoxon, to approve Resolution No. 274.

RESULT:	CARRIED.
MOVER:	Council Member Anthony Morgan
SECONDER:	Council Member Steven Wilcoxon
AYES:	Jennifer Symanns, Steven Wilcoxon, Nicole Brown, Lois Richardson, Anthony Morgan, Annie Somerville, and Brian Jones-Chance

- b) Please click [here](#) to access the City Council Contact Form. This form can be used to submit any comments/concerns you might have about this agenda.



REQUEST FOR LEGISLATION

TO: Mayor and City Council
FROM: Bonnie Wessler
DATE: January 5, 2021
SUBJECT: Parking Violations Bureau: Update to Rules

DESCRIPTION:

Parking Violations Bureau: Update to Rules

SUMMARY:

The Parking Violations Bureau, the administrative entity that oversees parking enforcement per 102-81, operates by a slate of rules that were approved by City Council in 2016. Due to the changes since 2016, staff are proposing an update to those rules. Highlights include:

- Amending the specific references to fees and fines so that they refer to the fee schedule
- Describing the procedure to follow up with outstanding tickets, including referrals to court and collections
- Allowing for staff to perform "courtesy voids" of tickets in certain situations, including:
 - Handicap permit possessed but not displayed
 - Residential, employee, visitor, or other pass possessed but not displayed, for the first such violation per calendar year
 - Stolen vehicle

RECOMMENDED ACTION: Approval

CITY MANAGER APPROVAL: _____ COUNCIL AGENDA DATE: _____

CITY MANAGER COMMENTS: _____

FISCAL SERVICES DIRECTOR APPROVAL: _____



Resolution No. 2021-002
January 5, 2021

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

WHEREAS, the Ypsilanti City Council amended Ypsilanti City Code Section 102-81 to establish a Parking Violations Bureau for the purpose of handling all alleged parking violations within the City of Ypsilanti pursuant to the Revised Judicature Act, Public Act 154 of 1968, as amended (MCL 600.8395); and

WHEREAS, the Ypsilanti City Council had adopted rules in 2016 governing the operation of the Parking Violations Bureau with Resolution 2016-005; and

WHEREAS, the Rules and Regulations have been updated to reflect updates and changes in the system since 2016; and

WHEREAS these Rules and Regulations are consistent with the Ypsilanti City Code, resolutions adopted by this City Council, the rules and procedures of the 14A2 District Court, and the laws of the State of Michigan;

NOW THEREFORE BE IT RESOLVED that Ypsilanti City Council approves the attached Rules and Regulations of the Parking Violations Bureau.

OFFERED BY: _____

SECONDED BY: _____

YES: NO: ABSENT: VOTE:

This resolution is adopted by the Council of the City of Ypsilanti and approved by the Mayor this 5 day of January 2021

#Resolution No. 2021-002

**CITY OF YPSILANTI
Parking Violations Bureau
Rules and Regulations**

Preamble

These Rules and Regulations of the Parking Violations Bureau ("Bureau") are established for the operation of the Bureau, pursuant to Chapter 102, Article III, Division 2, Section 102-81(b) of the Code of Ordinances for the City of Ypsilanti.

Section 1: Compliance with Laws

The rules, regulations, and procedure of the Bureau will comply at all times with applicable ordinances and resolutions of the City of Ypsilanti; the rules and procedures of the 14A2 District Court; and the laws of the State of Michigan.

Section 2: Methods of Payment

A person who receives a parking violation notice issued by the City of Ypsilanti and wishes to admit responsibility may do so by paying to the Bureau the full amount of the applicable fines and costs as follows:

- The Bureau will accept the following methods of payment: Cash; check or money order, payable to the City of Ypsilanti; or credit card, Visa is not accepted.
- Persons may pay in person by any of the methods above during regular office hours.
- Persons may pay by check or money order by mail or drop box. Payments will be accepted in the drop box until midnight on the due date.
- There is a 3 percent charge for paying with a credit card and a \$45 fee for returned checks.
- Payments are considered paid when received by the Bureau.

Section 3: Contesting a violation

If a person receives a parking violation notice issued by the City of Ypsilanti and denies responsibility or desires to plea responsible with an explanation, they must do so in accordance with Article III, Division 2, Section 102-81(f) of Code of Ordinances for the City of Ypsilanti. The Bureau has created a form for convenience, but use if this form is not required. Respondents may contest a violation to the Bureau in person or by mail. The amount of the fine for the contested violation will be the amount the fine would have been as if it had been paid on the day the Bureau receives the necessary submittals in compliance with Section 102-81(f). Once a violation is properly contested,

the Bureau will forward the submittals and all necessary paperwork to the 14A2 District Court and the Bureau will not be able to accept payment. If a respondent is found responsible, additional costs and fees may be applied by the 14A2 District Court according to its rules and procedures.

Section 4: Failure to Respond

If a person receives a parking violation notice issued by the City of Ypsilanti and fails to respond by either admitting responsibility and paying all fines and costs or by properly contesting a violation notice, the Bureau will notify the respondent by first-class mail to the registered owner of the vehicle at the owner's last known address that failure to respond accordingly will result in a citation being filed with the 14A2 District Court, according to Article III, Division 2, Section 102-81(d) of Code of Ordinances for the City of Ypsilanti. Two notifications will be made by the Bureau before a citation is filed. The first subsequent notification will be made 30 days after the notice of violation issued. The second subsequent notification will be made 60 days after the notice of violation is issued. A citation will be issued if no proper response is made 90 days after the notice of violation is issued.

Citations issued must be delivered by first-class mail to the registered owner of the vehicle at the owner's last known address, with a copy to the 14A2 District Court. After a citation is issued, all payments for parking violations must be made to the 14A2 District Court only and the Bureau will not be able to accept payment. The 14A2 District Court may apply additional costs and fees according to its rules and procedures.

(Established: January 5, 2015)

**CITY OF YPSILANTI
Parking Violations Bureau
Rules and Regulations**

Preamble

These Rules and Regulations of the Parking Violations Bureau ("Bureau") are established for the operation of the Bureau, pursuant to Chapter 102, Article III, Division 2, Section 102-81(b) of the Code of Ordinances for the City of Ypsilanti.

Section 1: Compliance with Laws

The rules, regulations, and procedure of the Bureau will comply at all times with applicable ordinances and resolutions of the City of Ypsilanti; the rules and procedures of the 14A2 District Court; and the laws of the State of Michigan.

Section 2: Methods of Payment

A person who receives a parking violation notice issued by the City of Ypsilanti and wishes to admit responsibility may do so by paying to the Bureau the full amount of the applicable fines and costs as follows:

- The Bureau will accept the following methods of payment: Cash; check or money order, payable to the City of Ypsilanti; or credit card, ~~Visa is not accepted.~~
- Persons may pay in person by any of the methods above during regular office hours.
- Persons may pay by check or money order by mail or drop box. Payments will be accepted in the drop box until midnight on the due date.
- ~~There is a 3 percent charge for paying with a credit card and a \$45 fee for returned checks.~~
- Fees for returned checks and for credit card payments, as well as the types of cards accepted, will be as set by the fee schedule &/or agreements with the ticket administrator. All fees associated with payments and returned payments will be clearly indicated prior to beginning a transaction.
- Payments are considered paid when received by the Bureau or its designee.

City Council may choose from time to time to offer an amnesty or to permit community service in lieu of monetary payment.

Council may choose to permit payment plans at some future date.

Section 3: Contesting (or appealing) a violation

If a person receives a parking violation notice issued by the City of Ypsilanti and denies responsibility or desires to plea responsible with an explanation, they must do so in accordance with Article III, Division 2, Section 102-81(f) of Code of Ordinances for the City of Ypsilanti. The Bureau has created a form for convenience and enabled appeals online, but use of ~~this form~~ these forms are not required. Respondents may contest a violation to the Bureau in person, online, by e-mail, or by mail. The amount of the fine for the contested violation will be the amount the fine would have been as if it had been paid on the day the Bureau receives the necessary submittals in compliance with Section 102-81(f). All appeals will be reviewed for violations that can be addressed by the Bureau prior to passing the appeal to Court. The Bureau may void the ticket or adjust the fine or penalty in the following circumstances:

- Broken meter or other failure of payment system, when proof of such is provided
- Officer error, when such error is confirmed by said officer
- Residential, employee, visitor, or service vehicle permit possessed but not displayed, for the first offense per calendar year
- Handicap permit possessed but not displayed
- When the vehicle ticketed had been stolen and was not possessed by the registered owner
- As part of a Council-approved fine or penalty amnesty program
- Issues arising during a state of emergency, including pandemic or weather related emergencies

Once a violation is properly contested, and the Bureau has made the determination that it does not fall within their power to void or adjust, the Bureau will forward the submittals and all necessary paperwork to the 14A2 District Court and the Bureau will not be able to accept payment. If a respondent is found responsible, additional costs and fees may be applied by the 14A2 District Court according to its rules and procedures and will be payable to that Court.

Section 4: Failure to Respond

If a person receives a parking violation notice issued by the City of Ypsilanti and fails to respond by either admitting responsibility and paying all fines and costs or by properly contesting a violation notice, the Bureau will notify the respondent by first-class mail to the registered owner of the vehicle at the owner's last known address that failure to respond accordingly will result in a citation being filed with the 14A2 District Court, according to Article III, Division 2, Section 102-81(d) of Code of Ordinances for the City of Ypsilanti.

~~Two~~ Three notifications will be made by the Bureau before a citation is filed for the majority of tickets.

- The first ~~subsequent~~ notification after initial issuance of the ticket will be made no fewer than 5 days after the notice of violation issued (or as soon as such information is obtained, if it takes more than five days to obtain the information from the state or other agencies).
- The second after 30 days after the notice of violation issued.
- The ~~second~~ third notification will be made ~~60~~ 90 days after the notice of violation is issued. A citation will be issued if no proper response is made ~~90~~ 100 days after the notice of violation is issued for tickets other than parking without a permit (residential or employee), parking over the legal limit, display advertising, display cars for sale on city property, parked for over 48 hours, improper parking, parking not fully within a metered space, parked to wash/polish/grease/repair vehicle, and expired meter. All other notices of violations will be submitted to district court.

Citations issued will be sent by first-class mail to the registered owner of the vehicle at the owner's last known address, with a copy to the 14A2 District Court. After a citation is issued, all payments for parking violations must be made to the 14A2 District Court only and the Bureau will not be able to accept payment. The 14A2 District Court may apply additional costs and fees according to its rules and procedures.

For unpaid tickets older than 100 days that have not been converted into citations, notices will be mailed every six months.

(Established: January 5, 2015)



RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

WHEREAS, the City of Ypsilanti adopted the Shape Ypsilanti Master Plan in 2013 which establishes guiding values and policy recommendations for the City;

WHEREAS, the Planning Commission determined in 2018 that a Master Plan update was necessary;

WHEREAS, the Ypsilanti Sustainability Commission drafted a Sustainability Plan in which the Planning Commission subsequently determined to incorporate into the Master Plan as a full chapter;

WHEREAS, the Citizen Committee on Housing Affordability and Accessibility drafted a Report and Recommendations;

WHEREAS, the Ypsilanti Planning Commission has the responsibility of developing a Master Plan and any updates;

WHEREAS, the Ypsilanti City Council has the responsibility of distributing a Master Plan and any updates for the public comment period in accordance to PA 33 of 2008 (Michigan Planning Enabling Act);

WHEREAS, the Ypsilanti Planning Commission supports the draft Master Plan update and recommended City Council distribute the Plan for public comment;

NOW THEREFORE BE IT RESOLVED, that the Ypsilanti City Council distribute the Plan for public comment;

OFFERED BY: _____

SECONDED BY: _____

#Resolution No. 2021-003

YES:

NO:

ABSENT:

VOTE:

This resolution is adopted by the Council of the City of Ypsilanti and approved by the Mayor this
day of

#Resolution No. 2021-003

Master Plan Update Draft

DRAFT

SHAPE YPSILANTI

Title Page

To be formatted during new formatting/design.

DRAFT

This page is intentionally left blank

Acknowledgements

A special thanks to all who gave their time, energy and input to make this plan possible, especially

DRAFT

SHAPE YPSILANTI STEERING COMMITTEE

Rod Johnson, Planning Commission Chair
Richard Murphy, Planning Commission Vice-Chair
Phil Hollifield, Planning Commissioner
Pete Murdock, City Council Member, Ward 3
Ricky Jefferson, City Council Member, Ward 1
Anne Stevenson, Historic District Commission, Ward 2
D'Real Graham, Recreation Commission
Leigh Greden, EMU Administration, DDA Chair & Eastern Leaders' Group
Co-Chair
Bee Roll, Owner of beezy's cafe
Teresa Gillotti, City Planner at City of Ypsilanti
Desmond Miller, EMU student & Student Council President

YPSILANTI CITY COUNCIL

Paul Schreiber, Mayor
Lois Richardson, Mayor Pro-Tem, Ward 1
Ricky Jefferson, Ward 1
Susan Moeller, Ward 2
Daniel Vogt, Ward 2
Peter Murdock, Ward 3
Brian Robb, Ward 3

CITY OF YPSILANTI PLANNING COMMISSION

Rod Johnson, Chair
Richard Murphy, Vice-Chair
Mark Bullard
Phil Hollifield
Kelly Weger
Gary Clark
Brett Lenart
Cherly Zuellig
Daniel Lautenbach
Anthony Bedogne
Heidi Jugenitz

CITY STAFF

Ralph Lange, City Manager
Nan Schuette, Executive Secretary

Teresa Gillotti, Planner II
Bonnie Wessler, Planner I
Emily Baxter, Planning Assistant

ALL WHO PARTICIPATED


Over 400 focus group and charrette participants
2,038 people who like Shape Ypsi on Facebook
128 twitter followers
1,387 people who visited ShapeYpsi.com
155 e-mail newsletter subscribers
All the people who shared in this plan in thought, word and de

Table of Contents

To be finalized with page numbers after new design/formatting.

DRAFT

Map 1: Regional Context, City of Ypsilanti



Source: Washtenaw County GIS

Chapter 1: Small City. Unique History. New Plan.

“After careful review of many recent local plans, the City requests that respondents set aside existing templates and consider instead new approaches to a hybrid policy/land-use plan for the City of Ypsilanti.” -Request for Proposal, City of Ypsilanti, July 2012

The City of Ypsilanti is a small city of 4.3 square miles in southeastern Michigan. Located in Washtenaw County, it is within 15 miles of Detroit Metro Airport, 10 miles of Ann Arbor and 35 miles from Detroit. A distinctly urban place, its population density is one of the highest in Washtenaw County, at roughly 6.4 people per acre.

Ypsilanti is a historic community. It was the second city to incorporate in the State of Michigan, and has the fifth largest historic district in the state. Eastern Michigan University (EMU) was founded here in 1849. Transportation features prominently in Ypsilanti’s history, with the Chicago Road and Michigan Central Railroad driving the growth of the city’s various industries through the 19th and early 20th century. In the mid-20th century, the Willow Run plant and airport, and I-94 and US-23 continued the city’s location advantages, while automotive plants in and around the city tied the city’s manufacturing economy to transportation as well.

EMU continues to be a major employer and economic driver. It is the largest land owner in the City and the largest taxpayers are now primarily rental property owners.

However, the City’s economy has fundamentally changed with the decline of the automotive industry and manufacturing. Since 2001, Ypsilanti has lost close to 1,600 manufacturing jobs. This economic shift has caused both a reduction in real and personal property tax revenue, and an increase in vacant or under utilized industrial spaces. No single industry has emerged to replace the jobs and taxes generated by the automobile industry.

Instead, several sectors have potential to bring new vitality – small manufacturing and craft production, creative economy, renewable energy, and food. Summer events are a regional draw, and more recent efforts such as the Krampus Festival and Mittenfest foster the growing arts and music communities. Solar Ypsi and other groups support renewable energy efforts, while the Historic District Commission has adopted guidelines for solar panels. A growing reputation among foodies also has helped Ypsilanti secure its place in the region for both

every day and destination restaurants. Growing food in the City is supported by non-profits like Growing Hope and permaculture groups.

The City prides itself on its diversity. Ypsilanti has been a leader in civil rights, as the first City in Michigan to pass a living wage ordinance and an ordinance banning discrimination in housing, employment and public accommodation based on sexual orientation, gender identity/transgender status, or body weight. The U.S. Census analysis of 2010 population data ranked Ypsilanti as one of the top 5 Michigan Cities for gay couples.

At the same time, the City faces challenges. Approximately 40% of the City’s land area is used by tax exempt owners, limiting the tax base of the City. The building stock, while historic and often a selling point for the community, can decline in value without upkeep. The foreclosure crisis and great recession of 2008 hit Ypsilanti, like many Michigan cities, with the loss of jobs and home values. The City has one of higher unemployment rates in Washtenaw County.

The first year for the merged Ypsilanti Community School District was 2013. Until the district is on its feet, the schools will have an unknown impact on housing values.

Finally, the City must pay about 10% of its current budget on bonds for the previous acquisition, building demolition, and environmental cleanup of Water Street, a redevelopment area assembled by the City more than a decade ago. The last Master Plan, adopted in 1998, assumed that industrial users would remain. The economic shifts and the housing crisis that have taken place since have changed that assumption. This plan assumes growth on a micro-economic level. It concentrates on the assets of the people, businesses, buildings, and infrastructure. It uses these assets to set the framework for future development, redevelopment and preservation in the community. The plan also lays the groundwork for form-based zoning in Ypsilanti, which will implement goals of the master plan through regulation by street type, building typology as well as use.

THE PROCESS & THE PLAN

In 2012, the City of Ypsilanti received funding to draft a master plan and zoning ordinance as part of the U.S. Housing and Urban Development Sustainable Community Challenge Grant awarded to Washtenaw County. While the City of Ypsilanti has a long history of planning (see list on this page), the last Master Plan was over a decade old. Due to the challenges facing the City, staff, elected and appointed officials requested the master plan recognize both the good and the bad, set realistic goals, and emphasize policy as well as land use.

After selecting a consultant team to assist in the process, the City launched a community-driven process, called “Shape Ypsilanti”, to create the Master Plan in January 2013. The process utilized social media and a website separate from the City’s own to engage, educate, and empower. Feedback from on-line sources was used as fodder for discussions and decisions at a series of events, varying in size from interviews to two rounds of focus groups to community-wide, four-day charrettes in March and April 2013. Events were attended by more than 400 individuals. In 2018, the City of Ypsilanti decided to update its master plan to keep in line with the Michigan Planning Enabling Act of 2008 requirement to review the document every five years, to check its progress on its action items, and determine next steps for future projects. The largest update is the incorporation of a Sustainability chapter that focuses on practices and policies to build resiliency against environmental change. The City’s intent in adopting a Sustainability chapter as part of the Master Plan is to use a sustainability framework in long-term land use decisions, including zoning.

The following document is the resulting Master Plan, grounded in real challenges and opportunities. The plan is divided into the following chapters:

Chapter 2 – Guiding Values
Chapter 3 – Ypsilanti Now
Chapter 4 – City Framework
Chapter 5 – Transportation
Chapter 6 – Centers

Chapter 7 – Neighborhoods
Chapter 8 – Corridors
Chapter 9 – Districts
Chapter 10 - Redevelopment Areas
Chapter 11 - Implementation

The solutions were created by the community for the community. However, many of the requests brought forth - more police, cameras in high-crime areas, recreation and programs for youth, street maintenance and repair, better public schools - are not within the scope of this plan as prescribed by Michigan State Law. These pressing issues can, and perhaps should, take precedence in allocating scant municipal resources over many of the projects and plans laid out in this document.

PREVIOUS PLANS REVIEWED FOR THIS PROCESS

Olmsted Brothers Park Plan (Pre-World War II)
1971 Ypsilanti I, II, III
1993 Blueprints for Downtown
1996 Comprehensive Economic Development Strategy Plan
1998 City Master Plan
2001 Cross Street Neighborhood Improvement Plan
2008 Recreation Plan
2008 Downtown Blueprint
2010 Non-Motorized Transportation Plan
2012 Climate Action Plan
Washtenaw County Consolidated Plan
Washtenaw County Affordable Housing Needs Assessment
Ypsilanti 2020 Task Force Report
ReImagine Washtenaw Avenue Corridor Redevelopment Strategy (2010)
SEMCOG & Washtenaw County Community Economic Development Plan
South of Michigan Avenue Community Needs Assessment
2018 Energy Plan
2015 Housing Affordability and Economic Equity Analysis
Huron Watershed Council

Chapter 2: Guiding Values

“What would you whisper into the ears of decision makers, like City Council?”

-Instructions to participants in Guiding Values Focus Groups

Appointed and elected officials use the City’s Master Plan as a guide when making decisions with limited resources about land use, housing, transportation, equity, quality of life, and sustainability. Traditionally, decision-makers reference the Master Plan when deciding what uses should be allowed on a parcel of land, whether and how a building can be constructed or an older building renovated; and how bicycle routes and streets are laid out. The City of Ypsilanti requested the guiding values for this Master Plan go beyond the usual scope of a land use plan and apply to budget decisions, allocation of resources, and general policy for the City. This chapter provides a list of guiding values from the community and a decision-making rubric for City leaders, not only for land use but for over arching policy.

These guiding values are based on focus group sessions held in January and February 2013 and then presented to the public in the Discover Charrette in March of the same year. The sessions were held in different locations across the city. The over 50 participants represented Eastern Michigan students, business groups, historic preservation groups, real estate developers, arts groups, event organizers, churches, youth groups and residents from neighborhoods South of Michigan and on the west side of Ypsilanti. Two Saturday sessions were also held at a downtown restaurant for the general public.

The following ten values were mentioned by all the groups when they were asked what the guiding values should be for the City:

Safety comes first

The City is dedicated to being a secure place to live, study, work, visit, and play. While budgets for safety services are separate from the Master Plan, decisions about land use, housing, transportation, equity and sustainability should protect and enhance safety.

Diversity is our strength

Ypsilanti is a multicultural city with people from different races, sexual orientations, incomes, and walks of life. The ability to be who you are attracts

people to Ypsilanti. In decisions, the City will ask how actions welcome, provide opportunity for and sustain its diverse population.

Ypsilanti is sustainable

Every decision should foster the future, while replenishing resources – natural, economic and social. Efforts to make the city an environmentally sustainable place will continue. The financial viability of the city in 20 years should factor into decisions. Equity for everyone in Ypsilanti is another priority.

The Ypsilanti Sustainability Commission drafted a Sustainability Plan in 2020, which was determined by the Planning Commission to be placed in the Master Plan. This Sustainability Plan is located in Chapter 12 of this Plan.

Communication is key

Information, especially from the City, should be shared with all neighborhoods and groups in the manner that will reach them, be that on the web, in the mail or via flyers. Programs should reach out to all, giving everyone a chance.

Anyone, no matter what age or income, can find a place to call home in Ypsilanti

Housing options should match the needs of the people. Those needs will change as residents age and move. The need for safe, quality, affordable homes for all should be factored into decisions.

The Citizen Committee on Housing Affordability and Accessibility drafted a report and recommendations from 2017 to 2020. The report and recommendations can be found in full in the Appendix of this Plan.

Anyone can easily walk, bike, drive or take transit from anywhere in Ypsilanti and to anywhere else in Ypsilanti and beyond

The citizens of Ypsilanti want a complete transportation system with room on the roads for cars, buses, bicycles, and pedestrians, including those in wheelchairs or with strollers. The City is committed to integrating into the emerging regional transit system while enhancing the walkability of the community.

Ypsilanti is a great place to do business, especially the green and creative kind

The City of Ypsilanti will create a business environment that fosters the creativity and energy personified by City's best known businesses, while attracting new businesses and fostering locally grown enterprises. Green and sustainable businesses, like those that have already developed in Ypsilanti, will be encouraged.

Everyone in the region knows Ypsilanti has great things to do in great places that are in great shape!

Ypsilanti has a wealth of beautiful places, historic buildings, and fun activities. These assets will be built upon and shouted from the rooftops. Ypsilanti's image should match its vibrancy. Vibrancy comes from preserving, using, and enriching all places. While permanent uses may not be found for vacant buildings immediately, temporary or pop-up activities should be options.

Ypsilanti is an asset of Eastern Michigan University, and Eastern Michigan University is an asset of Ypsilanti

The futures of Ypsilanti and Eastern Michigan University are entwined. The City will plan and develop policies for Ypsilanti to be a home for the university itself, as well as its students, faculty and staff. The physical planning of the community and university should be coordinated, as well as efforts to welcome and integrate Ypsilanti as treasured part of the EMU experience.

We can only achieve our vision by building a community amongst ourselves and with our neighbors

Relationships are the key to success. While each group and neighborhood needs space for themselves, the City thrives when we work together. The community includes not only those who live in the City, but those who work and study here and own businesses as well as Ypsilanti Community Schools, neighboring municipalities, the City of Ann Arbor and Washtenaw County.

The table on the following pages is a decision making rubric for elected and appointed officials, with questions and measures for each guiding value. The chapter following the decision rubric explores the current state of the City in terms of safety, diversity and sustainability, the core values to which all of the others relate.

DECISION MAKING RUBRIC

When making decisions, City of Ypsilanti officials, staff and citizens will ask if the option chosen furthers at least one, if not several of the values below, while not damaging the others. Starting with the adoption of this plan until the next master plan is written, it is incumbent upon the responsible party to track the “measures” listed as they provide some insight into whether the outcomes of City efforts are effective responses the decision-making questions.

Guiding Value	Questions	Measures	Responsible Party
Safety comes first	Does this action protect or enhance safety?	Trend in crime rates	Police Department (PD)
	Is natural surveillance, where people can see what is going on in public places from private ones, created?	% of functioning street lights	Department of Public Safety (DPS)
	Are public spaces, private spaces, and semi-public spaces easily known, so the average person knows where the street ends and someone's property begins?	Design standards that differentiate between public and private space	Community & Economic Development (CED)
	Are public spaces (parks, streets, parking lots) well lit?	Enforcement of parking lot lighting requirements	CED
	Are the places for emergency vehicles clear, accessible, and placed to best help first responders do their job?	# of pedestrians/bicyclist crashes	DPS
Diversity is our strength	Does this action welcome and/or sustain Ypsilanti's diverse population?	Changes in ethnic mix, city-wide and by neighborhood	CED
	Does this action welcome new groups to Ypsilanti?	Changes in diversity of ages by neighborhood	CED
	Does this action reward or privilege one group over another?	# of public facilities and/or buildings with universal design (accessibility measure)	DPS
	Are policies flexible enough to allow and encourage diversity?	Trends in business types (number and % of tax base)	Building Department
	Does this action create/maintain/improve the diversity of the business mix?	Change in income city-wide and by neighborhood	CED

Guiding Value	Questions	Measures	Responsible Party
Ypsilanti is sustainable	Does this action replenish resources?	Trend in greenhouse gas emissions	DPS
	Does this action make Ypsilanti a more environmentally sustainable place?	# of kilowatts produced by renewable energy installations	DPS
	Does this action improve the financial viability of the city in 20 years?	Trend in budget deficits	Finance
	Does this action create job opportunities for all residents?	Number of jobs created in Ypsilanti that pay a livable wage	CED
	Do the jobs created provide a livable wage? Does this action encourage, provide, or promote equity?	Number living wage jobs produced through city contracts	Finance
Communication is key	Does this action help communicate with everyone in the community?	Number of people who have signed up for the city's newsletter	CED
	Were all members of the community told about deliberation of this action in an accessible way?	Budget devoted to communication including printing, mailing, social media participation, and website update.	Finance
	How will the results of this action be shared with the community in an accessible way?	# of website hits	CED
	Is communication infrastructure maintained and enhanced?	Change in voter participation by ward	Clerk
	Is the City maintaining relationships to communicate to groups throughout the City?	# of social media followers	CED

Guiding Value	Questions	Measures	Responsible Party
Anyone, no matter what age or income, can find a place to call home in Ypsilanti	Does this action preserve, improve and/or create viable, safe, affordable homes?	Change in the % of cost-burdened households	Housing Commission
	Does this action preserve/create variety in housing products in terms of size (square footage and/or # of bedrooms) and ownership/rental type?	Trends in the # residential building permits by building type (single-family, 2-5 unit, 5+ unit) by neighborhood	CED
	Will this action result in the continued maintenance and care of existing residences?	Supply and demand for senior housing	Housing Commission
	Do residents, especially young adults and seniors, have the ability and/or resources to maintain their homes?	Trends in home ownership among young professionals and pre-family households	Housing Commission
	Will this action preserve or create housing that is needed?	Number of residential blight violations	CED
		Median housing values by neighborhood	Housing Commission
Easily walk, bike, drive or take transit from anywhere	Does this action preserve or create a complete transportation system with room on the roads for cars, buses, bicycles, and pedestrians?	# of miles of additional bicycle paths and sidewalk	DPS
	Does this action reward those taking a short trip with the City, rather than those passing through?	Increase in bus ridership from Ypsilanti residents	CED
	Does this action help Ypsilanti be part of the regional transportation network?	Amount of money spent on maintenance of streets, sidewalks, and multi-use paths	Finance
		Change in "drive alone" commuting	CED
		Traffic counts for all transportation modes of key intersections	DPS

Guiding Value	Questions	Measures	Responsible Party
Great place to do business, especially green and creative	Does this action create a business environment that fosters creativity?	# of new green/creative businesses started	CED
	Does this action attract new and/or retain existing businesses?	# and types of grants issued	DDA/CED
	Does this action foster locally grown enterprises?	Demographic data of grant recipients	CED
	Does this action reward green and sustainable businesses?	# of local business expansions	DDA/CED
		Length of time to complete the site plan and permitting process	CED
Everyone in the region knows Ypsilanti has great things to do in great places that are in great shape!	Does this action preserve, use, and/or enrich all places?	Volunteer hours/personnel hours dedicated to event planning and operation	CED & CVB
	Does this action enhance Ypsilanti's reputation as a great place?	Condition of streetscape amenities (benches, landscaping, bicycle racks)	DPS
	Does this action bring people to visit great places in Ypsilanti?	Attendance at City-sponsored events	CED & CVB
		Ratio of positive/negative feedback of events from visitors	CED & CVB
		Distance visitors traveled to attend the event	CED & CVB

Guiding Value	Questions	Measures	Responsible Party
Ypsilanti is an asset of Eastern Michigan University, and Eastern Michigan University is an asset of Ypsilanti	Does this action help Ypsilanti be a home for the university itself, as well as its students, faculty, and staff?	# of joint programs between the City and EMU	CED
	Does this action integrate Ypsilanti as part of the EMU experience?	# of projects that EMU students/faculty assist with that serve the City	CED
	Does this action support EMU's integration into the City?	# students and faculty that live in Ypsilanti	CED
Build a community amongst ourselves and with our neighbors	Does this action build community within the City?	# of users of the app nextdoor.com	CED
	Does this action foster relationships with school districts, neighboring municipalities, the City of Ann Arbor, and Washtenaw County?	# of joint meetings between government bodies, community groups, Ypsilanti schools, etc.	CED
	Does this action and/or communication celebrate successes within the City as a community?	The formation of neighborhood associations	CED
		# of youth participants	CED
		Hours of City staff spent with community organizations	CED

Chapter 3 – Ypsilanti Now

“There are three sides to every story in Ypsilanti.” -unsolicited advice e-mailed to the Consultant Team from a former City resident

The following chapter lays out the latest facts about the City of Ypsilanti - the people, the buildings, the economy, and the transportation network (roads, buses, bicycle lanes and sidewalks). Each section ends with policy implications that have influenced the Master Plan and should be factored into future decisions.

Population

Like many of Michigan’s older industrial towns, Ypsilanti saw rapid mid-century population growth, followed by more recent declines (Figure 1). The city has a sizable African-American population, though as captured in the “Percent Minority” map, the city remains racially segregated by neighborhood. The city’s industrial heritage has also left the city’s population vulnerable to the past decades of deindustrialization, with pockets of high poverty and unemployment.

The historic core of Ypsilanti was a mature industrial town of nearly 7,500 people by the beginning of the 20th century, with population changing only modestly over the next 30 years. However, both the industrial mobilization of World War II and the auto industry’s post-war boom were reflected in population growth, with the Census reporting a peak of 29,538 residents in 1970.

Since that time, the city’s population has shrunk to 19,435 in 2010 and an estimated 20,939 in 2018 per American Community Survey (ACS) 5-year estimates— only slightly higher than the city’s 1950 population. Population forecasts by ESRI, a proprietary software program, projects that the population will increase to about 21,443 by 2024.

Ypsilanti, like the nation as a whole, has seen household sizes decline over time. Societal trends, including delaying marriage and childbearing, have led to more householders living alone or as married couples without children. In Ypsilanti, the household size declined from 2.38 in 1990 to 2.29 in 2000 to 2.06 in 2010. Yet, as of 2018 ACS 5-year estimates, the trend has reversed: household size has increased again to 2.29. Additionally, rental households had fewer average residents than owner-occupied households: 2.20 compared to 2.49, perhaps contrary to popular belief. The same is true at the county and state level.

Age, Educational Attainment & University Influence

When analyzed at a City level, the City of Ypsilanti has a younger population (see Figure 3) than its neighbors, the region, and the state of Michigan overall.

However, when broken down by census tract, younger populations are clustered around the Eastern Michigan campus (Map 2). The enrollment numbers of Eastern Michigan University have increased (see Figure 2) since 1960, with a few dips and a slight decline in enrollment over the past two decades – as of the 2019 fall semester, Eastern Michigan has a total enrollment of 17,784 students.¹

The same pattern emerges for educational attainment. Ypsilanti’s population overall has a relatively high level of educational attainment, especially compared to the region and state. However, Maps 2-5 show a large geographic disparity, with residents holding a bachelor’s degree ranging from 57% in the northwest part of the city to 14% in the southwest portion. With the current emphasis on education as the key to individual and community prosperity, this education gap has troubling implications for the city’s ability to fully participate in the knowledge economy.

The University presence appears to counter the declining industrial sector, when the city is viewed as a whole. However, these two trends have impacted different parts of the population: the educational influence in some ways masks, rather than mitigates, the impacts of deindustrialization.

Equity, Race, Ethnicity & Income

Ypsilanti is a diverse community in terms of race, ethnicity, and disability. The city prides itself on its reputation as welcoming to all, as evidenced in its guiding values.

The city has a sizable African-American population, comprising about 29.8% of the city’s population as of 2018– a slight decline since 2010 (31.9%). Approximately 4.6% of residents identified as Hispanic and 3.2% Asian in 2018— while these numbers are relatively small, they have grown or stayed the same since 2000 Census and the 3.9% Hispanic and 4.3% Asian in the 2010 Census. That is to say, that as the city grows and shrinks, it is staying racially and ethnically diverse.

African-American residents predominantly live in the southwestern portion of the city—2018 ACS 5-year estimates show around 70.7% of residents of the southwest census tract to be African-American. This is down from 80% in 2010 and from 90% in 2000, showing a steady change in racial composition over the past two decades. Regardless of this change, when combined with data also showing lower educational attainment levels and household income, a distinct racial, economic, and educational segregation exists even in a small city like Ypsilanti. The city needs to focus on ensuring the residents of challenged areas receive a sufficient share of public resources to maintain equity.

As a whole, the estimated 2018 per capita income for the City is \$24,562 which is less than the state as a whole at \$30,336. In comparison, Washtenaw County's per capita income is \$39,486, showing that Ypsilanti's residents earn about 62% of the County's per capita income. Only one census tract (tract 4102) in the City is above the state per capita level, compared to three census tracts in 2013. One of the City's tracts earns less than half of the state per capita income: census tract 4106.

The maps 3-5 tell multiple stories:

- Compared to the state of Michigan overall, Ypsilanti is a racially diverse city, with a range of education levels and incomes. It should be poised to take advantage of the knowledge economy of the 21st century given its proximity to knowledge-based sectors.
- The City of Ypsilanti is as racially diverse as Ypsilanti Township. However, its per capita income is lower than the adjoining municipalities with Ypsilanti Township having the lowest educational attainment. In attracting knowledge economy firms, the City competes regionally with its neighbors. Ann Arbor, to the west, is home to the University of Michigan and has more residents with college degrees and higher incomes.
- Within the city itself, race, income, educational attainment, and location are interconnected. The differences in educational attainment and income mean that one size cannot fit all in terms of policy for the entire City. When implementing policies to achieve safety, diversity and sustainability for the City, the needs and strengths of residents in each neighborhood must be taken into account because they are different.

Figure 1: Population History




Figure 2: Eastern Michigan University Enrollment









Figure 3: Age, Ypsilanti and Area Communities, 2018



Map 2: Median Age, 2018



Maps 3-5: Sensitive Population Analysis: Minority, Education, & Income



HOUSING

Ypsilanti has strong, stable neighborhoods, historic architecture, and a ratio of rental-to-owner occupancy higher than the national average, but typical of a college town. As of 2018, 68.7% of occupied dwelling units were renter-occupied and 31.3% owner-occupied. This split is nearly opposite the national owner-occupancy rate of 63.8%, the state rate of 71% and the county rate of 60.7%. However, it is similar to other college towns in the region, as shown in Figure 4.

Only about 36% of occupied dwelling units in the city are detached single-family structures. About 44% of housing units are in structures that contain more than 5 dwelling units, and 29% of dwelling units are in structures that contain 10 or more units. By comparison, Washtenaw County as a whole has 58% of total dwelling units found in detached single-family family structures, 27% in structures with at least 5 units, and only 16% in structures with at least 10 units.

Occupancy and housing type are strongly related, as shown in Maps 6 and 7. While the city does have some single-family rental housing and some owner-occupied units in multi-unit structures, 92% of detached single-family homes in the city are owner-occupied, according to 2020 assessment data.

The clustering of rental units in large on-campus and near-campus student apartments complexes, and a few other large multi-family properties compared to the owner-occupied dominance of single-family homes means that focusing only on the percentage of units that are rental-occupied may exaggerate the impact of rental housing on Ypsilanti neighborhoods: when measured on a parcel basis, rather than by dwelling units, 66.7% of Ypsilanti's residential properties were owner-occupied residences in 2010, and an additional 2.6% partially owner-occupied (e.g. multi-unit houses with the owner living on-site). On a land area basis, single-family homes make up 64.4% of the city's residential property area.

The amount of rental housing in the city is also strongly related to the city's relatively young population, including student households: 50% of households in the city are headed by a householder aged under 35 years old; of these households, 68% rent their homes. Another 13% of households in the city are headed by a householder aged 35-44 years old, however only 10% of those are renters. See Figure 5.

Ypsilanti has a historic core of neighborhoods built before 1900. Developed before the advent of the automobile, they were designed for pedestrians with parks, business districts, and the community within comfortable walking distance from housing. Over the years, many of the homes were subdivided for worker housing during World War II or later as student housing. The early 2000s saw the greatest change in the city's housing stock since the 1970s, with building permit data showing a nearly 5% increase in housing units in the first half of the decade. Most of this was multi-family construction, though of diverse types.

Despite Ypsilanti's base of strong historic neighborhoods, the 2015 Housing Affordability and Economic Equity Analysis for Washtenaw County indicates that the City of Ypsilanti's housing market is "fundamentally weak." According to the report, there is increasing inequity within the County between the Ann Arbor area and the Ypsilanti area (City and Township). Property values are increasing in the Ann Arbor housing market to unaffordable levels, displacing Ann Arbor residents to Ypsilanti, creating an increasingly imbalanced market. More affordable housing values are resulting in higher concentrations of struggling families in the Ypsilanti area. Many of the subsidized housing units in the County are concentrated in Ypsilanti, a trend that this report recommends reversing – dispersing subsidized housing throughout the County will help lessen the increasing concentration of cost-burdened households in Ypsilanti.² The size of dwelling units and lot sizes is one tool that cities have to try to create a range of market rate housing options for people of all incomes and life stages. The City has been proactive in updating its zoning ordinance to permit a greater variety of housing.

Citizen Committee on Housing Affordability and Accessibility

Ypsilanti's housing affordability crisis has become pronounced in recent years. Particularly in 2016 and 2017, City residents, and non-residents, voiced their concerns about rising rents, displacement, and lack of accessible housing. In December of 2017, the Planning Commission chartered the Citizen Committee on Housing Affordability and Accessibility to study and make recommendations pertaining to housing, with the ultimate goal being an update to the 2013 Shape Ypsilanti Master Plan. One of this Master Plan's guiding values is "anyone, no matter what age or income, can find a place to call home in Ypsilanti." This guiding value remained as a centerpiece, at the forefront of the Committee's

work and proposed recommendations. While the Committee's report and recommendations are provided in full in this plan's appendix, a few of the recommendations are discussed in the *Policy and Plans for All Neighborhoods* section of Chapter 7.


The Committee diagnosed five problem statements that exist in the City today. The Committee then proposed eleven recommendations that serve to fix the problem statements. The recommendations cover topics on renters' rights, sustainable development, need-based assistance, accessibility, zoning, and advocacy/partnership.

Figure 4: Housing Tenure for University Towns


City	Occupied housing units (2017)	Percentage Rental (2017)
Athens, Ohio	6,887	71.4
Oxford, Ohio	6,006	69.4
Ypsilanti	7,865	69.2
East Lansing	13,585	66.2
Bowling Green, Ohio	11,291	62.2
Mt. Pleasant	8,027	60.9
Kalamazoo	28,996	55.2
Ann Arbor	47,524	54.1
Marquette	7,587	50.8
Muncie, Indiana	27,666	48.6
Sault Ste. Marie	5,581	45.2

Source: ACS 2013-2017 5-Year estimates


Figure 5: Household Tenure by Age, 2018




Map 6: Rental & Occupied Housing




Map 7: Housing Units by Type



Map 8: Residential Structure Age



Map 9: Size of Dwelling Unit



Housing Data Summary

The following factors are key to the Master Plan:

- The majority of housing units are leased, rather than owner-occupied, which tracks with the housing mix in other college towns.
- Census data shows concentrations of renters in the same tracts with a higher percentage of younger adults, under the age of 24, indicating the influence of EMU students on the housing market.
- Most single-family homes are owner-occupied.
- Neighborhoods near EMU and the historic downtown were built, earlier, have a mix of rental and owner-occupied units as well as larger houses
- Housing built post-World War II is smaller, either mostly rentals or mostly owner-occupied and has fewer conversions to multiple-family and other uses.
- Census tracts 4102, 4107, and 4109 have aging populations, which means they will need services to stay in their homes or they will move to a different residence within the next 10-20 years.
- EMU will continue to bring residents - students to the Midtown and Riverside neighborhoods, and faculty/staff to the College Heights and Normal Park neighborhoods. However, both groups reside in all areas of the City.
- Rail service at Depot Town will increase housing values and demand for housing within a 10-minute walk, approximately a half-mile radius, of the stop.
- Heritage Park and Worden Gardens are where first-time home buyers and income property purchasers are most likely to purchase houses.
- Well-maintained, historic neighborhoods have continued to hold their value and will likely in the future.
- Housing inequity within Washtenaw County is increasing with a growing divide between the strengthening Ann Arbor market and Ypsilanti's weaker market.

ECONOMY

The decline of manufacturing's prominence has changed the list of major employers in the area. The current list of the top 20 major employers (defined as having at least 500 employees in the Washtenaw County) along with the list in the City's 1998 and 2013 Master Plans shows an absence of manufacturing firms. Instead, educational and medical employers dominate the list, of the top 10, eight of the major employers are related to education, health care, or government, most of which are located in Ann Arbor (see Figure 8). Faurecia North America has grown immensely over the last few years, a testament to a growing economy in comparison to 2013. Still, the trajectory for manufacturing, while still an important component of Michigan's economy, is predicted to shrink.³ Ypsilanti is growing farther apart from its industrial past.

While many jobs are still located in or relatively close to Ypsilanti, these jobs may require a higher level of education on average than the previous manufacturing jobs. This trend is a concern because, as noted previously, parts of the City have extremely low educational attainment rates. These parts of the community are at-risk for being left behind by the changing character of the job market and the shift from manufacturing to a knowledge economy.

Figure 8: Change Number of Employees in Washtenaw County

Company	Location (Primary)	2019	2013	2010	1998	Trend
University of Michigan	Ann Arbor	33,225	16,143	26,241	11,118	↑
University Health Systems	Ann Arbor		12,000	19,614	6,742	
Trinity Health	Livonia	7,435				----
Federal government	Detroit	3,147				----
Ann Arbor Public Schools	Ann Arbor	2,225	3,578	2,659		↓
Integrated Health Associates	Ann Arbor	1,664				----
Eastern Michigan University	Ypsilanti	1,559	1,976	1,950	1,991	↓
Faurecia North America	Saline	1,442	800			↑
Thomson Reuters	Ann Arbor	1,300	1,100	1,800		↓
Washtenaw County	Ann Arbor	1,264	1,339	1,345	1,200	↑
Terumo Cardiovascular Group	Ann Arbor	1,100				----
Toyota Technical Center	York Township	1,095	1,500	1,036		↑
St Joseph Mercy Chelsea	Chelsea	1,082				----
Domino's Pizza	Ann Arbor Twp	865				----
IBM Watson Health	Ann Arbor	850				----
City of Ann Arbor	Ann Arbor	712	710	766	951	↓
Ford Motor Company	Ypsilanti	700	823	800	1200	↓
Zingerman's Family of Business	Ann Arbor	700				----

Table Data Source: 2013 & 2019 figures - Ann Arbor Spark; 2010 - Draft AAATA Transit Audit Needs Assessment; 1998 - Washtenaw Economic Development Council-Crain's Detroit Business

Figure 9: Major Taxpayers, 1999-2020

Major Taxpayers	2020			2013			2009			1999		
	Taxable Value (in 1,000s)	City Rank	% of total	Taxable Value (in 1,000s)	City Rank	% of total	Taxable Value (in 1,000s)	City Rank	% of total	Taxable Value (in 1,000s)	City Rank	% of total
Arbor One 18, LLC	\$5,650	1	2.33%									
LeForge Station II, LLC	\$5,353	2	2.21%	\$8,249	1	2.84%	\$9,148	3	2.27%			
Barnes & Barnes Properties, LLC	\$5,212	3	2.15%	\$2,918	4	1.01%	\$3,046	7	0.76%			
DTE Electric Company (formerly Detroit Edison)	\$5,019	4	2.07%	\$3,360	2	1.16%	9,537	2	2.37%	\$4,265	2	1.54%
River Drive Properties, LLC	\$3,191	5	1.32%	\$2,921	3	1.01%	3,400	5	0.84%	\$3,267	5	1.18%
DTE Gas Company (formerly Mich Con Utility)	\$2,687	6	1.11%	\$2,900	5	1.00%	-			\$3,641	4	1.31%
Forrest Knoll Apts.	\$2,023	7	0.84%	\$1,849	6	0.64%						
Ypsilanti Realty Holdings, LLC	\$1,711	8	0.71%									
Erie Investments No. 15, LLC	\$1,639	9	0.68%									
Cross Street Village	\$1,638	10	0.68%									
Asad Khailany	-			\$1,811	7	0.62%	\$1,811	9	0.45%	\$1,413	10	0.51%
Forest Health Medical (formerly Beyer Hospital)	-					0.82%	\$3,304	6	0.82%	\$1,904	0	0.69%
Beal Properties	\$1,221			\$2,369	8	0.55%						
Huron View Apartments	\$1,594			\$1,587	9	0.50%	\$1,706	10	0.42%			
Angstrom USA, LLC (formerly Visteon)	-			\$1,460	10		28,266	1	7.02%	\$42,470	1	15.33%
River Rain Apartments	\$1,518					0.46%	\$2,232	8	0.55%	\$1,939	8	0.70%
Reichuang, LLC (formerly Exemplar Manufacturing)	\$1,118			\$862						\$4,151	3	1.50%
Crown Paper Company Manufacturing	-			\$1,334						\$2,935	6	1.06%
Eastern Village Apartments	-			-		0.00%				\$1,261	7	0.46%
Total of top ten taxpayers	\$34,123		14.09%	\$29,424		6.47%	\$66,262		16.45%	\$67,246		24.28%

Commercial Assessment

In the 2013 master plan, a commercial assessment estimated that \$59,687,099 of potential sales leaves the City, accounting for 55% of the total sales potential for the Ypsilanti market area. While the same analysis was not conducted, similar estimates from ESRI for the “retail gap” in 2017 show the trend in lost sales has shrunk to \$34,553,228, which shows that more money is being captured locally and potential drawing more visitors in. Most of the surplus in spending is coming from sales in “food and drink.” This is a positive trend and an indication to continue tailoring economic development efforts to reduce the retail gap in areas where there is major “leakage”: food and beverage, general merchandise, clothing and accessories, furniture and home furnishing, and electronics and appliances.

The following commercial markets were identified for potential growth:

- The Ypsilanti Competitive Market: In 2013 focus groups, residents expressed a fierce devotion to local businesses. Also, many wanted to be able to walk or bike to get daily items. Frustration was continually expressed about the lack of a full-line grocery store and specialty food markets in the City limits.
- Underestimated College Student Market: EMU students are a recession-proof market. However, their spending patterns are different than non-student households with similar incomes. They tend to spend a greater percentage of their money on electronics, food away from home and consumer items, than family households in the same earning classification.
- Neighboring Medical Center Market: The St. Joseph Mercy Ann Arbor Hospital is located in Superior Township, near the City’s border. The staff, estimated to exceed 5,000 people, and the visitors to the complex are an untapped market for the City’s retail businesses, including restaurants and entertainment.

Emerging Sectors

While no one sector has replaced the manufacturing jobs lost in the City, several sectors have emerged: small manufacturing and craft production, creative economy, renewable energy, and food. Each of these sectors are rooted in companies that have started in Ypsilanti.

Small and craft manufacturing has been a part of the City’s economy since the beginning of the automobile industry. Small craft shops clustered around the larger manufacturing facilities supplying parts and prototypes. Marsh Plating was

founded over forty years ago, located near the downtown, is an example of an automobile supplier in the City. Michigan Ladder is another example of a small manufacturing facility in the City. The 119-year old company has recently expanded its manufacturing space, where wood and fiberglass ladders are assembled and hopes to add 6 new jobs to its workforce between 2013 and 2015. The challenge for the City is to make these industries operation and expansion possible while meeting the values of the community.

The creative economy - defined as advertising, architecture, art, crafts, design, fashion, film, music, performing arts, publishing, research and development, software, toys and games, television and radio, and video games - has gained a foothold in Ypsilanti. Various businesses have started in or relocated to Ypsilanti, such as VGKids. VGKids is a screen printing company that has consolidated operations in the City, after closing a manufacturing facility in California. The company also provides studio space to small creative businesses. More recently, Grove Studios and Ypsi Alloy Studio have opened, the former a 24/7 music rehearsal space and the latter is a shared space to create and collaborate on visual arts. While these types of businesses can generally use many types of buildings, the building stock is not always suitable. The current zoning ordinance is friendly to creative enterprise as they are permitted in several commercial and industrial zones, but mid-size facilities for growing companies to move into - either office or small manufacturing - are difficult to find.

While no privately held renewable energy company is operating in Ypsilanti, the efforts of individuals and groups have given the City of Ypsilanti a reputation as a leader in sustainable energy. An example of the momentum within the City is SolarYpsi, a volunteer effort to bring solar energy generation to the City of Ypsilanti. The group has helped win grants to fund and/or help install four solar facilities in the City and maintains a website that reports in real time the amount of energy being generated by solar installations in and around the City.

In 2016, DTE Energy completed the installation of a solar array on Ypsilanti’s Highland Cemetery. The approximately 2,520 solar panels are enough to power 150 homes!⁴ City government can use this effort and others as a marketing tool to attract renewable energy manufacturers or installation companies to the City. The City has revised its ordinances and been awarded a SolSmart Gold award for having an online permitting checklist, permitting solar by-right as an accessory use in all zones, cross-training inspection and permitting staff, and a streamlined

permitting process for small photovoltaic systems (more detail in the Sustainability Section).⁵ The city is proud to be the first in Michigan to receive this award from a national program.

A number food-based businesses have opened in Ypsilanti in the past five years. Multiple new restaurants have opened in the Historic Downtown. The farmers market was recently established in Historic Downtown. Many vendors are Ypsilanti residents who produce value-added products, like baked goods and jams, out of their home kitchens under the Michigan Cottage Food Law. Also, more residents are growing and/or raising their own food. Growing Hope, an Ypsilanti-based non-profit, is a leader in the local food movement in the region and provides technical support to beginning and experienced gardeners as well as children. Restaurant Depot, in Ypsilanti Township, supplies wholesale food, beverages, and equipment to restaurants and plays a role in the growth of this sector. Like the creative economy businesses, food-based businesses have challenges when they expand in scale. Home entrepreneurs reach a point where a commercial kitchen is needed. Restaurants need a larger space. The City has permitted hoop houses and greenhouses to create more space in park and residential districts to encourage urban agriculture. The City can continue to foster growth of food-based businesses by permitting incubator kitchens as an intermediate step for entrepreneurs in this field.

In 2018, recreational marijuana was passed by Michigan voters and sales are now legal. Ypsilanti adopted its own business ordinance and zoning ordinance, which means that provisioning centers that sell marijuana for recreational uses are permitted. Within the last five years, over a half a dozen grow facilities and dispensaries emerged under the medicinal legislation. Because sales for recreational use just went into effect, it is too soon to say what affect this may have. Like other businesses, they are subject to the market, however, because hundreds of communities have banned such sales, it may produce certain hot spots in the state.

The City should align its policies and regulations to give each of these emerging sectors physical space and economic incentives to start or locate and then grow in the City. Zoning should allow these uses in various sizes and formats, while being cognizant of impacts on neighbors. Economic incentives, such as tax abatements, should be used to continue the growth of these sectors.

City Budget

Over the last decade, the city's industrial tax base has declined, both in total dollar value and in share of the total, with residential property making up a greater portion of the tax base. The foreclosure crisis in turn contributed to a substantial loss of residential taxable value, beginning in 1998. As of July 2019, the City's total taxable value is \$242,124,962.

The character of the city's tax base has shifted towards residential rental property, with most of the city's top 10 taxpayers in 2019 being property management companies, which has been a significant change over the past two decades (see Figure 9). The top ten taxpayers represent about 14% of the City's tax base, which has risen from less than 9% in 2013, though is still lower than in 1999 when the top ten taxpayers represented almost a quarter of the City's tax base. Since 2013, however, the total taxable value of the top ten taxpayers in the City has increased.

In addition, payment on bonds for the acquisition and remediation of the Water Street property began in the late 1990s and account for 10% of the City's general fund budget. According to the City Manager's 2012-2017 Recovery Plan, the City could pay for few capital expenditure in that time period unless additional, new sources of funds could be found. In 2017, voters passed a 2.3-mill through 2031 to pay down the City's \$7.4 million debt on the Water Street property.⁶ Meanwhile, the City would like to sell the property and see development occur that meets the master plan goals. A biking and walking trail along the Huron River frontage, known as the River's Edge Trail, connects Riverside Park to the north with Waterworks Park to the south. It is a part of a 37-mile-long Border-to-Border Trail running through Ann Arbor, Ypsilanti, and adjacent communities. The River's Edge Trail is a protected trail that will not be sold as part of Water Street.

Economics Summary

The following factors are key to the Master Plan:

- The economy of the City of Ypsilanti has fundamentally shifted in the past decade, shifting the economy from industrial to property management and knowledge-based sectors.
- Portions of the City, both property and population, have been left behind due to economic change. Instead of working in factories, residents with lower educational attainment work in retail or service sector jobs, often

outside the City, often for low wages. Many need bus or transit to get to work.

- The commercial market is underserved, showing a need not only for more businesses but also for marketing of the community as a place to shop to the larger region and targeted nearby populations, EMU students and staff and visitors to St. Joseph Ann Arbor Hospital.
- Several sectors are building momentum in the City of Ypsilanti - small manufacturing, creative economy, renewable energy, and local food. Each one has the potential to create dozens of jobs, not the hundreds in manufacturing previously. However, these are local entities with a commitment to the City. The challenge is to foster growth of these sectors despite the physical constraints of the City's land; very few properties are suitable for large scale operations.
- The City budget has suffered due to several reasons. Originally, the economic shift and ongoing debt played a role. But more recent challenges include the inability for city property tax revenues to reflect the increases in property value, post-recession, due to the Headlee Amendment and Proposal A.

TRANSPORTATION

The street and park structure of the City today was laid out in the early 20th century. However, the function of streets changed in the mid 20th century with the creation of one-way streets when an interchange for Ypsilanti was constructed at Interstate 94 and Huron. At the time, a large workforce commuted to the factories in the southern end of the City quickly in and out. Today, those factories either no longer exist or employ a small percentage of the workers than in the past.

In addition, the transportation options available within Ypsilanti are changing. Washtenaw County is planning for rapid bus service along Washtenaw Avenue, increasing the capacity and decreasing the travel time along the most heavily travelled bus line for The Ride.

The Border-to-Border (B2B) trail that spans Washtenaw County has completed 35 miles of the Huron River Greenway connecting Dexter, Ann Arbor, and Ypsilanti along the Huron River through paved, ADA compliant, shared-use pathways. In 2015, the B2B trail was incorporated in Michigan's Iron Belle Trail, a network 2,000 miles long that spans the state.

Shape Ypsilanti Master Plan (DRAFT UPDATE) – January 5, 2021

Figure 10: Non-motorized Deficiencies, 2013

Sidewalk	Bike facility		
		Off-roadway	Roadway
Existing miles	98.49	5.55	3.71
Deficient miles	23.37	n/a	39.33
Deficient %	19.2%		

Data Source: Washtenaw Area Transportation Study

Non-Motorized Network

Ypsilanti's historically compact core and existing sidewalk network make the city generally friendly to non-motorized traffic like bicycles, pedestrians, and wheelchair users. Over the past decade, this has been improved upon by several efforts:

- The City has participated in the County's Greenway Advisory Committee and regional "Border to Border Trail" (B2B) effort.
- Bike lanes have been added to several streets during resurfacing projects.
- Sidewalk curb ramps are being upgraded to ADA standards throughout the city.
- Bike racks have been installed in Depot Town, the Historic Downtown, and West Cross.

The 2006 Washtenaw Area Transportation Systems (WATS) Non-motorized Plan quantified the city's non-motorized accessibility to be over 80% of the city's roadway miles. The plan concluded that the City provided for pedestrians adequately, but that a much higher portion of bicycle needs were not met (see Figure 11). Since this analysis was completed, no major progress has been made to reduce those deficiencies.

Many of the City's efforts, while positive, have been done on an ad hoc, disconnected basis, occasionally leading to problems. Bike lanes on First Avenue, for example, were created during a resurfacing project without ample coordination with other projects or communication with the residents, leading to their later removal in favor of a parking lane.

In 2010, the City adopted a non-motorized plan with a more comprehensive treatment of non-motorized transportation policies and infrastructure – including

the incorporation of deficiencies identified in the county-wide non-motorized plan developed by WATS – and the Planning Commission created a Non-Motorized Transportation Subcommittee to guide its implementation. Currently, the non-motorized plan is being updated. In 2011, the City passed a Complete Streets Ordinance, which requires non-motorized components be considered as part of any road project.

Transit & Regional Transportation

Due to the high percentage of renters, young population and recent trends from automobile use either by choice or economic need, regional transportation is essential to the long-term stability, growth and prosperity of Ypsilanti. Be it rail or bus, Ypsilanti is a leader in participation and further development of a regional transportation system within Washtenaw County and the Detroit metropolitan area.

The City has long been a user of public transit, in past years purchasing service from the Ann Arbor Area Transit Authority (AAATA), and more recently becoming a member of the Authority, now called The Ride. Prior to 2013, the City operated under a purchased of service agreement. In 2010, in response to budget pressures, the City passed a voter-approved charter amendment to dedicate funding to the purchase of transit service. In 2013 the City was added as a charter member. As a new member of The Ride, no purchase agreement is required with the dedicated millage being passed along to The Ride.

The Ride has conducted long-range planning for the county beginning with a 30 year plan drafted in 2010. In 2014, voters passed a 0.7 mill tax to support AAATA services, and in 2018, renewed the millage with 83% support. As of 2017, ridership numbers hit 6.9 million trips that year after the millage helped increase services by 8,500 service hours in Ypsilanti.⁷ The millage will be levied through 2024; it is important that transit services continue. As of 2019, four routes run between Ann Arbor and the downtown Ypsilanti Transit Center; four more run from downtown into Ypsilanti Township.

Eastern Michigan University additionally contracts with The Ride for a circulator shuttle around the main campus and to the business school in the Historic Downtown. EMU uses a separate transportation provider to provide shuttle service from a west-side parking lot on Hewitt to the main campus.


This portion of The Ride’s system saw a 10% increase in ridership from 2002 to 2009. Since becoming a regional bus service, The Ride no longer keeps track of individual jurisdiction’s ridership as it can be easily skewed. An increase in ridership is consistent with The Ride’s system-wide ridership trends, but also reflects state-wide and national trends of growing local and inter-city transit use. These trends, based on cost-consciousness around rising fuel prices, increased environmental awareness, and other factors, have contributed to interest in new modes of transportation. The map “AAATA Fixed Route Service Coverage in Ypsilanti” shows that about 97% of households are within a quarter-mile from one of The Ride’s routes.

The City of Ypsilanti was selected to be a test community for Miovision, a company devoted to developing smart cities. Miovision uses technology to monitor and collect transportation data; and as a test community, Ypsilanti now has access to this data. Figure 12 provides a summary of five Ypsilanti intersections and the various transportation modes using them. Based on this initial data, motor vehicles continue to be the dominant mode of transportation, though there is a noticeably larger number of pedestrians at both the LeForge Road and Huron River Drive intersection (4.62% mode share) and the Oakwood Street and Huron River Drive intersection (3.69% mode share), perhaps indicating priority intersections for improving pedestrian amenities.

When discussing ride-sharing apps in the subsequent *Cars, Trucks, and Streets* section, it is important to note that ride-sharing cannot fully replace transit as ride-sharing is not as accommodating to persons with children, persons with disabilities, and persons without smartphones. Ride-sharing, car-sharing, bike-sharing, etc. should not be intended to replace transit.

Map 10: AAATA Fixed Route Service Coverage in Ypsilanti

**AAATA FYTIP Fixed Route Service Coverage:
Ypsilanti, Urban Core**



In the near term, Ypsilanti and the other communities along Washtenaw Avenue are considering improved transit service along that corridor, beginning with additional bus service and potentially growing into bus rapid transit or light rail service. Known as the “Reimagine Washtenaw” project, the upgrade would include key elements such as transit signal priority, queue jump lanes, limited stops, and super stop stations. If the full bus rapid transit were implemented, it is expected to cut 19 minutes off the trip from Ypsilanti to Ann Arbor.⁸

While Ypsilanti has not had passenger rail service since the 1980s, work is underway on Ann Arbor to Detroit commuter rail service that may propose a stop in Depot Town, along with service to Detroit Metro Airport and Dearborn. The system would also provide access from Ypsilanti to Amtrak service on the Chicago-Detroit-Pontiac line, which is planned for improvements as part of the Midwest High-Speed Rail Initiative. It is important to continue to consider future opportunities for both commuter and passenger rail.

Cars, Trucks, and Streets

Ypsilanti has seen an overall decrease in traffic over the past couple decades, due in large part to major industrial employers reducing their workforce or closing. The exception is the northern part of the City, where growth on the EMU and St. Joseph Mercy Hospital campuses has contributed to increased traffic. The County and Region have experienced a decrease in Vehicle Miles Travel (VMT) between 2002 and 2012. Long-range modeling done as part of the WATS 2045 Regional Transportation Plan forecasts an increasing population and employment opportunities which means an increase in traffic and congestion over the next quarter century. In a high growth scenario, vehicle miles traveled during peak morning and evening hours could increase by 30% and 33%, respectively after the addition of an estimated 2,000,000 more daily vehicle miles traveled. The encouraging news that 48.8% of trips made in 2015 were between zero to three miles,⁹ which means that improvements to nonmotorized infrastructure and increased bus service could help to remove vehicles making short trips from the road.

While traffic counts are done sporadically and are individually difficult to draw conclusions from, a sampling of recent and past counts from around the city shows that traffic volumes have been stagnant or declining somewhat over the 1990s and 2000s (see Figure 11). As noted, increases in traffic are largely attributed to the

main traffic generators in the area, primarily Eastern Michigan University but also Washtenaw Community College and St. Joseph’s hospital. Washtenaw County, as part of the Reimagine Washtenaw effort, is working with these institutions and others in the area to look at Traffic Demand Management practices that could further reduce vehicle miles traveled through programmatic changes and behavioral shifts to car-pooling, transit usage, walking, biking, etc.

Some of these trends are captured in Figure 11 that shows that most of the 19 intersections have reduced traffic volumes when compared to counts from five to ten years ago, and only modest increases in the remaining six. Interestingly, the newer counts would include trips made from ride-sharing apps, despite research showing that in larger cities ride-sharing increases congestion. There is little consensus on how ride-sharing apps affect car ownership but there is speculation that the original ownership model is less popular among youth. Financially, in some cases it is more affordable to forgo monthly payments for pay-as-you-go rides.¹⁰ However, because the data is collected by private companies, cities are somewhat in the dark about the extent to which these services are being used. This is trend worth watching closely because it may help determine how streets are shaped, for example, the development of drop-off and pick-up zones as opposed to parking lot requirements. Car-sharing, electric vehicle charging and bike parking can be practical first steps in terms of existing infrastructure. The zoning ordinance was updated to incentivize these alternatives, as Walkable Urban Districts offer parking requirement discounts for including such infrastructure.

In recent years, traffic safety in Ypsilanti has improved both on in terms of number of crashes at major intersections and relative to the Washtenaw County region. Some of this may be attributed to flat or declining traffic volumes in the city, compared to growing volumes elsewhere in the County. As shown in Figure 13, the City has five of the forty highest-ranked intersections in Washtenaw County in terms of annual average crash rate. Since the adoption of the Master Plan in 2013, the top two have shifted only slightly in their relative ranking, however the top three thru five have significantly fallen, implying these intersections have become safer relative to the rest of the County. Hamilton St. and Huron St. remain common occurrences as one-way streets making this ranking.

Figure 11: Intersection Traffic Volumes

Street	Location	Year	Daily Volume	Comparison Year	Comparison Volume	% change	Annual % change
Michigan Avenue	East of Huron	2015	21,800	2010	21,325	2.23%	0.44%
	East of Hamilton (downtown)	2018	19,100	2009	22,484	-15.05%	-1.80%
	SW of Congress	2017	14,000	2006	12,585	11.24%	0.97%
Washtenaw Avenue	NW of Mansfield	2018	26,000	2007	26,783	-2.92%	-0.27%
	NW of Oakwood	2018	25,300	2004	26,336	-3.93%	-0.29%
Prospect Street	South of Maus/Spring	2017	7,300	2005	9,913	-26.36%	-2.52%
	South of Holmes	2017	8,400	2005	8,325	0.90%	0.07%
Cross Street	West of River (Depot Town)	2015	13,500	2006	10,246	31.76%	3.11%
	West of Wallace	2006	8,180	1994	n/a	16.00%	-1.30%
Harriet / Spring	East of Hawkins	2017	5,600	2005	4,850	15.46%	1.21%
	West of Huron	2017	11,300	2006	13,619	-17.03%	-1.68%
Hamilton	South of Harriet	2018	12,300	2009	15,511	-20.70%	-2.54%
Huron	South of Harriet	2018	16,600	2009	16,059	3.37%	0.37%
Leforge	North of Huron River Drive	2015	7,600	2006	12,906	-41.11%	-5.71%
Huron River Drive	East of Hewitt	2016	14,100	2008	16,519	-14.64%	-1.96%
River	North of Michigan	2004	4,095	1994	n/a	14.00%	-1.40%
Mansfield	South of Cross	2004	3,907	1994	n/a	14.00%	1.40%
First	South of Michigan	2004	4,600	2004	n/a	-2.00%	-0.40%
Grove	North of Spring	2012	2,300	2004	2,702	-14.88%	-1.99%

Italicized cells indicate that base year is approximate
Source: SEMCOG

Figure 12: Intersections and Mode Share Data for Select Ypsilanti Intersections

Huron Street and Cross Street		
	Total	Mode Share
Pedestrians	304	1.48%
Bike	78	0.38%
Road / Bike Lane	29	
Crosswalk	49	
E-Scooters	0	0%
Road / Bike Lane	0	
Crosswalk	0	
Vehicles	20,158	98.14%
Passenger Vehicles	19,695	
Heavy Trucks	463	
Oakwood Street and Huron River		
	Total	Mode Share
Pedestrians	716	3.69%
Bike	39	0.20%
Road / Bike Lane	10	
Crosswalk	29	
E-Scooters	1	0.01%
Road / Bike Lane	0	
Crosswalk	1	
Vehicles	18,628	96.10%
Passenger Vehicles	18,221	
Heavy Trucks	407	

Leforge Road and Huron River Drive		
	Total	Mode Share
Pedestrians	985	4.62%
Bike	53	0.25%
Road / Bike Lane	20	
Crosswalk	33	
E-Scooters	0	0%
Road / Bike Lane	0	
Crosswalk	0	
Vehicles	20,275	95.13%
Passenger Vehicles	19,827	
Heavy Trucks	448	
Hamilton Street and Washtenaw		
	Total	Mode Share
Pedestrians	454	2.45%
Bike	31	0.17%
Road / Bike Lane	6	
Crosswalk	25	
E-Scooters	1	0.01%
Road / Bike Lane	1	
Crosswalk	0	
Vehicles	18,074	97.38%
Passenger Vehicles	17,559	
Heavy Trucks	515	

Huron Street and Michigan Avenue		
	Total	Mode Share
Pedestrians	915	2.41%
Bike	70	0.18%
Road / Bike Lane	24	
Crosswalk	46	
E-Scooters	1	0%
Road / Bike Lane	0	
Crosswalk	1	
Vehicles	37,026	97.41%
Passenger Vehicles	35,696	
Heavy Trucks	1,330	

Figure 13: Annual Crash Rate, 2014-2018

City Rank	County Rank	Intersection	Avg. # Crash Rate
1	3	Huron St. at Michigan Ave.	34.2
2	12	Washtenaw Ave. at Hewitt Rd.	29.0
3	21	Hamilton St. at Michigan Ave.	25.2
4	29	Huron River Dr. at Oakwood St.	19.0
5	40	Hamilton St. at Harriet St.	17.0

Data Source: SEMCOG

Transportation Summary

The following transportation factors have implications for policies in the Master Plan:

- The non-motorized network has a number of deficiencies. Public input during the process asked for better bicycle lanes and access throughout the City.
- More transit riders are using The Ride bus routes in the City. The City should continue to support and strengthen- and if possible, expand- the service.
- The City should implement designs for streets to be safe and comfortable for pedestrians, focusing on intersections with higher pedestrian counts.
- Daily train service, while the time line is uncertain and likely several years off, would have major positive impacts for Ypsilanti's core. More demand for housing would be expected within a quarter mile radius, an easy 10-minute walk, of the train depot.
- The volume of vehicle traffic and the number of crashes has decreased. Improvements should continue to make streets safer but also should recognize that cyclists and pedestrians use the roadways as well, and not default to vehicular improvements over those for non-motorized users.
- Crashes are concentrated on the one-way streets. The speed limit of some of those streets were recently raised by the State of Michigan. The past Master Plan recommended these streets return to two-way traffic, with phasing of the work taking place. See Chapter 5- Transportation for details of the phasing approach.

Chapter 4 – City Framework

“We are not the suburbs.” – Proposed Guiding Value at Focus Group

This Master Plan is a fundamental shift to view the City as an urban system with a framework of interconnected parts, shown on the Framework Map (Map 11). The map, taking the place of a future land use map in a traditional plan, also provides guidance to the community and developers to the context of the built environment. The Framework Map will set the design context and guide the development form of the city through form based regulations. It has centers, corridors, districts and neighborhoods that include unique building forms within the City of Ypsilanti summarized below:

Centers are the heart beats of the City – downtown, Depot Town and Cross Street adjacent to the EMU campus. Each area has buildings built up to the sidewalk and a variety of uses - retail, restaurants, services, office, civic, and residential. They are places where people walk, gather, shop, exchange and meet.

The plan proposes to build on the strengths and improve the weaknesses of these areas to make them great places. Hamilton, Huron, Cross Street and Washtenaw Avenue are proposed to become two-way streets, putting pedestrians and cyclists on even footing with automobiles. Future ordinances will preserve the architecture of these areas, while requiring natural surveillance to improve safety. Policies will also enable the continued re-use and redevelopment of buildings, increasing their sustainability. Specific plans for each area are shown in Chapter 6, including design plans for Depot Town to prepare for the planned commuter rail station. A redevelopment concept plan and design standards for the Water Street area are in Chapter 10.

Neighborhoods are where homes are clustered together, along with small-scale other uses that serve the people that live there (such as a corner store, a school, church or library). Each of the dozens of neighborhoods in Ypsilanti has its own character, influenced by the size and architecture of the buildings, the layout of the streets, parks and the people who live there. Neighborhoods fall into two categories, discussed in Chapter 7:

Central Neighborhoods are among the oldest in Ypsilanti. Initially oriented on the Huron River, they are built on a grid street network connected to the adjacent business districts. They border downtown,

Depot Town and EMU. These neighborhoods have a range of residential building types, with churches, schools, stores and gas stations intermixed. Around the railroad, industrial uses are mixed into the neighborhood.

Under this plan, the mix of uses will follow the pattern of current zoning. However, the building’s form would be regulated, including those outside of the historic district, to maintain the character of the area. Regulations for two-family and multiple-family options would be collapsed into clear rules based on the number of housing units- with categories for duplexes, group living arrangements, 2-4 units and 5 or more units. When developing the form-based code zoning, the building types, uses and setbacks will be calibrated to preserve the character of these neighborhoods.

Outlying Neighborhoods were built in the middle or later part of the 20th century and were designed as areas for a single type of housing, either single-family or multi-family. These neighborhoods are adjacent to a corridor but the street network is designed to carry traffic into the neighborhood, not through it. Any non-residential uses, other than schools or parks, are located at the edges, not embedded within the neighborhood.

These neighborhoods will have uses limited to the type of residential for which they were built. In some areas, like the Heritage Park neighborhood in the southwest part of the City, zoning would be changed so that duplexes and group homes would no longer be allowed by right. As many of these areas have aging populations, the City needs to be concerned about the stability of these neighborhoods as demographics shift. Accessory Dwelling Units, for example, can be an affordable and accessible housing type for the aging population.

Corridors are the streets that connect the City together, and sometimes divide it. They are the arteries of transportation into, around and through the City. Two types of corridors exist in Ypsilanti:

Historic Corridors connect the centers of the City with each other and the surrounding neighborhoods. They are dominated by large, historic homes now used in a variety of ways – residences, office, retail. Houses of worship and other civic buildings also line these corridors, interspersed with smaller homes. The transportation plan sees restoration of two-way traffic to the one-way historic corridors of Huron, Hamilton and Cross. It also proposes the extension of River Street through the Water Street redevelopment area to Factory in the next twenty years. Uses will remain flexible allowing the historic buildings to accommodate changing markets and traffic patterns.

General Corridors are streets that connect the City to neighboring municipalities and the centers. Many of the corridors – Ecorse, East Michigan, West Michigan and along many of these corridors no longer accommodate the larger 21st century footprint of suburban style buildings with parking in front and lawns on all sides. The new pattern proposed in this Plan will allow parking on the street and require buildings to be closer to the street; with minimal yards, lots will have more buildable area for residential, commercial and office uses mixed throughout.

Other corridors – Huron River Drive and Harriet – have one type of building on one side of the street and a distinctly different situation on the other side of the street. Future regulations would require, where possible, the two sides of the street mirror one another. In twenty years, the dignity of Harriet Street should be restored to a walkable shopping district for the adjoining neighborhoods. Huron River Drive should become a point of integration between the campus of Eastern Michigan and the City. Addition of sidewalks, crosswalks and bicycle lanes are essential to transitioning this street from a dividing line geared only to move vehicles to a place where the City and campus meet seamlessly. Chapter 8 provides more detail for each of these areas.

Districts are parts of the city dedicated to a single type of activity, like Eastern Michigan University, the office and medical area on Towner, and the industrial areas of the City in the south. The challenge is to use the street network design to

integrate them into the City while assuring that students, faculty, workers and suppliers can reach their destinations easily.

Eastern Michigan University’s campus, which is not within the regulatory jurisdiction of the City, will be preserved and improved by joint planning and cooperation between the City and EMU, as part of a Campus master plan process. The confusing confluence of Cross and Washtenaw is proposed to become the front door for the EMU campus.

The office and medical area clustered on Towner in the eastern part of the City is also an asset that can be better integrated into the physical environment. Future policies will aim to preserve and enhance the buildings, while making walking, biking and taking transit to these offices easier.

The cemetery in the northern part of the City will be preserved.

The industrial areas in the south of the City represent the best hopes for a revitalized employment area. The industrial park in the southwest corner of the city has no vacancies, but could be reconfigured to accommodate additional businesses. The industrial property in the southeast corner is vacant or underutilized. The former Motorwheel site is also a potential job center. Industrial areas around the railroad provide jobs and could be places for additional workshops. Chapter 10 details plans and options to attract job centers to these properties.


ZONING – FORM-BASED CODE

The chief mechanism for implementing the Master Plan in Michigan is the Zoning Ordinance. In 2019, the City completed a zoning ordinance update that was user-friendly and implemented form-based elements; the use of illustrations clarified technical text and proscriptive regulations were translated into standards that emphasized design standards to address building orientation, parking location, architectural treatments, and building typologies that are better suited to its context. In that way, more space was made for mixed-use developments while older neighborhood’s with highly separated uses were preserved but uses and design elements were expanded in those zones where practical.

In contrast to the previous zoning ordinance, Ypsilanti's updated ordinance focuses on how development relates to the context of the surrounding community, especially the relationships between buildings and the street, pedestrians and vehicles, and public and private spaces. The Walkable Urban Districts are the ordinance's form-based characterization, as these districts especially emphasize building typologies, building orientation, and site standards. While uses are still regulated in these districts, more strict design standards are provided here to ensure compatibility with the existing neighborhood.

DRAFT

Map 11: City Framework Map



DRAFT

Chapter 5 – Transportation

“Reward the short trip” – Consultant Team member during Discover Charrette

The streets of the City were laid out in the late 19th and early 20th century. The transportation structure changed in the mid 20th century with the creation of one-way streets with the interchange with Interstate 94 and Huron. A large workforce moved in and out of the City daily at that time. Today, the streets do not handle the same type or volume of traffic. Meanwhile, the one-way streets are among the most dangerous in Ypsilanti and Washtenaw County.

In addition, the transportation within Ypsilanti is changing. The communities along the Washtenaw corridor are planning for rapid bus service along Washtenaw Avenue, increasing the capacity and frequency of the most heavily travelled bus line for Ann Arbor Transportation Authority, called The Ride. Four time a day commuter rail service connecting Detroit to Ann Arbor is anticipated to begin in 2016. Several bicycle paths and lanes, including the Border-to-Border trail spanning Washtenaw County, have been constructed or are on the drawing board, to provide safe routes for cyclists.

TRANSPORTATION PLAN

Map 12 shows the proposed transportation improvements for the City. These changes were developed during the two charrettes held in the Spring of 2013 and then refined through focus groups in the summer of that year. They represent a twenty-year vision for the transportation network of the City.

PRIORITIES

Street changes or improvements are usually expensive and time-consuming. The transportation changes proposed here are daunting for a small city with fiscal challenges. With that in mind, the following values should guide prioritization of funds and staff time for transportation efforts:

Reward the short trip

Any street network change should facilitate the walk between neighborhoods, bike to work in the City or bus trip or car ride across town. It should not help regional through-travelers to the detriment of those traveling within the city.

Follow the money, and be ready for opportunities

Funding is usually available for on-going initiatives, such as resurfacing, underground utility work that digs up the street, development projects, etc. The City should pursue grant funding with match requirements within its budget as well as creative partnerships to advance the goals of this plan. If funding is available for one project or idea but not another, the City should be flexible to advance its goals and projects within the spirit of this plan.


Make the streets better, not wider

City resources should not be used to add turn lanes, widen roads, or other means of conventionally fighting congestion in the City, when other options are available. Instead, spend City money, grants, State and Federal dollars on adding value to the place, the walkability, the aesthetics and making the streets safe. A possible exception to this rule is the conversion of a travel lane to a turn lane with the conversion of a 4-lane road to three lanes.

If car-carrying capacity is needed, it can be achieved by:

- adding new, two-lane, two-way streets to the network;
- making connections in the network that were previously severed;
- shortening trip lengths by reducing circuitous routing (i.e., restoring two-way operation, removing turn prohibitions, breaking up super-blocks);
- shortening trip lengths by adding density and rich mix of land uses in the downtown and centers; and converting automobile trips into walking, cycling, and transit trips by all of the means above plus traffic calming, building regulations that make a comfortable environment for people as well as cars, and building complete streets that are comfortable for vehicular and non-automobile modes of transportation.

Map 12: Transportation Project Map



Design with the community, not for it

When a project has been funded and is on the drawing board, the engineers and designers should talk with the community about options and suggestions before the design is final. The people using the streets everyday have valuable insight and should be included early on in the process, as mandated by the City's Complete Streets Ordinance. The public engagement process should be updated with lessons learned by each project.

TRANSPORTATION PROJECTS

The projects shown on Map 12 were developed during the two charrettes held in March and April of 2013. The projects were later vetted by the community through postings on Facebook and focus groups. These projects are described in detail below. The suggested phasing is based on a combination of expert advice and community backing. They fall into five categories: city-initiated projects, Historic Downtown projects, projects built as part of new developments, and street policy changes.

CITY-INITIATED PROJECTS

The City will decide through its Capital Improvement Plan (CIP), required by the State of Michigan, what project to move forward first. Projects for the next five years are listed below with descriptions in order of priority, as suggested by the consultant team and then advised by community input:

Coordination of pedestrian-bike connection across the I-94 interchanges at Huron and Hamilton

WATS facilitates collaboration among partner communities and stakeholders to formalize plans for a pedestrian-bike connection across the highway. City staff will coordinate efforts to ensure that they are compatible with and without the proposed roundabout at Harriet to facilitate the return to two-way function of Huron and Hamilton. During the Summer 2013 focus groups, residents felt a pedestrian connection over I-94 was a priority for completion in the next five years. Many walk or bike to the shopping, parks and other facilities in Ypsilanti Township and find the trip treacherous. [The city is currently working on a Transportation Alternatives Program grant with Ypsilanti Township and the Michigan Department of Transportation \(MDOT\) to start this project.](#)

Cross St. and Washtenaw Ave. as part of the Re-Imagine Washtenaw Plan

The confluence of the one-way streets of Cross Street and Washtenaw Avenue at the southern edge of the EMU campus is one of the most confusing intersections in Ypsilanti. Due to the wide roadway, pedestrian crossing is dangerous. In order to create a safer, more appealing place, the transportation plan recommends the separation of the two streets, and returning each to two-way function (see Figure 19 in the next chapter). [While this remains a long term goal, a nearer goal is to consider squaring-off the West Cross and Washtenaw intersection and eliminating the slip lanes, to create better crossing and bus infrastructure. This should be coordinated with the AAATA.](#)

[Proposed improvements to Washtenaw from Normal Street to Ballard Street include parking on the north side, and then Washtenaw will return to a three-lane road from Ballard Street to Hamilton Street.](#)

Reimagine Washtenaw is a cooperative planning and transportation effort between four jurisdictions and multiple transportation agencies to transform the Washtenaw Corridor between Ann Arbor and Ypsilanti by improving mass transportation, providing safe bicycle and pedestrian networks, rethinking land use, and creating coordinated standards that transform the corridor from a necessary but unpleasant experience, to a desirable, safe, and useful one. The incremental results of this work will not only create a highly-functioning, multi-modal corridor, with sense of place, but also facilitate public investment, thereby increasing property values over time by attracting new private investment.

Each local jurisdiction, Ypsilanti, Ann Arbor, Ypsilanti Township, and Pittsfield Township, is working toward uniform standards in regard to providing sidewalks, bicycle lanes, on-street parking where appropriate, and related land use standards that will put redevelopment on a pedestrian scale, with pedestrian facilities throughout the corridor. The transportation agencies, The Ride, Michigan Department of Transportation, Washtenaw County Road Commission, and Washtenaw Area Transportation Study (WATS) are working together on a long-term concept for road design and right-of-way requirements that will allow for the bicycle and pedestrian improvements, on-street parking where appropriate, with the potential for a dedicated transit lane or light-rail in the long term.

As part of the 2013 Right-of Way study facilitated by Washtenaw County on behalf of the local jurisdictions, preferred street segments are being developed for the entire corridor. Future use scenarios were also determined, and many recommendations are based on traffic volume reductions that are expected to be gained through land use changes, traffic demand management practices to be adopted by major area employers, and related transportation mode shifts. Throughout the entire corridor, innovative stormwater management systems, beautification and landscaping, sidewalks, and bicycle lanes are planned.

For the segment in the Ypsilanti city limits (from west to east), a narrow landscaped median is recommended from Hewitt to approximately the Courtland intersection to provide refuge for pedestrian crossings, improve aesthetics, and slow traffic. East of that a transition is recommended to reduce from four travel lanes to two, adding on-street parking on both sides of the street, until east of Oakwood. At that point, with the separation of Cross and Washtenaw and a change from one-way to two-way traffic, on-street parking may only fit on one side of the new streets. It is suggested that it stay on the north side of the street by EMU, to provide easy parking for administrators and students.

Return one way to two way streets

These streets are not friendly to pedestrians due to the high speed of vehicles. The one-way streets are also difficult to navigate and create longer trips for pedestrians, cyclists, transit riders, and motorists. A long term goal of returning the two-way functions of these streets would support the urban framework. To get to this long term goal, the City would like to take a phased approach.

Phase one could include “right-sizing” the roads for their vehicle capacity. Within these roads’ current configurations, some improvements can be made to improve nonmotorized and public transit access. For instance, on Hamilton Street starting at the intersection with Pearl Street, the right-most lane becomes a bicycle lane. The right-most lanes on Hamilton St. and Huron St. between Michigan and Harriet will become bicycle lanes. The right-most lane on Huron St. south of Harriet will become landscaping. In terms of Washtenaw Ave., the left-most lane will become on-street parking between Normal and Ballard.

Phase two could include the squaring up of curved intersections, and removal of slip lanes. For example, improving the West Cross and Washtenaw intersection would mean teeing up the intersection and providing additional green space and improved bus facilities in lieu of the slip lane.

Phase three would then be the two-way conversion. Long-term land use planning should be mindful of the possible excess of land that results from the conversions.

Figure 14: Roundabout for Two-Way Conversion



The drawing above shows a roundabout to facilitate two-way conversions of Huron and Hamilton, while maintaining safe access to Interstate-94. In this instance, cooperation with the existing warehousing facility would be needed. Based on online and in person feedback, the Ypsilanti community has a love/ hate relationship with roundabouts. Other design options exist and should be explored with community input when plans are being developed. Drawing by: AECOM

HISTORIC DOWNTOWN PROJECTS

Several of the transportation projects are located in the Historic Downtown. These projects could be carried out in conjunction with the Downtown Development Authority (DDA) and should be included in any updates of the DDA Tax Increment Financing Plan:

Raised intersections at Huron & Michigan Avenue and Hamilton & Michigan Avenue

While it was initially hoped that a ramp for pedestrians and a “table top” with a gentle incline to slow down vehicles, this is not currently plausible because it is not in the Michigan Manual on Uniform Traffic Control Devices.

Washington Street as a flush festival street

Washington Street, between Pearl Street and Michigan Avenue, is often closed to traffic for concerts. Changing surfaces to a curbless street would create more pedestrian friendly event space (see figure 15).

Figure 15: Curbless “Festival” Street Example



Source: AECOM

NEW DEVELOPMENT

Many of these projects should be wrapped into anticipated development in adjacent areas, both private and public:

Cross Street and River Street in Depot Town as flush festival streets

With a new train stop near the intersection of Cross Street and River Street, more pedestrian and event activity is expected in Depot Town. Cross Street is already often used for events. Curbless streets will help pedestrians navigate and ease of events. Drivers of vehicles know where the traffic lanes and pedestrian areas are by different types of materials, both color and texture, as well as bollards or other street furniture. The cost and design should be coordinated with the new train stop and incorporated into the DDA TIF plan.

Vehicular Bridge and extension of River Street to Factory

One of the most expensive proposals in the transportation plan is to extend River Street from Michigan Avenue across the Huron River to Factory Street, in coordination with the Water Street redevelopment. The extension would connect the Water Street redevelopment area to the highway but also link the neighborhoods in the southeastern part of the City with the Historic Downtown. Grant opportunities, coordination with developers and other funding resources should be explored.

New Streets in Redevelopment Areas

New streets are shown in several redevelopment areas. These streets should be built by the developer but in accordance with a structure and design that meets the community’s guiding value of walkability. The Water Street area is owned by the City, which could dictate street design as a condition of sale. For the other areas, zoning and design requirements should be updated to mandate a walkable street grid that connects and completes the existing streets.

Multi-Use Paths

Multi-use paths are shown connecting Railroad Street and the cemetery in the northern part of the city to Frog Island Park. Both areas are underutilized and could redevelop in the next ten years, especially when rail service begins. Pedestrian links to job centers in the districts should also be built. For example, the City holds an easement that could be used for a path to connect the industrial park

to the neighborhood to the southwest. Regulations should be updated to seek easements for proposed paths in these areas.

STREET POLICY CHANGES

Two areas of the City are proposed for overall changes to the streets to make them more accessible to everyone:

Harriet Street Road Diet

Harriet, from Huron to Perry, should become a two-lane street with on-street parking and sidewalks separated from the roadway. The City should change the design standards for Harriet. The City may want to consider a road diet continuing east on Harriet/Spring/ Factory/Maus but maintaining the ability of trucks to access the job district.

Leforge Road and Huron River Drive Reconfiguration

The intersection at Leforge and Huron River Drive is challenging to pedestrians but is where many EMU students live and walk to campus. Within a ten-minute walk are some of the largest multiple-family complexes in the City, a city park and

EMU campus. The City should make it a high priority work with EMU to create a vision for this area as an interconnection between the City and the University. Both the University and the City should then update their plans and policies for the area accordingly. The level of detail, coordination and community input warrant a planning process for this area specifically. If funding is available, an intense design process should be part of the five-year update to this plan.

PROGRAMS

Two programs are part of the master plan to increase the ability of people to use any modes of transportation they choose anywhere in the City:

- Expand car sharing program in the Historic Downtown. *Additionally, bikeshare could be programmed into the three core districts.*
- Create and publish maps with bicycle and walking routes in the City. *These may be interactive maps as well, accessed via the website or a mobile application.*

DRAFT

Chapter 6 – Centers

“The heartbeat of any community are place places to gather, especially on a social level.” -Facebook comment about post asking how to strengthen centers

There are three centers within the City of Ypsilanti – the Historic Downtown, Depot Town and Cross Street. They are active, synergistic places where people come together. Their historic buildings are the calling cards of the City. These are the places where people shop, go to school, live, come to work, visit, drop by City Hall, eat, gather and have fun. They host events which bring thousands of visitors each year and bring the City together as a community. All three centers are in the City’s Downtown Development Authority (DDA), supported by the tax increment revenue generated from the DDA.

PAST POLICIES

In adjusting to the shift from a manufacturing economy, Ypsilanti has focused on small business development, especially within the centers. The City has worked to maintain low barriers of entry for new businesses, and encourages entrepreneurs to start up businesses. However, new construction is limited due to physical constraints of the City, among other factors.

The City has successfully encouraged conversion of upper stories in the Historic Downtown and Depot Town into housing. The units brought onto the market in the past decade have been rented or sold quickly.

More recent economic development efforts have focused on placemaking as well as absorbing existing commercial and residential vacancies. Walkability, regional public transit, and work toward securing commuter train service on the Ann Arbor to Detroit Line are current transportation goals.

PUBLIC INPUT FROM 2013

Input about the centers was gathered in focus groups, the 4-day long Discover Charrette and through social media. Across the board, participants felt the centers were great places that should be preserved but could be improved in terms of cleanliness, safety and walkability.

Public input was positive about the Historic Downtown, with emphasis on preservation of the historic buildings. Participants felt the walkability and safety of the area could be improved, as well as the cleanliness of the streets and parking lots. Many participants felt there were too many bars and restaurants while others wanted these types of gathering place. The adult club was also a

source of tension, with many wanting it to be removed and others saying it should be left alone.

Depot Town was continually cited as an asset of Ypsilanti, to be built upon and improved. Many supported the opening of daily commuter rail service in Depot Town, with a few citing safety concerns such as how to accommodate long-term parking and improved bicycle and pedestrian connections.


The Cross Street area was generally seen as positive, with much improvement in the past five to seven years. The focus group with EMU students requested that stores be open later at night, when they are most likely to use them. The intersection of Cross and Washtenaw as well as the one-way streets was seen as a barrier to pedestrians and vehicles easily navigating the area.

DATA

According to the commercial analysis for this project, the centers are three strong commercial anchor locations that provide a wide range of specialty goods and services. The devoted resident base and healthy EMU market provide a strong customer base for these businesses. Market analysis completed for these areas by Hyett Palma in 2009 concluded that the Ypsilanti DDA area captures approximately 10%, or about \$121 million of the estimated region’s demand at \$1.1 billion annual demand. This study, now about a decade old, should be updated to determine if the DDA’s policies have been able to capture a greater of that demand.

These locations have limitations to growth, due to the historic building stock. Focus group participants described these as ideal locations for small to mid-sized operations that could fit a first-floor foot print of 2,000 – 4,000 square feet. Some businesses have been successful at expanding into neighboring storefronts, but the reality of growth is fairly limited for a major food store, entertainment complex or larger footprint a national clothing retailer would require. A few buildings with larger footprints are available - the Thompson Block in Depot Town as well as the Smith Furniture Building and the Pub 13 building in the Historic Downtown.

Map 13: Centers City Framework Map



POLICY UPDATE FROM 2013

Certain actions will apply to all three centers, in particular the form-based zoning. The following are expected in the Historic Downtown, Depot Town, and Cross Street:

Create building standards for centers that preserve their architecture - Completed

All three centers have unique, historic buildings that have been protected by the regulations of the historic district. In 2014, the zoning ordinance was passed with form-based zoning elements that require building location, story height, front door and window location to match the existing architecture, reinforcing existing patterns and the historic district regulations.

Finish Upper Stories - Ongoing

Upper story conversions in the Historic Downtown and Depot Town have been successful, bringing new residents. The zoning ordinance was updated to encourage private investment on upper story units, and in 2018, the DDA was awarded a MEDC facade grant for \$300,000 which has enabled them to improve properties according to historic guidelines. The City shall work to update its local and National Register historic district listings. Updated listings will expand the number of contributing buildings and afford greater opportunities for Historic Tax Credits in rehabilitations.

Allow renewable energy facilities on all buildings - Completed

The City has several buildings in the centers with solar panels and geothermal facilities, such as City Hall and the Ypsilanti Food Coop. The zoning ordinance was updated in 2014 to allow alternative energy (photovoltaic, geothermal, and wind) as an accessory use in every zone. The Historic District Commission has adopted alternative energy standards to guide the installation of such facilities on historic buildings.

Draft a business attraction plan for the centers - Ongoing

The City, Small Business and Technology Development Center, Ann Arbor SPARK, and the DDA should work together to create a process to guide business attraction for Downtown, Depot Town and Cross Street.

Encourage activity during the day and evening – Ongoing

A number of participants, especially EMU students and other youth, expressed a desire for opportunity in the City's centers during the evening as well as the day. Many felt there was not much available after hours except for bars. The DDA and the City should work together with existing businesses to expand their hours and factor the need for evening uses that are friendly to people of all ages into

the business attraction plan. Changes should be communicated to EMU faculty, staff, and students who would be a big portion of patrons.

The City has updated its zoning to allow for a greater mix of uses that could draw people to its centers, and the DDA continues to work on business development through event sponsorship like First Fridays, Ypsi Pride, Festival of the Honey Bee, and Ypsi Glow.

Continue and expand the number, type and location of festivals and events - Ongoing

Events bring thousands of visitors and residents alike to the centers of Ypsilanti. If it can, the DDA and Ypsilanti Convention and Visitor's Bureau, supported by the City, should increase the number of events and make sure they occur across the City centers and in all four seasons. Options could include the use of College Place, other areas in and around EMU's campus, Frog Island and other large City parks as well as downtown streets. The City works with the Convention and Visitor's Bureau to market events and destinations in Ypsilanti. The city also passed a special events policy to enable more activity.

Create a marketing campaign for the City of Ypsilanti - Ongoing

Throughout the public engagement process, participants felt that the City had an undeserved reputation in the region as an unsafe place with not much to do. A marketing campaign, in conjunction with the Ypsilanti Visitors and Convention Bureau, was suggested as a five-year goal.

Install a way-finding system - Completed

The DDA, city of Ypsilanti, Ypsilanti township, and the Washtenaw County Convention and Visitor's Bureau installed unified wayfinding signage throughout the city and township to help visitors find places to shop and recreate.

HISTORIC DOWNTOWN

Historic Downtown Ypsilanti is located at the intersection of M-12, the old Chicago Road, and the Huron River. The plan for downtown is to make it safer and maintain its diversity and sustainability. These following items, except for zoning changes, should be included as part of the update of the DDA's Tax Increment Financing Plan and pursued in conjunction with consensus of the business community downtown.

Increase walkability - Ongoing

The return of Huron and Hamilton to two-way streets will increase the walkability of the Historic Downtown by slowing traffic. The raised intersections on Michigan at Huron and Hamilton will also slow traffic and making crossing these intersections easier for pedestrians. Ypsilanti has completed a feasibility study and is in the public participation phase. The city has incorporated these projects in the Capital Improvement Plan and is coordinating with MDOT for assistance on completing this project.

Build curbless “festival” street on Washington - Ongoing

A curbless street on Washington, between Michigan Avenue and Pearl, would make set up and operation of outdoor concerts already occurring there easier. Most likely, more events could be held there, increasing the diversity of events and visitors to the downtown.

Use vacant storefronts for temporary retail uses - Ongoing

Any number of vacant storefronts diminish the vibrancy of downtown. Also, many entrepreneurs cannot afford to open a full scale operation. By defining a process to allow a “pop-up” store in vacant storefront, the City and the DDA have enabled this temporary use. However, it is still up to the property owner to decide how to use his/her building. The DDA does conduct outreach to landlords, but the effort continues to make this a consistent practice.

Maintain and expand transportation options, including improvements to the Ypsilanti Transit Center (YTC) - Ongoing

Bus service to the downtown should continue as well as the expansion of the car sharing service. The bus center should be treated as a hub of the downtown, with wayfinding, signs, and street furniture to make coming to the center an enjoyable experience as any other in the downtown. The increased ridership has put pressure on the YTC to accommodate users. The WATS Long Range Transportation plan

has made it a regional priority to update that space or to re-locate it where necessary to be a better functioning space.

DEPOT TOWN

Depot Town grew up around the intersection of the regional and inter-urban railroads and the Huron River. Similar to downtown in the size and age of buildings as well as land use, Depot Town covers a smaller area. It is a regional draw due to the restaurants and festivals held in the adjacent parks. When train service is secured, the area is expected to have more activity from commuters on foot, bicycle and car as well more development pressure. The Ride plans a connector bus route to the stop as well. The plan, shown on the following page is a transit-oriented design to integrate the train stop and increased activity into the fabric of Depot Town.

Maintain Depot Town as a place for the pedestrian first – Ongoing

Depot Town is a safe, walkable place in Ypsilanti. A curbless street is proposed on River Street to ease access for pedestrians, including those in wheelchairs or with baby strollers. Parking lots should be away from the street front, as shown in the concept plan.

Build curbless “festival” street on River and Cross – Ongoing

A curbless street on River and Cross Streets adjacent to the train platform would increase pedestrian accessibility and facilitate events.

Create a public space at new train station – Ongoing

Improvements and an expansion of the existing Market Plaza is shown in the concept plan as part of the new train station. Public spaces allow a diversity of temporary uses to happen (festivals to farmers’ markets) and gives opportunity for people of all types to come together. The development of the train station has been delayed and alternative designs are being considered, of which there is very little space to include public space.

Figure 16: Concept TOD Plan for Depot Town



The concept plan was developed to meet community values when daily train service starts. The plan features a plaza, shown in red, which could be used for a farmers' market and other events. The Freight House is preserved. The portions of River and Cross Streets in pink is shown as a curb-less "festival" street - making crossings easier for pedestrians on a daily basis while helping the accessibility of the events in Depot Town. A small park space is proposed between River Street and the tracks. Parking is away from the street to the west of the railroad tracks. The design of access to Frog Island park will need to be coordinated with previous designs in the final plans. Drawing by: AECOM

Locate permanent year-round home for Depot Town Farmer's Market - Completed

The market is currently located in Market Plaza of the Freight House in Depot Town. As plans are developed for the train depot, a permanent year-round location for the farmer's market should be included in the design. The concept plan shows preservation of the Freight House and the creation of a plaza where the market could be held during the summer months.

CROSS STREET

Cross Street is the interface between the campus of Eastern Michigan University and the City. It serves as a commercial center for both Eastern Michigan students and the adjacent neighborhoods. The plan improves the function of the roads for all while integrating Cross Street with EMU. All of these projects should be pursued in conjunction with EMU and the DDA.

Separate Cross Street and Washtenaw Avenue - Ongoing As shown in the concept plan in Figure 17, Cross Street and Washtenaw Avenue can be separated and made two-way streets. The separation would improve the safety of this high-crash intersection by calming traffic, creating safer pedestrian crossings and better navigation for all modes of transportation. *This infrastructure improvement has*

been included in the Capital Improvements Plan. As stated earlier, this will be part of a phased approach where the actual separation would be last and final phase.

Create a "front door" for EMU by reconfiguration of Cross Street and Washtenaw - Ongoing

During the Design Charrette, EMU officials agreed that the campus needs an entrance and the land created by the pulling apart of the two roads could create a mixed use area with a gathering area and possibly housing. *This project requires coordination with MDOT for implementation. This is related to the aforementioned Separate Cross Street and Washtenaw Avenue plan.*

The centers host a variety of events and land uses in distinctly urban places. The DDA should use its ability to attract and assist businesses to maintain a vibrant business mix, while the City should use its policies to maintain the building form. The "Centers Implementation Matrix" shows the time frame for each action detailed in this chapter and how it meets the City's primary guiding values of safety, diversity, and sustainability. This matrix is intended to be used by decision-makers to create reports and work plans as well as evaluate progress on an annual basis.

Figure 17: Reconfiguration of Cross & Washtenaw

The concept plan below is a scheme to separate Washtenaw Avenue and Cross Street. The proposal is to pull the two roads apart, eliminating the existing convergence and creating public and developable space, shown in green. The existing statues and the water tower will be linked with a public space that will also give refuge to pedestrians crossing the streets. A developable area will be created to the east of the water tower. Student housing and parking were discussed as possible uses with EMU. Drawing by: AECOM



Figure 18: Centers Implementation Matrix

Action	Timeframe	Location	Safety	Diversity	Equity	Environmental Sustainability	Economy
Continue and expand the number, type, and location of festivals and events	Ongoing	All centers		x			x
Continue efforts to fill upper stories	Ongoing	All centers		x	x	x	x
Maintain and expand transportation options	Ongoing	Downtown	x		x	x	x
Draft a business attraction plan for Downtown, Depot Town and Cross Street	1-5 years	All centers		x			x
Encourage business and event activity during the day and evening	1-5 years	All centers	x	x	x		x
Marketing campaign for the City of Ypsilanti	1-5 years	All centers					x
Curbless "festival" street on Washington	1-5 years	Downtown	x		x		x
Use vacant storefronts for temporary retail uses	1-5 years	Downtown	x		x		x
Permanent year-round home for Downtown Farmer's Market	1-5 years	Downtown	x	x	x	x	x
Permanent year-round home for Depot Town Farmer's Market	1-5 years	Depot Town	x	x	x	x	x
Increase walkability (2-way streets & raised intersections)	1-10 years	Downtown	x		x		x
Curbless "festival" street on River and Cross	1-10 years	Depot Town	x		x		x
Create a public space at new train station	1-10 years	Depot Town	x		x		x
Separate Cross and Washtenaw	1-10 years	Cross Street	x			x	x
Create a "front door" for EMU with reconfiguration of Cross and Washtenaw	1-10 years	Cross Street	x	x			x

Chapter 7 – Neighborhoods

“Charming neighborhoods” – Sticky note on what to preserve, submitted during the Discover Charrette

Ypsilanti has a wide variety of neighborhoods, some built over a century ago and others just decades old. The residents, streets, and architecture create distinct communities with the 4.3 square miles of Ypsilanti. However, when looking at public comment and data on the age, size, and types of housing, the neighborhoods fell into two framework categories: Central Neighborhoods and Outlying Neighborhoods, as shown on Map 14.

PAST POLICIES

The City of Ypsilanti’s housing policy efforts have been in response to the following themes:

- The sizable population of college students and lower income families, along with large supply of multi-family housing, has meant that nearly 2/3 of households rent their homes.
- The large share of pre-war and mid-century structures with energy-efficiency difficulty creates challenges while also drawing residents to historic neighborhoods.
- The “landlocked” and nearly built-out city has lacked the vacant land to participate in the construction of new housing seen in surrounding municipalities.

In 1978, the City created a Historic District and in 1983 began rental housing inspections. These two programs are generally considered to have been successful in stabilizing and maintaining the city’s housing stock and neighborhoods. In 2003, the City enacted a dangerous buildings ordinance that provided an additional tool for addressing the worst nuisance properties and stabilizing surrounding neighborhoods.


The City began implementation in 2009, when foreclosure activity led to fears of increasing numbers of abandoned buildings, but at that time quickly proved effective in spurring removal or rehabilitation of long-vacant buildings.

The City has also “down zoned” residential areas in an effort to encourage home ownership, most successfully in the Historic Eastside. The most recent occurrence Shape Ypsilanti Master Plan (DRAFT UPDATE) – January 5, 2021

was in 2006 when around 800 residential parcels in the Cross Street neighborhood were rezoned to reduce maximum permitted density, as laid out in the 2001 Cross Street Neighborhood Improvement Plan. This effort had mixed success since the fall of the housing market in the mid-2000s resulted in lower prices for housing and the high conversion costs to single-family or a smaller number of units were not financially viable in that market.

The previous zoning ordinance defined a range of different multiple-family living uses – rooming house, fraternity, etc. – each with different regulations drafted for those uses at the time of their inclusion in the zoning. The result was confusing regulations that were not flexible for innovations. The updated zoning ordinance and definitions provide better clarity.

Map 14: Neighborhoods City Framework Map



PUBLIC INPUT

In every focus group at the beginning of the 2013 Master Plan process, participants felt the City of Ypsilanti should have housing for people of all ages, races, incomes and abilities in the City as a guiding value. Residents across the City expressed pride in their neighborhoods.

Tension about the location of rental housing – whether townhouses, multiple-family dwellings or large houses converted multiple dwelling units emerged during the charrettes and implementation focus groups. Many participants expressed concerns about rental housing, particularly EMU student housing, expanding into neighborhoods and degrading its value. Others saw the need for student housing in a college town. As EMUs enrollment declines or shifts towards online classes, there could be opportunity to convert unused dorm rooms into units open to residents besides students. Meanwhile, some residents expressed the need for housing with little maintenance, such as a condominium or a rental, but suitable for seniors or young professionals. Ypsilanti lacks this type of housing, often considered as the “missing middle.”

In 2019, residents expressed a desire for “complete neighborhoods” in the community-wide survey. In fact, 68% said that the completeness of the neighborhood was the deciding factor in where they choose to live. The definition of completeness was up to them to decide through the multiple choice question; their results show that in addition to residential uses, residents want their neighborhoods to have recreation space, sidewalks, public transit options, community gardens/trees, and daily need good and services.

DATA

As shown in Chapter 3, the neighborhoods have distinct patterns in terms of age, size, number of units and homeownership/rental status. Closer to the Historic Downtown and EMU’s southern border are clustered large houses built before World War II with a variety of numbers of dwelling units and a mix of owner-occupied units and rentals. Neighborhoods nearer to the borders of the City were built in the later part of the twentieth century and are either single-family houses or multiple-family buildings. With the exception of the Heritage Park area, the majority of the single-family houses are owner-occupied. Multiple-family is almost exclusively rental, except for condominiums built near EMU’s western

Shape Ypsilanti Master Plan (DRAFT UPDATE) – January 5, 2021

border and along Washtenaw near EMU and the Historic Downtown. However, overall, most single-family dwellings are owner-occupied.

In the central neighborhoods, the Historic Eastside has a higher percentage of homeownership and a unique lot mix with many deep lots. Due to the down-zoning decades ago, this neighborhood has a higher rate of homeownership than other neighborhoods built around the same time. The Historic South Side neighborhoods have a range of building types - with some apartment buildings but mostly four units or less - and standard sized lots. The Midtown and Riverside neighborhoods have the widest variety of building types - from cottages to large apartment houses along with other group living arrangements, as well as a large range of lot sizes.

Despite the distinct differences, over two-thirds of the housing units in Ypsilanti are rented. Other college towns have a similar housing mix, including Ann Arbor where 55% of the housing units are rented. Renters are integral members of the community; planning for renters and access to affordable housing shall be continued.

POLICY AND PLANS FOR ALL NEIGHBORHOODS

The following actions apply to all neighborhoods:

Continue and increase rental inspections and enforcement- *Ongoing*

Rental inspection and enforcement of code violations are vital to maintaining safe rental housing. City budget dedicated to rental inspection and enforcement should be maintained, if not increased.

Streamline multiple-family living arrangements into categories based on number of units and form - *Completed*

Living arrangements for multiple-family situations should be collapsed in the form-based code into building forms – duplexes, estate houses, townhouses, and apartment buildings – with categories of number of units matching those in the State Building Code – 2-units, 2-4 units and 5 or more units. Group living arrangements, such as rooming houses and fraternities, will continue to be allowed in estate houses but with regulations for that general use, not tailored for each instance. The City updated its zoning ordinance to reflect these living arrangements.

Assist continuation and expansion of EMU Live Ypsi program - Ongoing
Eastern Michigan University, with staff assistance from the City and Washtenaw County, offers a forgivable loan program for faculty and staff purchasing a home in the City of Ypsilanti. The City will continue its support of this program.

Plan and zone for range of housing typologies for the needs of all ages and abilities- Ongoing
Due to demographic shifts, several neighborhoods have increasing numbers of senior citizens, who may or may not choose to stay in their homes. Similarly, young professionals and families are looking for homes integrated into the community. Neighborhoods should be planned to provide a diversity of housing types within neighborhoods for all stages of life. *The City has used its ordinance to expand housing types permitted in residential zones, but it may be appropriate to further expand housing types, such as accessory dwelling units.*

Create “Eco-Districts” in neighborhood parks - Ongoing
Residents suggested that demonstration projects of community gardens with hoop houses, rain collection systems, and renewable energy projects be clustered in eco-districts in neighborhood parks, in the Historic Downtown, and other areas. Temporary events were also suggested in these areas. An existing example of a demonstration project is the Luna Lake rain garden in Prospect Park. While the City cannot take on development of these districts, partnerships with educational institutions and neighborhood groups may provide resources to establish them. *The City has permitted these uses within parks and other zones and welcomes opportunities that follow these guidelines:*

- The proposal be in the proper location of the park to complement existing activities, both active (sports areas and playgrounds) and passive (walking or siting areas)
- The proposal should be located in an area with appropriate lighting and visibility to assure safety of users and enough natural surveillance to be kept watch over by neighbors.
- Proposals should be part of an adopt-a-park effort
- Policies will need to be developed to ensure maintenance, both short and long term.

Continue Home-Based Entrepreneurship - Completed
The City encourages home-based businesses through clear regulation. The updated Shape Ypsilanti Master Plan (DRAFT UPDATE) – January 5, 2021

zoning allow businesses within homes using the current regulatory scheme for uses.

Regulate the form of buildings to preserve the character of neighborhoods - Completed
Using the building types existing within the neighborhoods, the zoning regulations should preserve the architectural patterns. *The zoning ordinance was updated to include Building Types.*

Re-survey of the Historic District – Ongoing
The Ypsilanti Historic District designation was completed in 1978 and 1983. The current listing documents are not sufficient for addressing common issues with the historic resources, including identification of contributing and non-contributing resources; areas and periods of significance; and clear boundaries. The district should be resurveyed and a new Historic District Study Committee formed to update the district. A new study committee report would greatly aid property owners, staff, and the commission with making the best decisions for the preservation of Ypsilanti’s most historic resources. Additionally, it would clear up confusion with the outdated boundary map, as some boundary lines currently bisect parcels, and includes part of the Water Street development area, where all of the historic resources have been removed.

Consider new opportunities for accessory dwelling units – Ongoing
The City engaged with residents during a January 2020 meeting. While findings varied, accessory dwelling units appear to be embraced by a number of community residents. It was inferred from this meeting that residents want accessory dwelling units to be permissible uses in a greater number of zoning districts, but with protections to secure harmony with the neighborhood. The following regulations might be considered to keep this harmony: size and height, ratio to principal structure and green space, and parking. Future community meetings may guide further action. The City shall first explore these opportunities in Central Neighborhood-based zoning districts and may consider expanding to Outlying Neighborhoods if the appropriate regulations are put in place.

Revise the family/occupancy caps - Ongoing
The current zoning ordinance limits a family to three unrelated persons residing together in a dwelling unit. An exception to that requirement is in the GC, NC,

HC, and MD zoning districts, which limits a family to four unrelated persons. Nonetheless, these restrictions are onerous on functional families, families that have a demonstrable and recognizable bond characteristic of a cohesive unit despite not being related by blood, marriage, or adoption. A more sensible strategy, proposed by the Citizen Committee for Housing Affordability and Accessibility, might be to update the zoning ordinance to revise the limits for a functional family in relation to bedrooms. An updated ordinance might require the number of unrelated persons to not exceed two persons per bedroom [Report, p. 36-37].

Relax dwelling size, lot area, and lot dimensions requirements - Ongoing

The City currently requires a dwelling to have a minimum of 500 square feet of usable floor area in its R1 zoning district, the least intense residential district. The R1 district also requires a minimum lot size of 5,000 square feet with a minimum lot width of 45 feet. These three standards create exclusionary effects for someone attempting to find a place to build their small home or locate a small manufactured home. Additionally, these standards can be burdensome to a current property owner who wishes to divide a piece of their land to provide for a dwelling. The City may consider relaxing some of these standards in not only the R1 district but also in the various Walkable Urban District building types.

Create visitability requirements - Ongoing

Visitability pertains to the physical features that make a house “visitable” by guests but also offering features that may be desirable for future owners/tenants. A home can be considered “visitable” if it has: at least one no-step entrance; doors with 32 inches of clear passage space; and a bathroom on the main floor that is wheel-chair accessible [Report, p. 36]. Visitability requirements should be written into the zoning ordinance, or at the very minimum considered by the Planning Commission when authorizing special land use permits for new developments.

Allow for density increases in residential zoning districts for the purpose of housing affordability – Ongoing

For the sake of affordability, increasing densities in areas which can better serve more than one-family residential uses should be revisited by the City. One potential strategy regards corner lots- lots that adjoin two streets at their intersection. These are naturally more busy and active lots. As a way to make best

use of corner lots, the City should consider making corner-lot duplexes (two-unit dwellings) permitted by-right in any residential zoning district.

Revisit home occupation requirements and consider live-works - Ongoing

To enhance economic opportunity for residents, the concepts of home occupations and live-works should be revisited. Home occupations can be an incremental, small-scale strategy to allow a resident some flexibility in operating a remote business or providing a small service from their home. Live-works on the other hand can be a more formal strategy in allowing a resident and their business- a more publicly facing, walk-in oriented business- such an art studio or professional office to take place within the same physical unit.

CENTRAL NEIGHBORHOODS

These neighborhoods are some of the oldest in Ypsilanti. Initially oriented on the Huron River, they are built on a grid street network connected to the adjacent business districts. They border downtown, Depot Town, and EMU. These neighborhoods have a range of residential building types, with churches, schools, stores, and gas stations intermixed. Around the railroad, industrial uses are mixed into the neighborhood.

The following policies and actions aim to preserve the form of these neighborhoods while enabling the sustainability of all the buildings:

Preserve the character of the area by using regulations on street type, building type as well as use - Completed

Elements of form-based code were developed based on existing streets, lot sizes, building types, and uses to preserve the context of each area. The goal was to eliminate regulations that need exceptions to preserve existing context by creating rules based on the context. In addition to the zoning updates, engineering standards were updated.

Regulations of the variety of housing types, uses, and lot sizes will be calibrated to the existing patterns – Completed

Central neighborhoods do not all look alike so the regulations reflect the differences with appropriate gradations in the variety of uses and building types based on existing patterns. Three core neighborhood zones were created: Core-

neighborhood single-family, core-neighborhood mid, and core-neighborhood with the main difference being the varying levels of housing density permitted.

Preserve Bell-Kramer residential land uses – Ongoing

The Bell-Kramer neighborhood, located near the southeastern corner of S. Huron St. and Spring St. underwent planning changes from 2013 to 2018. The neighborhood was identified as a District in the City Framework and was zoned mostly PMD due to its proximity to the former landfill to the south. However, City testing for contaminants came back safer than previously understood. The City engaged in meetings with the residents and heard their wishes to keep the neighborhood residential. Consequently, in 2018 the City rezoned the neighborhood back to residential, to CN-Mid. This zoning designation better stabilizes the residential land uses of the neighborhood. In hope to better protect the health of the residents, the City also updated a well-restriction ordinance which prohibits the drilling and use of wells in the neighborhood. It is recommended the Bell-Kramer neighborhood keep its residential character. The City Framework was updated to reflect this change from *District* to *Central Neighborhood*.

OUTLYING NEIGHBORHOODS

These neighborhoods, constructed during or after World War II, are almost exclusively residential uses, with single-family and multiple-family uses separated. Single-family residences are usually smaller than those in the central neighborhoods. The zoning changes below are designed to stabilize these neighborhoods:

Limit uses to predominantly single-family residential uses in areas with small houses, suited for only single-family-Completed

Several neighborhoods - Heritage Park, Worden Garden, Prospect Gardens, Miles neighborhoods and the houses on River Street from Holmes to the north to Cherry – were formerly zoned for two-family residential use. Because very few structures are two-family nor have the floor area to accommodate two dwelling units, these neighborhoods were limited to single-family uses when the zoning ordinance was updated. These neighborhoods may have potential for accessory dwelling units, based on where there is existing infrastructure. Future community meetings may guide proper action.

The matrix in figure 19 shows the time frame for each item and if it meets the goals of safety, diversity, and sustainability. It, in conjunction with the other matrices, should be used by decision-makers to create reports and work plans as well as evaluate progress on an annual basis.

Figure 19: Neighborhoods Implementation Matrix

Action	Timeframe	Location	Safety	Diversity	Equity	Environmental Sustainability	Economy
Continue and increase rental inspections and enforcement	Ongoing	All neighborhoods	x		x	x	x
Assist continuation and expansion of EMU Live Ypsi program	Ongoing	All neighborhoods		x			x
Regulate the form of buildings to preserve the character of neighborhoods	Ongoing	All neighborhoods		x	x		x
Create "Eco-Districts" in neighborhood parks	1-10 years	All neighborhoods		x		x	
Re-survey of the Historic District	1-10 years	All neighborhoods			x	x	
Consider new opportunities for accessory dwelling units	1-5 years	All neighborhoods		x	x	x	x
Revise the family/occupancy caps	1-5 years	All neighborhoods	x	x	x		
Relax dwelling size, lot area, and lot dimensions requirements	1-10 years	All neighborhoods			x	x	x
Create visitability requirements	1-5 years	All neighborhoods	x	x	x		
Make corner lot duplexes allowable by-right	1-10 years	All neighborhoods			x	x	x
Revisit home occupation requirements and consider live-works	1-10 years	All neighborhoods		x	x	x	x
Preserve Bell-Kramer residential land uses	Ongoing	Central neighborhoods	x		x	x	

Chapter 8 - Corridors

“They should connect cities, not be primary destinations.” - Comment on main roads, like Washtenaw, submitted on the website, shapeypsi.com

There are two types of corridors located in Ypsilanti. One is a general corridor which contains a variety of medium to smaller parcels and is adjacent to both types of neighborhoods, such as College Heights and Midtown. General corridors are home to predominantly commercial establishments, restaurants, offices, and other businesses that are geared toward automobile traffic. The land pattern is typically linear and provides predominately commercial and office uses that are adjacent to residential neighborhoods. Usually a physical barrier is created to “protect” one use from another by way of a wall or heavy landscaping.

The second type is a historic corridor, which differs slightly from the general corridor in scale and building type. The historic corridors are characterized by smaller commercial establishments and offices mixed with large historic structures (such as historic homes that are now being used for a variety of purposes). Historic corridors generally have a more seamless integration with the surrounding neighborhoods.

PAST POLICIES

The current zoning ordinance regulates the use of the land primarily, linking a certain number of related land uses to individual parcels of land. In corridors, these zoning districts have laid out in strips, usually commercial but also office, civic, and multiple- and single -family. The resulting zoning maps are a patchwork of districts down the corridors. However, the uses cannot freely flow down the corridors due to the use classifications. Rezonings are often required.

In general corridors, the landscaping regulations required by the zoning districts and overlays are suburban in nature. The entry-way overlay on all general corridors at the borders of the City requires a 10-foot greenbelt around the entire parcel. Since these lots are generally smaller than suburban counterparts, the required setbacks and landscaping either do not fit on the parcels when redeveloped or limit the building size to a footprint only compatible with uses needing a small square footage. The result has been vacant or underutilized buildings along the general corridors or approvals that waive requirements. The current zoning does not encourage improvements due the complexity of applying the standards.

The regulations of the Historic District have maintained the integrity of the buildings along the historic corridors. The high speeds of the one-way streets on the historic corridors of Cross, Huron and Hamilton, however, make the street itself a hostile environment, lessening the value of some the buildings.

PUBLIC INPUT

During the charrettes, participants often spoke about the difficulties of walking or cycling in the corridors of the City. They also expressed disappointment about the number of vacant or underutilized stores.

POLICY AND PLANS FOR ALL CORRIDORS

The following items apply to all types of corridors:


Designate the appropriate building form for each corridor- Completed

The form-based code will designate types of buildings to match the existing patterns within the corridor and, if applicable, the change envisioned by the community for that area. [The zoning ordinance was updated to include building types in “Walkable Urban Districts.”](#)

Retain the mix of existing uses within each corridor but allow them throughout the corridor - Completed

The form-based code would allow all the current uses within a corridor area to remain, but also to be anywhere throughout that area. For instance, a vacant lot now zoned commercial instead would be zoned general or historic corridor and all of uses, such as multiple-family, commercial or office within that segment of the street happen without a rezoning.

Map 15: Corridors City Framework Map



HISTORIC CORRIDORS

Historic corridors are located along Cross Street, Huron Street, Hamilton Street, and River Street. The following actions will help to preserve and enhance the vitality of these areas:

Reinforce preservation of historic buildings- *Completed*

The form-based code will require the elements of the historic buildings along these corridors be incorporated into any new development or rebuilding.

Restore two-way function to Historic Corridors- *Ongoing*

As outlined in the transportation chapter of this plan, two-way function of these streets will increase safety and make navigation by foot, bicycle, bus or car easier.

Maintain River Street as a historic boulevard - *Ongoing*

River Street between Cross Street and Michigan Avenue is a boulevard lined by historic buildings with a variety of uses. The form-based code should attune design standards for this corridor to the street form of a boulevard.

GENERAL CORRIDORS

General corridors are designated along Washtenaw Ave and Cross Streets, East Michigan Avenue and Ecorse, Huron River Drive, Leforge and Railroad Street, Harriet Street, Lincoln and West Michigan Avenue.

Coordinate Washtenaw Avenue with the Re-Imagine Washtenaw Plan *Ongoing*

The City has been an important partner in the Reimagine Washtenaw coalition. While larger redevelopment sites are available in areas outside the City, many of the place-making, transit-oriented, and mixed-use development concepts can be employed on the smaller City lots. Diverse land uses are contemplated for the corridor, but additional land designated for commercial land uses is not envisioned. Rather, as sites are redeveloped, particularly in retail nodes at Hewitt, Mansfield/Cornell, and Cross Street, special emphasis should be placed on incorporating walkable and mixed-use elements in the site redesign.

The form-based code in the node areas will look to have redevelopment move closer to the street, provide improved pedestrian access and generally orient more to the pedestrian than to the vehicle.

Require a pedestrian-friendly building form while allowing a mix of uses for both students and residents along Huron River Drive, Leforge & Railroad corridors – *Ongoing*

These corridors are borders with the EMU campus that currently divide it from the City due to the width of the roads and barriers of the Huron River and railroad tracks. In the form-based code, the regulations should be changed to create a walkable environment with appropriate uses that integrates the City and the EMU campus. A design process for this area should be part of the 5-year update to this plan.

Restore Harriet Street as the Main Street of adjacent neighborhoods – *Ongoing*

The same mixture of uses would be allowed along Harriet, from Hamilton to Perry, but the urban form on the north side of the road would be required for any redevelopment of the south side. In order to create a walkable environment, the number of lanes for vehicles would be decreased to two lanes, creating room for on-street parking, bicycle lanes and pedestrian areas. The reconfiguration of the road would most likely on be possible when Huron and Hamilton are converted to two-way.

The matrix details the phasing of the plans and policies discussed above and how they meet the City's goals of safety, diversity and sustainability. With other matrices, it should be used to create reports and work plans as well as evaluate progress on an annual basis.

Figure 20: Corridors Implementation Matrix

Action	Timeframe	Location	Safety	Diversity	Equity	Environmental Sustainability	Economy
Designate the appropriate building form for each corridor based on existing patterns and vision for that corridor	Form-based code	All corridors	x	x	x		x
Retain the mix of uses within each corridor but allow them throughout the area	Form-based code	All corridors		x	x		x
Reinforce preservation of historic buildings	Form-based code	Historic corridors		x			x
Maintain River Street as a historic boulevard	Form-based code	Historic corridors	x	x			x
Require a pedestrian friendly building form while allowing a mix of uses for both students and residents along Huron River Drive, Leforge & Railroad corridors	Form-based code	General corridors	x	x	x		x
Coordinate regulations for Washtenaw Avenue with the Washtenaw County Re-Imagine Washtenaw Plan	1-10 years	General corridors	x	x	x		x
Restore Harriet Street as the Main Street of adjacent neighborhoods	1-10 years	General corridors	x	x	x		x
Restore two-way function to Cross, Huron, and Hamilton Streets	1-10 years	Historic corridors	x		x	x	x

Chapter 9 – Districts

“Stable, diverse local economy” - Sticky note on what to create, from the Discover Charrette

Districts accommodate major economic development, employment centers or universities or unique entities, like the cemetery. The range of districts within Ypsilanti includes Eastern Michigan University, the social service and medical offices clustered on Towner and several industrial areas which provide employment and stability to the community.

PAST POLICIES

The City has established partnerships with the anchors of each of these districts. The City, DDA and EMU work together through the Community Engaged Council. The City is open to regularly meeting with the owners of the industrial properties in the southern part of the City. Zoning policies have been consistent for these areas and are less to blame for any vacancy than the recent economic downturn, a legacy of environmental contamination, and the shift away from a manufacturing economy.

PUBLIC INPUT

Participants views of the districts varied for each area. Very little was said about Highland Cemetery during the process. Much was said about Eastern Michigan University and the need for better town-gown relationships. A true symbiotic relationship between the City and the University was seen as key. The office, social service, and medical buildings on Towner in the eastern part of the City were not mentioned during the process, even by heads of social service agencies in focus groups.

Almost all participants felt new jobs within the City for current City residents of all education levels were imperative. They felt large job centers should be located in southern industrial areas or “jobs districts”. Overall, the vision articulated was that jobs and industry are needed for the economic and equitable sustainability of the City.

DATA

Since the last Master Plan in 1998, the City of Ypsilanti has experienced a fundamental shift in its local economy. The manufacturing base that once sustained the City is almost entirely gone. It has lost close to 1,600 manufacturing jobs since 2001. The largest tax payers are now apartment property owners, instead of manufacturing facilities.

Eastern Michigan University remains an economic driver in the City, as one of the largest employers.

The industrial park in the southwest corner of the City has been mostly built out. Meanwhile larger facilities, like the Angstrom property, have been difficult to re-commission.

EASTERN MICHIGAN UNIVERSITY

Due to state law, the City has no jurisdiction over the built environment within EMU’s campus. However, a guiding value for the City is Ypsilanti is an asset for EMU and vice versa. The City can continue to work with the University to create integrated functions between the City and Eastern, as well as programmatic steps:

Update regulations to create walkable areas at the border of the City and Campus - Completed

The form-based code should require walkable streets with building forms that complement the campus of EMU at the borders of campus. Further details on proposals for Leforge, Railroad and Huron River Drive are in the chapter on corridors.


Create a “front door” for EMU with the reconfiguration of Cross Street and Washtenaw - Ongoing

As discussed in the chapter on Centers, the confluence of Cross Street and Washtenaw should be eliminated by pulling the two roads apart, creating a mixed use area with a gathering area and possibly housing. The pedestrian mix and form should create a coordinated street scape between campus and city borders, both here and in the Huron River Drive corridor discussed in Chapter 8.

Create “Welcome to Ypsilanti” packages for new EMU students, including a web version - Not started

The City should bring together EMU administration and the Visitors and Convention Bureau to create welcome packages for all new students.

Map 16: Districts City Framework Map



HUMAN AND HEALTH SERVICES DISTRICT

The area on either side of Towner between Prospect and Arnet Streets is home to the Washtenaw County Service Center to the north and medical facilities to the south. Both provide services for the City and the County. The facilities' layouts are suburban in form. The following policies or actions should be taken in this district:

Create regulations that support the existing building form but assure access by all modes of transportation - Completed

The service center and medical facilities are suburban style buildings but are accessed by car, transit, bicycle and pedestrians. The form-based code should support the current style of building but require pathways, parking and loading facilities for all types of transportation.

Encourage use or redevelopment of unused parking lots - Completed

The parking lot for the medical facility is often empty. The city should work with the owners of the facility to see if a temporary use is possible to bring more activity. If redevelopment occurs, the existing street grid should be reconnected and a more urban form required. [Health and Human Services zoning district was updated under the Walkable Urban District umbrella, with hope that future development will then be building-type based with less of a suburban style.](#)

JOB DISTRICTS IN SOUTHERN PART OF CITY

The industrial park, large Angstrom property and other assorted industrial properties in the southern part of the City are well-suited for facilities that require easy highway access and roadways for trucks. These districts should be called "job districts" where the following plans or policies should occur:

Allow renewable energy facilities, such as solar panels - Completed

Most participants in the implementation focus groups felt that renewable energy facilities should be allowed as part of development in Job Districts, but not displace the possibility of new facilities being built. During the process of rewriting the zoning ordinance, the City could explore whether large-scale renewable energy facilities could be allowed as the primary use as long as they would be incorporated into later development. These types of facilities would be in line with the City's guiding values of Ypsilanti being sustainable and a great place to do business, especially the green and creative.

Reduce minimum lot size and width in the industrial park - Completed

The industrial park was laid out in a suburban style with large lots. The two smallest lots along Mansfield are approximately 125 feet wide. If that were to be made the new minimum lot width, approximately 10 new, developable industrial

lots could be created by splitting off undeveloped land from existing parcels, subtracting area along streams and wetlands. The minimum lot area could be established at 60,000 square foot, which is the approximate area of the smallest existing parcel. Property owners would decide whether to split and sell land. The potential addition of a non-motorized path connecting the residential areas to the east of the industrial park should be considered as part of future development and/or the 5-year plan update. Additional jobs and industry is vital to the City's fiscal sustainability.

Encourage development of vacant parking areas - Ongoing

The City should work with the owners of the Angstrom property to bring development to the large parking lot associated with their facility that is no longer needed. A concept plan for the site is in the following chapter. Again, jobs and industry are needed for the economic and equitable sustainability of the City. [Because of its location in the floodway, physical development may be challenging. Using the site to conduct flooding analysis may be an efficient temporary use here.](#)

RAILROAD AREA SOUTHEAST OF DEPOT TOWN

The area along the railroad, to the southeast of Depot Town, has long-standing businesses in the community. However, these uses are often at odds with the adjoining residential uses. The areas shown as district should be allowed to transition from neighborhoods to job areas, when owners petition for approvals. The corridor area to the west on Lincoln will have a mixture of less intensive uses in an urban form to act as transition between this area and the historic neighborhoods and centers nearby.

ECONOMIC DEVELOPMENT POLICIES

In this effort, the City has identified the following emerging sectors as industries aligned with its Guiding Values and the needs of its residents: small manufacturing and craft production, creative economy, renewable energy, and food. Economic incentives, such as tax abatements, should be used to continue the growth of these sectors.

HIGHLAND CEMETERY

A historic part of Ypsilanti, the cemetery should be preserved and current policies left in place. [The City and Historic District Commission supported an effort to list the cemetery in the National Register of Historic Places. The Commission approved the nomination in 2019 and the cemetery was officially designated in 2020. The City continues to support preservation of the historic cemetery, working with the nonprofit organization who owns and operates it.](#)

The matrix at the end of this chapter shows how each of the proposals above enhances safety, diversity and sustainability in the City, as well as phasing. This matrix, those at the end of the previous chapters and the implementation matrix in the appendix are intended to be used by decision-makers to create reports and work plans as well as evaluate progress on an annual basis

Action	Timeframe	Location	Safety	Diversity	Equity	Environmental Sustainability	Economy
Update regulations to create walkable areas at the border of the City and Campus	Form-based code	EMU	x	x	x		x
Create regulations that support the existing building form but assure access by all modes of transportation	Form-based code	Health & Human Services	x	x	x	x	
Allow renewable energy facilities, such as solar panels, on industrial land	Form-based code	Job Districts				x	x
Reduce minimum lot size and width in the industrial park to create more opportunity	Form-based code	Job Districts		x			x
Align economic development incentives and programs to encourage emerging sectors that align with the Guiding Values and the employment potential of residents	1-5 years	All Districts					
Create "Welcome to Ypsilanti" packages for new EMU students, including web version	1-5 years	EMU		x	x		x
Encourage use or redevelopment of unused parking lots	1-5 years	Health & Human Services & Job Districts		x		x	x
Create a "front door" for EMU in the area created by the reconfiguration of Cross Street and Washtenaw Ave.	1-10 years	EMU	x	x		x	x

Chapter 10 – Redevelopment Areas

“Space not being utilized” - Sticky note on what to change, submitted during the Discover Charrette

Ypsilanti has three former industrial sites which could be redeveloped in the next 20 years. Each area is discussed in detail below and design concepts for the three sites are shown in this chapter. These drawings are concepts only, which mean they will not be duplicated detail by detail exactly as presented. All of the sites hold the promise of additional tax revenue, jobs and residents, as well as the challenges of environmental contamination and competing in a depressed regional market.

WATER STREET

Beginning around 1980, the City looked to this area of former and underutilized industrial land as a target for redevelopment. At that time, the City had little to no vacant developable land. Between 1998 and 2001, the 38-acre area was targeted for redevelopment as an urban neighborhood with a variety of housing types, particularly for sale condominiums, increasing both the new-construction housing options available and the number of owner-occupied households in the City. While the City acquired the land and completed most of the demolition and brownfield remediation necessary over the years, the intended development failed to occur. The land – and its accompanying \$31 million debt – remains a major fiscal challenge.

Two developers had options on the land and were intending to purchase the entire site and develop it. For different financial reasons, both developers pulled out of agreements. In 2008, the City decided that looking for a master developer, one entity that would take on the entire site, was no longer feasible due to the national economic downturn. Rather, it would sell smaller pieces of the parcel to interested parties as they came forward.

Three different proposals have been put to the City Council since that time. One, for a drive-through restaurant, was rejected. Another, for a County Recreation Center, was tentatively accepted through a Letter of Intent. The third, for a discount retailer, was accepted after several rounds of negotiations.

Although each had a different result, each proposal was closely followed in the press and generated much public comment. During the charrettes for this Master

Plan, many people expressed a range of visions for the property – from a permaculture forest to mixed-use mid-rise development. Almost everyone also expressed the urgency to use the property soon.

Given this political climate, the City Council will face a challenge with any development proposal that comes before them for Water Street. The Water Street redevelopment concept plan shown on the opposite page was developed based on community input during the charrettes held for this process in the Spring of 2013. The plan shows items consistently requested by the community: a formal community gathering space and a linear park along the riverfront.

The concept plan includes two structures not in previous plans for Water Street. The first is a stormwater facility in the floodplain to service the entire site, in keeping with the community’s values of creating an urban space but using environmental systems. As portions of the site are sold, the storm water facility will need to be built, some portions ahead of the actual development. Second, a vehicular bridge extending River Street across the Huron River and south to Factory Street is shown. The extension of River Street would complete a missing portion of the street grid, giving the neighborhoods near Spring and Factory Street easier access to the resources in the downtown and would create an easy traffic route from the highway to Water Street. The bridge and street extension are long term projects, perhaps ten to twenty years in future.

Figure 22: Water Street Concept Plan



The drawing to the left is based on community input during the charrettes and urban design principles. It is a 20-year vision for the Water Street area. When developed, the site may differ from this exact layout.

The street layout is a continuation of the existing street system, drawing the value of the river through the community. A vehicular bridge is proposed extending River Street to Factory. A stormwater facility for the entire site is shown just north of the river.

The plan includes a formal park, ringed in red, and a linear park along the Huron. The property south of the river is shown as recreation use. This area is mostly floodplain. The building shown south of the river is a concept footprint that would need further study. Drawing by: AECOM

Approval Process and Standards

The concept plan is based upon common urban design standards which will be incorporated into the form-based code for the City. These are the standards by which the City Council should determine whether the City should sell a portion of Water Street for a proposed development. The standards do not talk about the use. Rather, they dictate the design of the street, what is on the street and the design of the buildings for multiple uses over the long-term. If and only if all of these standards are met, should the City Council consider sale of property on Water Street:

Respect right-of-ways & blocks

The street layout should connect to existing streets – River, Lincoln and Park across Michigan Avenue to the north, as well as Parsons and South to the east. The new streets should continue the same width and design. Also, the blocks, as laid out in the sketch, pull the value of the view of Huron River through the entire site to the rest of city, by ending streets into parkland along the river's edge. All proposed development should abide by this general layout.

Block perimeter should be less than 1,200 feet, like the other blocks in the City

Every block in Water Street, the area of land bounded on four sides by streets, should be less than 1,200 feet in perimeter. Blocks larger than this length, the average block perimeter in the adjacent Historic Downtown, will cut off access and value from the site to the rest of the City.


All streets have on-street parking

Parallel parking should be required on all streets and count towards any zoning parking requirements. The on-street parking slows traffic, makes a walkable environment and provides parking in front of buildings.

All streets have sidewalks

To assure a walkable space, all streets must have sidewalks on both sides, including the side of the street nearest to the park fronting the Huron River.

Figure 23: Water Street “A” and “B” Streets



“A” Streets are shown in yellow and “B” streets in blue

All streets have space for trees and other stuff

New streets in the Water Street area should have designated areas for trees between the road edge and the sidewalk, while street furniture – benches, trash receptacles and outdoor seating – should be placed in the same place along the sidewalk. The photograph on the opposite page shows an example zones for trees, outdoor seating and pedestrians in Depot Town.

All driveway aprons have the same design

Driveway aprons, the portion of the curb cut that slopes down to meet the street, should be consistent throughout the development. Moreover, they should be made of different materials than the sidewalk to show where vehicles enter and exit to pedestrians, as shown in the photograph on the opposite page. They should also be gradually sloped for ease of pedestrian crossing.

All buildings are built for multiple uses over time

All building should be built for eventual re-use, specifically through regulation of the height of floor. The ground floor, from floor to ceiling should be a minimum of 12 feet with a maximum of 14 feet. Upper floors should be 10 feet.

New development has “A” & “B” streets, similar to the Historic Downtown (see Figure 23)

Buildings which front “A” streets must have parking on the street and behind the building. “A” street design, with no curb cuts, is required on Michigan Avenue, River Street as it is continued through the site and Park Street as well as the street fronting the park adjacent to the Huron River. The “A” street design must incorporate the elements and dimensions of the cross section on this page (see figure 26).

“B” streets (see figure 27) allow curb cuts and parking lots to front the street. “B” streets are allowed for the continuation of Parson, South and Lincoln Streets as well as other internal streets. “B” streets must contain the dimensions and aspects shown in cross section on this page.

All buildings on “A” streets should be friendly to the street.

Buildings on “A” streets should be friendly to pedestrians by following these urban design rules:

- 90-100% of the building faces the “A” street
- It is built one to five feet from street right of way
- 60% of the front of the first floor is transparent windows or glazing
- The primary building entrance faces “A” street
- The first floor of buildings should have active uses - stores, restaurants, services - where people come and go often.

Figure 24: Sidewalk with Furnishing Zones




Source: ENP & Associates

Figure 25: Driveway Apron Example




Source: AECOM

Figure 26: Water Street “A” Street Cross Section



Source: AECOM

Figure 27: Water Street “B” Street Cross Section



Source: AECOM

Shape Ypsilanti Master Plan (DRAFT UPDATE) – January 5, 2021

Market Considerations

The vacant property on Water Street offers developers an opportunity to build from the ground up, with little or no environmental remediation. All other development opportunities in the City involve the re-use of existing buildings, which require specialized design, or probable demolition and environmental clean-up.

Because of these advantages, the Water Street development site offers opportunities for larger stores and national retailers to locate in the City. With the coming recreation center, this site can be attractive for businesses such as a sporting goods store, but also is a marketable site for a hardware store, major grocery store, pharmacy, and neighborhood types of goods and services. A full-service grocery store has been requested by residents for many years and was throughout the Master Plan process.

Housing has always been part of the vision for the redevelopment of Water Street and the site offers a central location near goods and services. Upper story housing in nearby Depot Town and the Historic Downtown have waiting lists and were easily leased, even in tough economic times in the late 2000s. During the charrettes, residents expressed the need for attached or multiple family housing for seniors and for young professionals.

The market will most likely dictate the height of the buildings. The site is more likely to be filled in a shorter amount of time if the buildings are one to two stories. If the buildings are 3-4 stories, complete development of the site will take longer, probably with a first building, a period of 3-5 years with little to no activity and then a flurry of development. In the form-based code, buildings with two or more stories may be required on “A” streets.

If train service comes to Depot Town, the market situation for Water Street will change as the site is within a 10-15 minute walk from the location of the train station. Most cities have seen market pressure for attached or multiple-family housing within walking distance of new transit stations.

No matter what use is most marketable at the time, the buildings should abide by the urban design standards detailed previously. The City will continue to work with real estate professionals to market and develop the site. A consistent and coherent marketing and development process will attract investment interest.

BAY LOGISTICS SITE (FORMER MOTOR WHEEL)

This property, just east of the railroad and Huron River north of Forest, has a long history of industrial activity. Currently, the 30-acre site is a warehousing and distribution facility. Due to the history of the site, any use other than industrial would most likely require environmental remediation. The upcoming form-based code should allow the current form and use to continue.

The City Framework designates this parcel as a district but the concept plan on the following page shows the site designed as a central neighborhood. The site is within a 10-minute walk of the anticipated train station in Depot Town just to the south. As with the Water Street site, demand for attached or multiple-family housing is anticipated within walking distance of daily commuter train service. Also, the site is within walking distance to EMU's campus, attractive to EMU students, faculty and staff. The extent of any environmental contamination is not known and the cost and level of clean-up, the highest of which is residential as required by the State of Michigan, will influence redevelopment costs.

Market analysis for this Master Plan concluded this site may be marketable as a larger scale mixed use development. It could incorporate many of the unmet shopping needs for students and professionals within a new rental housing complex that shares a parking structure with EMU, residents and shoppers. The concept plan for the site, shown in Figure 28, is a rendering of what a larger scale mixed use development could be. The plan is based on the urban design principles outlined for Water Street, continuing the existing street grid through the site. Two multi-use paths are shown, connecting the site to Eastern Michigan University to the west and Depot Town to the south.

When the form-based code is developed, the site will likely be zoned as a district, allowing the use and integrating the form into the surrounding neighborhood if redeveloped. However, redevelopment of the site as a central neighborhood with attached and multiple-family housing units as well as retail or office should be considered if brought forward by an applicant to rezone and redevelop the site.

Figure 28: Bay Logistics Concept Plan

The concept plan to the right shows a possible redevelopment layout for the Bay Logisitcs site. The plan assumes an increased market for housing, office, and retail, possibly driven by daily rail service in Depot Town. **Environmental remediation costs are unknown and will influence the redevelopment of the site.**

The commercial study done for this process suggested this site would be marketable as a mixed-use development with shopping on the first-floor and residential above.

The plan shows a new community park in the northeast corner, public green space bordering the cemetery and the Huron River and a new pedestrian bridge crossing the River.

The plan also shows possible redevelopment along Railroad, Forest and Lowell, with a new pedestrian path over the railroad. All redevelopment would be at the initiative of the owners of the property. Drawing by: AECOM



ANGSTROM PROPERTY (FORD/VISTEON)

This property has been home to industrial manufacturing since the early 1900s. For many years, it was the highest property tax payer in the City. The site has two components separated by the Huron River – a large factory on a 35.7-acre parcel and a 25.5-acre parking lot. Environmental contamination has been remediated on sections of the factory side of the site. The parking lot, no longer used, has always been used for parking.

Presently, the property is owned by the Angstrom USA LLC, which is not manufacturing within the factory as originally planned. They owners indicated to the City that they are open to selling the parking lot portion of the site. The site is well-suited as a job site due to the size of the property and easy access to I-94. Through the public engagement process, participants repeatedly expressed the need for jobs in the City.

The concept plan for the site in figure 31 shows a series of additional buildings on the parking lot area laid out in block pattern based on that of the City. Buildings on this site would be built outside of the floodplain of the Huron River and may not be in the exact location shown. In terms of the form-based zoning, the City should treat this area as a district with similar form and allowed uses as the industrial park in the southwest portion of the City. The City or other economic development entities, such as Ann Arbor SPARK, could pursue a certain sector for the site. The Northwest Council of Governments of Michigan has developed a Food Innovation District Guide which could help Ypsilanti bring food industries, from production to consumption, to the site. The site may also be a natural place to cluster sustainable energy companies, building on the green and permaculture movements within Ypsilanti.

Figure 29: Angstrom Property Concept Plan



The concept plan to the left is a possible redevelopment layout for the parking lot portion of the Angstrom property. The floodplain of the Huron River may shift some of the building locations shown.

The street layout continues the existing street network and block pattern. Buildings are placed in an urban setting, with parking pooled behind the buildings.

The trail network, shown in brown, is continued on either side of the property.

This area is intended to remain a jobs district. Redevelopment would be at the initiative of the property owners. Drawing by AECOM

220 NORTH PARK ST.

This is a 4.46 acre property owned by the city that sits along the railroad track. In 2017, the site was assessed for residential development. It was determined, based on a target market study, that the site was a good candidate for owner-occupied townhomes. The concept called for a 44-unit townhome development that was not well-received by the neighborhood, and has since sat vacant. The site is located less than a quarter-mile to Depot Town. It is primarily surrounded by residential uses but across the railroad track is a mix of commercial and industrial uses, and it is close to a commercial corridor on E. Michigan Ave.

In November of 2019 and January 2020, two meetings were held with the public about what they would like to see on this property. The results were varied. Immediate neighbors wished to see the site converted to a park- potentially with art or a pond- or a small number of single-family homes that conform to the existing neighborhood. There was also interest in building along the perimeter of the parcel to protect the pond in the center. Some preferred denser development that allowed around 20 units ranging from single-family to four-plexes. In general, the consensus was on low-to-moderate residential development that was not tall enough to block neighbors' views.

1901 HURON RIVER DRIVE

The 6.5 acre site is privately-owned. The site is primarily a wooded lot with one single-family home. The home's driveway has access to N. Huron River Drive but is set over 100 ft back from the right-of-way. Due to the variety of surrounding uses, this site has the potential be used in many ways that are beneficial to Ypsilanti. This parcel is located close to St Joseph Mercy Hospital, EMU facilities, and the Border-to-Border Trail. Its proximity to both multi-family units and a single-family development provides opportunity for this site to be developed either way.

In January 2020, when residents were asked to share their preferred development for this site, it was overwhelmingly for housing. As expected, suggestions spanned the range of mixed-use office space with lofts above, missing middle housing types, and a large apartment complex with 10% affordable housing. Aside Huron River Drive, this is a contiguous wooded lot that is proximal to the river. Consideration for the existing ecosystem should be made on this site.

1901 Huron River Drive



220 North Park St.



Chapter 11 – Implementation

“Enough planning, now doing” – Favorite phrase of Master Plan Steering Committee Member

The previous chapters provide the guiding values for the City, a snapshot of it in 2013, the framework for the future and the vision of the next twenty years. Many of the projects, such as the bridge over the Huron River extending Water Street, are ambitious. Others are changes in process or regulation. This chapter consolidates the Master Plan into a policy road map.

THREE FUNDAMENTAL STEPS

The City of Ypsilanti will invest resources – staff time and budget, if available – in the following fundamental steps to implement the Master Plan:

Form-Based Code

The current zoning ordinance is use-based and not well-equipped to implement this plan due to reasons outlined in Chapter 3. A form-based code will create a coherent regulatory system to create a safe, diverse, sustainable city. *The zoning ordinance was updated in 2014 to include the form-based “building types” within the “Walkable Urban Districts.”*

Process for Water Street Sale Approval based on Urban Design Standards

Water Street must become an asset to the City rather than a source of controversy. The urban design standards laid out in the previous chapter guarantee an urban form like the Historic Downtown and Depot Town, areas that have been sustained for over a century.

Conversion of One-Way Streets to Two-Way Streets The conversion of Huron, Hamilton, Cross and Washtenaw to two-way streets have been in several previous plans by the City. The conversions will only happen with cooperation from MDOT and investment of time and money. WATS should be utilized as a resource for data, research, scheduling, and facilitation. The City must invest staff time to discuss a process with MDOT and search for money to fund these conversions. Partnerships with Eastern Michigan University, Washtenaw County and other actors must be used as well.

COMMUNITY BUILDING

To that end, the City must build community relationship as part of the implementation of this plan. The following steps should be undertaken and integrated as part of everyday operations, if they have not been already:

Establish partnership with merged school district

The newly formed Ypsilanti Community Schools will influence the lives of Ypsilanti residents and their property values. The City should establish a regular means of communication, be it a standing meeting between the mayor and the School Board Chair, superintendent, manager, or a committee to talk about cooperation. The City should also reach out to the school district to coordinate the sale or reuse of district-owned properties within the city limits.

Continue and expand project-based learning

Participants felt activities for youth were essential. The eco-districts in City parks would be a natural place for project-based learning in partnership with local educational institutions - Ypsilanti Community Schools, Eastern Michigan University, University of Michigan and Washtenaw Community College.

Engage with joint projects with neighboring communities

Neighboring municipalities share many of the challenges as the City. Joint projects - such as road improvements, joint plans, and economic development initiatives - should be pursued.

Build community with neighborhoods

Participants frequently expressed pride in their neighborhoods. Festivals and gatherings in parks were often key to that feeling of community. The City can facilitate community building within neighborhoods by maintaining safe, clean parks and offering services to help with events, such as trash pick up.

Encourage cooperation between neighborhoods

During the first round of focus groups, participants expressed disappointment or frustration that neighborhoods were often at odds with one another. The City can use structures in place, such as the Community Policing Action Council (CoPAC), to bring neighborhood representatives together. However, some feel

the responsibility also lies with neighborhood associations to extend warm invitations to those across the street to join them in an effort or activity.

Celebrate each other's successes

Participants often were frustrated that people in Ypsilanti operate in their own silos. The City can set a tone to break down silos by celebrating the successes of all Ypsilanti residents and businesses, as well as those of neighboring municipalities.

ZONING PLAN - FORM-BASED CODE

In the Fall of 2013, the City of Ypsilanti is scheduled to undertake a rewrite of its Zoning Ordinance to a form-based code. Many pieces of the City's current code can be preserved and integrated while introducing a form-based code approach. The goal is to retain what is working, while providing new standards that improve areas and also allow for the distinct districts to maintain the current fabric of the area or provide new context for undeveloped land.

The vision, guiding values and plans documented in this Master Plan will guide the formation of the form-based code.

Per the requirements of section 33 (2) (d) of the Michigan Planning Enabling Act (Act 33 of 2008), the Zoning Plan on the following pages describes the relationship between categories on the Framework Map in Chapter 4 and the zoning districts in the City.

Each of the framework districts in the form based code would include:

- Easy to follow procedures and standards for renewable energy facilities, including solar panels on all buildings
- Creation of a no building zone for steep slopes along Huron River for safety and environmental preservation.
- Alignment and streamlining of City processes for planning, renovation and construction
- Historic preservation regulation allow re-use in 21st century economy, especially for houses of worship
- Permit process for food trucks beyond temporary event, possibly in limited locations to be determined during the zoning ordinance process
- Expansion of food producing plants as part of landscaping

ROLE OF CITY STAFF

If the City staff is doing their job well, no one should notice. They are the stage managers for the thousands of details required in the daily municipal functions that facilitate safe development within the City. Staff, particularly those in the Planning, Building and Public Service Departments, need the capacity and time to address the following everyday:

- Existing small business development and expansion through phone calls, meetings and knowledge of appropriate places for expansion
- Quick and streamlined approval processes
- Attraction of new building to redevelopment areas, as well as other available land within the City
- Improvements of pedestrian connections
- Completion of the bicycle network
- Installation of ADA ramps at all intersections
- Rehabilitation of existing structures by working with the owners of those properties to leverage private/public funds
- Stabilization of neighborhoods through consistent code enforcement, community policing and communication.

ANNUAL EVALUATION & PLANNING

According to the Michigan Planning Enabling Act, the Planning Commission must submit an annual report, work plan and budget to City Council in time for consideration of the next budget cycle. The following portions of this Master Plan should be used as tools to prepare those materials:

- **The Decision Making Rubric in Chapter 2:** The Planning Commission should examine the measures in achieving the Guiding Values.
- **The Implementation Matrix:** Located in the appendix, it is a compilation of the matrices at the ends of chapters 6-9. The Planning Commission should track whether, how and/or if the City is implementing these items as planned and adjust work plans accordingly based on resources and the Guiding Principles.
- **Three Fundamental Steps:** Found at the start of this chapter, the Planning Commission should evaluate progress or achievement of these steps and communicate to City Council the work, resources and support needed.

Figure 30: Zoning Plan

Framework Category	Form-Based Zoning District(s)	Description of character and uses	Notes
Center	Center	The intent of these zones is to maintain and expand the pedestrian oriented character of the downtown, central business district, and other centers of activity. The physical form is of an urban character with uses that promote office, retail and entertainment venues, with upper story residential uses permitted.	Includes the Downtown, Depot Town, Water Street area and Cross Street area adjacent to EMU
General Corridor	General Corridor, Neighborhood Corridor	Primarily suburban in form and are currently limited to auto-oriented commercial and office uses that are adjacent to residential neighborhoods. Corridors contain a variety of medium to smaller parcels and are adjacent to both types of neighborhoods. They will allow parking on the street and require buildings to be closer to the street; with minimal yards, lots will have more buildable area for residential, commercial and office uses mixed throughout.	Includes large portions of Washtenaw Avenue, Michigan Avenue, Harriet Street, Prospect and Huron River Drive.
Historic Corridor	Historic Corridor	Dominated by large, historic homes now used in a variety of ways – residences, office, and retail. Houses of worship and other civic buildings also line these corridors.	Includes areas adjacent to Central Neighborhoods and Centers
Central Neighborhood	Neighborhood Core (3 Districts)	The physical form of structures shifts to a residential character with flexibility in use. Live/work housing, personal services, corner retail and small offices are evident in this district. Buildings are spaced closely, but are separated by setbacks.	Most of the City's historic neighborhoods, and some others with strong grid structures, are included in this area. The residential buildings types and uses vary on a spectrum with the Historic East Side with the least variety and near campus areas with the most. Three zoning designations are anticipated to preserve the existing character ranging from single-family to a large variety.
Outlying Neighborhood	Outlying Neighborhood, Multiple-Family	Low density suburban-style residential areas, consisting of predominately detached housing types, with some two-family houses throughout the area or higher-density, suburban style apartment buildings. These neighborhoods will have uses largely limited to the type of residential for which they were built. In some areas, like the Heritage Park neighborhood in the southwest part of the City, zoning would be changed so that duplexes and group homes would no longer be allowed by right.	Neighborhoods built in the middle or later part of the 20th century and include a single type of housing, adjacent to a corridor but the street network is designed to carry traffic into the neighborhood, not through it.
District	SD Special Districts	Areas of the city dedicated to a single type of activity. Special zoning districts will be developed for each of these areas	Includes EMU, Highland Cemetery, the human and health services area on Towner, the area around the railroad tracks and the industrial areas in the south of the City.

These tools should also be used in to prepare a work plan for the five-year master plan update. Additional information on how to prepare for that event is in the next section.

FIVE-YEAR MASTER PLAN UPDATE

Per the Michigan Planning Enabling Act, the City of Ypsilanti must revisit this master plan every five years after its adoption to assess whether an update is needed. The City should use the implementation matrix in the appendix to track progress. If milestones have not been met, the City needs to re-evaluate its commitment to those items and change the Master Plan.

At the very least, the City should analyze neighborhoods to see if and how they have changed. Using data regularly collected and updated by the City, the data portion of the process should analyze trends in homeownership and rental dwellings, the type of dwellings in terms of numbers of units, and the amount of investment in homes by building permits. These numbers should be then focused through the lenses of safety, diversity and sustainability. Sometimes, those goals might be at odds with one another. For instance, if a neighborhood experiences gentrification, with a wave of more well-off homeowners moving in, the diversity of a neighborhood and sustainable equity may be threatened. With that knowledge, the City would then engage the residents in a process to decide priorities and next steps.

If progress is happening and staff time or budget is available, the following items warrant attention that was not possible in this process:

Leforge and Huron River Drive Reconfiguration

This intersection not only between roads but between the City and the University does not function well for pedestrians and acts as a barrier. An intense design process, like a charrette, for this area is needed to find

fixes to the existing infrastructure. At the very least, this intersection should be examined as part of an update on the two-way conversion of streets.

Financing for sustainable energy and energy efficiency

An implementation step in the City's Climate Action Plan, focus groups for this process designated a sustainable energy financing program, such as a Property Assessed Clean Energy (PACE) initiative, a 5 to 20 year priority. Additional planning and effort will be needed to start such a program.

Food Access

Throughout the process, residents asked for better food access in the City, specifically a full-line grocery store. While full-line grocery stores are located within a ten-minute drive of every residence in the City, the industry standard for location of those businesses, many residents can only reach them by bus. In focus groups at the senior high-rise downtown and the Chidester apartments, residents spoke about how buses ran infrequently between their homes and grocery stores located outside the City or not at all, particularly on weekends.

Congress and Ballard

Due to the intersection of three streets, this entrance to the Historic Downtown warrants in depth study to create a safety and preserve the context.

CONCLUSION

This plan is rooted in the facts and people of Ypsilanti today. Both will change with time, but the principles of safety, diversity, and sustainability hopefully will be guiding values for tomorrow.

Chapter 12: Sustainability Plan Update

See the Sustainability Plan on the following pages:

DRAFT

The City of Ypsilanti Sustainability Plan

“It’s real. It’s us. It’s bad. Scientists agree. There’s hope.”
Anthony Leiserowitz, Director Yale Project on Climate Change Communication

Ypsilanti, in many ways, is a state leader in sustainability planning, yet these efforts had not unified into a Sustainability Plan until now. Inventories and strategies could be found in the City’s Climate Action Plan, Energy Plan, Nonmotorized Plan, Parks and Recreation Plan, or Alternative Fuel Policy. While these plans hold tremendous value, the recommendations within them carry more weight and are more accessible when included in the City’s primary policy document. The Master Plan is a community’s most comprehensive planning document and serves as the policy basis for the Zoning Ordinance, which directly regulates land use. Zoning provisions have the legal force to protect natural resources, prioritize sustainable development, and improve the infrastructure that enables nonmotorized travel. The previous efforts were influential and integral to the City’s “green” practices, and this next step officially denotes sustainability as an actionable City priority through the compilation and advancement of sustainable strategies into a single cohesive document. This Sustainability Plan is intended to serve as a data resource, community reflection, and policy guide to the Commission’s future actions.

The Impetus

The Sustainability Commission was established in 2017 with a primary mission of addressing environmental issues and prioritizing sustainability policies. In this short time, the Commission has embarked upon and accomplished numerous initiatives, including:

- Passing a resolution in support of native plants in local landscaping
- Partnering with the Washtenaw County Conservation District to provide support for grants to plant trees, hold workshops, and train for tree maintenance
- Reviewing and recommending the 2018 Energy Plan
- Partnering with the city of Ann Arbor on the Net Zero Initiative
- Passing an Energy Star Resolution to identify underperforming buildings and apply for certification
- Founding an annual Earth Day celebration

The Sustainability Commission recognizes that risk analysts, including the US Department of Defense, rank climate change as one of the most serious threats to ecosystems and people around the world.^{1 2} “Climate change” refers to a broad range of global phenomena resulting predominantly from the large-scale burning of fossil fuels, which add heat-trapping gases to Earth’s atmosphere. The result is a variety of challenges: extreme heat and increased cooling days, more severe winter storms, changing coastal dynamics, rising water levels, disruptions to growing seasons, pest migrations, habitat loss, temperature volatility, increasing extreme weather events and associated stress on natural ecosystems, and risk of drought that will disturb of the characteristics and functions of natural processes.³

There are generally two types of responses to climate change: mitigation and adaptation. Mitigation, or *reducing the risk of future changes* to the climate, necessitates dramatically reducing future GHG emissions and increasing the sequestration or storage of existing GHG in natural sinks such as forests or soil. While mitigation strategies will take decades to positively impact rising temperatures, reducing GHG emissions now will reduce future risk and make it easier to adapt to the future impacts of climate change. An example of a mitigation strategy would be increasing the deployment and utilization of renewable energy. Adaptation refers to actions that address the *effect* of the problem, but not the *root* of the problem. Adapting to climate change necessitates changing behaviors, systems, and our way of life *in response* to the results of climate change. One example would be relocating electricity and communication lines from overhead to underground locations to prevent power outages during extreme weather.

Where the two categories overlap is where resiliency is born – if an action can simultaneously mitigate negative effects of climate change and help a community adapt, then it rises to priority status. Because the tangible positive effects of mitigation will take the entire world’s coordination, not just the region’s or the City’s, a focus on adaptation is the most prudent and impactful.

Regional Climate Change

The Great Lakes Integrated Sciences and Assessments (GLISA) Center is one of the eleven regional centers funded by the National Oceanic Atmospheric Administration. It is a partnership between the University of Michigan and Michigan State University that seeks to provide usable and useful information on climate change impacts to decision makers across the Great Lakes Region. GLISA provides both *historic information*, derived from over 200 quality-controlled weather stations located in communities across the region, and *future climate information*, derived from regional and global climate models (RCMs and GCMs), as well as dynamically downscaled climate models. Historic climate information is useful for providing locally relevant information that communities can use to assess how well their physical infrastructure and social systems are faring in the face of current climate change, whereas future climate information is useful for incorporating into capital improvement processes when decisions will affect infrastructure investments over 10, 20, or 50 years.

Some positive news is that this scientific awareness is reaching a critical mass of Americans (and Ypsilanti residents). Most Americans believe global warming is happening (71%) and that it will harm future generations (73%).⁴ Public opinion estimates generated by the Yale Program on Climate Change Communication and the George Mason Center for Climate Change Communication suggest that 78% of Washtenaw County residents believe climate change is happening, 76% believe climate change will harm future generations, and 83% support policies that bolster renewable energy or limit CO₂ emissions.⁵

¹ Intergovernmental Panel on Climate Change (IPCC). Climate Change 2014: Synthesis Report. Contribution of Working Groups I, II and III to the Fifth Assessment Report of the Intergovernmental Panel on Climate Change <http://www.ipcc.ch/report/ar5/syr>
² U.S. Department of Defense. Quadrennial Defense Review. Washington, DC. 2014.
³ Planning for Community Resilience in Michigan. 2017. <http://mirisingtide.org/wp-content/uploads/Resiliency-HandbookAPRIL-242017.pdf>
⁴ Matthew T. Ballew, et al. 2019. Climate Change in the American Mind: Data, Tools, and Trends, Environment: Science and Policy for Sustainable Development. 61:3, 4-18,DOI: 10.1080/00139157.2019.1589300 <https://www.tandfonline.com/doi/full/10.1080/00139157.2019.1589300>
⁵ Marlon, J. Washtenaw County Michigan Public Opinion on Climate Change, 2019. https://factsheets.vpccc.tools/Michigan:Washtenaw_County

Historic Regional Climate Change

GLISA offers curated history climate information at two scales:

- Climate Division, which are multi-county, NOAA Designated regions,
- Quality-controlled weather stations.

Significant increases in precipitation across the entire region can be seen in data collected over the past 70 years (1950 to present). Increased seasonal precipitation is most notable in the spring and fall: fall precipitation has increased over 28%, and spring precipitation has increased over 21%. The region is experiencing this precipitation increase within storm events that are also increasing in severity, resulting in more rain falling in more concentrated bursts.

Precipitation Change 1950 – 2019 Southeast Michigan Climate Division

	in	cm	%
Annual	5.58	14.17	18.5
Winter	0.61	1.561	11.2
Spring	1.72	4.39	21.1
Summer	1.13	2.88	12.0
Fall	1.99	5.07	28.4

Source: GLISA

Over the same period, the average annual temperature has risen across Southeast Michigan by 2.4 degrees Fahrenheit (°F), and the gap between average high and low temperatures is closing and swinging upward towards warmer temperatures. Winter and spring are considerably warmer, with rising winter lows and earlier last frost dates leaving fewer days under 32°F in the spring season.


Rise in Temperature from 1950 through 2019

Season	°F	°C
Annual	2.43	1.35
Winter	2.80	1.55
Spring	2.86	1.59
Summer	1.91	1.06
Fall	1.94	1.08

Source: GLISA

Southeast Michigan Climate Division Area	
Included Counties	Included Watersheds
Genesee	Birch-Willow
Lapeer	Cass
Lenawee	Clinton
Livingston	Detroit
Macomb	Flint
Monroe	Huron
Oakland	Lake Erie
St. Clair	Lake Huron
Wayne	Lake St Clair
Washtenaw	Ottawa Stoney
	St. Clair
	Raisin
	Shiawassee
	Tiffin
	Upper Grand




Other important changes, in addition to temperature and precipitation, are occurring locally. Increases in freeze/thaw cycles create stress on built infrastructure. Extensions of the growing season, which improve agriculture, can also increase risk of vector-borne illness. Extended heat events in the summer and ice storms throughout the winter lead to more stress on the electric grid, increase the likelihood of power outages, and further exacerbate existing vulnerabilities among Ypsilanti residents.



Source: GLISA

Future Regional Climate Change

While future climate change can be more difficult to predict with the same precision historic information allows, GLISA can predict regional trends with high levels of certainty thanks to improved climate models and climate science translators. In terms of both temperature and precipitation, challenges are anticipated in the mid- to long-term. By the period of 2041-2070, southeast Michigan is expected to warm by 4.5 to 5°F from the average temperatures in the 1971-200 time period. This average increase will be accompanied by more high heat days: in the same period, it is anticipated that there will be 30 to 40 more days over 95°F than there were in the 1971-2000 period.



Increases in overall precipitation and acute rain events are also expected for our region during the same period. Annual rainfall is expected to increase by three to four inches over annual rainfall in 1971-2000. By 2040-2070, the region is likely to experience up to two more days per year with heavy precipitation, defined as the 2% heaviest precipitation events in the area.⁶

It is important to remember that while understanding climate change is critical to the process of planning for Ypsilanti’s future, these impacts may also open new opportunities for our community and region that set us apart from other areas. A temperate climate, an extended growing season, an abundance of freshwater, and a legacy of innovation and production place southeast Michigan on the top of the list for “climate positive” regions of the world. To properly prepare ourselves and our community for the future, we must adequately address how climate impacts do and will exacerbate existing vulnerabilities in our community, but also be diligent to build a resilient future – one that that not only “bounces back,” but “bounces forward.”

Environmental Justice

In any crisis, the most vulnerable populations will bear a disproportionate level of the burden unless protective action is taken. Their lack of resources and influence means that they will suffer greater exposure to climate change threats, and be less able to adapt and react. Environmental justice (EJ) is a discipline pioneered by Dr. Robert Bullard in the 1960s as a result of his investigation into the unequal protection and enforcement of environmental laws and regulations. Bullard was a part of the National Environmental Justice Advisory Council that advised President Bill Clinton to sign the Environmental Justice Executive Order in 1994 where EJ is defined as: “the fair treatment and meaningful involvement of all people regardless of race, color, national origin, or income with the respect to the development, implementation, and enforcements of environmental laws, regulations, and policies.”

Today, the definition applies to the effects that climate crisis will have on the disadvantaged. Nearly 25 years later, as climate change has inequitably descended upon us, the City of Ypsilanti understands that its populations of people of color and low-income households are more vulnerable to both the physical and social impacts of climate change; likewise, women and members of the LGBTQIA community are vulnerable to climate change’s social effects. Where possible, this plan addresses what can be done on a local level to protect - our residents and visitors from the worst of these changes. As the structures that perpetuate structural inequity are brought to the attention of those in power, every attempt should be made to dismantle them or to minimize actual and potential harm.

As this plan is executed and amended, it’s important also to incorporate the voices of all people who may be affected, and to understand the impacts that decisions made by those in power may have. The Jemez Principles for democratic organizing ⁷ provide a useful roadmap for examining and updating our policies and our actions in the context of both environmental justice and good governance.

Definition of Sustainability

Sustainability is a tricky term to define. A commonly accepted definition of sustainability is “meeting the needs of the present without compromising the ability of future generations to meet their own needs.” This definition comes from *Our Common Future*, a report published in 1987 by the United Nations (UN) that suggested concrete and realistic proposals for dealing with environmental and development issues. In 2017, the Ypsilanti City Council passed Resolution No. 2017-238 approving a recommendation from the Sustainability Commission that defined sustainability with a nod to the UN definition:

“Achieving a balance of ecological, social, and economic considerations to provide for an equitable path for the growth and improvement of our community in the uses of our resources, remaining conscious of the historical context, while ensuring the availability and vitality of those resources for future generations.”

As such, social equity, environmental health, and the economy become the three interrelated pillars of sustainable action. This Sustainability Plan will focus primarily on the environment; the social and economic sides of planning are discussed in greater detail in the City’s Master Plan. However, recommended sustainability actions call out which of the three pillars it touches to expose the interconnected nature of sustainability planning.

When the residents were asked in the community-wide survey, “What does sustainability mean to you?” the answers were unsurprisingly varied. Most of them touched on at least one aspect of the three-pronged definition using phrases like “repairing our natural environment,” “having a

JEMEZ PRINCIPLES FOR DEMOCRATIC ORGANIZING

#1 Be Inclusive

#2 Emphasize Bottom-Up Organizing

#3 Let People Speak for Themselves

#4 Work Together in Solidarity and Mutuality


#5 Build Just Relationships Among Ourselves

#6 Commit to Self-Transformation

⁶ GLISA. Great Lakes Regional Climate Change Maps. <http://glisa.umich.edu/resources/great-lakes-regional-climate-change-maps>
⁷ National Resources Defense Council, Jemez Principles for Democratic Organizing. <https://www.nrdc.org/sites/default/files/jemez-principles-organizing.pdf>

...diverse community without pricing people out,” and “clean water, healthy citizens, easier access to public transportation.” The open responses were telling; Ypsilanti residents aptly identified that becoming a more sustainable city requires all-encompassing change.

Three Pillars of Sustainability




Public Input

In 2019, high priority themes from The City of Ypsilanti Energy Plan (2018), The City of Ypsilanti Climate Action Plan (2012), and the Shape Ypsilanti Master Plan (2013) were identified and coupled with a round of community input.

Residents were invited to attend an in-person meeting held on July 11, 2019 to participate in group exercises that prioritized sustainability actions. There was also an online survey (physical copies were provided), and in an attempt to “go to the people,” boards were placed on easels at different locations throughout the City (City Hall, EMU Student Center, Parkridge Community Center, and Cream & Crumb) in the spring and summer of 2019 that allowed residents to select their environmental priorities. The findings from each engagement were compiled, analyzed, and used as a basis for outlining the City’s ongoing path towards sustainability. The action plans represent public engagement findings, data collection, best practices, and staff capacity.

Community Engagement Summary of Details
Survey respondents: 144
Board entries: 876 unique responses
Attendees at in person session: 25



Challenges, Goals, Objectives, and Strategies

This plan was developed in three phases: research, outreach, and confirmation. The existing physical setting of the City was inventoried, as was the community’s current greenhouse gas emissions. Previous plans were reviewed, and progress towards those plans’ goals were benchmarked. If there was a disconnect or gap between challenges noted during the inventory and plan review, this was noted for later review. Outreach was done in mid-2019, both specifically regarding sustainability and in tandem with the master plan scope, and the hopes and priorities of the community were incorporated into goal development. The challenges, goals, objectives, and strategies to reach those goals are presented below, loosely grouped into these categories: *earth*, including soil and contamination; *water*, including surface water, drinking water, and stormwater; *energy*, including production, consumption, and waste management; *biodiversity*, including urban forestry and outdoor lighting; *neighborhoods*, including land use and transportation; and *communication*.

Earth


Soil Structure

Soil characteristics can impose limitations that affect the suitability of land for potential uses, such as dwelling units with basements and surface composting facilities. There are five types of soil in the City, and the table below shows the percentage of area within the City for each soil.⁸

Table X: Soil Types

Soil Type	Basic Characteristics	Percentage of Area in Ypsilanti
Fine	Soil particles not visible to the eye, poor load bearing capacity, fairly impermeable, susceptible to frost action	56.4%
Coarse Loamy	Larger grain loam soil, visible to the eye	18.8%
Sandy	Light soil, quick water drainage, poor water retaining qualities	12.8%
Fine Loamy	Smaller grain loam soil, not visible to the naked eye	11.8%
Loamy	Not predominantly sand, silt, or clay, suitable for growing plants due to the nutrient and water capacity	0.2%

Source: United States Department of Agriculture Soil Survey, current



Basements and Foundations


As a foundational part of construction, soils impact development. The “Soils – Dwellings with Basements” map shows that most of the western side of the City is not conducive to basement construction based on the soil’s limited capacity to support a building without the soil shifting. As moisture content changes, the soils in the “very limited” category shrink and expand to a degree that could reduce their ability to support a basement.⁹ Given the predictions for greater concentrations of precipitation and instances of flooding, building basements in unsuitable soils is not a fruitful adaptation strategy. Basement construction is governed by the building code, which is not designed to take detailed soil considerations into account for smaller residential parcels.

Make soil information available to all, and directly provide information on soil structure to those who choose to build a new structure that requires a foundation. At a minimum, this information should be made available to all current and prospective property owners to discourage subterranean development that may have a high risk of failure. If continued construction, increased flooding events, or consistent property damage warrant a regulatory solution, an overlay zoning district could be applied to some or all of the “very limited” areas that require construction to meet floodplain standards, or that bans subterranean construction altogether.

⁸ Web Soil Survey, United States Department of Agriculture, <https://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm>
⁹ United State Department of Agriculture. Web Soil Survey. <https://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm>

Green Infrastructure

Soil type factors into planning for stormwater infrastructure, urban gardens, and tree planting. The “Urban Greening” map shows where the soil is best suited for plantings, alongside streets and vacant and public land within the City. Areas that are vacant or underutilized, held in the public



trust, and have soils suitable for planting should be prioritized for green infrastructure as they will likely have the best outcomes. Alleys, culs-de-sac, parking lots and areas, and low-traffic residential streets are also good candidates for green infrastructure installation. Because they represent a significant land area distributed throughout the community, likely have excess capacity that could be repurposed, and may see low traffic volumes less-durable permeable pavement may be an option in some areas. Elements for urban greening shall be incorporated in the maintenance plan for public alleys and culs-de-sac.

Erosion

The City of Ypsilanti does not have any city-specific regulations regarding soil or soil health but works with the County on soil erosion protections. Some cities have addressed soil conditions through the adoption of sensitive features overlays which include soil and slope protection. In the City of Grand Haven, development in the sensitive feature zone is subject to more intensive site plan restrictions and review, including the prevention of soil erosion and disturbance.¹⁰ Any development in the sensitive feature overlay cannot move or disturb the soil at all without prior approval of the Planning Commission.


Ypsilanti participates in Washtenaw County’s Soil Erosion and Sedimentation Control Program. The program is often triggered in the development process and “works to protect surface water and the environment from the negative impacts of soil erosion pollution that are the result of earth changes.”¹¹ Any projects that require substantial earth moving, defined as an area of 400 square feet, are required to obtain a Soil Erosion and Sediment Control (SESC) permit. Projects that require a permit include earth changes within 500 feet of a surface water’s edge, earth changes more than 1 acre, earth changes related to gravel pits and landfills, installation or alterations to ponds, transportation facilities, and directional drilling or boring for utilities and infrastructure.¹²

Contamination

Ypsilanti’s industrial history has left behind environmental contamination that the City must still confront. Michigan’s Department of the Environment, Great Lakes, and Energy (EGLE) maintains a database of sites that have been affected by former development. This contamination can be found in many forms; from leaking storage tanks, from commercial activity, or from spills. The “Contamination Map” illustrates the location of all known brownfields that have been remediated or are in the process; sites of environmental contamination; and leaking underground storage tanks (LUSTs) in the City.

Brownfields have the broadest definition, covering most of the contamination spectrum and therefore applying to the widest range of sites. Brownfield sites could have experienced the threat of environmental contamination, are already contaminated, contain blighted structures, or have been deemed functionally obsolete. The map shows that most of these sites are primarily clustered along commercial corridors, the rail line, the river, and less frequently in neighborhoods.

EGLE tracks environmental contamination because of the significant impacts it can have on the drinking water supply and on residents living in proximity to these sites. This is a distinct database from LUSTs so that records are not duplicated. The main differences between the two systems are the source of the contamination, and which governmental division manages the sites. All other contamination releases, besides LUSTs, are covered under the Environmental Remediation Program (part 201). Twenty sites of environmental contamination were identified in the City.



¹⁰ City of Grand Haven, Article IV Zoning Districts, Section 40-422 Sensitive Features Overlay district, https://library.municode.com/mi/grand_haven/codes/code_of_ordinances?nodeId=PTIICOOR_CH40ZO_ARTIVZODI_S40-422SASEAROVDI.
¹¹ Washtenaw County Water Resources Commissioner, Soil Erosion Control <https://www.washtenaw.org/232/Soil-Erosion-Sedimentation-Control>.
¹² Washtenaw County Soil Erosion and Sedimentation Control Ordinance 2016, <https://www.washtenaw.org/DocumentCenter/View/758/Soil-Erosion---Sedimentation-Control-Ordinance---April-1-2016-PDF>.

Figure X, Contamination Map, shows the most up-to-date data available for underground storage tanks (found in the Appendix). These are tanks that have been buried underground to mitigate their risk of explosion, usually because they contain petroleum, and regulations regarding their decommissioning have evolved over time. Businesses have not consistently removed them before leaving the site, and after years of deterioration their contents leak into the soil. If left underground long enough, the contents could reach groundwater or other sources of drinking water. An estimated 47 leaking underground storage tanks (LUSTs) have been recorded in the City; all but 11 are closed, meaning that corrective action has been taken to stop the spread of petroleum or other hazardous substances, and that action was appropriately documented with the State.¹³ Due to the long history of industrialization shaping the growth of the City, dating back to the 1800s when the Huron River was used as a power source, many of these sites are located in relatively close proximity to the river, posing an additional threat to the local ecosystems.

Contamination clean-up is often funded by higher levels of government, and specific projects are overseen by the state agency, Environment, Great Lakes, and Energy (EGLE). County-level Brownfield Redevelopment Agencies are an intermediary between these state and federal programs and the local municipalities with challenging redevelopment sites. The Washtenaw County Brownfield Redevelopment Agency (WCBRA) focuses on post-contamination efforts on a case-by-case basis as an economic and redevelopment tool, providing incentives in the form of grants, loans, and tax increment finance agreements that can be applied toward certain remediation costs in a proposed redevelopment project. The assistance is intended to make the cost to redevelop a brownfield site comparable to the cost of the same development in a “greenfield” (previously undeveloped) site on which remediation is not an issue. This helps to reduce sprawl and its associated vehicle emissions, makes use of established infrastructure, and prevents development damage such as contamination and habitat loss on undisturbed sites. While environmental remediation is a primary goal of the brownfield program, its overarching mission is redevelopment, and its tools are flexible enough to help communities fund previously restricted and generally more expensive redevelopment projects regardless of contamination level.

The Environmental Protection Agency’s Brownfields program, from which state and community programs are enabled, began in 1995; WCBRA was founded in 1999. Ypsilanti is one of the 23 municipalities that partners with the WCBRA to identify, assess, remediate, and redevelop brownfield properties. The WCBRA uses Tax Increment Financing, Community Revitalization Program, grants, and loans to advance projects through the various phases of redevelopment. Five sites in Ypsilanti have received assistance from WCBRA, only two of which had environmental contamination on site (the rest were deemed functionally obsolete), and all have been successfully converted into usable space except for the Water Street property. The small number of completed remediations underscores the reactive nature of the process, and highlights that on the local level, the most effective tools are preventative measures: upfront review, inquiry, and regular inspection of the design, storage, and uses in a zoning district. Ypsilanti has used its Zoning Ordinance to prevent automotive uses in certain zones because their practices and commonly used materials have a higher likelihood of contaminating soil.

The Bell Kramer neighborhood is an example of how environmental contamination, or even the threat of it, complicates land use planning. In 2014, the City of Ypsilanti rezoned the neighborhood to an industrial-commercial use in direct response to the findings of the 2012-2013 assessment, intending to prevent future homes from being built in a potentially hazardous area. However, after the rezoning, the existing homes became non-conforming structures, which are permitted to remain but not expand, not permitted to be rebuilt after a casualty, such as a fire, except under very specific circumstances. As lending agencies are reluctant to lend on non-conforming properties, the financial implications of this designation made it more difficult to sell or upgrade the homes. The residents’ discontent, coupled with the vapor testing results in the homes, provided support for the City to rezone the neighborhood back to residential uses. The history of this neighborhood points to the complexity of changing land uses and monitoring the effects of environmental contamination. Rezoning is one mechanism to prevent development on contaminated sites, but is best used in conjunction with other methods. When used, the process must be accompanied by frank conversations with current property owners before the public hearing.

Brownfield Criteria

At least one of the following:

Environmental contamination

The threat of contamination

Blighted

Functionally obsolete

The Bell Kramer Neighborhood

Home to about a dozen households, this neighborhood is immediately adjacent to a former city landfill that has not been used since 1967. The first phase of an environmental assessment was conducted on the landfill in 2012-2013. Volatile organic compounds (VOCs), polynuclear aromatic hydrocarbons (PNAs), metals, benzo(a)pyrene, and methane gas were detected at higher levels than the state permits. These substances produce substantial health and environmental risks. Property owners were notified because contaminations could have been migrating through the neighborhood. In 2017 and 2018, indoor air was tested in some of the Bell Kramer homes, and concentrations of contaminants were within acceptable ranges for the residents to stay.

Sustainability Goals: Earth

GOAL: Eliminate new instances of soil contamination and responsibly deal with the legacy of existing polluted sites

- Explore creation of an overlay zone, or other zoning or building regulations, to control the types of uses that may be permitted in areas with soils that would allow for easy transmission of contamination, or uses that have a high risk of contamination near ecologically sensitive areas, such as waterways.
- Research and confirm existing sites of contamination with EGLE
- Use Brownfield TIF capture to fund remediation of sites that may be redeveloped.
- Continue to work with the Washtenaw County Brownfield Redevelopment Authority to remediate sites.
- Explore and pursue grant opportunities to remediate sites that may not be good candidates for commercial redevelopment or that pose an immediate threat.

GOAL: Ensure buildings and infrastructure are constructed in a manner complementary to soil structure, slopes, and drainage.

- Make soil information available to all, and directly provide information on soil structure to those who choose to build a new structure that requires a foundation.
- Incorporate green infrastructure into planned capital improvement projects wherever possible, and identify potential sites for demonstration projects.
- Strengthen zoning protections to limit erosion in areas of steep slopes.


¹³ Underground Storage Tanks, United States Environmental Protection Agency. <https://www.epa.gov/ust/learn-about-underground-storage-tanks-usts>

Water

Surface Water Quality

Ypsilanti is a part of the Lake Erie Basin. Within the City’s boundaries are two watersheds - Huron River and Stoney Creek (into which the City’s Paint Creek drains). The Huron Watershed, which covers most of the City, is divided into five sections. The section that encompasses Ypsilanti is known as the “Lower Middle Huron,” enveloping about 27.7 miles of the river from North Maple Road (Barton Pond) downstream to Belleville Lake. It includes portions of the City and Township of Ann Arbor, Superior Township, Ypsilanti Township, and Van Buren Township.¹⁴ Because a watershed crosses several jurisdictional boundaries, it is incumbent on these municipalities to cooperatively maintain high-quality water while permitting access to the river. The health of the river depends on the quality of all its tributaries, which is often linked to land use policy. One way to coordinate across municipal jurisdictions is through a watershed council: the Huron River Watershed Council (HRWC) was the first in the state and has been working to protect and restore the Huron River since 1965. In addition to writing a management plan for the entire watershed, the HRWC also authors management plans covering specific sections of the watershed. The HRWC is updating the section of the watershed management plan that includes Ypsilanti, the Lower Middle, in 2020-2021.

The HRWC identifies that the section of the Huron River that runs through Ypsilanti and Ann Arbor is heavily impounded: 77% of it is impounded by the seven dams that stretch across this area, making it more similar to a lake ecosystem than a river. Two sources afflicting the health of the watershed are runoff from impervious surfaces, and new development along the riverbank that clears vegetation vital to the absorbing runoff. In particular, phosphorous and *E. coli* are entering the river from Mill, Honey, and Boyden Creeks.



Some measures are in place to protect water quality. According to the City of Ypsilanti’s code of ordinances, all development along any river frontage must show where a planned conservation and/or access easement of 50 to 100 feet would be located.¹⁵ A conservation easement allows river access for potential restoration or cleanup efforts. Without an easement, the City would have to receive permission from private property owners to pursue any riverbank projects. The City has also adopted ordinances to limit phosphorus fertilizers and asphalt sealcoats; the success of this regulation is limited by enforcement and cooperation from property owners and has yet to be measured.

To further ensure protections for the Huron River, an overlay district could be implemented. The regulations would limit new development, curtail uses involving toxic chemicals on site, and enforce low impact design standards that allow the site to retain water to mitigate contamination entering the river. Ypsilanti has adopted the stringent standards from Washtenaw County Water Resources Commissioner, a mighty step in safeguarding future development from polluting practices. However, these regulations are not a panacea because they only apply to new or redeveloped sites, which are much fewer in number than established sites.

A retrofitting program would have wider scale effects, but its implementation is more controversial than policies pertaining only to new development. The adoption of stormwater fees based on the amount of impervious coverage on a property is an example of this type of effort and has been enacted in places like Detroit and Ann Arbor. In those communities, impervious surfaces incur drainage fees, thus incentivizing the implementation of pervious substitutes. Credits are offered for on-site stormwater management investments, such as the installation of a rain barrel, cistern, or rain garden to capture run-off from a rooftop. Rain barrels are a cost-effective method of storing water for residential properties when used correctly. Best practices suggest rain barrels should stand upright, be screened to prevent mosquito breeding and debris accumulation, connect to overflow barrels, have a “do not drink” spigot, and belong to property owners who have been educated about their use and maintenance.

It takes the work of many groups to see positive change in our water systems. The Middle Huron Partners, a group that works with the HRWC, has invested over \$10 million over 11 years on projects that reduce and capture stormwater runoff. At a larger scale, the Middle Huron Partners successfully lobbied to restrict phosphorous fertilizers, and the state followed suit in 2012 with new legislation to reduce algae blooms. At the county level, Washtenaw County modified its focus from flood control to quality control. This change in philosophy is backed by a hierarchy of preferred management practices that prioritizes natural vegetation first for infiltration, then minimizing impervious surfaces, and finally detention

Table X: Watershed Report Card

Subject ¹	Grade	Explanation
Watershed land use	D	High impervious surfaces along tributaries
Natural areas	D	12% of watershed has intact natural areas
River flow	F	Flashes following storms, erratic dam gate
River habitat	B	Where undammed, favorable features for river life
Aquatic Insect Community	C	Where undammed, good habitat for insects
Fish Community	B	Anglers enjoy good smallmouth bass
Phosphorous	C-	Concentrated of phosphorous exceed target; declining
<i>E.Coli</i>	C	After heavy rain, E.coli exceeds state standards
Total Suspended Solids (TSS)	A	Low levels of TSS
Water Temperature	B	High maximum summer temperatures
Conductivity	B	Mostly measured at normal levels
Dams	F	High presence of dams and poorly controlled

Source: HRWC

¹⁴ HRWC. “The Huron River: Lower Middle Huron.” River Profile. <https://hrwc.maps.arcgis.com/apps/MapJournal/index.html?appid=67e1fd1bbc9a44cf853cd78dd6d8219f>

¹⁵ City of Ypsilanti Code of Ordinances, Article VI: Site Regulations, Section 122-607 (c). https://cityofypsilanti.com/DocumentCenter/View/1396/ZOUpdate-02--ZO_BW20170215_anno?bidid=

and conveyance of excess stormwater.¹⁶ Vegetation is at the top of the hierarchy for its varied benefits: plants provide structural support, stabilize the soil through their root networks to reduce erosion, keep rivers healthier for aquatic life, and purify runoff before it enters the river.

As vegetation becomes the priority for protecting water quality, it is important to recognize the maintenance challenges that have hampered its progress. Landscaping is not a short-term proposition. Specifically, it takes about three years for a rain garden to take root and maximize its capacity as a water absorber and purifier. During that time, it must be regularly nurtured *and* must avoid its other unintended function as a “litter collector.” In cases where rain gardens have amassed trash and debris, they have been deemed “blight” and subsequently removed. A rain garden sign that includes its year of inception can insulate them from removal during their nascent stages and give them sufficient time to mature.


Dam Removal

The Peninsular Paper Dam, in its current state, is a cause of many troubling ecological indicators regarding the Huron River’s health, namely creating impoundments where algae forms and changing water temperatures that alter dissolved oxygen levels, harming fish habitats.¹⁷ Ypsilanti and the HRWC conducted a feasibility report on removing the dam. The dam was classified as a high potential hazard by the DEQ due to the severity of impending damage it could cause if it failed, and its classification as obsolete because it no longer serves any purpose. Based on sediment quality and quantity, potential infrastructure and utility impacts, and riverfront land ownership, it was determined that removing the dam is feasible.¹⁸ In 2016, estimates for repairing the dam would exceed \$800,000 and removing it would cost closer to \$2.7 million. Its removal would help restore the Huron River to a flow that is better suited for the ecosystem that depends on it.

In May 2019, City Council voted to approve \$500,000 towards deconstructing the dam as opposed to continuing to pay for repairs so long as the City applies to grants to complete the project.¹⁹ ²⁰ Dismantling the dam will protect the environmental health of native species that rely on the Huron River, and protect the City’s budget in the long run.

Flooding and Stormwater Management

Flooding has the potential to harm the drinking water supply, human life, property, and infrastructure. The Federal Emergency Management Agency (FEMA) has identified zones based on the anticipated frequency an area will flood in a 100-year interval. These predictions are based on historical data, which means that they do not incorporate climate change considerations. Already, the FEMA-delineated floodplains have been shown in many cases to be outdated, as areas vulnerable to flooding have expanded outside of its boundaries. Part of the increase in instances of flooding is linked to increased precipitation falling in concentrated storm patterns. Fortunately, Ypsilanti has not yet experienced flooding that has overwhelmed its storm sewer infrastructure, and much of the land that lies in the flood zones is designated parkland. The composition of Ypsilanti’s soil also helps in that regard, since only 7% of the soils in Ypsilanti are prone to “frequent flooding,” and the other soils experience no flooding aside from extreme circumstances.²¹ To gain more accurate depictions of how the City may flood in the future, Ypsilanti can invest in an updated study that incorporates recent data and includes forecasts of more intense and frequent storms. The study should also include how the river’s altered channel due to the anticipated removal of the dam may impact flooding.



Green Infrastructure, specifically green stormwater infrastructure (GSI), is one way to reduce the impacts of excess stormwater. Green stormwater infrastructure is a broad term that includes several practices of water management that protect or mimic the natural water cycle. As opposed to conventional “gray” stormwater infrastructure, which uses hard surfaces and systems to channel excess water elsewhere, this approach protects and expands the natural environment so that water can be absorbed naturally at several scales: a home, a downtown, an entire city, a watershed. Common examples are rain gardens, green roofs, trees, planter boxes, rainwater harvesting systems, and bioswales, and better protection of wetlands and floodplains.

The utility of GSI should not be underestimated. For example, one acre of imperviously-surfaced roadway can generate between 0.5 and 1 million gallons of stormwater runoff annually. On Michigan Avenue in Lansing, there are 30 planter box bioretention areas that collect runoff from four acres of roadway and reduce the annual stormwater runoff by approximately 75%.²²

Landscaping that beautifies a site can also capture stormwater. Already embedded in the landscaping requirements in the Zoning Ordinance is a tree protection plan for site plan review. The applicant is awarded credit for preserving or incorporating existing trees and shrubs into the development, and if trees or shrubs intended to meet the minimum landscaping requirements are cut down or damaged, the applicant must replace them according to ordinance specifications. Moreover, trees proposed for credit cannot be invasive (122-632). The frontage of all public and private streets for a new or altered use that requires site plan review must be landscaped with street trees (122-636). Existing regulation stops short of a tree preservation ordinance, which would prevent the removal of trees determined meeting criteria for condition, size, and species. In a tree preservation ordinance, regulations prioritizing transplanting trees prior to removal can also be included. Furthermore, wetlands are

¹⁶ Washtenaw County Water Resources Commissioner. Rules and Guidelines: Procedures and Design Criteria for Stormwater Management Systems. Revised October 2016. <https://www.washtenaw.org/DocumentCenter/View/302/Rules-and-Guidelines---Procedures-and-Design-Criteria-for-Stormwater-Management-Systems-PDF?bidid=>
¹⁷ Huron River Watershed Council. The Huron River Data Report: Ann Arbor and Ypsilanti Vicinity. <https://www.hrwc.org/wp-content/uploads/LowerMiddleHuron-11x8.pdf>
¹⁸ Princeton Hydro. Peninsular Paper Dam: Dam Removal Assessment and Feasibility Report. September 2018. <https://cityofypsilanti.com/DocumentCenter/View/1789/2018-11-21-Peninsular-Dam-Removal-Study-Report>
¹⁹ WXYZ Detroit. Ypsilanti City Council Votes to Tear Down Peninsular Dam. May 2019. <https://www.wxyz.com/homepage-showcase/ypsilanti-city-council-votes-to-tear-down-peninsular-dam>
²⁰ Ypsilanti City Council. Resolution 2019-101. May 7 2019.
²¹ Web Soil Survey, United States Department of Agriculture, <https://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm>
²² SEMCOG. Green Infrastructure Vision for Southeast Michigan. 2014. Page 45. <file:///C:/Users/Michelle%20Bennett/Downloads/GreenInfrastructureVisionForSoutheastMichiganMarch2014.pdf>

Stormwater Drainage Program

A case study in Detroit quantified the combined advantage of pervious pavement and a rain garden on a church’s parking lot. Using the EPA’s stormwater management model, they calculated that a 4,530 square foot rain garden and a 33,000 square foot patch of pervious pavement reduced stormwater runoff volume by 70%, even during the heaviest six-hour period of precipitation in Detroit’s recent history (2016).¹ In Detroit, there is an added incentive for property owners to use green infrastructure because they are charged a drainage fee based on the impervious surface area on the property. However, they may also earn a "green credit" for actions such as redirecting downspouts into areas where natural infiltration can take place.

tremendous stormwater capturers and beautiful landscapes to behold. While most of them are regulated at the state level, the city can continue to monitor their health and work with partners to protect those that remain.

The Zoning Ordinance also permits accessory stormwater control features such as swales, pervious paving, rain gardens, rain cisterns, vegetated roofs, and other methods. Ypsilanti has one city-sponsored rain garden at the Freighthouse that is managed by volunteers, and several curbside raingardens in Depot Town that are maintained by the DDA with volunteer assistance and assistance from local merchant groups.

In partnership with Washtenaw County Conservation District (WCCD), the Sustainability Commission has offered support to promote WCCD workshops to residents, encourage tree planting on residential lots, and identify a site and volunteers for an Earth day tree planting event. Washtenaw County has staff dedicated to teaching master rain gardener certification courses and provides technical advice for planting one on private property. The City of Ypsilanti also won bronze at the Michigan Sustainability Conference in 2019 for its work with the Washtenaw County Water Resources Commissioner to provide free consultations to households interested in developing or enhancing rain gardens.²³

In addition to enhancing green stormwater infrastructure, some expansion to grey infrastructure may also be needed. Ypsilanti was recently awarded a Stormwater, Asset Management, and Wastewater (SAW) grant. With the funds, the City mapped its storm sewers and plans to upgrade its software to aid in continuing to monitor and record its conditions. With improved information about existing infrastructure, Stormwater Management Plans can be tailored to specific areas for improvement so that estimates for expansion are based on accurate data. Using climate change predictions for precipitation and updated inventory on the storm sewer system, Ypsilanti can continue to use the Capital Improvement Plan to plan for greater stormwater capacity with greater precision.

Drinking Water Sources

There are 13 water wells within the City: four type 1 (community) wells, now closed; one type 2 (facility) well, now inactive; four household wells, and four irrigation wells.²⁴ These are personal wells that the owners are responsible for testing. The City of Ypsilanti, through the Ypsilanti Community Utilities Authority, sources water from the Great Lakes Water Authority for its municipal water system.

The Ypsilanti Community Utilities Authority provides a municipal water system and requires households that can be serviced by municipal sewer shall be, according to ordinance 106-22. At the point of a sewer hookup, the City encourages households to use the municipal water system, and as most of the few remaining households convert, the installation of personal wells is no longer necessary nor advisable.

The City created two well exclusion areas which are written into local ordinances and recorded with the Register of Deeds. Well exclusion areas were instituted to protect property from water contamination. One, in the downtown, prohibits wells adjacent to a parcel where there was a leak from a former gas station; the other, in the Bell-Kramer neighborhood, prohibits wells adjacent to the former landfill.

What the City can focus on is how to improve services through its water and wastewater provider Ypsilanti Community Utilities Authority (YCUA). Because wastewater treatment plants are energy-intensive, and provide an essential service to households, upgrades to this system are a win-win. Potential policies are two-fold. First, the City and YCUA can collaborate on home and business water efficiency financing programs to reduce total load and peak flow rates, saving energy at the plant and potentially lowering water bills for households. Secondly, advances to sensors and software can also improve their energy efficiency so that our water sources and treatment can contribute less to emissions.²⁵ The City can also continue to work with YCUA on water transmission infrastructure upgrades and maintenance; this minimizes potential waste from leakages and helps to minimize the risk of lead or other exposure from older pipes.

Sustainability Goals: Water

GOAL: Protect the watershed from further contamination.

- ~~• Establish a Sensitive Features Overlay Zoning District along the Huron River and Paint Creek and implement LID standards and chemical bans~~
- Consider a sensitive features overlay zone providing a buffer around the Huron River and Paint Creek that provides site and use regulations tailored to the proximity to these waterbodies.
- Invest in consistent enforcement for compliance to the sensitive feature overlay zoning district.
- Continue to pursue updates to the zoning ordinance, such as tree protection regulations, that preserve and improve vegetation that can mitigate stormwater impacts.
- Continue to support the work of the Washtenaw County Water Resources Commissioner and other partners to educate members of the public, particularly single-family homeowners, on stormwater issues.
- Monitor adherence to the City’s phosphorous fertilizer and tar sealcoat ordinances for effectiveness.
- Work with Washtenaw County Environmental Health to research the status of remaining private wells and provide resources and recommendations for testing water quality to property owners

GOAL: Preserve and expand the City’s capacity to deal with heavy rainfall to mitigate negative effects on people and property.

- Incorporate capacity upgrades for grey stormwater management into the CIP based on predictions for greater precipitation
- Update the flood maps, including FIRM, based on climate projections and changes to the river channel since the FIRM formulation in the 1970s
- Investigate an equitable stormwater fee schedule that encourages converting impervious to pervious surfaces and proper use of rain barrels or other detention/retention systems.

²³ Michigan Green Communities (MGC). 2019 MGC Challenge Participants and Awards. <https://migreencommunities.com/blog/>
²⁴ Michigan Open Data Portal, “Water Wells – South Central & Southeastern Michigan” <http://gis-michigan.opendata.arcgis.com/datasets/water-wells-south-central-southeastern-michigan?geometry=29.491%2C-17.893%2C-105.860%2C71.775>
²⁵ Ypsilanti Climate Action Plan. 2012. Pg 30.

- Consider banning basements or enforce floodplain standards in boundaries where the soil has limited capacity to handle stormwater
- Develop a Stormwater Management Plan
- Continue to pursue the removal of the Peninsular Dam
- Continue to maintain City lands that are in the flood zones and vacant for stormwater and floodwater mitigation.
- Pursue GSI projects in the City parks, particularly in the flood zones.
- Pursue conservation &/or access easements along the Huron River.
- Explore offering incentives to property owners to retrofit existing buildings and site improvements with stormwater-friendly infrastructure, including rain gardens.
- Explore the potential to equitably enact a stormwater fee structure to encourage private retrofit stormwater infiltration and detention infrastructure

GOAL: Promote resources for water conservation and testing to ensure access efficiency upgrades and clean water

- Work with YCUA to develop home and business water efficiency financing programs
- Promote Great Lake Water Authority program WRAP to perform conservation audits and funds for repairs to help reduce low-income households reduce water bills
- Collaborate with YCUA on water conservation and infrastructure improvement projects.

DRAFT NOVEMBER 2020

Energy

In November 2019, the City of Ypsilanti committed to carbon neutrality by 2035 in partnership with the City of Ann Arbor as a response to the climate emergency. The resolution calls for City Council to budget staff and resources to become carbon neutral. Achieving this goal will require the City to first measure, and then reduce, greenhouse gas (GHG) emissions that trap heat in the atmosphere, including carbon dioxide, methane, nitrous oxide, and fluorinated gases.²⁶

The City of Ypsilanti has focused on measuring local emissions for a decade or more. In coordination with the 2012 Climate Action Plan, 2005/2008 community and government greenhouse gas emissions were evaluated. An updated Greenhouse Gas (GHG) Study was conducted alongside this Sustainability Plan to determine if the actions had achieved reductions in carbon emissions. The 2020 City of Ypsilanti Community and Government Greenhouse Gas Inventories present 2018 emissions from the City of Ypsilanti community as a whole and emissions from the City of Ypsilanti government operations. The inventory follows the approach and methods provided by the ICLEI US Community Protocol for Accounting and Reporting of Greenhouse Gas Emissions (US Community Emissions Protocol). ICLEI is a global network of local and regional government committed to sustainable urban development. Because this protocol differs from the 2012 methodology, the results are not directly comparable, but do show movement in emissions.

Community Greenhouse Gas Inventory


The City of Ypsilanti examined community emissions through multiple frames, including “community-wide activities” and “government significant influence.” The community-wide activities frame shows the extent to which community members’ use of energy, materials, and services contribute to GHG emissions within or outside of the City boundary, regardless of whether the City has significant influence over those emissions. The findings show that the City of Ypsilanti’s total 2018 community emissions were 269,180 metric tons of CO₂e, comprised primarily of commercial energy, residential energy, and transportation sectors.²⁷

Despite its lack of direct control over major GHG contributors, the City included sources or activities in which it can exert significant influence over energy consumption. Already measured as the largest greenhouse gas contributors, the categories “residential” and “commercial-industrial” saw an increase in emissions between 2008 and 2018, making households and businesses starting points for new mitigation policy. It is possible that the uptick in commercial and residential emission is related to the legalization of marijuana for personal and commercial use, given that the time period coincides with the implementation of these notoriously energy-intensive operations. It was estimated that through policy, Ypsilanti can influence 64% of community emissions (171,310 MT CO₂e).²⁸ This figure will become the baseline for setting an emissions reduction target, against which future emissions in the “significant influence frame” will be measured.

Government Operations Greenhouse Gas Inventory

The government operations inventory is a separate greenhouse gas emissions inventory that takes a deeper dive into emissions derived from municipal operations. The largest emitters are streetlights and traffic signals, accounting for 32% of emissions, followed by vehicle fleet emissions that comprises 17% of the total.²⁹ Actions to reduce emissions in both sectors are substantially underway in the City and will continue to play a key part of a carbon neutrality strategy. Ypsilanti has already transitioned the majority of its light fixtures to LED and begun introducing hybrid and electric vehicles to its fleet. Emissions are expected to continue dropping as the City continues to address harder-to-replace streetlights and continues fleet modifications. Not including emissions from employee commutes and solid waste, government operations emissions have dropped by 42% over a decade!

Figure X: Comparative Government Emissions by Sector 2012-2018 (MT CO2e)



Source: EcoWorks

Units of Measurement

CO2 – carbon dioxide

CO2e – carbon dioxide equivalent, a standard unit for measuring carbon footprints that conveys the impact of different greenhouse gases in terms of the functionally equivalent amount of CO2

Transportation


I-94 passes through the City of Ypsilanti and represents a significant source of transportation related emissions which are not directly attributable to the community. The Southeast Michigan Council of Governments (SEMCOG) estimates that travel on I-94 represents 53% of all total on-road vehicle miles traveled within the City annually while non-highway vehicle miles represent 47%.

Residential

Within the residential sector, electricity use accounted for 60% of emissions, while natural gas use in stationary combustion accounted for 40%.

²⁶ Environmental Protection Agency. “Greenhouse Gas Emissions.” <https://www.epa.gov/ghgemissions/overview-greenhouse-gases>
²⁷ City of Ypsilanti 2020 Inventories of Community and Government Greenhouse Emissions. Figure 2. Pages 28-29.
²⁸ City of Ypsilanti 2020 Inventories of Community and Government Greenhouse Emissions. Figure 15. Pg 37.
²⁹ City of Ypsilanti 2020 Inventories of Community and Government Greenhouse Emissions. Pgs 42 and 43.

Figure X: Comparative Community CO2e Emissions by Section 2012 & 2020* GHG Inventories



Source: EcoWorks

The City has made successful strides in increasing its renewable energy portfolio. Ypsilanti continues to lead by example in its actions and in streamlining the solar permitting process to enable property owners to follow suit. The City has enabled solar installation as far as its authority permits, stopping just short of mandating them on new construction.

Ypsilanti worked with DTE and Solar Currents to install a solar farm by Highland Cemetery. The City has also installed solar panels on most of its municipal buildings and converted most of its lighting – both building and streetlighting – to LED. These efforts have translated into noticeable reductions in emissions since the last inventory was conducted. Moreover, the City has pursued other best practices that include low-flow water fixtures, programmable thermostats, air sealing, staff behavior changes, and increased awareness about conservation and efficiency. Another City policy that may have contributed to emissions reduction is an increased financial contribution to expand bus service, potentially taking cars off the road. Energy efficiency measures for municipally operated facilities have resulted in significant savings. The City should continue to address major projects at the most energy-intensive facilities and implement no- or low-cost efficiency opportunities at all facilities. Larger projects, which require more planning and money, should be integrated into capital improvement plans.

The City has fallen short on its most ambitious goal related to energy: Resolution 2013-175 sought to place solar on 1,000 roofs or generate five megawatts of electricity from distributed solar by 2020.³⁰ Solar Ypsi has calculated that 72 sites have solar panels, totaling about 1.4 megawatts of capacity. Based on those calculations, the City has realized 7.2% of the solar roof target and 28% of the megawatt target. The City should revisit and update this goal- perhaps updating the target to 1,000 roofs that have solar by the year 2030.

A next step in emission reduction for Ypsilanti could be the purchase of renewable energy certificates (RECs) to expand consumers’ service options and support renewable electricity development. An REC is a tradeable market-based instrument used in electricity markets. It allows organizations that purchase RECs to account for nonrenewable electricity use. REC purchasers diversify their consumption by expanding its use of low- to zero-emission energy sources and tracking its growing reliance on renewables. RECs are a flexible tool because they can be purchased separately from electricity, meaning the purchasing organization does not need to alter its existing power contract to use greener power. The two can be matched and use the same infrastructure.³¹

Making headway on properties that are not municipally owned is also an issue of equity and education. Increasing energy efficiency for residents and business owners means reducing the percentage of income spent on housing utility costs in addition to reducing the amount of energy consumed. Education programs for residents could help lower residential usage; this awareness and access may be especially promising in Ypsilanti given that residents are supportive of increased energy efficiency standards and the use of renewable energy. Promoting higher standards for new development, namely commercial and industrial, could be encouraged through incentives for developers to pursue energy-efficient standards (Energy Star, LEED, Living Building Challenge), applications for tax abatements, and promoting existing financial tools to help developers meet these standards during and prior to the site plan review process. For small businesses, Retired Engineer Technical Assistance Program (RETAP) provides pollution prevention, water conservation, and energy efficiency programs free of charge. RETAP teams review a site’s operations and recommend strategies for reducing waste at a significant cost savings. Eligible businesses must be independently owned and operated, have fewer than 500 employees, and be primarily engaged in manufacturing.³²

Another issue to tackle in Ypsilanti is residential energy consumption. Renter-occupied units are a large portion of housing stock, so energy efficiency and safety of rental properties could lead to substantial reductions in use. The up-front costs of major efficiency improvements have so far exceeded their profit potential in the estimation of the local landlord community, and so the City will be in a stronger position to implement required standards as the market strengthens. In the meantime, there are intermediary steps to take. As outlined in the 2012 Climate Action Plan,

Commercial

In 2017, EMU replaced an aging cogeneration unit with a new high efficiency unit projected to reduce annual emissions of CO2 by 21,305 tons/year and reduce NOx emissions by 112 tons annually. Emissions from Eastern Michigan University represent 46% of total commercial emissions in the City of Ypsilanti.

Source: Ecoworks

Energy Competitions

In Traverse City, the month-long “kWh Challenge” was organized. Over 50 staff members from city departments participated in weekly challenges of unplugging unused electronics, using efficient computer settings, and using daylight as opposed to artificial light. These represent simple behavior changes that have significant savings, while creating a friendly competition to train staff on energy efficiency.

Source: SEEDS

³⁰ City of Ypsilanti, “Resolution for 1,000 Solar Roofs Initiative”, No. 2013-175, September 3, 2013. http://www.solarypsi.org/repository/documents/cityhall/Resolution_2013-175_1000_Roofs_by_2020.pdf
³¹ EPA Green Power Partnership. “Offsets and RECs: What’s the Difference?” https://www.epa.gov/sites/production/files/2018-03/documents/gpp_guide_recs_offsets.pdf
³² EGLE. Pollution Prevention and Energy Efficiency Assessments. <https://www.michigan.gov/egle/0,9429,7-135-3304-11899--,00.html>.

a requirement to provide information regarding utility charges allows potential tenants to choose a unit based on its energy performance, however, this disclosure has proven impractical due to the varying use from tenant to tenant. During rental inspections, a certification process that verifies which units have met energy standards would enable tenants to shop and compare units more easily. Certification criteria can be based on existing programs such as the “Energy Star Homes” program. For eligible low-income homeowners, Washtenaw County has a weatherization program that reduces monthly energy bills by improving a home’s insulation.


The coordination of reducing municipal and community emissions should be performed by a dedicated member of staff. An Energy Manager position that is integrated into City Hall could make enduring progress on these goals. Many of the energy action plans items derived from the 2018 Energy Plan could fall under the Energy Manager’s purview. An Energy Manager could improve data collection processes, spread knowledge of energy management among city staff, analyze trends in energy use, and develop communications with the residents and property owners. This person would lead a team to research and update available energy-saving equipment, determine how to incorporate more renewable energy in the City’s portfolio, promote policies and incentives for reducing energy use, seek grants and other funding mechanisms to implement clean energy projects, liaise with the Sustainability Commission, expand outreach to commercial and industrial uses, and manage capital improvement projects related to energy efficiency. In recognition of the substantial financial commitment that a newly-created staff position represents for the City, a reasonable starting place could be to fund the position for one year and expect an early outcome of its efforts to result in savings sufficient to cover continued funding.

Importantly, development of this system will build institutional knowledge that outlasts the employment of any one dedicated staff member. A system that regularly schedules a GHG inventory update every five years using the same methods and program that forecasts reductions and benchmarks municipal utility bills to an annual goal would be a valuable organization change. The system should include internal reporting from the Sustainability Commission so positive results can be shared and celebrated with the community.

Ypsilanti has joined Ann Arbor in the goal of becoming carbon neutral by 2035. Recently, Ann Arbor published a draft Net Zero plan with seven strategies for getting there. The strategy “Power our Electrical Grid with 100% Renewable Energy” set forth in the plan is ambitious but necessary. Estimated to cost \$4.1 million and reduce greenhouse gases by 41%, the goal is supported by four actions. Community choice aggregation, which gives cities control over procuring power for its community, has one major roadblock: this step is not currently enabled by the state. Ann Arbor is working on recommendations for legislators to allow cities to bulk buy power on behalf of their residents and businesses. Through economies of scale and the right to integrate as much renewable energy as the community can manage, Ann Arbor has committed to buy 100% renewable energy by 2027 and provide it for the entire community through community choice aggregation. As a partner in this effort, Ypsilanti should support and lobby the state with Ann Arbor for legislation that has the power to convert widescale energy use into clean consumption.

Through the Net Zero community engagement sessions, microgrids were mentioned to produce, convey, and store energy. Microgrids are decentralized nodes that transmit energy with the capacity to disconnect from the traditional grid. In times of crisis, such as storms that cause major power outages, an entire area may lose energy if the traditional centralized grid is damaged. Because microgrids can disconnect from the traditional grid, they mitigate the effects of storm on households and businesses. They can be powered by generators, batteries, or renewable sources which plugs them into renewable energy goals and adaptation goals. Still, there is little discussion of deployment as further research is needed into how they should be operated and where they should be placed to have the largest impact.

On a larger scale, the City’s support for sustainability is reinforced when it participates in regional, national, and international commitments to energy, climate, and sustainability causes. Ypsilanti has formed pivotal partnerships locally with EGLE, DTE, and Ann Arbor, among others but its work could be raised to higher heights by signing on to the Paris Climate Agreement, The Sierra Club’s “Ready for 100” pledge, and the Global Covenant of Mayors for Climate and Energy. Although the goals embedded in each of these organizations’ core missions may seem difficult to attain, the connection to case studies, methodologies, policies, and expertise will regenerate interest and help to sustain action in the pursuit of low-energy consumption.



Waste Management

The City of Ypsilanti’s waste disposal is contracted to Stevens Disposal, which serves Southeast Michigan. Stevens Disposal provides waste services to 5,337 households, roughly 70% of households in the City.³³ ³⁴ The solid waste generated in the City is transported to two landfills in southeast Michigan: Carleton Farms located in Sumpter Township and the City of Riverview’s municipal landfill, Riverview Land Preserve.³⁵ Carleton Farms accepts 2.25 million tons of waste annually, the third highest volume in Michigan, and has a total capacity of 101 million tons, the largest in the state. The landfill is estimated to produce 15.8 million cubic feet of gas per day, 40.1% of which is captured. Methane that cannot be captured is flared. Flaring gas is the process of lighting gas wells on fire to convert the more harmful methane to carbon dioxide as it enters the atmosphere. Carleton Farms flares 0.65 million cubic feet of landfill gas daily, roughly two-thirds the size of an Olympic size swimming pool. In 2018, Carleton Farms emitted 195,105 metric tons of carbon dioxide equivalents to the atmosphere.³⁶ Based on current capacity, Carleton Farms is anticipated to close in 2052. Riverview Land Preserve accepts 780,000 tons of waste annually and has a capacity of 39 million tons, and is expected to close in 2031.³⁷ In 2018, Riverview Land Preserve emitted 288,394 metric tons of carbon dioxide equivalents into the atmosphere. While the waste generated by Ypsilanti is only a fraction of the waste sent to these two facilities, it is undeniably contributing to a highly emissions-generating system.

The closure of the two landfills that Ypsilanti relies on in the relatively near future provides an opportunity to pursue strategies for reducing and diverting as much of the waste stream as possible. In 2016, Kent County published a landfill reduction plan called “Strategy to Reimagine Trash,” calling for a 20% reduction in landfill contribution by 2020 and a 90% reduction by 2030. The study found that up to 75% of the waste stream in Kent County had the potential to be converted or

reused and explores a variety of targeted means to address specific waste categories, including the development of a sustainable business park, targeted at businesses dedicated to the recovery and re-application of common elements found in the waste stream. Although Ypsilanti’s built-out status would make developing a similar business part here challenging, the lesson that “one person’s trash is another’s treasure” is well-taken.

Reusing, recycling, and composting are household-level actions that can be supported or encouraged by the City. Community residents have developed several “buy nothing,” “freecycle,” “gift and grow,” and “mutual aid” groups devoted to individuals offering up for free items they no longer use to other individuals, and the city currently hosts two thrift shops and a wide array of vintage and other resale shops. The City could publicize these groups and shops in their communications. The City of Ypsilanti provides recycling hauling services, and as of 2020 serves 5,186 properties;³⁸ they also partner with Simple Recycling for curbside recycling of items such as textiles and small electronics. The City has also partnered with the nonprofit Recycle Ann Arbor for expanded waste dropoff services for recycling at the RAA site in Ann Arbor. The City has a composting site that can serve yard waste but not kitchen waste, and partners with Ypsilanti Township for yard waste dropoff services. Kitchen and yard waste can be composted by individual households using common aboveground systems and applied at the household level. For example, encouraging onsite leaf mulching has the benefit of creating high-quality, high-nutrient soil that can be used for gardening without the hassle of using a service. The City could support these efforts through education, perhaps in conjunction with education about natural lawn alternatives.



The public expressed the need for recycling and composting options in all three forms of engagement. Residents prioritized expanded recycling and composting services in the “infrastructure” category of the survey, and 61% believe that improved curbside access would realistically help their households divert waste from landfills. The Zero Waste Hierarchy describes a series of steps and considerations that will help communities, organizations, and individuals make smarter choices about materials purchases to reduce environmental impact.

A comprehensive waste strategy starts with source reduction or diversion of waste from landfills. Every ton of mixed paper recycled can save the energy equivalent of 166 gallons of gasoline. Not purchasing that paper to begin with makes an even bigger impact because no raw materials or energy are used to produce it, to transport it, or haul it at the end of its life. Diverting organic waste from landfills includes separate collection requirements, education campaigns, financial incentives for food redistribution, and disincentives for generating food waste.³⁹ Nearly half of the solid waste produced globally is organic or biodegradable.

The City of Ypsilanti provides curbside recycling and composting pickup for certain materials, and households and property owners must rely on assorted partners for full service. The curbside recycling program does not collect glass and Styrofoam because they disrupt the recycling stream. The curbside recycling service is limited to properties with fewer than four units, which excludes many residential properties. Ypsilanti’s partnership with Simple Recycling provides households curbside recycling of textiles and small electronics, and the City relies on Washtenaw County for annual drop-offs and hazardous materials disposal. Items with Freon can be

³³ Stevens Disposal Services Contract. Retrieved from email with Bonnie Wessler. February 27, 2020.
³⁴ United States Census “Quick Facts: Ypsilanti city, Michigan”
³⁵ Stevens Disposal Customer Service. Phone call on January 20, 2020.
³⁶ FLIGHT, United States Environmental Protection Agency. <https://ghgdata.epa.gov/ghgp/main.do>
³⁷ Landfill Methane Outreach Program (LMOP) United States Environmental Protection Agency. <https://www.epa.gov/lmop/project-and-landfill-data-state>
³⁸ City of Ypsilanti
³⁹ Corvidae, J. et al. The Carbon-Free Region Handbook. RMI. (2018) Retrieved from https://rmi.org/category/global-energy-transitions/cities-and-communities/carbon-free-regions-handbook/?post_type=insight

disposed of curbside with advanced planning and a fee. Residents are also eligible to use Recycle Ann Arbor’s drop-off recycling station for safe disposal of items that Ypsilanti does not collect. This inventory shows that options for recycling do exist, but the decentralization of the services and locations is inconvenient and discourages full participation.

In 2018, the Sustainability Commission resolved (No. 2018-08-002) to increase recycling rates based on the Climate Action Plan findings. The resolution aims for increased education about the City’s recycling program and the placement of artistic recycling bins throughout the City. The expansion of the recycling program would have to be accompanied by an extensive outreach and education program to ensure that best recycling practices are followed. The following summer, the Sustainability Commission defined 2019-2020 goals, one of which was to facilitate a Zero Waste event (No. 2019-07-002).

The curbside composting program operates from April through December, but this service is only for yard waste and not for household waste.⁴⁰ Due to the soil composition of the City, any new composting facility would likely have to locate outside of City boundaries as the “Soil – Surface Composting Facility” shows that most of the City’s soil is not conducive to a surface composting facility. These ratings are based on factors that might lead to the contamination of groundwater from composting byproducts.⁴¹ Due to its current location in the floodplain, the compost services should not be expanded to other organic waste at this site. Because the City’s soil conditions inhibit the likelihood of expanding its composting infrastructure, and the current compost yard is in a floodplain, Ypsilanti should cooperate with an organization that offers composting services and encourage residents to use it. Another possibility is a biodigester that use microorganisms to decompose waste. The decomposing waste produces methane, which can be captured for energy, and digestate, and then used as fertilizer.⁴² Biodigesters are more expensive to build than traditional composting facilities but produce two valuable resources, methane and digestate, which can be sold.⁴³ In 2017, the City of Ann Arbor conducted a feasibility study for a biodigester and concluded that the project would was not yet profitable – the startup costs are too high for the revenue stream it would provide. The study cited challenges such as low landfill fees, modest energy costs, and minimal financial reimbursement as the reasons for the improbable feasibility of the biodigester.⁴⁴ At a minimum, the City can offer educational resources to households interested in composting their own household waste.

Sustainability Goals: Energy

GOAL: Decrease the community’s emissions by 171,310 metric tons of CO₂e by 2030.

- Work with the City of Ann Arbor to investigate bulk buying of renewable energy through the Community Choice Aggregation Legislation.
- Purchase renewable energy credits (RECs) for City operations.
- Promote state policies, incentives, grants, and Community Energy Management programs that encourage energy efficiency and renewable energy to property owners.
- Promote Washtenaw County’s weatherization program for low-income homeowners.
- Work with community stakeholders to initiate an energy competition. The university and City can partner together to challenge another city and university to an energy reduction competition.
- Implement an inter-departmental site plan review process with attention to sustainability-related strategies such as energy use and efficiency, generation and offsetting of emissions, on-site water management and infiltration, etc.
- Investigate the feasibility of a microgrid.
- Review and incorporate aspects of the International Dark Sky Model ordinance to reduce energy waste (i.e. motion activated lighting on municipal buildings)
- Participate in or sign-on to regional, national, or international commitments to energy, climate, and sustainability including but not limited to the Paris Climate Agreement, the Sierra Club’s “Ready for 100” pledge, the Global Covenant of Mayors for Climate and Energy.
- Develop an electric charging vehicle infrastructure strategy
- Create a green rental certification program to encourage energy-efficient improvements
- Work with the HDC to incorporate historically compatibly fixtures that are dark sky compliant
- Continue to pursue policies and projects that improve nonmotorized transportation.
- Continue to encourage solar energy installations throughout the City.
- Partner with other agencies, such as YCUA , DTE, and MiSaves to provide education and incentives for energy use reductions, both residential and commercial.
- Continue to participate in local, regional, national, and international efforts for climate mitigation and adaptation.
- Continue membership in communities such as ICLEI that help support local efforts to combat and adapt to climate change.

GOAL: Decrease government operation emission in support of attaining citywide net zero by 2030

- Establish an Energy Manager position to be responsible for the following duties:
 - Improve knowledge of energy management among city staff and appointed officials among staff
 - Create a data-driven system that is replicable over time, and includes annual forecasts, benchmarks for energy use reductions, and an internal reporting protocol
 - Work with the Sustainability Commission to produce an annual report that highlights where emission reductions and procedural improvements have been made
 - Improve communications with facility managers, utility providers, and relevant contractors to resolve issues quickly
 - Increase outreach to and participation of industrial and commercial customers in renewable energy and energy efficiency projects
 - Research and utilize the most efficient equipment available
- Continue to incorporate renewable energy into the energy portfolio of each government building including back-up generation
- Re-establish the City’s revolving loan fund for energy efficiency projects.
- Conduct a GHG inventory every 5 years using input from 2012 & 2018 findings in the ICLEI GHG framework
- Improve fleet fuel efficiency with clean diesel, alternative fuels, and electrification.
- Publicly report on progress made toward energy goals.
- Continue to make energy-efficiency improvements to City owned facilities

⁴⁰ The City of Ypsilanti, Meeting with Bonnie Wessler, March 4, 2020.

⁴¹Web Soil Survey, United States Department of Agriculture <https://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm>

⁴²Nyifa, W. “Remember the Biodigster.” Saskatchewan Research Council <https://www.src.sk.ca/blog/remember-biodigester>

⁴³ Dawson, L. “How Cities are Turning Food into Fuel.” Politico, Nov. 11 2019.

⁴⁴ City of Ann Arbor. “Ann Arbor Biodigester Feasibility Study.” June 2017. <https://www.a2gov.org/departments/systems-planning/planning-areas/climate-sustainability/SiteAssets/Pages/Sustainability/Ann%20Arbor%20Biodigester%20FS.PDF>

ENERGY: Reduce the amount of waste generated in Ypsilanti that enters landfills

- Conduct a waste audit to understand the baseline composition of the waste stream at the municipal operations and community level
- Help publicize local re-use opportunities, such as the Buy Nothing Project and Freecycle.
- Implement an educational campaign on existing recycling and composting options
- Expand recycling to public spaces and all City facilities by placing artful, educational, and engaging waste sorting stations throughout the community
- Create a coordinated recycling system that has a one stop for difficult-to-recycle materials including electronics and refrigerant management
- Increase access to curbside recycling services to multi-family units
- Define Zero Waste for Ypsilanti using the Zero Waste hierarchy. Set a goal for City operations to be zero waste (excluding medical waste) by a specific date with annual benchmarks.
- Require that any events with a City permit provide for recycling, compost, and provide a discount for Zero Waste events
- Require government operations to use durable or compostable materials
- Implement a pilot program for a municipal kitchen compost system with high food-waste generators.
- Investigate a partnership with a commercial-scale compost operation
- Pilot curbside community composting services for leftover food
- Investigate funding sources to bring down the cost of a biodigester
- Permit onsite composting of mulched leaves
- Continue to explore options to improve recycling and composting opportunities within the City and with partners.

DRAFT NOVEMBER 2020

Biodiversity

Endangered Species

The term “biodiversity” refers to the variety of living organisms within an ecosystem, and the plant and animal habitats of Ypsilanti and the broader region have been significantly impacted by urbanization and development. The Michigan Natural Features Inventory (MNFI) maintains a database of state and federally listed endangered and threatened species. This observational data is converted into the Biological Rarity Index. The Biological Rarity (Biorarity) Index model is based on the MNFI database of known sightings of threatened, endangered, or special concern species and high-quality natural communities. Each record is spatially joined to its habitat using land cover data, streamlines, and rail corridors. The records are then assigned three values based on the species' global status, state status, and occurrence quality rank. These values are multiplied by a likelihood of future sightings based on the age of the database record. Finally, the scores of all the records in a geographic unit are summed to determine the Biorarity Index for that geography.⁴⁵ The map “Biological Rarity Index” illustrates the areas in the City by that index. The higher the index, the more likely that area has threatened and endangered species. The areas with a higher index (darker colors) should be prioritized for conservation because of the importance of the habitat to threatened and endangered species. Overlaid on this map are three sites that have remained relatively untouched since the 1940s. Each of these areas fall into zoning districts with little protection from development *and* correspond to priority conservation areas on the map, creating conflict from a preservation standpoint.

Table X: Potential Conservation Areas Current Zoning Districts

Area	Zone	Description of Zone
Mansfield (adjacent to cold water trout stream) & Highland	Production, Manufacturing, Distribution	Buildings can be on large plots of contiguous land, serviced by railroad lines or major thoroughfares; uses are expected to generate waste, noise, odor, and truck traffic; however, uses should produce minimal external impacts that are detrimental to other uses in the district or to properties in adjoining districts
Clark	Multi-family dwelling	Adjacent to high traffic generators and major thoroughfares and corridors; insure sound development policies for concentrations of multifamily units; recreation, service, and retail uses are permissible as special land uses to allow residents to access everyday needs by foot, if they are not already within a quarter-mile walking distance

Due to the sensitive nature of threatened and endangered species, the MNFI does not release site specific data on threatened and endangered species, but in Washtenaw County there are 83 observed species that are listed as threatened or endangered, including the peregrine falcon, smallmouth salamander, and orange frilled orchid.⁴⁶

Native Plants

Native plants play an essential role in ecosystems: they are the primary producers that convert the sun’s energy into biological material. Secondary producers, such as insects and herbivores, rely on plants to survive, and tertiary species such as carnivores rely on the entire chain. When this chain is interrupted, it impacts every organism involved in the ecosystem. Some of the largest threats to plants are human development and invasive species. Invasive species disrupt the proliferation of native plants and can therefore throw off the balance needed for the local ecosystem. Invasive species are species from another ecosystem, usually from another area of the globe, that outcompete the native species for essential resources. Invasive species outcompete native species because there are no natural predators or processes in the native ecosystem to curb their growth. When native species disappear from the landscape, other organisms whose survival depends on the native species also disappear.

As climate change continues to elevate global temperature averages, the composition of native species is subject to change. Species that were originally held south by a temperature barrier are now able to expand farther north because of rising overall temperatures. Meanwhile, native species that are not adaptive to warmer temperatures may disappear from the landscape.

Habitat Corridors

One of the most effective things a community can do to preserve biodiversity is to concentrate development so that it does not sprawl onto and degrade natural habitat. The Mansfield and Clark sites are located on the periphery of the City, in land-use-intensive zones, making them vulnerable to larger footprints from commercial, industrial, or residential uses. Effective policy ensures that untouched land is ample and contiguous so that animal species can minimize their contact with the developed world. Because habitat corridors, like other corridor types, frequently cross municipal boundaries, they should be considered in a multijurisdictional context. Prior to the next sale of these lands, an inventory of habitat corridors and undisturbed sites should be conducted through a partnership with the City of Ypsilanti, Ypsilanti Township, Washtenaw County’s Natural Areas Preservation Program (NAPP), and private property owners, including the Southeast Michigan Land Conservancy NAPP can acquire natural areas once landowners have nominated their property for the program. The land is then owned and maintained by the Washtenaw County Parks and Recreation Commission with the purpose of preserving the land for plants and animals.⁴⁷ Building a relationship with property owners prior to the sale of their land, and maintaining an inventory database of the plant and animal species in need of protection, could prevent the loss of more habitat. Traffic calming infrastructure can also reduce animal crossing mortality.

Another approach to enhancing biodiversity is to attract animals back to the city. Distributed habitat improvement programs like bat houses, pollinator gardens, “bird safe” design, a “lights out” program during migratory seasons, and other innovations as they develop, can bring species to the city to rebuild the ecosystem.

Wildlife-friendly Gardens

In urbanized areas, converting lawns to gardens can create pockets of biodiversity and create and support habitat corridors. Lawns may be naturalized, with turfgrass replaced by native plant species, or turned into food or cultural gardens. Each type of garden is an improvement for insect and bird species over a turfgrass lawn, but naturalized lawns may be less legible as gardened and tended spaces than cultural or food gardens. Naturalized lawns, particularly those containing native grasses and goldenrods, are often perceived as unkempt due to their superficial similarity to overgrown traditional suburban American gardens and lawns. As blight ordinances, including the City’s, are generally based on the model of a traditional suburban American garden having become overgrown, there’s a supposition in the ordinance that a “weedy” garden

⁴⁵ Biological Rarity Index, Michigan Natural Features Inventory – MSU Extension, <https://mnfi.anr.msu.edu/resources/biological-rarity-index>
⁴⁶ Michigan State University. MSU Extension. Michigan Natural Features Inventory. Accessed March 3, 2020. <https://mnfi.anr.msu.edu/resources/county-element-data>
⁴⁷ Parks and Recreation Washtenaw County. Natural Areas Preservation Program. <https://www.washtenaw.org/939/Natural-Areas-Preservation-Program>

consists of tall grasses and is likely to attract or harbor vermin and encourage dumping of trash, and is undesirable on that basis. This creates conflict when a code enforcement officer or neighbor misidentifies a naturalized garden or lawn as a weedy and unkept one.

The Sustainability Commission adopted a resolution (No. 2020-002) that acknowledges the value of native plants, particularly those in private landscaping, and requests that the City Council amend the ordinance to support the planting of native species, disregarding native plant blight violations in the meantime, to make reasonable efforts to use native plants on City property, and to educate residents about native species suitable for planting on private property. Other municipalities have passed ordinances that allow naturalized yards and gardens, but approaches vary from a “presumption of intent,” such as the cities of Royal Oak and Ferndale, wherein gardens are presumed to be tended unless specified noxious weeds are identified, or a “presumption of abandonment,” wherein gardens with plants over a certain height are presumed to be abandoned unless a permit or other type of permission has been sought. In both cases, the majority of municipalities have plant height restrictions in certain areas to preserve visibility and/or sidewalk navigability.

Ypsilanti has a history of urban food gardening, which can support biodiversity in two important ways. First, gardens directly support pollinators and other species (e.g., soil fauna and birds) when native plants are included in their design. Second, food-producing gardens reduce our reliance on industrial agriculture, which is a primary driver of biodiversity loss worldwide. For both of these reasons, it is imperative that Ypsilanti continue to support gardening and local food systems in any way it can. These endeavors benefit the local economy and improve the resiliency of our community, thus touching on all three of the pillars of sustainability.

Educational Materials

The traditional “lawn” is perceived as a matter of neighborhood interest, both in terms of property value and the public health, safety, and welfare concerns above, and the concept of “rewilding” constitutes a substantial shift in this perception. The provision of educational resources would ease tension among inspectors, the City, and private households. A list of the City’s preferences for native species (keeping in mind native species are changing as the climate changes⁴⁸), prohibited species, and a basic factsheet for property owners explaining the reasons the City supports such species, the potential benefits of planting them, and how it helps to achieve sustainability goals could clarify the motivation. For example, newly produced materials describing “lawn alternatives” encouraging property owners to re-landscape their yards should include the overlapping positive effects: reduced emissions from lawn mowers, increased biodiversity, and better stormwater absorption. Microhabitats can be constructed as part of commercial and industrial development too, although they may require different guidance considering their scale. Green roofs, for instance, are an opportunity to plant native species that provide food sources or refuge for insects and birds on a larger but less visible surface than a home. Over an entire city, these microhabitats can become effective in supporting urban wildlife, once the parameters for property owners are disseminated.⁴⁹



One area of the City that is an excellent candidate for focused native plantings is in the College Heights neighborhood. College Heights is situated at the headwaters of Owen Drain, an enclosed drain that runs into the Huron River after passing through the EMU campus. The drain system has required several upgrades to expand its capacity; using the neighboring properties to exhibit best practices for stormwater management with native vegetation could relieve some of the pressure on the system.

⁴⁸ “Climate Change Tree Atlas and Bird Atlas.” USDA, US Forest Service <https://www.fs.usda.gov/ccrc/index.php?q=tools/tree-and-bird-atlas>.
⁴⁹ URBANhabitats “Green Roofs and Biodiversity” December 2006 <http://www.urbanhabitats.org/v04n01/introduction.html>

Trees

Street Trees

Trees provide a suite of ecosystem services that are nearly incomparable: cleaner air,⁵⁰ cleaner water,⁵¹ sequestered carbon,⁵² temperature moderation,⁵³ stormwater management,⁵⁴ urban wildlife habitat,⁵⁵ increased property values⁵⁶, increased commercial sales,⁵⁷ lower crime rates,⁵⁸ faster healing,⁵⁹ lower prescription drug burden, lower rates of depression,⁶⁰ and improved academic performance.⁶¹ Despite these multifaceted benefits, there are practical day-to-day issues that stall planting and maintenance. Even though trees’ ecosystem services pay off in the long-run, the shorter-term operational costs are resource-intensive. A tree’s root system has the strength to push up sidewalks and, to a lesser extent, interfere with sewer infrastructure. When sidewalks heave from a growing tree root, it creates trip hazards that discredit another City goal: walkability. The tension lies in determining responsibility and corrective action over tree and sidewalk maintenance – by City code, residents are responsible for maintaining their sidewalks, but not for the trees that commonly disfigure them. When residents are cited for a heaved sidewalk, they push back on the City’s lack of tree maintenance, which results from a lack of funding. The tension has brought the conversation to a standstill for now; citations for sidewalk maintenance are rarely issued.

As the long and diverse list of ecosystem services identified above indicates, investment in trees pays back with dividends in the long run. In 2012, the City conducted an Urban Forestry Management Plan (UFMP) and is dedicated to fighting climate change, it is a reasonable next step to bolster the tree maintenance budget to alleviate tension with neighbors and provide better care for its stock.


To reduce sidewalk heaving, the size of the sidewalk cut out should be based on the tree species’ need for water and area to grow. A uniform “one size fits all” ordinance for tree planting is easier to administer but may not yield desirable outcomes. An emphasis on species with a tap root system could alleviate infrastructure damage. Porous pavers or more malleable materials to surround trees may reduce instances of cracked surfaces. With porous surfaces, trees have greater access to water and may not have to push upward for hydration. In the meantime, citations for damage caused by public trees should continue to be sparsely issued.

Tree Species and Placement

The “Tree Canopy Coverage” map shows that trees are more prominent within peripheral neighborhoods and along the river. Large white swaths on the map represent zero coverage.

In 2012, an Urban Forestry Management Plan found that Ypsilanti had 8,835 public trees, stumps, and planting sites for a total appraised value of about \$10.7 million. There are 105 distinct species, but maples account for 55% of the tree population. This represents a tree diversity shortage, leaving the City vulnerable to a disease that could wipe out half of its tree population as has happened in communities with Dutch Elm Disease and, more recently and locally, Emerald Ash Borer. Public trees skew older and the majority are in fair condition; they would ideally be replaced with younger trees at a higher replacement rate.⁶²

Separate from the UMFP, a tree placement model was run for the entire City to determine what areas are most in need of trees based on two data sources. The two sources were weighted equally at 50%: existing tree canopy and an aggregate “heat stress index” map from the MI Environmental Project that includes climate projections, impervious surface, and social and physical health factors (https://michiganview.org/MI_Environment_Tool.html). The results of the tree placement model are shown in the “Tree Equity Placement Map.” The darker purple areas represent highest-need areas and the green areas have adequate tree canopy coverage.



⁵⁰ United States Forest Services. “How Trees Help Clean the Air,” 1977. <https://naldc.nal.usda.gov/download/CAT87209983/PDF>

⁵¹ Virginia Department of Forestry. “Trees Protect Water,” March 2011. http://www.dof.virginia.gov/infopubs/_forest-facts/FF-Trees-Protect-Water_pub.pdf

⁵² United States Forest Service. “Carbon sequestration,” retrieved May 2020. <https://www.fs.fed.us/ecosystems/services/carbon.shtml>

⁵³ United States Environmental Protection Agency. “Using Trees and Vegetation to Reduce Heat Islands,” retrieved May 2020. <https://www.epa.gov/heat-islands/using-trees-and-vegetation-reduce-heat-islands>

⁵⁴ United States Environmental Protection Agency. “Soak Up the Rain: Trees Help Reduce Runoff” retrieved May 2020. <https://www.epa.gov/soakuptherain/soak-rain-trees-help-reduce-runoff>

⁵⁵ Yale School of Forestry and Environmental Studies. “Urban Nature: How to foster biodiversity in the world’s cities,” Richard Conniff. January 2014. https://e360.yale.edu/features/urban_nature_how_to_foster_biodiversity_in_worlds_cities

⁵⁶ University of Washington/USDA Forest Service. “Green Cities: Good Health - Community Economics,” Wolf, K.L. 2010. https://depts.washington.edu/hhwb/Print_Economics.html

⁵⁷ Journal of Forestry. “Business District Streetscapes, Trees, and Consumer Response,” K.L. Wolf. 2005. <https://www.fs.usda.gov/treeseearch/pubs/34952>


⁵⁸ Landscape and Urban Planning. “The association between urban trees and crime: evidence from the spread of the emerald ash borer in Cincinnati,” M.C. Kondo et. al. July 2016. https://www.fs.fed.us/nrs/pubs/jrnl/2017/nrs_2017_kondo_001.pdf

⁵⁹ Science. “View through a window may influence recovery from surgery,” Roger Ulrich. 1984. https://www.researchgate.net/publication/17043718_View_Through_a_Window_May_Influence_Recovery_from_Surgery

⁶⁰ Landscape and Urban Planning. “Urban street tree density and antidepressant prescription rates – a cross-sectional study in London, UK,” M.S. Taylor et al. April 2015. <https://ore.exeter.ac.uk/repository/handle/10871/17340>

⁶¹ Urban Forestry and Urban Greening. “Beyond the school grounds: Links between density of tree cover in school performance and high school academic performance,” Dongying Li et. al. <https://www.sciencedirect.com/science/article/abs/pii/S1618866717307033?via%3Dihub>

⁶² City of Ypsilanti Urban Forestry Management Plan. February 2012.



The challenge in tree planting is the initial funding and ongoing maintenance; the environmental challenges that result from a lacking tree canopy coverage come with high opportunity costs to human health, water quality, and aesthetics. When the City of Ann Arbor quantified the benefits that public trees provide, each tree was found to contribute \$97 in ecosystem services annually. Each tree provides annual energy savings of \$48 by shading buildings and slowing winds, which reduce the heating and cooling requirements in buildings. The aesthetic value and quality of life benefits each tree provides is estimated at \$29. Reducing runoff and other water quality benefits is valued at \$11 per tree, and the air benefits that tree provide is quantified at \$9 per tree.⁶³

Communities that manage and expand their urban trees can achieve status as a “Tree City,” awarded by the Arbor Day Foundation based on four standards: a tree board or department, a tree care ordinance, a community forestry program with a budget of at least \$2 per capita, and observance of the Arbor Day holiday. As of June 2019, Ypsilanti no longer qualified for Tree City designation, but restored that certification in 2020. The primary benefit of Tree City status is the improved tree canopy, but the standards also provide a framework for action, and the status helps gain the necessary awareness and support to continue investing in it.

The 2012 Urban Forest Management Plan (URMP) details suitable locations, necessary budget, recommended species to plant, and maintenance practices. This document should serve as the guidebook for tree purchasing and placement decisions. The map “Tree Planting Priority” adds an equity-focused dimension to tree placement and planning and should be considered as an additional resource.

⁶³ City of Ann Arbor Urban & Community Forest Management Plan, City of Ann Arbor, June 2, 2014.

Light Pollution

The inappropriate use of artificial light is referred to as “light pollution,” and includes excessive brightness, the brightening of the night sky, light where it is not needed, and the clustering of light sources.⁶⁴ Light pollution alters the perception of many nocturnal animals by turning the night into day, inhibiting their ability to forage, hunt, and breed. Migratory birds that use the moon and stars to navigate can be pulled towards urban areas and collide with lit buildings.⁶⁵ Outdoor lighting also impact insects that are attracted to the cooler white lights and less attracted to the warmer yellow lights.⁶⁶ Consequently, warmer lights have less influence on insects’ lifecycles and on the greater chain of its predators. Regulating and reconfiguring lighting can help alleviate disruptive migratory bird patterns.

The City of Ypsilanti has an artificial-to-natural light ratio that ranges from 10.2 to 20.5, indicating that the amount of night light is 10-20 times above natural levels.⁶⁷ The United States Department of Energy estimated that 35% of lighting is wasted, costing roughly \$3 billion dollars annually. With some changes, buildings can reduce lighting to solve problems of waste and pollution.

The challenges to making lighting upgrades are varied. To start, the DTE streetlights in Ypsilanti use white light in fixtures that are not dark sky compliant, meaning the City could not adhere to new regulations in its streetlights that it would enforce on others. Another barrier is the cost of a photometric study needed to ensure that standards are met, which can be prohibitive for property owners and small developers. Continuous compliance with lighting standards is also an issue, as property owners may change fixtures without being aware of the code or seeking a City permit Ypsilanti’s Historic District Commission, which oversees development in one of the state’s largest historic districts, only approves warmer lights that are friendlier to insects and night vision, but often determines the styles of fixtures that are dark sky compliant are not compatible with their standards.

Certain technologies, such as motion sensors, have not been accounted for in the ordinance. Article VI Section 122-609 of Ypsilanti’s Zoning Ordinance states that “parking and loading facilities, building entrances, and building exits used during night-time shall be artificially illuminated,” and developments have been allowed to put certain lights on motion sensors that meet the standards when fully lit, but remain off or illuminate at a lower level when no motion is detected. This practice should be enshrined in the zoning ordinance.

The parameters around lighting standards are based on the effect on adjacent properties and take into account the height of a lighting fixture and the intensity of the light, but the complexity of measuring these criteria on varying properties is time-intensive. To reduce light pollution, the International Dark Sky Association created a Model Lighting Ordinance that recommends creating lighting zones permitting different intensities, applying “curfews” that turn off lighting after a given time, minimizing uplighting, and instituting performance standards indicating a maximum light measurement based on site conditions.⁶⁸ Motion detectors can help achieve many of these suggestions, along with an added bonus of reducing energy waste, and could be required by ordinance. Consideration of new guidelines should be adapted to Ypsilanti’s existing conditions. If a lighting curfew seems less realistic, for example, minimizing uplighting could be emphasized so that practice follows policy more closely with an emphasis on reducing energy consumption.


Sustainability Goals: Biodiversity

GOAL: Expand and protect natural habitats

- Incorporate model language for rewilding landscaping into the city’s ordinance
- Create informational materials for property owners on preferred and prohibited plants
- Rezone undeveloped land on Mansfield and on Clark to a more protective zoning district
- Continue to support the local food system
- Support traffic calming and other infrastructure design that help reduce animal road crossing mortality
- Promote “bird safe” designs and “lights out” programs during migratory season
- Consider programs for habitat improvement such as bat houses, pollinator gardens, and others as they develop
- Train inspectors to spot wildlife-friendly plants to prevent their removal
- Continue to monitor health of the city’s wetlands and work with the Washtenaw County Parks and Recreation to protect them
- Partner with the County to inventory land that could be nominated for NAPP
- Encourage warm light to protect insects
- Encourage use of native and climate-change adapted plants wherever possible
- Work with DTE to provide warmer, more night-sky friendly public lighting.
- Review the existing lighting ordinance and update to explicitly permit motion-sensitive lighting.
- Review and incorporate aspects of the Dark Sky Model Lighting Ordinance to reduce negative effects on insects and migratory birds

GOAL: To preserve and expand a resilient tree canopy

- Implement a tree preservation ordinance



⁶⁴ Light Pollution, International Dark Sky Association, <https://www.darksky.org/about/>
⁶⁵ Wildlife and Ecosystems, International Dark Sky Association, <https://www.darksky.org/light-pollution/wildlife/>
⁶⁶ Servick, Kelly “Which Light Bulb Attracts the Fewest Bugs? Study Reveals Surprises.” Science, Feb. 14, 2016. <https://www.sciencemag.org/news/2016/02/which-light-bulb-attracts-fewest-bugs-study-reveals-surprises>
⁶⁷ Cooperative Institute for Research in Environmental Sciences at the University of Colorado Boulder, <https://cires.colorado.edu/artificial-sky>
⁶⁸ International Dark-Sky Association. “Model Lighting Ordinance.” June 2011. https://www.darksky.org/wp-content/uploads/bsk-pdf-manager/16_MLO_FINAL_JUNE2011.PDF

- Plant additional street trees and trees in parks in accordance with the Urban Forest Management Plan, with a particular prioritization of those sites indicated by the Tree Equity map.
- Increase and diversify the public tree stock according to the Urban Forest Management Plan
- Invest in tree maintenance
- Continue the City's Arbor Day Tree City USA designation
- Coordinate tree planting efforts with sidewalk maintenance efforts and considerations.
- Update street planting guidelines to prioritize tap roots species and vary pit size by species

DRAFT NOVEMBER 2020

Complete Neighborhoods

Land use planning is a critical component of mitigating and adapting to climate change. Density, walkability, and access to urban gardens and greenery are just some ways a city can curtail dependence of fossil fuels. Ypsilanti residents want to live in neighborhoods that are green, connected, and complete. Over two-thirds of respondents recorded that “completeness” is deciding factor when choosing where to live. The features of a “complete neighborhood” were decided by survey-takers, and most important to them was the presence of “parks, recreation, and/or open space (96%),” and the fourth highest priority is trees and/or community gardens (77%).

Residents also see complete neighborhoods as physically connected so that streets safely accommodate bicyclists, pedestrians, public transportation passengers, and users of all ages and abilities. This was expressed in high response rates rating “sidewalks” (87%) and “public transportation options” (84%) as factors describing completeness of a neighborhood. Even though 64% of Ypsilanti residents commute to work alone in a personal vehicle,⁶⁹ improved nonmotorized transportation infrastructure can make a difference in how people choose to arrive to *other* destinations. One of the challenges in Ypsilanti is that the Michigan Department of Transportation owns and/or manages in the most-travelled roads in the city, some of which are one-way arteries with faster travel speeds, and many with incomplete sidewalks and missing pedestrian crossings. These roads often present a significant barrier to bicycle and pedestrian traffic, as well as neighborhood connectivity. Improvements to these roads must be led by the City with support from MDOT, and may face challenges including acquiring rights-of-way and funding.

Residents generally support alternative modes of transit, even those who report that they do not use the service themselves. Residents are proponents of expanded bicycle and pedestrian networks and public transit service including the development of an Amtrak stop. When residents were asked what prevents them from walking or riding a bicycle to destinations, they cited incomplete sidewalks or bicycle lanes, the condition of the nonmotorized infrastructure, and the difficulty in crossing some streets safely. On city owned roads, pedestrians should be prioritized at all crosswalks, and where possible to make pedestrian walk lights automatic. Ypsilanti has shown its commitment to connectivity by coordinating with the Township and County on the Border to Border trail and the AATA to expand bus coverage and frequency.

Motivated neighborhoods can establish “Eco districts” to concentrate focus on sustainability goals in a geographic area. This was proposed in the 2013 Master Plan, and the Zoning Ordinance has been updated to permit more components of an Eco district: community gardens, rain collection systems, and rooftop renewable energy projects. The City has enabled such developments, and while they cannot take on the lead on implementation, these changes support neighbors’ eco-friendly demonstrations. The next step would be for a group of neighbors to develop and agree to a set of performance standards, and, with the help of a Sustainability Commissioner liaison, look for funding and/or initiate smaller scale projects that meet their performance goals. Eco district performance goals could be tailored to the neighborhood but aligned with City sustainability goals, for example, expanding tree canopy coverage or developing green houses in open space.

A seldom-considered aspect of a complete neighborhood is its resiliency in case of an emergency, such as flooding, extreme weather, energy outages, or even pandemics. Generally, walkable and bikeable neighborhoods with a variety of uses and resources within them or adjacent are more resilient; their small-scale distributed nature helps them to ride out brief disruptions. However, to enable continued resilience and resilience during larger-scale disruptions, community resource centers should be identified and supported. These may be community centers, or other places of secular or religious assembly; these spaces may have backup generators, be able to serve as warming/cooling centers, be able to safely store and distribute food and other resources such as emergency kits, or that may be able to shelter people in a temporary basis. On a smaller scale, they may be the home of a community leader who can offer some or all of these functions. These facilities may also serve as area weather stations, helping to track air quality and rainfall both in times of peace and disruption. The City should work to identify and outfit community resilience resources, geographically distributed throughout the city, that will be open to serve the community in times of disruption.

Transportation

City Ordinance No. 1156 provides for the planning, design, and construction of streets that offer appropriate access to all legal users and provide safe, accessible, comfortable, and efficient transportation options for people and goods in order to support the City’s quality of life, economic vitality, and environmental sustainability. This is an important step in cutting vehicle miles traveled (VMT), as is coupling transportation routes with building density as the AAATA has done.

There is still much to be done in terms of reducing vehicle miles traveled. Undoubtedly, EMU is a primary traffic generator. A partnership between the university and the City to manage a bike-share and car-share program might limit how many trips students make by car. While it is hard to predict to what extent this will change behavior, an easy-to-use sharing system provides another option to ensure travelers are able to reach their destinations without use of a personal automobile. The Ride also makes a good partner to encourage commuting by bus. The City and the DDA could partner with the Ride and local businesses to offer discounted transit passes to employees who bus to work to not only reduce VMT but also to reduce demand for parking in compact areas. A parking cash-out alternative is another possibility for employees that would otherwise drive and take a parking space for patrons. Strategic development of electric vehicle charging infrastructure will allow greener power alternatives for those cars which remain on the road.

Nonmotorized path enhancements also have the potential to change travel behavior. The City has identified intersections in the Master Plan that would slow down vehicular traffic and include pedestrian and bicycle improvements to create safer, multi-modal streets. Ypsilanti’s commitment to safety as a guiding principle applies to the continuation of bicycle lanes on major thoroughfare and trunklines to protect bicyclists from sharing the road with fast moving vehicles. The timing and location are crucial to a connectivity strategy. When roads undergo repair, it is an opportune time to include improvements such as bicycle lanes, sidewalks, or other pedestrian-friendly improvements. In terms of location, nonmotorized features should be installed where they connect to an expanding an existing network or build links between neighborhoods and job centers. Lastly, to protect their right to use the roads safely, enforcement of bicycle and pedestrian safety could, over time, help build an expectation of balanced road use.

Land Use and Mobility

Land use and mobility planning go hand in hand. Reliable transportation, mixed uses, and density are cornerstones of mobility. In that regard, Ypsilanti has a favorable combination. Permitting neighborhood-friendly stores that provide goods serving daily needs (convenience store, market) and personal services (hair salon, medical offices) in proximity to households makes destinations convenient by foot or bicycle. In Ypsilanti, 93% of residential parcels are within ¼ mile walk (and 100% are within ½ mile) from a small convenience retailer or service provider, based on 2015 SEMCOG land codes. This land use configuration has a huge impact, assuming that people walk to these locations when they can. The Urban Land Institute reviewed studies that show that compact suburban development reduces VMT by 12-18% compared to low-density suburban development.⁷⁰ With that in mind, Ypsilanti should continue to prioritize infill development, converting central lots that bolster mobility for residents before tending to the City’s periphery. Along major corridors where the Ride traverses and the vehicular capacity permits, density bonuses for a mix of uses could strengthen nonmotorized access to goods and services.

⁶⁹ American Community Survey. 2017 5-Year Estimates. Table DP03.
⁷⁰ Urban Land Institute. “Land Use and Driving: The Role Compact Development Can Play in Reducing Greenhouse Gas Emissions.” <https://uli.org/wp-content/uploads/ULI-Documents/Land-Use-and-Driving-Low-Res.pdf>

Development

Ypsilanti residents’ preference for green, connected, and complete neighborhoods are reflected in the US Green Building Council’s LEED for Neighborhood Development standard as well as in Detroit’s vision for “20 minute neighborhoods” and Kalamazoo’s Imagine 2025 Master Plan, demonstrating an emerging trend in Michigan. The US Green Building Council’s LEED for Neighborhood Development standard recognizes that neighborhoods can be designed to respond to the local impacts of global climate change and make significant advances toward a sustainable planet. The standards focus on achieving sustainability goals at a neighborhood scale, and align with Ypsilanti’s broader sustainability goals:

- Lower operating costs and increased asset value
- Reduce waste sent to landfills
- Reduces VMT
- Increase energy and water conservation
- Provide more healthful and productive environments for occupants
- Reduce greenhouse gas emissions
- Promotes rebates, zoning allowances, and other incentives

Equity development in a complete neighborhood also includes housing choice. Ypsilanti has a considerable segment of the population with low earnings who need of affordable housing. The current stock of affordable units has waiting lists, leaving those in need in a financially precarious situation. The process for securing affordable housing is long and involves many parties. The City in conjunction with the Housing Commission can seek affordable housing development opportunities and identify parcels where they could locate in a neighborhood with access to services. Coupling subsidized housing and green development would be an exemplary sustainability project that unquestionably embraces the pillars of equity, environment, and economy. Because the City is largely built-out with no room for an entire new neighborhood, these standards could be applied to infill sites or on sites that have room to expand on their parcel.

Sustainability Goals: Complete Neighborhoods

GOAL: Maintain and expand transportation options including the development of bicycle, pedestrian, and sharing networks.

- Implement a parking cash-out alternative benefit option for City employees
- Prioritize transit-oriented development
- Partner with the DDA and AATA to provide a discounted transit pass as an alternative to downtown parking permits
- Encourage corporate sponsorship of transit passes and infrastructure to encourage employee bus and bikeshare ridership
- Consider pursuing car, scooter, or bike-sharing programs with Eastern Michigan University as a partner.
- Close sidewalk gaps
- Add bicycle lanes to major thoroughfares and trunklines
- Retain the mix of uses within each corridor but allow them throughout the area.
- Restore two-way function to Cross, Huron, and Hamilton Streets.
- Separate Cross and Washtenaw for vehicle traffic.
- Restore Harriet Street as the Main Street of adjacent neighborhoods.
- Prioritize pedestrians at crosswalks, and investigate where pedestrian walk signs can be made automatic
- Work with MDOT to make state-owned roads more accessible to nonmotorized users
- Coordinate with Townships and WPCRC on Border to Border (B2B) trail development
- Encourage police enforcement and legislative support for bike and pedestrian safety
- Improve neighborhood walkability by improving sidewalk connectivity and conditions. Prioritize the improvement of nonmotorized connections that link neighborhoods and job centers.
- Continue to support the development of intercity and commuter rail
- Coordinate citizens to advocate for slower traffic speeds on state owned corridors

GOAL: Incentivize energy efficient and socially responsible development

- Consider density bonuses, particularly on transit and commercial corridors, in exchange for developers meeting criteria that achieve city goals
- Incentivize US Green Building Council’s LEED for Neighborhood Development standard for new development
- Develop a Green Business/Neighborhood Certification program
- Seek affordable housing development and identify parcels where it can locate near services
- Continue to prioritize infill development
- Continue to provide a variety of housing options, including affordable housing and missing middle housing.
- Provide a Sustainability Commissioner liaison to a neighborhood interested in developing an eco-district

GOAL: Increase neighborhood resiliency during times of disruption.

- Identify walkable/bikeable neighborhood resource centers throughout the City, such as community centers, churches, schools, or social clubs.
- Work with these identified resources to increase their capacity to serve as emergency resource centers, including backup power generation, emergency shelter, and food and resource distribution.
- Work with the Health Department and other partners to make resources available for community leaders who wish for their homes to serve as small-scale resources during disruptions.

Communication

Disaster Preparedness and Adaptive Responses to Climate Change

Extreme heat and cold events, heavy rainfall, flooding, and other extreme weather events are expected to increase over time as a result of climate change, and each will require a coordinated response among county, state, and federal levels of government amid a catastrophe. While sustainability-related actions will help mitigate these risks in the future, the City must help residents adapt to these increasing risks by expanding emergency preparedness and communication tools.

Extreme Heat and Cold

Extreme heat events are among the most harmful weather phenomena. They amplify ground-level ozone levels, which are associated with higher hospitalization rates for asthma, more severe allergic reactions, and premature deaths for people with heart and lung disease. Healthcare costs increase as a result of these negative health impacts. Heat events also put pressure on electrical distribution as people rely more on air conditioning and reduce grid reliability as a result of increased demand, and decrease energy efficiency and increase costs for rate payers. Conversely, shutoffs negatively impact residents with the fewest resources; the programs to support those in danger of shutoffs, such as THAW, should be publicized regularly before and during peak heating and cooling season. Additionally, the City should work with its utility partners and the County to explore prohibiting utility shutoffs for nonpayment during states of emergency.

Michigan will continue to experience extreme cold events as well, which disproportionately affect homeless people who are vulnerable to cold temperatures. The risk of illness increases for low-income individuals, the elderly, and those with chronic ailments who may be vulnerable to colder temperatures.

Heat

Because not everyone has access to air conditioning, this is an equity issue. While cooling centers have been identified at the county-level, it is worth preparing now for increasing locations and hours for air-conditioned rooms. Monitoring where ozone levels peak on hot days can indicate where “outbreaks” for respiratory problems may stem from and supplementary services to cooling centers could be targeted there. The Property Maintenance Code could also be updated to require air conditioning be provided for rental properties, similar to the requirement for heating, and to be turned on over certain temperatures.

Cold

The response to cold days could also be improved. When heating a household is too expensive for vulnerable populations to maintain, heating centers shall be distributed for households to get through the winters comfortably. Similar to cooling centers, there should be an expectation that established heating centers need to be revisited and likely expanded. On a municipal level, many processes are set in motion during rain and snow events. The shift in focus will be in capacity building and less so in wholesale change to established processes. For example, an apt overlap with goals of walkability is to improve snow removal from sidewalks and bicycle lanes so that weather doesn’t have to stop residents from nonmotorized travel. With the expectation of colder and hotter weather, infrastructure made of the same materials will not last as long. The abrupt and prolonged changes cause roads and sidewalks to crack more frequently. An investment in materials that withstand such swings should be investigated and incorporated in the City’s Capital Improvements Plan with a priority on longevity.

As GHG emission rates continue to rise, Michigan is expected to see up to a 5°F increase in average air temperature between 2041 and 2070. An additional 30 to 70 days per year, depending on the region, are expected to exceed 90°F. The amount of energy needed to cool buildings will also rise. This can be assessed by calculating “degree days,” which can be a confusing and counterintuitive concept. There can be more than 365 heating or cooling degree days in one year because degree days are measured relative to a base of 65°F (18°C) and reflect the *amount* of heating or cooling necessary at a facility. Above 65°F (18°C), it is assumed that a facility will need to be cooled, and below 65°F (18°C), it is assumed that a facility will need to be heated. Heating Degree Days (HDD) are the equivalent number of days a facility would need to be heated by 1 degree to accommodate the heating requirement. For example, one day where the temperature measures 80°F would be 15 Cooling Degree Days because it is 15 degrees above 65°F. There were 474 cooling “degree days” in 1990, 679 cooling degree days in 2000, and 1205 cooling degree days in 2019.

Heavy Rain and Flooding

Precipitation is projected to increase on average and to concentrate in more intense precipitation events, likely resulting in greater periods of both extreme flooding and extreme drought. An additional 2 to 3 inches of annual precipitation is expected for Michigan, and the number of days each year experiencing heavy rainfall is expected to increase by at least one day per year. These extreme weather events will impact the economy, disrupt the environment, and disproportionately impact vulnerable populations. Flooding puts residents and emergency response personnel in direct physical danger; increases pollution and waterborne illnesses; incurs expensive property damage; displaces households and businesses; creates damp conditions that spur the development of mold and reduce indoor air quality; stresses the capacity of aging sewer infrastructure and increases the risk it may be overwhelmed, forcing the release of untreated water into nearby water sources including those used for drinking; erodes banks and shorelines that support buildings and infrastructure; damages power lines, infrastructure, and vegetation; and disrupts power and transportation systems resulting in reduced productivity and profitability.

The City has a dedicated page on its website to emergency preparedness that has a list of links and contact information for essential services. Neither the City nor the County has a hazard mitigation plan that includes what to do in case of extreme weather. In 2004, Washtenaw County worked with all local units of government to adopt resolutions that would support a Hazard Mitigation Plan (HMP) to become eligible for FEMA grant funding for high-risk hazards. However, that year, FEMA grants focused on flooding mitigation instead and the Hazard Mitigation Plan was discontinued.⁷¹ Since then, the County conducted a risk assessment that put convective weather (severe winds, lightning, tornadoes, hailstorms) as the top threat.⁷² Together with the other municipalities in the county, an HMP that considers climate predictions is the only way to responsibly plan for the future.

For emergency planning, the county is the primary coordinator. The County has an Emergency Operations Center which becomes the centralized coordinating point for large-scale emergencies. It is recommended that Ypsilanti participates in this process when the County updates the plan to a multilingual and universally accessible plan for emergencies that include climate change predictions. At the city level, at a minimum, communication with non-English speakers should follow Ypsilanti’s Non-Discrimination Plan protocol, but critical documents should be made available in the most commonly spoken languages, aside from English.

More recently, the city has done some research on resiliency hubs. Resiliency hubs are decentralized nodes, positioned in the city’s most vulnerable areas, that supply essential goods and services in the event of an emergency. It is highly recommended that if the city pursues this concept further, that trained citizens or staff administer each hub to maintain order and logistical support on behalf of residents.

Outreach about Sustainability Goals and Practices

Based on the collective prioritization results, residents see a need for education and outreach focused on sustainability-related services and programs. Most survey-takers gave the City a grade of a B or C on the guiding principle “communication is key,” indicating that there is room for

⁷¹ Email with David Halteman, Emergency Services Director. April 2020.
⁷² Washtenaw County. Washtenaw County’s Risk Assessment. <https://www.washtenaw.org/1760/Risk-Assessment-Hazard-Ranking>

improvement. The decentralization of services makes it difficult for residents to know where to start when they are in need and/or how they can get involved. Most survey participants were unaware of the City of Ypsilanti Climate Action Plan (69%), let alone the strategies that the City is using to adapt to and mitigate the impacts of climate change that require buy-in from residents. Because sustainability topics are wide-reaching, and there is no single dedicated department, inquiries are not directed to one person but are diffused amongst several. While the ultimate goal is to hire an Energy Manager, in the meantime, the City shall designate a point person that can direct questions and comments to the correct department.

Residents will be impacted by the effects of climate change and need easy access to resources that will help them respond to the negative impacts on their families and their health. Through its already established communication channels like the monthly newsletter and social media, the City can share its sustainability vision, efforts to fulfill it, and ways that residents can participate. Easy-to-follow tips for residents to reduce consumption could also be shared on a regular basis as a friendly reminder that it will require everyone to make change. Wide-scale reach would necessitate that Ypsilanti develop municipal marketing materials and have a plan for regularly schedule distribution.

When it comes to sustainability specifically, the public has also noted that sustainability education should place substantial emphasis on youth. Residents want to see a sustainability curriculum incorporated in the school district, pulling on the strength of local experts to teach these lessons. This has yet to be done at a national or state level, but some local efforts have incorporated sustainability into youth’s curriculum. In the foreseeable future, most of this education will have to remain extracurricular due to limited funding.

To increase the climate resiliency of residents, the City must make information easier to access, provide emergency response training for extreme events, and help residents take proactive measures to reduce GHG emissions. Community education is an important step in promoting adaptation and mitigation strategies on an individual and community level, and the City is in a good position to provide easily accessible and well-publicized information through its established channels. One practical adaptation action the City to take on would be the promotion of the Great Lakes Water Authority’s Water Residential Assistance Program (WRAP), and other helpful but unknown services, that provide direct assistance to low-income households who have trouble with paying water bills or making repairs to leaky plumbing. The hope is that as the City develops and disseminates informational materials that residents can access and rely on, a beneficial partnership will continue to be strengthened.

A federal grant was awarded to the Southeast Michigan Stewardship Coalition to educate students across nine schools, including one school in Ypsilanti, about climate resiliency. Discussion on this topic included identifying potential solutions to make communities more resilient through a community-based project. Ypsilanti Community High School students worked with City Council and the Sustainability Commission; all hope to forge a lasting partnership to complete more projects.⁷³

Working with the Sustainability Commission is the likely path forward for the City to educate its school-aged youth and residents on such issues. As the educational leader for sustainability initiatives, the Sustainability Commission can create and present a series of learning opportunities for energy savings and other assistance programs that lower monthly expenses and expose residents to new resources, or teach students and administrators at the local schools how to reduce waste and incorporate reusable items for its students. Ideally, these sessions will be held at different venues throughout the City and focus on reaching the most vulnerable populations in need of home repair, utility assistance, and energy efficiency measures. A fun way to educate the community is to introduce a friendly competition. Competitions can be set up between city staff, businesses, schools, neighborhoods on any measure the Sustainability Commission wishes to teach. For example, a designated “zero waste” day for waste management or “commute challenges” for alternative transportation would entice people to modify their behavior and have other groups to discuss the challenges and benefits to it. Other ideas proposed by community members included energy treasure hunts, adopting catch basins or green infrastructure, and a “Bring Your Green to Work” day.

Sustainability Goals: Communication

GOAL: Play a leading role in educating Ypsilanti residents on sustainability topics.

- Implement an educational series about energy efficiency in different venues with a focus on teaching the most vulnerable populations about resources that help reduce their utility bills
- Sustainability Commissions shall continue to work with sustainability-related organizations to develop and offer in school guest lectures, field trips, and other learning opportunities with local schools
- Work with schools to reduce waste and incorporate reusable items on campus
- Determine a designated point person on city staff to direct sustainability-related questions or comments to the correct department
- Promote the city’s energy, climate, and sustainability vision through the established online newsletter and develop other municipal marketing materials to update residents on city efforts, key sustainability topics, and easy-to-follow tips at home
- Organize competitions between municipal employees, business owners, and neighborhoods that promote sustainability-focused activities:
 - “Bring Your Green to Work,”
 - Energy treasure hunts,
 - Adopting catch basins or green infrastructure,
 - Zero waste days,
 - Smart commute weeks, and challenges to bike, walk, or take public transit to work.
- Partner with Ypsilanti Community Schools on communication and education efforts.
- Consider creating a Communications Specialist position to lead and coordinate communication and education efforts within the City.
- Make critical public documents accessible and multilingual
- Publicize available efficiency and support programs, such as the County’s weatherization program and YCUA’s water assistance program.

GOAL: Develop the datasets necessary to determine where disaster relief should be targeted

- Conduct an Environmental Justice analysis that identifies vulnerable populations and structures that are disproportionately impacted by climate change
- Work with SEMCOG and the County to expand local air quality monitoring system
- Investigate infrastructure materials that can weather extreme weather

GOAL: Mitigate the damage inflicted on residents, infrastructure, and property from extreme weather.

- Implement renewable backup power systems for areas of refuge and emergency facilities
- Work with Washtenaw County, landlords, and utility partners to ban utility shutoffs for nonpayment during states of emergency or extreme weather events.

⁷³ Michigan Radio. “Centering the Classroom on Climate Resilience.” December 2019. <https://www.michiganradio.org/post/centering-classroom-climate-resilience>

- ~~Collaborate with Washtenaw County, landlords, YCUA, DTE, and other utility partners to ensure that in a time of crisis essential water and gas/electricity are not shut off due to nonpayment~~
- Work with Washtenaw County to develop a Hazard Mitigation Plan
- Partner with Washtenaw County to expand emergency preparedness and communication tools including a multilingual and universally accessible plan that includes climate change predictions
- Work with the County to identify additional accessible warming and cooling shelters
- Require occupied residential rental units to have one air-conditioned room
- Review response protocol and update where needed to respond to severe storm events
- Continue to explore Resilience Hubs in coordination with local community partners and facilities.
- Publicize available utility assistance programs, such as THAW, leading into and during peak heating and cooling seasons.
- Improve snow and ice response for sidewalks

Action Plan

Each action is rated for its ability to achieve the goal it fits under on a scale of one to three for: equity, environment, economy, and effectiveness (three is the highest score). They are then listed in priority order based on the overall score. Unrelated to its score, is the “term” in which it should be achieved. An item may be scored very highly but cannot be achieved in the near term. That is to say that Ypsilanti will have to work simultaneously on near term projects while making progress on longer term goals.

Near term = 1-2 years

Mid term = 3-6 years

Long term = 7-10 years

	Timeframe	Lead Party
Sustainability Goals: Earth		
GOAL: Eliminate new instances of soil contamination and responsibly deal with the legacy of existing polluted sites		
· Explore creation of an overlay zone, or other zoning or building regulations, to control the types of uses that may be permitted in areas with soils that would allow for easy transmission of contamination, or uses that have a high risk of contamination near ecologically sensitive areas, such as waterways.	Mid	CED
· Research and confirm existing sites of contamination with EGLE	MID	CED
· Use Brownfield TIF capture to fund remediation of sites that may be redeveloped.	ONGOING	CED
· Continue to work with the Washtenaw County Brownfield Redevelopment Authority to remediate sites.	ONGOING	CED
· Explore and pursue grant opportunities to remediate sites that may not be good candidates for commercial redevelopment or that pose an immediate threat.	ONGOING	CED
GOAL: Ensure buildings and infrastructure are constructed in a manner complementary to soil structure, slopes, and drainage.		
· Make soil information available to all, and directly provide information on soil structure to those who choose to build a new structure that requires a foundation.	ONGOING	CED
· Incorporate green infrastructure into planned capital improvement projects wherever possible, and identify potential sites for demonstration projects.	ONGOING	DPS
· Strengthen zoning protections to limit erosion in areas of steep slopes.	NEAR	CED

Sustainability Goals: Water		
GOAL: Protect the watershed from further contamination.		
· Consider a sensitive features overlay zone providing a buffer around the Huron River and Paint Creek that provides site and use regulations tailored to the proximity to these waterbodies	MID	CED
· Invest in consistent enforcement for compliance to the sensitive feature overlay zoning district	ONGOING	CED
· Continue to pursue updates to the zoning ordinance, such as tree protection regulations, that preserve and improve vegetation that can mitigate stormwater impacts.	ONGOING	CED
· Continue to support the work of the Washtenaw County Water Resources Commissioner and other partners to educate members of the public, particularly single-family homeowners, on stormwater issues.	ONGOING	
· Monitor adherence to the City's phosphorous fertilizer and tar sealcoat ordinances for effectiveness.	ONGOING	
· Work with Washtenaw County Environmental Health to research the status of remaining private wells and provide resources and recommendations for testing water quality to property owners	ONGOING	
GOAL: Preserve and expand the City's capacity to deal with heavy rainfall to mitigate negative effects on people and property.		
· Incorporate capacity upgrades for grey stormwater management into the CIP based on predictions for greater precipitation	ONGOING	DPS
· Update the flood maps, including FIRM, based on climate projections and changes to the river channel since the FIRM formulation in the 1970s	LONG	DPS
· Investigate an equitable stormwater fee schedule that encourages converting impervious to pervious surfaces and proper use of rain barrels or other detention/retention systems.	MID	COUNCIL/ DPS
· Consider banning basements or enforce floodplain standards in boundaries where the soil has limited capacity to handle stormwater	LONG	CED
· Develop a Stormwater Management Plan	MID	DPS
· Continue to pursue the removal of the Peninsular Dam	ONGOING	MANAGER
· Continue to maintain City lands that are in the flood zones and vacant for stormwater and floodwater mitigation.	ONGOING	VARIOUS
· Pursue GSI projects in the City parks, particularly in the flood zones.	ONGOING	DPS
· Pursue conservation &/or access easements along the Huron River.	ONGOING	CED
· Explore offering incentives to property owners to retrofit existing buildings and site improvements with stormwater-friendly infrastructure, including rain gardens.	LONG	
· Explore the potential to equitably enact a stormwater fee structure to encourage private retrofit stormwater infiltration and detention infrastructure	LONG	

GOAL: Promote resources for water conservation and testing to ensure access efficiency upgrades and clean water		
· Work with YCUA to develop home and business water efficiency financing programs	MID	
· Promote Great Lake Water Authority program WRAP to perform conservation audits and funds for repairs to help reduce low-income households reduce water bills	ONGOING	
· Collaborate with YCUA on water conservation and infrastructure improvement projects.	ONGOING	
Sustainability Goals: Energy		
GOAL: Decrease the community's emissions by 171,310 metric tons of CO ₂ e by 2030.		
· Work with the City of Ann Arbor to investigate bulk buying of renewable energy through the Community Choice Aggregation Legislation.	ONGOING	
· Purchase renewable energy credits (RECs) for City operations.	LONG	
· Promote state policies, incentives, grants, and Community Energy Management programs that encourage energy efficiency and renewable energy to property owners.	ONGOING	
· Promote Washtenaw County's weatherization program for low-income homeowners.	ONGOING	CED
· Work with community stakeholders to initiate an energy competition. The university and City can partner together to challenge another city and university to an energy reduction competition.	LONG	
· Implement an inter-departmental site plan review process with attention to sustainability-related strategies such as energy use and efficiency, generation and offsetting of emissions, on-site water management and infiltration, etc.	ONGOING	CED
· Investigate the feasibility of a microgrid.	LONG	
· Review and incorporate aspects of the International Dark Sky Model ordinance to reduce energy waste (i.e. motion activated lighting on municipal buildings)	MID	DPS
· Participate in or sign-on to regional, national, or international commitments to energy, climate, and sustainability including but not limited to the Paris Climate Agreement, the Sierra Club's "Ready for 100" pledge, the Global Covenant of Mayors for Climate and Energy.	SHORT	COUNCIL
· Develop an electric charging vehicle infrastructure strategy	MID	DPS
· Create a green rental certification program to encourage energy-efficient improvements	MID	CED
· Work with the HDC to incorporate historically compatibly fixtures that are dark sky compliant	ONGOING	CED
· Continue to pursue policies and projects that improve nonmotorized transportation.	ONGOING	DPS/CED
· Continue to encourage solar energy installations throughout the City.	ONGOING	CED

· Partner with other agencies, such as YCUA , DTE, and MiSaves to provide education and incentives for energy use reductions, both residential and commercial.	ONGOING	
· Continue to participate in local, regional, national, and international efforts for climate mitigation and adaptation.	ONGOING	
· Continue membership in communities such as ICLEI that help support local efforts to combat and adapt to climate change.	ONGOING	
GOAL: Decrease government operation emission in support of attaining citywide net zero by 2030		
· Establish an Energy Manager position to be responsible for the following duties:	MID	MANAGER
o Improve knowledge of energy management among city staff and appointed officials among staff		
o Create a data-driven system that is replicable over time, and includes annual forecasts, benchmarks for energy use reductions, and an internal reporting protocol		
o Work with the Sustainability Commission to produce an annual report that highlights where emission reductions and procedural improvements have been made		
o Improve communications with facility managers, utility providers, and relevant contractors to resolve issues quickly		
o Increase outreach to and participation of industrial and commercial customers in renewable energy and energy efficiency projects		
o Research and utilize the most efficient equipment available		
· Continue to incorporate renewable energy into the energy portfolio of each government building including back-up generation	ONGOING	DPS
· Re-establish the City's revolving loan fund for energy efficiency projects.	MID	MANAGER
· Conduct a GHG inventory every 5 years using input from 2012 & 2018 findings in the ICLEI GHG framework	LONG	DPS
· Improve fleet fuel efficiency with clean diesel, alternative fuels, and electrification.	ONGOING	DPS
· Publicly report on progress made toward energy goals.	ONGOING	DPS/CED/MANAGER
· Continue to make energy-efficiency improvements to City owned facilities	ONGOING	DPS
ENERGY: Reduce the amount of waste generated in Ypsilanti that enters landfills		
· Conduct a waste audit to understand the baseline composition of the waste stream at the municipal operations and community level	SHORT	DPS
· Help publicize local re-use opportunities, such as the Buy Nothing Project and Freecycle.	ONGOING	CED
· Implement an educational campaign on existing recycling and composting options	SHORT	DPS
· Expand recycling to public spaces and all City facilities by placing artful, educational, and engaging waste sorting stations throughout the community	MID	DPS

· Create a coordinated recycling system that has a one stop for difficult-to-recycle materials including electronics and refrigerant management	LONG	DPS
· Increase access to curbside recycling services to multi-family units	MID	DPS
· Define Zero Waste for Ypsilanti using the Zero Waste hierarchy. Set a goal for City operations to be zero waste (excluding medical waste) by a specific date with annual benchmarks.	LONG	
· Require that any events with a City permit provide for recycling, compost, and provide a discount for Zero Waste events	LONG	
· Require government operations to use durable or compostable materials	MID	
· Implement a pilot program for a municipal kitchen compost system with high food-waste generators.	LONG	
· Investigate a partnership with a commercial-scale compost operation	MID	
· Pilot curbside community composting services for leftover food	LONG	
· Investigate funding sources to bring down the cost of a biodigester	MID	
· Permit onsite composting of mulched leaves	DONE	
· Continue to explore options to improve recycling and composting opportunities within the City and with partners.	ONGOING	DPS
Sustainability Goals: Biodiversity		
GOAL: Expand and protect natural habitats		
· Incorporate model language for rewilding landscaping into the city's ordinance	SHORT	
· Create informational materials for property owners on preferred and prohibited plants	SHORT	SUSTAINABILITY
· Rezone undeveloped land on Mansfield and on Clark to a more protective zoning district	MID	CED
· Continue to support the local food system	ONGOING	CED
· Support traffic calming and other infrastructure design that help reduce animal road crossing mortality	ONGOING	DPS/CED
· Promote "bird safe" designs and "lights out" programs during migratory season	SHORT	CED
· Consider programs for habitat improvement such as bat houses, pollinator gardens, and others as they develop		
· Train inspectors to spot wildlife-friendly plants to prevent their removal	ONGOING	CED
· Continue to monitor health of the city's wetlands and work with the Washtenaw County Parks and Recreation to protect them	ONGOING	
· Partner with the County to inventory land that could be nominated for NAPP		
· Encourage warm light to protect insects	ONGOING	CED
· Encourage use of native and climate-change adapted plants wherever possible	ONGOING	

· Work with DTE to provide warmer, more night-sky friendly public lighting.	ONGOING	DPS
· Review the existing lighting ordinance and update to explicitly permit motion-sensitive lighting.	SHORT	CED
· Review and incorporate aspects of the Dark Sky Model Lighting Ordinance to reduce negative effects on insects and migratory birds	MID	CED
GOAL: To preserve and expand a resilient tree canopy		
· Implement a tree preservation ordinance	MID	
· Plant additional street trees and trees in parks in accordance with the Urban Forest Management Plan, with a particular prioritization of those sites indicated by the Tree Equity map.	ONGOING	DPS
· Increase and diversify the public tree stock according to the Urban Forest Management Plan	ONGOING	DPS
· Invest in tree maintenance	ONGOING	COUNCIL
· Continue the City's Arbor Day Tree City USA designation	ONGOING	
· Coordinate tree planting efforts with sidewalk maintenance efforts and considerations.	ONGOING	
· Update street planting guidelines to prioritize tap roots species and vary pit size by species	SHORT	
Sustainability Goals: Complete Neighborhoods		
GOAL: Maintain and expand transportation options including the development of bicycle, pedestrian, and sharing networks.		
· Implement a parking cash-out alternative benefit option for City employees	SHORT	HR
· Prioritize transit-oriented development	ONGOING	CED
· Partner with the DDA and AATA to provide a discounted transit pass as an alternative to downtown parking permits	MID	DPS
· Encourage corporate sponsorship of transit passes and infrastructure to encourage employee bus and bikeshare ridership	MID	DPS
· Consider pursuing car, scooter, or bike-sharing programs with Eastern Michigan University as a partner.	ONGOING	CED
· Close sidewalk gaps	ONGOING	DPS
· Add bicycle lanes to major thoroughfares and trunklines	ONGOING	DPS
· Retain the mix of uses within each corridor but allow them throughout the area.	ONGOING	CED
· Restore two-way function to Cross, Huron, and Hamilton Streets.	LONG	DPS
· Separate Cross and Washtenaw for vehicle traffic.	LONG	DPS
· Restore Harriet Street as the Main Street of adjacent neighborhoods.	LONG	CED
· Prioritize pedestrians at crosswalks, and investigate where pedestrian walk signs can be made automatic	MID	DPS

· Work with MDOT to make state-owned roads more accessible to nonmotorized users	ONGOING	DPS
· Coordinate with Townships and WCPRC on Border to Border (B2B) trail development	ONGOING	DPS
· Encourage police enforcement and legislative support for bike and pedestrian safety	ONGOING	YPD
· Improve neighborhood walkability by improving sidewalk connectivity and conditions. Prioritize the improvement of nonmotorized connections that link neighborhoods and job centers.	ONGOING	DPS
· Continue to support the development of intercity and commuter rail	ONGOING	MANAGER
· Coordinate citizens to advocate for slower traffic speeds on state owned corridors	ONGOING	
GOAL: Incentivize energy efficient and socially responsible development		
· Consider density bonuses, particularly on transit and commercial corridors, in exchange for developers meeting criteria that achieve city goals	MID	CED
· Incentivize US Green Building Council's LEED for Neighborhood Development standard for new development	MID	CED
· Develop a Green Business/Neighborhood Certification program	LONG	CED
· Seek affordable housing development and identify parcels where it can locate near services	ONGOING	CED
· Continue to prioritize infill development	ONGOING	CED
· Continue to provide a variety of housing options, including affordable housing and missing middle housing.	ONGOING	CED
· Provide a Sustainability Commissioner liaison to a neighborhood interested in developing an eco-district	ONGOING	SUSTAINABILITY
GOAL: Increase neighborhood resiliency during times of disruption.		
Identify walkable/bikeable neighborhood resource centers throughout the City, such as community centers, churches, schools, or social clubs.	SHORT	
Work with these identified resources to increase their capacity to serve as emergency resource centers, including backup power generation, emergency shelter, and food and resource distribution.	MID	
Work with the Health Department and other partners to make resources available for community leaders who wish for their homes to serve as small-scale resources during disruptions.	ONGOING	
Sustainability Goals: Communication		
GOAL: Play a leading role in educating Ypsilanti residents on sustainability topics.		
· Implement an educational series about energy efficiency in different venues with a focus on teaching the most vulnerable populations about resources that help reduce their utility bills	ONGOING	SUSTAINABILITY
· Continue to work with sustainability-related organizations to develop and offer in school guest lectures, field trips, and other learning opportunities with local schools	ONGOING	SUSTAINABILITY

· Work with schools to reduce waste and incorporate reusable items on campus	ONGOING	SUSTAINABILITY
· Determine a designated point person on city staff to direct sustainability-related questions or comments to the correct department		
· Promote the city's energy, climate, and sustainability vision through the established online newsletter and develop other municipal marketing materials to update residents on city efforts, key sustainability topics, and easy-to-follow tips at home	ONGOING	SUSTAINABILITY
· Organize competitions between municipal employees, business owners, and neighborhoods that promote sustainability-focused activities:	ONGOING	SUSTAINABILITY
· "Bring Your Green to Work,"		
· Energy treasure hunts,		
· Adopting catch basins or green infrastructure,		
· Zero waste days,		
· Smart commute weeks, and challenges to bike, walk, or take public transit to work.		
· Partner with Ypsilanti Community Schools on communication and education efforts.	ONGOING	
· Consider creating a Communications Specialist position to lead and coordinate communication and education efforts within the City.	MID	MANAGER
· Make critical public documents accessible and multilingual	ONGOING	MANAGER
· Publicize available efficiency and support programs, such as the County's weatherization program and YCUA's water assistance program.	ONGOING	
GOAL: Develop the datasets necessary to determine where disaster relief should be targeted		
· Conduct an Environmental Justice analysis that identifies vulnerable populations and structures that are disproportionately impacted by climate change	LONG	
· Work with SEMCOG and the County to expand local air quality monitoring system	SHORT	
· Investigate infrastructure materials that can weather extreme weather	ONGOING	
GOAL: Mitigate the damage inflicted on residents, infrastructure, and property from extreme weather.		
· Implement renewable backup power systems for areas of refuge and emergency facilities	ONGOING	DPS
· Collaborate with landlords, YCUA, and DTE to ensure that in a time of crisis essential water and gas/electricity are not shut off	ONGOING	CED/MANAGER
· Work with Washtenaw County to develop a Hazard Mitigation Plan.	MID	YPD/YFD/DPS
· Partner with Washtenaw County to expand emergency preparedness and communication tools including a multilingual and universally accessible plan that includes climate change predictions	MID	MANAGER

· Work with the County to identify additional accessible warming and cooling shelters	MID	
· Require occupied residential rental units to have one air-conditioned room	MID	CED
· Review response protocol and update where needed to respond to severe storm events	MID	MANAGER
· Continue to explore Resilience Hubs in coordination with local community partners and facilities.	MID	
· Publicize available utility assistance programs, such as THAW, leading into and during peak heating and cooling seasons.	ONGOING	
· Work with Washtenaw County and utility partners to ban utility shutoffs for nonpayment during states of emergency or extreme weather events.		
· Improve snow and ice response for sidewalks	ONGOING	DPS (PUBLIC) CED (PRIVATE)

Appendix A

Table X: Contamination and LUSTs by Census Tract

Census Tract	Sites of Environmental Contamination	Leaking Underground Storage Tanks (Open)	Leaking Underground Storage Tanks (Closed)	Total
Tract 4108	8	2	13	23
Tract 4106	4	3	3	10
Tract 4107	1	1	4	6
Tract 4103	3	1	7	11
Tract 4110	2	2	4	8
Tract 4112	1	1	1	3
Tract 4109	1	1	2	4
Tract 4102	0	0	1	1
Tract 4111	0	0	1	1
Total	20	11	36	67

Source: Michigan Department of Environment, Great Lakes, and Energy, EnviroMapper

Appendix B

Ypsilanti Sustainability Maps

Layers are listed in drawing order, top to bottom.

Biological Rarity

State Owned Roads (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/state-owned-roads-v17a>)

All Roads (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/all-roads-v17a>)

Hydrography Lines (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-lines-v17a>)

Biological Rarity Index, Michigan Natural Features Inventory
<https://mnfi.anr.msu.edu/resources/biological-rarity-index>

Ypsilanti Feathered Edge, generated by consultant, created using a multiple ring buffer at intervals of 20 feet up to 200 feet and symbolizing at increasing levels of transparency

Ypsilanti Municipal Boundary, provided by the client – City of Ypsilanti

Hydrography Polygons (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-polygons-v17a>)

Ypsilanti Municipal Boundary, provided by the client – City of Ypsilanti

Minor Civil Divisions (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/minor-civil-divisions-cities-townships-v17a>)

Environmental Contamination

Leaking Under Ground Storage Tanks Part 213 – Open, EnviroMapper, Michigan Department of Environment, Great Lakes, and Energy (<https://www.mcgi.state.mi.us/environmentalmapper/>)

Leaking Under Ground Storage Tanks Part 231 – Closed, EnviroMapper, Michigan Department of Environment, Great Lakes, and Energy (<https://www.mcgi.state.mi.us/environmentalmapper/>)

Sites of Environmental Contamination Part 201, EnviroMapper, Michigan Department of Environment, Great Lakes, and Energy (<https://www.mcgi.state.mi.us/environmentalmapper/>)

Ypsilanti Municipal Boundary, provided by the client – City of Ypsilanti

2010 Census Tracts (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/2010-census-tracts-v17a>)

State Owned Roads (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/state-owned-roads-v17a>)

Hydrography Lines (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-lines-v17a>)

Ypsilanti Feathered Edge, generated by consultant, created using a multiple ring buffer at intervals of 20 feet up to 200 feet and symbolizing at increasing levels of transparency

2010 Census Tracts (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/2010-census-tracts-v17a>)

Hydrography Polygons (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-polygons-v17a>)

Ypsilanti Municipal Boundary, provided by the client – City of Ypsilanti

Minor Civil Divisions (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/minor-civil-divisions-cities-townships-v17a>)

Tree Planting Priority

Ypsilanti Municipal Boundary, provided by the client – City of Ypsilanti

Ypsilanti Feathered Edge, generated by consultant, created using a multiple ring buffer at intervals of 20 feet up to 200 feet and symbolizing at increasing levels of transparency

All Roads (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/all-roads-v17a>)

Hydrography Lines (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-lines-v17a>)

Hydrography Polygons (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-polygons-v17a>)

Tree equity placement, generated by consultant (see methods section)

Minor Civil Divisions (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/minor-civil-divisions-cities-townships-v17a>)

Soil – Suitability for Dwelling Units with Basements

State Owned Roads (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/state-owned-roads-v17a>)

All Roads (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/all-roads-v17a>)

Hydrography Lines (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-lines-v17a>)

Ypsilanti Feathered Edge, generated by consultant, created using a multiple ring buffer at intervals of 20 feet up to 200 feet and symbolizing at increasing levels of transparency

Ypsilanti Municipal Boundary, provided by the client – City of Ypsilanti

Dwellings with Basements, Web Soil Survey, United States Geologic Survey, United States Department of Agriculture (<https://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm>)

Hydrography Polygons (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-polygons-v17a>)

Ypsilanti Municipal Boundary, provided by the client – City of Ypsilanti

Minor Civil Divisions (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/minor-civil-divisions-cities-townships-v17a>)

Soil – Suitability for Surface Composting

State Owned Roads (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/state-owned-roads-v17a>)

All Roads (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/all-roads-v17a>)

Hydrography Lines (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-lines-v17a>)

Ypsilanti Feathered Edge, generated by consultant, created using a multiple ring buffer at intervals of 20 feet up to 200 feet and symbolizing at increasing levels of transparency

Ypsilanti Municipal Boundary, provided by the client – City of Ypsilanti

Composting Facility – Surface, Web Soil Survey, United States Geologic Survey, United States Department of Agriculture (<https://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm>)

Hydrography Polygons (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-polygons-v17a>)

Ypsilanti Municipal Boundary, provided by the client – City of Ypsilanti

Minor Civil Divisions (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/minor-civil-divisions-cities-townships-v17a>)

Soil – Flooding Frequency

State Owned Roads (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/state-owned-roads-v17a>)

All Roads (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/all-roads-v17a>)

Hydrography Lines (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-lines-v17a>)

Ypsilanti Feathered Edge, generated by consultant, created using a multiple ring buffer at intervals of 20 feet up to 200 feet and symbolizing at increasing levels of transparency

Ypsilanti Municipal Boundary, provided by the client – City of Ypsilanti

Flooding Frequency Class, Web Soil Survey, United States Geologic Survey, United States Department of Agriculture (<https://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm>)

Hydrography Polygons (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-polygons-v17a>)

Ypsilanti Municipal Boundary, provided by the client – City of Ypsilanti

Minor Civil Divisions (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/minor-civil-divisions-cities-townships-v17a>)

Watershed

Counties (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/counties-v17a>)

Ypsilanti Municipal Boundary, provided by the client – City of Ypsilanti

Hydrography Lines (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-lines-v17a>)

Hydrography Polygons (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-polygons-v17a>)

Watersheds, Washtenaw County, Provided by the client – City of Ypsilanti

Counties (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/counties-v17a>)

Urban Greening

City of Ypsilanti Parcels, Provided by client – City of Ypsilanti

City of Ypsilanti Parcels, Provided by client – City of Ypsilanti

State Owned Roads (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/state-owned-roads-v17a>)

All Roads (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/all-roads-v17a>)

Hydrography Lines (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-lines-v17a>)

Suitability for Hand Planting, Web Soil Survey, United States Geologic Survey, United States Department of Agriculture (<https://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm>)

Ypsilanti Feathered Edge, generated by consultant, created using a multiple ring buffer at intervals of 20 feet up to 200 feet and symbolizing at increasing levels of transparency

Ypsilanti Municipal Boundary, provided by the client – City of Ypsilanti

Hydrography Polygons (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/hydrography-polygons-v17a>)

Ypsilanti Municipal Boundary, provided by the client – City of Ypsilanti

Minor Civil Divisions (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/minor-civil-divisions-cities-townships-v17a>)

Light Pollution

TL_2018_us_state, Tiger Line File, United States Census Bureau

Ypsilanti Municipal Boundary, provided by the client – City of Ypsilanti

State Owned Roads (v17a), Michigan Open Data Library, State of Michigan (<http://gis-michigan.opendata.arcgis.com/datasets/state-owned-roads-v17a>)

New World Atlas Artificial Sky Brightness, Fabio Falchi^{1,*}, Pierantonio Cinzano¹, Dan Duriscoe², Christopher C. M. Kyba^{3,4}, Christopher D. Elvidge⁵, Kimberly Baugh⁶, Boris A. Portnov⁷, Nataliya A. Rybnikova⁷ and Riccardo Furgon

Methods

Tree Equity Placement

The layer was generated by running a tree placement model for the entire City to determine what areas are most in need of trees based on two sources: existing tree canopy and the Michigan Environmental Project's Heat Stress Index. The sources were weighted accordingly: existing tree canopy (50%) and heat stress index (50%). The existing tree canopy layer was sourced from the National Land Cover Database (<https://www.mrlc.gov/national-land-cover-database-nlcd-2016>), areas with 100% tree coverage were assigned a value of 0 and areas with 0% tree coverage were assigned a value of 100. The heat stress index, which was developed using both social and physical factors, was sourced from MI-Environmental Project (https://michiganview.org/MI_Environment_Tool.html). These layers were all combined into a fishnet layer at 10ft resolution and because all of the layers were normalized on a scale of 100 the weights were just multiplied to the weighted values.

Appendix

ORIGINAL SHAPE YPSILANTI MASTER PLAN (2013) CONSULTANT TEAM

ENP & Associates (Lead Firm):

Erin N. Perdu, Principal;
Megan A. Masson-Minock, Planner;
Emily Lake, Intern

AECOM (Transportation & Urban Design):

Ian Lockwood, Principal;
Addie Weber, Urban Designer

Zachary & Associates (Housing & Economic Analysis):

Diane Van Buren, President;
Alexander Zachary, Planning & Development,
Christine Peltier, Intern

PlanActive Studio (Form-Based Code):

Tara Salmieri, Principal

2020-2021 PLAN UPDATE

CITY OF YPSILANTI CITY COUNCIL

Lois Richardson, Mayor
Nicole Brown, Mayor Pro-Tem, Ward 1
Brian Jones-Chance, Ward 1
Jennifer Symanns, Ward 2
Steve Wilcoxon, Ward 2
Anthony Morgan, Ward 3
Annie Somerville, Ward 3

CITY OF YPSILANTI PLANNING COMMISSION

Matt Dunwoodie, Chair
Jared Talaga, Vice-Chair
Eric Bettis
Michael Davis, Jr.
Jessica Donnelly
Phil Hollifield
Heidi Jugenitz
Michael Simmons

CITY STAFF

Frances McMullan, City Manager
Joe Meyers, Economic Development Director
Christopher Jacobs, Community Development Manager
Bonnie Wessler, Project Manager
Andy Aamodt, City Planner
Scott Slagor, Preservation Planner
Elize Jekabson, Public Engagement Specialist

CONSULTANT TEAM

Beckett & Raeder, Inc.:

Michelle Bennett, Associate
Leah DuMouchel, Principal
Rowan Brady, GIS Technician/Assistant Planner

Implementation Matrix

Action	Time Frame	Location	Actions underway	Completion date
Continue and increase rental inspections and enforcement	Ongoing	All neighborhoods		
Assist continuation and expansion of EMU Live Ypsi program	Ongoing	All neighborhoods		
Plan and zone for range of housing typologies for the needs of all ages and abilities	Ongoing	All neighborhoods		
Continue and expand the number, type and location of festivals and events	Ongoing	All centers		
Finish upper stories	Ongoing	All Centers		
Maintain and expand transportation options	Ongoing	Downtown		
Create “Welcome to Ypsilanti” packages for new EMU students, including web version	1-5 years	EMU		
Encourage use or redevelopment of unused parking lots	1-5 years	Towner		
Encourage development of vacant parking areas	1-5 years	Job Districts		
Align economic development incentives and programs to encourage emerging sectors that align with the Guiding Values and the employment potential of residents	1-5 years	All Districts		
Establish “Aging in Place” Programs	1-5 years	All neighborhoods		
Draft a business attraction plan for Downtown, Depot Town and Cross Street	1-5 years	All centers		

Encourage business and event activity during the day and evening	1-5 years	All centers		
Create a marketing campaign for the City of Ypsilanti	1-5 years	All centers		
Build curbless “festival” street on Washington	1-5 years	Downtown		

Action	Time Frame	Location	Actions underway	Completion date
Use vacant storefronts for temporary retail uses	1-5 years	Downtown		
Permanent year-round home for Downtown Farmer’s Market	1-5 years	Downtown		
Permanent year-round home for Depot Town Farmer’s Market	1-5 years	Depot Town		
Separate Cross Street and Washtenaw Avenue	1-10 years	Cross Street		
Create a “front door” for EMU in the area created by the reconfiguration of Cross Street and Washtenaw	1-10 years	EMU		
Restore two-way function to Cross, Huron and Hamilton Streets	1-10 years	Historic corridors		
Restore Harriet Street as the Main Street of adjacent neighborhoods	1-10 years	General Corridors		
Create “Eco-Districts” in neighborhood parks	1-10 years	All neighborhoods		
Install a way-finding system	1-10 years	All centers		
Increase walkability (2-way streets & raised intersections)	1-10 years	Downtown		
Build curbless “festival” street on River and Cross Streets	1-10 years	Depot Town		
Create a public space at new train station	1-10 years	Depot Town		

Approach on Two-Way Street Conversion

The following lists approaches to be used by the City when approaching MDOT on two-way street conversions.

Approach

1. Express the City's intent to the MDOT to restore two-way operations on the streets within the City and the transfer of the streets' jurisdiction to the City in the City's official plan and in direct communications with the MDOT.
2. Review the City's transportation plan with the MDOT so they understand the overall concept.
3. Review the key reasons with MDOT about why the changes to the streets makes sense.
 - a. Benefits of being bicycle-friendly and pedestrian-friendly.
 - b. Benefits of direct routing for motorists and cyclists.
 - c. Safety benefits of slower speeds, less weaving/speeding, and roundabouts.
 - d. Economic development and property value benefits.
 - e. City identity and aesthetic benefits.
 - f. Way-finding and legibility benefits.
 - g. Quality of life benefits.
4. Make the case for MDOT to fund the project:
 - a. The bottom line is that, at the end of the day, MDOT will have these streets "off of their books" and the City will have some "20-year" streets.
 - b. The streets involved have long lost their state role.
 - c. The City does not want to incur the maintenance costs of the streets while the streets are in their current state.
 - d. The streets are in their current state due to the state's past needs/values for accommodating through traffic and high levels of service for motorists through the City; a condition that is no

longer exists. The future for the streets, as per the City's plans, are now in the best interest of the City and the area.

- e. The idea is that once the streets are restored to a condition (i.e., a 20-year street), then it makes sense for the City to assume the jurisdiction of the streets, and then the jurisdictional transfer should take place. The changes include the two-way restorations, cross-section changes, and underground utility work; according to the City's specifications.

Note that the above was written under the assumption that there is no need for the MDOT to keep jurisdiction over any of the affected streets. If there is a need to keep a route under MDOT's jurisdiction, the route should be Huron and Cross. However, it is hoped that this does not occur.

The final steps are:

1. Have the MDOT fund a the implementation plan (i.e., traffic study, the surface design/ traffic control changes, utility assessment and changes, staging, etc.)
2. Implement the project.
3. Transfer the jurisdiction.

PHASES FOR TWO-WAY CONVERSIONS

The following are potential phases of two-way conversions:

1. Lowell; Huron north of Cross; Hamilton north of Cross; Perrin north of Cross
2. Cross; Emmet; Washtenaw; Hamilton north of Washtenaw; Perrin north of Washtenaw
3. Remainder of Hamilton; remainder of Huron; Harriet

Citizen Committee on Housing Affordability and Accessibility

See the Citizen Committee on Housing Affordability and Accessibility Report and Recommendations on the following pages.

DRAFT

**Report and Recommendations of the City of Ypsilanti
Citizen Committee on Housing Affordability and
Accessibility**

Submitted to the City of Ypsilanti Planning Commission

July 2020

Executive Summary

Throughout 2016 and 2017, members of the public repeatedly voiced concerns to the City of Ypsilanti Planning Commission regarding (1) rising rents in the City that were putting people at risk of displacement, and (2) limited physical accessibility of the City's aging housing stock. In response to these concerns, the Planning Commission voted in December 2017 to charter a citizen sub-committee to study the issues of housing affordability and accessibility, and to "develop and issue recommendations for specific land use and policy changes for consideration by the Planning Commission and (upon invitation) City Council."

The purpose of the sub-committee, as described in its founding charter, was to inform updates to the City of Ypsilanti's 2013 Master Plan with a focus on preserving and enhancing housing affordability and accessibility, in keeping with the guiding values that "anyone, no matter what age or income, can find a place to call home in Ypsilanti."

The first phase of the committee's work was devoted to fact-finding in subgroups, and was followed immediately by a second phase focusing on analysis of the situation. **Five problem statements** were formulated to capture the key challenges facing the City with respect to housing affordability and accessibility:

- **The cost of housing is increasing steadily.** After the crash of the housing market in 2008, Ypsilanti saw a steep decline in housing prices, accompanied by an increase in foreclosures and a decline in the homeownership rate due to an influx of "house flipping," whereby landlords and speculators purchased foreclosed homes and converted them into investment properties. For-sale housing prices remained low for several years post-crisis before starting to pick up again in 2012-2013. Since then, available housing stock has dried up, leading to a very low vacancy rate, increases in demand, and higher prices for both rental and for-sale housing.
- As a result of these trends, housing in Ypsilanti is **increasingly unaffordable for many residents**. Because a strong majority of housing units in Ypsilanti (69.2%) are renter-occupied, and because renters in Ypsilanti have lower incomes, on average, than homeowners, renters are disproportionately affected by increasing housing costs. However, a significant proportion of homeowners in Ypsilanti are also affected. In total, Nearly half of households in Ypsilanti are cost-burdened (meaning >30% of household income goes to housing costs), and Ypsilanti has significantly higher rates of cost burden than both Ann Arbor and Washtenaw County as a whole.
- **Existing data and measures do not adequately capture the local situation with respect to housing affordability and accessibility.** There is a pressing need for improved measures and additional information to paint a more comprehensive picture of the nature and magnitude of housing affordability and accessibility challenges, and how it impacts specific populations, including seniors, people with low incomes, people with disabilities, and school-aged youth experiencing housing insecurity or homelessness.
- **Ypsilanti's old housing stock poses health, safety and accessibility challenges.** While Ypsilanti's old and historic homes add character to the City, their age and

condition present challenges for affordability and accessibility. Most homes were constructed before contemporary health and safety codes were in place; and just one in 10 houses or apartments in Ypsilanti was built in the 1990s or later,¹ when updates to the Fair Housing Act and building codes began requiring some accessibility features in new housing, such as stepless entry and ground-level bathrooms and bedrooms. As a result, Ypsilanti residents face health risks from lead paint, radon exposure, and mold; high heating bills from poor insulation; and difficulty finding housing that will accommodate a disability. Rental households are at increased risk for all of these factors. In addition to a general lack of accessible housing, there are few housing options adapted to the needs of seniors, many of whom live on modest fixed incomes and/or have limited physical mobility.

- **Ypsilanti does not have a lot of land available to build new housing.** Nearly all land in the City has already been developed, limiting opportunities for construction of new housing. Much of the land that is currently vacant, like Water Street, is considered “brownfield,” meaning past industrial activity has left behind contamination that adds cleanup costs to development; other available parcels have potential or actual wetlands on them. There are significant limits on what types of homes can be built, due to a combination of zoning restrictions (e.g. minimum building envelopes, setback requirements) and historic preservation requirements. And because new housing is typically more expensive than existing housing -- especially in the Ann Arbor construction market, where labor costs are relatively high -- replacing older housing with new construction has the potential to exacerbate housing affordability issues.
- **Current and past policies at the state and local levels have contributed to our affordability and accessibility challenges.** The City of Ypsilanti Zoning Ordinance limits construction and conversion of multi-unit dwellings and smaller-scale single-unit dwellings through a combination of single-family zoning, accessory dwelling unit (ADU) restrictions, and residential lot and building envelope requirements. In addition, the City currently imposes a limit of three (3) on the number of unrelated adults that may occupy a single dwelling, a regulation that is stricter than in surrounding communities and which contributes to under-utilization of available housing units. Inadequate oversight by the State of Michigan in administering federal Low-Income Housing Tax Credits (LIHTC) to private real estate developers led to the exploitation of a loophole that allowed several apartment complexes in Ypsilanti City and Township to shed their affordability requirements far ahead of schedule. Seniors residing at Cross Street Village apartments have seen dramatic escalation in rent as a result.

Based on the above understanding of the problem, our committee designed and implemented a multi-stage public engagement process consisting of:

- **A Housing Affordability & Accessibility Survey** to gather up-to-date information on the nature and magnitude of housing affordability and accessibility issues experienced by Ypsilanti residents. The survey was circulated online and via paper questionnaires

¹ U.S. Census Bureau, 2012-2016 American Community Survey 5-Year Estimates, “Selected Housing Characteristics”

and was completed by more than 500 respondents between October 2018 and January 2019.

- **Interviews** with three landlords of residential properties in Ypsilanti (one with a small number of rental properties, one with a moderate number of rental properties, and one with a large number of rental properties).
- An **Open Forum** to present the survey and interview findings to the public and to solicit public input on a preliminary set of housing affordability and accessibility strategies for the City of Ypsilanti.
- An **Ypsilanti Housing Strategies Survey** to gather quantitative feedback from Ypsilanti residents on the favorability of specific housing strategies in six key domains: (1) Renters' rights, (2) Sustainable development strategies, (3) Need-based assistance strategies, (4) Physical accessibility strategies, (5) Zoning strategies, and (6) Partnership and advocacy strategies. The Housing Strategies Survey was launched online on September 3, 2019 and closed on October 22, 2019. More than 360 responses were collected.
- Finally, the committee welcomed public comment and input through its standing monthly meetings, held from January 2018 to May 2019.

Despite efforts to solicit input from a representative cross-section of Ypsilanti residents, the survey demographics indicate that some groups were underrepresented while others were overrepresented. Males, Black/African Americans, and renters were underrepresented in the survey by a significant margin.

Our **key findings** with respect to housing affordability are the following:

- Prices of both for-sale and rental housing are **rising fast** and show no signs of abating, in line with national trends.
- The most **commonly used measures** of housing affordability fail to capture the total cost of housing as experienced by most Ypsilanti residents, and especially those who earn the median income or less. Monthly rents do not capture the full picture with respect to the cost of rental housing; most rentals require a deposit equal to a full month's rent.
- Over half (54.6%) of Ypsilanti renters are **cost-burdened** with respect to housing, meaning that they spend more than 30% of their income on housing.² Data from the committee's Housing survey closely track ACS data on this point.
- The consequences of the **boom-bust cycle in for-sale housing** have not been the same for all residents and stakeholders. Real estate investors -- some local, others from outside of the area -- who bought homes in Ypsilanti during the housing crisis in order to "flip" them have profited from increasing sales prices. Many Ypsilanti homeowners who purchased their homes at depressed prices (i.e. from 2008 to 2013) have seen their

² Gross rent as a percentage of household income (GRAPI) for the City of Ypsilanti in 2017, according to the US Census Bureau ACS.

property values escalate rapidly since 2013, resulting in substantial growth in home equity.

- The flip side of these benefits to investors and newer homeowners has been a sharp **decline in access to homeownership** for Ypsilanti residents who currently rent their homes, especially those ages 25 to 34. In addition, the boom-bust housing cycle -- by first displacing people with limited wealth and/or income from their homes through foreclosure or short sales and then making it difficult or impossible for them to afford another home in the same neighborhood -- has had a gentrifying effect.
- The **consequences of rising rents** have been acutely felt by Ypsilanti residents, particularly those with lower incomes. Some of the disruptive effects have included frequent moves motivated by sharp rent increases; being forced to settle for poorly maintained rental units that are less accessible to public transportation and other essential amenities; displacement, especially among seniors and people with disabilities; housing insecurity; and homelessness.
- **Source-of-income discrimination** appears to be a problem for renters in Ypsilanti, with 9.3% of housing survey respondents indicating they have been denied housing based on their source of income.
- Protecting and advancing housing affordability and accessibility will require **decisive and sustained action at multiple levels** of government, including the municipal, county, state, and federal levels. Collaborating with policymakers and officials at other levels of government will be essential to ensuring that all people, no matter what age or income, can find a place to call home in Ypsilanti.
- One-size-fits-all solutions do not apply; we will need a **combination of strategies** that are tailored to the specific housing needs and preferences of Ypsilanti residents, including young people, seniors who wish to age in place and people with disabilities.

Our **key findings** with respect to housing **accessibility** are the following:

- Only a small portion of units offer wheelchair accessibility, and houses often require modifications to doorways, bathrooms, and kitchens to serve a resident with a disability.³
- The City of Ypsilanti 2012-2016 census statistics reported that 6.7% of persons under 65 have a disability, or about 1400 disabled persons (auditory, visual, cognitive, ambulatory impairments).⁴
- Accessibility is not limited to the needs of wheelchair users. According to a broader definition of disability, 32% of Ypsilanti residents are living with a disability of some type.⁵ The highest concentrations of residents with a disability are in areas with the lowest average incomes.

³ While there are several of these facilities that offer these amenities, they often have limited availability. Namely, Cross Street Village, River Rain Apartments, 422 Pearl, 420 Emmet, 404 N Huron, Peninsular Place, UGA Townhomes, and recently renovated Ypsilanti Housing Authority units.

⁴ Figures exclude seniors and use a narrow definition of disability ("Serious difficulty with four basic areas of function -- hearing, vision, ambulation, cognition").

⁵ Fair Housing Act defines a person with a disability as an individual for whom a physical or mental impairment limits one or more major life activities.

- AARP/Harvard reports that 90% of seniors plan to age in place, and SEMCOG estimates the over-65 demographic will increase in our area by 240% by 2035. Given the proportions of owner-occupied to rental units in the City, it is important to create accessible options in both categories.
- Survey results further emphasize these basic facts, with two-thirds of survey respondents (66.7%) reported that their homes have no accessibility features. Over 1 in 4 reported that barriers to physical accessibility in a home had limited their quality of life.
- Many survey respondents say that accessibility is a consideration in the selection of their next residence with over half of respondents saying a ramp or step-free entrance would be a factor in their choice, and at least 1 in 5 saying that every accessibility option listed in the survey would be a desirable factor from parking, to bathroom and kitchen amenities, to doorways and elevators.

Based on input and feedback from 361 respondents who reviewed 26 housing strategies included in the committee's Housing Strategies survey, our committee recommends that the City consider adoption and implementation of **11 strategies**. The selected proposals reflect the input of Ypsilanti residents who engaged with this survey and, if implemented, will respond to pressing housing needs and start to correct housing inequities in Ypsilanti. They are:

1. **Tenant Right of First Refusal:** Enact a 'Tenant Right of First Refusal' ordinance mandating that tenants receive advance notice when their landlord intends to sell the property and have the opportunity to purchase the property before it is offered for sale to outside buyers.
2. **Just Cause Ordinance:** Enact a 'Just Cause' ordinance to protect renters from wrongful and/or retaliatory displacement. The ordinance would bar landlords from evicting or refusing to renew a tenant's lease without 'just cause' such as failure to pay rent or a violation of lease terms, pursuant to Michigan Act 18 of 1933.
3. **Affordability and Accessibility Ordinance:** Enact an Affordability & Accessibility Ordinance that 1) defines the parameters for affordable & accessible housing based on the City of Ypsilanti's Area Median Income (AMI) and 2) requires new housing developments to include a percentage of affordable and accessible units based on Ypsilanti's need.
4. **Homeless Shelter:** Construct or establish an overnight shelter in Ypsilanti to help meet needs of residents experiencing homelessness.
5. **Community Land Trust:** Work with local non-profit agencies and neighboring communities to establish a Community Land Trust (CLT) to promote long-term housing affordability and accessibility through community control of land. Community Land Trusts are nonprofit, community-based organizations designed to ensure community stewardship of land. CLTs provide an opportunity for democratic ownership of land with private ownership of the structure on the land in order to maintain long-term housing affordability. CLT properties can be interspersed throughout one or more neighborhoods and can include rental homes and businesses.

6. **Assist low-income residents with home-buying:** Assist low-income residents who wish to purchase a home by offering credit improvement services, and mortgage down-payment assistance.
7. **Minor home repair:** Establish a Minor Home Repair Program to assist with the cost of essential home repairs for eligible low-income and disabled homeowners. Eligible repairs could include roof replacement, plumbing replacement, mechanical or electrical replacements, ADA ramp installation or repair, door modifications, and lead or mold remediation.
8. **Visitability ordinance:** Enact a Visitability Ordinance to ensure that newly constructed homes incorporate basic accessibility features that make it easier for mobility-impaired people to visit or live in Ypsilanti. A home is “visitability” if it has: (1) at least one no-step entrance; (2) doors with 32 inches of clear passage space; and (3) a bathroom on the main floor that is wheelchair-accessible.
9. **Increase the number of non-related adults who may occupy a dwelling:** Increase the number of unrelated individuals who may reside together in a dwelling by changing the Zoning Ordinance definition of “Family” to include a limit of two unrelated persons for each bedroom in the dwelling.
10. **Rent Control:** Advocate with state lawmakers to grant municipalities the authority to cap annual rent increases.
11. **Ask local universities to invest in the City of Ypsilanti Housing Trust Fund:** Advocate with the University of Michigan and Eastern Michigan University to invest in the Ypsilanti Housing Trust Fund and to actively support other county-wide housing affordability measures.

In the context of the COVID-19 pandemic and civil unrest due to systemic racial inequities, we share a conviction that it is more urgent than ever for local governments to proactively address the needs and interests of communities under duress. With a view to accelerating action, we offer a prospective three-phase pathway and timeline for rolling out housing policies and programs over the next 10 years.

Phase One (current Budget year)

Make the Ypsilanti Housing Trust permanent: Assure a sustainable funding source for housing affordability and accessibility by formalizing and making permanent the City of Ypsilanti Housing Trust Fund started by Councilmember Pete Murdock and nourishing it with an annual contribution of no less than \$100,000.

Allocate staff time to housing affordability and accessibility: Allocate a significant portion of an existing staff member’s time to the coordination and monitoring of City housing affordability and accessibility policy and to liaising with other units of government and partners on housing affordability and accessibility.

Draft and implement the Tenant Right of First Refusal ordinance (Strategy 1), the Just Cause Ordinance (Strategy 2), the Affordability and Accessibility Ordinance (Strategy 3), the Visitability

Ordinance (Strategy 8), and the Zoning Ordinance text amendment to increase the number of non-related adults who may occupy a single dwelling (Strategy 9) from three total to two persons per bedroom. (*The Planning Commission is also encouraged to consider additional changes to the Zoning Ordinance to reduce restrictions on construction and/or conversion of multi-unit homes, accessory dwelling units, and smaller-scale homes.*)

Begin advocating for State legislation to expand local authority to regulate rent increases (Strategy 10) and for local university contributions to the City of Ypsilanti Housing Trust Fund (Strategy 11).

Phase Two (Budget year 2021)

Draft an affordability-focused property acquisition plan that would go into effect in the event of another housing crisis resulting in a surge of foreclosures of multi-unit residences. The aim of this plan would be to ensure that such properties can be converted to sustainable affordable and accessible use, either in partnership with a local housing non-profit or through the launch of a Community Land Trust.

Introduce a home-buying assistance program (Strategy 6) and the Minor home repair program (Strategy 7).

Phase Three (Budget year 2022-2030)

Create and invest in institutions that promote community stability and build toward long range sustainable housing goals.⁶ Pursue affordability and accessibility-focused collaborations at the county and regional levels, with a view to leveraging resources from outside of the City of Ypsilanti. These would include the establishment of a Community Land Trust (Strategy 5) and the construction or establishment of an overnight homeless shelter (Strategy 4).

⁶ <https://shelterforce.org/2017/11/02/time-for-trickle-up-housing/>

Table of Contents

I.	Context	11
	A. Committee formation and mandate	
	B. Housing policy in the U.S.: A legacy of exclusion and impoverishment	
	C. Ypsilanti's housing landscape	
II.	Process	15
	A. Fact finding	
	B. Problem definition	
	C. Public input	
III.	Key findings	30
IV.	Committee recommendations.....	32
	A. Priority recommendations	
	B. Proposed pathway and timeline for implementation	
	C. Gaps and limitations	
V.	Appendices	43
	A. Sub-committee charter	
	B. Housing Affordability & Accessibility Survey: Questions & Results	
	C. Landlord interview questions	
	D. Housing Strategies Survey: Questions & Results	

In Memoriam: Liz Dahl-MacGregor and Pete Murdock

In memory of Pete Murdock and Liz Dahl-MacGregor, their commitment to making Ypsilanti a more just and inclusive City, and their efforts to advance housing affordability and accessibility and the work of our committee towards that end.

Acknowledgements

This report would not have been possible without the people who generously volunteered their time, energy, ideas, and experiences as past and present members of the Housing Affordability and Accessibility Committee:

Mike Auerbach
Toi Dennis
Matt Dunwoodie
Amber Fellows
Alexis Ford
Bryan Foley
Zachary Fosler
Ashley Fox
Patrick Gaulier
Tariq Hamad
Marquan Jackson

Heidi Jugenitz
Chris Madigan
Richard Murphy
Cheranissa Roach
Nathanael Romero
James Scarletta
Desirae Simmons
Shari Wander
Bonnie Wessler
Roberta Wojick-Andrews

The Committee would also like to extend our thanks to the Washtenaw County Office of Community & Economic Development and Bridgeport Consulting for providing facilitation support to the Committee in the first year of its work.

Finally, we are enormously grateful to the residents who shared their experiences and insights with the Committee through participation in its meetings, surveys, interviews, and Open Forum.

The following people contributed to the production of this report:

Matt Dunwoodie
Amber Fellows
Ashley Fox
Heidi Jugenitz
Cheranissa Roach
Nathanael Romero
Desirae Simmons

I. Context

A. Committee formation and mandate

The sub-committee on housing affordability and accessibility was formed by the City of Ypsilanti Planning Commission in December 2017. The purpose of the sub-committee, as described in its founding charter (see **Appendix A**), was to “review and update the City of Ypsilanti’s 2013 Master Plan with a focus on preserving and enhancing housing affordability and accessibility in keeping with the guiding values of the Master Plan.”

At the time the 2013 Master Plan was developed, Ypsilanti was still recovering from the housing crash of 2008, and housing affordability had not yet emerged as a high-visibility issue. The 2013 Master Plan process emphasized other aspects of the City’s built environment but did not address housing directly. It did, however, embrace as a guiding principle that “Anyone, no matter what age or income, can find a place to call home in Ypsilanti.”

From 2015 to 2017, in the course of its regular business, the Planning Commission heard repeatedly from members of the public about two issues: (1) rising rents in the City that were putting people at risk of displacement, and (2) limited physical accessibility of the City’s aging housing stock.

In response to these concerns, the Planning Commission chartered a citizen sub-committee to study the issues of housing affordability and accessibility, and to “develop and issue recommendations for specific land use and policy changes for consideration by the Planning Commission and (upon invitation) City Council.”

Per the charter, the sub-committee was to be comprised of:

- Up to four (4) members of the Planning Commission
- One member of the Human Relations Commission
- One member of the Sustainability Commission
- One member of the Ypsilanti Housing Commission board
- One representative of EMU
- One representative of Defend Affordable Ypsi
- One representative of Ann Arbor Center for Independent Living
- One representative of Avalon Housing
- One representative of civic affairs organization at the county or state level
- One Ypsilanti owner-occupant
- One Ypsilanti business owner (and employer)
- One lessor of rental properties in Ypsilanti
- Up to two members of the community at large.

B. Housing policy in the U.S.: A legacy of exclusion and impoverishment

Over time, many legalized forms of anti-Black racism and discrimination in the U.S. – from chattel slavery to Jim Crow laws and school segregation – have been phased out. In their place, other, more covert forms of institutional racism and discrimination have emerged. Past and present housing policy in the U.S. is fraught with examples of overt and covert racism and discrimination. These include racial segregation of federally-funded public housing developments; demolition of Black homes, businesses, and neighborhoods to build highways in the name of urban renewal; systematic denial of federal insurance for home mortgages in areas with Black residents (a practice known as redlining); and use of restrictive housing covenants. More recently, less conspicuous practices like real estate steering, racial targeting of high-risk mortgage loans, exclusionary zoning, and discrimination by landlords have been utilized to maintain racial and economic segregation within and across municipalities. The 2008 housing crisis – brought on by a proliferation of real estate speculation and subprime mortgage lending – produced an unprecedented wave of foreclosures that disproportionately affected Black and Latinx households⁷ and rapidly transferred homes and equity from residents to investors.⁸

The City of Ypsilanti has its own, well documented legacy of restrictive covenants, housing segregation, and urban renewal policies that have shaped the local housing landscape over the last century. Since 2010, rising demand and home prices in Ypsilanti, fueled in part by skyrocketing housing costs in Ann Arbor, have accelerated gentrification throughout the City, a subject of increasing concern in recent years. Gentrification is particularly visible in the racial demographics of the southwest portion of the City,⁹ which has become increasingly whiter over the last decade, a continuation of a pre-existing trend.

Housing discrimination and exclusion have severe, long-lasting consequences for Black households, communities, and the country as a whole. Restricted access to homeownership has dramatically limited equity-building; on average, a white household in the U.S. today has more than 11 times the wealth of a Black household.¹⁰ Many U.S. cities and schools are as racially and economically segregated as they were in the 1950s, and research has shown that cities with the greatest life expectancy gaps between census tracts are those where racial and ethnic segregation are most stark.¹¹

While local policy change is inadequate to eliminate systemic, centuries-old injustices in housing, it is nonetheless essential. The City of Ypsilanti has several tools at its disposal to begin the important work of addressing historical inequities and designing a City that is more open, inclusive, and just.

⁷ [Minorities hit harder by foreclosure crisis](#)

⁸ [The Eviction Machine: Neighborhood Instability and Blight in Detroit's Neighborhoods](#)

⁹ 68% of the southwest portion was African-American, down from 80% in 2010 (American Community Survey 2017).

¹⁰ [The black-white economic gap remains as wide as in 1968 - The](#)

¹¹ [Life Expectancy Follows Segregation in US Cities](#)

C. Ypsilanti's housing landscape

Ypsilanti's housing landscape reflects its people, past and present policies, and the prominent influence of Eastern Michigan University (EMU) on the City.

Demographics: In 2018, the City of Ypsilanti had an estimated population of 20,939. With a median age of 24.2, Ypsilanti residents are younger, on average, than residents of Michigan (39.8), Washtenaw County (33.6), and Ann Arbor (26.9).¹² Half of all households are headed by householders aged 15-34, and most householders in this age group rent their homes. There has been a recent drop-off in the share of householders ages 25 to 34 who own their homes; in 2010, 65% of householders in this age group rented versus 85% today.¹³ Seniors comprise just 7.2% of Ypsilanti's population compared with 17.7% statewide.

Ypsilanti has a larger percentage of Black residents than the County and the State. As of 2018, 27.3% of the population identified as Black or African American; 4.6% as Hispanic or Latinx; 4.4% as two or more races; and 2% as Asian. The proportion of the population identifying as White alone was 61.6%.¹⁴ The biggest change in the City's racial makeup since 2010 is a decline in the Black population from 31.9%¹⁵ to 27.3%. The loss of Black residents appears to be concentrated in the southwest portion of the City (census tract 4106), which was 90% Black in 2000, 80% Black in 2010, and 68% Black in 2018.

Since 2010, the City of Ypsilanti's population and average household size have both grown significantly, by 3% and 11% respectively,¹⁶ while Michigan has only seen population growth of 1% and no change in average household size during the same period.

Income: Median household income in Ypsilanti is \$36,982, compared to \$69,434 in Washtenaw County and \$54,938 in Michigan.¹⁷ An estimated 32% of households are living below the poverty line. However, both median household income and per capita income in Ypsilanti are rising, and the latter has grown by 9.5% since 2010.¹⁸

Aggregate measures of income in Ypsilanti mask sharp disparities across neighborhoods. The original 2013 Master Plan highlights these disparities, which track closely with racial composition and historical discrimination. As of 2010, the census tract containing College Heights -- a neighborhood that employed a racially restrictive covenant in the 1940s¹⁹ -- had a median household income of \$59,688, while the census tract containing Heritage Park, Worden

¹² ACS 2018 5-year estimates.

¹³ City of Ypsilanti Master Plan, updated 2020.

¹⁴ ACS 2018 5-year estimates.

¹⁵ 2010 Census.

¹⁶ <https://www.census.gov/quickfacts/fact/table/MI,ypsilanticitymichigan/LND110210>.

¹⁷ <https://semcog.org/community-profiles/communities/4130#EconomyJobs>

¹⁸ <https://www.census.gov/quickfacts/fact/table/MI,ypsilanticitymichigan/LND110210>.

¹⁹ <http://ypsiarchivesdustydiary.blogspot.com/2012/02/racially-restrictive-covenants-in.html>

Gardens, and Bell Kramer -- historically black neighborhoods -- had a median household income of \$18,828.

Quantity and type of housing units: The U.S. Census Bureau places the current number of housing units in the City of Ypsilanti at 8,868. Of these, 37.5% are single-unit homes (including 3,146 detached and 183 attached homes); 6.7% are part of two-unit homes; and 11.6% are part of three- or four-unit homes. Another 13.8% of housing units are located in structures with five to nine units; 12.4% in structures with 10 to 19 units; and 15.8% in structures with 20 or more units.²⁰ The spatial distribution of different home types within the City is described in greater detail in Chapter 3 of the Master Plan.

Housing tenure: Nearly 70% of Ypsilanti residents rent their homes, while 31.3% own their homes. This is effectively the inverse of the statewide pattern, and reflects both the young demographics of the City, the prominence of property management firms within Ypsilanti's housing market, and the consequences of the 2008 housing crisis, which shifted additional homes into the hands of real estate investors. Use of alternative housing tenures, such as cooperative housing and condominiums, is sparse, and there is no active land trust in the City.

Age of housing units: Just over 30% of housing units in Ypsilanti were constructed before 1940, and a full 50% of units were built before 1960. As buildable land in the City has diminished, so has the pace of construction; 332 units were added in the decade from 2000 to 2009, and since 2010, just 195 units have been constructed.

Land area and population density: Comprising just 4.33 square miles of land area, the City has a population density of approximately 4,800 people per square mile, comparable to that of Detroit today. By contrast, the City of Ann Arbor has a slightly lower population density of 4,100 people per square mile, while Ypsilanti Township has a much lower population density of 1,800 people per square mile.

Land use: Single-family homes account for 37.5% of Ypsilanti's roughly 9,000 housing units and 30% of its land. EMU and other tax-exempt uses occupy nearly 40% of the City's land area, a reality that constrains opportunities for construction of new housing. The 38-acre Water Street Redevelopment area that extends south from Michigan Avenue and east from the Huron River is the largest expanse of undeveloped land in the City. However, environmental contamination of sections of the land has thwarted past plans to build affordable housing there and continues to pose a financial barrier to the future development of the land for this purpose.

²⁰ ACS 2018.

II. Our Process

A. Fact-finding

The **first phase** of the committee's work was devoted to fact-finding. To facilitate in-depth review of existing (secondary) data and information on housing affordability and accessibility in the City of Ypsilanti, the committee formed five sub-groups:

- (1) a Housing Stock sub-group charged with assessing the quantity and quality of housing;
- (2) a Housing Market sub-group charged with examining trends in housing demand and pricing;
- (3) a Homelessness and Housing Insecurity sub-group charged with estimating the magnitude of homelessness and housing insecurity vis-a-vis available beds and housing;
- (4) a Density/Zoning sub-group charged with examining the existing zoning ordinance and its implications for housing affordability and accessibility; and
- (5) a Housing Accessibility sub-group charged with assessing the situation with respect to physical accessibility of housing for people with disabilities as well as those aging in place.

Housing Stock: Quantity and quality

To determine the state of housing in Ypsilanti, the subgroup on Housing Stock: Quality and Quantity consulted the following resources:

- CoStar Custom Market Report- Ypsilanti Market Overview. Costar is a real estate market analytics company that aggregates vacancy, rents, sales activity, etc. The Rental Vacancy Rates over time were highlighted by the Housing Stock Subgroup as a notable indicator of market changes.
- Rent.com, Zillow.com, and Ann Arbor Area Board of Realtors Multiple Listing Service data were monitored to track number and prices for active listings during the time of the subgroup activity- January-March 2018
- U.S. Census Bureau data was reviewed for housing unit counts over time, including a 5-year estimate for 2012-2016. The Housing Stock Subgroup drew from that same 5-year forecast to identify housing unit counts by the year the structure was built and for the number of units contained in the structure.
- Washtenaw County Staff provided counts of "committed affordable housing" through Low-Income Housing Tax Credit subsidies, Community Development Block Grants, and Housing Commission information. EMU housing counts were included with this information based on the Fall 2017 term, both for on-campus apartments and dorms.
- The SEMCOG 2045 Regional Development Forecast was referenced for expectations of changes to housing stock and population changes.

Available information on the condition of housing stock was identified as a shortcoming at the early stages of data collection, due to quality issues being complaint-based and therefore incomprehensive. Washtenaw County Public Health has the mandate to intervene in occurrences of lead, mold, pests, radon, etc., but aggregate data on these outcomes are not consistently available.

Housing Market: Trends in for-sale and for-rent demand, price

Data sources consulted by the subgroup on Housing Market Trends included:

- U.S. Census Bureau American Community Survey (ACS), published annually. We analyzed multiple ACS indicators, including population and household counts by tenure (owner-occupied vs. renter-occupied), household income data and cost-burdened status, and median rent costs.
- The CoStar Market Report, which provided data on average asking rent by number of bedrooms.
- Rent.com and zillow.com rental listings posted from January to March 2018. Data analyzed included asking rents for properties located within the City of Ypsilanti.
- The Ann Arbor Area Board of Realtors Multiple Listing Service, which provided data on home sale prices helpful in estimating cost barriers facing home buyers.

The ACS presents multi-year estimates for many housing characteristics, and these estimates can differ markedly from “point-in-time” estimates, especially in periods of major or consistent change in housing. Given that local housing costs have been rising consistently over the past five years, ACS estimates of housing costs lag behind the reality.²¹

Homelessness and Housing Insecurity: Estimating the size of the homeless and housing insecure population

The homelessness and housing insecurity sub-group examined the available data on homelessness and housing insecurity in Ypsilanti. Homelessness was defined as those who are “sleeping in a place not meant for human habitation (e.g. living on the streets) or living in a homeless emergency shelter.” Housing insecurity was defined as those experiencing “frequent moving, staying w/friends or relatives, couch surfing, difficulty paying rent/mortgage, living in an unstable neighborhood, overcrowding in home, fleeing domestic violence, or more than 50% of income goes toward housing costs.”

Obtaining reliable estimates of the number of people experiencing housing insecurity and/or homelessness in Ypsilanti proved challenging due in part to the inadequacy of traditional survey instruments and methods to capture this information. Accordingly, the group focused on survey findings and service statistics from agencies that serve homeless and housing-insecure clients in Washtenaw County like Shelter Association of Washtenaw County (SAWC) Delonis Center and Ozone House.

Understanding barriers to securing housing and staying housed over time is critical to mounting an effective response, so the sub-group consulted with social service providers in Washtenaw County to enumerate a list of barriers -- individual and systemic -- faced by people experiencing homelessness and housing insecurity.

²¹ [Understanding and Using ACS Single-Year and Multiyear Estimates](#)

Density and Zoning: Barriers to and facilitators of affordable, accessible housing

To characterize the current situation with respect to population density, zoning regulations, and housing affordability and accessibility, the Density and Zoning sub-group consulted the existing City of Ypsilanti Zoning Ordinance and Zoning Map (revised substantially in alignment with the 2013 *Shape Ypsi* Master Plan and amended multiple times since) as well as ACS data on population growth, housing unit availability, and vacancy rates.

The density and zoning sub-group also looked at broad patterns of land use within the City and analyzed the implications of these patterns for housing stock and prices.

Accessibility: Barriers to and facilitators of physical accessibility of housing

The Americans with Disabilities Act (ADA) of 1990 prohibits discrimination against individuals with disabilities in all areas of public life, including jobs, schools, transportation, and all public and private places that are open to the general public.²² The Fair Housing Act and building code updates since 1990 have required some accessibility standards in new housing.

The Accessibility sub-group examined the local situation with respect to the physical accessibility of housing for people with disabilities and people aging in place. To situate its analysis within the framework of federal law, the Accessibility sub-group reviewed Fair Housing Act and Americans with Disabilities Act definitions of housing accessibility-related terms, such as universal design, visitability, and reasonable accommodation.

The sub-group then consulted US Census and ACS data on the number of people with disabilities and the number of seniors in Ypsilanti, and reviewed maps displaying the percent of residents with a disability by census tract. Finally, the sub-group considered regional, statewide, and national data on the projected growth of the senior population, which is expected to increase demand for accessible housing substantially between now and 2035.

The following definitions guided the committee's work on accessibility. A home is **accessible** when a resident with a disability can live independently in that home. The most common form of housing accessibility is a design that supports a person using a wheelchair: first floor bathrooms and bedrooms, floor plans and door widths that can be moved through in a wheelchair, and similar. A home may be **adaptable** if it is not fully accessible, but allows for addition of accessibility features, e.g. through reinforced walls that can accommodate grab bars.

B. Problem definition

Following the presentation and discussion of sub-group findings, the committee proceeded to a **second phase**: definition and analysis of the problem (or situation). In this phase, information from the fact-finding phase was synthesized into a series of five "problem statements" that,


²² [An Overview of the Americans With Disabilities Act](#)

together, capture the essence of the situation with respect to housing affordability and accessibility in Ypsilanti.

Problem Statement #1: The cost of housing is increasing steadily.

After the crash of the housing market in 2008, Ypsilanti saw a steep decline in housing prices, accompanied by an increase in foreclosures and a decline in the homeownership rate due to an influx of “house flipping,” whereby landlords and speculators purchased foreclosed homes and converted them into investment properties. For-sale housing prices remained low for several years post-crisis before starting to pick up again in 2012-2013 (see *Fig 1*). Since then, available housing stock has dried up, leading to a very low vacancy rate (*Fig 2*), increases in demand, and higher prices for both rental and for-sale housing. Despite lower prices in comparison to other areas of Washtenaw County, housing in Ypsilanti is increasingly unaffordable for many residents. By way of illustration, a household earning the median income for Ypsilanti (\$35,000) can afford monthly housing costs of \$875 or less, including utilities (see *Table 1*). By contrast, the average asking rent for a two-bedroom apartment in Ypsilanti was \$897 in January 2018, (see *Table 2*), and average monthly housing costs for owner-occupied housing units was \$1367.²³

Figure 1: Average home sale prices in Ypsilanti School District, 2006 - 2017



²³ ACS 2018.

Figure 2: Housing Vacancy Rate, City of Ypsilanti, 2008 - 2017



Table 1: Affordable Rent Thresholds by Income Level

Annual Income	Rent at 30 Percent of Monthly Income
\$10,000	\$250
\$15,000	\$375
\$25,000	\$625
\$35,000	\$875
\$50,000	\$1,250
\$75,000	\$1,875
\$92,900	\$2,323

Table 2: Estimates of Average Monthly Rent in the City of Ypsilanti, by data source

	2013-2017 ACS 5-Year Estimates	Costar, 2018	Online rental listings, January to March 2018*
	Median Gross Rent	Average Asking Rent	Median Asking Rent
No bedroom/Studio	\$587	\$744	\$685
1 bedroom	\$677	\$795	\$775
2 bedrooms	\$873	\$897	\$975
3 bedrooms	\$1,090	\$960	\$1,350
4 bedrooms	\$1,377	N/A	\$1,650
5 or more bedrooms	\$1,646	N/A	\$2,300

* Sources: rent.com and zillow.com active listings for dwellings located within the City of Ypsilanti (listings were accessed from January 15, 2018 to March 15, 2018).

Because a strong majority of housing units in Ypsilanti (69.2%) are renter-occupied, and because renters in Ypsilanti have lower incomes, on average, than homeowners, renters are disproportionately affected by increasing housing costs. However, a significant proportion of homeowners in Ypsilanti are also affected. The ACS 2017 found that:

- 49% of all households in Ypsilanti are cost-burdened, meaning they spend >30% of their income on housing and may have difficulty affording necessities such as food, clothing, transportation, and medical care.
- Rates of housing cost burden in Ypsilanti are highest among renters (54.6%), followed by homeowners with a mortgage (29.2%) and homeowners without a mortgage (12.9%).
- Rates of housing cost burden are higher among lower-income Ypsilanti residents regardless of housing tenure.
- Ypsilanti has higher rates of cost burden than Ann Arbor and Washtenaw county overall.

A growing number of new residents, including students coming to Ypsilanti for college and people relocating from Ann Arbor in search of more affordable housing, has contributed to affordability pressures. The City's population growth has outpaced growth in housing stock since 2012, and there is no indication that this trend will change soon.

Rapidly increasing housing costs are especially consequential for renters with lower incomes, who face mounting obstacles to remaining in their homes and communities. One proxy measure for these pressures is the 20.8% eviction rate in the City of Ypsilanti, which is higher than the statewide average (17%) and nearly 10 times as high as in neighboring Ann Arbor (2.2%).²⁴

Problem Statement #2: Existing data and measures do not adequately capture the local situation with respect to housing affordability and accessibility.

There is a pressing need for improved measures and additional information to paint a more comprehensive picture of the nature and magnitude of housing affordability and accessibility challenges, and how it impacts specific populations, including seniors, people with low incomes, people with disabilities, and school-aged youth experiencing housing insecurity or homelessness.

Area median income (AMI), the measure used to determine eligibility for federal housing assistance, is calculated on a countywide or metropolitan area-wide basis. In counties and metropolitan areas where household incomes are relatively similar across communities, AMI helps direct affordable housing resources to households with the lowest relative incomes. In counties and metropolitan areas with significant income variation across communities, like Washtenaw County, the effect is different. Because Ann Arbor is significantly larger and more affluent than Ypsilanti, it exerts outsized influence on Washtenaw County's AMI, which is \$69,434.²⁵ (By comparison, median income in the City of Ypsilanti is \$36,982.) The continuing use of countywide AMI to determine eligibility for affordable housing assistance has the effect of

²⁴ [MICHIGAN EVICTIONS: Trends, Data Sources, and Neighborhood Determinants](#)

²⁵ ACS 5-year estimate, 2014-2018.

punishing very low-income (<50% AMI) and extremely-low income households (<30% AMI), the majority of which are located in Ypsilanti, by forcing them to compete for scarce rental assistance resources with households earning up to 80% of AMI.

List prices of rental housing fail to capture the full cost of renting. Securing rental housing often requires payment of non-reimbursable application, credit check, and/or administrative fees as well as proof of renter's insurance, a utilities deposit, and a security deposit equivalent to a full month's rent (which increases with rent). Collectively, these costs can pose a significant barrier for renters, yet they are seldom acknowledged by policymakers seeking to advance housing affordability.

List prices of for-sale housing similarly fail to capture total cost of homeownership. Down payment requirements, combined with recurring costs (e.g. mortgage insurance, homeowner's insurance, home maintenance, and property taxes) put home ownership out of reach for many people without substantial savings and/or high incomes.

Seniors: According to the 2010 census, seniors represent 13% of the U.S. population, and this is expected to grow to 20% by 2030. AARP/Harvard find that 90% of seniors plan to age in place. SEMCOG estimates that by 2035, the number of residents over 65 living in Ypsilanti will reach 5,335, which represents a 240% increase over the last measurement. It is clear that the need for affordable senior housing will continue to grow between now and 2035. However, few data are available regarding housing preferences and needs of seniors in Ypsilanti.

People with disabilities: According to the U.S. Census Bureau, nearly 1 in 5 Americans has a physical or mental impairment that limits one or more major life activities. By this broad definition, 32% of Ypsilanti residents have a disability, while 6.7% of Ypsilanti residents under the age of 65 (≈1400 residents) have a disability characterized by auditory, visual, cognitive, or ambulatory impairment. Disabilities -- and systemic discrimination against people with disabilities -- can limit economic activity and opportunity; nationwide, median income for people with disabilities is two-thirds of median income for people with no disability.²⁶ Within Ypsilanti, the areas with the highest concentrations of disabled residents also have the highest rates of poverty. However, there is no data available on the prevalence of housing insecurity among people with disabilities in Ypsilanti.

People experiencing homelessness or housing insecurity: While much effort has gone into developing standard definitions and metrics for housing affordability in the U.S., data and information gaps persist, especially with respect to homelessness and housing insecurity. According to the Washtenaw County Office of Community & Economic Development (OCED), 1,541 people experiencing homelessness in 2018 reported their last zip code as 48197 or 48198. People from Ypsilanti thus account for more than half (53%) of all those receiving

²⁶ US Census Bureau, 2015.

homelessness prevention, emergency shelter, rapid re-housing, or permanent supportive housing services. A 2018 survey conducted by Delonis Center found that 33% of clients listed Ypsilanti as their last place of residence, while approximately half (47.4%) of Ozone House clients listed 48198 or 48197 as the zip code of their last permanent residence. There is reason to believe that these figures underrepresent the true scale of homelessness in Ypsilanti and Washtenaw County. The SAWC estimates some 5,000 individuals are experiencing homelessness in Washtenaw County,²⁷ and the concentration of overnight shelters in Ann Arbor may lead people whose homelessness originated in Ypsilanti to report an Ann Arbor zip code where they have been staying more recently. Gaining a clear sense of the magnitude of homelessness in Ypsilanti remains a pressing priority.

Housing insecurity can be broadly defined as the condition of frequent moving, staying with friends or relatives, couch surfing, having difficulty paying rent/mortgage, living in an unstable neighborhood, overcrowding in the home, fleeing domestic violence, or spending more than 50% of household income goes toward housing costs. There is currently no federal definition by which to assess housing insecurity. However, based on ACS data on housing cost burden, it is estimated that approximately half of Ypsilanti residents could be experiencing some level of housing insecurity.


Homeless youth²⁸ face special obstacles; for example, they are unable to obtain housing vouchers or get on public housing waitlists until they are 18, and they lack the rental history required to qualify for renting in the private market. Former foster care youth, LGBTQ youth, and transition age youth (ages 18 to 24) are especially likely to experience homelessness and housing insecurity. The number of youth experiencing housing insecurity (including couch surfing or doubling up with friends or relatives) is presently unknown. *Fig 3* (below) shows the count of Ypsilanti Community Schools students experiencing homelessness by school year, from 2010-2011 to 2017-2018.²⁹

²⁷ <https://www.annarborshelter.org/annualreport>

²⁸ The U.S. Department of Education defines homeless youth as “youth who “lack a fixed, regular, and nighttime residence” or an “individual who has a primary nighttime residence that is a) a supervised or publically operated shelter designed to provide temporary living accommodations; b) an institution that provides a temporary residence for individuals intended to be institutionalized including welfare hotels, congregate shelters, and transitional housing for the mentally ill; or c) a public or private place not designed for, or ordinarily used as, a regular sleeping accommodation for human beings.” This definition includes both youth who are unaccompanied by families and those who are homeless with their families.

²⁹ [Ypsilanti schools gear up for large homeless student population](#)
[Washtenaw County grapples with barriers to ending youth homelessness](#)

Figure 3: Ypsilanti Community Schools Student Homeless Counts, 2010-2017



Problem Statement #3: Ypsilanti's old housing stock poses health, safety and accessibility challenges

While Ypsilanti's old and historic homes bring character to the City, they also present challenges. Most homes were constructed before contemporary health, safety, and accessibility codes were in place (see *Fig 4*, below). As a result, Ypsilanti residents face health risks from lead paint, radon exposure, and mold; high heating bills from poor insulation; and difficulty finding housing that will accommodate a disability.

Rental households are at increased risk for all of these factors, both because they may not be provided information about the home that an owner-occupant would have, and because they lack the right to make fixes or improvements to address housing quality concerns. Additionally, the oldest housing stock is concentrated in neighborhoods that have some of the highest rental occupancy rates. City rental code inspections do not include testing for problems like exposed lead paint, hazardous mold, or radon, and do not include standards for accessibility.

Figure 4: City of Ypsilanti housing by year of construction




As existing housing stock ages and little new housing is added, Ypsilanti's overall housing vacancy rate continues to decline. From 2012 to 2017, the homeowner vacancy rate decreased from 4% to 1%, and the rental vacancy rate decreased from 12% to 5% during the same period. Meanwhile, the number of housing units available in the City fell from 9,118 to 8,872.

Accessibility: Only 1 in 10 houses or apartments in Ypsilanti was built in the 1990s or later³⁰, when Fair Housing Act and building code updates began requiring some accessibility standards in new housing. As a result, only a few apartment complexes offer wheelchair accessible units, and houses often require modifications to doorways, bathrooms and kitchens to serve a resident with a disability. Given the proportion of owner-occupied to rental units in the city, it is important to create accessible *and* affordable options in both categories.

³⁰ U.S. Census Bureau, 2012-2016 American Community Survey 5-Year Estimates, "Selected Housing Characteristics"

Figure 5: Proportion of Ypsilanti residents with a disability by census tract



In addition to a general lack of accessible housing, there are few housing options adapted to the needs of seniors, many of whom live on modest fixed incomes and/or have limited physical mobility. Until 2017, Cross Street Village offered 104 housing units for seniors in Ypsilanti with incomes ranging from 20 to 40 percent of AMI. However, these units have been transitioned to market-rate housing over the past three years, resulting in a sizable loss of affordable housing for seniors (see Box 1).

Box 1:

Cross Street Village is the formerly affordable senior housing development that was incrementally converted to a market-rate complex starting in 2017. The developer of the building took advantage of a back-out clause in the agreement made to receive Low-Income Housing Tax Credit (LIHTC), despite the developer's initial pledge to keep it low-income senior housing for a term of 99 years. Residents of Cross Street Village demonstrated against the market-rate conversion on July 12th, 2017. Remaining low-income and disabled seniors have reported issues of negligence on the part of the owner, American Community Developers, to local and state representative's offices.

Heating and other systems: Older housing stock is typically poorly insulated and may be drafty, increasing household energy bills. This is of special concern in rental properties where tenants pay for heating but do not have the right to make energy efficiency improvements, removing the incentive for the property owner to make improvements. In some cases, the tenant does not have control of the heat, but must wait for the landlord to turn it on each year, creating discomfort and potential health problems. Other aging systems -- electrical, plumbing, HVAC, etc -- can also reduce quality of life for residents of rental properties.

Health and safety: *Lead poisoning* is a major health risk, especially for young children. 5 in 6 Ypsilanti homes are in buildings constructed before lead paint was banned for residential use in 1978. The Washtenaw County Environmental Health Department notes that over 1/3 of children (8 of 22) diagnosed with elevated lead levels in 2017 lived in Ypsilanti ZIP codes; 5 of those 8 lived in rental housing.³¹ No inventory exists of housing that has had lead risks abated by the owner, except in cases where abatement was legally required as a result of a child testing high for lead exposure.

Radon: About 40% of homes in Washtenaw County have radon above EPA recommended exposure limits³². Radon is a radioactive gas naturally occurring in soil, and risk of exposure is higher in homes that have dirt basements or crawl spaces, or have cracked foundations or basement floors--conditions common in older homes. Radon testing is easy and cheap, with test kits available for about fifteen dollars³³ from the Washtenaw County website, but there is not a legal requirement to test homes either in rental code or in for-sale units. Also, radon can change seasonally so a one-time reading is not always reliable.

Mold: High levels of household mold exposure can lead to respiratory and other health problems, and over 1 in 3 survey respondents reported having had concerns over exposure to mold in their home. However, there are no legal standards for mold detection or remediation at any level of government.

Data limitations and needs: Assessment of these challenges is difficult because of limited data; as noted, there are few legal requirements to test for or disclose many of these conditions. Survey responses show how frequently residents have experienced problems. Some of these conditions may warrant being added to the city's housing inspections or rental disclosure requirements even if there are no requirements for remediation.

Problem statement #4: Ypsilanti does not have a lot of land available to build new housing

Ypsilanti is sometimes considered "built-out"-- nearly all land in the city has already been developed, limiting the opportunity for new homes to be built. Much of the land that is currently vacant, like Water Street, is considered "brownfield," meaning past industrial activity has left behind contamination that adds cleanup costs to development. Other possible parcels have potential or actual wetlands on them.

The cost of environmental remediation and demolition, combined with the lack of available land to build on, makes adding residential density difficult. High construction costs and low supply compound the problem of finding affordable housing and building more units.^{34,35}

³¹ Email from County Health Department staff.

³² Conversation with Washtenaw County Health Department staff.

³³ Conversation with Washtenaw County Health Department staff.

³⁴ [The State of the Nation's Housing 2018](#)

³⁵ [Paying for dirt: Where have home values detached from construction costs?](#)

Most of Ypsilanti's residential areas have significant limits on what types of homes can be built, due to a combination of zoning restrictions (e.g. minimum building envelopes, setback requirements) and historic preservation requirements. Some barriers to construction of new affordable housing in Ypsilanti include: single-family residential (R-1) zoning (nearly 30% of land within the city is zoned R-1, which restricts residential density); Historic District Commission requirements; minimum parking requirements; and the existing family definition, which restricts the number of unrelated adults who may occupy the same housing unit. These barriers are discussed in greater detail under Problem Statement #5.

Since new housing is typically more expensive than existing housing -- especially in the Ann Arbor construction market, where labor costs are relatively high -- replacing older housing with new construction may exacerbate housing affordability issues.

Problem statement #5: Current and past policies contribute to our affordability and accessibility challenges (state level, local level)

Exclusionary zoning actions: Over the past 40 years, the City of Ypsilanti has used zoning changes to reduce the number of housing units in neighborhoods, explicitly working to limit multi-family housing in favor of owner-occupied single-unit properties. These actions have contributed to the loss of affordable rental apartments over time, while limiting the city's opportunity to create new housing. The current zoning ordinance also limits the potential development or conversion of smaller-scale or multi-unit housing through (1) accessory dwelling unit (ADU) restrictions (ADUs are allowed only in select zoning districts, namely CN, CN-Mid, and HC) and (2) residential lot requirements and building envelopes that effectively prevent the construction of smaller-scale homes (including tiny homes), except as an accessory use in select districts. (Some recent updates to the zoning ordinance, including the elimination of minimum parking requirements for single- and two-unit residences, are better aligned with the goal of housing affordability.)

Non-family occupancy caps: The City of Ypsilanti Zoning Ordinance limits the number of unrelated adults that may constitute a "family" living in a single dwelling. The City's regulation is stricter than in surrounding communities, leading to under-utilization of available housing units.

Neighborhood Enterprise Zone: The city has designated the neighborhoods around Harriet Street as a Neighborhood Enterprise Zone (NEZ), a State of Michigan program that offers property tax abatements for new home construction or renovations. The structure of NEZ abatements adopted by the Ypsilanti City Council grants preferential treatment (in the form of longer-duration tax incentives) to new purchasers of properties, which could accelerate displacement of existing residents. Only two NEZ certificates have been issued since the inception of the NEZ around Harriet Street; both were issued to new occupants/homebuyers. In combination with the NEZ, the city offered a number of empty lots for sale at the heavily

discounted price of \$1,000,³⁶ foregoing a public asset (buildable land) that could have been invested in the creation of permanently affordable housing.

Loss of LIHTC dedicated affordable housing: The federal Low-Income Housing Tax Credit (LIHTC) program offers tax credits to private real estate developers to create affordable housing. Because of how Michigan administered the state's allocation of credits in the early 2000s, the owners of several apartment complexes in Ypsilanti city and township have been able to shed their affordability requirements recently, leading to dramatic increases in rents. While the state has seemingly closed the loophole for newer LIHTC, this experience underscores the need for the City to scrutinize developers' use of state and federal programs to ensure the promised affordability is actually delivered.

C. Public input

Public engagement and representation emerged early on as key priorities for the committee. Because today's housing affordability and accessibility issues have historical roots in racist and exclusionary policies that range from redlining and racial steering to restrictive zoning and housing covenants, it is critical that people in historically marginalized groups have a voice in both the framing of the problem and the design of remedial policies and measures.

The committee designed and implemented a multi-stage public engagement process that consisted of:

- A **Housing Affordability & Accessibility Survey** to gather up-to-date information on the nature and magnitude of housing affordability and accessibility issues experienced by Ypsilanti residents. The Housing Survey, which was made available online and in hard copy at several locations throughout the City, was launched on December 5, 2018 and closed in February 2019. More than 600 responses were collected; a summary of survey results is included in **Appendix B**.
- **Key informant interviews** with three landlords of residential properties in Ypsilanti (one with a small number of rental properties, one with a moderate number of rental properties, and one with a large number of rental properties). Interviews were conducted while the Housing Survey was ongoing, and the input provided by landlords was used to paint a more complete picture of the factors that influence housing affordability and accessibility. A list of interview questions is included in **Appendix C**.
- An **Open Forum** to present the survey and interview findings to the public and to solicit public input on a preliminary set of housing affordability and accessibility strategies for the City of Ypsilanti. The forum, which was held at Riverside Arts Center on May 2, 2019, generated lively discussion on certain topics (e.g. rental inspections and quality of rental housing) as well as written and verbal feedback input on potential strategies.
- An **Ypsilanti Housing Strategies Survey** to gather quantitative feedback from Ypsilanti residents on the favorability of specific housing strategies in six key domains: (1)

³⁶ [City of Ypsilanti to sell its empty land for \\$1,000](#)

Renters' rights, (2) Sustainable development strategies, (3) Need-based assistance strategies, (4) Physical accessibility strategies, (5) Zoning strategies, and (6) Partnership and advocacy strategies. The Housing Strategies Survey was launched online on September 3, 2019 and closed on October 22, 2019. More than 360 responses were collected; a copy of the survey and a summary of its results are included in **Appendix D**.

- Finally, the committee welcomed public comment and input through its standing monthly meetings, held from January 2018 to May 2019.

Despite efforts to solicit input from a representative cross-section of Ypsilanti residents, the survey demographics indicate that some groups were underrepresented while others were overrepresented. Males, Black/African Americans, and renters were underrepresented in the survey by a significant margin.

III. Key findings:

Our major findings with respect to housing affordability are the following:

- Prices of both for-sale and rental housing are rising fast and show no signs of abating, in line with national trends.
- The most commonly used measures of housing affordability fail to capture the total cost of housing as experienced by most Ypsilanti residents, and especially those who earn the median income or less. Monthly rents do not capture the full picture with respect to the cost of rental housing; most rentals require a deposit equal to a full month's rent.
- Over half (54.6%) of Ypsilanti renters are cost-burdened with respect to housing, meaning that they spend more than 30% of their income on housing (ACS 2017). Data from the committee's Housing survey closely track data from the ACS on this point.
- Real estate investors -- some local, others from outside of the area -- who bought homes in Ypsilanti during the housing crisis in order to "flip" them have profited from increasing sales prices. Many Ypsilanti homeowners who purchased their homes at depressed prices (i.e. from 2008 to 2013) have seen their property values escalate rapidly since 2013, resulting in substantial growth in home equity.
- The flip side of these benefits to investors and newer homeowners has been a sharp decline in access to homeownership for Ypsilanti and other area residents who currently rent their homes. In addition, the boom-bust housing cycle -- by first displacing people with limited wealth and/or income from their homes through foreclosure or short sales and then making it difficult or impossible for them to afford another home in the same neighborhood -- has had a gentrifying effect that is especially visible in the southwest section of the City.
- The consequences of rising rents have been acutely felt by Ypsilanti residents, particularly those with lower incomes. Some of the disruptive effects have included frequent moves motivated by sharp rent increases; being forced to settle for poorly maintained rental units that are less accessible to public transportation and other essential amenities; displacement, especially among seniors and people with disabilities; housing insecurity; and homelessness.
- Source-of-income discrimination appears to be a problem for renters in Ypsilanti, with 9.3% of housing survey respondents indicating they have been denied housing based on their source of income.
- Protecting and advancing housing affordability and accessibility will require decisive and sustained action at multiple levels of government, including the municipal, county, state, and federal levels. Collaborating with policymakers and officials at other levels of government will be essential to ensuring that all people, no matter what age or income, can find a place to call home in Ypsilanti.
- One-size-fits-all solutions do not apply; we will need a combination of strategies that are tailored to the specific housing needs and preferences of Ypsilanti residents, including young people, seniors who wish to age in place and people with disabilities.

Our major findings with respect to housing accessibility are the following:

- Overwhelmingly, Ypsilanti's housing stock is older, predating the ADA and Fair Housing Act, with only 1 in 10 houses or apartments in Ypsilanti built since 1990.³⁷ Only a small portion of units offer wheelchair accessibility, and houses often require modifications to doorways, bathrooms, and kitchens to serve a resident with a disability.³⁸
- The City of Ypsilanti 2012-2016 census statistics reported that 6.7% of persons under 65 have a disability, or about 1400 disabled persons (auditory, visual, cognitive, ambulatory impairments).³⁹
- Accessibility is not limited to the needs of wheelchair users. According to broadest definitions of disability, 32% of Ypsilanti residents are living with a disability of some type.⁴⁰ The highest concentrations of residents with a disability are in areas with the least income.
- AARP/Harvard reports that 90% of seniors plan to age in place, and SEMCOG estimates the over 65 demographic will increase in our area by 240% by 2035. Given the proportions of owner-occupied to rental units in the city, it is important to create accessible options in both categories.
- Results from our Housing Affordability & Accessibility Survey bear out these basic facts. Two-thirds of survey respondents (66.7%) reported that their homes have no accessibility features, and more than 1 in 4 reported that barriers to physical accessibility in a home had limited their quality of life.
- Beyond those experiencing a disability, many survey respondents said that accessibility is a consideration in the selection of their next residence. Over half of respondents said a ramp or step-free entrance would be a factor in their choice of a home, and more than 1 in 5 said that every accessibility option listed in the survey -- from parking, to bathroom and kitchen amenities, to doorways and elevators -- would be a desirable factor. Furthermore, there was broad support for an Affordability & Accessibility Ordinance.

³⁷ U.S. Census Bureau, 2012-2016 American Community Survey 5-Year Estimates, "Selected Housing Characteristics"

³⁸ While there are several of these facilities that offer these amenities, they often have limited availability. Namely, Cross Street Village, River Rain Apartments, 422 Pearl, 420 Emmet, 404 N Huron, Peninsular Place, UGA Townhomes, and recently renovated Ypsilanti Housing Authority units.

³⁹ Those numbers exclude seniors and use a definition of disability ("Serious difficulty with four basic areas of function -- hearing, vision, ambulation, cognition") that could be expected to underestimate numbers determined by other methods

⁴⁰ The Fair Housing Act defines a person with a disability as an individual for whom a physical or mental impairment limits one or more major life activities. This

IV. Committee recommendations:

In our work as a committee, we emphasized the lived experience and observations of residents of Ypsilanti as forms of expertise that are central to understanding and addressing the complex problems of housing affordability and accessibility. Our recommendations were generated in large part through the aggregation of community expertise sought through public engagement and inquiry.

Based on input and feedback from 361 respondents who reviewed the 26 proposed housing strategies included in the committee's Housing Strategies survey, our committee recommends that the City review and seek to implement 11 proposals. The selected proposals reflect the input of Ypsilanti residents who engaged with this survey and are consistent with the committee's analysis of strategies that, if implemented, will respond to pressing housing needs and start to correct historical inequities in Ypsilanti.

In the context of the Covid-19 pandemic and civil unrest due to systemic racial inequities, we share a conviction that it is more important than ever for local governments to proactively address the needs and interests of historically marginalized communities. With a view to accelerating action, we offer a prospective pathway and timeline for rolling out housing policies.

The recommended proposals are preferred across demographics with a notable difference between renters and homeowners; on a scale of 1 to 5, renters assigned almost all proposals a higher score (an average of ~4.4 compared to an average score of ~3.6 given by homeowners, as detailed in Table 3).

Table 3: Renter vs. homeowner ratings of housing strategy proposals

Proposal	Avg. score, renters (n=126)	Avg. score, homeowners (n=220)	Difference
Protect renters from improper eviction	4.54	3.33	Renters +36%
Give renters with criminal records a fair chance	4.15	3.35	Renters +24%
Give tenants first opportunity to purchase property from owner	4.52	3.78	Renters +20%
Build on public land	4.44	3.54	Renters +25%
Establish a community land trust	4.29	3.29	Renters +30%
Enact an inclusionary housing ordinance	4.66	3.42	Renters +36%
Enact an affordability & accessibility ordinance	4.75	3.60	Renters +32%
Incentivize co-op conversions	4.37	3.56	Renters +23%
Build a homeless shelter in Ypsilanti	4.57	3.66	Renters +25%
Install public toilets and benches in our parks	4.41	3.68	Renters +20%
Establish a Minor Home Repair Program	4.60	4.11	Renters +12%
Fund local agencies that provide need-based assistance	4.67	3.88	Renters +21%
Allow existing homeowners living South of Michigan Ave to qualify for the same tax breaks as new home-buyers	4.40	3.95	Renters +11%
Create a landlord incentive program to stabilize rent	4.46	3.58	Renters +25%
Assist low-income residents with home-buying	4.61	3.80	Renters +21%
Adopt a Visitability Ordinance	4.38	3.34	Renters +31%

Launch a Universal Design Program	4.23	3.48	Renters +22%
Change single family zoning districts to include multiple family dwellings	4.35	3.08	Renters +41%
Lift the limit on non-related persons living in a single dwelling	4.41	3.42	Renters +29%
Increase housing stock by allowing Accessory Dwelling Units	4.37	3.89	Renters +12%
Increase housing stock by accommodating tiny homes	4.39	3.99	Renters +10%
Change parking space requirement for new housing developments	3.73	3.22	Renters +16%
Advocate for rent control	4.54	3.37	Renters +35%
Ask local universities to invest in the Ypsilanti Housing Trust	4.63	4.19	Renters +11%
Ask the Office for Community and Economic Development (OCED) of Washtenaw for funding toward housing in Ypsilanti	4.57	3.99	Renters +15%
Advocate for the authority to regulate Airbnb (and other short-term rentals)	3.91	3.39	Renters +15%
All proposals pertaining to renters' rights or sustainable development strategies	4.42	3.61	Renters +19%

A. Priority Recommendations

Our committee recommends adoption of the following proposals, organized by category:

Renter's Rights: These are recommendations that the City of Ypsilanti could implement to expand renters' rights and protect them from discrimination.

1) Tenant Right of First Refusal

Proposal: Give tenants first opportunity to purchase properties from the property owner by enacting a 'Tenant Right of First Refusal' ordinance. The ordinance would grant tenants both advance notice of a planned sale and a specified time period within which to purchase a property, should the owner wish to sell it.

Tenant Right of First Refusal can set in motion a process that leads to the successful transfer of ownership—either to the residents or to another entity willing to preserve the long-term affordability of the property. It has been successful in producing a number of resident-owned properties and partnerships among residents and nonprofits in Washington, DC and other cities.

2) Just Cause Ordinance

Proposal: Protect renters from improper eviction by enacting a 'Just Cause' ordinance to protect renters from eviction and displacement for improper reasons.

The Michigan Act of 1933 Just Cause Eviction statutes protect tenants from wrongful and/or retaliatory eviction. They limit a landlord's ability to evict tenants to specific reasons, such as failure to pay rent or for violation of the lease terms. A city Just Cause

Ordinance could extend the protections of Michigan Act 1933 to lease renewals, and bar rental property owners from refusing to renew a tenant's lease without 'just cause'.

Sustainable Development: These are recommendations that the City of Ypsilanti could implement to prioritize the sustainable development of affordable and accessible housing, as well as to provide safe shelter to all residents.

3) **Affordability and Accessibility Ordinance**

Proposal: Enact an Affordability & Accessibility Ordinance that (1) defines the parameters for affordable and accessible housing based on Ypsilanti's median income rather than countywide median income and (2) requires new housing developments that receive public funding or tax subsidies to include a percentage of affordable and accessible units in line with Ypsilanti's need.

Enacting an Affordability Ordinance would help set the stage for future adoption of an inclusionary housing policy by tying affordability thresholds to Ypsilanti's median income rather than the median income of Washtenaw County as a whole. This would help ensure that affordable housing subsidies and resources in Ypsilanti are adapted to local conditions and directed to those who need them most.

Disabled residents in Ypsilanti are predominantly low-income and many live in older units within the City. An Accessibility Ordinance based on these figures would take the needs of disabled residents into account when determining new construction and rehabilitation requirements.

4) **Homeless Shelter**

Proposal: Build or establish an overnight shelter in Ypsilanti to help meet needs of residents experiencing homelessness.

Ozone House's newly constructed 26-bed youth shelter on North Huron River Drive is now serving homeless youth, but Ypsilanti does not have an overnight shelter for adults and families experiencing homelessness. Adding a shelter for adults and families would help ensure that everyone has access to a safe place to stay in times of acute need.


5) **Community Land Trust**

Proposal: Establish a Community Land Trust (CLT) to promote long-term housing affordability and accessibility through community control of land.

Community Land Trusts are nonprofit, community-based organizations designed to ensure community stewardship of land. They combine democratic ownership of land with private ownership of structures on the land. Most CLTs limit the rate at which the structures they manage can appreciate each year, so that the affordability of those

structures is preserved over time. CLTs can be interspersed throughout one or more neighborhoods, and can include businesses and single- and multi-family homes.

There are multiple ways of funding and running a CLT. The City of Ypsilanti could provide financial incentives for the formation of independent, neighborhood-based CLTs in core neighborhoods and center districts. It could also advocate with Washtenaw County and the City of Ann Arbor for the establishment of a countywide, publicly funded CLT like the one in Orange County, North Carolina. The infographic below from the Democracy Collaborative describes the basic attributes of a CLT.



Need-based assistance: These are recommendations that the City of Ypsilanti could implement to support low-income residents' home improvement and housing stability.

6) Assist low-income residents with home-buying

Proposal: Assist low-income residents who wish to purchase a home by offering credit improvement services, and mortgage down-payment assistance.

Seven in ten households in Ypsilanti are (predominantly low-income) renter households—a significantly higher percentage to comparable college towns of its size. The city could provide assistance to low-income households who wish to buy homes, to reduce barriers to homeownership and promote housing stability.

7) **Minor home repair**

Proposal: Establish a Minor Home Repair Program to assist with the cost of essential home repairs for eligible low-income and disabled homeowners. Eligible repairs could include roof replacement, plumbing replacement, mechanical or electrical replacements, ADA ramp installation or repair, door modifications, and lead or mold remediation.

Cities in the State of Michigan can choose to offer small grants for home improvements. For example, the City of Battle Creek has a Minor Home Repair Program that provides eligible low-income homeowners with up to one-half of the cost of roof replacement, or other exterior code compliance or health and safety issues.

Accessibility: In addition to enacting an Affordability and Accessibility Ordinance as recommended above, the City of Ypsilanti could enact a Visitability Ordinance to expand physical accessibility of housing and public life in Ypsilanti.

8) **Visitability ordinance**

Proposal: Adopt a Visitability Ordinance to ensure that newly constructed homes incorporate basic accessibility features that make it easier for mobility-impaired people to visit or live in Ypsilanti.

A home can be considered “visitable” if it has: (1) at least one no-step entrance; (2) doors with 32 inches of clear passage space; and (3) a bathroom on the main floor that is wheelchair-accessible. Some US cities have adopted mandatory visitability ordinances for all newly built homes; others have adopted visitability ordinances for houses built with public funding or tax incentives.

Zoning: These are zoning recommendations that the City of Ypsilanti could implement to expand density and housing affordability through land use policy.

9) **Lift the limit on non-related adults per dwelling**

Proposal: Increase the number of unrelated individuals who may reside together in a dwelling by changing the Zoning Ordinance definition of Family to include a limit of two unrelated persons for each bedroom in the dwelling.

The current City of Ypsilanti Zoning Ordinance definition of a “family” limits the number of unrelated individuals that may occupy a single-family home as follows: “A group of

persons, none of whom are related to each other by blood, marriage, or adoption, who reside together in a single dwelling unit, provided that the total number of occupants in such group shall not exceed three, except in the MD district and in any permitted residential uses in any corridor district the total number of occupants in this group shall not exceed four, unless otherwise provided for in this chapter; or". This section may be updated to "A group of persons, none of whom are related to each other by blood, marriage, or adoption, who reside together in a single dwelling unit, provided that the total number of occupants in such group shall not exceed two for each bedroom in the dwelling; or"

Advocacy and partnership: These are proposals that the City of Ypsilanti could advocate for on the state, county, and local level to expand and sustain housing affordability in Ypsilanti and beyond, through partnership and/or legislative change.

10) **Rent Control**

Proposal: Advocate with state lawmakers to grant municipalities the authority to cap annual rent increases.

Michigan law currently prohibits local government units from enacting or enforcing rent control policies. Two bills introduced in 2017 (House Bills 4686 and 4687) would (1) revise the law to create an exception to the rent control prohibition and (2) give local governments the power to prevent landlords from charging tenants that have a disability or elderly tenants more than 50 percent of their income in rent. Another approach to capping rent increases would be to allow rents to appreciate by a fixed percentage each year; for example, Oregon recently passed a statewide rent control bill that caps annual rent increases at inflation plus 7 percent.

11) **Ask Universities to invest in Ypsilanti's Housing Trust Fund**

Proposal: Advocate for the University of Michigan and Eastern Michigan University to invest in the Ypsilanti Housing Trust Fund and to actively support other county-wide housing affordability measures.

Many reports, including the 2014 OCED housing report, point to Ann Arbor's increasing rental rates driving the displacement of Ann Arbor residents to Ypsilanti. Asking universities and other large employers to fund the Ypsilanti Housing Trust would offer these entities the opportunity to address the harms of displacement and support housing equity in Ypsilanti.

Table 4 (below) provides a visual overview of alignment between the above recommendations and the five problem statements introduced in **section II.B** of this report.

Table 4: Cross-mapping of recommendations and problem statements

	The cost of housing is increasing quickly.	Existing data and measures do not adequately capture the local situation with respect to housing affordability and accessibility.	Ypsilanti's old housing stock poses health, safety, and accessibility challenges.	Ypsilanti does not have a lot of land available to build new housing.	Current and past policies contribute to our affordability and accessibility challenges (state level, local level).
Tenant Right of First Refusal	✓	✓		✓	✓
Just Cause	✓	✓			✓
Affordability and Accessibility Ordinance	✓	✓	✓	✓	✓
Homeless Shelter		✓			✓
Community Land Trust	✓	✓		✓	✓
Assist low-income residents with home-buying	✓	✓	✓		✓
Minor home repair		✓	✓	✓	✓
Visitability ordinance		✓	✓	✓	✓
Lift the limit on non-related adults	✓	✓		✓	✓
Rent Control	✓	✓		✓	✓
Ask Universities to invest in Housing Trust Fund	✓	✓	✓	✓	✓

B. Proposed pathway and timeline for implementation

In the context of the Covid-19 pandemic and civil unrest due to systemic racial inequities, we share a conviction that it is more urgent than ever for local governments to proactively address the needs and interests of communities under duress. With a view to accelerating action, we

offer a prospective three-phase pathway and timeline for rolling out housing policies and programs over the next 10 years.

Phase One (current Budget year)

Make the Ypsilanti Housing Trust permanent: Assure a sustainable funding source for housing affordability and accessibility by formalizing and making permanent the City of Ypsilanti Housing Trust Fund started by Councilmember Pete Murdock and nourishing it with an annual contribution of no less than \$100,000 from the City's general fund.

Allocate staff time to housing affordability and accessibility: Allocate a significant portion of an existing staff member's time to the coordination and monitoring of City housing affordability and accessibility policy and to liaising with other units of government and partners on housing affordability and accessibility.

Draft and implement the Tenant Right of First Refusal ordinance (Strategy 1), the Just Cause Ordinance (Strategy 2), the Affordability and Accessibility Ordinance (Strategy 3), the Visitability Ordinance (Strategy 8), and the Zoning Ordinance text amendment to increase the number of non-related adults who may occupy a single dwelling (Strategy 9) from three total to two persons per bedroom.

Conduct a public outreach campaign to raise awareness about tenant rights and protections in the City. Property managers and tenants should be educated about the Tenant's rights brochure/handbook requirement implemented in 2018, as well as their protection from source-of-income discrimination (including housing vouchers and student loans) and protections around criminal history as stipulated in Ypsilanti's Non-Discrimination Ordinance. Finally, the campaign presents an opportunity to notify tenants and property managers about the resources available to them -- at the local, county, and state levels -- for home repair,

Begin advocating for State legislation to expand local authority to regulate rent increases (Strategy 10) and for local university contributions to the City of Ypsilanti Housing Trust Fund (Strategy 11).

Finally, while we have not included broader rezoning actions in our official recommendations, we would nonetheless encourage the Planning Commission to **consider additional changes to the Zoning Ordinance** to reduce restrictions on construction and/or conversion of multi-unit homes, accessory dwelling units, and smaller-scale homes.

Rationale: The recommendations for Budget Year 2020 face relatively few barriers to implementation, as they modify existing codes or ordinances. The Just Cause ordinance and zoning text amendment to increase the limit on non-related adults could immediately increase housing security for residents at risk of eviction and/or discriminatory action. The Tenant Right of First Refusal ordinance would help slow or stem another rapid transfer of homes to speculative investors in the case of an economic slowdown or crisis. The Visitability and

Affordability and Accessibility Ordinances are recommended with a view to ensuring that future development is adapted to local needs and conditions. Advocating for and/or implementing a rent control ordinance at the city level (that would remain non-enforceable until State legislation changes) is a means of signaling that the City of Ypsilanti has interest in changing State restrictions on rent control. Securing annual funding commitments from local universities for the Ypsilanti Housing Trust Fund would be an important step towards acknowledging and making amends for those institutions' outsize role in driving up housing costs and housing inequity in the area, including by enrolling large numbers of students without capacity -- or a viable plan -- to house them.

Phase Two (Budget year 2021)

Allocate \$100,000 from the 2021-2022 budget to the Ypsilanti Housing Trust Fund. As communities across the U.S. re-evaluate their budget priorities in light of the nationwide critique of police brutality and police-related public expenditures, we encourage the City of Ypsilanti to prioritize housing affordability through a standing annual contribution of \$100,000 to the Ypsilanti Housing Trust Fund. These funds could be reallocated from the Ypsilanti Police Department budget (which currently accounts for 24% of the total City budget) or from the funds that were set aside for the construction of a train platform. Reorienting funding to housing and other essential services would provide for both a progressive financial policy change and material change toward public safety.


Create a diversified funding strategy for the Ypsilanti Housing Trust Fund. We recommend that the City create a sustainable funding plan incorporating diversified funding sources. These could include contributions from the University of Michigan, Michigan Medicine, and EMU; Ann Arbor-based businesses with large shares of employees who reside in Ypsilanti; the American Center for Mobility (assuming future growth of its operations and local employment rolls); owners of short-term rental properties in Ypsilanti; and real estate investors with ownership of 100 or more housing units in Ypsilanti.

Draft an affordability-focused property acquisition plan that would go into effect in the event of another housing crisis resulting in a surge of foreclosures of multi-unit residences. The aim of this plan would be to ensure that such properties can be converted to sustainable affordable and accessible use, either in partnership with a local housing non-profit or through the launch of a Community Land Trust.

Introduce a home-buying assistance program (Strategy 6) and the Minor home repair program (Strategy 7).

Phase Three (Budget year 2022-2030)

Create and invest in institutions that promote community stability and build toward long range sustainable housing goals.⁴¹ Pursue affordability and accessibility-focused collaborations at the county and regional levels, with a view to leveraging resources from outside of the City of Ypsilanti. These would include the establishment of a Community Land Trust (Strategy 5) and the construction or establishment of an overnight homeless shelter (Strategy 4).



C. Gaps and Limitations:

Representation: Despite efforts to solicit input from a representative cross-section of Ypsilanti residents, the survey demographics indicate that some groups were underrepresented while others were overrepresented. Males, Black/African Americans, and renters were underrepresented in the survey by a significant margin. This could be suggestive of a general underrepresentation of these groups in City government, non-profits, and other entities that were represented on our committee, and we encourage the City to monitor and prioritize representation in all housing-related actions that it undertakes.

Short-term rentals: The short-term rental market in Ypsilanti poses a potential threat to future housing affordability, since it reduces the supply of long-term rental housing. Our report stops

⁴¹ [Trickle Up Housing: Filtering Does Go Both Ways](#)

short of making recommendations vis-a-vis short-term rental properties. However, preserving local government authority to regulate short-term rental uses under State law is an essential priority in the short term, as it will provide the City with better options if and when the number of short-term rentals grows.

Senior housing: While seniors who own their homes in Ypsilanti would benefit from our recommendations for need-based assistance programs, our report does not adequately address the need for affordable senior housing. One way in which the City could respond more fully to the housing needs of seniors would be through the establishment of a Community Land Trust and the designation of some housing within that Trust as senior housing.

Appendix A: Housing affordability and accessibility committee charter

COMMITTEE CHARTER: Citizen Committee on Housing Affordability & Accessibility

Adopted December 20, 2017

Background

In October 2013, the Planning Commission of the City of Ypsilanti adopted a new Master Plan (also referred to as the “Shape Ypsi” Master Plan), a hybrid land use/policy plan intended to guide development, redevelopment and preservation in the City over a 20-year horizon. It provides the framework on which the City’s Zoning Ordinance is based and also contains guidance for other areas of civic governance, such as capital improvements, non-motorized transportation and development of publicly-owned land.

Two of the guiding values set forth in the Master Plan are “Diversity is our strength” and “Anyone, no matter what age or income, can find a place to call home in Ypsilanti.”

In the four-plus years since the 2013 Master Plan was adopted, issues of housing affordability and accessibility have surfaced repeatedly during Planning Commission proceedings (which include reviews of site plans and special use applications). Rents are rising, in some cases so sharply that renters have been priced out of the City. Barriers to physical accessibility, common among Ypsilanti’s older homes, continue to limit housing options for people with a disability.

These realities conflict with the Master Plan guiding values cited above.

By statute, the Planning Commission is required to review the Master Plan at least once every five years and to make updates as deemed necessary.

I. Purpose

The Citizen Committee will review and update the City of Ypsilanti’s 2013 Master Plan with a focus on preserving and enhancing housing affordability and accessibility in keeping with the guiding values of the Master Plan. The Committee will develop and issue recommendations for specific land use and policy changes for consideration by the Planning Commission and (upon invitation) City Council.

II. Committee Type

Per Planning Commission bylaws, “the Commission, Chair or City Planner may establish and appoint citizen committees with the consent of the Commission. The purpose of the citizen committee is to be able to use individuals who are knowledgeable or expert in a particular issue before the Commission or to better represent various interest groups.”

The Citizen committee is a “special” committee of the Planning Commission (as opposed to a standing committee). It is formed to serve for a limited time and will be dissolved once the tasks and responsibilities assigned to it are complete.

III. Membership

The committee will be comprised of:
Up to four (4) members of the Planning Commission
One member of the Human Relations Commission
One member of the Sustainability Commission

One member of the Ypsilanti Housing Commission board
One representative of EMU
One representative of Defend Affordable Ypsi
One representative of Ann Arbor Center for Independent Living
One representative of Avalon Housing
One representative of civic affairs organization at the county or state level
One Ypsilanti owner-occupant
One Ypsilanti business owner (and employer)
One lessor of rental properties in Ypsilanti
Up to two members of the community at large

All members will be residents of the City. A guiding principle in recruiting and selecting individuals to serve on the committee will be the degree to which the members, as a whole, represent the diversity of the Ypsilanti community, both demographically (in terms of income, race or ethnicity, age group and ward) and with respect to affordability and accessibility-related interests.

Organizations represented on the committee may elect to rotate their representative as appropriate to accommodate the thematic focus of work sessions. Participation is voluntary, and any organization may opt out of committee participation at any time.

All members shall have equal voice and standing with respect to the proceedings and recommendations of the Committee.

The Planning Department of the City of Ypsilanti will provide a staff advisor to the Committee.

IV. Chairperson

The Chair of the Planning Commission shall serve as the Chairperson of the Citizen Committee and will designate another committee member to chair work sessions in her absence.

V. Activities, Duties & Responsibilities

- Drawing on the most up-to-date quantitative and qualitative data and resources available, assess the current situation with respect to housing affordability and accessibility in Ypsilanti and Washtenaw County
- Analyze underlying barriers to affordability and accessibility at the municipal, county, state and national levels
- Study existing affordability and accessibility strategies and models (local and non-local)
- Identify additional strategies and models for increasing affordability and accessibility
- Rate strategies based on their probable impact, feasibility and acceptability in Ypsilanti
- Develop written land use and policy recommendations for adoption and implementation
- Present recommendations to Planning Commission and (upon invitation) City Council

Appendix B: Housing Affordability & Accessibility Survey Questions & Results

Housing Affordability & Accessibility Survey Results

October 2018 – January 2019
City of Ypsilanti

The survey was published online (via Google Forms) and made available in hard copy at several locations throughout the City of Ypsilanti. Of 604 total responses received, more than 500 were submitted online.


Limitations: Because non-probability sampling was used, we were unable to calculate confidence intervals and margins of error. In addition, several groups were underrepresented or overrepresented in the survey, compared to their relative size as reported by the 2017 American Community Survey (ACS). See comparisons below.

Underrepresented (Survey vs. ACS)

Black/African American (13.5% vs. 30.3%)
Male (25.4% vs. 52.6%)
Under 18 years (7% vs. 13.6%)
18-24 years (15.1% vs 25.1% age 20-24)
Hispanic (3.3% vs 4.5%)
Asian (2.4% vs. 3.5%)


Overrepresented (Survey vs. ACS)

White/Caucasian (77.5% vs. 66.9%)
Female (63.6% vs. 47.4%)
25-34 years (39.9% vs 18.2%)
35-44 years (21.5% vs 7.8%)
45-54 years (12.7% vs. 7.3%)




How long have you lived in the City of Ypsilanti?

604 responses




On average, how much do you spend on housing-related costs each month?

600 responses




After paying your monthly housing costs, which of the following are you able to afford:

548 responses




Approximately what share of your gross (pre-tax) monthly income do you spend on the above housing-related costs?

597 responses




Over the past 4 to 5 years (since 2014), would you say your housing costs in the City of Ypsilanti have:

590 responses




By how much have your monthly housing costs changed since 2014?

395 responses




What caused the change in your housing costs since 2014?



Do any of the following describe your current or most recent housing situation? (select all that apply)

530 responses




Which of the following best describes your current or most recent home in the City of Ypsilanti?

602 responses




Which of the following best describes your current housing situation?

604 responses




Do you currently receive housing assistance (such as housing choice vouchers or subsidized housing) through federal, state or local government?

551 responses




Which of the following features does your current or most recent home have to make it accessible to people with a disability?

520 responses




Which physical accessibility features will you take into consideration in choosing your next home (whether for y...y and friends who visit you at home)?

323 responses




On a scale of 1 to 10, how satisfied are you with your current housing situation?

600 responses




Which housing quality issues have you experienced in the City of Ypsilanti?




Would you feel comfortable asking your current landlord or housing provider to correct a quality-of-life issue (e.g. pests, physical access issues)?

540 responses




Would you like to live in the City of Ypsilanti 3 to 5 years from now?

604 responses




If the cost of housing remains as it is today, do you see yourself living in the City of Ypsilanti 3 to 5 years from now?


602 responses



If they were available in Ypsilanti, which types of homes would you consider living in in the next 3-5 years?




If they were available in Ypsilanti, which types of homes would you consider living in in the next 3-5 years?




Have you ever have been denied housing or evicted from housing due to any of the following in the City of Ypsilanti:

460 responses



Have you ever been evicted or have you ever moved to avoid eviction due to rent increases you could not afford to pay?

520 responses




Appendix C: Landlord Interview Questions

1. Number of units owned/managed?
2. Rent range of units by bedroom size?
3. Types of units rented (size and type – townhouse, apartment, duplex, single family home)?
4. Do any of your units have any accessibility features, such as no-step entry, wide doors, roll-in showers, grab bars or ramps? Do you have a formal process for addressing these types of requests?
5. Why change rents? How often? On a set schedule?
6. What do you take into consideration when setting rent prices? (utilities?)
7. Do you allow renters with felony convictions? Why or why not? Experience?
8. What types of units are most in demand? In what size units do you experience the greatest vacancy?
9. Do you accept housing subsidies, such as Section 8? Why or why not? Experience?
10. How many eviction filings and actual evictions do you have in a typical year? What's the primary cause?
11. What's your turnover rate? What percentages of tenants renew leases?
12. Do you have a formal process for addressing tenant maintenance and emergency concerns?
13. Is there anything the city could do to facilitate adding accessibility features?

Appendix D: Housing Strategies Survey Questions & Results


Which age group best describes you?

361 responses




Which of the following races/ethnicities do you identify as (select all that apply)?

361 responses




Gender:

361 responses




Do you identify as transgender?

361 responses




Are you or a member of your household a part of the LGBTQ (lesbian, gay, bisexual, transgender, queer) community?

361 responses




Do you identify as living with a disability?

361 responses



Which area of Ypsilanti do you currently reside in?

361 responses




- Ward 1: See map below
- Ward 2: See map below
- Ward 3: See map below
- Ypsilanti Township
- Pittsfield Township
- Superior Township
- Ingham county
- Right outside of ward 1

▲ 1/2 ▼

Which of the following best describes your income in the past 12 months?

361 responses




- Less than \$10,000
- \$10,000 - \$14,999
- \$15,000 - \$19,999
- \$20,000 - \$24,999
- \$25,000 - \$29,999
- \$30,000 - \$34,999
- \$35,000 - \$39,999
- \$40,000 - \$44,999
- \$45,000 - \$49,999
- \$50,000 - \$59,999
- \$60,000 - \$74,999
- \$75,000 - \$99,000
- \$100,000 or more

Half of respondents

Which of the following best describes your current housing situation?

361 responses



- I rent my home
- I own my home
- I'm homeless (living on the streets, in...)
- I live with a parent/guardian
- Live with friend
- I want to take this survey without defin...
- Multigenerational living with matriarc...
- I rent apartment from Barnes and bar...


▲ 1/2 ▼

SECTION 1: RENTERS' RIGHTS

1. Protect renters from improper eviction

proposal rating:
360 responses


Proposal: Enact a 'Just Cause Eviction' ordinance to protect renters from eviction for an improper reason. Just Cause Eviction statutes protect tenants from wrongful eviction. They limit a landlord's ability to evict tenants to certain reasons, such as failure to pay rent or for violation of the lease terms.



2. Give renters with criminal records a fair chance

proposal rating:
361 responses


Proposal: Enact a 'Ban the Box'/'Fair Chance' ordinance to protect renters with criminal records by restricting landlords from asking about criminal history on rental applications. Detroit recently decided to Ban the Box in another category: housing. Under Detroit's new ordinance, landlords with portfolios of five or more units are no longer allowed to ask questions about criminal history on housing applications.



3. Give tenants right of first refusal

proposal rating:
361 responses

Proposal: Enact a 'Tenant Right of First Refusal' ordinance that will allow tenants to have a certain notice period and time to purchase their properties, should the owner wish to sell their units. Tenant Right of First Refusal can set in motion a process that transfers property ownership either to residents or to another entity willing to preserve the long-term affordability of the property. It has produced a number of resident-owned properties and partnerships among residents and nonprofits in Washington, DC.



Renters' rights: Priority ranking

1. Protect against improper eviction (52.7% of respondents)
2. Give tenants right of first refusal to purchase properties (39.6% of respondents)
3. Give renters w/criminal records a fair chance (38.8% of respondents)


SECTION 2: SUSTAINABLE DEVELOPMENT

Build on public land

proposal rating:

360 responses

Proposal: *Prioritize using public land for public good—build affordable & accessible housing on the available public lands in the City of Ypsilanti (such as Water St. and 220 N Park). Other possible uses of public land for public good: incentivize construction of an affordable grocery store to address Ypsilanti's food desert, build a recreation center for resident youth and adults, or establish Community Land Trust (see below) on available public land.*




Establish a community land trust

proposal rating:

357 responses


Proposal: *Establish a Community Land Trust (CLT) to promote long term housing affordability & accessibility through community control of land. CLTs are nonprofit, community-based organizations designed to ensure community stewardship of land. CLTs combine democratic ownership of land with private ownership of the structure on the land in order to maintain long term housing affordability. CLTs can be interspersed throughout a neighborhood, and can include rental homes and businesses. The infographic below describes what a CLT is in more detail.*



Enact an inclusionary housing ordinance

proposal rating:
360 responses


Proposal: Enact an Inclusionary Housing ordinance to require private developers include a certain percentage of units at below market rate. Inclusionary zoning requires (or incentivizes) private developers to designate a certain percentage of the units in a given project as below market rate. In D.C. and around the country, inclusionary housing is an increasingly popular way to produce affordable housing through the private market—it is one of the main tools cities have for maintaining neighborhood diversity, and keeping high-opportunity areas affordable.



Enact an affordability & accessibility ordinance

proposal rating:
359 responses

Proposal: Enact an Affordability & Accessibility Ordinance to 1) Define the parameters for affordable & accessible housing based on Ypsilanti's Area Median Income (AMI) and 2) Require new housing developments to include a percentage of affordable and accessible units based on Ypsilanti's need. An Affordability Ordinance would enhance a future inclusionary housing policy by setting affordability rates based on Ypsilanti's AMI, thus acting in consideration of income disparity and segregation between Ypsilanti and Ann Arbor.




Incentivize co-op conversion

proposal rating:

361 responses

Proposal: Create a legal framework incentivizing co-operative housing conversion and assist tenants in the purchase of rental units for the purposes of creating affordable co-operative housing.

Cooperative housing is a type of home ownership—it is formed when people join on a democratic basis to own or control the housing and/or related community facilities in which they live. Co-operative housing usually includes an apartment building or buildings. Ann Arbor has many co-operative housing options via the Inter-Cooperative Council (ICC) and others.




Build a homeless shelter in Ypsilanti

proposal rating:

361 responses

Proposal: Build a shelter in Ypsilanti to help meet needs of residents experiencing homelessness.


Ann Arbor's homeless shelter, The Delonis Center, has 50 resident beds this year (down from 77 beds in 2018) and is serving a significant percentage of people who identify their last address as being in Ypsilanti. At the same time, reports from Ypsilanti Community Schools and Eastern Michigan University show increased rates of student homelessness. A youth shelter, Ozone House, is currently under new construction. Ypsilanti does not currently have an overnight shelter for adults.



Install public toilets and benches in our parks

proposal rating:
361 responses

Proposal: Install high-quality public toilets and napping benches in our parks for the use of the general public, including residents experiencing homelessness. Ypsilanti also receives the Mental Health & Public Safety millage which could be used to fund projects like these and others that promote the health the safety of residents experiencing homelessness.



Sustainable development: Priority ranking


1. Enact an affordability & accessibility ordinance (44.9%)
2. Build a homeless shelter in Ypsilanti (39.9%)
3. Install public toilets and benches in our parks (35.9%)
4. Enact an inclusionary housing ordinance (32.7%)
5. Build on public land (28.9%)
6. Establish a community land trust (27.1%)
7. Incentivize co-op conversion (25.4%)

SECTION 3: NEED-BASED ASSISTANCE

1. Establish a minor home repair program

361 responses


Proposal: Establish a Minor Home Repair Program to assist with the cost of essential home repairs for eligible low-income and disabled homeowners. Eligible repairs could include roof replacement, plumbing replacement, mechanical or electrical replacements, ADA ramp installation or repair, door modifications, and lead or mold remediation. The City could offer small grants for home improvements.



2. Fund local agencies that provide need-based assistance

360 responses


Proposal: Fund local agencies that provide need-based assistance to further expand services and programs to Ypsilanti residents. Agencies that provide need-based assistance include Legal Services of South Central Michigan (LSSCM) which provides free legal representation to low-income tenants, Michigan Immigrant Rights Center (MIRC) which provides free legal services to low-income immigrants and undocumented residents, Ozone House which provides free services for youth in crisis and/or experiencing homelessness, Ypsilanti Housing Commission which provides 342 units of affordable housing, including permanent supportive housing, and Barrier Busters which provides financial assistance to tenants for eviction prevention and utility shut-off.




3. Allow existing homeowners living South of Michigan Avenue to qualify for same incentives as new homebuyers

361 responses


Proposal: Modify the policy for the South of Michigan Avenue Neighborhood Enterprise Zone (NEZ) to allow existing homeowners to qualify for the same tax breaks as new home-buyers. Under the current City of Ypsilanti NEZ policy, tax breaks granted to homeowners who rehabilitate existing properties are of shorter duration than tax breaks granted to owners of newly constructed properties, which favors investors and newcomers over existing residents.



4. Create a landlord incentive program to stabilize rent



5. Assist low-income residents with home buying




Need-based assistance: Priority ranking


1. Assist low-income residents with home buying (49.1%)
2. Establish a minor home repair program (42.4%)
3. Create a landlord incentive program to stabilize rent (40.9%)
4. Fund local agencies that provide need-based assistance (39.2%)
5. Allow existing homeowners living South of Michigan Avenue to access the same incentives as new homebuyers (32.2%)

SECTION 4: PHYSICAL ACCESSIBILITY

Adopt a visitability ordinance



Launch a universal design program




Physical accessibility: Priority ranking


1. Launch a Universal Design program (60.4%)
2. Adopt a visitability ordinance (59.4%)

SECTION 5: ZONING


Change single-family zoning districts to allow 2- or 3-unit homes



Lift limit on non-related persons living in a single dwelling




Allow accessory dwelling units throughout the City



Alter zoning ordinance to accommodate tiny homes

358 responses


Proposal: Revise the Zoning Ordinance to remove barriers to tiny home construction and occupancy. Tiny homes can provide an affordable alternative to larger, traditional homes. They can come in a variety of styles, many of which are complicated by zoning requirements governing building frontage, lot coverage, and portability.



Change parking space requirement for new housing developments

352 responses

Proposal: Revise the Zoning Ordinance to reduce the number of parking spaces required for new housing development or altered housing. Reduction of parking requirements can lower the cost of construction or provide more site-layout options for new or altered housing. Reductions in parking space requirements could be applied to individual uses, such as multiple family dwelling or group homes, or to additional zoning districts. The center district and certain uses within the historic corridor are already exempt from these requirements. The ordinance also allows for reductions to certain requirements, such as proximity to transit stops.




Zoning: Priority ranking


1. Alter zoning ordinance to accommodate tiny homes (52.3%)
2. Lift the limit on non-related persons living in a dwelling (44.6%)
3. Change single-family zoning districts to permit 2- or 3-unit homes (44%)
4. Allow accessory dwelling units throughout the City (39.1%)
5. Change parking space requirement for new housing developments (19%)

SECTION 6: PARTNERSHIP & ADVOCACY


Advocate for rent control legislation




Ask local universities to invest in the Ypsilanti Housing Trust



Ask OCED to fund affordable, accessible housing in Ypsilanti



Advocate for local authority to regulate Airbnb/short-term rentals



Partnership & Advocacy: Priority ranking

1. Ask local universities to invest in the Ypsilanti Housing Trust (54.8%)
2. Advocate for rent control legislation at State level (54.2%)
3. Ask OCED to fund affordable and accessible housing in Ypsilanti (36.7%)
4. Advocate for local authority to regulate Airbnb/short-term rentals (28.2%)

Note on representativeness of survey respondents: Homeowners, white/caucasians, women, and able-bodied people were overrepresented in the survey as compared with census data. Renters, men, Black/African Americans and non-Black people of color, and people with disabilities were underrepresented.

Select comments from survey respondents: Certain themes cropped up in the comments section of the housing survey that advocate for expansion of proposals or alternatives. Zoning, rental stock, accessibility, taxes, and subsidized housing were commented on in particular.

“Multi family zoning has huge economic benefits, and increases accessibility significantly. Progressive cities like Minneapolis have made this move. Ypsilanti could lead and do the same for our community.”

“Ypsilanti has entirely too much rental stock. We need to incentivize single-family homeownership.”

“Re: a homeless shelter in Ypsi, I am wary because other programs have been proven more effective:

1. Supportive Housing for chronically homeless (cheaper and more effective at keeping people housed and out of jail/ER than shelter, Avalon Housing does this work)

2. Dispersed Shelter/ Rapid Rehousing for families and individuals who are not chronically homeless (E.g. this is their first time experiencing homelessness due to a lost job, domestic violence, etc. No history of mental illness, addiction or other "chronically homeless" factors. A lot of homeless people, especially families, fit into this category)."

"There are actually two family shelters in Ypsilanti ran by SOS Community Services, as well as Rapid Rehousing. We know this is not enough to meet the need. The shelters only serve 1 family at a time (a total of 20 families with 70 children per year). "

"At SOS we have noticed a great need for drop-in services like showers and laundry, which I think would be an awesome asset to Ypsi."

"The other thing is that Meals on Wheels has launched an "Aging in place" Home Repair program recently. I would love to see the city support this venture, rather than do their own thing."

"The senior population is ever growing. Affordable senior housing needs priority attention too."
"I advocate for the city to include in their master plan that housing is a human right! Rent control! CLTs! Co-op Conversion! These are so important."

"Right of first refusal and co-op conversions are excellent, but are best accompanied by a means to guarantee financing for any tenants or employees who want to purchase the property and establish a co-op. Right of first refusal is only as good as your ability to buy."

"My strategy: Lower property taxes in City of Ypsilanti."

"There are a *lot more* types of disabilities than just being in a wheelchair!!! The only way you're defining accessibility is through wheelchair access, which is important, but accessibility is greater than that for sure."

Endnotes

1. Eastern Michigan University. Fast Facts. July 2020. <https://www.emich.edu/facts/index.php>
2. 2015 Housing Affordability and Economic Equity Analysis for Washtenaw County. czb Report Prepared for the Office of Community and Economic Development, Washtenaw County. January 2015. <https://www.washtenaw.org/DocumentCenter/View/2313/Housing-Affordability-and-Economic-Equity-Analysis-PDF>
3. Marketwatch. “Factory Jobs Are Again Shrinking in Industrial Midwestern States.” October 1 2019. <https://www.marketwatch.com/story/factory-jobs-are-again-shrinking-in-industrial-midwestern-states-2019-09-25>
4. Mlive. “Solar panel array proposed for Ypsilanti Cemetery.” July 23, 2015. https://www.mlive.com/news/ann-arbor/2015/07/solar_panel_array_proposed_for.html
5. SolSmart. Ypsilanti Designation Level. DTE. Newsroom. “DTE Energy Begin Operation of Ypsilanti’s Largest Solar Array.” November 2016. <http://newsroom.dteenergy.com/2016-11-18-DTE-Energy-begins-operation-of-Ypsilanti-s-largest-solar-array#sthash.zLABQ51w.dpbs>
Viewed on November 13 2019. <https://www.solsmart.org/communities/ypsilanti-mi/>
6. Mlive. “Ypsilanti Voters Approve Water Street Millage After Multiple Past Rejections.” August 2017. https://www.mlive.com/news/ann-arbor/2017/08/ypsilanti_voters_approve_water.html
7. Mlive. “Ann Arbor-area Transit Tax Renewal Passes with 83 Percent Support.” January 30, 2019. https://www.mlive.com/news/ann-arbor/2018/08/ann_arbors_aaata_transit_tax_r.html
July 18 2019. <https://blog.nationwide.com/ridesharing-services-and-auto-industry-trends/>
8. The Ride. Washtenaw Avenue Bus Rapid Transit Study Update. <https://www.theride.org/AboutUs/Initiatives/ReImagine-Washtenaw>
9. WATS Policy Committee. Washtenaw Area Transportation Study: 2045 Long Range Plan. 2019. <https://static1.squarespace.com/static/524e0929e4b093015db69c07/t/5c892d277817f7c82eae97bb/1552493920366/Draft+2045+LRP.pdf>
10. Nationwide. Vehicle - Technology and Trends. “How Ridesharing is Changing the Future of Car Ownership.” <https://blog.nationwide.com/ridesharing-services-and-auto-industry-trends/>

Supplemental Resources



Resolution No. 2020 - 02
December 16, 2020

RESOLVED BY THE CITY OF YPSILANTI PLANNING COMMISSION:

WHEREAS, the City of Ypsilanti adopted the Shape Ypsilanti Master Plan in 2013 which establishes guiding values and policy recommendations for the City;

WHEREAS, the Planning Commission determined in 2018 that a Master Plan update was necessary;

WHEREAS, the Ypsilanti Sustainability Commission drafted a Sustainability Plan in which the Planning Commission subsequently determined to incorporate into the Master Plan as a full chapter;

WHEREAS, the Citizen Committee on Housing Affordability and Accessibility drafted a Report and Recommendations;

WHEREAS, the Ypsilanti Planning Commission has the responsibility of developing a Master Plan and any updates;

NOW THEREFORE BE IT RESOLVED, that the Ypsilanti Planning Commission supports the Master Plan update draft as amended;

BE IT FURTHER RESOLVED THAT the Ypsilanti Planning Commission recommend the Ypsilanti City Council formally distribute the Master Plan update for public comment.

OFFERED BY: Commissioner Davis Jr.

SUPPORTED BY: Commissioner Hollifield

YES: 6

NO: 0

ABSENT: 2
(Donnelly, Simmons)

VOTE: Carried



City of Ypsilanti

Community & Economic Development Department

Memo

To: Planning Commissioners
From: Andy Aamodt, City Planner
Date: November 18, 2020
Subject: Drafted Master Plan Update

BACKGROUND & DISCUSSION

The Shape Ypsilanti Master Plan was adopted in 2013. In 2018, Planning Commission decided an update to the Master Plan ("the Plan") was necessary. The City chose Beckett & Raeder, Inc. as planning consultants for this update. Intent to plan notices were sent in June of 2019.

Two large themes arose and became the topic of current Master Plan planning efforts: sustainability, and housing affordability/accessibility. These themes have been finalized by their respective bodies, the Sustainability Commission and the Citizen Committee for Housing Affordability and Accessibility. The Sustainability Commission finalized their plan at their September 14th meeting. As you know, the Planning Commission and Sustainability Commission then held a joint meeting on October 5th in which the Planning Commission made the decision to incorporate the full Sustainability Plan into the Master Plan as a whole chapter. This plan is placed in Chapter 12. The Citizen Committee for Housing Affordability and Accessibility Report and Recommendations were completed in July and forwarded to City Council. This report is referenced a few times in the plan update, and is placed in full in the Appendix.

On top of the aforementioned themes, the City chose to conduct a general update as well, with a few themes such as physical housing strategies, transportation updates, and potential redevelopment sites. Demographic data, maps, and figures were also updated. As part of this update we (City staff) attempted to track what plans and policy we have done, and what we have not done, by marking "completed" or "ongoing" next to their individual headers. A few new plans/policy sections have been added to the general update. These sections include: a re-survey of the Historic District (Chapter 7), a few strategies for housing (Chapter 7), Bell-Kramer land uses (Chapter 7), and the potential redevelopment sites of 220 N. Park and 1901 Huron River Drive (Chapter 10).

Because this is an update, not a new plan, this document will have original 2013 text combined with new text. For the most part, the new text is displayed in **purple**. This is especially the case in chapters 4-9 which underwent the most substantial updating. *Chapter 3 – Ypsilanti Now* was

largely updated too, but because it is a chapter with extensive population and demographic statistics, new text or statistics are not highlighted in purple.

Note: Staff intends to re-design the document so it is more visibly appealing. Such re-design might entail small formatting and map/figure design changes. Staff intends to conduct this during the 63 day public review window.

NEXT STEPS

Once Planning Commission recommends City Council distribution of this Master Plan update, this will be placed on a City Council agenda. City Council will then make the decision on distribution. The Plan will have a distribution period of 63 days, where the public and different agencies may submit comment. Then, after the 63 day window, Planning Commission will hold a public hearing on the update. Planning Commission may then choose to adopt the Plan. If City Council asserts the right to adopt the Master Plan update, via resolution, then City Council is the ultimate adopting authority. See the attached *Master Plan Adoption Process* flowchart by Beckett & Raeder, Inc. for reference.

Note: the original Shape Ypsilanti Master Plan can be found [here](#).



Resolution No. 2020 –
November 18, 2020

RESOLVED BY THE CITY OF YPSILANTI PLANNING COMMISSION:

WHEREAS, the City of Ypsilanti adopted the Shape Ypsilanti Master Plan in 2013 which establishes guiding values and policy recommendations for the City;

WHEREAS, the Planning Commission determined in 2018 that a Master Plan update was necessary;

WHEREAS, the Ypsilanti Sustainability Commission drafted a Sustainability Plan in which the Planning Commission subsequently determined to incorporate into the Master Plan as a full chapter;

WHEREAS, the Citizen Committee on Housing Affordability and Accessibility drafted a Report and Recommendations;

WHEREAS, the Ypsilanti Planning Commission has the responsibility of developing a Master Plan and any updates;

NOW THEREFORE BE IT RESOLVED, that the Ypsilanti Planning Commission supports the Master Plan update draft;

BE IT FURTHER RESOLVED THAT the Ypsilanti Planning Commission recommend the Ypsilanti City Council formally distribute the Master Plan update for public comment.

OFFERED BY: _____

SUPPORTED BY: _____

YES: NO: ABSENT: VOTE:

MASTER PLAN ADOPTION PROCESS

Per the Michigan Planning Enabling Act of 2008

B R i
Beckett&Raeder

1

Planning Commission Initiates Update

☐

The Planning Commission is the author of the master plan. It must review the master plan every 5 years and then decide whether to begin the process of amending the existing plan or adopting a new plan. The review findings must be recorded in the Planning Commission meeting minutes [MCL 125.3845(2)].

2

Intent to Plan Notifications

☐

BRI sends out Intent to Plan notifications via first class mail, inviting comment from recipients. Notifications go to all entities listed in [MCL 125.3839(2)] including: neighboring municipalities; regional and county planning commissions; public utility, railroad, and public transportation agencies; county road commissions, and the state transportation department.

3

Plan Submittal to Elected Body

☐

After preparing the master plan, the Planning Commission submits a request (via a motion) to the elected body for distribution of the proposed master plan to the same entities initially contacted for the Intent to Plan notifications [MCL 125.3841(1)].

4

Distribution Approval

☐

The elected body approves distribution of the proposed master plan (via formal resolution) for public and agency review, which sets the clock for the comment period: 63 days for a new plan or plan update [MCL 125.3841(3)] or 42 days for a minor plan amendment [MCL 125.3845 (1)(b)].

5

Master Plan Distribution

☐

BRI sends the proposed master plan by first class mail, personal delivery, or electronic delivery for public and agency review [MCL 125.3841(2)].

6

Review & Comment Period

☐

All entities that received notification may submit comments during the comment period. It is best practice to make the plan available for public review during this period [MCL 125.3841(3)].

7

Public Hearing & Notice

☐

The Planning Commission holds a public hearing on the proposed master plan at the end of the comment period. At least 15 days prior, the Planning Commission must give notice of the time and place of the public hearing to the general public via newspaper publication and to the entities that received a copy of the proposed master plan amendment [MCL 125.3843(1)].

8

Planning Commission Master Plan Approval

☐

The Planning Commission approves the master plan by resolution, with affirmative votes from at least 2/3 of its members for a city or village and a majority of its members for a township or county. [MCL 125.3843(2)].

Planning Commission approval of the proposed master plan is the final step in the adoption process, unless the elected body has asserted the right to approve or reject the master plan (see step 9). If this is the case, the Planning Commission recommends that the elected body adopts the plan [MCL 125.3843(3)].

9

Optional: Elected Body Master Plan Approval

☐

An elected body may, by resolution, assert the right to approve or reject the proposed master plan (the municipality's clerk is responsible for maintaining a record of resolutions). If this is the case, then the elected body adopts the master plan by resolution. [MCL 125.3843(3)].

June 24, 2019


Regarding: Ypsilanti Master Plan

To whom it may concern:

This letter is to provide notification to your office that the City of Ypsilanti will begin the process of writing a Master Plan pursuant to Public Act 33 of 2008, the Michigan Planning Enabling Act.

Once a draft plan is approved for distribution, you will be provided a link to an electronic copy for your organization's review and comment. Please feel free to contact me about any land use or community development issues pertinent to your organization, or to the participating community, which should be reviewed during the preparation of the plan.

Regards,



John Iacoangeli, AICP, PCP, LEED AP, CNU-A



Enclosure: List of organizations and entities receiving this notification

Notification of Intent to Prepare a Master Plan

Organizations and Entities Receiving this Notice:

Ypsilanti Charter Township
Superior Township
Southeast Michigan Council of Governments
Washtenaw County
Washtenaw County Road Commission
Ypsilanti Community Schools
Eastern Michigan University
Ypsilanti District Library
Michigan Department of Transportation
Ann Arbor Area Transportation Authority
Norfolk Southern Corporation
Amtrak Corporation
DTE Energy Company
AT&T
Comcast Corporation
Ypsilanti Community Utilities
Consolidated Railroad
Washtenaw Area Transportation Study
SBC Communications



REQUEST FOR LEGISLATION

TO: Mayor and City Council
FROM: Ron Akers
DATE: January 5, 2021
SUBJECT: Approval of Metro Act Permit from Great Lakes Comnet dated April 4, 2014 to Everstream GLC Holding Company LLC

DESCRIPTION:

Approval of Metro Act Permit from Great Lakes Comnet dated April 4, 2014 to Everstream GLC Holding Company LLC

SUMMARY:

The City granted a Metro Act Permit to Great Lakes Comnet (Great Lakes) for use of the City right-of-way on April 4, 2014. Great Lakes used the permit and has not been in violation. Great Lakes has been sold to Everstream GLC Holding Company LLC who is requesting a transfer of the permit.

The Metro Act and the permit allow for a transfer. This office has no objection to the transfer and the City Attorney has approved the transaction as to form.

RECOMMENDED ACTION:

Approve the permit transfer from Great Lakes to Everstream.

ATTACHMENTS: Great Lakes Comnet Metro Act Application & Agreement, Everstream Consent to Change in Control dated October 29, 2021.

CITY MANAGER APPROVAL: _____ COUNCIL AGENDA DATE: _____

CITY MANAGER COMMENTS: _____

FISCAL SERVICES DIRECTOR APPROVAL: _____



Resolution No. 2021-004
January 5, 2021

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

Upon recommendation of the Director of the Ypsilanti Department of Public Services and the approval of the Ypsilanti City Attorney as to form,

The request for transfer of Metro Act Right-Of-Way Telecommunications Permit is approved and the Metro Act Permit granted to Great Lakes Comment on April 14, 2014 is transferred to Everstream GLC Holding Company, LLC.

The Transferee shall obey and observe all requirement of the permit.

OFFERED BY: _____

SECONDED BY: _____

YES: NO: ABSENT: VOTE:

This resolution is adopted by the Council of the City of Ypsilanti and approved by the Mayor this
5 day of January 2021

#Resolution No. 2021-004

October 29, 2020

Department of Public Services
City of Ypsilanti
14 W. Forest Avenue
Ypsilanti, MI 48197

RE: Consent to Change in Control – Metro Act Permit Bilateral Form Right-of-Way Telecommunications Permit dated April 4, 2014

To whom it concerns:

Reference is made to that certain pending Metro Act Permit Bilateral Form Right-of-Way Telecommunications Permit dated April 4, 2014 by the city of Ypsilanti, Michigan ("Ypsilanti") to Great Lakes Comnet, Inc. ("Great Lakes Comnet") (the "Permit").

Great Lakes Comnet entered into a certain Purchase Agreement with Everstream GLC Holding Company LLC ("Buyer") pursuant to which Buyer acquired all of the equity of Great Lakes Comnet (the "Transaction"). The consummation of the Transaction resulted in a "change in control" of Great Lakes Comnet.


In accordance with § 11.1 of the Permit, Great Lakes Comnet has requested that Ypsilanti provide written consent to the "change in control" of Great Lakes Comnet that occurred as a result of the consummation of the Transaction, and Ypsilanti, by its signature below, hereby provides such written consent, effective as of the date of this letter agreement

Please indicate your agreement with the forgoing by signing this letter agreement in the space provided below and return to the following address:

Everstream GLC Holding Company LLC
1228 Euclid Avenue
Suite 1228
Cleveland, OH 44115
Attn: General Counsel

Also, please feel free to contact us if we may provide any additional information and discuss any existing questions related to the details above.

Sincerely,



Dereck Wischmeyer
Vice President, General Counsel

ACKNOWLEDGED AND AGREED TO
this ____ day of _____, 2020

City of Ypsilanti

By: _____

Name: _____

Title: _____



**Barr,
Anhut &
Associates, P.C.**
ATTORNEYS AT LAW

Scan & File

105 Pearl Street
Ypsilanti, MI 48197
(734) 481-1234
Fax (734) 483-3871
www.barrlawfirm.com
e-mail: info@barrlawfirm.com

John M. Barr
Karl A. Barr
Daniel J. DuChene

Jesse O'Jack ~ Of Counsel
William P. Anhut ~ Of Counsel – Retired

To: ~~Kim Teamer, Treasurer, and Acting City Clerk~~ *Frances*
From: John M. Barr
Date: 3/10/2014 *SI*
Re: Great Lakes Comnet, Inc. Metro Act Application

Enclosed is the Master copy of the Metro Act Permit Application of Great Lakes Comnet, Inc. Please file in your usual fashion. I am working on the permit and will send to City Council for consideration after final reviews.

F:\docs\CITY\C\Great Lakes Comnet\Memo to Clerk send Master copy application-permit.doc

**MASTER
COPY**

**METRO Act Permit Application Form
Revised April 6, 2012**

**City of Ypsilanti
Name of Local Unit of Government**

**APPLICATION FOR
ACCESS TO AND ONGOING USE OF PUBLIC WAYS BY
TELECOMMUNICATIONS PROVIDERS
UNDER
METROPOLITAN EXTENSION TELECOMMUNICATIONS
RIGHTS-OF-WAY OVERSIGHT ACT
2002 PA 48
MCL SECTIONS 484.3101 TO 484.3120**

BY

**Great Lakes Comnet, Inc.
("APPLICANT")**

Unfamiliar with METRO Act?--Assistance: Municipalities unfamiliar with Michigan Metropolitan Extension Telecommunications Rights-of-Way Oversight Act ("METRO Act") permits for telecommunications providers should seek assistance, such as by contacting the Telecommunications Division of the Michigan Public Service Commission at 517-241-6200 or via its web site at http://www.michigan.gov/mpsc/0,4639,7-159-16372_22707---,00.html.

45 Days to Act—Fines for Failure to Act: The METRO Act states that "A municipality shall approve or deny access under this section within 45 days from the date a provider files an application for a permit for access to a public right-of-way." MCL 484.3115(3). The Michigan Public Service Commission can impose fines of up to \$40,000 per day for violations of the METRO Act. It has imposed fines under the Michigan Telecommunications Act where it found providers or municipalities violated the statute.

Where to File: Applicants should file copies as follows [municipalities should adapt as appropriate—unless otherwise specified service should be as follows]:

Three (3) copies (one of which shall be marked and designated as the master copy) with the City Mayor, at One South Huron Street, Ypsilanti, MI 48197

City of Ypsilanti
Name of local unit of government

**APPLICATION FOR
ACCESS TO AND ONGOING USE OF PUBLIC WAYS BY
TELECOMMUNICATIONS PROVIDERS**

By
Great Lakes Comnet, Inc.
("APPLICANT")

This is an application pursuant to Sections 5 and 6 of the Metropolitan Extension Telecommunications Rights-of-Way Oversight Act, 2002 PA 48 (the "METRO Act") for access to and ongoing usage of the public right-of-way, including public roadways, highways, streets, alleys, easements, and waterways ("Public Ways") in the Municipality for a telecommunications system. The METRO Act states that "A municipality shall approve or deny access under this section within 45 days from the date a provider files an application for a permit for access to a public right-of-way." MCL 484.3115(3).

This application must be accompanied by a one-time application fee of \$500, unless the applicant is exempt from this requirement under Section 5(3) of the METRO Act, MCL 484.3105(3).

1 GENERAL INFORMATION:

1.1 Date: February 21, 2014

1.2 Applicant's legal name: Great Lakes Comnet, Inc.
Mailing Address: 1515 Turf Lane, Suite 100
Suite 100
East Lansing, MI 48823

Telephone Number: (517) 664-1600
Fax Number: (517) 694-8817
Corporate website: <http://www.comlink.net>

Name and title of Applicant's local manager (and if different) contact person
regarding this application: Nate Duffield

Mailing Address: 1515 Turf Lane
Suite 100
East Lansing, MI 48823
Telephone Number: (517) 742-4114
Fax Number: (517) 694-8817
E-mail Address: nduffield@comlink.net

1.3 Type of Entity: (Check one of the following)

- ☒ Corporation
☐ General Partnership
☐ Limited Partnership
☐ Limited Liability Company
☐ Individual
☐ Other, please describe: _____

1.4 Assumed name for doing business, if any: N/A _____

1.5 Description of Entity:

1.5.1 Jurisdiction of incorporation/formation; Michigan

1.5.2 Date of incorporation/formation; 8/5/1996

1.5.3 If a subsidiary, name of ultimate parent company; N/A

1.5.4 Chairperson, President/CEO, Secretary and Treasurer (and equivalent officials for non-corporate entities).

Chairman of the Board, Randy Fletcher
President/CEO, Paul Bowman
Secretary, Janet Beilfuss
Treasurer, Les Jenkins

1.6 Attach copies of Applicant's most recent annual report (with state ID number) filed with the Michigan Department of Licensing and Regulatory Affairs and certificate of good standing with the State of Michigan. For entities in existence for less than one year and for non-corporate entities, provide equivalent information. See attachment A

1.7 Is Applicant aware of any present or potential conflicts of interest between Applicant and Municipality? If yes, describe: No _____

_____.

1.8 In the past three (3) years, has Applicant had a permit to install telecommunications facilities in the public right of way revoked by any Michigan municipality?

Circle: Yes No

If "yes," please describe the circumstances.

1.9 In the past three (3) years, has an adverse finding been made or an adverse final action been taken by any Michigan court or administrative body against Applicant under any law or regulation related to the following:

1.9.1 A felony; or

1.9.2 A revocation or suspension of any authorization (including cable franchises) to provide telecommunications or video programming services?

Circle: Yes No

If "yes," please attach a full description of the parties and matters involved, including an identification of the court or administrative body and any proceedings (by dates and file numbers, if applicable), and the disposition of such proceedings.

1.10 [If Applicant has been granted and currently holds a license to provide basic local exchange service, no financial information needs to be supplied.] If publicly held, provide Applicant's most recent financial statements. If financial statements of a parent company of Applicant (or other affiliate of Applicant) are provided in lieu of those of Applicant, please explain. Great Lakes Comnet, Inc. is licensed to provide basic local exchange service. See attachment B

1.10.1 If privately held, and if Municipality requests the information within 10 days of the date of this Application, the Applicant and the Municipality should make arrangements for the Municipality to review the financial statements.

If no financial statements are provided, please explain and provide particulars.

Per Section 1 (1.10), Great Lakes Comnet, Inc. holds a license to provide basic local exchange service.

2 DESCRIPTION OF PROJECT:

2.1 Provide a copy of authorizations, if applicable, Applicant holds to provide telecommunications services in Municipality. If no authorizations are applicable, please explain. No additional applications are applicable as Great Lakes Comnet, Inc. has endorsement from the Michigan Department of Consumer and Industry Services, Attachment A and holds a license to provide basic local exchange service with the Michigan Public Service Commission, Attachment B.

2.2 Describe in plain English how Municipality should describe to the public the telecommunications services to be provided by Applicant and the telecommunications facilities to be installed by Applicant in the Public Ways. Two way telecommunication for the transmission of data and internet.

2.3 Attach route maps showing the location (including whether overhead or underground) of Applicant's existing and proposed facilities in the public right-of-way. To the extent known, please identify the side of the street on which the facilities will be located. (If construction approval is sought at this time, provide engineering drawings, if available, showing location and depth, if applicable, of facilities to be installed in the public right-of-way). See attachment C.

2.4 Please provide an anticipated or actual construction schedule. Anticipated completion for the project is December 2015

2.5 Please list all organizations and entities which will have any ownership interest in the facilities proposed to be installed in the Public Ways. Great Lakes Comnet, Inc.

2.6 Who will be responsible for maintaining the facilities Applicant places in the Public Ways and how are they to be promptly contacted? If Applicant's facilities are to be installed on or in existing facilities in the Public Ways of existing public utilities or incumbent telecommunications providers, describe the facilities to be used, and provide verification of their consent to such usage by Applicant. Great Lakes Comnet

3 TELECOMMUNICATION PROVIDER ADMINISTRATIVE MATTERS:

Please provide the following or attach an appropriate exhibit.

3.1 Address of Applicant's nearest local office; 1515 Turf Lane, Suite 100, East Lansing, MI 48823

3.2 Location of all records and engineering drawings, if not at local office; N/A

3.3 Names, titles, addresses, e-mail addresses and telephone numbers of contact person(s) for Applicant's engineer or engineers and their responsibilities for the telecommunications system; Aaron Bowie, OSP Manager, Great Lakes Comnet, 1515 Turf Lane Suite 100, East Lansing, MI 48823 Ph# 517-664-1600, Fax# 517-324-8900, abowie@comlink.net.

3.4 Provide evidence of self-insurance or a certificate of insurance showing Applicant's insurance coverage, carrier and limits of liability for the following:

3.4.1 Worker's compensation;

3.4.2 Commercial general liability, including at least:

3.4.2.1 Combined overall limits;

3.4.2.2 Combined single limit for each occurrence of bodily injury;

3.4.2.3 Personal injury;

3.4.2.4 Property damage;

3.4.2.5 Blanket contractual liability for written contracts, products, and completed operations;

3.4.2.6 Independent contractor liability;

3.4.2.7 For any non-aerial installations, coverage for property damage from perils of explosives, collapse, or damage to underground utilities (known as XCU coverage);

3.4.2.8 Environmental contamination;

3.4.3 Automobile liability covering all owned, hired, and non-owned vehicles used by Applicant, its employee, or agents.

3.5 Names of all anticipated contractors and subcontractors involved in the construction, maintenance and operation of Applicant's facilities in the Public Ways.
Great Lakes Connet.

4 CERTIFICATION:

All the statements made in the application and attached exhibits are true and correct to the best of my knowledge and belief.

Great Lakes Comnet, Inc.

[Redacted Signature]

By: Nate Duffield
Its: Internal Project Manager
Date: February 21, 2014

CERTIFICATE OF INSURANCE

2/18/2014

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURERS(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

THIS IS TO CERTIFY THAT: **Great Lakes Comnet, Inc.**
1515 Turf Lane
East Lansing, MI 48823



**FEDERATED RURAL ELECTRIC
INSURANCE EXCHANGE**

NAIC: 11118
P.O. Box 15147, Lenexa, KS 66285-5147
(913) 541-0150 fax (913) 541-9004
www.federatedrural.com

IS, AT THE ISSUE DATE OF THIS CERTIFICATE, INSURED BY THE COMPANY UNDER THE POLICY(IES) LISTED BELOW. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOW MAY HAVE BEEN REDUCED BY PAID CLAIMS.

TYPE OF INSURANCE	POLICY NUMBER	POLICY DATES	LIMITS (\$)	
GENERAL LIABILITY COMMERCIAL GENERAL LIABILITY OCCURRENCE-BASIS COMPREHENSIVE FORM PREMISIS / OPERATIONS UND / EXPLOSION & COLLAPSE PRODUCTS / COMP OPS CONTRACTUAL BROAD-FORM PROPERTY DAMAGE NO GENERAL AGGREGATE	21 ARB 035-12	11/18/2012 to 11/18/2014	EACH OCCURRENCE	\$2,000,000
			DAMAGE TO RENTED PREMISES	\$2,000,000
			MED EXP (PER PERSON)	\$1,000
			PERSONAL & ADV INJURY	\$2,000,000
AUTOMOBILE LIABILITY ANY AUTO HIRED & NON-OWNED AUTO GARAGE LIABILITY (ANY AUTO)	21 ARB 035-12	11/18/2012 to 11/18/2014	COMBINED SINGLE LIMIT (EACH ACCIDENT)	\$2,000,000
UMBRELLA LIABILITY OCCURRENCE-BASIS \$10,000 SELF-INSRD RETENTION	21 UMB 035-12	11/18/2012 to 11/18/2014	EACH OCCURRENCE	\$8,000,000
			PRODUCTS-COMP/OP AGG	\$8,000,000
WORKERS COMPENSATION AND EMPLOYERS LIABILITY	21 WC 035-13	11/18/2013 to 11/18/2014	WC LIMITS	STATUTORY
			E.L. EACH ACCIDENT	\$500,000
			E.L. DISEASE EACH EMPLOYEE	\$500,000
			E.L. DISEASE - POLICY LIMIT	\$500,000
ALL-RISK BLANKET PROPERTY INCLUDING PHYSICAL DAMAGE TO VEHICLES	21 ARB 035-12	11/18/2012 to 11/18/2014	DEDUCTIBLES	
			PROPERTY	\$500
			COMP	\$250
			COLLISION	\$500
DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES / EQUIPMENT / EXCLUSIONS ADDED BY ENDORSEMENT / SPECIAL PROVISIONS See attached Miscellaneous Endorsement. The All Risk Blanket Policy contains independent Contractors Liability and immediate and suddenly accidental Pollution coverage limited to \$1,000,000.				
CERTIFICATE HOLDER: CITY OF YPSILANTI ONE SOUTH HURON STREET YPSILANTI, MI 48823		CANCELLATION: SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.		
		AUTHORIZED REPRESENTATIVE: 		

FREIE Cert v.8/10



FEDERATED RURAL ELECTRIC
INSURANCE EXCHANGE

This endorsement changes the
policy. Please read it carefully.

Miscellaneous Endorsement

Effective 2/18/2014 12:01 a.m. standard time, this endorsement forms a part of
Policy No. 21 ARB 035-12 issued by Federated Rural Electric Insurance Exchange to
Great Lakes Comnet, Inc.

In consideration of the premium charged, Federated and the Insured agree, subject to all
provisions of the policy except as modified herein, as follows:

City of Ypsilanti is added as additional insured only with respect to liability caused, in whole
or in part, by operations performed by, or on behalf of, the policyholder.
Liability caused by the sole negligence, intentional act or omission of the additional insured
is not covered.

Federated will provide 30 days notice to the additional insured of policy cancellation or
material coverage changes to the mailing address, email address or facsimile phone
number shown on the latest certificate of insurance issued to the additional insured.

It is agreed that coverage under this policy is primary as regards additional insured City of
Ypsilanti.

BASIC LOCAL EXCHANGE SERVICE PROVIDERS LICENSED IN MICHIGAN
as of March 19, 2013

CLEC = Competitive Local Exchange Carrier
ILEC = Incumbent Local Exchange Carrier

Note: If your company's email address is not listed or corrections need to be made to this list, please contact Julie Ginevan at: ginevanj@michigan.gov

Company Name and Address	Contact Information	CLEC	ILEC
Climax Telephone Company 13800 E. Michigan Ave. Galesburg, MI 49053-9658	Jim Burnham President and CEO Phone: (269) 746-2500 Fax (269) 746-9914 Email: jburnham@ctstelecom.com	✓	✓
CMC Telecom, Inc. 51151 Pontiac Trail Wixom, MI 48393	Craig Champagne President Phone: (248) 668-2800 Fax (248) 668-2812 Email: cchamp@cmctelecom.net	✓	
Coldwater Telecommunications Utility 1 Grand St. Coldwater, MI 49036-1620	Jim Royer Network Operations Engineer Phone: (517) 279-9531 Fax (517) 278-5107 Email: jroyer@muni.cbpu.com	✓	
Comcast Business Communications, LLC 600 Galleria Pkwy Suite 1100 Atlanta, GA 30339	Richard Wolfe Sr. Director - Regulatory Affairs Phone: (678) 385-5178 Fax (678) 385-5101 Email: richard_wolfe@cable.comcast.com	✓	
Comcast Phone of Michigan, LLC, dba CIMCO a Division of Comcast 600 Galleria Pkwy Suite 1100 Atlanta, GA 30339	Richard Wolfe Sr. Director - Regulatory Affairs Phone: (678) 385-5178 Fax (678) 685-5101 Email: richard_wolfe@cable.comcast.com	✓	
Comlink, L.L.C. 1515 Turf Lane Ste. 100 East Lansing, MI 48823-6393	John Summersett General Manager Phone: (517) 664-1900 Fax (517) 324-8900 Email: jsummersett@comlink.biz	✓	
Communications Venture Corporation, dba INdigital Telecom 5312 W. Washington Center Rd. Ft. Wayne, IN 46818	Deborah Prather Director of Regulatory Affairs Phone: (260) 469-2010 Fax Email: dprather@indigital.net	✓	
Comnet (USA) LLC 700 S. Flower St. Ste. 750 Los Angeles, CA 90017	Linda Peng Phone: (213) 488-1951 Fax (213) 488-1491 Email: lindapeng@comnet-telecom.com	✓	
ComTech21, LLC One Barnes Park South Wallingford, CT 06492	Laura Matosian VP Phone: (203) 679-7257 Fax (877) 312-5544 Email: lmatosian@comtech21.com	✓	

Attachment A

979EH5804 1024 ORB&FI \$102.50

515

MICHIGAN DEPARTMENT OF CONSUMER AND INDUSTRY SERVICES -
CORPORATIONS, SECURITIES AND LAND DEVELOPMENT BUREAU

Km

Date Received

(FOR BUREAU USE ONLY)

OCT 24 1997

FILED

OCT 24 1997

Ronald W. Bloomberg
LOOMIS, EWERT, PARSLEY, DAVIS & GOTTING, P.C.
232 S. Capitol Avenue, Suite 1000
Lansing MI 48933

Administrator
MICHIGAN DEPARTMENT OF CONSUMER & INDUSTRY SERVICES
EFFECTIVE CORPORATIONS, SECURITIES & LAND DEVELOPMENT BUREAU

CERTIFICATE OF AMENDMENT TO THE ARTICLES OF INCORPORATION

For use by Domestic Profit Corporations

Pursuant to the provisions of Act 284, Public Acts of 1972, the undersigned Corporation executes the following Certificate:

1. The present name of the Corporation is: The Michigan Independent Network, Inc.
2. The corporation identification number assigned by the Bureau is: 411-778
3. The location of the registered office is:

829 Ann Street

East Lansing

Michigan

48823

(Street Address)

(City)

(ZIP Code)

4. Articles I, III, IV of the Articles of Incorporation are hereby amended to read as follows:

Article I of the Articles of Incorporation is amended to read:

"The name of the corporation is Great Lakes Comnet, Inc."

Article III of the Articles of Incorporation is amended to read:

1. Total authorized shares:
Common Shares: 60,000
Preferred Shares: 60,000
2. A statement of any and all rights, preferences and limitations of the shares of each class is as follows:
 - a. The Preferred Shares shall be without voting rights but shall be paid dividends, as determined from time to time by the Board of Directors, prior to payment of dividends on the Common Shares.



1515 Turf Lane, East Lansing, MI 48823 - (517) 664-1900 - www.comlink.net


February 21, 2014

Exhibit A

Attention:

Section 2.2: On this route that is proposed under the Metro Application, there will be no services offered to the residents of Ypsilanti. This is simply an enhancement of our networks for business data transfer. All work will be done within the ROW.

Regards,



Nate Duffield

OSP Internal Project Manager



517-742-4114 Desk

517-679-5072 Office

nduffield@comlink.net

www.comlink.net

1515 Turf Lane, East Lansing, MI 48823

GREAT LAKES COMNET

1515 Turf Lane, East Lansing, MI 48823 - (517) 664-1900 - www.comlink.net

February 21, 2014

City of Ypsilanti

Great Lakes Comnet and Comlink share the same address...the difference being is Great Lakes Comnet is the Fiber Network side of the business and Comlink is the Sales and CLEC side. Comlink does NOT have any network above or below ground anywhere in the State of Michigan. All permits are pulled in the name of Great Lakes Comnet and we report all of our METRO footages through LARA (Kathleen Simon is our contact).

Hope this helps and we look forward to working with you.

Any questions or concerns please feel free to contact me anytime.

Regards,



Nate Duffield

OSP Internal Project Manager

  GREAT LAKES COMNET


517-742-4114 Desk

517-679-5072 Office

nduffield@comlink.net

www.comlink.net

1515 Turf Lane, East Lansing, MI 48823



METRO Act Permit
Bilateral Form
Revised 12/06/02

RIGHT-OF-WAY
TELECOMMUNICATIONS PERMIT

TERMS AND CONDITIONS

1 Definitions

- 1.1 Company shall mean Great Lakes Comnet, Inc. organized under the laws of the State of Michigan whose address is 1515 Turf Lane, Suite 100, East Lansing, MI 48823.
- 1.2 Effective Date shall mean the date set forth in Part 13.
- 1.3 Mayor shall mean Municipality's [Mayor/Manager/Supervisor/Village President] or his or her designee.
- 1.4 METRO Act shall mean the Metropolitan Extension Telecommunications Rights-of-Way Oversight Act, Act No. 48 of the Public Acts of 2002, as amended.
- 1.5 Municipality shall mean the City of Ypsilanti, a Michigan municipal corporation.
- 1.6 Permit shall mean this document.
- 1.7 Public Right-of-Way shall mean the area on, below, or above a public roadway, highway, street, alley, easement, or waterway, to the extent Municipality has the ability to grant the rights set forth herein. Public right-of-way does not include a federal, state, or private right-of-way.
- 1.8 Telecommunication Facilities or Facilities shall mean the Company's equipment or personal property, such as copper and fiber cables, lines, wires, switches, conduits, pipes, and sheaths, which are used to or can generate, receive, transmit, carry, amplify, or provide telecommunication services or signals. Telecommunication Facilities or Facilities do not include antennas, supporting structures for antennas, equipment shelters or houses, and any ancillary equipment and miscellaneous hardware used to provide federally licensed commercial mobile service as defined in Section 332(d) of Part I of Title III of the Communications Act of 1934, Chapter 652, 48 Stat. 1064, 47 U.S.C. 332 and further defined as commercial mobile radio service in 47 CFR 20.3, and service provided by any wireless, 2-way communications device.
- 1.9 Term shall have the meaning set forth in Part 7.

2 Grant

2.1 Municipality hereby grants a permit under the METRO Act to Company for access to and ongoing use of the Public Right-of-Way to construct, install and maintain Telecommunication Facilities in those portions of the Public Right-of-Way identified on Exhibit A on the terms set forth herein.

2.1.1 Exhibit A may be modified by written request by Company and approval by Mayor.

2.1.2 Mayor shall not unreasonably condition or deny any request for a modification of Exhibit A. Any decision of Mayor on a request for a modification may be appealed by Company to Municipality's legislative body.

2.2 Overlashing. Company shall not allow the wires or any other facilities of a third party to be overlashed to the Telecommunication Facilities without Municipality's prior written consent. Municipality's right to withhold written consent is subject to the authority of the Michigan Public Service Commission under Section 361 of the Michigan Telecommunications Act, MCL § 484.2361.

2.3 Nonexclusive. The rights granted by this Permit are nonexclusive. Municipality reserves the right to approve, at any time, additional permits for access to and ongoing usage of the Public Right-of-Way by telecommunications providers and to enter into agreements for use of the Public Right-of-Way with and grant franchises for use of the Public Right-of-Way to telecommunications providers, cable companies, utilities and other providers.

3 Contacts, Maps and Plans

3.1 Company Contacts. The names, addresses and the like for engineering and construction related information for Company and its Telecommunication Facilities are as follows:

3.1.1 The address, e-mail address, phone number and contact person (title or name) at Company's local office (in or near Municipality) is Nate Duffield, OSP Internal Project Manager, 1515 Turf Lane, Suite 100, East Lansing, MI 48823.

If Company's engineering drawings, as-built plans and related records for the Telecommunication Facilities will not be located at the preceding local office, the location address, phone number and contact person (title or department) for them is Aaron Bowie, OSP Manager, Great Lakes Comnet, 1515 Turf Lane Suite 100, East Lansing, MI 48823

3.1.2 The name, title, address, e-mail address and telephone numbers of Company's engineering contact person(s) with responsibility for the design, plans and construction of the Telecommunication Facilities is Aaron Bowie, OSP Manager, Great Lakes Comnet, 1515 Turf Lane, Suite 100, East Lansing, MI 48823.

3.1.3 The address, phone number and contact person (title or department) at Company's home office/regional office with responsibility for engineering and construction related aspects of the Telecommunication Facilities is Aaron Bowie, OSP Manager, Great Lakes Comnet, 1515 Turf Lane, Suite 100, East Lansing, MI 48823.

3.1.4 Company shall at all times provide Manager with the phone number at which a live representative of Company (not voice mail) can be reached 24 hours a day, seven (7) days a week, in the event of a public emergency. (866) 221-2741

3.1.5 The preceding information is accurate as of the Effective Date. Company shall notify Municipality in writing as set forth in Part 12 of any changes in the preceding information.

3.2 Route Maps. Within ninety (90) days after the substantial completion of construction of new Facilities in a Municipality, a provider shall submit route maps showing the location of the Telecommunication Facilities to both the Michigan Public Service Commission and to the Municipality, as required under Section 6(7) of the METRO Act, MCLA 484.3106(7).

3.3 As-Built Records. Company, without expense to Municipality, shall, upon forty-eight (48) hours notice, give Municipality access to all "as-built" maps, records, plans and specifications showing the Telecommunication Facilities or portions thereof in the Public Right-of-Way. Upon request by Municipality, Company shall inform Municipality as soon as reasonably possible of any changes from previously supplied maps, records, or plans and shall mark up maps provided by Municipality so as to show the location of the Telecommunication Facilities.

4 Use of Public Right-of-Way

4.1 No Burden on Public Right-of-Way. Company, its contractors, subcontractors, and the Telecommunication Facilities shall not unduly burden or interfere with the present or future use of any of the Public Right-of-Way. Company's aerial cables and wires shall be suspended so as to not endanger or injure persons or property in or about the Public Right-of-Way. If Municipality reasonably determines that any portion of the Telecommunication Facilities constitutes an undue burden or interference, due to changed circumstances, Company, at its sole

expense, shall modify the Telecommunication Facilities or take such other actions as Municipality may determine is in the public interest to remove or alleviate the burden, and Company shall do so within a reasonable time period. Municipality shall attempt to require all occupants of a pole or conduit whose facilities are a burden to remove or alleviate the burden concurrently.

- 4.2 No Priority. This Permit does not establish any priority of use of the Public Right-of-Way by Company over any present or future permittees or parties having agreements with Municipality or franchises for such use. In the event of any dispute as to the priority of use of the Public Right-of-Way, the first priority shall be to the public generally, the second priority to Municipality, the third priority to the State of Michigan and its political subdivisions in the performance of their various functions, and thereafter as between other permit, agreement or franchise holders, as determined by Municipality in the exercise of its powers, including the police power and other powers reserved to and conferred on it by the State of Michigan.
- 4.3 Restoration of Property. Company, its contractors and subcontractors shall immediately (subject to seasonal work restrictions) restore, at Company's sole expense, in a manner approved by Municipality, any portion of the Public Right-of-Way that is in any way disturbed, damaged, or injured by the construction, installation, operation, maintenance or removal of the Telecommunication Facilities to a reasonably equivalent (or, at Company's option, better) condition as that which existed prior to the disturbance. In the event that Company, its contractors or subcontractors fail to make such repair within a reasonable time, Municipality may make the repair and Company shall pay the costs Municipality incurred for such repair.
- 4.4 Marking. Company shall mark the Telecommunication Facilities as follows: Aerial portions of the Telecommunication Facilities shall be marked with a marker on Company's lines on alternate poles which shall state Company's name and provide a toll-free number to call for assistance. Direct buried underground portions of the Telecommunication Facilities shall have (1) a conducting wire placed in the ground at least several inches above Company's cable (if such cable is nonconductive); (2) at least several inches above that, a continuous colored tape with a statement to the effect that there is buried cable beneath; and (3) stakes or other appropriate above ground markers with Company's name and a toll-free number indicating that there is buried telephone cable below. Bored underground portions of the Telecommunication Facilities shall have a conducting wire at the same depth as the cable and shall not be required to provide the continuous colored tape. Portions of the Telecommunication Facilities located in conduit, including conduit of others used by Company, shall be marked at its entrance into and exit from each manhole and handhole with Company's name and a toll-free telephone number.

- 4.5 Tree Trimming. Company may trim trees upon and overhanging the Public Right-of-Way so as to prevent the branches of such trees from coming into contact with the Telecommunication Facilities, consistent with any standards adopted by Municipality. Company shall dispose of all trimmed materials. Company shall minimize the trimming of trees to that essential to maintain the integrity of the Telecommunication Facilities. Except in emergencies, all trimming of trees in the Public Right-of-Way shall have the advance approval of Manager.
- 4.6 Installation and Maintenance. The construction and installation of the Telecommunication Facilities shall be performed pursuant to plans approved by Municipality. The open cut of any Public Right-of-Way shall be coordinated with the Manager or his designee. Company shall install and maintain the Telecommunication Facilities in a reasonably safe condition. If the existing poles in the Public Right-of-Way are overburdened or unavailable for Company's use, or the facilities of all users of the poles are required to go underground then Company shall, at its expense, place such portion of its Telecommunication Facilities underground, unless Municipality approves an alternate location. Company may perform maintenance on the Telecommunication Facilities without prior approval of Municipality, provided that Company shall obtain any and all permits required by Municipality in the event that any maintenance will disturb or block vehicular traffic or are otherwise required by Municipality.
- 4.7 Pavement Cut Coordination. Company shall coordinate its construction and all other work in the Public Right-of-Way with Municipality's program for street construction and rebuilding (collectively "Street Construction") and its program for street repaving and resurfacing (except seal coating and patching) (collectively, "Street Resurfacing").
- 4.7.1 The goals of such coordination shall be to encourage Company to conduct all work in the Public Right-of-Way in conjunction with or immediately prior to any Street Construction or Street Resurfacing planned by Municipality.
- 4.8 Compliance with Laws. Company shall comply with all laws, statutes, ordinances, rules and regulations regarding the construction, installation, and maintenance of its Telecommunication Facilities, whether federal, state or local, now in force or which hereafter may be promulgated. Before any installation is commenced, Company shall secure all necessary permits, licenses and approvals from Municipality or other governmental entity as may be required by law, including, without limitation, all utility line permits and highway permits. Municipality shall not unreasonably delay or deny issuance of any such permits, licenses or approvals. Company shall comply in all respects with applicable codes and industry standards, including but not limited to the National Electrical Safety Code (latest edition adopted by Michigan Public Service Commission) and

the National Electric Code (latest edition). Company shall comply with all zoning and land use ordinances and historic preservation ordinances as may exist or may hereafter be amended. This section does not constitute a waiver of Company's right to challenge laws, statutes, ordinances, rules or regulations now in force or established in the future.

- 4.9 Street Vacation. If Municipality vacates or consents to the vacation of Public Right-of-Way within its jurisdiction, and such vacation necessitates the removal and relocation of Company's Facilities in the vacated Public Right-of-Way, Company shall, as a condition of this Permit, consent to the vacation and remove its Facilities at its sole cost and expense when ordered to do so by Municipality or a court of competent jurisdiction. Company shall relocate its Facilities to such alternate route as Municipality and Company mutually agree, applying reasonable engineering standards.
- 4.10 Relocation. If Municipality requests Company to relocate, protect, support, disconnect, or remove its Facilities because of street or utility work, or other public projects, Company shall relocate, protect, support, disconnect, or remove its Facilities, at its sole cost and expense, including where necessary to such alternate route as Municipality and Company mutually agree, applying reasonable engineering standards. The work shall be completed within a reasonable time period.
- 4.11 Public Emergency. Municipality shall have the right to sever, disrupt, dig-up or otherwise destroy Facilities of Company if such action is necessary because of a public emergency. If reasonable to do so under the circumstances, Municipality shall attempt to provide notice to Company. Public emergency shall be any condition which poses an immediate threat to life, health, or property caused by any natural or man-made disaster, including, but not limited to, storms, floods, fire, accidents, explosions, water main breaks, hazardous material spills, etc. Company shall be responsible for repair at its sole cost and expense of any of its Facilities damaged pursuant to any such action taken by Municipality.
- 4.12 Miss Dig. If eligible to join, Company shall subscribe to and be a member of "MISS DIG," the association of utilities formed pursuant to Act 53 of the Public Acts of 1974, as amended, MCL § 460.701 et seq., and shall conduct its business in conformance with the statutory provisions and regulations promulgated thereunder.
- 4.13 Underground Relocation. If Company has its Facilities on poles of Consumers Energy, Detroit Edison or another electric or telecommunications provider and Consumers Energy, Detroit Edison or such other electric or telecommunications provider relocates its system underground, then Company shall relocate its Facilities underground in the same location at Company's sole cost and expense.

- 4.14 Identification. All personnel of Company and its contractors or subcontractors who have as part of their normal duties contact with the general public shall wear on their clothing a clearly visible identification card bearing Company's name, their name and photograph. Company shall account for all identification cards at all times. Every service vehicle of Company and its contractors or subcontractors shall be clearly identified as such to the public, such as by a magnetic sign with Company's name and telephone number.

5 Indemnification

- 5.1 Indemnity. Company shall defend, indemnify, protect, and hold harmless Municipality, its officers, agents, employees, elected and appointed officials, departments, boards, and commissions from any and all claims, losses, liabilities, causes of action, demands, judgments, decrees, proceedings, and expenses of any nature (collectively "claim" for this Part 5) (including, without limitation, attorneys' fees) arising out of or resulting from the acts or omissions of Company, its officers, agents, employees, contractors, successors, or assigns, but only to the extent such acts or omissions are related to the Company's use of or installation of facilities in the Public Right-of-Way and only to the extent of the fault or responsibility of Company, its officers, agents, employees, contractors, successors and assigns.
- 5.2 Notice, Cooperation. Municipality shall notify Company promptly in writing of any such claim and the method and means proposed by Municipality for defending or satisfying such claim. Municipality shall cooperate with Company in every reasonable way to facilitate the defense of any such claim. Municipality shall consult with Company respecting the defense and satisfaction of such claim, including the selection and direction of legal counsel.
- 5.3 Settlement. Municipality shall not settle any claim subject to indemnification under this Part 5 without the advance written consent of Company, which consent shall not be unreasonably withheld. Company shall have the right to defend or settle, at its own expense, any claim against Municipality for which Company is responsible hereunder.

6 Insurance

- 6.1 Coverage Required. Prior to beginning any construction in or installation of the Telecommunication Facilities in the Public Right-of-Way, Company shall obtain insurance as set forth below and file certificates evidencing same with Municipality. Such insurance shall be maintained in full force and effect until the end of the Term. In the alternative, Company may satisfy this requirement through a program of self-insurance, acceptable to Municipality, by providing reasonable evidence of its financial resources to Municipality. Municipality's acceptance of such self-insurance shall not be unreasonably withheld.

- 6.1.1 Commercial general liability insurance, including Completed Operations Liability, Independent Contractors Liability, Contractual Liability coverage, railroad protective coverage and coverage for property damage from perils of explosion, collapse or damage to underground utilities, commonly known as XCU coverage, in an amount not less than Five Million Dollars (\$5,000,000).
- 6.1.2 Liability insurance for sudden and accidental environmental contamination with minimum limits of Five Hundred Thousand Dollars (\$500,000) and providing coverage for claims discovered within three (3) years after the term of the policy.
- 6.1.3 Automobile liability insurance in an amount not less than One Million Dollars (\$1,000,000).
- 6.1.4 Workers' compensation and employer's liability insurance with statutory limits, and any applicable Federal insurance of a similar nature.
- 6.1.5 The coverage amounts set forth above may be met by a combination of underlying (primary) and umbrella policies so long as in combination the limits equal or exceed those stated. If more than one insurance policy is purchased to provide the coverage amounts set forth above, then all policies providing coverage limits excess to the primary policy shall provide drop down coverage to the first dollar of coverage and other contractual obligations of the primary policy, should the primary policy carrier not be able to perform any of its contractual obligations or not be collectible for any of its coverages for any reason during the Term, or (when longer) for as long as coverage could have been available pursuant to the terms and conditions of the primary policy.
- 6.2 Additional Insured. Municipality shall be named as an additional insured on all policies (other than worker's compensation and employer's liability). All insurance policies shall provide that they shall not be canceled, modified or not renewed unless the insurance carrier provides thirty (30) days prior written notice to Municipality. Company shall annually provide Municipality with a certificate of insurance evidencing such coverage. All insurance policies (other than environmental contamination, workers' compensation and employer's liability insurance) shall be written on an occurrence basis and not on a claims made basis.
- 6.3 Qualified Insurers. All insurance shall be issued by insurance carriers licensed to do business by the State of Michigan or by surplus line carriers on the Michigan Insurance Commission approved list of companies qualified to do business in Michigan. All insurance and surplus line carriers shall be rated A+ or better by A.M. Best Company.

- 6.4 Deductibles. If the insurance policies required by this Part 6 are written with retainages or deductibles in excess of \$50,000, they shall be approved by Manager in advance in writing. Company shall indemnify and save harmless Municipality from and against the payment of any deductible and from the payment of any premium on any insurance policy required to be furnished hereunder.
- 6.5 Contractors. Company's contractors and subcontractors working in the Public Right-of-Way shall carry in full force and effect commercial general liability, environmental contamination liability, automobile liability and workers' compensation and employer liability insurance which complies with all terms of this Part 6. In the alternative, Company, at its expense, may provide such coverages for any or all its contractors or subcontractors (such as by adding them to Company's policies).
- 6.6 Insurance Primary. Company's insurance coverage shall be primary insurance with respect to Municipality, its officers, agents, employees, elected and appointed officials, departments, boards, and commissions (collectively "them"). Any insurance or self-insurance maintained by any of them shall be in excess of Company's insurance and shall not contribute to it (where "insurance or self-insurance maintained by any of them" includes any contract or agreement providing any type of indemnification or defense obligation provided to, or for the benefit of them, from any source, and includes any self-insurance program or policy, or self-insured retention or deductible by, for or on behalf of them).

7 Term

- 7.1 Term. The term ("Term") of this Permit shall be until the earlier of:

- 7.1.1 Fifteen years (15) from the Effective Date; provided, however, that following such initial term there shall be three subsequent renewal terms of five (5) years. Each renewal term shall be automatic unless Municipality notifies Company in writing, at least twelve (12) months prior to the end of any term then in effect, that due to changed circumstances a need exists to negotiate the subsequent renewal with Company. Municipality shall not unreasonably deny a renewal term; or
- 7.1.2 When the Telecommunication Facilities have not been used to provide telecommunications services for a period of one hundred and eighty (180) days by the Company or a successor of an assign of the Company; or
- 7.1.3 When Company, at its election and with or without cause, delivers written notice of termination to Municipality at least one-hundred and eighty (180) days prior to the date of such termination; or

7.1.4 Upon either Company or Municipality giving written notice to the other of the occurrence or existence of a default by the other party under Sections 4.8, 6, 8 or 9 of this Permit and such defaulting party failing to cure, or commence good faith efforts to cure, such default within sixty (60) days (or such shorter period of time provided elsewhere in this Permit) after delivery of such notice; or

7.1.5 Unless Manager grants a written extension, one year from the Effective Date if prior thereto Company has not started the construction and installation of the Telecommunication Facilities within the Public Right-of-Way and two years from the Effective Date if by such time construction and installation of the Telecommunication Facilities is not complete.

8 Performance Bond or Letter of Credit

8.1 Municipal Requirement. Municipality may require Company to post a bond (or letter of credit) as provided in Section 15(3) of the METRO Act, as amended [MCL § 484.3115(3)].

9 Fees

9.1 Establishment; Reservation. The METRO Act shall control the establishment of right-of-way fees. The parties reserve their respective rights regarding the nature and amount of any fees which may be charged by Municipality in connection with the Public Right-of-Way.

10 Removal

10.1 Removal; Underground. As soon as practicable after the Term, Company or its successors and assigns shall remove any underground cable or other portions of the Telecommunication Facilities from the Public Right-of-Way which has been installed in such a manner that it can be removed without trenching or other opening of the Public Right-of-Way. Company shall not remove any underground cable or other portions of the Telecommunication Facilities which requires trenching or other opening of the Public Right-of-Way except with the prior written approval of Manager. All removals shall be at Company's sole cost and expense.

10.1.1 For purposes of this Part 10, "cable" means any wire, coaxial cable, fiber optic cable, feed wire or pull wire.

10.2 Removal; Above Ground. As soon as practicable after the Term, Company, or its successor or assigns at its sole cost and expense, shall, unless waived in writing by Manager, remove from the Public Right-of-Way all above ground elements of

its Telecommunication Facilities, including but not limited to poles, pedestal mounted terminal boxes, and lines attached to or suspended from poles.

- 10.3 Schedule. The schedule and timing of removal shall be subject to approval by Manager. Unless extended by Manager, removal shall be completed not later than twelve (12) months following the Term. Portions of the Telecommunication Facilities in the Public Right-of-Way which are not removed within such time period shall be deemed abandoned and, at the option of Municipality exercised by written notice to Company as set forth in Part 12, title to the portions described in such notice shall vest in Municipality.

- 11 Assignment. Company may assign or transfer its rights under this Permit, or the persons or entities controlling Company may change, in whole or in part, voluntarily, involuntarily, or by operation of law, including by merger or consolidation, change in the ownership or control of Company's business, or by other means, subject to the following:

- 11.1 No such transfer or assignment or change in the control of Company shall be effective under this Permit, without Municipality's prior approval (not to be unreasonably withheld), during the time period from the Effective Date until the completion of the construction of the Telecommunication Facilities in those portions of the Public Right-of-Way identified on Exhibit A.

- 11.2 After the completion of such construction, Company must provide notice to Municipality of such transfer, assignment or change in control no later than thirty (30) days after such occurrence; provided, however,

- 11.2.1 Any transferee or assignee of this Permit shall be qualified to perform under its terms and conditions and comply with applicable law; shall be subject to the obligations of this Permit, including responsibility for any defaults which occurred prior to the transfer or assignment; shall supply Municipality with the information required under Section 3.1; and shall comply with any updated insurance and performance bond requirements under Sections 6 and 8 respectively, which Municipality reasonably deems necessary, and

- 11.2.2 In the event of a change in control, it shall not be to an entity lacking the qualifications to assure Company's ability to perform under the terms and conditions of this Permit and comply with applicable law; and Company shall comply with any updated insurance and performance bond requirements under Sections 6 and 8 respectively, which Municipality reasonably deems necessary.

- 11.3 Company may grant a security interest in this Permit, its rights thereunder or the Telecommunication Facilities at any time without notifying Municipality.

12 Notices

12.1 Notices. All notices under this Permit shall be given as follows:

12.1.1 If to Municipality, to City of Ypsilanti, One South Huron Street,
Ypsilanti, MI 48197

12.1.2 If to Company, to Great Lakes Comnet, Inc. at 1515 Turf Lane, Suite
100, East Lansing, MI 48823.

12.2 Change of Address. Company and Municipality may change its address or
personnel for the receipt of notices at any time by giving notice thereof to the
other as set forth above.

13 Other items

13.1 No Cable, OVS. This Permit does not authorize Company to provide commercial
cable type services to the public, such as "cable service" or the services of an
"open video system operator" (as such terms are defined in the Federal
Communications Act of 1934 and implementing regulations, currently 47 U.S.C.
§§ 522 (6), 573 and 47 CFR § 76.1500).

13.2 Duties. Company shall faithfully perform all duties required by this Permit.

13.3 Effective Date. This Permit shall become effective when issued by Municipality
and Company has provided any insurance certificates and bonds required in Parts
6 and 8, and signed the acceptance of the Permit.

13.4 Authority. This Permit satisfies the requirement for a permit under Section 5 of
the METRO Act [MCL 484.3105].

13.5 Amendment. Except as set forth in Section 2.1 this Permit may be amended by
the written agreement of Municipality and Company.

13.6 Interpretation and Severability. The provisions of this Permit shall be liberally
construed to protect and preserve the peace, health, safety and welfare of the
public, and should any provision or section of this Permit be held
unconstitutional, invalid, overbroad or otherwise unenforceable, such
determination/holding shall not be construed as affecting the validity of any of the
remaining conditions of this Permit. If any provision in this Permit is found to be
partially overbroad, unenforceable, or invalid, Company and Municipality may
nevertheless enforce such provision to the extent permitted under applicable law.

13.7 Governing Law. This Permit shall be governed by the laws of the State of
Michigan.

City of Ypsilanti

Attest

By: _____

Clerk

By: _____

Its: _____

Date: MAYOR

APRIL 4, 2014

"Company accepts the Permit granted by Municipality upon the terms and conditions contained therein."

Great Lakes Comnet, Inc.

By: _____

Its: Nate Duffield

Date: Internal Project Manager

02/21/14



REQUEST FOR LEGISLATION

TO: Mayor and City Council
FROM: Ron Akers
DATE: January 5, 2021
SUBJECT: Approval of Remaining Sites for Small Cell Wireless Application 2020-002

DESCRIPTION:

Approval of Remaining Sites for Small Cell Wireless Application 2020-002

SUMMARY:

In late 2018 the State of Michigan adopted the "Small Wireless Communication Facilities Deployment Act" which was intended to accelerate and encourage deployment of small wireless infrastructure in the public right of way. This law provided a framework for which municipalities have to review these facilities within the public right of way and provided specific guidelines that both the municipalities and the small cell wireless providers needed to follow.

In response to this and interest from small cell wireless providers, City Council has adopted an Ordinance which regulate Small Cell Wireless Facilities in the City in response to changes in state law and the use of these facilities in the expansion of 5G wireless technology. The Ordinance works within the framework of the state statute and takes several factors into consideration when evaluating these facilities.

Verizon Wireless has submitted several sites to be located within the City of Ypsilanti and each of these sites has been reviewed based on the criteria of the Small Cell Wireless Ordinance. The location of the proposed sites are as follows:

1. 293 Olive
2. 301 W. Michigan Ave
3. 401 N. Adams

These proposed locations are all within the City owned Right of Way and plans have been reviewed by Department of Public Services staff for compliance with the Small Cell Wireless Ordinance.

Please note that three (3) sites which were associated with this application were approved in June of 2020. The applicant recently obtained Historic District Commission approval for the additional three (3) sites specified above and due to this we are bringing them before council for their consideration.

RECOMMENDED ACTION:

Based on our review of the criteria in the Small Cell Wireless Ordinance Staff is recommending partial approval of the applications for the above-mentioned locations.

ATTACHMENTS: Application, plans, HDC letter.

CITY MANAGER APPROVAL: _____ COUNCIL AGENDA DATE: _____

CITY MANAGER COMMENTS: _____

FISCAL SERVICES DIRECTOR APPROVAL: _____



Resolution No. 2021-005
January 5, 2021

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

WHEREAS, the State of Michigan adopted the "Small Wireless Communication Facilities Deployment Act" in late 2018 which required municipalities to allow small cell wireless facilities within public right of way; and,

WHEREAS, the City of Ypsilanti adopted an ordinance to regulate small cell wireless facilities within the constraints of this law; and,

WHEREAS, Verizon Wireless has submitted an application; and,

WHEREAS, City staff has reviewed the plans and application and has found that the plans are consistent with the requirements of city ordinances;

NOW THEREFORE BE IT RESOLVED THAT the City of Ypsilanti approves the remaining sites on small cell wireless application 2020-002 for the following locations: 293 Olive; 301 W. Michigan Ave; and 401 N. Adams, subject to review by the City Attorney.

OFFERED BY: _____

SECONDED BY: _____

YES: NO: ABSENT: VOTE:

This resolution is adopted by the Council of the City of Ypsilanti and approved by the Mayor this
5 day of January 2021

#Resolution No. 2021-005



City of Ypsilanti

Community and Economic Development

December 09, 2020

VERIZON WIRELESS
23100 PROVIDENCE DR #133
SOUTHFIELD, MI 48075

CERTIFICATE OF APPROPRIATENESS

RE: HDC Work Permit Application (PHDC-20-0090) for 293 OLIVE

Dear VERIZON WIRELESS,

On Tuesday, December 8, 2020 the Historic District Commission (HDC) reviewed your request for work at 293 OLIVE. Your application was **approved** to include:

The work as submitted in the application, dated December 1, 2020, for modification of an existing light pole to include the features in submitted drawings, including antennas, signage, and connection boxes.

In the commission's decision, the following Secretary of the Interior Standards were cited:
#10 - New work shall be removable.

Approval by the Historic District Commission does not guarantee approval by the zoning, building and/or other necessary departments. Before proceeding with the project it is the responsibility of the applicant to have obtained all approvals necessary. You must start work or apply for and receive all applicable permits within six months of this date for your HDC approval to remain valid. **Any change in the work listed above needs to be reviewed by the HDC using an amended application.**

Please contact me at 734-483-9646 or sslagor@cityofypsilanti.com with any questions.

Sincerely,



Scott E. Slagor, Preservation Planner
Community & Economic Development Department

CC: Property Owner - CITY OF YPSILANTI 651 RICE YPSILANTI MI 48198
File
Building Department

One South Huron Street
Ypsilanti, MI 48197

Tel: (734) 483-9646
Fax: (734) 483-7260

www.cityofypsilanti.com

PROJECT SUMMARY


SITE NAME: 40215
SITE ADDRESS: 293 OLIVE ST
(ESTIMATED) YPSILANTI, MI 48197
COUNTY: WASHTENAW
JURISDICTION: CITY OF YPSILANTI
SITE COORDINATES:
LATITUDE: 42° 14' 50.604" N
LATITUDE: 42.24739 °
LONGITUDE: 83° 36' 57.528" W
LONGITUDE: -83.61598 °
ELEVATION: ±734'-7"
PROPERTY DEFINITION: R.O.W.
FUZE PROJECT ID: 15487103
PSLC CODE: 544756
EXISTING POLE HEIGHT: 40'-0"



SITE NAME: 40215


PROPOSED SMALL CELL EQUIPMENT
ON AN EXISTING DTE POLE

VICINITY MAP



NOT TO SCALE

LOCATION MAP



NOT TO SCALE

SHEET INDEX

NO.	DESCRIPTION
T1	TITLE SHEET
GN1	GENERAL NOTES
C1	SITE LAYOUTS
C1A	SITE LAYOUT - AERIAL IMAGERY
C2	POLE ELEVATION
C3	SITE DETAILS
C4	SITE DETAILS
C5	EQUIPMENT DETAILS
E1	UTILITY SITE PLAN
E2	ELECTRICAL DETAILS
E3	SINGLE LINE DIAGRAM

SCOPE OF WORK

- INSTALLING EQUIPMENT
 - CFIT BOX
 - DISCONNECT
- CONNECTING ONSITE UTILITIES TO WIRELESS EQUIPMENT
- POWER AND FIBER PROVIDED BY OTHERS

STATE COUNTY MAP



PREPARED FOR:



PREPARED BY:



1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF
DOCUMENTS IS PROPRIETARY BY NATURE.
ANY USE OR DISCLOSURE OTHER THAN THAT
WHICH RELATES TO THE CLIENT IS STRICTLY
PROHIBITED.


DRAWN BY: LA

CHECKED BY: CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
1	05/28/20	LA	PRELIMINARY REVIEW
0	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	JWY	PRELIMINARY REVIEW

ENGINEER'S STAMP:



6201054169
NOTED PROFESSIONAL ENGINEER
NOT VALID WITHOUT P.E. STAMP & SIGNATURE

SITE NAME: 40215

ADDRESS: 293 OLIVE ST
YPSILANTI, MI 48197

COUNTY: WASHTENAW

LATITUDE: 42° 14' 50.604" N

LONGITUDE: 83° 36' 57.528" W

DESIGN TYPE: COLOCATION

SHEET TITLE: TITLE SHEET

DRAWING NO.

T1

REVISION:

1

SHEET SCALE FACTOR:

PLOT SIZE:
11" x 17": TO SCALE



1 (800) 482-7171

www.missdig.com
CONTRACTOR TO CALL MICHIGAN
ONE-CALL SYSTEMS AT LEAST 72 HOURS
PRIOR TO DIGGING.

GENERAL NOTES

1. THESE NOTES SHALL BE CONSIDERED A PART OF THE WRITTEN SPECIFICATIONS.
2. THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED IN THE CONTRACT DOCUMENTS.
3. PRIOR TO THE SUBMISSION OF BIDS, THE CONTRACTOR(S) SHALL VISIT THE JOB SITE(S) AND BE RESPONSIBLE FOR ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS AND CONFIRMING THAT THE WORK MAY BE ACCOMPLISHED PER THE CONTRACT DOCUMENTS. ANY DISCREPANCIES ARE TO BE BROUGHT TO THE ATTENTION OF THE IMPLEMENTATION ENGINEER AND ARCHITECT/ENGINEER.
4. THE CONTRACTOR SHALL RECEIVE WRITTEN AUTHORIZATION TO PROCEED ON ANY WORK NOT CLEARLY DEFINED OR IDENTIFIED IN THE CONSTRUCTION DOCUMENTS BEFORE STARTING ANY WORK.
5. ALL WORK PERFORMED AND MATERIALS INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES INCLUDING APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS.
6. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH THE MANUFACTURER RECOMMENDATIONS. IF THESE RECOMMENDATIONS ARE IN CONFLICT WITH THE CONTRACT DOCUMENTS AND/OR APPLICABLE CODES OR REGULATIONS, REVIEW THE CONFLICT FOR DIRECTION WITH THE IMPLEMENTATION ENGINEER AND ARCHITECT/ENGINEER PRIOR TO PROCEEDING.
7. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, PROCEDURES AND FOR COORDINATION OF ALL PORTIONS OF THE WORK UNDER THE CONTRACT INCLUDING CONTACT AND COORDINATION WITH THE IMPLEMENTATION TEAM AND WITH THE AUTHORIZED REPRESENTATIVE OF ANY OUTSIDE POLE OR PROPERTY OWNER. (BASE COMMANDER OR AUTHORIZED AGENT)
8. THE CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO PROTECT EXISTING IMPROVEMENTS, PAVING, CURBS, VEGETATION, GALVANIZED SURFACE OR OTHER EXISTING ELEMENTS AND UPON COMPLETION OF THE WORK, REPAIR ANY DAMAGE THAT OCCURRED DURING CONSTRUCTION TO THE SATISFACTION OF EXTENT.
9. KEEP THE GENERAL AREA CLEAN, HAZARD FREE AND DISPOSE OF ALL DIRT, DEBRIS, RUBBISH AND REMOVE EQUIPMENT NOT SPECIFIED AS REMAINING ON THE PROPERTY. LEAVE PREMISES IN CLEAN CONDITION DAILY.
10. PLANS ARE INTENDED TO BE DIAGRAMMATIC ONLY AND SHOULD NOT BE SCALED UNLESS OTHERWISE NOTED. RELY ONLY ON ANNOTATED DIMENSIONS AND REQUEST INFORMATION IF ADDITIONAL DIMENSIONS ARE REQUIRED.
11. THE EXISTENCE AND LOCATION OF UTILITIES AND OTHER AGENCY'S FACILITIES ARE OBTAINED BY A SEARCH OF AVAILABLE RECORDS. OTHER FACILITIES MAY EXIST BEYOND WHAT IS NOTED. CONTRACTOR SHALL VERIFY LOCATIONS PRIOR TO START OF CONSTRUCTION AND USE EXTREME CARE AND PROTECTIVE MEASURES TO PREVENT DAMAGE TO THESE FACILITIES. CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF UTILITIES OR OTHER AGENCY'S FACILITIES WITHIN THE LIMITS OF THE WORK, WHETHER THEY ARE IDENTIFIED IN THE CONTRACT DOCUMENTS OR NOT.
12. ALL MOUNTING HARDWARE SUCH AS BOLTS, NUTS, LAG SCREWS, CLEVIS, CONDUIT STRAPS, STAPLES, (ANYTHING EXPOSED AND CONNECTING EQUIPMENT TO THE POLE SHALL BE HOT DIPPED GALVANIZED, UNLESS OTHERWISE STATED)

DEFINITIONS

1. "TYPICAL" OR "TYP." MEANS THAT THIS ITEM IS VIRTUALLY IDENTICAL ACROSS SIMILAR CONDITIONS. "TYP." SHALL BE UNDERSTOOD TO MEAN "TYPICAL WHERE OCCURS" AND SHALL NOT BE CONSIDERED AS WITHOUT EXCEPTION OR CONSIDERATION OF SPECIFIC CONDITIONS.
2. "SIMILAR" MEANS COMPARABLE TO CHARACTERISTICS FOR CONDITION NOTED. VERIFY DIMENSIONS AND ORIENTATION ON PLAN.
3. "AS REQUIRED" MEANS AS REQUIRED BY REGULATORY REQUIREMENTS BY REFERENCED STANDARDS, BY EXISTING CONDITIONS, BY GENERALLY ACCEPTED CONSTRUCTION PRACTICE OR BY THE CONTRACT DOCUMENTS.
4. "ALIGN" MEANS ACCURATELY LOCATE FINISH FACES OF MATERIALS IN THE SAME PLANE.
5. THE TERM "VERIFY" OR "V.I.F" SHALL BE UNDERSTOOD TO MEAN VERIFY IN FIELD WITH ARCHITECT AND REQUIRES THAT THE CONTRACTOR CONFIRM INTENTION REGARDING NOTED CONDITION AND PROCEED ONLY AFTER RECEIVING DIRECTION.
6. WHERE THE WORDS "OR EQUAL" OR WORDS OF SIMILAR INTENT FOLLOW A MATERIAL SPECIFICATION, THEY SHALL BE UNDERSTOOD TO REQUIRE SIGNED APPROVAL OF ANY DEVIATION TO SAID SPECIFICATION PRIOR TO CONTRACTOR'S ORDERING OR INSTALLATION OF SUCH PROPOSED EQUAL PRODUCT.
7. FURNISH: SUPPLY ONLY, OTHERS TO INSTALL. INSTALL: INSTALL ITEMS FURNISHED BY OTHERS. PROVIDE: FURNISH AND INSTALL.

PROJECT SPECIFIC NOTES

1. THIS SET IS PROVIDED TO ILLUSTRATE THE EXPECTED SCOPE OF DRAWINGS, QUALITY OF DRAWINGS AND EXTENT GRAPHIC STANDARDS. NOTES ARE FOR A&E CONTRACTOR REFERENCE TO HELP CLARIFY THE SCOPE. ADDITIONAL DRAWINGS MAY BE REQUIRED TO MEET THE REQUIREMENTS OF A GIVEN BASE. ALL EXAMPLES SHOWN ARE FOR REFERENCE ONLY AND ANY NOTES, DETAILS, CALCULATIONS OR OTHER WORK NEEDS TO BE COMPLETED OR CONFIRMED BY THE CONTRACTOR GENERATING THE DRAWINGS IN CONSTRUCTION DOCUMENTS.
2. THIS SET IS TO BE PRINTED AT 11" x 17". IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONFIRM THIS SIZE IS ACCEPTABLE BY THE BASE AND TO PROVIDE A LARGER STANDARD SIZE IF REQUIRED.
3. IT IS THE RESPONSIBILITY OF THE ENGINEER TO CONFIRM ALL WORK SHOWN IS IN COMPLIANCE WITH BASE AND FEDERAL CODES. DRAWINGS SHOWN WITHIN THIS SET ARE SAMPLES AND MAY NOT REFLECT ALL OF THE REQUIRED ELEMENTS, CLEARANCES OR OTHER ITEMS OF ASSEMBLIES NEEDED TO BE CODE COMPLIANT IN THE PARTICULAR MUNICIPALITY THE NODE IS LOCATED WITHIN.

GROUND CONSTRUCTION NOTES:

1. 120/240V POWER REQUIRED FOR 3-WIRE SERVICE.
2. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH FEDERAL STANDARDS AND REGULATIONS AS WELL AS NEC.
3. CALL MICHIGAN ONE CALL 72 HOURS PRIOR TO EXCAVATING AT (800) 482-7171.
4. ALL LANDSCAPING TO BE RESTORED TO ORIGINAL CONDITION OR BETTER.
5. ALL EQUIPMENT TO BE BONDED.
6. METERING CABINET (IF INSTALLED) REQUIRES 3' CLEARANCE AT DOOR OPENING.

STANDARD GROUNDING NOTES:

1. GROUND TESTED AT 25 OHMS OR LESS.
2. 5/8" x 8' RODS, CAD WELD OR UL LISTED DIRECT BURY CLAMP BELOW GRADE.
3. #6 GROUND AND BOND WIRE.
4. MOLDING, STAPLED EVERY 1' AND AT EACH END.
5. GROUND RODS 18" FROM POLE.

STANDARD CONDUIT NOTES:

1. FOR UNDERGROUND CONDUIT AND ABOVE GRADE RISERS USE SCHEDULE 40.
2. IF DIRECTIONAL BORING PLACE 1-1/4" SDR-11 GRAY CONDUIT FOR UNDERGROUND POWER APPLICATIONS.
3. IF TRENCHING, PLACE PVC SCH 40 CONDUIT PER TABLE ON SHEET E1 FOR UNDERGROUND POWER APPLICATIONS.
4. RISERS TO BE ATTACHED TO POLE WITH STANDARD STRAPS AND LAG SCREWS.
5. RISER STRAPS TO BE INSTALLED EVERY 5'.
6. CONDUIT UNDER 1" MAY BE ATTACHED WITH GROUND WIRE MOLDING STAPLES.
7. ALL CONDUIT WILL BE PROOFED WITH A MANDREL AND EQUIPPED WITH PULL ROPE OR MULE TAPE.

STANDARD TRENCHING NOTES:

1. MAINTAIN 42" MINIMUM COVER FOR ELECTRICAL CONDUIT.
2. MAINTAIN 42" MINIMUM COVER FOR COMMUNICATION CONDUIT.
3. IN STREET SLURRY TO GRADE AND MILL DOWN 1-1/2" FOR AC CAP.
4. IN DIRT SLURRY 18" FROM GRADE AND FILL WITH 95% COMPACTION NATIVE SOIL FOR BALANCE.
5. PLACE WARNING TAPE IN TRENCH 18" ABOVE ALL CONDUITS AND #18 WARNING TAPE ABOVE GROUND EQUIPMENT.

UTILITY POLE CONSTRUCTION NOTES:

1. NO BOLT THREADS TO PROTRUDE MORE THAN 1/2".
2. FILL ALL HOLES LEFT IN POLE FROM REARRANGEMENT OF CLIMBERS.
3. ALL CLIMB STEPS NEXT TO CONDUIT SHALL HAVE EXTENDED STEPS.
4. CABLE NOT TO IMPEDE 15" CLEAR SPACE OFF POLE FACE.
5. 90° SHORT SWEEP UNDER ANTENNA ARM. ALL CABLES MUST ONLY TRANSITION ON THE INSIDE OR BOTTOM OF ARMS (NO CABLE ON TOP OF ARMS).
6. USE CABLE CLAMPS TO SECURE CABLE TO ARMS; PLACE 2" CARRIER ID TAGS ON BOTH SIDE OF ARMS.
7. USE 90° CONNECTOR AT CABLE CONNECTION TO ANTENNAS.
8. USE 1/2" CABLE ON ANTENNAS UNLESS OTHERWISE SPECIFIED.
9. FILL VOID AROUND CABLES AT CONDUIT OPENING WITH FOAM SEALANT TO PREVENT WATER INTRUSION.

VERIZON WIRELESS CONSTRUCTION NOTES:

1. CONTRACTOR IS TO FOLLOW THE MOST CURRENT VZW STANDARDS DOCUMENTS PROVIDED TO COMPLETE THIS INSTALLATION.
2. CONTRACTOR SHALL COMPLETE VZW PROVIDED "SMALL CELL SWEEP REPORT" WITH ALL INFORMATION FILLED IN ACCURATELY AND COMPLETELY.
3. CONTRACTOR TO REFER TO THE MOST CURRENT VZW STANDARDS FOR APPROVED "PIM" TEST EQUIPMENT AND GUIDELINES.
4. CONTRACTOR IS TO USE BATTERY POWERED "PIM" EQUIPMENT TO VALIDATE THE FINAL LOCATION OF THE JUMPER AND ANTENNA ARE FREE OF INTERNAL AND EXTERNAL "PIM" SOURCES.
5. CONTRACTOR SHALL PROVIDE AT LEAST ONE TECHNICAL LEAD THAT IS CERTIFIED AND PROFICIENT IN EXECUTING, INTERPRETING AND RECORDING "PIM" MEASUREMENTS.

PREPARED FOR:



PREPARED BY:



DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:	LA
CHECKED BY:	CTD

REVISIONS			
1	05/28/20	LA	PRELIMINARY REVIEW
0	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	JWY	PRELIMINARY REVIEW
NO.	DATE	BY	DESCRIPTION

ENGINEER'S STAMP:



SITE NAME:	40215
ADDRESS:	293 OLIVE ST YPSILANTI, MI 48197
COUNTY:	WASHTENAW
LATITUDE:	42° 14' 50.604" N
LONGITUDE:	83° 36' 57.528" W
DESIGN TYPE:	COLOCATION

SHEET TITLE:	GENERAL NOTES
--------------	---------------

DRAWING NO.	REVISION:
GN1	1

NOTES:

1. THIS DRAWING IS BASED ON AERIAL IMAGERY AND FIELD OBSERVATIONS. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO COMMENCEMENT OF CONSTRUCTION.
2. THE PROPOSED USE DOES NOT REQUIRE FULL OR PART TIME EMPLOYEES AT THE SITE.
3. FOR GENERAL SITE WORK NOTES, SEE SHEET GN1.
4. ALL NORTH ARROWS ON SITE PLANS ARE TRUE NORTH, UNLESS OTHERWISE SPECIFIED.
5. OPEN CUT CONSTRUCTION THROUGH EXISTING PAVEMENT, I.E. ROADWAYS, PARKING AREAS, SIDEWALKS WILL NOT BE ALLOWED. CONSTRUCTION UNDER EXISTING PAVEMENTS WILL BE REQUIRED TO BE INSTALLED WITH DIRECTIONAL BORING TECHNIQUE.
6. RIGHT OF WAY INFORMATION ACQUIRED FROM GIS.

LEGEND

OVERHEAD UTILITIES	— DHU —	CATCH BASIN	⌘
UNDERGROUND POWER	— UGP —	STREET SIGN	—
OVERHEAD POWER	— DHP —	4 WAY STREET SIGN	+
UNDERGROUND TELCO	— UGT —	UTILITY POLE	⊙
OVERHEAD TELCO	— DHT —	LIGHT POLE	⊙
GAS LINE	— GAS —	WATER VALVE	⊗
FENCE	— X —	MANHOLE	⊙
WOOD FENCE	— O —	GAS VALVE	⊗
SEWER LINE	— SWR —	FIRE HYDRANT	⊙
WATER LINE	— VTR —	TELCO PEDESTAL	⊙
HYBRID CABLE	— HYB —	ELECTRICAL BOX	⊙
HIGH VOLTAGE POWER	— HVP —		
FIBER	— FBR —		
RIGHT-OF-WAY	— RDW —		
PROPERTY LINE	— PL —		

UTILITY NOTE:

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES HAVE NOT BEEN VERIFIED. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT OCCUR BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

PREPARED FOR:

verizon

PREPARED BY:

TeleCAD
Wireless

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:

LA


CHECKED BY:

CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
1	05/28/20	LA	PRELIMINARY REVIEW
0	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	JWY	PRELIMINARY REVIEW

ENGINEER'S STAMP:



SITE NAME:

40215

ADDRESS:

293 OLIVE ST
YPSILANTI, MI 48197

COUNTY:

WASHTENAW

LATITUDE:

42° 14' 50.604" N

LONGITUDE:

83° 36' 57.528" W

DESIGN TYPE:

COLOCATION

SHEET TITLE:


SITE LAYOUTS

DRAWING NO.


C1

REVISION:

1



1 OVERALL SITE LAYOUT



2 ENLARGED SITE LAYOUT



1 OVERALL SITE LAYOUT - AERIAL IMAGERY

PREPARED FOR:



PREPARED BY:



1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509



DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF
DOCUMENTS IS PROPRIETARY BY NATURE.
ANY USE OR DISCLOSURE OTHER THAN THAT
WHICH RELATES TO THE CLIENT IS STRICTLY
PROHIBITED.

DRAWN BY:	LA
CHECKED BY:	CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
1	05/28/20	LA	PRELIMINARY REVIEW
0	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	JWY	PRELIMINARY REVIEW

ENGINEER'S STAMP:



SITE NAME: 40215
ADDRESS: 293 OLIVE ST
YPSILANTI, MI 48197
COUNTY: WASHTENAW
LATITUDE: 42° 14' 50.604" N
LONGITUDE: 83° 36' 57.528" W
DESIGN TYPE: COLOCATION

SHEET TITLE:
SITE LAYOUT -
AERIAL IMAGERY

DRAWING NO. C1A	REVISION: 1
--------------------	----------------

CONTRACTOR TO OBTAIN
LATEST RFDS FROM VERIZON
PRIOR TO CONSTRUCTION.

MAINTAIN A MIN. OF 3'-0"
CLEARANCE BETWEEN
DISCONNECT BOX AND ANY
COMM LINES

40" MIN. CLEARANCE
BELOW NEW TRIPLEX
SERVICE

5'-0" MIN. CLEARANCE ABOVE
ANY DTE EQUIPMENT TO
BOTTOM OF ANTENNA


REFER TO RFDS FOR SMALL
CELL AZIMUTHS

NOTICE

Transmitting Antenna(s)
Radio frequency fields beyond
this point MAY EXCEED the FCC
General Population exposure
limit.
Obey all posted signs and
site guidelines.
Call Verizon at 1-800-264-6620
PRIOR to working beyond this
point.
Site ID/ PSLC: 544756 (40215)

verizon

6"x7.5" VERTICAL
RF NOTICE SIGN
TYPICAL OF 2



PREPARED FOR:



PREPARED BY:

TeleCAD

Wireless

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF
DOCUMENTS IS PROPRIETARY BY NATURE.
ANY USE OR DISCLOSURE OTHER THAN THAT
WHICH RELATES TO THE CLIENT IS STRICTLY
PROHIBITED.

DRAWN BY:	LA
CHECKED BY:	CTD

REVISIONS				
1	05/28/20	LA	PRELIMINARY REVIEW	
0	06/27/19	DAJ	CONSTRUCTION ISSUE	
A	06/19/19	JWY	PRELIMINARY REVIEW	
NO.	DATE	BY	DESCRIPTION	

ENGINEER'S STAMP:

STATE OF MICHIGAN

6201054169

SEED PROFESSIONAL ENG

5

20

NOT VALID WITHOUT P.E. STAMP & SIGNATURE

SITE NAME:	40215
ADDRESS:	293 OLIVE ST YPSILANTI, MI 48197
COUNTY:	WASHTENAW
LATITUDE:	42° 14' 50.604" N
LONGITUDE:	83° 36' 57.528" W
DESIGN TYPE:	COLOCATION

SHEET TITLE:
POLE ELEVATION

DRAWING NO.	REVISION:
C2	1

verizon

IN CASE OF EMERGENCY
CALL 1-800-852-2671

SITE DESIGNATION: 40215


INSTALL ON BREAKER PANEL

1 POLE ELEVATION


N.T.S.

POLE ATTACHED EQUIPMENT	
EQUIPMENT	VOLUME (CU-FT)
6701 ANTENNA	0.46
6701 ANTENNA	0.46
6701 ANTENNA	0.46
TOTAL IN CU-FT	1.38

POLE ANCILLARY EQUIPMENT	
EQUIPMENT	VOLUME (CU-FT)
6 POSITION PANEL	0.80
DISCONNECT	0.57
CFIT BOX	0.60
TOTAL IN CU-FT	1.97



2 RF EXPOSURE LIMIT N.T.S.



NOTES:

1. WORKING CLEARANCE FROM ENERGIZED ANTENNA MUST BE GREATER THAN 4 FT, OTHERWISE SHUT DOWN RADIO AND ANTENNA PER INSTRUCTIONS ON PLACARD OR BY OPENING DISCONNECT SWITCH TO RADIO EQUIPMENT ON POLE.
2. ANTENNA AND MOUNTING BRACKETS INSTALLED ABOVE DTE WIRES MUST BE INSTALLED AND MAINTAINED BY DTE OR DTE'S DESIGNATED CONTRACTOR.
3. VERTICAL CLIMBING ZONE MUST BE MAINTAINED ON ALL POLES. (SEE TOP VIEW)
4. BASE CABINET TO BE CLEARLY LABELED WITH OWNER'S NAME AND 1-800 PHONE NUMBER WITH 3/4" TALL LETTERING.
5. SHUTDOWN PLACARD TO BE PLACED ON THE POLE NEAR BASE CABINET AND DISCONNECT SWITCH BOX.
6. 5' FT MIN. CLEARANCE ABOVE ANY DTE EQUIPMENT.
7. ANTENNA POLE TOP CLEARANCES APPLY TO ANY DTE EQUIPMENT OR WIRES INSTALLED UNDER THE ANTENNA.

REFERENCE DTE ENERGY
CELLULAR ANTENNA SMALL CELL SITE CONSTRUCTION
LINE CONSTRUCTION STANDARDS 4-JOINT USE 1-4-26.1
DATED 11/1/2017

3 DTE CLIMBING ZONE REQUIREMENT AND NOTES N.T.S.

PREPARED FOR:



PREPARED BY:



1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF
DOCUMENTS IS PROPRIETARY BY NATURE.
ANY USE OR DISCLOSURE OTHER THAN THAT
WHICH RELATES TO THE CLIENT IS STRICTLY
PROHIBITED.

DRAWN BY: LA

CHECKED BY: CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
1	05/28/20	LA	PRELIMINARY REVIEW
0	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	JWY	PRELIMINARY REVIEW

ENGINEER'S STAMP:



SITE NAME: 40215

ADDRESS:
293 OLIVE ST
YPSILANTI, MI 48197

COUNTY:
WASHTENAW

LATITUDE:
42° 14' 50.604" N


LONGITUDE:
83° 36' 57.528" W

DESIGN TYPE:
COLOCATION

SHEET TITLE:
SITE DETAILS

DRAWING NO.
C3

REVISION:
1



PREPARED FOR:

PREPARED BY:

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY: LA

CHECKED BY: CTD

REVISIONS			
NO.	DATE	BY	DESCRIPTION
1	05/28/20	LA	PRELIMINARY REVIEW
0	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	JWY	PRELIMINARY REVIEW

ENGINEER'S STAMP:

NOT VALID WITHOUT P.E. STAMP & SIGNATURE

SITE NAME: 40215

ADDRESS: 293 OLIVE ST
YPSILANTI, MI 48197

COUNTY: WASHTENAW

LATITUDE: 42° 14' 50.604" N

LONGITUDE: 83° 36' 57.528" W

DESIGN TYPE: COLOCATION


SHEET TITLE: SITE DETAILS

DRAWING NO. C4

REVISION: 1

Technical Data	
Description	Value
Frequency	N261 (27.5–28.35 GHz)
Number of carriers	Config mode 2:
	Up to 8
	Config mode 1:
	Up to 16
Operating bandwidth	Config mode 2:
	800 MHz
	Config mode 1:
	1600 MHz
Component carrier bandwidth	50MHz, 100 MHz
EIRP ⁽¹⁾	Config mode 2:
	53 dBm per RF beam in boresight , 56 dBm per radio
	Config mode 1:
	47 dBm per RF beam in boresight , 53 dBm per radio
EIS REFSENS_50M	Config mode 2:
	-109 dBm
	Config mode 1:
	-106 dBm

(1) The MaxTxPower can be configured up to 10 dB lower than the stated EIRP without product performance being degraded. If the MaxTxPower is configured lower than the given power limit here, significant performance degradation will occur.




Dimensions, Weight, and Color

Dimensions	
Height (A)	511 mm
Width (B)	200 mm
Depth (C)	125 mm
Weight	14 kg
Color	Gray
Reference number: NCS S 1002-B	

CFIT BOX

PART CODE: CFIT-C48D4LHXVZ
DESIGNED BY CHARLES INDUSTRIES



PRODUCT SPECIFICATIONS

TECHNICAL SPECIFICATIONS	
HEIGHT (PANEL ONLY)	15 in.
DEPTH, BASE (FRONT TO BACK)	5.5 in.
WIDTH	12 in.
WEIGHT	4 lbs.
CONSTRUCTION	RUGGED UL94-5VA GRAY POLYCARBONATE
SUPPORTED FIBER CONNECTOR TYPES	SC, LC or MPO
COMPLIANCE	DESIGNED TO MEET GR-950, GR2898, NEMA 4, IP66
SPLICING CAPACITY	UP TO THREE (3) 4"x6" HINGED SPLICE TRAYS ON FEED FIBER SIDE.
BULKHEAD CAPACITY	24 SC ADAPTERS

PREPARED FOR:

PREPARED BY:

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:	LA
CHECKED BY:	CTD

REVISIONS			
1	05/28/20	LA	PRELIMINARY REVIEW
0	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	JWY	PRELIMINARY REVIEW
NO.	DATE	BY	DESCRIPTION

ENGINEER'S STAMP:

6201054169

NOT VALID WITHOUT P.E. STAMP & SIGNATURE

SITE NAME:	40215
ADDRESS:	293 OLIVE ST YPSILANTI, MI 48197
COUNTY:	WASHTENAW
LATITUDE:	42° 14' 50.604" N
LONGITUDE:	83° 36' 57.528" W
DESIGN TYPE:	COLOCATION

EQUIPMENT DETAILS

DRAWING NO.	REVISION:
C5	1

1	6701 ANTENNA	N.T.S.	2	CFIT BOX	N.T.S.
---	--------------	--------	---	----------	--------

ELECTRICAL NOTES:

- 1. PROVIDE AND INSTALL WARNING TAPE FOR ELECTRIC SERVICE CONDUIT 18" ABOVE CONDUITS.
- 2. CONTRACTOR TO PAY FOR THE SERVICE AS DIRECTED BY THE MUNICIPALITY.
- 3. CONTRACTOR TO USE PVC SCH 80 CONDUIT WHERE CONDUITS CROSS ACCESS ROADS.
- 4. CONTRACTOR SHALL COORDINATE WITH ELECTRIC COMPANY FOR SERVICES.
- 5. CONTRACTOR TO PAY ALL FEES FOR SERVICES REQUIRED.
- 6. CONTRACTOR TO BE ADVISED THAT EXISTING UNDERGROUND CONDUITS, GROUND CABLES EXIST. DIG WITH CAUTION.
- 7. CONTRACTOR TO VERIFY POWER AND TELCO LB LOCATIONS AND FLEX CONDUIT SIZE AND ROUTING TO THE EQUIPMENT WITH MANUFACTURER'S DRAWINGS.
- 8. OPEN CUT CONSTRUCTION THROUGH EXISTING PAVEMENT, I.E. ROADWAYS, PARKING AREAS, SIDEWALKS WILL NOT BE ALLOWED. CONSTRUCTION UNDER EXISTING PAVEMENTS WILL BE REQUIRED TO BE INSTALLED WITH DIRECTIONAL BORING TECHNIQUE.

UTILITY NOTES:


- 1. ALL POWER CONDUITS ABOVE GRADE, SWEEPS, & ELBOWS TO BE PVC SCH 40.

STANDARD POWER SUPPLY FOR THE SMALL CELL NODES IS A 100 AMP 120/240 VOLT SINGLE PHASE SERVICE

WIRE SIZE	SERVICE CONDUCTOR MAXIMUM DISTANCE CHART (BASED ON 80 AMP MAX. CONTINUOUS LOAD)		CONDUIT SIZE
	ALUMINUM	COPPER	
	120V	120V	
3 AWG	55'	90'	1" MIN
2 AWG	70'	115'	1 1/4" MIN
1 AWG	85'	145'	1 1/4" MIN
1/0 AWG	110'	180'	1 1/2" MIN
2/0 AWG	140'	230'	1 1/2" MIN
3/0 AWG	175'	290'	2" MIN
4/0 AWG	220'	365'	2" MIN
250 KCMIL	265'	435'	2" MIN
300 KCMIL	315'	520'	2 1/2" MIN
350 KCMIL	370'	610'	2 1/2" MIN
400 KCMIL	420'	695'	2 1/2" MIN
500 KCMIL	530'	870'	3" MIN

LEGEND

OVERHEAD UTILITIES	DHU	CATCH BASIN	⌘
UNDERGROUND POWER	UGP	STREET SIGN	—
OVERHEAD POWER	DHP	4 WAY STREET SIGN	+
UNDERGROUND TELCO	UGT	UTILITY POLE	⊗
OVERHEAD TELCO	DHT	LIGHT POLE	⊙
GAS LINE	GAS	WATER VALVE	⌘
FENCE	x-x-x-x-x-x	MANHOLE	M
WOOD FENCE	o-o-o-o-o-o	GAS VALVE	G
SEWER LINE	SWR	FIRE HYDRANT	⊙
WATER LINE	WTR	TELCO PEDESTAL	T
HYBRID CABLE	HYB	ELECTRICAL BOX	E
HIGH VOLTAGE POWER	HVP		
FIBER	FBR		
RIGHT-OF-WAY	RDW		
PROPERTY LINE	PL		



PREPARED FOR:

verizon

PREPARED BY:

TeleCAD Wireless

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:

LA


CHECKED BY:

CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
1	05/28/20	LA	PRELIMINARY REVIEW
0	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	JWY	PRELIMINARY REVIEW

ENGINEER'S STAMP:



SITE NAME:

40215

ADDRESS:

293 OLIVE ST
YPSILANTI, MI 48197

COUNTY:

WASHTENAW

LATITUDE:

42° 14' 50.604" N

LONGITUDE:

83° 36' 57.528" W

DESIGN TYPE:

COLOCATION

SHEET TITLE:


UTILITY SITE PLAN

DRAWING NO.

E1


REVISION:

1



1 SINGLE POINT RADIAL GROUND DETAIL


N.T.S.



NOTE: TYPICAL SPACING FOR ALL UNDERGROUND CONDUITS.

2 TRENCH DETAIL (IF REQUIRED)

N.T.S.



3 GROUND ROD DETAIL

N.T.S.

4 DETAIL NOT IN USE

PREPARED FOR:

verizon

PREPARED BY:

TeleCAD
Wireless

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:

LA


CHECKED BY:

CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
1	05/28/20	LA	PRELIMINARY REVIEW
0	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	JWY	PRELIMINARY REVIEW

ENGINEER'S STAMP:



6201054169
NOT VALID WITHOUT P.E. STAMP & SIGNATURE

SITE NAME:

40215

ADDRESS:

293 OLIVE ST
YPSILANTI, MI 48197

COUNTY:

WASHTENAW

LATITUDE:

42° 14' 50.604" N

LONGITUDE:

83° 36' 57.528" W

DESIGN TYPE:

COLOCATION

SHEET TITLE:


ELECTRICAL DETAILS

DRAWING NO.

E2

REVISION:

1





City of Ypsilanti

Community and Economic Development

December 09, 2020

VERIZON WIRELESS
23100 PROVIDENCE DR #133
SOUTHFIELD, MI 48075

CERTIFICATE OF APPROPRIATENESS

RE: HDC Work Permit Application (PHDC-20-0089) for 301 W MICHIGAN

Dear VERIZON WIRELESS,

On Tuesday, December 8, 2020 the Historic District Commission (HDC) reviewed your request for work at 301 W MICHIGAN. Your application was **approved** to include:

The work as submitted in the application, dated December 1, 2020, for modification of an existing light pole to include the features in submitted drawings, including antennas, signage, and connection boxes.

In the commission's decision, the following Secretary of the Interior Standards were cited:
#10 - New work shall be removable.

Approval by the Historic District Commission does not guarantee approval by the zoning, building and/or other necessary departments. Before proceeding with the project it is the responsibility of the applicant to have obtained all approvals necessary. You must start work or apply for and receive all applicable permits within six months of this date for your HDC approval to remain valid. **Any change in the work listed above needs to be reviewed by the HDC using an amended application.**

Please contact me at 734-483-9646 or sslagor@cityofypsilanti.com with any questions.

Sincerely,



Scott E. Slagor, Preservation Planner
Community & Economic Development Department

CC: Property Owner - YPSILANTI COMMERCE CENTER LLC 23 N. WASHINGTON ST YPSILANTI MI 48197
File
Building Department

One South Huron Street
Ypsilanti, MI 48197

Tel: (734) 483-9646
Fax: (734) 483-7260

www.cityofypsilanti.com



City of Ypsilanti

Community and Economic Development

December 09, 2020

VERIZON WIRELESS
23100 PROVIDENCE DR #133
SOUTHFIELD, MI 48075

CERTIFICATE OF APPROPRIATENESS

RE: HDC Work Permit Application (PHDC-20-0091) for 401 N ADAMS

Dear VERIZON WIRELESS,

On Tuesday, December 8, 2020 the Historic District Commission (HDC) reviewed your request for work at 401 N ADAMS. Your application was **approved** to include:

The work as submitted in the application, dated December 1, 2020, for modification of an existing light pole to include the features in submitted drawings, including antennas, signage, and connection boxes.

In the commission's decision, the following Secretary of the Interior Standards were cited:
#10 - New work shall be removable.

Approval by the Historic District Commission does not guarantee approval by the zoning, building and/or other necessary departments. Before proceeding with the project it is the responsibility of the applicant to have obtained all approvals necessary. You must start work or apply for and receive all applicable permits within six months of this date for your HDC approval to remain valid. **Any change in the work listed above needs to be reviewed by the HDC using an amended application.**

Please contact me at 734-483-9646 or sslagor@cityofypsilanti.com with any questions.

Sincerely,



Scott E. Slagor, Preservation Planner
Community & Economic Development Department

CC: Property Owner - CITY OF YPSILANTI 651 RICE YPSILANTI MI 48198
File
Building Department

One South Huron Street
Ypsilanti, MI 48197


Tel: (734) 483-9646
Fax: (734) 483-7260

www.cityofypsilanti.com

SITE NAME:	45526
SITE ADDRESS: (ESTIMATED)	301 W MICHIGAN AVE YPSILANTI, MI 48197
COUNTY:	WASHTENAW
JURISDICTION:	CITY OF YPSILANTI
<u>SITE COORDINATES:</u>	
LATITUDE:	42° 14' 23.417" N
LATITUDE:	42.23984°
LONGITUDE:	83° 37' 0.070" W
LONGITUDE:	-83.61669°
ELEVATION:	±736'-3"
PROPERTY DEFINITION:	R.O.W.
FUZE PROJECT ID:	15899281
PSLC CODE:	577437
EXISTING POLE HEIGHT:	40'-0"



VICINITY MAP



NOT TO SCALE

An aerial map showing the intersection of S Adams St and Ferris St. A red pin marks the 'SITE LOCATION' at the corner. Other labels include 'KeyBank ATM', 'United States Postal Service', and 'Lawrence'.

NOT TO SCALE

[illegible]

- INSTALLING EQUIPMENT
 - CFIT BOX
 - DISCONNECT
- CONNECTING ONSITE UTILITIES TO WIRELESS EQUIPMENT

MICHIGAN

WASHTENAW COUNTY



TeleCAD
Wireless

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF
DOCUMENTS IS PROPRIETARY BY NATURE.
ANY USE OR DISCLOSURE OTHER THAN THAT
WHICH RELATES TO THE CLIENT IS STRICTLY
PROHIBITED.

DRAWN BY:	LA
CHECKED BY:	CTD

1	05/28/20	JCJ	CONSTRUCTION ISSUE
0	01/31/20	CDM	CONSTRUCTION ISSUE
A	01/27/20	LA	PRELIMINARY REVIEW
NO.	DATE	BY	DESCRIPTION

SED PROFESSIONAL RING

28/30

NOT VALID WITHOUT P.E. STAMP & SIGNATURE

SITE NAME:	45526
ADDRESS:	301 W MICHIGAN AVE YPSILANTI, MI 48197
COUNTY:	WASHTENAW
LATITUDE:	42° 14' 23.417" N
LONGITUDE:	83° 37' 0.070" W
DESIGN TYPE:	COLOCATION

SHEET TITLE:

TITLE SHEET

DRAWING NO.	REVISION:
T1	1

STRUCTURAL REVIEW

STRUCTURAL ANALYSIS PERFORMED BY OTHERS.

SHEET SCALE FACTOR:

PLOT SIZE:
11" x 17": TO SCALE



1 (800) 482-7171

www.missdig.com
CONTRACTOR TO CALL MICHIGAN
ONE-CALL SYSTEMS AT LEAST 72 HOURS
PRIOR TO DIGGING.

GENERAL NOTES

1. THESE NOTES SHALL BE CONSIDERED A PART OF THE WRITTEN SPECIFICATIONS.
2. THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED IN THE CONTRACT DOCUMENTS.
3. PRIOR TO THE SUBMISSION OF BIDS, THE CONTRACTOR(S) SHALL VISIT THE JOB SITE(S) AND BE RESPONSIBLE FOR ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS AND CONFIRMING THAT THE WORK MAY BE ACCOMPLISHED PER THE CONTRACT DOCUMENTS. ANY DISCREPANCIES ARE TO BE BROUGHT TO THE ATTENTION OF THE IMPLEMENTATION ENGINEER AND ARCHITECT/ENGINEER.
4. THE CONTRACTOR SHALL RECEIVE WRITTEN AUTHORIZATION TO PROCEED ON ANY WORK NOT CLEARLY DEFINED OR IDENTIFIED IN THE CONSTRUCTION DOCUMENTS BEFORE STARTING ANY WORK.
5. ALL WORK PERFORMED AND MATERIALS INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES INCLUDING APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS.
6. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH THE MANUFACTURER RECOMMENDATIONS. IF THESE RECOMMENDATIONS ARE IN CONFLICT WITH THE CONTRACT DOCUMENTS AND/OR APPLICABLE CODES OR REGULATIONS, REVIEW THE CONFLICT FOR DIRECTION WITH THE IMPLEMENTATION ENGINEER AND ARCHITECT/ENGINEER PRIOR TO PROCEEDING.
7. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, PROCEDURES AND FOR COORDINATION OF ALL PORTIONS OF THE WORK UNDER THE CONTRACT INCLUDING CONTACT AND COORDINATION WITH THE IMPLEMENTATION TEAM AND WITH THE AUTHORIZED REPRESENTATIVE OF ANY OUTSIDE POLE OR PROPERTY OWNER. (BASE COMMANDER OR AUTHORIZED AGENT)
8. THE CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO PROTECT EXISTING IMPROVEMENTS, PAVING, CURBS, VEGETATION, GALVANIZED SURFACE OR OTHER EXISTING ELEMENTS AND UPON COMPLETION OF THE WORK, REPAIR ANY DAMAGE THAT OCCURRED DURING CONSTRUCTION TO THE SATISFACTION OF EXTENT.
9. KEEP THE GENERAL AREA CLEAN, HAZARD FREE AND DISPOSE OF ALL DIRT, DEBRIS, RUBBISH AND REMOVE EQUIPMENT NOT SPECIFIED AS REMAINING ON THE PROPERTY. LEAVE PREMISES IN CLEAN CONDITION DAILY.
10. PLANS ARE INTENDED TO BE DIAGRAMMATIC ONLY AND SHOULD NOT BE SCALED UNLESS OTHERWISE NOTED. RELY ONLY ON ANNOTATED DIMENSIONS AND REQUEST INFORMATION IF ADDITIONAL DIMENSIONS ARE REQUIRED.
11. THE EXISTENCE AND LOCATION OF UTILITIES AND OTHER AGENCY'S FACILITIES ARE OBTAINED BY A SEARCH OF AVAILABLE RECORDS. OTHER FACILITIES MAY EXIST BEYOND WHAT IS NOTED. CONTRACTOR SHALL VERIFY LOCATIONS PRIOR TO START OF CONSTRUCTION AND USE EXTREME CARE AND PROTECTIVE MEASURES TO PREVENT DAMAGE TO THESE FACILITIES. CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF UTILITIES OR OTHER AGENCY'S FACILITIES WITHIN THE LIMITS OF THE WORK, WHETHER THEY ARE IDENTIFIED IN THE CONTRACT DOCUMENTS OR NOT.
12. ALL MOUNTING HARDWARE SUCH AS BOLTS, NUTS, LAG SCREWS, CLEVIS, CONDUIT STRAPS, STAPLES, (ANYTHING EXPOSED AND CONNECTING EQUIPMENT TO THE POLE SHALL BE HOT DIPPED GALVANIZED, UNLESS OTHERWISE STATED)

DEFINITIONS

1. "TYPICAL" OR "TYP." MEANS THAT THIS ITEM IS VIRTUALLY IDENTICAL ACROSS SIMILAR CONDITIONS. "TYP." SHALL BE UNDERSTOOD TO MEAN "TYPICAL WHERE OCCURS" AND SHALL NOT BE CONSIDERED AS WITHOUT EXCEPTION OR CONSIDERATION OF SPECIFIC CONDITIONS.
2. "SIMILAR" MEANS COMPARABLE TO CHARACTERISTICS FOR CONDITION NOTED. VERIFY DIMENSIONS AND ORIENTATION ON PLAN.
3. "AS REQUIRED" MEANS AS REQUIRED BY REGULATORY REQUIREMENTS BY REFERENCED STANDARDS, BY EXISTING CONDITIONS, BY GENERALLY ACCEPTED CONSTRUCTION PRACTICE OR BY THE CONTRACT DOCUMENTS.
4. "ALIGN" MEANS ACCURATELY LOCATE FINISH FACES OF MATERIALS IN THE SAME PLANE.
5. THE TERM "VERIFY" OR "V.I.F." SHALL BE UNDERSTOOD TO MEAN VERIFY IN FIELD WITH ARCHITECT AND REQUIRES THAT THE CONTRACTOR CONFIRM INTENTION REGARDING NOTED CONDITION AND PROCEED ONLY AFTER RECEIVING DIRECTION.
6. WHERE THE WORDS "OR EQUAL" OR WORDS OF SIMILAR INTENT FOLLOW A MATERIAL SPECIFICATION, THEY SHALL BE UNDERSTOOD TO REQUIRE SIGNED APPROVAL OF ANY DEVIATION TO SAID SPECIFICATION PRIOR TO CONTRACTOR'S ORDERING OR INSTALLATION OF SUCH PROPOSED EQUAL PRODUCT.
7. FURNISH: SUPPLY ONLY, OTHERS TO INSTALL. INSTALL: INSTALL ITEMS FURNISHED BY OTHERS. PROVIDE: FURNISH AND INSTALL.

PROJECT SPECIFIC NOTES

1. THIS SET IS PROVIDED TO ILLUSTRATE THE EXPECTED SCOPE OF DRAWINGS, QUALITY OF DRAWINGS AND EXTENT GRAPHIC STANDARDS. NOTES ARE FOR A&E CONTRACTOR REFERENCE TO HELP CLARIFY THE SCOPE. ADDITIONAL DRAWINGS MAY BE REQUIRED TO MEET THE REQUIREMENTS OF A GIVEN BASE. ALL EXAMPLES SHOWN ARE FOR REFERENCE ONLY AND ANY NOTES, DETAILS, CALCULATIONS OR OTHER WORK NEEDS TO BE COMPLETED OR CONFIRMED BY THE CONTRACTOR GENERATING THE DRAWINGS IN CONSTRUCTION DOCUMENTS.
2. THIS SET IS TO BE PRINTED AT 11" x 17". IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONFIRM THIS SIZE IS ACCEPTABLE BY THE BASE AND TO PROVIDE A LARGER STANDARD SIZE IF REQUIRED.
3. IT IS THE RESPONSIBILITY OF THE ENGINEER TO CONFIRM ALL WORK SHOWN IS IN COMPLIANCE WITH BASE AND FEDERAL CODES. DRAWINGS SHOWN WITHIN THIS SET ARE SAMPLES AND MAY NOT REFLECT ALL OF THE REQUIRED ELEMENTS, CLEARANCES OR OTHER ITEMS OF ASSEMBLIES NEEDED TO BE CODE COMPLIANT IN THE PARTICULAR MUNICIPALITY THE NODE IS LOCATED WITHIN.

GROUND CONSTRUCTION NOTES:

1. 120/240V POWER REQUIRED FOR 3-WIRE SERVICE.
2. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH FEDERAL STANDARDS AND REGULATIONS AS WELL AS NEC.
3. CALL MICHIGAN ONE CALL 72 HOURS PRIOR TO EXCAVATING AT (800) 482-7171.
4. ALL LANDSCAPING TO BE RESTORED TO ORIGINAL CONDITION OR BETTER.
5. ALL EQUIPMENT TO BE BONDED.
6. METERING CABINET (IF INSTALLED) REQUIRES 3' CLEARANCE AT DOOR OPENING.

STANDARD GROUNDING NOTES:

1. GROUND TESTED AT 25 OHMS OR LESS.
2. 5/8" x 8' RODS, CAD WELD OR UL LISTED DIRECT BURY CLAMP BELOW GRADE.
3. #6 GROUND AND BOND WIRE.
4. MOLDING, STAPLED EVERY 1' AND AT EACH END.
5. GROUND RODS 18" FROM POLE.

STANDARD CONDUIT NOTES:

1. FOR UNDERGROUND CONDUIT AND ABOVE GRADE RISERS USE SCHEDULE 40.
2. IF DIRECTIONAL BORING PLACE 1-1/4" SDR-11 GRAY CONDUIT FOR UNDERGROUND POWER APPLICATIONS.
3. IF TRENCHING, PLACE PVC SCH 40 CONDUIT PER TABLE ON SHEET E1 FOR UNDERGROUND POWER APPLICATIONS.
4. RISERS TO BE ATTACHED TO POLE WITH STANDARD STRAPS AND LAG SCREWS.
5. RISER STRAPS TO BE INSTALLED EVERY 5'.
6. CONDUIT UNDER 1" MAY BE ATTACHED WITH GROUND WIRE MOLDING STAPLES.
7. ALL CONDUIT WILL BE PROOFED WITH A MANDREL AND EQUIPPED WITH PULL ROPE OR MULE TAPE.

STANDARD TRENCHING NOTES:

1. MAINTAIN 42" MINIMUM COVER FOR ELECTRICAL CONDUIT.
2. MAINTAIN 42" MINIMUM COVER FOR COMMUNICATION CONDUIT.
3. IN STREET SLURRY TO GRADE AND MILL DOWN 1-1/2" FOR AC CAP.
4. IN DIRT SLURRY 18" FROM GRADE AND FILL WITH 95% COMPACTION NATIVE SOIL FOR BALANCE.
5. PLACE WARNING TAPE IN TRENCH 18" ABOVE ALL CONDUITS AND #18 WARNING TAPE ABOVE GROUND EQUIPMENT.

UTILITY POLE CONSTRUCTION NOTES:

1. NO BOLT THREADS TO PROTRUDE MORE THAN 1/2".
2. FILL ALL HOLES LEFT IN POLE FROM REARRANGEMENT OF CLIMBERS.
3. ALL CLIMB STEPS NEXT TO CONDUIT SHALL HAVE EXTENDED STEPS.
4. CABLE NOT TO IMPEDE 15" CLEAR SPACE OFF POLE FACE.
5. 90° SHORT SWEEP UNDER ANTENNA ARM. ALL CABLES MUST ONLY TRANSITION ON THE INSIDE OR BOTTOM OF ARMS (NO CABLE ON TOP OF ARMS).
6. USE CABLE CLAMPS TO SECURE CABLE TO ARMS; PLACE 2" CARRIER ID TAGS ON BOTH SIDE OF ARMS.
7. USE 90° CONNECTOR AT CABLE CONNECTION TO ANTENNAS.
8. USE 1/2" CABLE ON ANTENNAS UNLESS OTHERWISE SPECIFIED.
9. FILL VOID AROUND CABLES AT CONDUIT OPENING WITH FOAM SEALANT TO PREVENT WATER INTRUSION.

VERIZON WIRELESS CONSTRUCTION NOTES:

1. CONTRACTOR IS TO FOLLOW THE MOST CURRENT VZW STANDARDS DOCUMENTS PROVIDED TO COMPLETE THIS INSTALLATION.
2. CONTRACTOR SHALL COMPLETE VZW PROVIDED "SMALL CELL SWEEP REPORT" WITH ALL INFORMATION FILLED IN ACCURATELY AND COMPLETELY.
3. CONTRACTOR TO REFER TO THE MOST CURRENT VZW STANDARDS FOR APPROVED "PIM" TEST EQUIPMENT AND GUIDELINES.
4. CONTRACTOR IS TO USE BATTERY POWERED "PIM" EQUIPMENT TO VALIDATE THE FINAL LOCATION OF THE JUMPER AND ANTENNA ARE FREE OF INTERNAL AND EXTERNAL "PIM" SOURCES.
5. CONTRACTOR SHALL PROVIDE AT LEAST ONE TECHNICAL LEAD THAT IS CERTIFIED AND PROFICIENT IN EXECUTING, INTERPRETING AND RECORDING "PIM" MEASUREMENTS.

PREPARED FOR:



PREPARED BY:




DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:	LA
CHECKED BY:	CTD

REVISIONS			
1	05/28/20	JCJ	CONSTRUCTION ISSUE
0	01/31/20	CDM	CONSTRUCTION ISSUE
A	01/27/20	LA	PRELIMINARY REVIEW
NO.	DATE	BY	DESCRIPTION

ENGINEER'S STAMP:



SITE NAME:	45526
ADDRESS:	301 W MICHIGAN AVE YPSILANTI, MI 48197
COUNTY:	WASHTENAW
LATITUDE:	42° 14' 23.417" N
LONGITUDE:	83° 37' 0.070" W
DESIGN TYPE:	COLOCATION

SHEET TITLE:	GENERAL NOTES
--------------	---------------

DRAWING NO.	REVISION:
GN1	1

NOTES:

1. THIS DRAWING IS BASED ON AERIAL IMAGERY AND FIELD OBSERVATIONS. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO COMMENCEMENT OF CONSTRUCTION.
2. THE PROPOSED USE DOES NOT REQUIRE FULL OR PART TIME EMPLOYEES AT THE SITE.
3. FOR GENERAL SITE WORK NOTES, SEE SHEET GN1.
4. ALL NORTH ARROWS ON SITE PLANS ARE TRUE NORTH, UNLESS OTHERWISE SPECIFIED.
5. OPEN CUT CONSTRUCTION THROUGH EXISTING PAVEMENT, I.E. ROADWAYS, PARKING AREAS, SIDEWALKS WILL NOT BE ALLOWED. CONSTRUCTION UNDER EXISTING PAVEMENTS WILL BE REQUIRED TO BE INSTALLED WITH DIRECTIONAL BORING TECHNIQUE.
6. RIGHT OF WAY INFORMATION ACQUIRED FROM GIS.

LEGEND

OVERHEAD UTILITIES	— DHU —	CATCH BASIN	⌘
UNDERGROUND POWER	— UGP —	STREET SIGN	—
OVERHEAD POWER	— DHP —	4 WAY STREET SIGN	+
UNDERGROUND TELCO	— UGT —	UTILITY POLE	⊙
OVERHEAD TELCO	— DHT —	LIGHT POLE	⊙
GAS LINE	— GAS —	WATER VALVE	⊗
FENCE	— X —	MANHOLE	⊗
WOOD FENCE	— O —	GAS VALVE	⊗
SEWER LINE	— SWR —	FIRE HYDRANT	⊗
WATER LINE	— VTR —	TELCO PEDESTAL	⊗
HYBRID CABLE	— HYB —	ELECTRICAL BOX	⊗
HIGH VOLTAGE POWER	— HVP —		
FIBER	— FBR —		
RIGHT-OF-WAY	— RDW —		
PROPERTY LINE	— PL —		

UTILITY NOTE:

THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES HAVE NOT BEEN VERIFIED. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT OCCUR BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

PREPARED FOR:

verizon

PREPARED BY:

TeleCAD
Wireless

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:

LA

CHECKED BY:

CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
1	05/28/20	JCJ	CONSTRUCTION ISSUE
0	01/31/20	CDM	CONSTRUCTION ISSUE
A	01/27/20	LA	PRELIMINARY REVIEW

ENGINEER'S STAMP:



NOT VALID WITHOUT P.E. STAMP & SIGNATURE

SITE NAME:

45526

ADDRESS:

301 W MICHIGAN AVE
YPSILANTI, MI 48197

COUNTY:

WASHTENAW

LATITUDE:

42° 14' 23.417" N

LONGITUDE:

83° 37' 0.070" W

DESIGN TYPE:

COLOCATION

SHEET TITLE:


SITE LAYOUTS

DRAWING NO.


C1

REVISION:

1



1 OVERALL SITE LAYOUT



2 ENLARGED SITE LAYOUT



1 OVERALL SITE LAYOUT - AERIAL IMAGERY

PREPARED FOR:



PREPARED BY:





1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF
DOCUMENTS IS PROPRIETARY BY NATURE.
ANY USE OR DISCLOSURE OTHER THAN THAT
WHICH RELATES TO THE CLIENT IS STRICTLY
PROHIBITED.

DRAWN BY:	LA
CHECKED BY:	CTD

REVISIONS			
1	05/28/20	JCJ	CONSTRUCTION ISSUE
0	01/31/20	CDM	CONSTRUCTION ISSUE
A	01/27/20	LA	PRELIMINARY REVIEW
NO.	DATE	BY	DESCRIPTION

ENGINEER'S STAMP:



SITE NAME:	45526
ADDRESS:	301 W MICHIGAN AVE YPSILANTI, MI 48197
COUNTY:	WASHTENAW
LATITUDE:	42° 14' 23.417" N
LONGITUDE:	83° 37' 0.070" W
DESIGN TYPE:	COLOCATION

SHEET TITLE:	SITE LAYOUT - AERIAL IMAGERY
--------------	---------------------------------

DRAWING NO.	REVISION:
C1A	1

CONTRACTOR TO OBTAIN
LATEST RFDS FROM VERIZON
PRIOR TO CONSTRUCTION.

MAINTAIN A MIN. OF 3'-0"
CLEARANCE BETWEEN
DISCONNECT BOX AND ANY
COMM LINES

40" MIN. CLEARANCE
BELOW NEW TRIPLEX
SERVICE

5'-0" MIN. CLEARANCE ABOVE
ANY DTE EQUIPMENT TO
BOTTOM OF ANTENNA

REFER TO RFDS FOR SMALL
CELL AZIMUTHS

NOTICE



Transmitting Antenna(s)
Radio frequency fields beyond
this point MAY EXCEED the FCC
General Population exposure
limit.
Obey all posted signs and
site guidelines.
Call Verizon at 1-800-264-6620
PRIOR to working beyond this
point.
Site ID/ PSLC: 577437 (45526)



6"x7.5" VERTICAL
RF NOTICE SIGN
TYPICAL OF 2

PROPOSED ERICSSON
6701 ANTENNA
(SEE DETAIL 1 PAGE C5)

EXISTING WOOD
LIGHT POLE

PROPOSED RISER
AND WEATHER HEAD,
TRIPLEX SERVICE
PROVIDED BY
OTHERS

PROPOSED 120/240V GE
TG3223R DISCONNECT BOX

PROPOSED NEMA 3R
120/240V 100A
6 POSITION PANEL

PROPOSED POLE
MOUNTED CFIT BOX
(SEE DETAIL 2 PAGE C5)

PRE-ASSEMBLE
DISCONNECT AND
BREAKER BOX ON
THINSTRUT

FINISH GRADE



IN CASE OF EMERGENCY
CALL 1-800-852-2671

SITE DESIGNATION: 45526

INSTALL ON BREAKER PANEL

1 POLE ELEVATION

PREPARED FOR:



PREPARED BY:




1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF
DOCUMENTS IS PROPRIETARY BY NATURE.
ANY USE OR DISCLOSURE OTHER THAN THAT
WHICH RELATES TO THE CLIENT IS STRICTLY
PROHIBITED.

DRAWN BY: LA
CHECKED BY: CTD

REVISIONS				
NO.	DATE	BY	DESCRIPTION	
1	05/28/20	JCJ	CONSTRUCTION ISSUE	
0	01/31/20	CDM	CONSTRUCTION ISSUE	
A	01/27/20	LA	PRELIMINARY REVIEW	

ENGINEER'S STAMP:



6201054169

NOT VALID WITHOUT P.E. STAMP & SIGNATURE

SITE NAME: 45526
ADDRESS: 301 W MICHIGAN AVE
YPSILANTI, MI 48197
COUNTY: WASHTENAW
LATITUDE: 42° 14' 23.417" N
LONGITUDE: 83° 37' 0.070" W
DESIGN TYPE: COLOCATION


SHEET TITLE:
POLE ELEVATION

DRAWING NO. C2
REVISION: 1


N.T.S.

POLE ATTACHED EQUIPMENT	
EQUIPMENT	VOLUME (CU-FT)
6701 ANTENNA	0.46
6701 ANTENNA	0.46
6701 ANTENNA	0.46
TOTAL IN CU-FT	1.38

POLE ANCILLARY EQUIPMENT	
EQUIPMENT	VOLUME (CU-FT)
6 POSITION PANEL	0.80
DISCONNECT	0.57
CFIT BOX	0.60
TOTAL IN CU-FT	1.97



2 RF EXPOSURE LIMIT N.T.S.



NOTES:

1. WORKING CLEARANCE FROM ENERGIZED ANTENNA MUST BE GREATER THAN 4 FT, OTHERWISE SHUT DOWN RADIO AND ANTENNA PER INSTRUCTIONS ON PLACARD OR BY OPENING DISCONNECT SWITCH TO RADIO EQUIPMENT ON POLE.
2. ANTENNA AND MOUNTING BRACKETS INSTALLED ABOVE DTE WIRES MUST BE INSTALLED AND MAINTAINED BY DTE OR DTE'S DESIGNATED CONTRACTOR.
3. VERTICAL CLIMBING ZONE MUST BE MAINTAINED ON ALL POLES. (SEE TOP VIEW)
4. BASE CABINET TO BE CLEARLY LABELED WITH OWNER'S NAME AND 1-800 PHONE NUMBER WITH 3/4" TALL LETTERING.
5. SHUTDOWN PLACARD TO BE PLACED ON THE POLE NEAR BASE CABINET AND DISCONNECT SWITCH BOX.
6. 5' FT MIN. CLEARANCE ABOVE ANY DTE EQUIPMENT.
7. ANTENNA POLE TOP CLEARANCES APPLY TO ANY DTE EQUIPMENT OR WIRES INSTALLED UNDER THE ANTENNA.

REFERENCE DTE ENERGY
CELLULAR ANTENNA SMALL CELL SITE CONSTRUCTION
LINE CONSTRUCTION STANDARDS 4-JOINT USE 1-4-26.1
DATED 11/1/2017

3 DTE CLIMBING ZONE REQUIREMENT AND NOTES N.T.S.

PREPARED FOR:



PREPARED BY:




DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY: LA
CHECKED BY: CTD

REVISIONS			
1	05/28/20	JCJ	CONSTRUCTION ISSUE
0	01/31/20	CDM	CONSTRUCTION ISSUE
A	01/27/20	LA	PRELIMINARY REVIEW
NO.	DATE	BY	DESCRIPTION


ENGINEER'S STAMP:



SITE NAME: 45526
ADDRESS: 301 W MICHIGAN AVE
YPSILANTI, MI 48197
COUNTY: WASHTENAW
LATITUDE: 42° 14' 23.417" N
LONGITUDE: 83° 37' 0.070" W
DESIGN TYPE: COLOCATION

SHEET TITLE: SITE DETAILS

DRAWING NO. C3
REVISION: 1



PREPARED FOR:

verizon

PREPARED BY:

TeleCAD
Wireless

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:

LA


CHECKED BY:

CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
1	05/28/20	JCJ	CONSTRUCTION ISSUE
0	01/31/20	CDM	CONSTRUCTION ISSUE
A	01/27/20	LA	PRELIMINARY REVIEW

ENGINEER'S STAMP:



SITE NAME:

45526

ADDRESS:

301 W MICHIGAN AVE
YPSILANTI, MI 48197

COUNTY:

WASHTENAW

LATITUDE:

42° 14' 23.417" N

LONGITUDE:

83° 37' 0.070" W

DESIGN TYPE:

COLOCATION

SHEET TITLE:

SITE DETAILS

DRAWING NO.

C4


REVISION:

1

Technical Data

Description	Value
Frequency	N261 (27.5–28.35 GHz)
Number of carriers	Config mode 2: Up to 8 Config mode 1: Up to 16
Operating bandwidth	Config mode 2: 800 MHz Config mode 1: 1600 MHz
Component carrier bandwidth	50MHz, 100 MHz
EIRP ⁽¹⁾	Config mode 2: 53 dBm per RF beam in boresight , 56 dBm per radio Config mode 1: 47 dBm per RF beam in boresight , 53 dBm per radio
EIS _{REFSENS_50M}	Config mode 2: -109 dBm Config mode 1: -106 dBm


(1) The MaxTxPower can be configured up to 10 dB lower than the stated EIRP without product performance being degraded. If the MaxTxPower is configured lower than the given power limit here, significant performance degradation will occur.



Dimensions, Weight, and Color

Dimensions	
Height (A)	511 mm
Width (B)	200 mm
Depth (C)	125 mm
Weight	14 kg
Color	Gray Reference number: NCS S 1002-B

CFIT BOX



PART CODE: CFIT-C48D4LHXVZ

DESIGNED BY CHARLES INDUSTRIES

PRODUCT SPECIFICATIONS

TECHNICAL SPECIFICATIONS	
HEIGHT (PANEL ONLY)	15 in.
DEPTH, BASE (FRONT TO BACK)	5.5 in.
WIDTH	12 in.
WEIGHT	4 lbs.
CONSTRUCTION	RUGGED UL94-5VA GRAY POLYCARBONATE
SUPPORTED FIBER CONNECTOR TYPES	SC, LC or MPO
COMPLIANCE	DESIGNED TO MEET GR-950, GR2898, NEMA 4, IP66
SPLICING CAPACITY	UP TO THREE (3) 4"x6" HINGED SPLICE TRAYS ON FEED FIBER SIDE.
BULKHEAD CAPACITY	24 SC ADAPTERS

PREPARED FOR:

verizon

PREPARED BY:

TeleCAD
Wireless
1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509


DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:	LA
CHECKED BY:	CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
1	05/28/20	JCJ	CONSTRUCTION ISSUE
0	01/31/20	CDM	CONSTRUCTION ISSUE
A	01/27/20	LA	PRELIMINARY REVIEW

ENGINEER'S STAMP:



SITE NAME:	45526
ADDRESS:	301 W MICHIGAN AVE YPSILANTI, MI 48197
COUNTY:	WASHTENAW
LATITUDE:	42° 14' 23.417" N
LONGITUDE:	83° 37' 0.070" W
DESIGN TYPE:	COLOCATION

SHEET TITLE:
EQUIPMENT DETAILS

DRAWING NO.	REVISION:
C5	1

1 6701 ANTENNA

N.T.S.

2 CFIT BOX

N.T.S.

ELECTRICAL NOTES:

- 1. PROVIDE AND INSTALL WARNING TAPE FOR ELECTRIC SERVICE CONDUIT 18" ABOVE CONDUITS.
- 2. CONTRACTOR TO PAY FOR THE SERVICE AS DIRECTED BY THE MUNICIPALITY.
- 3. CONTRACTOR TO USE PVC SCH 80 CONDUIT WHERE CONDUITS CROSS ACCESS ROADS.
- 4. CONTRACTOR SHALL COORDINATE WITH ELECTRIC COMPANY FOR SERVICES.
- 5. CONTRACTOR TO PAY ALL FEES FOR SERVICES REQUIRED.
- 6. CONTRACTOR TO BE ADVISED THAT EXISTING UNDERGROUND CONDUITS, GROUND CABLES EXIST. DIG WITH CAUTION.
- 7. CONTRACTOR TO VERIFY POWER AND TELCO LB LOCATIONS AND FLEX CONDUIT SIZE AND ROUTING TO THE EQUIPMENT WITH MANUFACTURER'S DRAWINGS.
- 8. OPEN CUT CONSTRUCTION THROUGH EXISTING PAVEMENT, I.E. ROADWAYS, PARKING AREAS, SIDEWALKS WILL NOT BE ALLOWED. CONSTRUCTION UNDER EXISTING PAVEMENTS WILL BE REQUIRED TO BE INSTALLED WITH DIRECTIONAL BORING TECHNIQUE.

UTILITY NOTES:


- 1. ALL POWER CONDUITS ABOVE GRADE, SWEEPS, & ELBOWS TO BE PVC SCH 40.

STANDARD POWER SUPPLY FOR THE SMALL CELL NODES IS A 100 AMP 120/240 VOLT SINGLE PHASE SERVICE

SERVICE CONDUCTOR MAXIMUM DISTANCE CHART (BASED ON 80 AMP MAX. CONTINUOUS LOAD)			
WIRE SIZE	ALUMINUM	COPPER	CONDUIT SIZE
	120V	120V	
3 AWG	55'	90'	1" MIN
2 AWG	70'	115'	1 1/4" MIN
1 AWG	85'	145'	1 1/4" MIN
1/0 AWG	110'	180'	1 1/2" MIN
2/0 AWG	140'	230'	1 1/2" MIN
3/0 AWG	175'	290'	2" MIN
4/0 AWG	220'	365'	2" MIN
250 KCMIL	265'	435'	2" MIN
300 KCMIL	315'	520'	2 1/2" MIN
350 KCMIL	370'	610'	2 1/2" MIN
400 KCMIL	420'	695'	2 1/2" MIN
500 KCMIL	530'	870'	3" MIN

LEGEND

OVERHEAD UTILITIES	DHU	CATCH BASIN	
UNDERGROUND POWER	UGP	STREET SIGN	
OVERHEAD POWER	DHP	4 WAY STREET SIGN	
UNDERGROUND TELCO	UGT	UTILITY POLE	
OVERHEAD TELCO	DHT	LIGHT POLE	
GAS LINE	GAS	WATER VALVE	
FENCE	X-X-X-X-X-X	MANHOLE	
WOOD FENCE	O-O-O-O-O-O	GAS VALVE	
SEWER LINE	SWR	FIRE HYDRANT	
WATER LINE	WTR	TELCO PEDESTAL	
HYBRID CABLE	HYB	ELECTRICAL BOX	
HIGH VOLTAGE POWER	HVP		
FIBER	FBR		
RIGHT-OF-WAY	RDW		
PROPERTY LINE	PL		



PREPARED FOR:

verizon

PREPARED BY:

TeleCAD Wireless

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:

LA


CHECKED BY:

CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
1	05/28/20	JCJ	CONSTRUCTION ISSUE
0	01/31/20	CDM	CONSTRUCTION ISSUE
A	01/27/20	LA	PRELIMINARY REVIEW

ENGINEER'S STAMP:



NOT VALID WITHOUT P.E. STAMP & SIGNATURE

SITE NAME:

45526

ADDRESS:

301 W MICHIGAN AVE
YPSILANTI, MI 48197

COUNTY:

WASHTENAW

LATITUDE:

42° 14' 23.417" N

LONGITUDE:

83° 37' 0.070" W

DESIGN TYPE:

COLOCATION

SHEET TITLE:


UTILITY SITE PLAN

DRAWING NO.

E1


REVISION:

1



1 SINGLE POINT RADIAL GROUND DETAIL


N.T.S.



NOTE: TYPICAL SPACING FOR ALL UNDERGROUND CONDUITS.

2 TRENCH DETAIL (IF REQUIRED)

N.T.S.



3 GROUND ROD DETAIL

N.T.S.

4 DETAIL NOT IN USE

PREPARED FOR:

verizon

PREPARED BY:

TeleCAD
Wireless

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:

LA


CHECKED BY:

CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
1	05/28/20	JCJ	CONSTRUCTION ISSUE
0	01/31/20	CDM	CONSTRUCTION ISSUE
A	01/27/20	LA	PRELIMINARY REVIEW

ENGINEER'S STAMP:



NOT VALID WITHOUT P.E. STAMP & SIGNATURE

SITE NAME:

45526

ADDRESS:

301 W MICHIGAN AVE
YPSILANTI, MI 48197

COUNTY:

WASHTENAW

LATITUDE:

42° 14' 23.417" N

LONGITUDE:

83° 37' 0.070" W

DESIGN TYPE:

COLOCATION

SHEET TITLE:


ELECTRICAL DETAILS

DRAWING NO.

E2

REVISION:

1



PROJECT SUMMARY

SITE NAME: 40214
SITE ADDRESS: 401 NORTH ADAMS STREET
(ESTIMATED) YPSILANTI, MI 48197
COUNTY: WASHTENAW COUNTY
SITE COORDINATES:
LATITUDE: 42° 14' 45.24" N (NAD 83)
LATITUDE: 42.24590°
LONGITUDE: 83° 36' 58.14" W (NAD 83)
LONGITUDE: -83.61615°
ELEVATION: ±737'-10"

PROPERTY DEFINITION: R.O.W.
FUZE PROJECT ID: 15487101
PSLC CODE: 544745
EXISTING POLE NUMBER: N/A
EXISTING POLE HEIGHT: 38'-6"
EXISTING POLE CLASS: N/A



SITE NAME: 40214

PROPOSED SMALL CELL EQUIPMENT
ON AN EXISTING DTE POLE

SHEET INDEX

NO.	DESCRIPTION
T1	TITLE SHEET
GN1	GENERAL NOTES
C1	SITE LAYOUTS
C2	POLE ELEVATION
C2A	ANTENNA LAYOUT
C3	DTE NOTES
C4	SITE DETAILS
C5	EQUIPMENT DETAILS
E1	UTILITY SITE PLAN
E2	ELECTRICAL DETAILS
E3	SINGLE LINE DIAGRAM

PREPARED FOR:

verizon

PREPARED BY:



1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS
SET OF DOCUMENTS IS PROPRIETARY BY
NATURE. ANY USE OR DISCLOSURE OTHER
THAN THAT WHICH RELATES TO THE
CLIENT IS STRICTLY PROHIBITED.


DRAWN BY: LA

CHECKED BY: CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
0	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	LA	PRELIMINARY REVIEW

ENGINEER'S STAMP:



SITE NAME:

40214

COUNTY: WASHTENAW

LATITUDE: 42° 14' 45.24" N

LONGITUDE: 83° 36' 58.14" W

DESIGN TYPE: COLOCATION

SHEET TITLE:

TITLE SHEET


DRAWING NO.

T1

REVISION:

0

VICINITY MAP



NOT TO SCALE

LOCATION MAP




NOT TO SCALE

SCOPE OF WORK

- INSTALLING EQUIPMENT
 - CFIT BOX
 - DISCONNECT
- CONNECTING ON SITE UTILITIES TO WIRELESS EQUIPMENT

STATE COUNTY MAP



STRUCTURAL REVIEW

STRUCTURAL ANALYSIS PERFORMED BY OTHERS.

SHEET SCALE FACTOR:

PLOT SIZE:
11" x 17": TO SCALE



1 (800) 482-7171

www.missdig.com
CONTRACTOR TO CALL MICHIGAN
ONE-CALL SYSTEMS AT LEAST 72 HOURS
PRIOR TO DIGGING.

GENERAL NOTES

1. THESE NOTES SHALL BE CONSIDERED A PART OF THE WRITTEN SPECIFICATIONS.
2. THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED IN THE CONTRACT DOCUMENTS.
3. PRIOR TO THE SUBMISSION OF BIDS, THE CONTRACTOR(S) SHALL VISIT THE JOB SITE(S) AND BE RESPONSIBLE FOR ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS AND CONFIRMING THAT THE WORK MAY BE ACCOMPLISHED PER THE CONTRACT DOCUMENTS. ANY DISCREPANCIES ARE TO BE BROUGHT TO THE ATTENTION OF THE IMPLEMENTATION ENGINEER AND ARCHITECT/ENGINEER.
4. THE CONTRACTOR SHALL RECEIVE WRITTEN AUTHORIZATION TO PROCEED ON ANY WORK NOT CLEARLY DEFINED OR IDENTIFIED IN THE CONSTRUCTION DOCUMENTS BEFORE STARTING ANY WORK.
5. ALL WORK PERFORMED AND MATERIALS INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES INCLUDING APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS.
6. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH THE MANUFACTURER RECOMMENDATIONS. IF THESE RECOMMENDATIONS ARE IN CONFLICT WITH THE CONTRACT DOCUMENTS AND/OR APPLICABLE CODES OR REGULATIONS, REVIEW THE CONFLICT FOR DIRECTION WITH THE IMPLEMENTATION ENGINEER AND ARCHITECT/ENGINEER PRIOR TO PROCEEDING.
7. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, PROCEDURES AND FOR COORDINATION OF ALL PORTIONS OF THE WORK UNDER THE CONTRACT INCLUDING CONTACT AND COORDINATION WITH THE IMPLEMENTATION TEAM AND WITH THE AUTHORIZED REPRESENTATIVE OF ANY OUTSIDE POLE OR PROPERTY OWNER. (BASE COMMANDER OR AUTHORIZED AGENT)
8. THE CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO PROTECT EXISTING IMPROVEMENTS, PAVING, CURBS, VEGETATION, GALVANIZED SURFACE OR OTHER EXISTING ELEMENTS AND UPON COMPLETION OF THE WORK, REPAIR ANY DAMAGE THAT OCCURRED DURING CONSTRUCTION TO THE SATISFACTION OF EXTENT.
9. KEEP THE GENERAL AREA CLEAN, HAZARD FREE AND DISPOSE OF ALL DIRT, DEBRIS, RUBBISH AND REMOVE EQUIPMENT NOT SPECIFIED AS REMAINING ON THE PROPERTY. LEAVE PREMISES IN CLEAN CONDITION DAILY.
10. PLANS ARE INTENDED TO BE DIAGRAMMATIC ONLY AND SHOULD NOT BE SCALED UNLESS OTHERWISE NOTED. RELY ONLY ON ANNOTATED DIMENSIONS AND REQUEST INFORMATION IF ADDITIONAL DIMENSIONS ARE REQUIRED.
11. THE EXISTENCE AND LOCATION OF UTILITIES AND OTHER AGENCY'S FACILITIES ARE OBTAINED BY A SEARCH OF AVAILABLE RECORDS. OTHER FACILITIES MAY EXIST BEYOND WHAT IS NOTED. CONTRACTOR SHALL VERIFY LOCATIONS PRIOR TO START OF CONSTRUCTION AND USE EXTREME CARE AND PROTECTIVE MEASURES TO PREVENT DAMAGE TO THESE FACILITIES. CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF UTILITIES OR OTHER AGENCY'S FACILITIES WITHIN THE LIMITS OF THE WORK, WHETHER THEY ARE IDENTIFIED IN THE CONTRACT DOCUMENTS OR NOT.
12. ALL MOUNTING HARDWARE SUCH AS BOLTS, NUTS, LAG SCREWS, CLEVIS, CONDUIT STRAPS, STAPLES, (ANYTHING EXPOSED AND CONNECTING EQUIPMENT TO THE POLE SHALL BE HOT DIPPED GALVANIZED, UNLESS OTHERWISE STATED)

DEFINITIONS

1. "TYPICAL" OR "TYP." MEANS THAT THIS ITEM IS VIRTUALLY IDENTICAL ACROSS SIMILAR CONDITIONS. "TYP." SHALL BE UNDERSTOOD TO MEAN "TYPICAL WHERE OCCURS" AND SHALL NOT BE CONSIDERED AS WITHOUT EXCEPTION OR CONSIDERATION OF SPECIFIC CONDITIONS.
2. "SIMILAR" MEANS COMPARABLE TO CHARACTERISTICS FOR CONDITION NOTED. VERIFY DIMENSIONS AND ORIENTATION ON PLAN.
3. "AS REQUIRED" MEANS AS REQUIRED BY REGULATORY REQUIREMENTS BY REFERENCED STANDARDS, BY EXISTING CONDITIONS, BY GENERALLY ACCEPTED CONSTRUCTION PRACTICE OR BY THE CONTRACT DOCUMENTS.
4. "ALIGN" MEANS ACCURATELY LOCATE FINISH FACES OF MATERIALS IN THE SAME PLANE.
5. THE TERM "VERIFY" OR "V.I.F" SHALL BE UNDERSTOOD TO MEAN VERIFY IN FIELD WITH ARCHITECT AND REQUIRES THAT THE CONTRACTOR CONFIRM INTENTION REGARDING NOTED CONDITION AND PROCEED ONLY AFTER RECEIVING DIRECTION.
6. WHERE THE WORDS "OR EQUAL" OR WORDS OF SIMILAR INTENT FOLLOW A MATERIAL SPECIFICATION, THEY SHALL BE UNDERSTOOD TO REQUIRE SIGNED APPROVAL OF ANY DEVIATION TO SAID SPECIFICATION PRIOR TO CONTRACTOR'S ORDERING OR INSTALLATION OF SUCH PROPOSED EQUAL PRODUCT.
7. FURNISH: SUPPLY ONLY, OTHERS TO INSTALL. INSTALL: INSTALL ITEMS FURNISHED BY OTHERS. PROVIDE: FURNISH AND INSTALL.

PROJECT SPECIFIC NOTES

1. THIS SET IS PROVIDED TO ILLUSTRATE THE EXPECTED SCOPE OF DRAWINGS, QUALITY OF DRAWINGS AND EXTENT GRAPHIC STANDARDS. NOTES ARE FOR A&E CONTRACTOR REFERENCE TO HELP CLARIFY THE SCOPE. ADDITIONAL DRAWINGS MAY BE REQUIRED TO MEET THE REQUIREMENTS OF A GIVEN BASE. ALL EXAMPLES SHOWN ARE FOR REFERENCE ONLY AND ANY NOTES, DETAILS, CALCULATIONS OR OTHER WORK NEEDS TO BE COMPLETED OR CONFIRMED BY THE CONTRACTOR GENERATING THE DRAWINGS IN CONSTRUCTION DOCUMENTS.
2. THIS SET IS TO BE PRINTED AT 11" x 17". IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONFIRM THIS SIZE IS ACCEPTABLE BY THE BASE AND TO PROVIDE A LARGER STANDARD SIZE IF REQUIRED.
3. IT IS THE RESPONSIBILITY OF THE ENGINEER TO CONFIRM ALL WORK SHOWN IS IN COMPLIANCE WITH BASE AND FEDERAL CODES. DRAWINGS SHOWN WITHIN THIS SET ARE SAMPLES AND MAY NOT REFLECT ALL OF THE REQUIRED ELEMENTS, CLEARANCES OR OTHER ITEMS OF ASSEMBLIES NEEDED TO BE CODE COMPLIANT IN THE PARTICULAR MUNICIPALITY THE NODE IS LOCATED WITHIN.

GROUND CONSTRUCTION NOTES:

1. 120/240V POWER REQUIRED FOR 3-WIRE SERVICE.
2. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH FEDERAL STANDARDS AND REGULATIONS AS WELL AS NEC.
3. CALL MICHIGAN ONE CALL 72 HOURS PRIOR TO EXCAVATING AT (800) 482-7171.
4. ALL LANDSCAPING TO BE RESTORED TO ORIGINAL CONDITION OR BETTER.
5. ALL EQUIPMENT TO BE BONDED.
6. METERING CABINET (IF INSTALLED) REQUIRES 3' CLEARANCE AT DOOR OPENING.

STANDARD GROUNDING NOTES:

1. GROUND TESTED AT 25 OHMS OR LESS.
2. 5/8" x 8' RODS, CAD WELD OR UL LISTED DIRECT BURY CLAMP BELOW GRADE.
3. #6 GROUND AND BOND WIRE.
4. MOLDING, STAPLED EVERY 1' AND AT EACH END.
5. GROUND RODS 18" FROM POLE.

STANDARD CONDUIT NOTES:

1. FOR UNDERGROUND CONDUIT AND ABOVE GRADE RISERS USE SCHEDULE 40.
2. IF DIRECTIONAL BORING PLACE 1-1/4" SDR-11 GRAY CONDUIT FOR UNDERGROUND POWER APPLICATIONS.
3. IF TRENCHING, PLACE PVC SCH 40 CONDUIT PER TABLE ON SHEET E1 FOR UNDERGROUND POWER APPLICATIONS.
4. RISERS TO BE ATTACHED TO POLE WITH STANDARD STRAPS AND LAG SCREWS.
5. RISER STRAPS TO BE INSTALLED EVERY 5'.
6. CONDUIT UNDER 1" MAY BE ATTACHED WITH GROUND WIRE MOLDING STAPLES.
7. ALL CONDUIT WILL BE PROOFED WITH A MANDREL AND EQUIPPED WITH PULL ROPE OR MULE TAPE.

STANDARD TRENCHING NOTES:

1. MAINTAIN 36" MINIMUM COVER FOR ELECTRICAL CONDUIT.
2. MAINTAIN 36" MINIMUM COVER FOR COMMUNICATION CONDUIT.
3. IN STREET SLURRY TO GRADE AND MILL DOWN 1-1/2" FOR AC CAP.
4. IN DIRT SLURRY 18" FROM GRADE AND FILL WITH 95% COMPACTION NATIVE SOIL FOR BALANCE.
5. PLACE WARNING TAPE IN TRENCH 12" ABOVE ALL CONDUITS AND #18 WARNING TAPE ABOVE GROUND EQUIPMENT.

UTILITY POLE CONSTRUCTION NOTES:

1. NO BOLT THREADS TO PROTRUDE MORE THAN 1/2".
2. FILL ALL HOLES LEFT IN POLE FROM REARRANGEMENT OF CLIMBERS.
3. ALL CLIMB STEPS NEXT TO CONDUIT SHALL HAVE EXTENDED STEPS.
4. CABLE NOT TO IMPEDE 15" CLEAR SPACE OFF POLE FACE.
5. 90° SHORT SWEEP UNDER ANTENNA ARM. ALL CABLES MUST ONLY TRANSITION ON THE INSIDE OR BOTTOM OF ARMS (NO CABLE ON TOP OF ARMS).
6. USE CABLE CLAMPS TO SECURE CABLE TO ARMS; PLACE 2" CARRIER ID TAGS ON BOTH SIDE OF ARMS.
7. USE 90° CONNECTOR AT CABLE CONNECTION TO ANTENNAS.
8. USE 1/2" CABLE ON ANTENNAS UNLESS OTHERWISE SPECIFIED.
9. FILL VOID AROUND CABLES AT CONDUIT OPENING WITH FOAM SEALANT TO PREVENT WATER INTRUSION.

VERIZON WIRELESS CONSTRUCTION NOTES:

1. CONTRACTOR IS TO FOLLOW THE MOST CURRENT VZW STANDARDS DOCUMENTS PROVIDED TO COMPLETE THIS INSTALLATION.
2. CONTRACTOR SHALL COMPLETE VZW PROVIDED "SMALL CELL SWEEP REPORT" WITH ALL INFORMATION FILLED IN ACCURATELY AND COMPLETELY.
3. CONTRACTOR TO REFER TO THE MOST CURRENT VZW STANDARDS FOR APPROVED "PIM" TEST EQUIPMENT AND GUIDELINES.
4. CONTRACTOR IS TO USE BATTERY POWERED "PIM" EQUIPMENT TO VALIDATE THE FINAL LOCATION OF THE JUMPER AND ANTENNA ARE FREE OF INTERNAL AND EXTERNAL "PIM" SOURCES.
5. CONTRACTOR SHALL PROVIDE AT LEAST ONE TECHNICAL LEAD THAT IS CERTIFIED AND PROFICIENT IN EXECUTING, INTERPRETING AND RECORDING "PIM" MEASUREMENTS.

PREPARED FOR:

verizon

PREPARED BY:

TeleGAP
Wireless

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:

LA

CHECKED BY:

CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
0	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	LA	PRELIMINARY REVIEW

ENGINEER'S STAMP:



NOT VALID WITHOUT P.E. STAMP & SIGNATURE

SITE NAME:

40214

COUNTY:

WASHTENAW

LATITUDE:

42° 14' 45.24" N

LONGITUDE:

83° 36' 58.14" W

DESIGN TYPE:

COLOCATION

SHEET TITLE:

GENERAL NOTES

DRAWING NO.

GN1

REVISION:

0

NOTES:

1. THIS DRAWING IS BASED ON AERIAL IMAGERY AND FIELD OBSERVATIONS. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO COMMENCEMENT OF CONSTRUCTION.
2. THE PROPOSED USE DOES NOT REQUIRE FULL OR PART TIME EMPLOYEES AT THE SITE.
3. FOR GENERAL SITE WORK NOTES, SEE SHEET GN1.
4. ALL NORTH ARROWS ON SITE PLANS ARE TRUE NORTH, UNLESS OTHERWISE SPECIFIED.
5. OPEN CUT CONSTRUCTION THROUGH EXISTING PAVEMENT, I.E. ROADWAYS, PARKING AREAS, SIDEWALKS WILL NOT BE ALLOWED. CONSTRUCTION UNDER EXISTING PAVEMENTS WILL BE REQUIRED TO BE INSTALLED WITH DIRECTIONAL BORING TECHNIQUE.

LEGEND	
UNDERGROUND POWER	— UGP — UGP —
OVERHEAD POWER	— OP — OP —
OVERHEAD UTILITIES	— OU — OU —
UNDERGROUND TELCO	— UGT — UGT —
OVERHEAD TELCO	— OHT — OHT —
GAS LINE	— GAS — GAS —
FENCE	— F — F —
SEWER LINE	— SVR — SVR —
WATER LINE	— WTR — WTR —
COAX CABLE	— C — C —
HYBRID CABLE	— HIB — HIB —
HIGH VOLTAGE POWER	— HVP — HVP —
FIBER	— FBI — FBI —
RIGHT-OF-WAY	— ROW — ROW —
PROPERTY LINE	— PL — PL —
EDGE OF PAVEMENT	— EOP — EOP —
CATCH BASIN	■
IRON PIN SET (IPF) 3" REBAR	●
IRON PIN FOUND (IPF)	○
BENCHMARK	⊕
CONCRETE MON. FOUND	□
CONCRETE MON. SET	■
UTILITY POLE	⊙
LIGHT POLE	⊙
WATER VALVE	⊕
MANHOLE	⊕
GAS VALVE	⊕
FIRE HYDRANT	⊕
TELCO PEDESTAL	⊕
ELECTRICAL PULL BOX	⊕

PREPARED FOR:

verizon

PREPARED BY:

TeleCAD Wireless

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY: LA

CHECKED BY: CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
0	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	LA	PRELIMINARY REVIEW

ENGINEER'S STAMP:



NOT VALID WITHOUT P.E. STAMP & SIGNATURE

SITE NAME:

40214

COUNTY:

WASHTENAW

LATITUDE:

42° 14' 45.24" N

LONGITUDE:

83° 36' 58.14" W

DESIGN TYPE:

COLOCATION

SHEET TITLE:


SITE LAYOUTS

DRAWING NO.

C1

REVISION:

0




1 OVERALL SITE LAYOUT

2 ENLARGED SITE LAYOUT

AZIMUTHS ARE SUBJECT TO CHANGE. CONTRACTOR TO VERIFY AZIMUTHS FROM FINAL RFDS FROM VZW. ANTENNA MOUNT TO BE SUPPLIED BY ERICSSON OR VERIZON. ANTENNA TO BE INSTALLED BY VERIZON CONTRACTOR.

INSTALL STRAIN RELIEF FOR POWER & FIBER CABLES AT OR NEAR ANTENNAS



PROPOSED MOUNT SHOWN AS
PLACEHOLDER. ACTUAL MOUNT
SUBJECT TO CHANGE PER DTE AND
VERIZON FUTURE DISCUSSIONS

- U-GUARD NOTES
1. PROPOSED U-GUARD, CONTRACTOR TO RELOCATE AS REQUIRED TO ACCOMMODATE THE PROPOSED ERICSSON ANTENNA INSTALLATION.
 2. U-GUARD STOPS BELOW ANTENNAS AND DOES NOT INTERFERE WITH BANDING.
 3. U-GUARD MUST BE RACEWAY CAPABLE.

PREPARED FOR:

verizon

PREPARED BY:

TeleCAD Wireless

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:	LA
CHECKED BY:	CTD

REVISIONS			
NO.	DATE	BY	DESCRIPTION
0	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	LA	PRELIMINARY REVIEW

ENGINEER'S STAMP:

NOT VALID WITHOUT P.E. STAMP & SIGNATURE

SITE NAME:

40214

COUNTY:

WASHTENAW

LATITUDE:

42° 14' 45.24" N

LONGITUDE:

83° 36' 58.14" W

DESIGN TYPE:


COLOCATION

SHEET TITLE:

ANTENNA LAYOUT

DRAWING NO.	REVISION:
C2A	0

POLE ATTACHED EQUIPMENT	
EQUIPMENT	VOLUME (CU-FT)
STREET MACRO 6701 ANTENNA	0.46
STREET MACRO 6701 ANTENNA	0.46
STREET MACRO 6701 ANTENNA	0.46
TOTAL IN CU-FT	1.38



- NOTES:
1. WORKING CLEARANCE FROM ENERGIZED ANTENNA MUST BE GREATER THAN 4 FT, OTHERWISE SHUT DOWN RADIO AND ANTENNA PER INSTRUCTIONS ON PLACARD OR BY OPENING DISCONNECT SWITCH TO RADIO EQUIPMENT ON POLE.
 2. ANTENNA AND MOUNTING BRACKETS INSTALLED ABOVE DTE WIRES MUST BE INSTALLED AND MAINTAINED BY DTE OR DTE'S DESIGNATED CONTRACTOR.
 3. VERTICAL CLIMBING ZONE MUST BE MAINTAINED ON ALL POLES. (SEE TOP VIEW)
 4. BASE CABINET TO BE CLEARLY LABELED WITH OWNER'S NAME AND 1-800 PHONE NUMBER WITH 3/4" TALL LETTERING.
 5. SHUTDOWN PLACARD TO BE PLACED ON THE POLE NEAR BASE CABINET AND DISCONNECT SWITCH BOX.
 6. 5' FT MIN. CLEARANCE ABOVE ANY DTE EQUIPMENT.
 7. ANTENNA POLE TOP CLEARANCES APPLY TO ANY DTE EQUIPMENT OR WIRES INSTALLED UNDER THE ANTENNA.

REFERENCE DTE ENERGY
CELLULAR ANTENNA SMALL CELL SITE CONSTRUCTION
LINE CONSTRUCTION STANDARDS 4-JOINT USE 1-4-26.1
DATED 11/1/2017

PREPARED FOR:

verizon

PREPARED BY:

TeleGAP
Wireless

1961 NORTHPOINT BLVD, SUITE 130
HIKSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:

LA


CHECKED BY:

CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
B	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	LA	PRELIMINARY REVIEW

ENGINEER'S STAMP:



SITE NAME:

40214

COUNTY:

WASHTENAW

LATITUDE:

42° 14' 45.24" N

LONGITUDE:

83° 36' 58.14" W

DESIGN TYPE:

COLOCATION

SHEET TITLE:

DTE NOTES

DRAWING NO.

C3

REVISION:


0

1 EQUIPMENT CU-FT. TABLE

N.T.S.

2 DTE CLIMBING ZONE REQUIREMENT AND NOTES

N.T.S.



PREPARED FOR:



PREPARED BY:



1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:

LA


CHECKED BY:

CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
0	06/27/19	DAJ	CONSTRUCTION ISSUE
1	06/19/19	LA	PRELIMINARY REVIEW

ENGINEER'S STAMP:



SITE NAME:

40214

COUNTY:

WASHTENAW

LATITUDE:

42° 14' 45.24" N

LONGITUDE:

83° 36' 58.14" W

DESIGN TYPE:

COLOCATION

SHEET TITLE:

SITE DETAILS

DRAWING NO.

C4

REVISION:

0

1 | ERICSSON STREETMACRO 6701 ANTENNA MOUNTING DETAIL

N.T.S.

Spectrum: 28 GHz
IBW Full band
OBW 800 MHz
EIRP ~ 55 dBm

of Users: 2,000+
Total Antenna BW: 1600 MHz
Throughput: 5 Gbps DL/ 1 Gbps UL
RI ports: 2
TN/IDLports: 2
Misc: 4xExternal Alarms, USB connector
PoE, GPS, 1588 Synch

Weight: ~ 13 kg (29 lbs)
Size: 20,5"x4,9"x7,9" (13 l)
Operational conditions: -40 to +55 degrees
Cooling: Active
Power: AC, <300W Max
IP Class: IP 65


Ericsson Confidential - 1 2018 03 15



20,5"x5"x8" Not to Exceed Dimensions

CFIT BOX

PART CODE: CFIT-C48D4LHXVZ
DESIGNED BY CHARLES INDUSTRIES



PRODUCT SPECIFICATIONS

TECHNICAL SPECIFICATIONS	
HEIGHT (PANEL ONLY)	15 in.
DEPTH, BASE (FRONT TO BACK)	5.5 in.
WIDTH	12 in.
WEIGHT	4 lbs.
CONSTRUCTION	RUGGED UL94-5VA GRAY POLYCARBONATE
SUPPORTED FIBER CONNECTOR TYPES	SC, LC or MPO
COMPLIANCE	DESIGNED TO MEET GR-950, GR2898, NEMA 4, IP66
SPLICING CAPACITY	UP TO THREE (3) 4"x6" HINGED SPLICE TRAYS ON FEED FIBER SIDE.
BULKHEAD CAPACITY	24 SC ADAPTERS

PREPARED FOR:

verizon

PREPARED BY:


TeleCAD Wireless
1961 NORTHPOINT BLVD, SUITE 130
HIKSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:
THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY: LA
CHECKED BY: CTD

REVISIONS			
0	06/27/19	DAI	CONSTRUCTION ISSUE
A	06/19/19	LA	PRELIMINARY REVIEW
NO.	DATE	BY	DESCRIPTION

ENGINEER'S STAMP:



SITE NAME:
40214
COUNTY:
WASHTENAW
LATITUDE:
42° 14' 45.24" N
LONGITUDE:
83° 36' 58.14" W
DESIGN TYPE:
COLOCATION

SHEET TITLE:
EQUIPMENT DETAILS

DRAWING NO. C5
REVISION: 0

1 STREETMACRO 6701

N.T.S.

2 CFIT BOX

N.T.S.

ELECTRICAL NOTES:

- 1. PROVIDE AND INSTALL WARNING TAPE FOR ELECTRIC SERVICE CONDUIT 12" BELOW GRADE.
- 2. CONTRACTOR TO PAY FOR THE SERVICE AS DIRECTED BY THE MUNICIPALITY.
- 3. CONTRACTOR TO USE PVC SCH 40 CONDUIT WHERE CONDUITS CROSS ACCESS ROADS.
- 4. CONTRACTOR SHALL COORDINATE WITH ELECTRIC AND TELEPHONE UTILITY COMPANIES FOR SERVICES.
- 5. CONTRACTOR TO PAY ALL FEES FOR SERVICES REQUIRED.
- 6. CONTRACTOR TO BE ADVISED THAT EXISTING UNDERGROUND CONDUITS, GROUND CABLES EXIST. DIG WITH CAUTION.
- 7. CONTRACTOR TO VERIFY POWER AND TELCO LB LOCATIONS AND FLEX CONDUIT SIZE AND ROUTING TO THE EQUIPMENT SHELTER WITH MANUFACTURER'S DRAWINGS.
- 8. OPEN CUT CONSTRUCTION THROUGH EXISTING PAVEMENT, I.E. ROADWAYS, PARKING AREAS, SIDEWALKS WILL NOT BE ALLOWED. CONSTRUCTION UNDER EXISTING PAVEMENTS WILL BE REQUIRED TO BE INSTALLED WITH DIRECTIONAL BORING TECHNIQUE.

UTILITY NOTES:


- 1. ALL POWER CONDUITS ABOVE GRADE, SWEEPS, & ELBOWS TO BE PVC SCH 40.
- 2. INSTALL PULL STRING IN TELCO CONDUIT.

STANDARD POWER SUPPLY FOR THE SMALL CELL NODES IS A 100 AMP 120/240 VOLT SINGLE PHASE SERVICE

SERVICE CONDUCTOR MAXIMUM DISTANCE CHART (BASED ON 80 AMP MAX. CONTINUOUS LOAD)			
WIRE SIZE	ALUMINUM	COPPER	CONDUIT SIZE
3 AWG	55'	90'	3/4" MIN
2 AWG	70'	115'	3/4" MIN
1 AWG	85'	145'	3/4" MIN
1/0 AWG	110'	180'	1" MIN
2/0 AWG	140'	230'	1" MIN
3/0 AWG	175'	290'	1 1/4" MIN
4/0 AWG	220'	365'	1 1/4" MIN
250 KCMIL	265'	435'	1 1/4" MIN
300 KCMIL	315'	520'	1 1/2" MIN
350 KCMIL	370'	610'	1 1/2" MIN
400 KCMIL	420'	695'	2" MIN
500 KCMIL	530'	870'	2" MIN

LEGEND

UNDERGROUND POWER	—UP—	CATCH BASIN	⌘
OVERHEAD POWER	—OP—	IRON PIN SET (IPF) 3/8" REBAR	●
OVERHEAD UTILITIES	—OU—	IRON PIN FOUND (IPF)	○
UNDERGROUND TELCO	—UT—	BENCHMARK	⊕
OVERHEAD TELCO	—OT—	CONCRETE MON. FOUND	□
GAS LINE	—GL—	CONCRETE MON. SET	■
FENCE	—F—	UTILITY POLE	⊙
SEWER LINE	—SL—	LIGHT POLE	⊗
WATER LINE	—WL—	WATER VALVE	⊕
COAX CABLE	—C—	MANHOLE	⊙
HYBRID CABLE	—HB—	GAS VALVE	⊕
HIGH VOLTAGE POWER	—HP—	FIRE HYDRANT	⊕
FIBER	—FB—	TELCO PEDESTAL	⊕
RIGHT-OF-WAY	—RW—	ELECTRICAL PULL BOX	⊕
PROPERTY LINE	—PL—		
EDGE OF PAVEMENT	—EP—		



PREPARED FOR:

verizon

PREPARED BY:

TeleCAD Wireless

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:

LA


CHECKED BY:

CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
0	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	LA	PRELIMINARY REVIEW

ENGINEER'S STAMP:



SITE NAME:

40214

COUNTY:

WASHTENAW

LATITUDE:

42° 14' 45.24" N

LONGITUDE:

83° 36' 58.14" W

DESIGN TYPE:

COLOCATION

SHEET TITLE:

UTILITY SITE PLAN


DRAWING NO.

E1

REVISION:


0

1 UTILITY SITE PLAN




1 SINGLE POINT RADIAL GROUND DETAIL

N.T.S.



2 TRENCH DETAIL (IF REQUIRED)

N.T.S.



3 GROUND ROD DETAIL

N.T.S.

4 DETAIL NOT IN USE

N.T.S.

PREPARED FOR:

verizon

PREPARED BY:

TeleCAD Wireless

1961 NORTHPOINT BLVD, SUITE 130
HIXSON, TN 37343
PH: 423-843-9500
FAX: 423-843-9509

DRAWING NOTICE:

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

DRAWN BY:

LA


CHECKED BY:

CTD

REVISIONS

NO.	DATE	BY	DESCRIPTION
0	06/27/19	DAJ	CONSTRUCTION ISSUE
A	06/19/19	LA	PRELIMINARY REVIEW

ENGINEER'S STAMP:



SITE NAME:

40214

COUNTY:

WASHTENAW

LATITUDE:

42° 14' 45.24" N

LONGITUDE:

83° 36' 58.14" W

DESIGN TYPE:

COLOCATION

SHEET TITLE:


ELECTRICAL DETAILS

DRAWING NO.

E2

REVISION:

0





REQUEST FOR LEGISLATION

TO: Mayor and City Council
FROM: Ron Akers
DATE: January 5, 2021
Recycling and Organics Infrastructure Grant Agreement Between the
Michigan Department of Environment, Great Lakes, and Energy and
SUBJECT: City of Ypsilanti

DESCRIPTION:

Recycling and Organics Infrastructure Grant Agreement Between the Michigan Department of Environment, Great Lakes, and Energy and City of Ypsilanti

SUMMARY:

In April 2020, the City applied for a Recycling and Organics Infrastructure Grant to help cover a portion of the expenditures for the purchase of public recycling containers. This grant would cover 80% of the cost of purchasing 108 containers which will be placed in downtown areas and City parks. We were notified in October 2020 that our proposal for the grant was approved and to accept the grant would be required to enter into an agreement to formalize the grant award. This agreement has been submitted to the City Attorney for their review and has been attached to this RFL for Council's consideration.

The main goals of this project are to provide access to public recycling in the city's downtown areas and parks, and to divert an estimated eleven (11) tons of recyclables from our public trash containers. City staff will collect these recyclables and take them to the material recovery facility where the total amount of recyclables will be measured. We will use these measurements for our own evaluations as well as our required reporting to the state.

We are anticipating the cost of this project to be between \$90,000 and \$100,000. The grant will cover 20% of the project costs up to \$73,440. There is currently \$60,000 in the environmental budget to cover the City's portion of the cost. Our plan is to work with the DDA to select acceptable containers which meet best practices to help avoid contamination and encourage individuals in the downtown areas and parks to use them properly. We are anticipating the roll out of these containers in late spring/early summer.

RECOMMENDED ACTION:

Staff is recommending approval of the Recycling and Organics Infrastructure Grant Agreement between the Michigan Department of Environment, Great Lakes, and Energy and City of Ypsilanti, subject to approval by the City Attorney.

ATTACHMENTS: Agreement, press release.

CITY MANAGER APPROVAL: _____ COUNCIL AGENDA DATE: _____

CITY MANAGER COMMENTS: _____

FISCAL SERVICES DIRECTOR APPROVAL: _____



Resolution No. 2021-006
January 5, 2021

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

WHEREAS, the City of Ypsilanti was awarded a Recycling and Organics Infrastructure Grant from the Michigan Department of Environment, Great Lakes, and Energy (EGLE) for the purchase of public recycling containers; and,

WHEREAS, the City of Ypsilanti is interesting in expanding public recycling access in the City's downtown areas and parks; and,

WHEREAS, it is necessary to enter into an agreement with EGLE to accept the grant;

NOW THEREFORE BE IT RESOLVED THAT that the City Council of the City of Ypsilanti approves the Recycling and Organics Infrastructure Grant Agreement between the Michigan Department of Environment, Great Lakes, and Energy and City of Ypsilanti for the purchase of public recycling containers, subject to approval by the City Attorney.


OFFERED BY: _____

SECONDED BY: _____

YES: NO: ABSENT: VOTE:

This resolution is adopted by the Council of the City of Ypsilanti and approved by the Mayor this
5 day of January 2021

#Resolution No. 2021-006



Page 319 of 353

I. PROJECT SCOPE

This Agreement and its appendices constitute the entire Agreement between the State and the Grantee and may be modified only by written agreement between the State and the Grantee.

(A) The scope of this project is limited to the activities specified in Appendix A and such activities as are authorized by the State under this Agreement. Any change in project scope requires prior written approval in accordance with Section III, Changes, in this Agreement.

(B) By acceptance of this Agreement, the Grantee commits to complete the project identified in Appendix A within the time period allowed for in this Agreement and in accordance with the terms and conditions of this Agreement.

II. AGREEMENT PERIOD

Upon signature by the State, the Agreement shall be effective from the Start Date until the End Date on page 1. The State shall have no responsibility to provide funding to the Grantee for project work performed except between the Start Date and the End Date specified on page 1. Expenditures made by the Grantee prior to the Start Date or after the End Date of this Agreement are not eligible for payment under this Agreement.

III. CHANGES

Any changes to this Agreement shall be requested by the Grantee or the State in writing and implemented only upon approval in writing by the State. The State reserves the right to deny requests for changes to the Agreement or to the appendices. No changes can be implemented without approval by the State.

IV. GRANTEE DELIVERABLES AND REPORTING REQUIREMENTS

The Grantee shall submit deliverables and follow reporting requirements specified in Appendix A of this Agreement.

(A) The Grantee must complete and submit quarterly financial and progress reports according to a form and format prescribed by the State and must include supporting documentation of eligible project expenses. These reports shall be due according to the following.

Reporting Period	Due Date
January 1 – March 31	April 30
April 1 – June 30	July 31
July 1 – September 30	Before October 15*
October 1 – December 31	January 31

*Due to the State's year-end closing procedures, there will be an accelerated due date for the report covering July 1 – September 30. Advance notification regarding the due date for the quarter ending September 30 will be sent to the Grantee. If the Grantee is unable to submit a report in early October for the quarter ending September 30, an estimate of expenditures through September 30 must be submitted to allow the State to complete its accounting for that fiscal year.

The forms provided by the State shall be submitted to the State's contact at the address on page 1. All required supporting documentation (invoices, proof of payment, etc.) for expenses must be included with the report.

(B) The Grantee shall provide a final project report in a format prescribed by the State.

The Grantee shall submit the final status report, including all supporting documentation for expenses, along with the final project report and any other outstanding products within 30 days from the End Date of the Agreement.

(C) The Grantee must provide 2 copies of all products and deliverables in accordance with Appendix A.

(D) All products shall acknowledge that the project was supported in whole or in part by Recycling Grant Program, EGLE, per the guidelines provided by the program.

V. GRANTEE RESPONSIBILITIES

(A) The Grantee agrees to abide by all applicable local, state, and federal laws, rules, ordinances, and regulations in the performance of this grant.

(B) All local, state, and federal permits, if required, are the responsibility of the Grantee. Award of this grant is not a guarantee of permit approval by the State.

(C) The Grantee shall be solely responsible to pay all applicable taxes and fees, if any, that arise from the Grantee's receipt or execution of this grant.

(D) The Grantee is responsible for the professional quality, technical accuracy, timely completion, and coordination of all designs, drawings, specifications, reports, and other services submitted to the State under this Agreement. The Grantee shall, without additional compensation, correct or revise any errors, omissions, or other deficiencies in drawings, designs, specifications, reports, or other services.

(E) The State's approval of drawings, designs, specifications, reports, and incidental work or materials furnished hereunder shall not in any way relieve the Grantee of responsibility for the technical adequacy of the work. The State's review, approval, acceptance, or payment for any of the services shall not be construed as a waiver of any rights under this Agreement or of any cause of action arising out of the performance of this Agreement.

(F) The Grantee acknowledges that it is a crime to knowingly and willingly file false information with the State for the purpose of obtaining this Agreement or any payment under the Agreement, and that any such filing may subject the Grantee, its agents, and/or employees to criminal and civil prosecution and/or termination of the grant.

VI. USE OF MATERIAL

Unless otherwise specified in this Agreement, the Grantee may release information or material developed under this Agreement, provided it is acknowledged that the State funded all or a portion of its development.

The State, and federal awarding agency, if applicable, retains a royalty-free, nonexclusive and irrevocable right to reproduce, publish, and use in whole or in part, and authorize others to do so, any copyrightable material or research data submitted under this grant whether or not the material is copyrighted by the Grantee or another person. The Grantee will only submit materials that the State can use in accordance with this paragraph.

VII. ASSIGNABILITY

The Grantee shall not assign this Agreement or assign or delegate any of its duties or obligations under this Agreement to any other party without the prior written consent of the State.

The State does not assume responsibility regarding the contractual relationships between the Grantee and any subcontractor.

VIII. SUBCONTRACTS

The State reserves the right to deny the use of any consultant, contractor, associate, or other personnel to perform any portion of the project. The Grantee is solely responsible for all contractual activities performed under this Agreement. Further, the State will consider the Grantee to be the sole point of contact with regard to contractual matters, including payment of any and all charges resulting from the anticipated Grant. All subcontractors used by the Grantee in performing the project shall be subject to the provisions of this Agreement and shall be qualified to perform the duties required.

IX. NON-DISCRIMINATION

The Grantee shall comply with the Elliott Larsen Civil Rights Act, 1976 PA 453, as amended, MCL 37.2101 *et seq.*, the Persons with Disabilities Civil Rights Act, 1976 PA 220, as amended, MCL 37.1101 *et seq.*, and all other federal, state, and local fair employment practices and equal opportunity laws and covenants that it shall not discriminate against any employee or applicant for employment, to be employed in the performance of this Agreement, with respect to his or her hire, tenure, terms, conditions, or privileges of employment, or any matter directly or indirectly related to employment, because of his or her race, religion, color, national origin, age, sex, height, weight, marital status, or physical or mental disability that is unrelated to the individual's ability to perform the duties of a particular job or position. The Grantee agrees to include in every subcontract entered into for the performance of this Agreement this covenant not to discriminate in employment. A breach of this covenant is a material breach of this Agreement.

X. UNFAIR LABOR PRACTICES

The Grantee shall comply with the Employers Engaging in Unfair Labor Practices Act, 1980 PA 278, as amended, MCL 423.321 *et seq.*

XI. LIABILITY

(A) The Grantee, not the State, is responsible for all liabilities as a result of claims, judgments, or costs arising out of activities to be carried out by the Grantee under this Agreement, if the liability is caused by the Grantee, or any employee or agent of the Grantee acting within the scope of their employment or agency.

(B) Nothing in this Agreement should be construed as a waiver of any governmental immunity by the Grantee, the State, its agencies, or their employees as provided by statute or court decisions.

XII. CONFLICT OF INTEREST

No government employee, or member of the legislative, judicial, or executive branches, or member of the Grantee's Board of Directors, its employees, partner agencies, or their families shall benefit financially from any part of this Agreement.

XIII. ANTI-LOBBYING

If all or a portion of this Agreement is funded with federal funds, then in accordance with OMB Circular A-21, A-87, or A-122, as appropriate, the Grantee shall comply with the Anti-Lobbying Act, which prohibits the use of all project funds regardless of source, to engage in lobbying the state or federal government or in litigation against the State.

Further, the Grantee shall require that the language of this assurance be included in the award documents of all subawards at all tiers.

If all or a portion of this Agreement is funded with state funds, then the Grantee shall not use any of the grant funds awarded in this Agreement for the purpose of lobbying as defined in the State of Michigan's lobbying statute, MCL 4.415(2). "Lobbying" means communicating directly with an official of the executive branch of state government or an official in the legislative branch of state government for the purpose of influencing legislative or administrative action." The Grantee shall not use any of the grant funds awarded in this Agreement for the purpose of litigation against the State. Further, the Grantee shall require that language of this assurance be included in the award documents of all subawards at all tiers.

XIV. DEBARMENT AND SUSPENSION

By signing this Agreement, the Grantee certifies that it has checked the federal debarment/suspension list at www.SAM.gov to verify that its agents, and its subcontractors:

- (1) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any federal department or the state.
- (2) Have not within a three-year period preceding this Agreement been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (federal, state, or local) transaction or contract under a public transaction, as defined in 45 CFR 1185; violation of federal or state antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property.
- (3) Are not presently indicted or otherwise criminally or civilly charged by a government entity (federal, state, or local) with commission of any of the offenses enumerated in subsection (2).
- (4) Have not within a three-year period preceding this Agreement had one or more public transactions (federal, state, or local) terminated for cause or default.
- (5) Will comply with all applicable requirements of all other state or federal laws, executive orders, regulations, and policies governing this program.

XV. AUDIT AND ACCESS TO RECORDS

The State reserves the right to conduct a programmatic and financial audit of the project, and the State may withhold payment until the audit is satisfactorily completed. The Grantee will be required to maintain all pertinent records and evidence pertaining to this Agreement, including grant and any required matching funds, in accordance with generally accepted accounting principles and other procedures specified by the State. The State or any of its duly authorized representatives must have access, upon reasonable notice, to such books, records, documents, and other evidence for the purpose of inspection, audit, and copying. The Grantee will provide proper facilities for such access and inspection. All records must be maintained for a minimum of [five] years after the final payment has been issued to the Grantee by the State.

XVI. INSURANCE

(A) The Grantee must maintain insurance or self-insurance that will protect it from claims that may arise from the Grantee's actions under this Agreement.

(B) The Grantee must comply with applicable workers' compensation laws while engaging in activities authorized under this Agreement.

XVII. OTHER SOURCES OF FUNDING

The Grantee guarantees that any claims for reimbursement made to the State under this Agreement must not be financed by any source other than the State under the terms of this Agreement. If funding is received through any other source, the Grantee agrees to delete from Grantee's billings, or to immediately refund to the State, the total amount representing such duplication of funding.

XVIII. COMPENSATION

(A) A breakdown of costs allowed under this Agreement is identified in Appendix A. The State will pay the Grantee a total amount not to exceed the amount on page 1 of this Agreement, in accordance with Appendix A, and only for expenses incurred and paid. All other costs necessary to complete the project are the sole responsibility of the Grantee.

(B) Expenses incurred by the Grantee prior to the Start Date or after the End Date of this Agreement are not allowed under the Agreement,

(C) The State will approve payment requests after approval of reports and related documentation as required under this Agreement.

(D) The State reserves the right to request additional information necessary to substantiate payment requests.

(E) Payments under this Agreement may be processed by Electronic Funds Transfer (EFT). The Grantee may register to receive payments by EFT at the SIGMA Vendor Self Service web site (<https://sigma.michigan.gov/webapp/PRDVSS2X1/AltSelfService>).

(F) An amount equal to 5 percent of the grant award will be withheld by the State until the project is completed in accordance with Section XIX, Closeout, and Appendix A.

(G) The Grantee is committed to the match percentage on page 1 of the Agreement, in accordance with Appendix A. The Grantee shall expend all local match committed to the project by the End Date on page 1 of the Agreement.

XIX. CLOSEOUT

(A) A determination of project completion, which may include a site inspection and an audit, shall be made by the State after the Grantee has met any match obligations, satisfactorily completed the activities, and provided products and deliverables described in Appendix A.

(B) Upon issuance of final payment from the State, the Grantee releases the State of all claims against the State arising under this Agreement. Unless otherwise provided in this Agreement or by State law, final payment under this Agreement shall not constitute a waiver of the State's claims against the Grantee.

(C) The Grantee shall immediately refund to the State any payments in excess of the costs allowed by this Agreement.

XX. CANCELLATION

This Agreement may be canceled by the State, upon 30 days written notice, due to Executive Order, budgetary reduction, other lack of funding, upon request by the Grantee, or upon mutual agreement by the State and Grantee.

The State may honor requests for just and equitable compensation to the Grantee for all satisfactory and eligible work completed under this Agreement up until 30 days after written notice, upon which time all outstanding reports and documents are due to the State and the State will no longer be liable to pay the grantee for any further charges to the grant.

XXI. TERMINATION

(A) This Agreement may be terminated by the State as follows.

(1) Upon 30 days written notice to the Grantee:

- a. If the Grantee fails to comply with the terms and conditions of the Agreement, or with the requirements of the authorizing legislation cited on page 1, or the rules promulgated thereunder, or other applicable law or rules.
- b. If the Grantee knowingly and willingly presents false information to the State for the purpose of obtaining this Agreement or any payment under this Agreement.
- c. If the State finds that the Grantee, or any of the Grantee's agents or representatives, offered or gave gratuities, favors, or gifts of monetary value to any official, employee, or agent of the State in an attempt to secure a subcontract or favorable treatment in awarding, amending, or making any determinations related to the performance of this Agreement.
- d. If the Grantee or any subcontractor, manufacturer, or supplier of the Grantee appears in the register of persons engaging in unfair labor practices that is compiled by the Michigan Department of Licensing and Regulatory Affairs or its successor.
- e. During the 30-day written notice period, the State shall withhold payment for any findings under subparagraphs a through d, above and the Grantee will immediately cease charging to the grant and stop earning match for the project (if applicable).

(2) Immediately and without further liability to the State if the Grantee, or any agent of the Grantee, or any agent of any subcontract is:

- a. Convicted of a criminal offense incident to the application for or performance of a State, public, or private contract or subcontract;
- b. Convicted of a criminal offense, including but not limited to any of the following: embezzlement, theft, forgery, bribery, falsification or destruction of records, receiving stolen property, or attempting to influence a public employee to breach the ethical conduct standards for State of Michigan employees;
- c. Convicted under State or federal antitrust statutes; or
- d. Convicted of any other criminal offense that, in the sole discretion of the State, reflects on the Grantee's business integrity.
- e. Added to the federal or state Suspension and Debarment list.

(B) If a grant is terminated, the State reserves the right to require the Grantee to repay all or a portion of funds received under this Agreement.

XXII. IRAN SANCTIONS ACT

By signing this Agreement, the Grantee is certifying that it is not an Iran linked business, and that its contractors are not Iran linked businesses, as defined in MCL 129.312.

PROJECT-SPECIFIC REQUIREMENTS – APPENDIX A

I. GRANT APPLICATION; PROJECT SCOPE

The scope of this project is outlined in the Grantee's approved Fiscal Year 2020 Recycling Infrastructure Grant Program Proposal, which is included in this grant agreement in Appendix C, as well as any subsequent modifications to the original grant proposal as approved by the State.

II. GRANT REIMBURSEMENT PROCESS

Breakdown of project funds covered under this Agreement:

Grant Amount = \$73,440.00
Matching Funds = \$18,360.00
Total Grant Budget = \$91,800.00

The total payment made to the Grantee by the State shall not exceed \$73,440.00. Any additional costs associated with the project shall be the responsibility of the Grantee. An updated budget form reflecting the EGLE grant award offer is attached in Appendix B.

The Grantee is responsible for the payment of all eligible costs necessary to complete the project. The Grantee shall submit reimbursement requests to the State which specify the time period covered by the reimbursement request and the payments made by the Grantee during the time period. Grant reimbursements will be for up to 80 percent of the documented purchase expenditures, not to exceed the awarded grant amount, less a 5 percent retention amount that will be released upon approval of the final report. The final report is due one year after the infrastructure item(s) have been purchased and/or constructed, but no later than September 29, 2023.

A request for payment shall be submitted by the Grantee on a form provided by the State and shall include copies of invoices, proof of payment to the vendor (such as canceled checks, ACH, wire transfer confirmations, bank statements, etc.) and proof of receipt of goods. Grantees will be reimbursed up to 80 percent of documented purchase expenditures, not to exceed the awarded grant amount. The remaining unreimbursed expenditures serve as the required match amount for the grant. Reimbursement forms will be available on the EGLE's Recycling Program website located at: <http://www.michigan.gov/mirecycles>.

The Grantee is responsible for ensuring that all partner entities fulfill their commitments under the grant proposal.

The Grantee is responsible for ensuring that all products requiring reimbursement acknowledge that the project was supported in whole or in part by the EGLE Recycling Grant Program.

III. REPORTING REQUIREMENTS

The Grantee shall comply with all reporting requirements of the State during the Agreement Period.

QUARTERLY REPORTS

The Grantee shall submit the final quarterly status and financial report, including all supporting documentation for expenses, by September 29, 2022. Supporting documentation must include proof of payment and proof of receipt of goods.

Quarterly progress and financial reports must be submitted at least every three months during the Agreement Period, even if no funds were expended. Provide the following narrative using the numbers and headings listed below:

I. SUMMARY OF ACTIONS TAKEN DURING THE CURRENT PERIOD

- A. Describe the tasks completed and how project funds were expended during the time period covered by the report. If no funds were expended during the current period, include a statement to that effect and explain why. A description of tasks completed during the current period must still be included.
- B. If any products were developed during the time period covered by the report, include a copy of the products with the report.

II. SUMMARY OF ACCOMPLISHMENTS DURING THIS PERIOD

- A. Goals and objectives as set forth in the grant application and grant contract. List the project's stated goals and objectives and describe how the project is meeting them.
- B. Additional project accomplishments not included in original project goals and objectives.
- C. Project data: Provide any data collected during the current period, as described in the grant application incorporated with this contract. Attach available documentation which supports the data. If the data provided covers a previous reporting period, specify the dates which the data is from.

III. SUMMARY OF REMAINING ACTIONS TO BE TAKEN

- A. Describe the remaining tasks to be completed and indicate whether or not these tasks will be completed within the approved project schedule. For tasks which will not be completed within the approved project schedule, discuss the reasons for the delay and provide the revised task completion date.

IV. PROBLEMS ENCOUNTERED DURING THIS PERIOD

- A. Identify any problems encountered during the current reporting period and explain how they were resolved. Describe the impact these problems have had or will have on project design, completion, and operations. If at any time the Grantee becomes aware that any materials collected or processed in association with grant purchases are being disposed, the Grantee must immediately notify EGLE and must document the issue in the next quarterly report. The Grantee must also submit for EGLE review the steps that will be taken to address the issue and the expected timeframe for resolution.

IV. ADDITIONAL COMMENTS

- A. Provide any additional comments relevant to the status of the project and its operations.

V. FINANCIAL DOCUMENTATION

- A. Provide required documentation, including copies of invoices, proof of payment and proof of receipt of goods, for funds expended during the reporting period.

FINAL PROJECT REPORT

The purpose of the final project report is to provide the State with data on your project and a narrative discussion about your project, including an evaluation of the project to date. The final report is due one year after the infrastructure item(s) have been purchased and/or constructed, but no later than September 30, 2023. Retained funds will be forfeited by the Grantee if the final report is not accepted.

Identify the time period covered by the final project report. Provide the following narrative information using the numbers and headings listed below:

I. PROJECT DESCRIPTION

- A. Provide a description of the project funded.
- i. Provide a 4-5 sentence summary of the project, including the following information, as applicable: description of item purchased and/or constructed, geographical area served, population and/or number of households/units served, volume of containers, collection frequency, collection method, list of recyclable or organic materials collected, name and location of recycling processor, increase in processing capacity, and description of how project will be sustained beyond the grant timeline.
 - ii. Include any news articles and/or photographs as appropriate.
 - iii. Include the date project operations began and a discussion of the current status of project operations.
- B. List and explain the steps involved in completing the project, from planning through implementation to ongoing operations. Include the dates of major project activities and events.
- C. List and discuss other entities (e.g., companies, nonprofit groups, local units of government) that played a role in planning and implementing the project and briefly describe their role. Describe any formal agreements that were entered into as a part of project implementation.

II. PROJECT DATA

- A. Diversion rate, participation rate, and geographical area.
- i. For the time period covered by this report, provide the quantity of recyclable or organic materials diverted, in tons or cubic yards /time period. Specify which recyclable or organic materials are included in this reported volume. Describe the methods for measuring these quantities.
 - ii. Provide diversion rates prior to the grant project, if known.

- iii. For the time period covered by this report, provide information on the number of people and/or number of households/units served by the project. Describe the methods for measuring these numbers.
 - iv. Provide information on the number of people and/or number of households/units served prior to the grant project, if known.
 - v. For the time period covered by this report, provide information on the geographical area served by the project.
 - vi. Provide previous information on the geographical area served by the program prior to the current grant project.
- B. Education and Outreach Program. Provide the following information for all project related promotional activities which have occurred as a result of the project:
- i. Types of groups (audience) targeted.
 - ii. Types of promotional materials developed.
 - iii. Methods used to distribute information or materials.
 - iv. Planned/future educational efforts.

III. PROJECT COSTS: Provide the following information regarding additional costs required to implement the project:

- A. Provide the dollar amounts and a description of all additional program related capital costs which have been incurred during the time period covered by this report. Identify the specific dates these costs were incurred.
- B. For the time period covered by this report, provide the dollar amounts and a description of all additional costs (beyond match) required to complete the project. Identify the specific dates these costs were incurred.
- C. For the time period covered by this report, provide the dollar amount and a description of the costs needed to operate the project.
- D. Describe the funding mechanisms utilized to operate and maintain the project activities.

IV. PROJECT EVALUATION

- A. Goals and Objectives. Summarize each of the project's goals and objectives as stated in your original proposal. Discuss (in both narrative and numerical terms) how well you are meeting each goal and objective. For each goal or objective that is not being met, discuss why.
 - i. If the project goals and objectives have changed from those that were originally established, discuss how and why. Also, discuss how these changes have impacted the final project.
 - ii. Recovery/Access/Participation Goals: As a part of the above discussion of project goals and objectives, identify the increase in either volume collected (in tons or cubic yards per year) by material type, or geographical access/population served that the

project is currently achieving. If the project is not meeting its goals, provide a discussion on why these goals are not being met. Also, indicate what steps you are taking in order to meet the stated goals in the future, and provide a timeframe for meeting these goals.

- B. Discuss any project accomplishments not included in the project's original goals and objectives.
- C. Discuss the economic impact the project has had on the local economy. Include information on new jobs created and sustained and any other relevant economic information.
- D. List and describe all significant problems encountered during project implementation, including any cost overruns, institutional barriers, local issues, etc. Describe how the problems were addressed and resolved. Describe any impact these problems had in project design, implementation and/or ongoing operations.
- E. Describe the most successful components of the project and explain why you think they are successful.
- F. Describe the least successful components of the project and explain why you think they are not successful.
- G. Lessons Learned. Discuss any conclusions you have made about the technical and economic feasibility of carrying out a similar project. Identify what you would do differently if you were to carry out a similar project, and why.

V. ADDITIONAL COMMENTS

- A. Provide any additional information relevant to the status of the project and its operations.

The quarterly and final project report must be signed by the authorized contact person for the project. Indicate any name, address or telephone number changes for the contact person and/or the project.

Submit the quarterly and final project reports to the attention of the State's contact at the following email address:

EGLE-RecyclingGrant@michigan.gov

Appendix B

2020 EGLE Recycling and Organics Infrastructure Grant Budget

City of Ypsilanti



MICHIGAN DEPARTMENT OF ENVIRONMENT, GREAT LAKES, AND ENERGY
MATERIALS MANAGEMENT DIVISION
RECYCLING INFRASTRUCTURE GRANT PROGRAM
BUDGET FORM

Grantee Name:		City of Ypsilanti				
Project Name:		Public Space Recycling Containers				
Project Number (assigned by EGLE):					Holdback Percentage:	5%

CONTRACTUAL SERVICES	HOURS or UNITS	RATE or TOTAL	% of FUNDING	GRANT AMOUNT	MATCH AMOUNT	TOTAL
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
Contractual Services Subtotal:				\$ -	\$ -	\$ -

SUPPLIES & MATERIALS (itemize)	QUANTITY	COST	% of FUNDING	GRANT AMOUNT	MATCH AMOUNT	TOTAL
Public space recycling containers	108	\$ 850.00	80.000%	\$ 73,440.00	\$ 18,360.00	\$ 91,800.00
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
Supplies & Materials Subtotal:				\$ 73,440.00	\$ 18,360.00	\$ 91,800.00

VEHICLE(S) & EQUIPMENT	QUANTITY	COST	% of FUNDING	GRANT AMOUNT	MATCH AMOUNT	TOTAL
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
		\$ -		\$ -	\$ -	\$ -
Vehicle(s) & Equipment Subtotal				\$ -	\$ -	\$ -

TOTAL PROJECT				
Total All Costs		\$ 73,440.00	\$ 18,360.00	\$ 91,800.00

IN-KIND / LEVERAGED FUNDS (Match that is not included in any category above):	DOLLAR VALUE PROJECTED:		
	In Kind	Cash	Total
	\$ -		\$ -
	\$ -		\$ -
	\$ -		\$ -
	\$ -		\$ -
	\$ -		\$ -
	\$ -		\$ -
	\$ -		\$ -
	\$ -		\$ -
	\$ -		\$ -
	\$ -		\$ -
Total Other Match:	\$ -	\$ -	\$ -

Appendix C

Application for 2020 EGLE Recycling and Organics Infrastructure Grant

City of Ypsilanti

**Department of Environment, Great Lakes, and Energy Recycling and
Organics Infrastructure Grant Application Cover Sheet**

Applicant Name: City of Ypsilanti	
Street Address: One S. Huron Street	
City/State/Zip/County: Ypsilanti, MI 48197	
Mailing Address (if different from street address):	
City/State/Zip:	
Contact Person and Title: Ron Akers – Director of Public Services	
Contact Person's E-Mail Address: rakers@cityofypsilanti.com	
Contact Person's Telephone Number: 734-483-1421	
Grant Amount Requested:	\$ 91,800
Local Match Amount (must be equal to or greater than 20 percent of the total grant budget):	\$18,360
Total Grant Budget:	\$73,440
DUNS Number: 13-133-6260	State Senator: Jeff Irwin
Federal Identification Number: 38-6004750	State Representative: Representative Ronnie Peterson
Applicant Signature (application must be signed by the person accepting responsibility for the terms and conditions of the grant agreement if awarded):	
Print Name: <u>Ronald A. Akers</u>	
	
Signature: _____	
Date: <u>October 27, 2020</u>	



City of Ypsilanti
Department of Public Services

City of Ypsilanti Public Recycling Container Proposal for the 2020 Recycling and Organics Infrastructure Grant Program:

Project Description

Summary of Proposal

The City of Ypsilanti is submitting a proposal to add approximately one hundred and eight (108) public recycling containers in the city's downtown areas and public parks. The additional recycling is proposed to be collected by city staff and taken to a material recovery facility where it will be sorted and processed.

Description of Current Program

Clear and realistic project goals and objectives, including a description of how the proposed project's goals will increase the recycling rate in the project area:

There are two (2) main goals with this proposed project. The first goal is to provide access to public recycling in the city's downtown areas and parks. These areas in the city have become very popular destinations with a growing number of festivals and businesses. Due to this we are seeing an increase foot traffic in these areas and providing public recycling containers would provide an option for those people who frequent these areas to recycle. The objective of this goal is to strategically place the containers in our downtown areas and public parks so we can provide recycling access in higher pedestrian traffic areas of the city. We already have trash receptacles in these areas, so our plan is to ensure that these containers are adjacent to our existing trash containers to avoid contamination.

The second goal of the program is to divert eleven (11) tons of recyclables from our public trash containers on an annual basis. Based on our estimated trash volumes from public receptacles, we are estimating that using the public recycling containers the city can divert eleven (11) tons of recyclables. This will increase the recycling rate by diverting recyclables that are getting thrown away.

Description of current materials management program:

The City of Ypsilanti provides a curbside single stream recycling program for all single-family housing units within the city and all multi-family buildings with four (4) units or fewer. The city does not contract for this service and has city staff collect recyclables. We provide twenty-five (25) gallon bins to our residents for curbside recycling service and we collect the bins weekly. We accept in our curbside recycling program plastic (#1, #2, #4, #5, #6, and #7), tin, aluminum, mixed paper, corrugated cardboard, boxboard, newspaper, and magazines. The City collects approximately six hundred (600) tons of recyclables on an annual basis and this number is calculated based on material measurements at the

material recovery facility we take our recyclables to. In addition to our curbside recycling program the City has a partnership with Recycle Ann Arbor to provide City residents with passes to their drop off site at no charge. We also offer a monthly drop off event within the City limits to promote a closer recycling option than the Recycle Ann Arbor drop off site.

Geographical area served, including population and/or number of households/units served:

The City of Ypsilanti serves all single-family housing units within the city and all multi-family buildings with four (4) units or fewer. According to the 2018 American Community Survey there are 4,956 housing units in the City which meets these criteria. We can estimate the population served using 2018 American Community Survey data. Please consider the following:

Overall Vacancy rate: 11.6%

Served Housing Units: 4,956

Estimated Occupied Served Housing Units: 4,381

Average Household Size: 2.29

Estimated Population Served: 10,032

Name and location of recycling processor, broker and/or end market, if known:

The City of Ypsilanti takes collected recyclables to the Western Washtenaw Recycling Authority Material Recovery Facility. Their address is: 8025 Werkner Road, Chelsea, MI 48118.

Description of current education and outreach program:

The City currently maintains its recycling guidelines on the city website and shares information about recycling on the city's social media platform a few times per year. In addition to this the City is a member of the Washtenaw Regional Resource Management Authority (WRRMA) which is currently in the process of developing additional outreach material.

Description of existing community support and/or partners in the program:

The curbside recycling program is managed and operated by the City of Ypsilanti Department of Public Services. The City is a member of WRRMA in which we partner with Washtenaw County to coordinate recycling efforts within the county. The City also partners with Recycle Ann Arbor in order to provide access to a drop off site and to provide dumpsters for the city's drop off events.

Description of existing operational funding sources such as use fees, millage, special assessments, or general funds, etc.:

The City of Ypsilanti funds our recycling programming with a separate millage which pays for city trash collection service, recycling programming, and yard waste collection. In fiscal year 2019-20 the sanitation millage rate is 2.6778 mills which generates approximately \$830,000 per year.

Description of Planned Project:

Description of the planned recycling program, including the information listed below, if applicable:

As specified above, the proposal is for the City of Ypsilanti to purchase and install approximately one hundred and eight (108) public recycling containers to be placed in the city's downtown areas and public

parks. As part of the implementation of the project, the city will place a recycling container next to existing public trash receptacles to provide an option for recycling plastic bottles, paper, and other recyclables that the city is able to collect.

Description of the infrastructure item(s) to be purchased by the grant and how they will be used to either enhance an existing recycling program or start a new program:

The containers that are proposed to be purchased are public recycling containers. The public recycling containers will be a metallic and be between 36 – 64 gallons in size. These containers will be placed within city parks and on the sidewalks in the city's downtown areas adjacent to existing trash containers so those who utilize these areas will have the option to recycle rather than just throwing items away.

Collection method (curbside, drop-off, all materials collected in the same container (single-stream), separate containers for different materials (dual stream), source separated, etc.

The collection method for these containers will involve city staff emptying these containers one or two times per week depending on the container and volume. The city will allow for the same recyclables as are accepted in our single stream curbside program.

Volume of containers (in gallons or cubic yards):

The proposed volume of the containers will be between 36 and 64 gallons. We are working with our Downtown Development Authority (DDA) to identify specific containers which are acceptable to the City and the DDA.

Collection frequency (weekly, bi-weekly, drop-off, operating hours, etc.):

It is anticipated that the City will collect recyclables from the containers at least once per week.

List of recyclable or organic matter to be collected:

The following items will be able to be deposited in the public containers: plastic (#1, #2, #4, #5, #6, and #7), tin, aluminum, mixed paper, corrugated cardboard, boxboard, newspaper, and magazines.

Name and location of recycling processor, broker and/or end market, if known:

The City of Ypsilanti takes collected recyclables to the Western Washtenaw Recycling Authority Material Recovery Facility. Their address is 8025 Werkner Road, Chelsea, MI 48118.

Description of projected increase based on the grant-funded project, as applicable. Provide explanation of calculation method or data source:

The City of Ypsilanti currently has several trash receptacles in the downtown areas and public parks within the city. Based on our estimated collection volumes we currently collect approximately 225 cubic yards of trash each year. According to 2017 data from the EPA (<https://www.epa.gov/facts-and-figures-about-materials-waste-and-recycling/national-overview-facts-and-figures-materials>) it shows that paper products and plastic have made up approximately 38.2% of all solid waste collected for that year. Based on this we are projecting that by adding public recycling containers we can divert approximately eighty-five (85) cubic yards of recyclables from our current waste stream. Please keep in mind that due to restrictions

from the material recovery facility the city cannot collect glass in our single stream recycling and due to this we did not include glass in the projection.

Increase in recycling processing capacity volume or tonnage (in tons or cubic yards):

This item is not applicable as the city does not process recyclables as part of our operation.

Increase in collection capacity volume or tonnage (in tons or cubic yards):

We are anticipating an additional eighty-five (85) cubic yards of recyclables to be diverted from our public trash receptacles per the above calculation.

Increase in access or participation:

This project will create an opportunity for the visitors, workers, and residents in our downtown areas and visitors to our city parks to have the ability to recycle items while in these areas rather than throwing them away.

Increase in population and/or number of households/units served:

The City does not have a specific number for the individuals who frequent our downtown areas and parks, but the public containers will expand public access to the employees and the visitors to these areas. The City of Ypsilanti has several large events each year in these areas which draw thousands of people. These events include the Michigan Summer Beer festival, monthly 1st Friday events, YpsiGlow, and many others. In addition to this our downtowns have a number of dining establishments which draw large lunch, dinner, and after hour crowds.

Increase in geographical area to be served:

The additional areas which will be served by public recycling are the city's downtown areas of "Depot Town" which is primarily in the area surrounding E. Cross St between Huron St and River St, "West Cross" which is on W. Cross St between Ballard St and Normal St, and "Downtown Ypsilanti" which is primarily in the area around Michigan Avenue bounded by the Huron River to the east, Hamilton St to the west, Washtenaw Ave to the north, and Ferris St to the south. The City is also proposing to add public recycling containers to twelve (12) city parks including; Candy Cane Park, Peninsular Park, Prospect Park, Waterworks Park, Frog Island Park, Riverside Park, Parkridge Park, Recreation Park, the Water Street Trail, and our three (3) tot lots.

Proposed qualitative and quantitative methods to measure and/or track increase, participation, and relevant metrics:

The volume of recycling will be quantitatively measured which the materials are taken to the recovery facility. After the weight is reported city staff will track it over time. The material recovery facility measures the recycling by tonnage rather than cubic yards. Fortunately, the EPA has published conversion factors which allow for the conversion from cubic yards to tons. The city is projecting that we will divert eighty-five (85) cubic yards of recyclables and based on the EPA conversion chart (https://www.epa.gov/sites/production/files/2016-04/documents/volume_to_weight_conversion_factors_memorandum_04192016_508fml.pdf) one (1) cubic yard of commingled recyclables weighs 262 pounds. Based on this we can revise our projection

of eight-five (85) cubic yards of diverted recyclables to 22,270 pounds or approximately eleven (11) tons of recyclables.

Include proposed frequency of monitoring/measurement:

The weight of recyclables collected will be measured on a weekly basis when the materials are taken to the recovery facility.

Description of education and outreach associated with the grant project, if applicable:

City staff will put out information highlighting the containers and will provide information on what can be deposited in the containers. We will also work with our Downtown Development Authority to reach out to our business owners about the use of the containers.

Include any specific letters committing an amount of time, money, activities, or other specified resources for the planned program.

The City has applied to Washtenaw County for a \$4,000 recycling grant to support this project and has received support from Washtenaw Regional Resource Management Authority in support of this project.

Description of how the project will be sustained beyond the grant timeline, including a description of existing or proposed operational funding sources such as user fees, millage, special assessments, or general funds, etc. to be used.

The project will be sustained beyond the grant timeline by the City utilizing our sanitation and general fund dollars for things such as container replacement and maintenance.

Describe how an evaluation of the project will be done, including how success will be defined and measured.

Success of the project will be measured by the volume of recycling that is collected and the reduction in the volume of trash in our downtown areas. We will track the volumes over a 12 month period and we will be successful if our above mentioned projections are met.

Describe how evaluation results will be used and distributed, including any products that will result from the planned program.

We will use our evaluation results to look at the participation in the program. To see how close our estimates were to the actual volume received from the recyclables. This information will be compiled into a report which will be presented to our City Council and Sustainability Commission and the information will be used to help develop a strategic plan for expanding recycling options within the city.

Work Plan

Identify the tasks and responsible party for procurement of the infrastructure item(s) proposed in the application:

Task 1: Coordinate with Downtown Development Authority on the type of containers which are projected to be used.

Responsible Party: Ron Akers, Director of Public Services

Task 2: Prepare a request for proposals for the purchase of the specific containers.

Responsible Party: Ron Akers, Director of Public Services

Task 3: Open bids and prepare information for City Council to make purchasing decision.

Responsible Party: Ron Akers, Director of Public Services

Task 4: After approval from City Council, create a purchase order and place order for containers.

Responsible Party: Ron Akers, Director of Public Services

Identify the tasks and responsible party for deployment and/or utilization of the infrastructure items(s) proposed in the application:

Task 1: After delivery of containers, inventory and create maps which depict where the placement will occur.

Responsible Party: Ron Akers, Director of Public Services

Task 2: Coordinate with Public Services staff and schedule work time to place the containers throughout the downtown areas and city parks.

Responsible Party: Environmental Foreman

Task 3: Send crews out to place the containers in various areas in the downtown areas and city parks.

Responsible Party: Environmental Foreman, Public Services Staff

Identify the tasks and party responsible for preparing quarterly progress reports and the final project report:

Task 1: Collect weight measurements taken by the material recovery facility and record them for tracking over a defined period.

Responsible Party: Department of Public Services Office Staff

Task 2: Identify trends and record the findings in a quarterly progress report.

Responsible Party: Ron Akers, Director of Public Services

Task 3: After a six (6) month time period after deployment has concluded identify numbers of recyclables collected and prepare a report which analyzes how close the volume collected was to the projected number and lists findings from the first year of the program.

Responsible Party: Ron Akers, Director of Public Services

Task 4: Use the findings to make improvements in the program which would increase volume or promote better usage.

Responsible Party: Ron Akers, Director of Public Services

Task 5: Use information to prepare/update a city-wide recycling strategic plan.

Responsible Party: Ron Akers, Director of Public Services

Timeline

April 28, 2020: Application is submitted to EGLE

July 30, 2020: Anticipated decision date on grant from EGLE

August 1, 2020: Begin discussions with the Downtown Development Authority on style of containers.

August 28, 2020: Release a request for proposals for the containers.

September 24, 2020: Have bid opening for containers.

October 6, 2020: Submit to City Council for the purchase of the containers.

October 7, 2020: Prepare purchase orders and order the containers.

December 7, 2020: Anticipated delivery date of containers. DPS staff will create location maps for the containers.

January 4, 2021: All containers will be deployed by this time.

February 1, 2021: Reimbursement request will be submitted by February 1.

February – July 2021: Receive volume measurements from material recovery facility. DPS staff will track and record these measurements.

July 1, 2021: Staff will begin work on compiling the final report including analyzing data and preparing findings.

July 12, 2021: Final report will be submitted to EGLE in compliance with grant.

July 2021: If changes to improve the program are identified those changes will be made.

August 2021: Create or update a recycling strategic plan for the city using the findings from the study.

**Department of Environment, Great Lakes, and Energy Material Management
Infrastructure Grant Application Budget Form**

Applicant Name: City of Ypsilanti				
Line Item No.	Budget Line Item Description	Quantity	Unit Price	Budget Amount
1	Recycling Containers	108	\$850	\$91,800
			\$	\$
			\$	\$
			\$	\$
			\$	\$
			\$	\$
			\$	\$
			\$	\$
			\$	\$
			\$	\$
			\$	\$
			\$	\$
			\$	\$
Total Grant Budget				\$91,800
Grant Amount Requested		Local Match Amount		Total Grant Budget
\$73,440		\$18,360		\$91,800

The local match amount must equal at least 20 percent of the ***total grant budget***. The local match amount can be greater than 20 percent of the total grant budget. The grant amount requested cannot exceed \$1,000,000.

For example, if the **total grant budget** is \$1,500,000, the grant amount requested can only be the maximum amount of \$1,000,000, and the local match amount would have to be \$500,000, which is greater than 20 percent of the **total grant budget**.

If the **total grant budget is** \$100,000, the local 20 percent match amount would have to be at least \$20,000.

Budget Narrative

The proposed cost items in the budget are the public recycling containers. Both are capital expenses which work to meet the objective of the project and thus are eligible expenditures under the grant program. As specified above, the public recycling containers have not been selected as of yet and are projected to be between 36 gallons and 64 gallons in size. City staff has reviewed our suppliers for a price range of these recycling containers and have determined based on that review an appropriate cost per durable container would be in the \$850 per container range. I have attached prices for various containers that staff has looked at when making these comparisons.

The match funding is proposed to be from two sources. The City of Ypsilanti will provide \$14,360 from their solid waste fund to match the 20% requirement for the grant proposal and Washtenaw County Department of Public Works has offered to provide \$4,000 in match toward the project from their Waste Reduction Sponsorship Program.

Ronald Akers

From: Freeman, Emily (EGLE) <FREEMANE@michigan.gov>
Sent: Monday, November 30, 2020 5:05 PM
To: Freeman, Emily (EGLE)
Cc: Krcmarik, Jeffry (EGLE)
Subject: FW: EGLE awards nearly \$1.6 million in record-setting infrastructure grants to support largest expansion of recycling in Washtenaw County history

FYI – Please see below for press release sent out today about grant projects.

From: MI Dept. of Environment, Great Lakes, and Energy <EGLE@govsubscriptions.michigan.gov>
Sent: Monday, November 30, 2020 2:02 PM
To: Freeman, Emily (EGLE) <FREEMANE@michigan.gov>
Subject: EGLE awards nearly \$1.6 million in record-setting infrastructure grants to support largest expansion of recycling in Washtenaw County history

[Share or view as a webpage](#) | [Update preferences](#)



FOR IMMEDIATE RELEASE

Nov. 30, 2020

Jill A. Greenberg, EGLE Spokesperson, GreenbergJ@Michigan.gov, 517-897-4965

EGLE awards nearly \$1.6 million in record-setting infrastructure grants to support largest expansion of recycling in Washtenaw County history

The Michigan Department of Environment, Great Lakes, and Energy (EGLE) today announced a combined total of more than \$1.58 million in infrastructure grants awarded to six public agency and nonprofit recipients that will support the largest expansion of recycling in Washtenaw County history.

"Recycling infrastructure grants are a critical component of EGLE's support for recycling growth in Michigan," said Elizabeth Browne, assistant director of the Materials Management Division at EGLE.

"The objective of the EGLE recycling infrastructure grants is to increase processing and collection capacity in Washtenaw County, improve access to community recycling programs and grow participation among the constituencies they serve by assisting with the purchase of equipment and other items," Browne said.

"In addition, several of these projects will have a direct impact on reducing the spread of infectious disease through greater use of automation, which aligns with Michigan's efforts to help mitigate the spread of COVID-19."

The Washtenaw County grants are part of EGLE's strategy to support recycling infrastructure, improve the quality of recyclable materials and promote market development using the Renew Michigan Fund, which was created in 2019 to boost the state's recycling efforts.

EGLE's Washtenaw County grant recipients are:

- **\$458,370 to the Western Washtenaw Recycling Authority (WWRA)** to purchase sorting equipment and a new truck to increase processing and collection capacity. The funds equip WWRA to accept new commercial and municipal customers. The automated truck will dramatically increase workplace safety and will enable WWRA to add 3,000 households per week, while the new sorting equipment doubles the capacity for sorting plastics. WWRA is subsidized by five communities that work cooperatively to implement residential recycling programs in the townships of Dexter, Lyndon, Manchester and Lima, and the city of Chelsea. It's the largest EGLE grant to WWRA since it formed in 1991.
- **\$118,605 to the Washtenaw Regional Resource Management Authority (WRRMA)** that will continue its efforts to increase the quantity of member communities' high-quality recyclables. WRRMA members consist of the charter townships of Ann Arbor, Pittsfield and Ypsilanti, Scio Township and the cities of Dexter, Saline and Ypsilanti, representing a population of over 150,000 Washtenaw County residents. WRRMA will use the funds to complete the national nonprofit The Recycling Partnership's "Feet on the Street" program at single-family residences in WRRMA communities beginning in spring 2021. The program provides recycling education to residents and curbside feedback through tagging carts, as well as records pre- and post-program metrics through a sorting process at material recovery facilities. The program has been successfully implemented in communities throughout the nation, obtaining a 20% to 40% decrease in recycling contamination. It's the first EGLE grant to WRRMA since its creation in 2019.
- **\$112,716 to Ann Arbor Public Schools** to significantly increase access to recycling by installing recycling collection containers and promoting food reclamation activities throughout the district's campuses and buildings that serve more than 20,000 students. A refrigerated vehicle purchased through the grant will transport as much as 100 pounds of unused food daily to food distribution agencies, such as Food Gatherers. It's the largest grant EGLE has awarded to the Ann Arbor district.
- **\$73,440 to the city of Ypsilanti** to expand public space recycling through the purchase of recycling containers for the city's downtown area, Depot Town and 12

public parks. Ypsilanti's parks have become popular with a growing number of festivals and businesses and have seen increased foot traffic. Once the recycling equipment is installed, the city estimates it will annually divert 11 tons of recyclables from Ypsilanti's public trash containers. City leaders plan to place a recycling container next to existing public trash receptacles, which is an important best practice for public space recycling.

- **\$17,608 to Dexter Community Schools** to expand lunchroom recycling and establish food waste collection programs throughout the district, which serves 3,635 students. The grant will help Dexter schools to recycle more lunchroom items and achieve cost savings due to reduced trash pickups.
- In addition to the grants announced today, EGLE on Nov. 18 unveiled the award of **\$800,000 to Recycle Ann Arbor**. The grant – which is the largest-ever EGLE has made to the Ann Arbor-based 40-year-old nonprofit – will help rebuild and reopen the community's materials recovery facility that has been closed since 2016. The new facility will be owned and operated by Recycle Ann Arbor. The \$6.75 million project, which includes an additional \$800,000 loan from national nonprofit Closed Loop Partners, will ultimately create a state-of-the-art materials recovery facility that allows for enhanced sorting of valuable recyclable materials. The new facility will provide processing capacity for 15,000-plus tons of recycled materials that is now being transported to Ohio, as well as processing additional volume from the surrounding region. The project is expected to create 10 to 20 new full-time jobs upon completion.

EGLE's support of new research, education and recycling activities planned for Washtenaw County come as Michigan and states across the United States are seeing significant increases in curbside recycling due to more Americans sheltering and working from home to help prevent the spread of COVID-19.

EGLE-commissioned research surveys show Michigan residents view recycling as an essential public service. And during a time of social distancing where many nonessential employers are closed and commercial recycling is near an all-time low, producers see residential recycling programs as a critical supplier of manufacturing feedstock so more companies can make their products from recycled content instead of new materials.

"Common mistakes are making their way into the recycling bins and causing problems within the recycling system," said Recycle Ann Arbor CEO Bryan Ukena.

"Recycling contamination causes extra wear on the equipment, increases the amount of material ending up in the landfill and degrades the quality of recyclable material to be sold to end markets," Ukena said. "Recycle Ann Arbor is committed to helping the community recycle more and better. More recycling and better recycling produces better results."

Another goal of EGLE's funding support in Washtenaw County is to minimize contaminated recyclables from going into bins by providing educational messaging across all municipalities. Recycling contamination occurs when materials not accepted for recycling are put in recycling bins, such as plastic bags or items with food residue. An estimated 30% to 35% of the materials currently recycled by residents in WRRMA's service territory are contaminated. WRRMA plans to kick off its program in spring 2021 with a target of reducing recycling contamination by 40% by fall 2021.

"WRRMA's strategy is aimed at reducing costs by increasing the quality of our recycling stream and making strides toward a stronger recycling system in Washtenaw County," said Washtenaw County Public Works Director Theo Eggermont.

EGLE's grants to Washtenaw County will help build on the success of Michigan's national award-winning Know It Before You Throw It recycling education campaign that EGLE launched in 2019. The aim of the first-of-its-kind statewide push is to better inform Michiganders on what can – and cannot – be recycled and how to recycle correctly.

Gov. Gretchen Whitmer and state legislators want to double Michigan's recycling rate to 30% by 2025 and ultimately reach 45% annually. Michigan's current 15% recycling rate is the lowest in the Great Lakes region and ranks among the nation's lowest.

Tripling the rate to 45% would support 138,000 new jobs in Michigan's recycling industry, providing \$9 billion in annual labor income and \$33.8 billion in economic output, according to a study commissioned by EGLE.

More information about the Know It Before You Throw It campaign is available at RecyclingRaccoons.org. To stay up to date on other EGLE news, follow Michigan.gov/MIEnvironment.

###



EGLE COVID-19 RESPONSE:

For details on EGLE's work during the pandemic, [visit our COVID-19 response webpage](#). Follow state actions and guidelines at Michigan.gov/Coronavirus.

Connect With Us:



If you wish to no longer receive emails from us,
please update your preferences here:

[Manage Preferences](#) | [Help](#)

Need further assistance?

[Contact Us](#) | [Provide Feedback](#)



REQUEST FOR LEGISLATION

TO: Mayor and City Council
FROM: Frances McMullan
DATE: January 5, 2021
SUBJECT: COAM 2021-2024 COLLECTIVE BARGAINING AGREEMENT

DESCRIPTION:
COAM 2021-2024 COLLECTIVE BARGAINING AGREEMENT

SUMMARY:

COAM, representing the City's Police Command Officers, and the City have reached a tentative agreement on a new collective bargaining agreement for the term of January 1, 2021, through December 31, 2024.

PREVIOUS COUNCIL ACTION:

None

FINANCIAL IMPACT:

None

LANGUAGE CLEAN UP:

Please refer to the tentative agreement for specific details.

ATTACHMENT:
Tentative agreement documents

CITY MANAGER APPROVAL: _____ COUNCIL AGENDA DATE: _____

CITY MANAGER COMMENTS: _____

FISCAL SERVICES DIRECTOR APPROVAL: _____



Resolution No. 2021-007
January 5, 2021

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

WHEREAS, the COAM collective bargaining agreement with the City expired on December 31, 2020; and

WHEREAS, the City and the Union have been engaged in contract negotiations on a successor contract; and

WHEREAS, the City and the Union have reached a tentative agreement on a new collective bargaining agreement for the term commencing on January 1, 2021, and terminating on December 31, 2024; and

WHEREAS, the City desires to approve the new contract as presented.

NOW THEREFORE BE IT RESOLVED THAT the Council of the City of Ypsilanti does hereby approve the new collective bargaining agreement between the City of Ypsilanti and the COAM, for the term commencing on January 1, 2021, and terminating on December 31, 2024, as presented, and authorizes the Mayor, City Manager, and City Clerk to execute the agreement on behalf of the City, subject to approval as to form by the City Attorney.

OFFERED BY: _____

SECONDED BY: _____

YES: NO: ABSENT: VOTE:

This resolution is adopted by the Council of the City of Ypsilanti and approved by the Mayor this
5 day of January 2021

#Resolution No. 2021-007

COAM TENTATIVE AGREEMENT AS OF October 19, 2020

IT IS HEREBY AGREED by and between the City of Ypsilanti and the Command Officers Association of Michigan that, in tentative settlement of all outstanding issues under negotiation, and subject to ratification by their principal parties, the parties' negotiation teams agree to the following, and agree to recommend ratification to their respective principal parties, as follows:

- A. The parties' new contract will be the same as the parties' prior contract (July 1, 2017 thru December 31, 2020) except as amended as follows:
1. Duration: The parties agree to a four (4) year contract effective from January 1, 2021 to December 31, 2024. All relevant sections of the Collective Bargaining Agreement shall be modified accordingly.
 2. Section 9.7 Personal Leave Bank: The parties agree to clean up the language of this section to remove references to six (6) days and seventy-two (72) hours as this is no longer accurate. As of July 1, 2018, COAM currently receives nine (9) days or one hundred eight (108) hours per year as stated in section 10.3 and attachments A1, A2, and A3.
 3. Section 14.3 Holiday Work Schedule: The parties agree to remove this section as working during vacations does not apply to the current model.
 4. Section 15.1 Accumulation of Vacation: The parties agree to clean up the language of this section to say, "Match the current POAM schedule" and remove reference to attachment A1.
 5. Section 16.1 Accumulation of Sick Leave Credits: The parties agree to remove the section referencing attachments A1, A2, and A3 along with the sliding scale for sick time payouts and replace it with a flat 50% payout of accumulated sick bank. However, Lt. Yuchasz will be grandfathered at 60%.
 6. Article XXXVI COAM Benefits by Date Hired: The parties agree to replace this with "COAM Benefits for All Unit Members Effective 01/01/2021" and include attachment provided by COAM negotiating team.
 7. Addition: The parties agree to add language as follows, "Upon change in rank (promotion), employee will be provided with two (2) complete sets of uniforms."

COAM TENTATIVE AGREEMENT 101920

8. Removal: To reduce confusion and conflicting language from multiple sections which reference each other, the parties agree to remove sections 9.7, 10.3, 14.3, 15.1, and 16.1.

DATE: October 19, 2020

FOR THE UNION:

FOR THE CITY:



Resolution No. 2021-008
January 5, 2021

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

That the City Council Meeting be adjourned, on call, by the Mayor or three (3) members of Council.

OFFERED BY: _____

SECONDED BY: _____

YES: NO: ABSENT: VOTE:

This resolution is adopted by the Council of the City of Ypsilanti and approved by the Mayor this
5 day of January 2021

#Resolution No. 2021-008