

1. Revised Council Agenda

Documents:

[REVISION 2 FINAL AGENDA 3-21-17.PDF](#)

2. Revised Council Packet

Documents:

[MARCH 21ST COUNCIL PACKET.PDF](#)

3. Zoning Document 1

Documents:

[ZOUUPDATE- 02- ZO_BW20170315_ANNO.PDF](#)

4. Zoning Document 2

Documents:

[ZOUUPDATE- 03- ZO_BW20170315_PLAIN.PDF](#)

5. Zoning Document 3

Documents:

[ZOUUPDATE- 04- ZO_20170307.PDF](#)

6. Zoning Document 4

Documents:

[ZOUUPDATE- 05- WALL_ZONING.PDF](#)

7. Council Action Minutes

Documents:

[ACTION MINUTES 3-21-17.PDF](#)



(Revised 3/20/17)

**CITY OF YPSILANTI
REGULAR COUNCIL MEETING
CITY COUNCIL CHAMBERS – ONE SOUTH HURON ST.
YPSILANTI, MI 48197
TUESDAY, MARCH 21, 2017
7:00 p.m.**

I. CALL TO ORDER –

II. ROLL CALL –

Council Member Bashert	P A	Council Member Robb	P A
Mayor Pro-Tem Brown	P A	Council Member Vogt	P A
Council Member Murdock	P A	Mayor Edmonds	P A
Council Member Richardson	P A		

III. INVOCATION –

IV. PLEDGE OF ALLEGIANCE –

"I pledge allegiance to the flag, of the United States of America, and to the Republic for which it stands, one nation, under God, indivisible, with liberty and justice for all."

V. AGENDA APPROVAL –

VI. INTRODUCTIONS –

VII. PRESENTATIONS -

Medical Marijuana – City Planner Bonnie Wessler and Assistant City Attorney Dan DuChene

Resolution No. 2017-055, supporting the display of the Transgender Pride flag.

VIII. AUDIENCE PARTICIPATION –

IX. REMARKS BY THE MAYOR –

X. ORDINANCES – FIRST READING –

Ordinance No. 1285

1. An ordinance to amend Section 58-32 of the Ypsilanti City Code to add two youth non-voting members to the Human Relations Commission.

- A. Resolution No. 2017-060, determination
- B. Open public hearing
- C. Resolution No. 2017-061, close public hearing

XI. CONSENT AGENDA –

Resolution No. 2017 – 062

1. Resolution No. 2017-063, opposing elimination and reduction of US Department of Housing and Urban Development programs which are vital to Washtenaw County residents.
2. Resolution No. 2017-064, approving appointments to Boards and Commissions.
3. Resolution No. 2017-065, approving appointments to Boards and Commissions (non-residents).
4. Resolution No. 2017-066, approving minutes of January 24 and January 31, 2017.

XII. RESOLUTIONS/MOTIONS/DISCUSSIONS –

1. Resolution No. 2017-067, approving budget amendments changing loan to a fund transfer for the uncollected reimbursement from MNRTF of \$328,490.00.
2. Resolution No. 2017-068, approving Ordinance 1284, to amend Chapter 122 (Zoning ordinance) of the City's Code of Ordinances. ***(Second Reading)***
3. Resolution No, 2017-069, adopting a five-year road funding plan.
4. Resolution No. 2017-070, approving City Manager MERS Defined Compensation Plan.
5. Resolution No. 2017-071, scheduling a work session for the purpose of discussing and approving a list of priorities and expectations for the City Manager.
6. Resolution No. 2017-073, opposing oil transport through the Enbridge Energy Line 5 pipeline. ***(added 3/20/17)***

XIII. LIASON REPORTS –

- A. SEMCOG Update
- B. Washtenaw Area Transportation Study
- C. Urban County
- D. Ypsilanti Downtown Development Authority
- E. Eastern Washtenaw Safety Alliance
- F. Police-Community Relations/Black Lives Matter Joint Task Force
- G. Friends of Rutherford Pool
- H. Housing Equity Leadership Team
- I. Economic Development Coordinating Committee

XIII. COUNCIL PROPOSED BUSINESS –

XIV. COMMUNICATIONS FROM THE MAYOR –

XV. COMMUNICATIONS FROM THE CITY MANAGER –

XVI. COMMUNICATIONS –

XVII. AUDIENCE PARTICIPATION –

XVIII. REMARKS FROM THE MAYOR –

XIX. CLOSED SESSION –

Closed Session to discuss attorney-client privileged communication - OMA 15.267, Section 8(h)

XX. ADJOURNMENT -

Resolution No. 2017-072, adjourning the City Council meeting.



(Revised 3/20/17)

**CITY OF YPSILANTI
REGULAR COUNCIL MEETING
CITY COUNCIL CHAMBERS – ONE SOUTH HURON ST.
YPSILANTI, MI 48197
TUESDAY, MARCH 21, 2017
7:00 p.m.**

I. CALL TO ORDER –

II. ROLL CALL –

Council Member Bashert	P A	Council Member Robb	P A
Mayor Pro-Tem Brown	P A	Council Member Vogt	P A
Council Member Murdock	P A	Mayor Edmonds	P A
Council Member Richardson	P A		

III. INVOCATION –

IV. PLEDGE OF ALLEGIANCE –

"I pledge allegiance to the flag, of the United States of America, and to the Republic for which it stands, one nation, under God, indivisible, with liberty and justice for all."

V. AGENDA APPROVAL –

VI. INTRODUCTIONS –

VII. PRESENTATIONS -

Medical Marijuana – City Planner Bonnie Wessler and Assistant City Attorney Dan DuChene

Resolution No. 2017-055, supporting the display of the Transgender Pride flag.

VIII. AUDIENCE PARTICIPATION –

IX. REMARKS BY THE MAYOR –

X. ORDINANCES – FIRST READING –

Ordinance No. 1285

1. An ordinance to amend Section 58-32 of the Ypsilanti City Code to add two youth non-voting members to the Human Relations Commission.

- A. Resolution No. 2017-060, determination
- B. Open public hearing
- C. Resolution No. 2017-061, close public hearing

XI. CONSENT AGENDA –

Resolution No. 2017 – 062

1. Resolution No. 2017-063, opposing elimination and reduction of US Department of Housing and Urban Development programs which are vital to Washtenaw County residents.
2. Resolution No. 2017-064, approving appointments to Boards and Commissions.
3. Resolution No. 2017-065, approving appointments to Boards and Commissions (non-residents).
4. Resolution No. 2017-066, approving minutes of January 24 and January 31, 2017.

XII. RESOLUTIONS/MOTIONS/DISCUSSIONS –

1. Resolution No. 2017-067, approving budget amendments changing loan to a fund transfer for the uncollected reimbursement from MNRTF of \$328,490.00.
2. Resolution No. 2017-068, approving Ordinance 1284, to amend Chapter 122 (Zoning ordinance) of the City's Code of Ordinances. ***(Second Reading)***
3. Resolution No, 2017-069, adopting a five-year road funding plan.
4. Resolution No. 2017-070, approving City Manager MERS Defined Compensation Plan.
5. Resolution No. 2017-071, scheduling a work session for the purpose of discussing and approving a list of priorities and expectations for the City Manager.
6. Resolution No. 2017-073, opposing oil transport through the Enbridge Energy Line 5 pipeline. ***(added 3/20/17)***

XIII. LIASON REPORTS –

- A. SEMCOG Update
- B. Washtenaw Area Transportation Study
- C. Urban County
- D. Ypsilanti Downtown Development Authority
- E. Eastern Washtenaw Safety Alliance
- F. Police-Community Relations/Black Lives Matter Joint Task Force
- G. Friends of Rutherford Pool
- H. Housing Equity Leadership Team
- I. Economic Development Coordinating Committee

XIII. COUNCIL PROPOSED BUSINESS –

XIV. COMMUNICATIONS FROM THE MAYOR –

XV. COMMUNICATIONS FROM THE CITY MANAGER –

XVI. COMMUNICATIONS –

XVII. AUDIENCE PARTICIPATION –

XVIII. REMARKS FROM THE MAYOR –

XIX. CLOSED SESSION –

Closed Session to discuss attorney-client privileged communication - OMA 15.267, Section 8(h)

XX. ADJOURNMENT -

Resolution No. 2017-072, adjourning the City Council meeting.



Medical Marihuana:

Changes

CITY OF YPSILANTI, MI
21 MARCH 2017

Medical Marihuana Patient/Caregiver Framework

Michigan Medical Marihuana Act (MMMA – MCL 333.26421 et seq)

- Voter initiated in 2008
- Qualifying patient must have written certification of debilitating medical condition from physician to be issued registry ID card from LARA
 - Permitted to have 2.5 ounces of usable marijuana
 - Permitted to cultivate 12 plants, if no caregiver designated
 - May only designate one caregiver
- Primary caregiver must be 21 years of age, not be convicted of a felony within past 10 years, never been convicted of felony involving drugs or assault
 - Permitted 2.5 ounces per patient
 - Permitted 12 plants per patient
 - Permitted a total of five patients

Medical Marihuana Patient/Caregiver Framework

MMMA did not address medical marijuana businesses

- Statute and subsequent case law limited any sale of marijuana from caregiver and their specific patient.
 - Patient-to-patient sales specifically prohibited
 - Caregiver-to-patient only authorized if patient tied to that specific caregiver
- Activity that is protected under the MMMA is immune from criminal prosecution, monetary sanction, abatement as a nuisance, and prohibition through zoning
- If activity is not protected by MMMA, then such immunities do not exist
- Until adoption of Medical Marihuana Facilities Licensing Act (discussed later), commercial marijuana enterprises operated in a very limited gray area.



Current Process in the City: Licensing

Both dispensaries and grow facilities must apply for a Medical Marijuana License prior to operating, under Chapter 7 of the Code of Ordinances.

- The current licensing ordinance caps the number of dispensaries at 6, and grow facilities at 3.
- Applicants must meet certain conditions for initial issuance of license, and similar conditions for renewal.
- Licenses may be revoked or not renewed for the following reasons:
 - (1) A failure to meet the conditions or maintain compliance with the standards established by this division in reference to applications for a new license or the renewal of an existing license;
 - (2) One or more violations of any city ordinance on the premises;
 - (3) Maintenance of a nuisance on the premises;
 - (4) A demonstrated history of excessive calls for public safety (police, fire, and EMS) originating from the premises, being three or more calls in any 30-day period; or
 - (5) Nonpayment of real and/or personal property taxes, fines, fees or liens owed to the city.
- To date, no licenses have been revoked or not renewed.

Current Process in the City: Zoning

Dispensaries (§122-813):

- **May be located in the Center District (Downtown, Depot Town, West Cross); permitted use (no site plan or Special Use permit needed)**
- **Must be located 500 feet from other dispensaries or grow facilities; 1000 feet from grade schools.**
- **Drive-throughs not permitted**
- **No use permitted within the dispensary**
- **All business must be done within the facility, nothing outdoors**
- **Cannot grow/cultivate at the facility**
- **Must be licensed by the City**
- **If ceases operation for 60 days, all approvals expire**
 - Note: this conflicts with the licensing provision: licenses terminate if operation ceases for 90 days or more
- **Must be open to inspection by the City at the request of Building Official, Fire Marshal, or other City Officials at any time;**
 - Must keep an accurate logbook/database with information on amount of marijuana on-hand, amount dispensed, with patient and caregivers identified.
 - Must allow up to quarterly inspections by City to maintain license;
 - Inspections shall be conducted to ensure compliance with local and State laws and regulations.

Current Process in the City: Zoning

Grow Facilities (§122-814):

- **May be located in the PMD (industrial) or GC (general corridor) districts; must obtain a Special Use permit (public hearing)**
- **Must be located 500 feet from other dispensaries or grow facilities; 1000 feet from grade schools.**
- **Drive-throughs not permitted**
- **No use permitted within the facility**
- **All business/growing must be done within the facility, nothing outdoors**
- **Must be licensed by the City**
- **If ceases operation for 60 days, all approvals expire (including Special Use permit)**
 - Note: this conflicts with the licensing provision: licenses terminate if operation ceases for 90 days or more
- **Must be open to inspection by the City at the request of Building Official, Fire Marshal, or other City Officials at any time;**
 - Must keep an accurate logbook/database with information on amount of marijuana on-hand, amount dispensed, with patient and caregivers identified.
 - Must allow up to quarterly inspections by City to maintain license;
 - Inspections shall be conducted to ensure compliance with local and State laws and regulations.

Newly Adopted State Statutes

Medical Marihuana Facilities Licensing Act (MMFLA – MCL 333.27101 et seq)

- Effective as of December 20, 2016
- Establishes Medical Marihuana Licensing Board
 - Governor-appointed five-member board under LARA
 - Deciding on license applications
 - Promulgating rules under Act
 - Overseeing operation of provisions of Act
- Also establishes Marihuana Advisory Panel
 - 17-members
 - Recommendations to the Board regarding all of Board's responsibilities
- No licenses will be issued until December 15, 2017

Newly Adopted State Statutes

Medical Marihuana Facilities Licensing Act (MMFLA – MCL 333.27101 et seq), cont...

- Five types of licenses
 - Grower
 - Class A – 500 plants
 - Class B – 1,000 plants
 - Class C – 1,500 plants
 - Processor (purchases from grower, creates and sells marijuana-infused products to provisioning centers)
 - Provisioning center (buys from growers and processors and sells to patients)
 - Safety compliance
 - Tests marijuana for contaminants and cannabinoids
 - Functions for both facilities and primary caregivers
 - Secure transporter
 - Stores and transports marijuana for facilities
 - Required for transfers of marijuana (aside from provisioning centers to patients)

Newly Adopted State Statutes

Medical Marihuana Facilities Licensing Act (MMFLA – MCL 333.27101 et seq), cont...

- Limits ability of licensees to be invested in more than one type facility
 - Growers, Processors, and Secure Transporters may not be primary caregivers
 - Secure Transporters may not be primary caregivers or patients and may not have interest in any other type of facility
 - Safety compliance facility may not have an interest in any other type of facility

Newly Adopted State Statutes

Medical Marihuana Facilities Licensing Act (MMFLA – MCL 333.27101 et seq), cont...

- Local control
 - Marijuana facilities may only operate in a community if the local municipality has adopted an ordinance authorizing that specific type of facility
 - Municipalities may authorize **some, all, or none** of the different types of facilities
 - Municipalities **may also limit the number of each type of facility** authorized
- Licensing framework
 - Statute provides that individuals may apply the state for licenses by December 2017
 - Applicants apply to state for state license
 - Must notice municipality within 10 days that state application filed
 - Municipality required to provided information to the state within 90 days

Newly Adopted State Statutes

Medical Marihuana Facilities Licensing Act (MMFLA – MCL 333.27101 et seq), cont...

- Information to be supplied by municipality
 - Copy of local ordinance authorizing facility
 - Copy of zoning regulations that apply to the facility
 - A description of any violation of relevant ordinances
- Municipality may charge annual, non-refundable fee of up to \$5,000 per license
- All information obtained by municipality for application exempt from disclosure under FOIA
- Taxes and Fees
 - Local and state application fees
 - Regulatory assessment of not more than \$10,000 for grower license
 - Three percent excise tax on sales made by provisioning centers

Newly Adopted State Statutes

Medical Marihuana Facilities Licensing Act (MMFLA – MCL 333.27101 et seq), cont...

- Taxes and Fees
 - Local application fee stays with municipality
 - State application fee and regulatory assessment goes to Marihuana regulatory fund
 - Costs of implementing, administering, and enforcing act
 - \$500,000 and five percent of regulatory assessments to be used for expenditures for licensing substance use disorder programs
 - Funding for standardized field sobriety tests.
 - Administrative costs of Michigan Commission on Law Enforcement Standards
 - Money from excise tax placed in Medical Marijuana Excise Fund

Newly Adopted State Statutes

Medical Marihuana Facilities Licensing Act (MMFLA – MCL 333.27101 et seq), cont...

- 30 percent to counties with marijuana facilities, in proportion to number of facilities within the county.
- Additional five percent to counties, accordingly, to county sheriffs.
- 25 percent to municipalities with marijuana facilities, in proportion to number facilities in municipality
- Five percent to Michigan Commission on Law Enforcement Standards for training local law enforcement officers
- Five percent to the MSP
- 30 percent to the state
 - General fund until September 30, 2017
 - Beginning October 1, 2017, to first responder presumed coverage fund of worker's disability compensation act of 1969

Newly Adopted State Statutes

Marihuana Tracking Act (MMFLA – MCL 333.27901 et seq)

- LARA required to establish a statewide monitoring system for
 - Tracking
 - Inventory
 - Verification
 - Must be able to interact with third-party inventory and tracking systems used by licensed facilities
 - Must allow verification of registry ID card for sales from provisioning centers
 - Facilities are required to enter all transactions, inventory and other relevant information in this database
 - Provisioning centers required to check registry IDs through this system
 - All information in this system is exempt from disclosure under FOIA
- 

State Licensing Board: Status, Process

- As of March 14th, the State licensing board has not yet been appointed. GCSI is anticipating that they will be appointed “soon,” and we will begin to see draft rules presented for Board review in late April/early May.
- LARA’s Marijuana Licensing Division will be hiring up to 150 FTEs to meet the anticipated demand for processing applications for facility licenses. The precise process for approval is yet unknown. For instance:
 - We are required to submit a copy of the authorizing ordinance, etc, per the MMFLA. However, we do not yet know if LARA will be interpreting that ordinance themselves (unlikely), or if there will also be a separate authorization form (as for childcare, auto sales, etc) wherein we confirm the facility’s legality (more likely).
 - There are no spacing requirements in the MMFLA, but there are ownership separation requirements. It appears there *may* be an ability to “stack” licenses in one location/under one roof, so long as each facility is under separate ownership and each facility’s ownership is separate from the building’s. There is one such facility being proposed in Kingsley; its total size would be approximately 100,000 square feet.

What's Next for Ypsi?

- **Do we want to continue to allow medical marijuana uses in Ypsilanti?**
- **Do we want to open up City to additional medical marijuana businesses authorized under statute?**
 - Maintain and update current licensing procedure
 - Cap: Remove? Update to reflect the current number of dispensaries, etc?
 - Update the zoning ordinance:
 - Which facilities in which districts?
 - Dispensaries in commercial? all else industrial?
 - Potential changing of zoning districts?
 - Currently, dispensaries only permitted in C; grows in PMD and GC.
 - Maintain buffer for PMD-zoned marijuana facilities, or allow the industrial types to cluster?
 - Update/alter existing requirements under zoning for facilities?
 - For example, hours of operation for dispensaries.



A RESOLUTION SUPPORTING THE DISPLAY OF THE TRANSGENDER PRIDE FLAG

WHEREAS, no federal or state of Michigan law currently prohibits discrimination based on gender identity in employment, housing, or public accommodations; and,

WHEREAS, the state of Michigan's own Department of Civil Rights has concluded that anti-LGBT discrimination "exists and is significant" and that such discrimination has "direct negative economic effects on Michigan"; and,

WHEREAS, discrimination impedes the city of Ypsilanti and the state of Michigan's ability to attract and retain talented, hard working, determined people and by extension economic growth and prosperity; and,

WHEREAS, in the absence of state action by Michigan's legislature forty-two Michigan communities, including the city of Ypsilanti, have enacted local, comprehensive nondiscrimination ordinances; and,

WHEREAS, March 31 has been recognized annually as "Transgender Day of Visibility" since 2009 when Michigan transgender activist Rachel Crandall founded the observance; and,

WHEREAS, recent action by the Trump administration withdrawing federal guidance on the rights of transgender students at school make it more important than ever for communities to speak out in support of these students,

NOW, THEREFORE, BE IT RESOLVED, that in recognition of "Transgender Day of Visibility" and in solidarity with and support of transgender people across the United States, the city of Ypsilanti shall fly the transgender pride flag on Friday, March 31, 2017.

OFFERED BY: _____

SUPPORTED BY: _____

YES: NO: ABSENT: VOTE:



**Barr,
Anhut &
Associates, P.C.**
ATTORNEYS AT LAW

105 Pearl Street
Ypsilanti, MI 48197
(734) 481-1234
Fax (734) 483-3871
www.barrlawfirm.com
e-mail: jhealy@barrlawfirm.com

John M. Barr
Karl A. Barr
Daniel J. DuChene

Jesse O'Jack ~ Of Counsel
William F. Anhut ~ Of Counsel – Retired
Jennifer A. Healy ~ Legal Assistant

REQUEST FOR LEGISLATION

DATE: 3/17/17

FROM: John M. Barr, Ypsilanti City Attorney

SUBJECT: Addition of two non-voting youth members to Human Relations Commission

SUMMARY/BACKGROUND

The City's Human Relations Commission has requested the addition of two youth commissioners to its membership. The Commission was created and established by ordinance, per requirement of the City Charter. Thus, an amendment to the existing ordinance is required to fulfill such a request.

As has been previously provided, state law requires that members of City boards and commissions be qualified electors, which requires in part that members be at least 18 years of age. However, youth members may serve in an advisory capacity in that they be non-voting members.

RECOMMENDED ACTION: Review and consideration

DATE RECEIVED: _____ AGENDA ITEM NO. 2017-060

CITY MANAGER COMMENTS:

FOR AGENDA OF: _____ FINANCE DIR. APPROVAL: _____

COUNCIL ACTION TAKEN: _____



Resolution No. 2017-060
March 21, 2017

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI that:

The ordinance entitled: "An ordinance to amend section 58-32 of the Ypsilanti City Code to add two youth non-voting members to the Human Relations Commission" be adopted on First Reading.

OFFERED BY: _____

SUPPORTED BY: _____

YES: NO: ABSENT: VOTE:



**CITY OF YPSILANTI
NOTICE OF ADOPTED ORDINANCE
Ordinance No. 1285**

An ordinance to amend section 58-32 of the Ypsilanti City Code to add two youth non-voting members to the Human Relations Commission

- 1. THE CITY OF YPSILANTI HEREBY ORDAINS** That section 58-32 of the Ypsilanti City Code is hereby amended to add the following language to the section: "Two additional, youth non-voting-members, may also be appointed, in addition to the nine regular voting members."

The section as amended shall read as follow:

a)

There is hereby created a *human relations commission* to be appointed by the mayor with the approval of the city council. The *human relations commission* shall be composed of nine members, all city residents, one of whom shall be designated as chair to be selected by the mayor to serve until a new chair is elected by a majority of the *human relations commission*. Term of chair shall be one year. The term of members shall be three years. The first members shall be appointed in groups of three for terms of one, two and three years, and thereafter the terms of three members shall expire each year. Two additional, youth non-voting-members may also be appointed, in addition to the nine regular voting members.

- 2. Severability.** If any clause, sentence, section, paragraph, or part of this ordinance, or the application thereof to any person, firm, corporation, legal entity, or circumstances, shall be for any reason adjudged by a court of competent jurisdiction to be unconstitutional or invalid, such judgment shall not effect, impair, or invalidate the remainder of this Ordinance and the application of such provision to other persons, firms, corporations, legal entities, or circumstances by such judgment shall be confined in its operation to the clause, sentence, section, paragraph, or part of this Ordinance thereof directly involved in the case or controversy in which such judgment shall have been rendered and to the person, firm, corporation, legal entity, or circumstances then and there involved. It is hereby declared to be the legislative intent of this body that the Ordinance would have been adopted had such invalid or unconstitutional provisions not have been included in this Ordinance.

3. Repeal. All other Ordinances inconsistent with the provisions of this Ordinance are, to the extent of such inconsistencies, hereby repealed.

4. Savings Clause. The balance of the Code of Ordinances, City of Ypsilanti, Michigan, except as herein or previously amended, shall remain in full force and effect. The repeal provided herein shall not abrogate or affect any offense or act committed or done, or any penalty or forfeiture incurred, or any pending fee, assessments, litigation, or prosecution of any right established, occurring prior to the effective date hereof.

5. Copies to be available. Copies of the Ordinance are available at the office of the city clerk for inspection by, and distribution to, the public during normal office hours. A complete copy of the ordinance is also available for inspection on the City's website, www.cityofypsilanti.com.

6. Publication and Effective Date. The City Clerk shall cause this Ordinance, or a summary of this Ordinance, to be published by printing the same in the publication of record. This Ordinance shall become effective after publication at the expiration of 30 days after adoption.

MADE, PASSED AND ADOPTED BY THE YPSILANTI CITY COUNCIL THIS _____
DAY OF _____, 2017.

Frances McMullan, City Clerk

Attest

I do hereby confirm that the above Ordinance No. ____ was published in The Washtenaw Legal News on the _____ day of _____, 2017.

Frances McMullan, City Clerk

CERTIFICATE OF ADOPTING

I hereby certify that the foregoing is a true copy of the Ordinance passed at the regular meeting of the City Council held on the _____ day of _____, 2017.

Frances McMullan, City Clerk

Notice Published: March 2, 2017

First Reading: March 21, 2017

Second Reading: _____

Published: _____

Effective Date: _____



Resolution No. 2017-061
March 21, 2017

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI that:

The public hearing on an ordinance entitled: "An ordinance to amend section 58-32 of the Ypsilanti City Code to add two youth non-voting members to the Human Relations Commission" be officially closed.

OFFERED BY: _____

SUPPORTED BY: _____

YES: NO: ABSENT: VOTE:



Resolution No. 2017- 062
March 21, 2017

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

That the following items be approved:

1. Resolution No. 2017-063, opposing elimination and reduction of US Department of Housing and Urban Development programs which are vital to Washtenaw County residents.
2. Resolution No. 2017-064, approving appointments to Boards and Commissions.
3. Resolution No. 2017-065, approving appointments to Boards and Commissions (non-residents).
4. Resolution No. 2017-066, approving minutes of January 24 and January 31, 2017.

OFFERED BY: _____

SUPPORTED BY: _____

YES:

NO:

ABSENT:

VOTE:



REQUEST FOR LEGISLATION
March 21, 2017

To: Mayor and Council

From: Beth Ernat, Community and Economic Development Director

Subject: A resolution opposing elimination and reduction of US Department of Housing and Urban Development programs which are vital to Washtenaw County residents

SUMMARY & BACKGROUND: On March 8th, staff received notice that the Washington Post reported significant cuts to the proposed HUD budget. The proposed budget includes:

- Cuts in funding for public housing repairs by \$1.3 billion or 68%.
- Cuts in funding for Housing Choice Vouchers by \$300 million, not including the additional resources that would be needed to cover inflationary costs. This is equal to 200,000 vouchers being lost.
- Cuts in funding that would result in about 12,000 homes for seniors and 6,000 homes for people with disabilities being lost.
- Eliminates Community Development Block Grant (CDBG).
- Eliminates HOME Investment Partnership Program.

As the City of Ypsilanti is a partner in the Washtenaw County "Urban County" program, we leverage Community Development Block Grant (CDBG) funds, HOME (HOME Investment Partnership Program), and Emergency Solutions Grant (ESG) funds as a County network. As reported by the County:

"This year, we received nearly \$3 million in CDBG, HOME and ESG funding:

•	(CDBG)	\$ 1,858,189
•	(HOME)	\$ 931,541
•	(ESG)	\$ 166,266
•	TOTAL	\$ 2,955,996

And even more importantly, these federal programs allow us to **leverage \$20 million or more annually** in additional funds for community projects and programs. The loss of these dollars will hurt local businesses, destabilize neighborhoods and limit access to critical human services for residents in need. "

These programs provide critical community infrastructure, neighborhood stabilization, human services, homelessness prevention, and affordable housing resources for Washtenaw County residents. The programs provided are barely sufficient to meet our needs as a community and a county. To lose any of this funding would be disastrous.

The CDBG funding we receive has been used to meet our legal settlement requirements for the sidewalk ramps. Loss of any of the CDBG funds would add a minimum of \$50,000 liability annually to our general fund.

Had it not been for the investment of HOME funds by the County, the YHC would not have been able to undertake the full demolition and replacement of the former Parkridge Homes public housing site. While tax credits provided most of the equity for the deal, there was still a significant need for gap funding. The YHC applied for, and successfully obtained, HOME funds in two separate funding rounds. In total, the County has invested \$915,000 of HOME funds in the New Parkridge redevelopment project and over \$40,000 in the Hamilton Crossing project.

RECOMMENDED ACTION: Staff recommends approval of the attached resolution and the distribution of the resolution to Washtenaw County, State of Michigan, and all elected representatives to the State and Federal legislative bodies.

ATTACHMENTS: Resolution

CITY MANAGER APPROVAL: _____

COUNCIL AGENDA DATE: 3/21/17

CITY MANAGER COMMENTS: _____

FISCAL SERVICES DIRECTOR APPROVAL: _____



RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

WHEREAS, On March 8, 2017, the Washington Post reported on proposed budget cuts to the U.S. Department of Housing and Urban Development (HUD); and

WHEREAS, among other significant cuts, the proposed HUD budget:

- Cuts funding for public housing repairs by \$1.3 billion or 68%.
- Cuts funding for Housing Choice Vouchers by \$300 million, not including the additional resources that would be needed to cover inflationary costs. This is equal to 200,000 vouchers being lost.
- Cuts funding that would result in about 12,000 homes for seniors and 6,000 homes for people with disabilities being lost.
- Eliminates Community Development Block Grant (CDBG).
- Eliminates HOME Investment Partnership Program.

WHEREAS, The Community Development Block Grant (CDBG) and HOME Investment Partnership (HOME) programs are operated in Washtenaw County by the Washtenaw County Office of Community and Economic Development; and

WHEREAS, Other programs such as the Emergency Solutions Grant (ESG) program could be at risk of elimination or significant cuts; and

WHEREAS, For FY 2017 alone, Washtenaw County received nearly \$3,000,000 in CDBG, HOME and ESG funding; and

WHEREAS, These federal programs allow Washtenaw County to leverage \$20 million or more annually in additional funds for community projects and programs; and

WHEREAS, CDBG, HOME and ESG programs provide critical community infrastructure, neighborhood stabilization, human services, homelessness prevention, and affordable housing resources for Washtenaw County residents; and their elimination would have disastrous impacts on quality of life for our neighborhoods and residents; and

WHEREAS, The Ypsilanti Public Housing Commission applied for and received approximately \$1 million in Home funds for the Parkridge redevelopment project and the Hamilton Crossing project; and

WHEREAS, The Parkridge redevelopment project and Hamilton Crossing redevelopment would not have happened but for County HOME funds; and

WHEREAS, The loss of public housing capital and operating funds will hasten the deterioration of existing public housing properties and potentially displace residents; and

WHEREAS, These reductions in funding will hurt local businesses, destabilize neighborhoods and limit access to critical human services for residents in need;

NOW THEREFORE BE IT RESOLVED BY THE CITY OF YPSILANTI that the Washtenaw County delegation to the United States Senate and United States House of Representatives should actively oppose this HUD budget unless funding for these vital programs is protected; and

BE IT FURTHER RESOLVED, Copies of this resolution shall be provided to U.S. Senators Debbie Stabenow and Gary Peters, U.S. Representatives Debbie Dingell and Tim Walberg, and Governor Rick Snyder.

OFFERED BY: _____

SUPPORTED BY: _____

YES: NO: ABSENT: VOTE:



Resolution No. 2017 - 064
March 21, 2017

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

THAT, the following individuals be appointed to the City of Ypsilanti Boards and Commissions as indicated below:

<u>NAME</u>	<u>BOARD</u>	<u>TERM EXPIRATION</u>
Kurt Kohlmann 326 Maple Ypsilanti, MI 48198	Parks & Recreation Commission	July 1, 2020
Ashanti Harris 305 E. Cross Ypsilanti, MI 48198	Parks & Recreation Commission	July 1, 2020
Ben Connor Barrie 1111 Westmoorland Ypsilanti, MI 48197	Parks & Recreation Commission	July 1, 2020
Emily Drennan 309 Middle Dr. Ypsilanti, MI 48197	Sustainability Commission	May 1, 2020
Nancy Heine 214 S. Washington St. Ypsilanti, MI 48197	Sustainability Commission	May 1, 2020
Natalie Sampson 703 Hemphill St. Ypsilanti, MI 48198	Sustainability Commission	May 1, 2020
Thomas McKee 408 N. Huron St. Ypsilanti, MI 48197	Sustainability Commission	May 1, 2019
Leah VanLandingham 113 Downing Ypsilanti, MI 48197	Sustainability Commission	May 1, 2019
Brett Zeuner 318 Oak St., #1 Ypsilanti, MI 48198	Sustainability Commission	May 1, 2019

Julie Bayha
401 W. Michigan Ave., #614
Ypsilanti, MI 48197

Sustainability Commission

May 1, 2018

Keith Michalowski
410 Maple
Ypsilanti, MI 48198(1 year term)

Sustainability Commission

May 1, 2018

OFFERED BY: _____

SUPPORTED BY: _____

YES: NO: ABSENT: VOTE:



Resolution No. 2017 - 065
March 21, 2017

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

THAT, the following individuals (non-residents) be appointed to the City of Ypsilanti Boards and Commissions as indicated below:

<u>NAME</u>	<u>BOARD</u>	<u>TERM EXPIRATION</u>
Thomas Kovacs 4647 Nutmeg Dr. Ypsilanti, MI 48197	Sustainability Commission	May 1, 2018
Deiter Otto, EMU Representative EMU Director of Grounds and Custodial 200 Boone Hall Ypsilanti, MI 48197	DDA	N/A

OFFERED BY: _____

SUPPORTED BY: _____

YES: NO: ABSENT: VOTE:

Print**Citizen Advisory Boards and Commissions Participation Resume - Submission #217****Date Submitted: 1/19/2017**

The people of Ypsilanti are involved in their City government and are an important part of the community's achievements. Individuals interested in receiving more information in regards to serving on an advisory board or commission are invited to contact the City Clerk's Office at 734-483-1100. Alternatively, citizens who would like to participate can submit their information in the form below.

Name*

Kurt Kohlmann

Email Address*

Kurtkohlmann@gmail.com

Address

326 Maple St.

City

Ypsilanti

State

MI

Zip Code

48198

Phone Number*

419-936-0488

Fax Number**Number of Years in the Community**

3.5

Ward You Live In

3

Education

Masters in Social Work

Occupation

Social Worker

Employer

Starfish Family Services

I would like to be considered and could devote sufficient time to serve on the following board or commission:

- | | | |
|---|--|---|
| ☐ Board of Review | ☐ Economic Development Corporation/Brownfield Redevelopment Authority | ☐ Property Maintenance Construction Board of Appeals |
| ☐ Board of Ethics | ☐ Historic District Commission | ☒ Parks and Recreation Commission |
| ☐ Civil Service Commission | ☐ Housing Commission | ☐ Ann Arbor Transit Authority |
| ☐ YCUA | ☐ Human Relations Commission | ☐ Police and Fire Pension Board |
| ☐ Ypsilanti Downtown Development Authority | ☐ Planning Commission | ☐ Sustainability Commission |

Why are you interested in serving on these boards/commissions?*

I've been interested in community development for most of my adult life, and believe recreational opportunities have the ability to transcend economic barriers in bringing communities together.

Work/volunteer experience related to the board or commission:

I've spent the past 7 years in youth and community development.

I understand that appointment to a City of Ypsilanti board or commission requires regular attendance at board meetings.

☒ Yes

I hereby certify that all of the information above is true.

☒ Yes



FORM CENTER

[VIEW SITE](#)

MAIN

FIELD SETS

LEGACY FORMS

PROPERTIES

BACK

PRINT

Form Center ► Boards & Commissions ► Citizen Advisory Boards and Commissions Participation Resume ► Submission #218

The people of Ypsilanti are involved in their City government and are an important part of the community's achievements. Individuals interested in receiving more information in regards to serving on an advisory board or commission are invited to contact the City Clerk's Office at 734-483-1100. Alternatively, citizens who would like to participate can submit their information in the form below.

Name *

Ashanti Harris

Email Address *

ashantih@umich.edu

Address

305

City

Ypsilanti

State

MI

Zip Code

48198

Phone Number *

7344762428

Fax Number

Number of Years in the Community

Ward You Live In

[SAVE CHANGES](#)[CANCEL](#)Form
Details

Submitted By:

Ashanti Harris

Submitted On:

January 20, 2017 9:30 AM

IP Address:

141.211.32.5

Referrer:

[http://cityofypsilanti.com/FormCent...](http://cityofypsilanti.com/FormCenter/Commissions-6/Citizen-Advisory-Boards-and-Commissions--45)
Commissions-6/Citizen-Advisory-
Boards-and-Commissions--45

Answered 16 of 18 (88.9%)



HOMEPAGE



DASHBOARD



MODULES



ANDREW H

HELP

Education

In Progress of completing graduate work

Occupation

Meeting and Event Manager

Employer

University of Michigan

I would like to be considered and could devote sufficient time to serve on the following board or commission:

Board of Review	Economic Development	Property Maintenance Construction
Board of Ethics	Corporation/Brownfield	Board of Appeals
Civil Service Commission	Redevelopment Authority	Parks and Recreation Commission
YCUA	Historic District Commission	Ann Arbor Transit Authority
Ypsilanti Downtown Development Authority	Housing Commission	Police and Fire Pension Board
	Human Relations Commission	Sustainability Commission
	Planning Commission	

Why are you interested in serving on these boards/commissions? *

I understand the importance of having recreation activities available in our community parks accessible for all residents. I want to take part in being sure the parks have activities that are educational, fun, relevant in a clean and safe environment. The goal would be that residents think of our parks and programming first.

Work/volunteer experience related to the board or commission:



HOMEPAGE



DASHBOARD



MODULES



ANDREW H

HELP

for two years. I have volunteered staffing registration stations for various local running events. I was a volunteer coach for Girls on the Run of Southeastern Michigan for seven years which brought me great joy as I watched girls grow throughout the season as they spent time rain or shine being active and learning. I hold certifications in Meeting Management and am a Certified Tourism Ambassador through the Ann Arbor-Ypsilanti Area Tourism Ambassador Program. My undergraduate degree was in Recreation and Park Management. I am in the process of finishing my graduate degree in Hotel and Restaurant Management.

I understand that appointment to a City of Ypsilanti board or commission requires regular attendance at board meetings.

Yes

I hereby certify that all of the information above is true.

Yes

This site is powered by [CivicPlus](#) Rev: 5.0.65150

For assistance, please [visit our support site](#)

Learn more about the [CivicPlus Service](#)

Print**Citizen Advisory Boards and Commissions Participation Resume - Submission #223****Date Submitted: 1/24/2017**

The people of Ypsilanti are involved in their City government and are an important part of the community's achievements. Individuals interested in receiving more information in regards to serving on an advisory board or commission are invited to contact the City Clerk's Office at 734-483-1100. Alternatively, citizens who would like to participate can submit their information in the form below.

Name*

Benjamin Connor Barrie

Email Address*

ben.connorbarrie@gmail.com

Address

1111 Westmoorland

City

Ypsilanti

State

Mi

Zip Code

48197

Phone Number*

7342559562

Fax Number**Number of Years in the Community**

3

Ward You Live In

2

Education

MS Ecology, University of Michigan

Occupation

Lecturer

Employer

Eastern Michigan

I would like to be considered and could devote sufficient time to serve on the following board or commission:

- | | | |
|---|--|---|
| ☐ Board of Review | ☐ Economic Development Corporation/Brownfield Redevelopment Authority | ☐ Property Maintenance Construction Board of Appeals |
| ☐ Board of Ethics | ☐ Historic District Commission | ☒ Parks and Recreation Commission |
| ☐ Civil Service Commission | ☐ Housing Commission | ☐ Ann Arbor Transit Authority |
| ☐ YCUA | ☐ Human Relations Commission | ☐ Police and Fire Pension Board |
| ☐ Ypsilanti Downtown Development Authority | ☐ Planning Commission | ☐ Sustainability Commission |

Why are you interested in serving on these boards/commissions?*

I am passionate about urban green spaces and the benefits they bring to the community.

Work/volunteer experience related to the board or commission:

For my graduate research I studied natural areas in urban environment and how the urban environment shapes their regeneration. In addition to my research I also work with groups managing urban parks to advise them on how to maximize biodiversity.

I understand that appointment to a City of Ypsilanti board or commission requires regular attendance at board meetings.

☒ Yes

I hereby certify that all of the information above is true.

☒ Yes

Print**Citizen Advisory Boards and Commissions Participation Resume - Submission #213****Date Submitted: 1/18/2017**

The people of Ypsilanti are involved in their City government and are an important part of the community's achievements. Individuals interested in receiving more information in regards to serving on an advisory board or commission are invited to contact the City Clerk's Office at 734-483-1100. Alternatively, citizens who would like to participate can submit their information in the form below.

Name*

Emily Drennen

Email Address*

redheadresist@gmail.com

Address

309 Middle Drive

City

Ypsilanti

State

MI

Zip Code

48197

Phone Number*

4153749556

Fax Number**Number of Years in the Community**

1

Ward You Live In

3

Education

Master's of Public Administration

Occupation

Sustainability Associate

Employer

City of Ann Arbor

I would like to be considered and could devote sufficient time to serve on the following board or commission:

- | | | |
|---|--|---|
| ☐ Board of Review | ☐ Economic Development Corporation/Brownfield Redevelopment Authority | ☐ Property Maintenance Construction Board of Appeals |
| ☐ Board of Ethics | ☐ Historic District Commission | ☐ Parks and Recreation Commission |
| ☐ Civil Service Commission | ☐ Housing Commission | ☐ Ann Arbor Transit Authority |
| ☐ YCUA | ☐ Human Relations Commission | ☐ Police and Fire Pension Board |
| ☐ Ypsilanti Downtown Development Authority | ☐ Planning Commission | ☒ Sustainability Commission |

Why are you interested in serving on these boards/commissions?*

For my day job, I work hard to make the City of Ann Arbor as "green" as it can be. I very much want to take some of my skills and enthusiasm to greening the wonderful town I live in.

Work/volunteer experience related to the board or commission:

see email sent to the Mayor

I understand that appointment to a City of Ypsilanti board or commission requires regular attendance at board meetings.

☒ Yes

I hereby certify that all of the information above is true.

☒ Yes

Print**Citizen Advisory Boards and Commissions Participation Resume - Submission #224****Date Submitted: 1/25/2017**

The people of Ypsilanti are involved in their City government and are an important part of the community's achievements. Individuals interested in receiving more information in regards to serving on an advisory board or commission are invited to contact the City Clerk's Office at 734-483-1100. Alternatively, citizens who would like to participate can submit their information in the form below.

Name*

Nancy Heine

Email Address*

heinen567@gmail.com

Address

214 S. Washington St.

City

Ypsilanti

State

Mich

Zip Code

48197

Phone Number*

734-482-2840 or 734-262-1296 - cell

Fax Number**Number of Years in the Community**

30+

Ward You Live In

1

Education

Bachelors in Human Resource Admin.

Occupation

Office Support Supervisor

Employer

Washtenaw County Community Mental Health

I would like to be considered and could devote sufficient time to serve on the following board or commission:

- | | | |
|---|--|---|
| ☐ Board of Review | ☐ Economic Development Corporation/Brownfield Redevelopment Authority | ☐ Property Maintenance Construction Board of Appeals |
| ☐ Board of Ethics | ☐ Historic District Commission | ☐ Parks and Recreation Commission |
| ☐ Civil Service Commission | ☐ Housing Commission | ☐ Ann Arbor Transit Authority |
| ☐ YCUA | ☐ Human Relations Commission | ☐ Police and Fire Pension Board |
| ☐ Ypsilanti Downtown Development Authority | ☐ Planning Commission | ☒ Sustainability Commission |

Why are you interested in serving on these boards/commissions?*

Vested interest as a long time City of Ypsilanti resident. Am interested in the future of our community to create a vision of environmentally sound policies and cultivate a clearer understanding of why it is so important to sustain them.

Work/volunteer experience related to the board or commission:

Live and work right in the City of Ypsilanti. VP of the Huron Valley Area Labor Federation. As well as a labor official at Washtenaw County. These are issues that are often discussed within these circles and we often weigh in on and offer opinions/recommendations of support. Huron Valley Area Labor Federation (HVALF) encompasses a wide support area.

I understand that appointment to a City of Ypsilanti board or commission requires regular attendance at board meetings.

☒ Yes

I hereby certify that all of the information above is true.

☒ Yes

Print**Citizen Advisory Boards and Commissions Participation Resume - Submission #235****Date Submitted: 1/27/2017**

The people of Ypsilanti are involved in their City government and are an important part of the community's achievements. Individuals interested in receiving more information in regards to serving on an advisory board or commission are invited to contact the City Clerk's Office at 734-483-1100. Alternatively, citizens who would like to participate can submit their information in the form below.

Name*

Natalie Sampson

Email Address*

nrsampson@gmail.com

Address

703 Hemphill St

City

Ypsilanti

State

MI

Zip Code

48198

Phone Number*

2487677149

Fax Number**Number of Years in the Community**

6 months

Ward You Live In

3

Education

PhD, MPH

Occupation

Assistant Professor of Public Health

Employer

U of M-Dearborn

I would like to be considered and could devote sufficient time to serve on the following board or commission:

- | | | |
|---|--|---|
| ☐ Board of Review | ☐ Economic Development Corporation/Brownfield Redevelopment Authority | ☐ Property Maintenance Construction Board of Appeals |
| ☐ Board of Ethics | ☐ Historic District Commission | ☐ Parks and Recreation Commission |
| ☐ Civil Service Commission | ☐ Housing Commission | ☐ Ann Arbor Transit Authority |
| ☐ YCUA | ☐ Human Relations Commission | ☐ Police and Fire Pension Board |
| ☐ Ypsilanti Downtown Development Authority | ☐ Planning Commission | ☒ Sustainability Commission |

Why are you interested in serving on these boards/commissions?*

As new residents of Ypsilanti, our family is looking to engage more deeply in our community. I am a scholar that works on issues largely related to the health implications of land use issues. I am engaged nationally and in Detroit but would like to engage in my own hometown. The Sustainability Commission seems like an appropriate way to do so while maximizing my skills.

Work/volunteer experience related to the board or commission:

Some of my most related experience:

- I have served on the Steering Committee & led the Public Health workgroup for the Detroit Climate Action Collaborative: <http://www.detroitclimateaction.org/>
- I do applied research related to green infrastructure in Detroit: <http://graham.umich.edu/water/news/Nassauer>
- I partner with the MDHHS in various ways as they implement their work as a CDC Climate Ready State: http://www.michigan.gov/mdhhs/0,5885,7-339-71548_54783_54784_55975--,00.html

I understand that appointment to a City of Ypsilanti board or commission requires regular attendance at board meetings.

☒ Yes

I hereby certify that all of the information above is true.

☒ Yes

Print**Citizen Advisory Boards and Commissions Participation Resume - Submission #227****Date Submitted: 1/26/2017**

The people of Ypsilanti are involved in their City government and are an important part of the community's achievements. Individuals interested in receiving more information in regards to serving on an advisory board or commission are invited to contact the City Clerk's Office at 734-483-1100. Alternatively, citizens who would like to participate can submit their information in the form below.

Name*

Thomas McKee

Email Address*

mckeetho@umich.edu

Address

408 N Huron St

City

Ypsilanti

State

MI

Zip Code

48197

Phone Number*

7345450948

Fax Number**Number of Years in the Community**

2

Ward You Live In

3

Education

Pursuing BS in Architecture

Occupation

Retail Sales

Employer

Plum Market

I would like to be considered and could devote sufficient time to serve on the following board or commission:

- | | | |
|---|--|---|
| ☐ Board of Review | ☐ Economic Development Corporation/Brownfield Redevelopment Authority | ☐ Property Maintenance Construction Board of Appeals |
| ☐ Board of Ethics | ☐ Historic District Commission | ☐ Parks and Recreation Commission |
| ☐ Civil Service Commission | ☐ Housing Commission | ☐ Ann Arbor Transit Authority |
| ☐ YCUA | ☐ Human Relations Commission | ☐ Police and Fire Pension Board |
| ☐ Ypsilanti Downtown Development Authority | ☐ Planning Commission | ☒ Sustainability Commission |

Why are you interested in serving on these boards/commissions?*

I believe strongly that local government can pursue outcomes that increase the sustainability of our communities. I am interested in a broad definition of sustainability, that includes environmental, economic, equity, and aesthetic goals for the future of our city. I believe that addressing sustainability will help with other issues facing the community as well.

Work/volunteer experience related to the board or commission:

I understand that appointment to a City of Ypsilanti board or commission requires regular attendance at board meetings.

☒ Yes

I hereby certify that all of the information above is true.

☒ Yes

Print**Citizen Advisory Boards and Commissions Participation Resume - Submission #230****Date Submitted: 1/26/2017**

The people of Ypsilanti are involved in their City government and are an important part of the community's achievements. Individuals interested in receiving more information in regards to serving on an advisory board or commission are invited to contact the City Clerk's Office at 734-483-1100. Alternatively, citizens who would like to participate can submit their information in the form below.

Name*

Leah VanLandingham

Email Address*

Ivanland@emich.edu

Address

113 Downing Hall

City

Ypsilanti

State

MI

Zip Code

48197

Phone Number*

7346242439

Fax Number**Number of Years in the Community**

2

Ward You Live In

3

Education

Eastern Michigan University

Occupation

Director of Sustainability

Employer

Eastern Michigan University Student Government**I would like to be considered and could devote sufficient time to serve on the following board or commission:**

- | | | |
|---|--|---|
| ☐ Board of Review | ☐ Economic Development Corporation/Brownfield Redevelopment Authority | ☐ Property Maintenance Construction Board of Appeals |
| ☐ Board of Ethics | ☐ Historic District Commission | ☐ Parks and Recreation Commission |
| ☐ Civil Service Commission | ☐ Housing Commission | ☐ Ann Arbor Transit Authority |
| ☐ YCUA | ☐ Human Relations Commission | ☐ Police and Fire Pension Board |
| ☐ Ypsilanti Downtown Development Authority | ☐ Planning Commission | ☒ Sustainability Commission |

Why are you interested in serving on these boards/commissions?*

I am currently the student Director of Sustainability at Eastern Michigan University. My job is focused around promoting and implementing sustainability related policies and procedures at EMU, as well as being the Director of the Energy and Sustainability Commission here at EMU. My work so far has been only at EMU, but I want to get involved in the Ypsilanti community and aid in promoting sustainability not only at EMU but in the community as a whole. Community collaboration and developing a strong relationship between EMU and Ypsilanti is the most effective way for combating sustainability related issues in our community as well as promoting community wide sustainable practices in the future. I am extremely passionate about sustainability and have committed my studies to learning about how to promote sustainability. I am an Environmental Science major as well as minoring in leadership and sustainability. I also studied sustainability abroad in Peru. These disciplines have aided me in not only learning about the political aspect and importance of sustainability, but as well as the science behind sustainable changes. I feel as though I would be a suitable member on the Ypsilanti Sustainability Commission and would be able to carry out and promote the mission of the commission in an active and meaningful way.

Work/volunteer experience related to the board or commission:

Student Government Director of Sustainability at Eastern Michigan University
Director of the Student Government Energy and Sustainability Commission
Environmental Science major with minors in Leadership and Sustainability

I understand that appointment to a City of Ypsilanti board or commission requires regular attendance at board meetings.

☒ Yes

I hereby certify that all of the information above is true.

☒ Yes

Print**Citizen Advisory Boards and Commissions Participation Resume - Submission #242****Date Submitted: 2/1/2017**

The people of Ypsilanti are involved in their City government and are an important part of the community's achievements. Individuals interested in receiving more information in regards to serving on an advisory board or commission are invited to contact the City Clerk's Office at 734-483-1100. Alternatively, citizens who would like to participate can submit their information in the form below.

Name*

Brett Zeuner

Email Address*

bzeuner@emich.edu

Address

318 Oak Street APT #1

City

Ypsilanti

State

Michigan

Zip Code

48198

Phone Number*

7345602436

Fax Number**Number of Years in the Community**

3.5

Ward You Live In

6

Education

Bachelor's of Science, Sociology, Eastern Michigan University (exp. 4/17) and an applicant for Master's of Science in Natural Resources and Environment from University of Michigan 2017

Occupation

Research fellow

Employer

Greater Research Opportunities Fellowship Program, Environmental Protection Agency

I would like to be considered and could devote sufficient time to serve on the following board or commission:

- | | | |
|---|--|---|
| ☐ Board of Review | ☐ Economic Development Corporation/Brownfield Redevelopment Authority | ☐ Property Maintenance Construction Board of Appeals |
| ☐ Board of Ethics | ☐ Historic District Commission | ☐ Parks and Recreation Commission |
| ☐ Civil Service Commission | ☐ Housing Commission | ☐ Ann Arbor Transit Authority |
| ☐ YCUA | ☐ Human Relations Commission | ☐ Police and Fire Pension Board |
| ☐ Ypsilanti Downtown Development Authority | ☐ Planning Commission | ☒ Sustainability Commission |

Why are you interested in serving on these boards/commissions?*

I am interested in serving on the Sustainability Commission to help Ypsilanti solve its pressing sustainability issues while also helping the city to be progressive and proactive in developing solutions to emerging sustainability initiatives. I have wanted to get involved in local government, especially following the most recent election cycle and the perceived breakdown in efficacy of the federal government. Additionally, protecting our resources as a community in Michigan is extremely important to me.

Work/volunteer experience related to the board or commission:

Since becoming a research fellow through the EPA's GRO program I have learned a lot about environmental regulation, specifically in regard to drinking water. My current research project is focused on how residents in a Ypsilanti neighborhood perceive environmental contamination. Additionally, as part of the fellowship I spent a Summer in San Francisco, CA working at a regional EPA headquarters in the office of drinking water management. I have also worked on a soil contamination research project at Wayne State University as a research assistant in the Summer of 2015. My role in that study was to survey and interview community garden managers about their perceptions of soil contamination.

I understand that appointment to a City of Ypsilanti board or commission requires regular attendance at board meetings.

☒ Yes

I hereby certify that all of the information above is true.

☒ Yes

Print**Citizen Advisory Boards and Commissions Participation Resume - Submission #250****Date Submitted: 3/1/2017**

The people of Ypsilanti are involved in their City government and are an important part of the community's achievements. Individuals interested in receiving more information in regards to serving on an advisory board or commission are invited to contact the City Clerk's Office at 734-483-1100. Alternatively, citizens who would like to participate can submit their information in the form below.

Name*

Julia Bayha

Email Address*

juliabayha@gmail.com

Address

401 W. Michigan Ave. #614

City

Ypsilanti

State

MI

Zip Code

48197

Phone Number*

734-945-2739

Fax Number**Number of Years in the Community**

off and on for over 30 years

Ward You Live In**Education**

AAHSS from WCC [2000] & B.Sc. Literature, Language & Writing from EMU [2011]

Occupation

Education & Activism

Employer

n/a

I would like to be considered and could devote sufficient time to serve on the following board or commission:

- | | | |
|--|---|---|
| ☐ Review and Tax Assessment Board | ☐ Historic District Commission | ☐ Property Maintenance Construction Board of Appeals |
| ☐ Board of Ethics | ☐ Ypsilanti Housing Commission | ☐ Parks and Recreation Commission |
| ☐ Fire Civil Service Commission | ☐ Human Relations Commission | ☐ Ann Arbor Area Transit Authority |
| ☐ YCUA | ☐ Sidewalk Review Board | ☐ Police and Fire Pension Board |
| ☐ Ypsilanti Downtown Development Authority | ☐ Planning Commission | ☐ Huron River Watershed Council |
| ☐ Economic Development Corporation/Brownfield Redevelopment Authority | ☐ Non-motorized Advisory Committee | ☒ Sustainability Commission |

Why are you interested in serving on these boards/commissions?*

I am interested in serving on the Sustainability Commission because without sustainability, no other endeavor is even possible to maintain. I am also interested because I believe in thinking global and acting local, while working to create mutually beneficial working relationships among cities and townships across whole regions. I cannot expect someone else to do this and to do nothing myself. I believe that a strong and sustainable community is only possible with a high degree of citizen participation, so here I am!

Work/volunteer experience related to the board or commission:

Over 40 years of learning, living, teaching & being green, working on social justice issues, creating rapport in various diverse communities, and working on projects small and large including fund-raising events and educational efforts.

I understand that appointment to a City of Ypsilanti board or commission requires regular attendance at board meetings.☒ Yes**I hereby certify that all of the information above is true.**☒ Yes

Print**Citizen Advisory Boards and Commissions Participation Resume - Submission #236****Date Submitted: 1/27/2017**

The people of Ypsilanti are involved in their City government and are an important part of the community's achievements. Individuals interested in receiving more information in regards to serving on an advisory board or commission are invited to contact the City Clerk's Office at 734-483-1100. Alternatively, citizens who would like to participate can submit their information in the form below.

Name*

Keith Michalowski

Email Address*

kmichalowski@gmail.com

Address

410

City

Ypsilanti

State

MI

Zip Code

48198

Phone Number*

7342174554

Fax Number**Number of Years in the Community**

20

Ward You Live In

Ward: 3, Precinct: 3

Education

Some college

Occupation

Hardware Engineer

Employer

Drew Technologies, Inc.

I would like to be considered and could devote sufficient time to serve on the following board or commission:

- | | | |
|---|--|---|
| ☐ Board of Review | ☐ Economic Development Corporation/Brownfield Redevelopment Authority | ☐ Property Maintenance Construction Board of Appeals |
| ☐ Board of Ethics | ☐ Historic District Commission | ☐ Parks and Recreation Commission |
| ☐ Civil Service Commission | ☐ Housing Commission | ☐ Ann Arbor Transit Authority |
| ☐ YCUA | ☐ Human Relations Commission | ☐ Police and Fire Pension Board |
| ☐ Ypsilanti Downtown Development Authority | ☐ Planning Commission | ☒ Sustainability Commission |

Why are you interested in serving on these boards/commissions?*

I have a sincere desire to make the world a better place. I am extremely political. I am a avid supporter of clean energy and preservation of nature. I feel my diverse skill set would be applied well to government. Bottom line, I want to make a difference and feel strongly that this would be a great first step in that direction.

Work/volunteer experience related to the board or commission:

No previous experience

I understand that appointment to a City of Ypsilanti board or commission requires regular attendance at board meetings.

☒ Yes

I hereby certify that all of the information above is true.

☒ Yes



Resolution No. 2017 - 065
March 21, 2017

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

THAT, the following individuals (non-residents) be appointed to the City of Ypsilanti Boards and Commissions as indicated below:

<u>NAME</u>	<u>BOARD</u>	<u>TERM EXPIRATION</u>
Thomas Kovacs 4647 Nutmeg Dr. Ypsilanti, MI 48197	Sustainability Commission	May 1, 2018
Deiter Otto, EMU Representative EMU Director of Grounds and Custodial 200 Boone Hall Ypsilanti, MI 48197	DDA	N/A

OFFERED BY: _____

SUPPORTED BY: _____

YES: NO: ABSENT: VOTE: _____

Print**Citizen Advisory Boards and Commissions Participation Resume - Submission #229****Date Submitted: 1/26/2017**

The people of Ypsilanti are involved in their City government and are an important part of the community's achievements. Individuals interested in receiving more information in regards to serving on an advisory board or commission are invited to contact the City Clerk's Office at 734-483-1100. Alternatively, citizens who would like to participate can submit their information in the form below.

Name*

Thomas Kovacs

Email Address*

tkovacs@emich.edu

Address

203 Strong Hall

City

Ypsilanti

State

Michigan

Zip Code

48197

Phone Number*

734-487-8591

Fax Number**Number of Years in the Community**

10

Ward You Live In

Pittsfield Township (not sure of the ward)

Education

PhD Meteorology

Occupation

Professor and Chair of the Environmental Science and Society, Interdisciplinary program

Employer

Eastern Michigan University

I would like to be considered and could devote sufficient time to serve on the following board or commission:

- | | | |
|---|--|---|
| ☐ Board of Review | ☐ Economic Development Corporation/Brownfield Redevelopment Authority | ☐ Property Maintenance Construction Board of Appeals |
| ☐ Board of Ethics | ☐ Historic District Commission | ☐ Parks and Recreation Commission |
| ☐ Civil Service Commission | ☐ Housing Commission | ☐ Ann Arbor Transit Authority |
| ☐ YCUA | ☐ Human Relations Commission | ☐ Police and Fire Pension Board |
| ☐ Ypsilanti Downtown Development Authority | ☐ Planning Commission | ☒ Sustainability Commission |

Why are you interested in serving on these boards/commissions?*

Sustainability is important to me and to the students in the academic program that I chair. I continually push for Sustainability at Eastern Michigan University including efforts to ban the use of toxic chemicals while finding more economical solutions, participating in dialogue on environmental issues with and seek opportunities for citizens that typically cannot participate in sustainable efforts, but would mostly benefit from them, and supporting sustainability efforts of our students and faculty.

Work/volunteer experience related to the board or commission:

Chair and co-founder of the Environmental Science and Society, Interdisciplinary academic program at Eastern Michigan University, which also includes a Sustainability minor; Advisory committee for a United States Environmental Protection Agency-funded project on water quality research and education at post-secondary academic institutions in the state of Michigan; Planning committee for the Water Quality Day event in Roscommon, MI on October 9, 2015. University Corporation for Atmospheric Research (UCAR) and the United Nations Foundation participant in the Climate Voices Science Speakers Network. I was also awarded the College of Arts and Sciences Dean's Program Development Initiative entitled, "Sustainability contest to develop the IEES program and sustainability at EMU.

I understand that appointment to a City of Ypsilanti board or commission requires regular attendance at board meetings.

☒ Yes

I hereby certify that all of the information above is true.

☒ Yes



Resolution No. 2017-066
March 21, 2017

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

THAT the minutes of January 24 and January 31, 2017 be approved.

OFFERED BY: _____

SUPPORTED BY: _____

YES:

NO:

ABSENT:

VOTE:



Draft

**CITY OF YPSILANTI
REGULAR COUNCIL MEETING
CITY COUNCIL CHAMBERS – ONE SOUTH HURON ST.
YPSILANTI, MI 48197
TUESDAY, JANUARY 24, 2017
7:00 p.m.**

I. CALL TO ORDER –

The meeting was called to order at 7:03 p.m.

II. ROLL CALL –

Council Member Bashert	Present	Council Member Robb	Present
Mayor Pro-Tem Brown	Present	Council Member Vogt	Present
Council Member Murdock	Present	Mayor Edmonds	Present
Council Member Richardson	Present		

III. INVOCATION –

Mayor Edmonds asked all to stand for a moment of silence.

IV. PLEDGE OF ALLEGIANCE –

"I pledge allegiance to the flag, of the United States of America, and to the Republic for which it stands, one nation, under God, indivisible, with liberty and justice for all."

V. AGENDA APPROVAL –

Mayor Pro-Tem Brown moved, Council Member Bashert seconded to approve the agenda.

Council Member Robb moved to remove Resolution No. 2017-023 from the Consent Agenda, and move to Resolution/Motions/Discussions.

On a voice vote, the motion carried, and the agenda was approved as amended.

VI. PRESENTATIONS –

— Resolution No. 2017-001, supporting the "Don't Stand Idly By" campaign.

Mayor Edmonds introduced John Weiss and Rabbi Josh Whinston.

John Weiss spoke in support of the "Don't Stand Idly By" campaign. He said this is a common sense method to address gun violence. The companies that manufacture and distribute firearms have the ability to take action to reduce the incidents of gun related crimes and accidental shootings in the United States. These include improvements and innovation in technology and more accountable distribution methods. This resolution would add the City of Ypsilanti to the list of over 100 municipalities from across the country that are asking gun manufacturers about what steps they are taking to improve distribution practices and the development of new safety technologies. There is hope that if enough

municipalities sign on that gun manufacturers will become more accountable with their distribution practices and invest more in creating safety technology.

Rabbi Whinston stated the resolution is also intended to protect police officers by reducing the amount of black market guns on the streets. With the expectation that gun manufactures in the United States are taking care of their weapons from shipment to arrival at retail locations. The resolution is an important first step in Michigan and thanked Council for showing leadership for this issue.

WHEREAS more than 33,000 people per year in the United States have been killed with firearms in recent years; and

WHEREAS a resident of the United States is 25 times as likely to be murdered with a gun than is a resident of other advanced nations; and

WHEREAS Americans from across the political spectrum agree that our nation should strive to reduce the number of our neighbors who are killed or injured with firearms or terrorized by gun-related crime; and

WHEREAS the companies that manufacture and distribute firearms have the ability to take actions that will reduce the incidence of gun-related crimes and accidental shootings in the United States; and

WHEREAS these actions – including improvements and innovations in gun-safety technologies and distribution practices – can be taken voluntarily by these companies and without the slightest harm to the established rights of Americans to own and use firearms; and

WHEREAS in a growing number of municipalities, counties and states across the nation – more than 100 jurisdictions to date – public officials and law enforcement leaders have taken steps to initiate dialogue with leading gun manufacturers about these actions; and

WHEREAS these public-sector leaders and their jurisdictions are customers of the gun industry, purchasing firearms for the purpose of equipping law enforcement officers in order to protect public safety; and

WHEREAS the public sector collectively represents a significant share of the marketplace for guns and ammunition in the United States; and

WHEREAS religious and civic leaders, public officials and law enforcement officials across the nation have created the “Do Not Stand Idly By” campaign to use the collective purchasing power of the public sector to encourage life-saving innovation in the gun industry; now, therefore,

BE IT RESOLVED that the City Council of the City of Ypsilanti call upon the Mayor Amanda Edmonds and Police Chief DeGiusti to participate in this nationwide effort by taking the following actions:

- **Adding their names, as representatives of the City of Ypsilanti, to the Request for Information being submitted to leading firearms manufacturers from more than 100 public-sector jurisdictions seeking information about the companies' gun-safety technologies and distribution practices.**
- **Taking additional steps as they see fit to encourage leadership within the gun industry in the improvement of distribution practices and the development of new safety technologies, such as:**
 - **Testing and evaluating existing gun-safety technologies – including “smart guns” – as well as new technologies as they become available.**
 - **Developing purchasing practices and specifications that maximize the public safety benefits achieved through [the City’s] firearms purchases.**
 - **Collaborating with peers in other jurisdictions in these efforts.**

BE IT FURTHER RESOLVED that we call upon the leaders of the gun manufacturers that receive the Request for Information from the City of Ypsilanti and other jurisdictions across the United States to respond in writing to the “Do Not Stand Idly By” campaign and participating jurisdictions.

BE IT FURTHER RESOLVED that suitable copies of this resolution be presented to the chief executive officers of Glock, SIG Sauer, Beretta, Smith & Wesson, Colt, Remington, and Sturm, Ruger & Co.

OFFERED BY: Mayor Pro-Tem Brown
 SECONDED BY: Council Member Vogt

Mayor Edmonds thanked Mr. Weiss and Rabbi Whinston for bringing this resolution to the attention of Council and is happy to be a sign on to this campaign.

On a roll call, the vote to approve Resolution No. 2017-001 was as follows:

Mayor Pro-Tem Brown	Yes	Council Member Robb	Yes
Council Member Murdock	Yes	Mayor Edmonds	Yes
Council Member Richardson	Yes	Council Member Vogt	Yes
Council Member Bashert	Yes		

VOTE:

YES: 7 NO: 0 ABSENT: 0 VOTE: Carried

VII. INTRODUCTIONS –

Mayor Edmonds introduced the following individuals; Interim City Manager Frances McMullan, Interim City Clerk Andrew Hellenga, City Attorney John Barr, Fire Chief Max Anthouard, City Planner Bonnie Wessler, Economic Development Director Beth Ernat, Police Chief Tony DeGiusti, and Community Development Manager/DDA Director Joe Meyers.

VIII. AUDIENCE PARTICIPATION –

1. Carole Clare, 324 Garland, stated she is the former City Assessor for Ypsilanti until 2006. In 2005 Joseph Golder requested aerial photos of his property, and since then she has been working with him to address the taking of his property. In 2014 she and Mr. Golder met with the City Manager and the City Attorney. At that meeting the City Manager called the claim frivolous and the City Manager agreed to meet with her later but never returned her phone calls. She distributed documents for Council to review and hope they consider this serious matter.
2. Lawrence Wartley, 423 S. Huron, stated last summer the previous City Manager threatened legal action against him, without due process. The action has made it difficult to sell his property and he has tried to determine the status of that issue. He said there was a civil rights investigation in which it was discovered the actions taken against him were discriminatory. He asked if his property, or himself still under conviction without being allowed due process.
3. Lilly Ellis, 760 Jenness, stated many people are here to speak about the Don't Ask Immigration Ordinance, but she would also like to voice her support for the Black Lives Matter Task Force Resolution to develop a Community Police Review Board.
4. Libby Hunter, 827 Bruce, Ann Arbor, stated she has three topics to discuss. She brought to the attention of an article written by the ACLU about Muskegon joining a nationwide push for community control over police surveillance. She asked for an update regarding Radical Washtenaw's report about bench warrant arrests in Ypsilanti. She said Radical Washtenaw received a response from Chief DeGiusti stating, "if you want to reduce bench warrants increase the money bond so individuals cannot be released before their court date". She said the response is cynical and heinous, and the department of justice has stated that practice is unconstitutional. The last point is recently there was a SWAT team shooting recently and the public has been given very little information regarding the incident.
5. Joseph Golder, 1002 Washtenaw, stated his property was illegally taken five years ago and since he has been lied to, bullied, intimidated, and treated like a second class home owner and human. He asked when Council will standup and honor the rights guaranteed to him by the US Constitution. He asked that Council vote tonight to have a real survey completed to uncover the misuse of the 1999 Michigan Institution Road Fund Grant and the 2011 Congestion Mitigation Air Quality Grant. He requested an independent investigation into the illegal taking of his property, tampering of public records, the withholding of FOIAed documents, grant fraud, questionable actions by the City and EMU, and anything else that could be uncovered. If Council does not follow through it does not fairly represent all residents of Ypsilanti. He was told to get an attorney, which would cause him to go bankrupt in order to have his rights served. He asked if the City would tell immigrants, minorities, LGBTQ, or individuals with disabilities to get an attorney to have their rights delivered.

IX. REMARKS BY THE MAYOR –

— Asked Chief DeGiusti for any information regarding the SWAT incident.

Chief DeGiusti responded there are multiple jurisdiction involved, and ultimately the State Police are in charge of the investigation. Because of that any information regarding the case would be coming from the State Police. He said the individual involved has been charged with some serious crimes, however, only half the investigation has been completed. Currently, other than what has already been said the Ypsilanti Police Department does not have further information to

provide. Mayor Edmonds asked the County's involvement in the incident. Chief DeGiusti responded the County Sheriff's Department is cooperating with the State Police investigation. Mayor Edmonds asked why the investigation was turned over to the State Police. Chief DeGiusti responded to provide greater transparency.

- Mayor Edmonds stated any further legal questions will be forwarded to the Attorney's Office for response.

Council Member Murdock stated he, Joe Golder, Carole Clare, the City Attorney, and the former City Manager met some time ago to resolve the issue. A solution was developed that both parties agreed to, which included another survey. Both parties agreed to adhere to the findings of that survey, unfortunately Mr. Golder withdrew from the agreement.

X. ORDINANCE – FIRST READING –

Ordinance No. 1281

1. An Ordinance amending Ypsilanti City Code by adding Article V. Solicitation of Immigration Status, to Chapter 58 Human Relations.

A. Resolution No. 2017-016, determination

IT IS RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI that:

An ordinance titled an ordinance to add a new Article V. to Chapter 58 of the Ypsilanti City Code, Solicitation of Immigration Status is hereby adopted, on first reading.

OFFERED BY: Council Member Murdock

SECONDED BY: Council Member Vogt

B. Open public hearing

1. Margaret Harner, Ypsilanti First Congregational Church & Washtenaw County Interfaith Coalition for Immigrant Rights (WICIR), stated around this room there are either immigrants, new immigrants, or immigrants with a familial history of immigration and together we have woven a very wonderful fabric of diversity. This community always has been very receptive to inclusion and values the diversity. There is a possibility that some of our neighbors might be taken away from this community as a result of their immigration status. That would be a tear in the communities tapestry, which is something this community should not allow to happen. Those in this community must be protected as this community has done in the past. There is possible legislation both at the state and federal levels and City officials should be in contact with attorney's that can assist with possible issues. Rachel Sutledge at Wayne State University has held an immigration clinic and is a well renowned attorney, and she would be more than happy to provide help.
2. Daphne Luhesa, 336 E. Clark, stated she is a member of the WICIR teen group and is here in support of the Non-solicitation of Immigration Status Ordinance. She hasn't been stopped with her family and questioned about

their ordinance status, however, she has been worried about what would happen to her or her family if this occurred. It would be very important for hers and other families to have this ordinance be passed.

3. Ashley Fox, 905 Pleasant Dr., stated he is here to speak in favor of the passage of this ordinance. He said if passed this ordinance could help public safety because it would give assurance they will not be deported as a result of assisting a police investigation. He noted the valedictorian of the STEM Middle College has an undocumented status. He said these individuals are contributing to the community and should be able to feel safe.
4. Lily Ellis, 760 Jenness, thanked Council for their work on not only this ordinance but the Non-Discrimination Ordinance that will be heard on second reading. She said as previously stated both the state and federal governments have been posturing to remove funding from communities that protect their immigrant populations, but have yet to pass any legislation doing so. She said Council should move forward with the passage of this ordinance and address any possible legislation in the future.
5. Maria Ibarra-Fraye, 2127 Golfside, stated she recently moved into the City and currently has Deferred Action for Childhood Arrivals status, which can be eliminated anytime the new administration chooses. To know Ypsilanti will provide safety and security if she were to have an encounter with the police. She encouraged Council to support this ordinance and think about young people who are afraid.
6. Paige Anderson, 610 Gott, stated she supports this ordinance, and asked for clarification of a section of the ordinance that states "an employee will not ask for a person immigration status unless it is required by state or federal law".
7. Quinn Phillips, 414 Emmet, stated she is here in support of the immigration status ordinance. She suggested strengthening the ordinance that no City funds will be used in the enforcement of immigration law, or gather and disseminate information regarding immigration status, or cooperating with INS in the detention of immigration, and any existing questions will be deleted in 60 days. She said she is a social worker who works with undocumented immigrants, some of whom are unable to take action against a landlord because of their immigration status.
8. Rich Stahler-Sholk, 1542 Sillers Terrace, Ann Arbor, stated he works at EMU teaching in the Political Science Department, specializing in Latin American Politics. He said one of the reasons many immigrants come here is fleeing the military and foreign policies of the United States Government. The last time there was a major sanctuary movement was during the Central American Wars. He said the world is going through very mean times and the discourse of the leadership is attempting to divide people. He said he is very glad to see Ypsilanti is moving in this direction, and strongly supports this initiative.

9. Sarah Shogren, 114 N. Hamilton, thanked Council for approving the Non-Discrimination Ordinance on first reading. She said she has lived the majority of her life in Ypsilanti, and although she has travelled the country she always chooses to return to Ypsilanti. When outside of Ypsilanti she always speaks with pride about her City. She thanked City Council for considering this ordinance.
10. Dominic Shoopman, 772 N. Wagner Rd., thanked Council for approving the Non-Discrimination Ordinance on first reading. Like many people we have a very good reason to expect profoundly evil federal policy from the present administration. This ordinance is an important measure Ypsilanti can take as a community to defend its richest form. He encouraged the passage of this ordinance.
11. Elizabeth Snook, 1344 Marlboro Dr., Ann Arbor, supported the passage of the ordinance. She stated human dignity should not be determined by borders, and putting focus on undocumented immigrants is taking away from what is really important.
12. Kim Daly, 407 E. Kingsley St., Ann Arbor, stated she is a graduate student at the University of Michigan and part of the Ann Arbor Solidarity Farmworkers Collective. She voiced her support for the ordinance and thanked everyone for showing up for this ordinance.
13. Maria Luz Garcia, 746 N. Mansfield, stated she is a faculty member at Eastern Michigan University and has been doing much of her work in the past fifteen years in Guatemala where large numbers of unaccompanied minors have been coming to the United States. These individuals have had difficulties with officials in the immigration system in regards to interpretation and understanding the system itself. She supported the passage of the ordinance.
14. Alice, 2011 Medford Rd, Ann Arbor, stated she works at the Family Learning Institute, which works to close the achievement gap in Washtenaw County. Many of the children she works with are undocumented, and the fear these children feel is incredibly difficult to describe. Many of these families are going through so much already, without adding the extra stress of deportation. She believes passing this measure could assist in the achievement later in life.
15. Audience Member, 523 Hill St., Ann Arbor, stated she is glad that local governments are taking a progressive stand against possible federal policy. She thanked Council for considering this ordinance.
16. Gabriel Recentives, 5229 W. Michigan Ave, stated he is currently a student at EMU and is working to make EMU a sanctuary university. If that is successful along with this ordinance it will help the student immigrant population feel safe.

17. Cosmo Abes, 615 N. Adams, stated an important viewpoint to consider is the borders of this country are on stolen land, and deportations are really tantamount to ethnic cleansing.

C. Resolution No. 2017-017, close public hearing

IT IS RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI that:

That the public hearing for an ordinance titled an ordinance to add a new Article V. to Chapter 58 of the Ypsilanti City Code, Solicitation of Immigration Status be officially closed.

OFFERED BY: Council Member Murdock

SECONDED BY: Council Member Richardson

On a voice vote, the motion carried, and the public hearing was closed.

Mayor Edmonds stated she was made aware that a Republican State Representative Pamela Hornberger informed the state house legislature she would be offering a sanctuary city prohibition act. This bill is could be introduced as soon as next week, and is similar to Senate Bill 445 introduced in September of 2015. She said she is still planning on moving forward with the passage of this ordinance because it is time to be on the right side of history. She explained the way this ordinance was drafted is beyond law enforcement and does apply to all members of staff, City Council, Boards and Commissions, and all contracted professional services.

Council Member Robb asked if the ordinance would apply to Friends Groups. Mr. Barr responded if the group has a contract with the City they would need to comply with the ordinance. Mr. Robb stated the MOU recently passed between the City and Washtenaw Community College (WCC) only states WCC would be required to follow the law. Mr. Robb asked if each MOU would need to be amended. Mr. Barr responded he would need to review each MOU individually to make his determination. Council Member Murdock explained contract employees would be the Attorney's Office, or other professional services contracts, and does not apply to general contracts. Mr. Robb asked if a new contracts would need to be passed if this language is not in those contracts. Mr. Barr responded the language presented is broad enough to cover those contracts.

Council Member Robb asked if the Police Department is assisting Immigration and Customs Enforcement they are permitted to inquire about a person's immigration status. Mr. Barr responded the ordinance was drafted to avoid unintended consequences. He explained if an immigrant is charged with certain crimes they are subject to deportation, and the immigrant should be aware of that before the process completes. He said if the individual pleads it could lead to an unintended consequence. The provisions of the contract are to protect both the immigrant and to allow the police to obey the law. Mr. Robb asked for an example of a crime that an officer could inquire about a person's immigration status. Mr. Barr responded criminal sexual conduct.

Council Member Robb said the ordinance also allows an officer to inquire a person's immigration status when processing an arrested person. He said if he were put in the back of a police car prior to being charged with a crime the police could ask him about his immigration status. Mr. Barr responded an arrest is when a person is taken into control by the police.

Council Member Robb asked what violations of this ordinance would be referred to Council and what would be referred to department heads. Mr. Barr responded that would depend on the chain of command and the severity violation. He

explained if an employee unintentionally violates the ordinance it could be handled internally. Council Member Murdock added it would follow the discipline procedure already set. The two employees that would automatically be referred to Council would be the City Manager and Clerk.

Council Member Robb asked what would happen if one of the professional services contractors violates this ordinance. Mr. Barr responded that would be subject to Council's decision.

Council Member Robb stated the Charter and Code of Ordinances to not reflect any disciplinary action that might arise from a violation of this proposed ordinance. He asked how this ordinance ties to the City's ethical code of conduct, and if something will need to be added to the ethical code of conduct. Mr. Barr responded no, and explained in the Preface of the City Charter it outlines the standards for public servants, and one standard is to follow the law.

Council Member Robb asked if this ordinance would apply to current union contracts. Mr. Barr responded the State of Michigan states labor law as the highest law in the land, and the City Ordinance cannot violate a union contract. He said the procedure would be to negotiate the terms of the contract. Mr. Robb asked if this is adopted union employees would not be subject to discipline for its violation. Mayor Edmonds asked if the ordinance does not actively disagree with the union contract it would still need to wait to renegotiate the contract. Mr. Barr responded yes, in terms of employment a union employee would not be subject to discipline until the contract is renegotiated. Council Member Murdock stated police officers need to abide by the General Orders of the Police Department. He said this should be acceptable, but if an employee wishes they could file a grievance. Mr. Barr added the Police Chief did not find issue with this ordinance. Chief DeGiusti stated this is similar to any other policy procedure at the Police Department. He said officers are given fair notice, usually a fourteen day period, and Police General Orders are changed as law changes and he does not see this as a contractual issue. Mr. Robb asked if this information has been shared with the labor attorney. Mr. Barr responded no.

Council Member Bashert asked if this is passed and the State Legislature passes the bill discussed by the Mayor what will happen to the City's law. Mr. Barr responded the authority starts with the Michigan Constitution and all the power the City receives comes from the state. He said generally if the State makes a law then the City has no power to change that. Mayor Edmonds responded her interpretation of the proposed bill the City would lose funding. Mr. Barr replied the proposed House Bill is said to be similar to Senate Bill 445, but until he knows what it actually says it makes it difficult to opine. Council Member Murdock stated there has been discussion about banning sanctuary cities both at the state and federal level. He said a case can be made that this ordinance would not be impacted by the proposal in Lansing. He said this matter more than likely will be disputed in court. He said if you look at the reaction of the community, which is in support of these measures Council should not be scared off by that possibility.

Council Member Vogt stated his reading of Senate Bill 445 implies City would lose funding if it did not comply with the law. However, there would be many law suits before the state would be able to get to that point. He said this is a moral issue, and what matters to him is the end goal of is the person a law abiding good citizen. That premise should be the sole issue when discussing citizenship. Deporting an individual without examining the merits of that individual is amoral. He said on a practical level it is also damaging to this country.

Mayor Edmonds stated what is important about this is Ypsilanti has worked to protect people for a long time. However, for this to be affective organizing will need to move across the City's borders, the County, and expand into the State. She said the goal is to ensure a person is safe if they are within the borders of the City or outside.

Council Member Richardson stated the threat the state will withhold revenue sharing from the City should not matter since the state has withheld the \$1.2 million in revenue sharing a year from municipalities. Mayor Edmonds added the state has withheld around \$10 million from the City over the past eight years.

Mayor Pro-Tem Brown stated she is a first generation of her family born in this country. Her parents and grandparents both immigrated, and some of her family is still undocumented. She is very fortunate to have worked on this ordinance and is very thankful this community is so welcoming to the immigrant population.

On a roll call, the vote to approve Resolution No. 2017-016 was as follows:

Mayor Pro-Tem Brown	Yes	Council Member Robb	Yes
Council Member Murdock	Yes	Mayor Edmonds	Yes
Council Member Richardson	Yes	Council Member Vogt	Yes
Council Member Bashert	Yes		

VOTE:

YES: 7 NO: 0 ABSENT: 0 VOTE: Carried

Ordinance No. 1282

2. An Ordinance amending Ypsilanti Zoning Code for PMD, Production, Manufacturing, and Distribution.

Community Development Director Beth Ernat stated residents of the Bell/Kramer neighborhood who are available for testing received an agreement to test. The agreements have been updated as a result of the language in the original agreement regarding liability. There was a belief the City would be absolved of any liability, and the new agreement states the City would be absolved from liability upon entering the structure, or property.

A. Resolution No. 2017-018, determination

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

Whereas, the Bell-Kramer neighborhood has a residential character; and

Whereas, the current zoning of PMD does not permit existing residences to be rebuilt in the case of a casualty; and

Whereas, the amendment to the Zoning Ordinance will help to ensure that current owners of residential properties can retain value in those properties;

Now therefore be it resolved that the Ypsilanti City Council approve the amendment to Chapter 122, Article IV, Section 205 of the City's Code of Ordinances on FIRST READING.

OFFERED BY: Council Member Vogt

SECONDED BY: Mayor Pro-Tem Brown

City Planner Bonnie Wessler stated the Bell/Kramer neighborhood, which is adjacent to a former landfill at I-94. This area was rezoned to PMD, Production, Manufacturing, and Distribution in 2014. This is an industrial designation and does not allow for homes to be rebuilt if there are destroyed as a result of a fire, nor does it allow for single family homes to be built.

In November of 2016 this was brought to Council for guidance on how this are should be zoned, and instruction was given to bring the matter before the Planning Commission. The Planning Commission reviewed the recommendation and agreed to add the sentence, "single family and two family homes on individual lots that are considered non-conforming use in a PMD zoning district shall be allowed to be rebuilt regardless of the amount of damage done as long as the rebuild is not enlarged, or expanded". This would allow for homes to be rebuilt in the case of a casualty, however, it does not allow for new construction.

B. Open public hearing

1. Larry Simmons, asked if what is being proposed is a person may rebuild their home, but it cannot be built new.

Mayor Edmonds responded a damaged home could be rebuilt, but new construction would not be permitted.

Mr. Simmons asked what can be done with vacant land. Mayor Edmonds responded vacant land is not eligible for new construction. However, the City owns most of the vacant land in that area.

2. Erin Schneider, 129 Bell, stated she supports this ordinance and it is a good first step. She hopes the City will continue to look at this further after the contamination testing is complete. She said this does allow for her property to have value again, but it does not allow all the property rights it once had. She added she hopes Council will strongly consider rezoning this are back to residential depending on the contamination levels.
3. Michael Simmons, 128 Bell St., stated he applauds the efforts being made by the City to restoring that community back to what it once was. From His understanding there is supposed to be a caveat to this ordinance that after the testing is complete it would be reviewed. If it is found the contamination is not at unsafe levels the neighborhood could be returned to residential. He said he did not here that in the resolution as read.
4. Cherissa Lamarr, 123 Bell St., stated it is her understanding is the neighborhood still has a PMD zoning designation. Her goal is for the neighborhood to be restored back to a residential designation. She does not see a reason for the neighborhood to have a PMD designation. She hopes the testing does come back favorably and the neighborhood will be returned back to a residential designation. She added she has not received an agreement for testing and thinks it is ludicrous that some have received the agreement, but not all.

C. Resolution No. 2017-019, close public hearing

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

That the public hearing for an ordinance to amend Chapter 122, Article IV, Section 205 of the City's Code of Ordinances by officially closed.

OFFERED BY: Council Member Vogt

SECONDED BY: Mayor Pro-Tem Brown

On a voice vote, the motion carried, and the public hearing was closed.

Council Member Richardson agreed with the comment that this is a good first step. She said the Planning Commission did commit to the residents that once the testing is complete and the results were clear this neighborhood would be made whole. She stands with the residents to restore the neighborhood to a residential designation. She asked Council to put themselves into the shoes of the people living in this neighborhood. She said many of these residents have lived there for years, and now their lives are being disrupted. She said there are property owners in the area that have a goal of building a home near their families.

Council Member Richardson moved, seconded by Mayor Pro-Tem Brown that if no contamination is found that this neighborhood be returned to R2.

Mayor Edmonds asked the City Attorney if it is proper to amend a resolution for a zoning ordinance amendment in this manner. Mr. Barr responded that could be a post script to this ordinance.

Council Member Robb stated the Planning Commission minutes were not included in the packet, and asked if the Planning Commission said they would revisit this, or they would change it. Ms. Wessler responded the Planning Commission would revisit this after testing was complete. Mr. Robb stated this would not require Council action if the Planning Commission has already agreed to revisit this. Mayor Edmonds stated if she understands what was said by Mr. Simmons it is the desire of the residents of that neighborhood that Council solidify the commitment in the resolution.

Ms. Wessler stated "making whole" is a legal specific term, and the Planning Commission spoke about an area plan and not making whole. Council Member Richardson disagreed, and said the Planning Commission did speak about making this neighborhood whole.

Mr. Barr stated the motion reads if no contamination is found it would go to the Planning Commission. He does not believe Council can order the Planning Commission to come to a particular conclusion, but they could revisit it. Council Member Richardson responded she is stating what was said by the Planning Commission.

Council Member Vogt stated he does not understand what is meant by "return" or "revisit", and asked what the ultimate thing is being asked for Council to declare. Council Member Richardson responded that this residential neighborhood be returned to the zoning designation it once had. Mr. Vogt asked what zoning designation that is. Ms. Richardson responded R2.

Mayor Edmonds asked what the previous zoning classification was. Ms. Wessler responded R2, but the last zoning code had a completely different set of zoning districts, and the R2 district no longer exists. Ms. Edmonds asked what the equivalent zoning district is. Ms. Wessler responded CN Mid, but it would probably would not be a good fit for this neighborhood, and suggested a designation of R1, but she would need to review the lot sizes.

Council Member Vogt objected to the term “made whole” stating is a vague term. He suggested providing a clear designation. Council Member Richardson stated in the motion she did state that this neighborhood be given its residential classification. Mr. Vogt asked for the motion to be restated.

Mr. Barr asked if Council is so inclined to pass this on first reading allowing time to work with Council Member Richardson to provide language for second reading. Mayor Edmonds asked if Council Member Richardson would like to withdraw her motion until the second meeting. Council Member Richardson denied to withdraw her motion.

Michael Simmons, 128 Bell St., asked for clarification of what is meant by “contamination” in the motion. Mayor Edmonds stated Mr. Simmons makes a valid point, the City is aware there is contamination in landfill, the question is where else the contamination is.

Council Member Richardson withdrew her motion.

Council Member Richardson stated she will work with the Attorney’s Office to form resolution language for second reading.

Council Member Murdock asked that the Planning Commission minutes be provided for second reading.

Council Member Richardson called to question.

On a roll call, the vote to Call to Question was as follows:

Mayor Pro-Tem Brown	Yes	Council Member Robb	Yes
Council Member Murdock	Yes	Mayor Edmonds	Yes
Council Member Richardson	Yes	Council Member Vogt	Yes
Council Member Bashert	Yes		

VOTE:

YES: 7 NO: 0 ABSENT: 0 VOTE: Carried

On a roll call, the vote to approve Resolution No. 2017-018 was as follows:

Mayor Pro-Tem Brown	Yes	Council Member Robb	Yes
Council Member Murdock	Yes	Mayor Edmonds	Yes
Council Member Richardson	Yes	Council Member Vogt	Yes
Council Member Bashert	Yes		

VOTE:

YES: 7 NO: 0 ABSENT: 0 VOTE: Carried

XI. CONSENT AGENDA –

Resolution No.2017 - 020

1. Resolution No. 2017 - 021, approving the minutes of December 17, 2016.

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

THAT the minutes of December 17, 2016 be approved.

2. Resolution No. 2017 - 022, approving nominations to Boards and Commissions.

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

THAT, the following individuals be appointed to the City of Ypsilanti Boards and Commissions as indicated below:

<u>NAME</u>	<u>BOARD</u>	<u>TERM</u> <u>EXPIRATION</u>
Ann Stevenson (Reappointment) 707 Collegewood Ypsilanti, MI 48197	Historic District Commission	1/31/2020

OFFERED BY: Council Member Vogt

SECONDED BY: Mayor Pro-Tem Brown

On a roll call, the vote to approve Resolution No. 2017-020 was as follows:

Mayor Pro-Tem Brown	Yes	Council Member Robb	Yes
Council Member Murdock	Yes	Mayor Edmonds	Yes
Council Member Richardson	Yes	Council Member Vogt	Yes
Council Member Bashert	Yes		

VOTE:

YES: 7 NO: 0 ABSENT: 0 VOTE: Carried

~~3. Resolution No. 2017-023, supporting the submission of a grant application to the Ralph C. Wilson Jr. Foundation for playground equipment for Riverside Park. (Moved and heard during Section XII, Resolution/Motions/Discussions)~~

XII. RESOLUTIONS/MOTIONS/DISCUSSIONS –

1. Resolution No. 2017- 024, approving Ordinance 1279 amending Article III Discrimination of Chapter 58 Human Relations, being Section 58-91 through Section 58-99 of the Ypsilanti City Code.
(Second Reading)

IT IS RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI that:

The certain ordinance entitled "An ordinance to amend the Discrimination Ordinance of the City of Ypsilanti" Article III Discrimination of Chapter 58 Human Relations, being Section 58-91 through Section 58-99 of the Ypsilanti City Code be adopted on second and final reading.

OFFERED BY: Council Member Bashert

SECONDED BY: Council Member Murdock

Council Member Bashert stated this year is the twentieth anniversary of the drafting of the original language of the Non-Discrimination Ordinance. She said she is proud and excited to be a part of the continued strength and flexibility of the ordinance. Mayor Edmonds stated Council Member Bashert was a strong part and leader during the passage and defense of this ordinance in previous years.

Mayor Edmonds stated she has asked the Attorney's Office to prepare a fact sheet regarding this ordinance. Mayor Edmonds asked when this ordinance will take effect. Interim City Manager McMullan responded thirty days after tonight.

On a roll call, the vote to approve Resolution No. 2017-024 was as follows:

Mayor Pro-Tem Brown	Yes	Council Member Robb	Yes
Council Member Murdock	Yes	Mayor Edmonds	Yes
Council Member Richardson	Yes	Council Member Vogt	Yes
Council Member Bashert	Yes		

VOTE:

YES: 7 NO: 0 ABSENT: 0 VOTE: Carried

2. Resolution No. 2017-025, approving Ordinance 1280 amending Ypsilanti City Code by adding a new Division 5 Sustainability Commission, to Chapter 2 Administration, Article IV Boards and Commissions. **(Second Reading)**

IT IS RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI that:

An ordinance titled an ordinance to add a new Article V. to Chapter 58 of the Ypsilanti City Code, Solicitation of Immigrant Status is hereby adopted, on first reading.

OFFERED BY: Council Member Murdock

SECONDED BY: Council Member Bashert

Mayor Edmonds stated she has received several applications to sit on this commission.

On a roll call, the vote to approve Resolution No. 2017-025 was as follows:

Mayor Pro-Tem Brown	Yes	Council Member Robb	No
Council Member Murdock	Yes	Mayor Edmonds	Yes
Council Member Richardson	Yes	Council Member Vogt	Yes
Council Member Bashert	Yes		

VOTE:

YES: 6 NO: 0 ABSENT: 0 VOTE: Carried

3. Resolution No. 2017-026, authorizing staff to apply for the SAFER Grant.

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

WHEREAS, The Fire Department qualifies to apply for a FEMA grant under the 2016 Staffing for Adequate Fire & Emergency Response (SAFER)

Grants. The goal of SAFER is to enhance the local fire departments' ability to comply with the staffing, response, and operational standards established by the NFPA 1710; and

WHEREAS, three firefighters will place the Fire Department back into compliance with NFPA 1710 and will also make the Department compliant with MIOSHA's "two-in, two-out" requirement.

WHEREAS, the total amount of the three year grant is \$819,216 and the maximum City's financial participation due to matching requirement will be \$314,033 if we do not obtain a "cost share" waiver; And,

WHEREAS, three additional personnel will reestablish a staffing level of six persons per shift and reduce overtime in excess of the City's maximum financial participation.

NOW THEREFORE BE IT RESOLVED THAT the Ypsilanti City Council authorizes the Fire Department to apply for the grant.

OFFERED BY: Council Member Murdock

SECONDED BY: Mayor Pro-Tem Brown

Fire Chief Max Anthouard stated in 2013 the Department had only fifteen firefighters in fire suppression. During that time period overtime increased to about \$250,000 a year. As of yesterday Lt. Schultz was promoted to Fire Marshall and in April two other firefighters will be lost to retirement again dropping the numbers to fifteen. He said he would like to apply for a SAFER grant for three firefighters in order to stay at the eighteen threshold. Three weeks before the end of the grant three more firefighters will retire, which will put the City in a situation to reapply once it expires in 2021. Chief Anthouard stated the numbers provided are accurate for the FEMA calculation, and the City's portion is \$314,000. However, considering the cost of \$250,000 yearly in overtime while staffed at fifteen in personnel, the investment made will be balanced by the savings in overtime. The SAFER Grant is now based on the first year salary of the firefighter, any raises are not reflected in the grant.

Council Member Murdock asked what the odds of the City are receiving continuous SAFER Grants. Chief Anthouard responded Dearborn Heights, Garden City, and Jackson were awarded consecutive SAFER Grants. He said he believes the City is in good shape to receive consecutive grants.

Council Member Bashert stated the City recently failed to pass a millage needed to keep the City solvent, and as a result Council instituted a hiring freeze. If the City needs to invest money in this grant to hire additional firefighters it is in conflict with the plans the City has made as a result of the failed millage. Mayor Edmonds responded the fire department overtime was at a level that was unsustainable before the City initially applied for the SAFER Grant. The City will find itself in the same place if the City does not receive this grant. Council Member Robb asked if Council needs to rescind the resolution that froze hiring. Ms. Bashert stated if Council decides to hire additional firefighters it might be seen as a credibility issue. Council Member Richardson responded in the City is awarded the grant it will pay for a major portion of the firefighters. Ms. Richardson explained she sees the firefighters paid for by the grant outside the hiring freeze. Mr. Robb stated this resolution

only authorizes the City to apply for the grant. Chief Anthouard replied if the City applies for the grant it is required to accept the award.

Council Member Murdock stated if the City receives the grant it will push the hiring of the firefighters forward three years. Chief Anthouard added the firefighters hired will be tier two, and will receive that benefit package. Mr. Murdock stated one the other firefighters retire the department will be back to fifteen people. Chief Anthouard responded in the affirmative, and explained that is why it is important to hire the new firefighters at the beginning of the grant.

Mayor Edmonds asked for an explanation of the "drop program". Chief Anthouard responded firefighters in the "drop program" have a set date for retirement, meaning the two personnel to retire in April cannot change their minds. He added the personnel participating in the "drop program" may leave before but not after the set date. Ms. Edmonds added new employees are hired in as tier two at a lower cost creating a savings for the City.

Council Member Robb asked does Council need to rescind its hiring freeze to apply for this grant. Council Member Murdock suggested amending the resolution to allow these employees to be hired."

Council Member Bashert asked if this is what fire protection looks like in Michigan. Chief Anthouard responded that is the trend, however it is beginning to improve. Council Member Murdock stated all fire departments, not just Ypsilanti, have been reduced significantly.

Chief Anthouard stated if the department decreases to fifteen it will not be able to provide the same level of service.

Council Member Murdock moved, seconded by Council Member Bashert that if City Council authorizes the hiring of three firefighters if the City is awarded the grant.

On a roll call, the vote to amend Resolution No. 2017-026 was as follows:

Mayor Pro-Tem Brown	Yes	Council Member Robb	Yes
Council Member Murdock	Yes	Mayor Edmonds	Yes
Council Member Richardson	Yes	Council Member Vogt	Yes
Council Member Bashert	Yes		

VOTE:

YES: 7 NO: 0 ABSENT: 0 VOTE: Carried

On a roll call, the vote to approve Resolution No. 2017-026 was as follows:

Mayor Pro-Tem Brown	Yes	Council Member Robb	Yes
Council Member Murdock	Yes	Mayor Edmonds	Yes
Council Member Richardson	Yes	Council Member Vogt	Yes
Council Member Bashert	Yes		

VOTE:

YES: 7 NO: 0 ABSENT: 0 VOTE: Carried

4. Resolution No. 2017-027, approving Parkridge Center endowment agreement with Mr. John Barfield.

IT IS RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI that:

The agreement between the City of Ypsilanti and John Barfield for endowment and financial support for Parkridge Center, entitled MEMORANDUM OF UNDERSTANDING BETWEEN THE CITY OF YPSILANTI AND JOHN BARFIELD REGARDING PARKRIDGE COMMUNITY CENTER be approved and the Mayor and City Clerk are authorized to sign for and on behalf of the city, subject to the approval of the city attorney.

OFFERED BY: Council Member Richardson

SECONDED BY: Mayor Pro-Tem Brown

Mr. Barr stated Mr. Barfield is very committed to the Parkridge Center and has committed to start an endowment, and commit to awarding the City \$11,000 a year to the City for Parkridge. Since that time he has established an endowment of \$200,000 with the Ann Arbor Community Foundation. The City has negotiated with Mr. Barfield and George Burrell, Mr. Barfield's CPA, who agreed to sign a draft contract. Essentially the contract states that Mr. Barfield will donate the interest of the \$200,000 to the operation of Parkridge. The cost to fund Parkridge totals around \$54,000 a year, and Mr. Barfield has agreed to pay \$27,000. Another aspect of that agreement is to purchase a home behind Parkridge Center for the City to demolish to use for further initiatives of the center. Mr. Barr added Mr. Burrell can facilitate the movement of funds while Mr. Barfield is out of town.

Council Member Robb stated the contract reads "Mr. Barfield will contribute \$27,000 if the City contributes at least \$27,000 for payment of such costs". He asked if the City is able to find outside funding to cover the City's share would that negate Mr. Barfield's contribution. Mr. Barr responded outside funding would count towards the City's contribution in his opinion. Mr. Robb asked when Mr. Barfield would be invoiced for his contribution. Mr. Barr responded he would be invoiced immediately for this year.

Mayor Edmonds asked for the status of the two years of payments he has already committed. Mr. Barr responded there has been no agreement for that payment. Ms. Edmonds asked if this contract would cover those payments. Mr. Barr responded no.

Council Member Murdock stated his concern is the contract contains several things that commit the City to expand services when the City is having difficulty supporting the services it already provides. The agreement is unclear on who will run the facility and who will be responsible for the facilities budget. Mayor Edmonds added the agreement also states a Parkridge Advisory Committee will also be established without providing explanation for what that is. She added there is already an established committee that has been operating for some time. Council Member Richardson stated there is currently a Parkridge Advisory Board. Ms. Edmonds asked if the current board presents a budget. Ms. Richardson responded in the affirmative. Ms. Richardson stated the City currently has a Memorandum of Understanding (MOU) with Washtenaw Community College (WCC) to provide the programming at Parkridge and provides that budget, and the advisory board budgets to keep the facility open.

Mr. Burrell stated the budget for Parkridge is \$54,000 this year, and to date the City has already paid roughly \$27,000 this year. He said Mr. Barfield recognizes that, and he will immediately contribute \$27,000 to fund the rest of the year.

Mayor Edmonds asked if it would be helpful to amend the contract under number 1, Center Operating Cost, section B to read "partial cost". Council Member Murdock stated as he understands it there is Parkridge staff outside of WCC. Interim City Manager McMullan stated the contract the City holds with WCC states the City is required to fund two staff members, and she is not certain if that would need to be addressed as a part of this contract. Ms. Edmonds replied it might be helpful to have it clarified. Ms. McMullan responded she does not feel it is necessary. Mr. Barr agreed that it would not be necessary.

Ms. McMullan explained when Council approved the MOU with WCC it was decided Parkridge would continue to stay open. To ensure the center would continue to operate a fund raising committee, comprised of city officials, was discussed, and that is what is included in this contract. The current advisory committee could be expanded to include fund raising. Ms. Richardson responded the committee has been participating in active fund raising, not just holding a funds raising event. Ms. McMullan replied city officials would like to be a part of that process. Ms. Richardson welcomed additional fundraising help, and any other ideas city staff might have.

Council Member Bashert asked what the cost is to demolish a home. Mr. Barr responded around \$11,000. Mayor Edmonds asked what the timeline is to demolish that structure. Mr. Barr responded the City will not acquire that property until the owner is ready to sell. Ms. Edmonds asked once the City acquires the property if funds are not available to demolish the building. Council Member Richardson stated the owner of the home in question is almost 103 years old, and the agreement made several years ago was that when she passed away the house would be sold to the Parkridge Advisory Board, and the home would then be deeded to the City.

Council Member Robb asked if this agreement will in any way commit the City to construct additional facility should Mr. Barfield raise the funds. Mr. Barr responded it does not.

On a roll call, the vote to approve Resolution No. 2017-027 was as follows:

Mayor Pro-Tem Brown	Yes	Council Member Robb	Yes
Council Member Murdock	Yes	Mayor Edmonds	Yes
Council Member Richardson	Yes	Council Member Vogt	Yes
Council Member Bashert	Yes		

VOTE:

YES: 7 NO: 0 ABSENT: 0 VOTE: Carried

5. Resolution No. 2017-028, authorizing the Community-Policing and Black Lives Matter Task Force to develop a Community and Police Commission.

IT IS RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI that:

Whereas, by act of City Council the Community-Policing and Black Lives Matter Task Force was created in October of 2015 to examine police procedure to better serve the City of Ypsilanti; and

Whereas, the Task Force has examined several possibilities to improve community relations, one of which is the formation of a Community and Police Commission; and

Whereas, a sub-committee was established to develop structure of said commission and forward to the Task Force for approval; and

Whereas, the sub-committee listed four main responsibilities of the Commission; to review accusations of police misconduct, facilitate review of two to three policies per year, promote community policing, and promote the Citizens Police Academy; and

Whereas, the Task Force asks for City Council approval to continue its work to develop a Community and Police Commission, and to engage with the appropriate City Staff to complete its task.

Now therefore be it resolved, that the City Council of the City of Ypsilanti authorizes the Task Force to pursue the development of a Community and Police Commission and engage with the appropriate personnel to complete its task.

OFFERED BY: Mayor Pro-Tem Brown

SECONDED BY: Council Member Richardson

Mayor Pro-Tem Brown stated a sub-committee was formed to examine best practices of community police commissions, and the committee developed an outline on how to structure that commission. After discussion through several Task Force meetings it was decided to seek approval from Council to move forward with the development of this commission. She stated she has met with Chief DeGiusti regarding the sub-committee recommendations regarding the review of policy, the Citizens' Police Academy, and community policing. The intention of this resolution is to receive the blessing of Council to move forward with the commission's development.

Council Member Murdock thanked the sub-committee and all others who have been working toward this goal. He suggested to add a timeframe to this resolution.

Council Member Murdock moved, seconded by Council Member Richardson to add "Further Resolved that the Task Force and staff bring forth an ordinance for first reading at the March 21, 2017 City Council meeting.

Council Member Robb stated that will only allow one meeting for the Task Force to develop the ordinance. Mayor Pro-Tem Brown stated she has another meeting scheduled with the Chief DeGiusti in the next couple of weeks. Council Member Murdock stated much of the work is complete, and the difficult part is the review of complaints. However, he believes it can be completed in that time. He stated if there is not a time scheduled for this to be on an agenda it might go back and forth between committee and the Task Force. He added once it gets to Council it can be modified over the first and second readings. Council Member Richardson agreed. Ms. Brown asked for the timeframe be pushed to the first meeting in April to allow for more time. Mr. Murdock agreed to postpone the deadline until the first meeting in April.

Council Member Murdock moved, seconded by Council Member Richardson to amend the motion moving the deadline from March 21st to April 4th.

Mayor Pro-Tem Brown moved, seconded by Council Member Vogt to extend the meeting to 11:00 p.m.

On a voice vote, the motion carried, and the meeting was extended.

On a roll call, the vote to amend Resolution No. 2017-028 was as follows:

Mayor Pro-Tem Brown	Yes	Council Member Robb	Yes
Council Member Murdock	Yes	Mayor Edmonds	Yes
Council Member Richardson	Yes	Council Member Vogt	Yes
Council Member Bashert	Yes		

VOTE:

YES: 7 NO: 0 ABSENT: 0 VOTE: Carried

On a roll call, the vote to approve Resolution No. 2017-028 was as follows:

Mayor Pro-Tem Brown	Yes	Council Member Robb	Yes
Council Member Murdock	Yes	Mayor Edmonds	Yes
Council Member Richardson	Yes	Council Member Vogt	Yes
Council Member Bashert	Yes		

VOTE:

YES: 7 NO: 0 ABSENT: 0 VOTE: Carried

6. Resolution No. 2017 – 023, supporting the submission of a grant application to the Ralph C. Wilson Jr. Foundation for playground equipment for Riverside Park.

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

WHEREAS, there is community support for a playground in Riverside Park; and,

WHEREAS, the proposed park design was community-driven, design of the playground was vetted publically by the Park Task Force, the proposed park has been formally adopted in the Ypsilanti Parks Plan, and the City Park and Recreation Commission supports the proposed plan; and

WHEREAS, the proposed park includes accessible features, low-maintenance equipment, and equipment for varying age groups; and

WHEREAS, the City of Ypsilanti needs grant support in order to implement the proposed park improvement in Riverside Park.

NOW THEREFORE BE IT RESOLVED, the City Council of Ypsilanti supports the application for grant being made to the Ralph C. Wilson, Jr. Foundation for grant funds in the amount \$50,000 for the creation of a playground in Riverside Park. Additionally, the City Council approves of the in-kind match for installation and maintenance of said playground.

OFFERED BY: Council Member Robb

SECONDED BY: Mayor Pro-Tem Brown

Council Member Robb asked for an explanation of the City match. Ms. Ernat responded there is not a match required for the grant, however, the support from the City is to install the equipment.

Mayor Edmonds asked if using this grant could prevent the City from submitting a larger proposal in the future. Ms. Ernat responded no. Ms. Edmonds added she may know of a person that could assist the City in being approved for this grant.

On a roll call, the vote to approve Resolution No. 2017-023 was as follows:

Council Member Brown	Yes	Council Member Robb	Yes
Council Member Murdock	Yes	Mayor Edmonds	Yes
Council Member Richardson	Yes	Council Member Vogt	Yes
Council Member Bashert	Yes		

VOTE:

YES: 7 NO: 0 ABSENT: 0 VOTE: Carried

XIII. LIASON REPORTS –

- A. SEMCOG Update – Council Member Richardson stated the meeting will be held on Friday, January 27th.
- B. Washtenaw Area Transportation Study – Council Member Murdock stated at one time the City was thinking of rearranging the allocation of the Federal Highway Funds from 2017 to 2019. However, a partner jurisdiction has not been located making that possibility unlikely. As a result the City will have \$360,000 for roads projects to be completed this year.
- C. Urban County – Mayor Edmonds stated there was not an application for a priority project in the current round. That 10% will be reallocated to each of the participating jurisdictions, although there are attempts being made to address the Leforge corridor.
- D. Freight House – Council Member Murdock stated a temporary certificate of occupancy has been granted for the Freight House.
- E. Parks and Recreation - None
- F. Ypsilanti Downtown Development Authority – Mayor Edmonds stated there have been discussions about moving the recycling center from Frog Island Park to another location. The City is in violation of the Natural Trust Fund Grants because of the current location of the center. This effects the City's eligibility for approval of future grants. There were also discussions regarding snow removal

creating a safe and accessible DDA District. The DDA is still waiting for EMU to recommend a person to fill their seat on the DDA Board.

- G. Eastern Washtenaw Safety Alliance – Meeting Monday, January 30th.
- H. Police-Community Relations/Black Lives Matter Joint Task Force - None
- I. Friends of Rutherford Pool - Mayor Pro-Tem Brown stated a youth member has been appointed to the pool board.

Mayor Edmonds asked for Council Members to inform her of what other meetings they are attending, and would like added to liaison reports. Council Member Richardson stated she currently is liaison to both SEMCOG and Parkridge, however she does not believe Parkridge needs to have an official liaison report. Council Member Murdock stated he does not wish to take on any more liaison positions. Council Member Bashert stated she would become the liaison for the Parks and Recreation Commission and Sustainability Commission. Mayor Pro-Tem Brown stated she would maintain her current liaison positions. Council Member Vogt stated he is currently the alternate for WATS and is liaison to the Streetlight Alliance. He offered to be liaison to the Parks and Recreation Commission, however, he is not certain of the time commitment. Council Member Robb stated he is satisfied with what he has.

Mayor Pro-Tem Brown asked for a list of community and regional meetings.

XIV. COUNCIL PROPOSED BUSINESS –

Murdock

- Asked for a follow-up on the SWAT shooting, and the relationship the City has with the SWAT team.
- Stated there is debris and graffiti on the railroad and asked what could be done to fix the problem.

Ms. Ernat responded she spoke with OHM and Mr. Kirton who informed her the debris is all located on the MDOT right-of-way. The City has submitted a request for clean-up and will continue to do so. The City would face repercussions if it enters the right-of-way to perform the clean-up itself. She suggested leaning on state representatives and the City's lobbyist. Mayor Edmonds suggested Manager McMullan contact Representative Peterson and Kirk Profit to solicit assistance.

Mayor Edmonds stated on Michigan Ave between Harmony House and Miles there is garbage and other debris along the railroad right-of-way. She stated nefarious activity occurs there and it needs to be fenced off.

Richardson

- Asked for an update on the SWAT shooting.
- Announced that on February 28th Parkridge will be holding its annual Black History Program. She asked if the City will like to partner with Parkridge it would be welcomed.
- Asked if the City was still creating a newsletter.

Ms. McMullan responded the City is currently shorthanded and has not been able to create a newsletter.

- Asked for an update on the Towne Center.

Mayor Edmonds responded the former head of MSHDA was appointed to another position. However, she was given contact information to another person that could provide assistance. Ms. Ernat added both elevators are currently operating.

- Stated because there is federal funding involved in the construction occurring at Parkridge the project is supposed to follow the Section III rule, and they are not.

Ms. Ernat responded the contract is through Washtenaw County, and will look into that.

- Asked for an update on Water Street.
- Stated the lights appear to be out in the City Parking Lot.

XIV. COMMUNICATIONS FROM THE MAYOR –

Nominations

Historic District Commission
Hank Prebys **(Reappointment)**
31 N. Grove
Ypsilanti, MI 48198
Exp. 1/2020

XV. COMMUNICATIONS FROM THE CITY MANAGER –

None

XVI. COMMUNICATIONS –

- January 31st – Council Goal Session Meeting, held at SPARK East, 215 Michigan Ave, from 6:00 p.m. to 10:00 p.m.

XVII. AUDIENCE PARTICIPATION –

1. Ms. Gelletly, 921 Sheridan, stated she has an issue with signs being posted to trees in the City, and asked if there is anything can be done about it.

XVIII. REMARKS FROM THE MAYOR –

- None

XIX. ADJOURNMENT -

Resolution No. 2017 - 029, adjourning the City Council meeting.

OFFERED BY: Council Member Richardson
SECONDED BY: Council Member Vogt

On a voice vote, the motion carried, and the meeting adjourned at 10:47 p.m.

City Council Meeting Minutes
January 24, 2017



DRAFT

**City of Ypsilanti
City Council Goal Setting Agenda**

Tuesday, January 31, 2017

6:00 – 10:00 p.m.

Spark East – 215 W. Michigan Avenue
Ypsilanti, Michigan

I. CALL TO ORDER –

The meeting was called to order at 6:09 p.m.

II. ROLL CALL –

Council Member Bashert	Present	Council Member Robb	Present
Mayor Pro-Tem Brown	Present	Council Member Vogt	Present
Council Member Murdock	Present	Mayor Edmonds	Present
Council Member Richardson	Present		

III. INVOCATION –

Mayor Edmonds asked all to stand for a moment of silence.

IV. PLEDGE OF ALLEGIANCE –

"I pledge allegiance to the flag, of the United States of America, and to the Republic for which it stands, one nation, under God, indivisible, with liberty and justice for all."

V. INTRODUCTIONS –

Mayor Edmonds introduced the following; State Representative Ronnie Peterson and Darwin McClary.

VI. AUDIENCE PARTICIPATION –

None

VII. REMARKS FROM THE MAYOR –

None

VIII. PRESENTATIONS –

— Capital Improvements Plan – Marcus McNamara, OHM

Marcus McNamara, OHM, provided a presentation regarding the Capital Improvements Plan.

*City Council Meeting
January 31, 2017*

Council Member Rob asked when we found out that we couldn't pass on this money to other communities. Mr. McNamara responded at the end of December. Mr. Robb asked if the City will need to have the money spent during our fiscal year or the state's fiscal year. Mr. McNamara responded within the state fiscal year. They don't obligate until you have a design package in by June.

Council Member Robb asked can the City do if it would like to complete a project not on the list, and will there be time to engineer that project. Mr. McNamara responded the project would not be completed in this season's construction, but you wouldn't lose the money. March or April is the latest if you wanted to get work done for construction this year.

Mayor Edmonds asked can be done to improve the Huron River Drive and Leforge corridor. That intersection has multiple issues. Mr. McNamara responded OHM has not looked at that project in detail, but it is something that could be examined.

Council Member Murdock stated the City is losing funding for roads each year. He said he is not sure what's going on in the Federal Aid. He believes that we should use the additional money to keep up in the next two years. Last year the City used \$350,000. \$300,000 for roads and \$50,000 for non-motorized. That funding came out of the major streets. The question is how much money is in major streets that can be used for road projects other than snow removal.

Council Member Murdock asked if the \$470,000 was for 2017. Mr. McNamara responded in the affirmative, and explained it is the Federal Aid Allocation.

Mayor Edmonds asked Council Member Murdock, as being the council member representative for this committee, are there pieces of the discussion of things that did or did not rise to the top as you were starting to say?

Council Member Bashert asked what is the City's commitment for the rail platform and what must Council do to ensure that contribution is available. Council Member Murdock responded Council approved a resolution promising \$2 million out of General Fund.

Council Member Bashert asked if lawsuit regarding ADA crossings has been resolved. Council Member Robb it will not resolve the issue completely, but it works toward an end.

Mayor Edmonds asked for clarification on how these projects will be funded. Mr. McNamara responded current federal aid allocated to the City in this fiscal year is \$470,000 dollars. There is no allocation in 2018, but there is \$390,000 for the city in 2019, which is a combination of some of the money that was originally in 2017. Council Member Murdock added the City would also receive funding from the county road millage, which is around \$120,000 each year. Mr. McNamara stated he does not disagree on anything that has been said, but for clarity it is important to understand what City receives from the county millage, or elsewhere to determine which projects you want to do with the money. The federal aid dollars are restricted to federal aid eligible roads, and that's part of the reason that the recommendation list you have. Council Member Murdock replied many of those were federal aid money. Mr. McNamara replied there could have been some overlap. That was part of the reason for the different list, and the money that is available through federal aid is roughly \$180,000. Mayor Edmonds asked if those funds would be allocated in just 2017. Mr. McNamara responded in the affirmative. He explained in order not to lose the federal aid allocation the City will need to find a match, and find projects that are on federal aid eligible roads.

Council Member Murdock asked if the City has \$300,000 in Act 51 funds the City would be able to add another project. Mr. McNamara responded in the affirmative, but the funding for that project would not be able to mix with Federal Aid.

Mayor Edmonds directed City Manager McMullan to work with DPS Director Kirton to create a master schedule of projects and available funding. Council Member Murdock added once Council is able to establish funding amounts it can receive project recommendations from staff.

Economic Development Director Ernat stated part of the purpose for creating the Capital Improvement Plan is the City is required to have one by the GFOA and Redevelopment Ready Communities. When OHM brought this to the City the purpose was to have a plan in place for when new funding becomes available. This will not replace Council policy, but it will allow staff to apply for grants as they become available. This will not replace Council policy and will not forbid the City from completed other projects, but it will allow staff to apply for grants as they become available.

DPS Director Kirton explained Act 51 funds are used for snow removal, and depending on how much snow falls it might decrease funds available to complete road projects.

Council Member Murdock stated there are funds specifically for roads, and it is his intention to plan what to do with this funds. He explained this is a budgetary question, and said the Capital Improvement Plan (CIP) was already approved by Council. Ms. Ernat responded the CIP does not include any roads, which is the intention of adding this document to the Plan. She added at the next Council agenda will include a resolution adding this document to the CIP.

A. DISCUSSION ITEMS –

— Fiscal Year 2017-2018 Goal Setting Discussion

Interim City Manager McMullan provided an overview of last year's goals, and future goals. She explained approved goals from last year were difficult to meet as a result of the failed millage. She introduced John Kaczor, Principal at Municipal Analytics.

John Kaczor, Principal at Municipal Analytics, provided a presentation on the City's current financial position.

Mayor Edmonds stated the City has not received the \$1.2 million in mandated state revenue sharing in some time. Mr. Kaczor responded the complexity of the revenue stream is something that residents do not understand. If municipality's only revenue streams were taxes they would be easier to control, but would be highly susceptible to changes in property value.

Council Member Murdock stated if the City had another \$700,000 in revenue it would it would assist in stabilizing the City. Mr. Kaczor responded in the affirmative.

Mayor Edmonds asked for the lawsuit Michigan municipalities have filled against the state for withholding mandated revenue sharing. City Attorney Barr responded Council would need to speak with the City's lobbyist. Ms. McMullan stated replied she would contact Mr. Profit for an update. Mr. Kaczor added the state is also discussing eliminating the state income tax, which begs the question where will the money come from for state operations if not the state income tax.

Council Member Murdock stated the City's debt is divided into three segments, one could be covered by 2.3 mills levied, another that isn't covered and the last in the amount of \$700,000. Mr. Kaczor interjected the final segment has been decreased to \$270,000. Mr. Murdock asked what would happen if the entire debt would be paid by a millage approved by voters. Mr. Kaczor responded he has not examined that possibility. Council Member Robb responded in order the City would need to levy 3.25 mills in order to cover the full debt. Mayor Edmonds asked how much 3.25 mills would generate. Mr. Robb responded \$950,000. Mr. Kaczor added that amount would pay both series A and B debt service. He added the ballot language would provide the City could levy up to a certain amount, but will have the option to levy less.

Mayor Edmonds asked if the increased gas tax is factored into this model. Mr. Kaczor responded it is not. Fiscal Services Director interjected the tax would have already been factored into the model.

Mayor Edmonds stated many municipalities have been successful in cutting healthcare costs through wellness programs. She asked what kind of savings those efforts could create. Mr. Kaczor responded the City is already seeing the savings because it has already switched. He explained the volatility is removed from the premium costs. Ms. Edmonds asked how a wellness program would increase those savings, and how they are structured. Mr. Kaczor responded he does not have exact information on the savings. Council Member Robb replied the City is not offering real wellness programs. Mr. Kaczor responded there are many forms of wellness programs.

Council Member Vogt stated the spike in 2020 is when the road money would become available. Mr. Kaczor responded he wanted to be certain that it was in the model, but it really is a "money in, money out" situation.

Mr. Kirton asked what City's financial position in the next five years. Mr. Kaczor responded the City's position is much better than it was five years ago, but it is still a downward trend. The City is in a structural deficit that needs additional revenue.

Mayor Edmonds stated she would like the department heads to highlight two items from their departmental report.

Fire Chief Anthouard stated depending on the Department receiving the SAFER grant changes goals of the department. He stated the mutual aid agreement with the Township provides that both the Township and the City would respond to calls together, which allows need for only one dispatch center.

Mayor Edmonds asked for a status of the solar panels. Chief Anthouard responded they are working well.

Mayor Edmonds stated one of the needed improvements listed in the Fire Department goals is improved dispatch, and asked for clarification. Chief Anthouard responded when a person calls 911 dispatch can move slowly because it begins with the County Dispatch, then to Huron Valley Ambulance, and to Ypsilanti. He explained there are new technologies that are becoming available that could alleviate this problem.

Mayor Edmonds asked if the Fire Department has the expertise needed for grant writing. Chief DeGiusti responded he has been able to solicit help from other departments.

Council Member Vogt asked how many firefighters are trained as paramedics. Chief Anthouard responded seven. Mayor Edmonds asked if the City pays for that training. Chief Anthouard responded it is paid for by the individual firefighter.

Council Member Richardson asked if the City passing an ordinance on the non-solicitation of immigration status would affect the City being awarded the SAFER grant. Chief Anthouard responded he is not certain, and explained the application does not ask for that information. Mayor Edmonds stated there is no legal explanation of sanctuary cities, and Ypsilanti's ordinance does not go to the degree that other sanctuary cities do. Council Member Bashert stated Council should be very proud of the ordinance it is working on, but it is not a sanctuary ordinance. Council Member Murdock stated the federal government has not defined what a sanctuary city is. Ms. Richardson added given the volatility of the Executive Branch of the government is difficult what will be the result. Mr. Murdock stated he is much more curious of what will happen at the state level because it involves much more money.

Police Chief DeGiusti stated one of the major goals from this past year was to stabilize the workforce, and that goal was been achieved. The department is currently at the budgeted 29 officers, and they have all completed training. The diversity has also been increased by adding two female officers. The nationwide average for female officers is 12% and Ypsilanti has 25%. He said the goals for this coming year mostly will not require additional funding except for \$2,700 to fund the Michigan Associations of Police Chiefs accreditation of Ypsilanti Police Department policies.

Council Member Richardson asked how many officers in the department are African American. Chief DeGiusti responded six or seven.

Mayor Edmonds asked what other languages police officers can speak. Chief DeGiusti responded one officer is fluent in Spanish, and others that have skills in conversational Spanish. Ms. Edmonds asked if any officers are able to speak Arabic. Chief DeGiusti responded no. Ms. Edmonds replied ideally that would be useful.

Council Member Bashert stated if the department reached 47 officers, as the Chief outlined in his report, the department could participate in community policing. She asked if the millage was passed would the department be able to be at that level. Chief DeGiusti responded no, and explained the 47 includes non-officer employees. The number of officers would be 41.

Mayor Edmonds asked for explanation in the trends in police calls and response times. Chief DeGiusti responded there was a reduction across the board in major crimes, and he hopes it is because the department is being effective, but it is hard to say for certain. Ms. Edmonds stated the response time was cut in half between 2014 and 2015. Chief DeGiusti responded part of that can be equated to the increase of officers in the field. He further explained the data is based on all runs not just emergencies, which can skew the data. The 911 reports state the response time as two to three minutes.

Mayor Edmonds asked what other areas the Washtenaw County Safety Alliance other than gang issues has been effective. Chief DeGiusti responded currently the alliance is specific to coordination, and is not actively using joint patrols. The department has also received training on how to approach mental health issues from the County. Overall, the alliance has been very profitable for all participants.

Mayor Edmonds asked if there is an increase on enforcement of sex trafficking. Chief DeGiusti responded no. He explained there were specific incidents that occurred in the City, but the action is more responsive rather than proactive. Council Member Richardson stated there was a location on Madison that was supposed to involve the Federal Government. Chief DeGiusti responded the department had a car parked outside the house, which proved effective. He further explained the Federal Government is no longer pursuing the matter because it seemed to only involve one location.

Council Member Bashert asked for an update of the work done by the Community-Police and Black Lives Matter Task Force, and how it fits in with the outlined goals. Chief DeGiusti responded he has not regularly attended those meetings, but he does have ideas regarding the Review Commission that is currently being discussed.

Mayor Edmonds stated the Police Department has begun carrying Narcan to combat opioid overdose, and recently two lives were saved. She asked if there were any additional lives saved as a result of officers carrying Narcan. Chief DeGiusti responded there have been a few, but on that day the same officer saved two people during his shift.

Mayor Edmonds asked about EMU installing cameras that are directed toward the City. Chief DeGiusti responded he does not have much information on that, and in the past the idea of public cameras was not something supported by Council. Ms. Edmonds asked Chief DeGiusti's thoughts on public cameras. Chief DeGiusti responded he is in support of public surveillance. However, he does not think it is a deterrent, but are an excellent investigative tool. Ms. Edmonds stated there has been talk about EMU installing cameras off campus as well. Council Member Bashert asked what the downside would be of installing cameras. Chief DeGiusti responded from a police standpoint there isn't a downside.

Council Member Murdock stated EMU has also discussed installing cameras that are directed toward Cross St. instead of directed at campus. Mayor Edmonds stated this is a policy decision that Council should discuss. Mr. Murdock stated the Mayor was part of discussions had by the DDA for some time. Ms. Edmonds responded she was a part of those discussions, but this is a more broad discussion.

Fiscal Services Director Marilou Uy stated Fiscal Services has digitized all of its records, saving money on storage. She stated a goal for next year is partner with Human Resources to utilize the HR module in Incode to extract benefits data for budget preparation. This will assist in saving time and minimizing error.

Mayor Edmonds highlighted the intern program in the Fiscal Services Department. Ms. Uy responded the department is lucky to have two unpaid interns. Ms. Edmonds added the department also created a training program and a mechanism to assess the interns to get them ready for the workforce. Ms. Edmonds stated it is something to be commended and could be a story of how the City has partnered with university during lean budgetary times.

Interim City Clerk Andrew Hellenga stated in 2016 the Clerk Department had four elections that all went very smoothly. The Department was down a person for November General, which was a very large election, and the department registered an additional 2,500 voters. He said currently the department has \$2,000 budget per precinct for replacing voting equipment, which will be used with Help America Vote Act (HAVA) funds to help with purchasing. The bid includes three vendors, which all provide similar documentation as the current machines do, as well as modem

into the County. The new equipment will not jam as easily as the current equipment that is years past their estimated use time. The new equipment should help to create more efficient elections and quicker lines at the polls.

Mayor Edmonds mentioned the establishment of two new polling locations.

Council Member Bashert stated she is pleased the Treasury is now accepting VISA for payments. She asked how much the voting machines will cost, and if the funds budgeted are necessary. Mr. Hellenga responded the County advised each jurisdiction to budget \$1,500 to \$2,000 for each precinct, and that each precinct could see a total cost of around \$10,000.

Mayor Edmonds stated the report stated several new election inspectors were recruited that may have been more effective. Mr. Hellenga responded for the November General there were around 25 to 30 new inspectors, who were younger and more technologically savvy. This was very helpful in the operation of the electronic pollbook.

Department of Public Service Director Stan Kirton stated the City Tot Lots have been completed. The City partnered with EMU and MDOT to construct a mid-block crossing on Washtenaw. Also, the City received a grant of around \$25,000 for the inconvenience of the sub-station. He said the goals for next year are to maintain City assets, continue striving for energy efficiency, and continue to upgrade the LED street lighting initiative.

Council Member Bashert asked when a City trees is removed is it replaced. Mr. Kirton responded if requested a replacement it would be put on the tree planting list. He explained the protocol is to allow the roots to die before it is replaced, which is around a year.

Council Member Richardson stated she noticed a light pole that was cracked on Harriet. Mr. Kirton responded he is aware and he will follow-up with DTE. Ms. Richardson stated there are barriers around it, but it still looked unsafe. Mr. Kirton added if DTE felt it was an imminent danger DTE would have replaced it immediately.

Council Member Vogt stated on Hewitt north of Washtenaw near the Convocation Center could benefit from adding another street light. He explained he can see people at night on the Border to Border Trail in the dark, and feels that it is a safety issue. Mr. Kirton replied he will contact EMU to see if they would be willing to add a light. Mr. Vogt added there is a pole in place and would only require the addition of a light.

Council Member Richardson stated the street lights were out at Spring St. and Huron this past Saturday, but were back on Sunday. She asked the cause of the malfunction. Mr. Kirton responded it might have been a temporary power outage.

Council Member Bashert stated she is appreciative of the LED conversions that have taken place. Mr. Kirton responded Ypsilanti was one of the first cities in the state that converted its lights to LED.

Mayor Edmonds outlined three goals; continuing pursuit to reduce the City's carbon footprint, HVAC conservation, especially at City Hall, and a number of possibilities in the realm of recycling. She stated she was pleased to see the recommendation for the summer youth hire.

Economic Development Beth Ernat stated the highlight for the Building Department goals of 2016 was the hiring of a second building inspector. Unfortunately, shortly after that hire the department did lose an inspector to medical leave. The Parkridge development, Paradise Manor, and the scatter site housing inspections are underway, and inspections of the Towne Center also continue. The biggest goal for 2017 is improving the amount of certificates of occupancies and incorporating that process with the business license program. The Planning Department has had a very good year; the Water Street trail was installed, and continued remediation of the Water Street site, the installation of the solar array at the Highland Park Cemetery. The future goals of the department are the sale of City owned property, preparing for the Master Plan update process, and future changes of the medical marijuana legislation. She a presentation will be given at a Council meeting in March. The Economic Development Department is very pleased with the progress of the Thompson Block, which has been sold. She said the department has been successful in grant applications for blight issues. She said the biggest goal for the combined departments is going to be a comprehensive parking study. She stated the Historic District Commission was able to promulgate rules and revise its ordinance.

Council Member Robb asked for a two year projection of the Water Street Development. Ms. Ernat responded in the past couple months the City has received several calls of interest, however none to the point of a letter of interest. She has had three meetings to discuss possible multi-acre developments, but most likely there will not be anything in ground within two years. Mr. Robb stated the reason he asks is the department was built up to address Water Street and now the City is getting ready to wind down the department. He added he isn't very optimistic about the Water Street development, and his goals do not even include Water Street.

Council Member Bashert asked if there has been progress in possible litigation regarding the Towne Center. Ms. Ernat responded litigation is being sought through Legal Aid and not by the City.

Downtown Development Director Joe Meyers stated the Community and Economic Development Department took over control of the DDA in 2016. He said there have been some successes during that time including stabilizing its finances. A key component that has been implemented is the business interaction component, in which staff visits each business to understand what is going on in the City. He said goals for next year are to work on parking and continue to address the downtown trash issue.

Council Member Bashert asked when patrons visit Go! Ice Cream! this summer will they be facing garbage cans. Mr. Meyers responded unfortunately, yes. He explained the owners of the building next to Go! Ice Cream! have decided not to participate in the DDA Dumpster program.

Council Member Robb asked what is charged per month per unit. Mr. Meyers responded it depends on the use of the building, that specific building is residential and the fee is \$25 per unit. Mr. Robb stated it would be in the best interest of the downtown to remove those trashcans. Mr. Meyers stated if the DDA were to cut every other service it still would not be able to fund the trash service without participant buy-in.

Council Member Bashert stated the downtown has redundant garbage service. Mr. Meyers responded not exactly. Mayor Edmonds explained some business are serviced by dumpsters and some are not, depending on where a business is. Mr. Meyers responded the City trash pick-up allows for three cans per unit. If a business produces more than that amount they would require a dumpster, however there is not space for each business to have its own dumpster. Council

Member Robb stated the DDA needs to speak with counsel to speak to other communities because Ann Arbor does not allow the downtown residents and businesses to put out trash cans. Mr. Meyers responded the DDA spoke with counsel and their opinion that nothing can be done.

Council Member Bashert asked if the City has control of the garbage routes. She stated she thinks redundancy is wasteful. Mayor Edmonds stated the DDA has a separate contract for the dumpsters. Ms. Bashert responded the City controls the routes to pick-up City trash, and should consider exercising that control. Council Member Vogt asked if the City should do what it thinks should be done regardless of the wishes of property owners. Ms. Bashert responded in the affirmative, and said it is not respectful to other businesses.

Council Member Murdock stated Ann Arbor City contracts the collection of trash in the downtown. Mayor Edmonds added DDA Board Member Andrew O'Neil owns property in Ann Arbor and Ypsilanti, and says the DDA prices for dumpster service are much lower than in Ann Arbor.

Robb

Council Member Robb stated the City brought parking enforcement in house a few years ago, and it has been a disaster. It has cost the City around a million dollars in revenue, partly because for two full years the City did not write parking tickets. The City also lost revenue from 13,000 parking tickets because the file the City received from Duncan Solutions was not readable. He said since the City created a Parking Bureau on December 1, 2015 13,469 tickets have been written. Of those ticket 7,191, leaving 6,278 tickets have not been paid. Meaning the City is only collecting 58% of potential revenue. He explained the problem is the City does not have a mechanism to collect revenue. The equipment the Parking Enforcement Officers use does not tell them how many outstanding tickets a particular vehicle has, making it difficult to know if that vehicle is at the six ticket limit to be towed. He stated currently the City uses the court for collection who only sends the City a check each month, without data as to which tickets it is for. The City used Duncan Solutions for nine years, and averaged \$183,000 a year. Mr. Robb stated the problem is if someone doesn't pay their ticket it will never be paid because there is not collections mechanism.

Council Member Robb suggested removing the 24 hour grace period for expired meter tickets. By changing the fee schedule the City can generate an additional \$103,000, only considering the 53% of tickets collected. If the City collects 100% the amount increases \$229,000 in additional revenue a year. This does not consider additional fine increases if not paid. He explained in Ypsilanti if tickets are not paid nothing happens, but in Detroit if a driver has unpaid tickets they would not be able to renew their license.

Council Member Robb stated his goal is for the City to release a Request for Proposals (RFP) for a third party vendor. He suggested the City create a new system that allows license plates of vehicles with unpaid tickets to be registered with the Secretary of State. He stated he would like to move away from using the court system if possible because issues with collection. He added the lost revenue is an entire Water Street debt payment.

Council Member Robb stated he would like to see a job instruction sheet in order to create a plan for new employees. He said See. Click. Fix is a great system, but it does have its problems. He mentioned an issue of submitted tickets not being closed in a reasonable time. This was mentioned by Mr. McClary specifically in his interview for City Manager. Another example of how a job instruction sheet could assist is for Parking Enforcement. He said if Parking Enforcement

were to carry batteries for parking meters they could be easily changed during the activities of that job. However, Council was informed that it would be against union rules to allow Parking Enforcement to complete that task. He asked how it could be against union rules if both positions are in AFSCME. Chief DeGiusti responded it is outside their job description. Mr. Robb replied all three union contracts will be negotiated this year, and that will be something that should be negotiated.

Council Member Robb stated pensions have dropped to 58% funded, and he wants to understand if the City will need to increase the tax levy to sustain the fund. His plan is to fund the pensions at 80%, which would mean the City would need to levy 34.6 mils. This is not a reasonable scenario, but getting to 80% should be a goal of the City.

Council Member Robb stated he would like the City to move to a wellness plan, and with the union contract negotiations upon us now is the time. He explained a wellness plan should outline goals for an employee, and if those goals are not met their deductible would increase.

Council Member Robb stated with all four union contracts up for negotiations he would proposed Council begin meeting in Closed Session 30 minutes after each meeting to begin these discussions.

Council Member Robb stated his last goal is for Council to receive meeting packets a week before the meeting. This would allow Council time to review material and ask staff questions. He added he would like the Clerk Department to create a policy of what is expected when submitting items for approval.

Council Member Robb stated except for parking enforcement, these are all low level process goals he would like to see implemented.

Bashert

Council Member Bashert stated she thinks the City has an incredible, overworked staff and a lot is demanded of them. However, she would like the staff to undergo training in service because she would love the citizens of this City to respect the staff as much as they deserve. She stated she is very concerned about the budget, and much of the cuts made by Council were more stop gaps than actual solutions.

Edmonds

Mayor Edmonds stated the two goals she would like to highlight are one, improving both internal and external communication. She has spoken with EMU's Vice-President of Communications to possibly provide some training. She added Council could also benefit from increased communications skills within that body.

Vogt

Council Member Vogt stated he would like to emphasize Council Member Robb's statements regarding the level of City fees. He agreed they are too low and the City underestimates what it costs to carryout City business. Most importantly he agrees with issues with parking enforcement, and emphasized the collection of outstanding fines. This might include a letter sent after 30 days stating the violator's car will be towed, and would be taken to court. He agreed

with Council Member Bashert that the City needs to actually balance the budget without a millage. He isn't sure how exactly that can be done, but it must be a priority. He added no City funds, including street and road funds, should be allocated to construct a rail platform, those funds should all come from other entities.

Murdock

Council Member Murdock stated getting the pension fund under control should be a top priority. He isn't sure it needs to be fully funded, or if it's possible, and could be a part of contract negotiations, as well as other things mentioned at this meeting. He said he supports providing customer service training for staff. He stated he would like to see a four, or five year road funding plan. He is concerned about the City's ability to maintain the City's park system, and would like to see strategies on how to improve. He said he would like to continue to maintain the City's vigilance in protecting residents from negative impacts of state and federal policies.

Brown

Mayor Pro-Tem Brown agreed with Council Member Robb in adjusting fines and fees. She said she would like to see improved communication amongst Council Members. She would like to see external communication improved, especially through social media, website, and See. Click. Fix. The implementation of a Community-Police Board as well as community involvement to meet the needs of the community. She added increased partnership with Eastern Michigan University.

Richardson

Council Member Richardson agreed that if the City is losing that much parking ticket revenue it needs to be improved. She agreed in enhancing community and police relationship, and said community policing is a philosophy and if adopted it could be implemented. She also agreed in enhancing communication among Council Members. She added increasing "town and gown" relationships with EMU.

DPS Director Stan Kirton stated during the last City Manager's tenure two or three salary comparison studies were completed. He said non-union employees have received one raise in the last eight years. Council is discussing spending money on training and other things, and asked about employee compensation. Mayor Edmonds stated that is something the new City Manager could address. Council Member Richardson agreed with Mr. Kirton, and said the City needs to take care of its employees.

Council Member Murdock suggested creation of two budgets; one including with and one without the millage. Council agreed.

Mayor Edmonds stated she would like to see an improvement in code compliance. This is something that each Council Member has heard from the community. She said it should not be something that is difficult to fix. Council Member Richardson asked if that is a result of staff levels. Ms. Edmonds responded she is not sure of the reason. Chief DeGiusti responded it is partially because there is only one Ordinance Officer. He is very busy and said his citation amount is in the hundreds as well as issued abatements. He stated again the volume of work is too much for one person. Council Member Bashert asked if an Ordinance Officer pays for themselves. Chief DeGiusti responded he does not know the answer to that. Council Member Robb responded the officer does pay for themselves, but the philosophy of the position is to

correct the problem not make money. Mr. Robb stated if the Ordinance Officer is not able to complete their job Council needs to know.

B. AUDIENCE PARTICIPATION –

None

C. REMARKS FROM THE MAYOR –

None

D. COMMUNICATIONS FROM THE MAYOR –

Nominations

Planning Commission

Christopher Madigan
223 N River St. Apt 6
Ypsilanti, MI 48198
Exp. 1/2020

E. ADJOURNMENT –

OFFERED BY: Council Member Richardson
SECONDED BY: Mayor Pro-Tem Richardson

On a voice vote, the motion carried, and the meeting adjourned at 10:04 p.m.



REQUEST FOR LEGISLATION

FROM: Marilou Uy, Fiscal Services Director

SUBJECT: Request for budget amendments changing the loan to a fund transfer for the uncollected reimbursement from MNRTF of \$328,490

DATE: March 21, 2017

Summary:

The City requested reimbursement from the Michigan Department Natural Resources - Grants Management on August 17, 2016 for the River's Edge Linear Park & Trail and Ypsilanti Heritage Bridge expenditures totaling \$300,000 and \$28,490 respectively.

To support the Capital Improvement fund's cash shortage, the General Fund last year loaned \$328,490 with the expectation that the request for reimbursements will be collected within a reasonable amount of time.

As of this date, the City has not collected these reimbursements. Therefore, I recommend amending the budget changing the loan to a fund transfer. This means that when the City collects the reimbursements, the revenue will be recorded in the General Fund instead of the Capital Improvement Fund. Below are the recommended budget amendments:

Transfer Out to Capital Imp Fund	101-7-9670-999-13	\$328,490
Transfer in from General Fund	414-4-0000-699-01	\$328,490

Upon receipt of payment from MNRTF, the General Fund will record:

CASH	101-001-01	\$328,490
MNRTF Grant REIMBURSEMENT	101-4-0000-539-00	\$328,490

Please feel free to contact me at 734-483-1105 or by e-mail at muy@cityofypsilanti.com if you have questions.

RECOMMENDED ACTION: Approval

ATTACHMENTS: Proposed Resolution, Development Reimbursement Requests

CITY MANAGER APPROVAL: DDPM 3/15/17

COUNCIL AGENDA DATE: March 21, 2017

CITY MANAGER COMMENTS: _____

FINANCE DIRECTOR APPROVAL: _____



Resolution No. 2017- 067
March 21, 2017

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

WHEREAS The City requested reimbursement from the Michigan Department Natural Resources - Grants Management on August 17, 2016 for the River's Edge Linear Park & Trail and Ypsilanti Heritage Bridge expenditures amounting \$300,000 and \$28,490 respectively; and

WHEREAS To support the Capital Improvement fund's cash shortage, the General Fund last year loaned \$328,490 with the expectation that the request for reimbursements will be collected within a reasonable amount of time; and

WHEREAS As of this date, the City has not collected these reimbursements. Therefore, I recommend to amend the budget to change the loan to a fund transfer; and

WHEREAS the revenue will be recorded in the General Fund instead of the Capital Improvement Fund; and

NOW BE IT HEREBY RESOLVED that the Ypsilanti City Council approve the recommended budget amendments as follows:

Transfer Out to Capital Imp Fund	101-7-9670-999-13	\$328,490
Transfer in from General Fund	414-4-0000-699-01	\$328,490

Upon receipt of payment from MNRTF, the general Fund will record:

CASH	101-001-01	\$328,490
MNRTF Grant REIMBURSEMENT	101-4-0000-539-00	\$328,490

OFFERED BY: _____

SUPPORTED BY: _____

YES:

NO:

ABSENT:

VOTE:



Michigan Department of Natural Resources - Grants Management

DEVELOPMENT REIMBURSEMENT REQUEST

By Authority of: Parts 19, 703, 715 and 716 of Act 451, P.A. 1994, as amended, submission of this information is required to receive payment.

INFORMATION: Payments are made on a reimbursement basis for up to 80-90% of the grant amount. The final 10-20% will be withheld pending satisfactory project completion, inspection, and audit. Do not submit a final request until all construction is completed. All completed projects are subject to audit by the Michigan Department of Natural Resources.

SECTION 1 - PROJECT INFORMATION

DNR Project No. (i.e., TFX-XXX, 26-XXXX, RPXX-XXX) TF 12-120	Project Title RIVER'S EDGE LINEAR PARK&TRAIL	Employer Federal I.D. # (required for payment) 38-6004750
Grantee City of Ypsilanti, Washtenaw County	Contact Name Frances McMullan	
Address 1 South Huron	Contact Telephone (734) 483-1840	
City, State, ZIP, County Ypsilanti, MI 48197	Email fmcullan@cityofypsilanti.com	
Request No: (1, 2, 3, etc.) 2	Payment Requested ☐ Partial ☒ Final, all work must be completed and the Grantee must submit the following: ☐ Final Compliance Onsite Inspection Form ☐ Picture(s) of installed plaque ☐ Picture(s) of scope item(s) ☐ Certificate of Final Electrical Inspection for electrical lighting projects (ballfields, tennis courts, etc.), if applicable. ☐ Certificate of Occupancy for public buildings & structures (including picnic pavilions and gazebos), if applicable. ☐ Copy of Recorded Declaration and Notice (Trust Fund & Land and Water Conservation Grants Only)	

SECTION 2 - EXPENDITURE DETAIL

A. Total Expenditures on Previous Requests	\$ 464,418.09
B. Total Expenditures This Request	\$ 37,872.10
C. Total Expenditures To Date (2A + 2B, should include all expenditures against project)	\$ 502,290.19
D. Fund Amount Requested (% of Expenditures Specified in Project Agreement X B)	\$ 300,000.00

SECTION 3 - DISBURSEMENT DETAIL

Use separate sheet(s) for documentation of use of force account labor and equipment. Two copies of all documentation such as canceled checks, invoices, payroll data, contractor's statement, etc., must be enclosed with each request for reimbursement. If more space is needed, attach additional sheet(s) using the format below.

Date of Check	Check No.	Invoice Amount	Vendor Name (Check Issued To)	Project Scope Item
			Please see attached detail and	
			summary of construction and	
			engineering costs	

SECTION 4 - GRANTEE CERTIFICATION

I hereby certify that the information is complete and accurate and all expenditures for which reimbursement is requested are for eligible scope items as defined in the Project Agreement for the above project, and that all expenditures have been made during the project period as listed in the Project Agreement, and are identified and filed according to accounting procedures set forth by the Michigan Department of Natural Resources. I also certify that contractors listed were selected according to the procedures outlined in the Development Project Procedures booklet.

Frances McMullan [Signature] Interim City Manager 8-17-2016

Grantee's Signature

Title

Date

SECTION 5 - PROFESSIONAL CERTIFICATION

I hereby certify that the plans and specifications for the above project were developed in accordance with the procedures set forth by the Michigan Department of Natural Resources and that all work and materials for which payment is requested conform to those plans and specifications and have been inspected by me or by a qualified person under my supervision. If this is a final request for reimbursement, I further certify that I have inspected all materials or items purchased as part of this project and the assembly and installation of these materials/items, and found them to be satisfactory.

Steve A. Bouws [Signature] Senior Project Engineer 37563-MI 8-17-2016

Signature of Prime Professional

Title - (Architect, Engineer, Landscape Architect)

Registration No. & Issuing State

Date

Signature - Other Professional (as required)

Title - (Architect, Engineer, Landscape Architect)

Registration No. & Issuing State

Date

SECTION 6 - FOR DNR USE ONLY - AUDIT AND CERTIFICATION

Grant Amount	\$	
Less Previous Payments	(	)
Total Expenditures This Request		
Less Ineligible Costs or Reductions	(	)
% of Adjusted Expenditures		
Less Audit Amount 10% (20% for "First & Final")	(	)
TOTAL REIMBURSEMENT AMOUNT	\$	

Payments will not be processed without expenditure documentation and the required signatures.

Return this completed request along with two (2) copies of all attachments to:

Grants Management
Michigan Department of Natural Resources
PO Box 30425
Lansing MI 48909-7925

Please make a copy for your records

Authorized DNR Grant Payment Officer Signature	Date	Authorized DNR Grant Coordinator Signature	Date	Authorized DNR Engineer Signature	Date
--	------	--	------	-----------------------------------	------



Michigan Department of Natural Resources - Grants Management

DEVELOPMENT REIMBURSEMENT REQUEST

By Authority of: Parts 19, 703, 715 and 716 of Act 451, P.A. 1994, as amended, submission of this information is required to receive payment.

INFORMATION: Payments are made on a reimbursement basis for up to 80-90% of the grant amount. The final 10-20% will be withheld pending satisfactory project completion, inspection, and audit. Do not submit a final request until all construction is completed. All completed projects are subject to audit by the Michigan Department of Natural Resources.

SECTION 1 - PROJECT INFORMATION		
DNR Project No. (i.e., TFX-XXX, 26-XXXXX, RPXX-XXX) TF 11-120	Project Title Ypsilanti Heritage Bridge Develop	Employer Federal I.D. # (required for payment) 38-6004750
Grantee City of Ypsilanti, Washtenaw County	Contact Name Frances McMullan	
Address 1 South Huron	Contact Telephone (734) 483-1840	
City, State, ZIP, County Ypsilanti, MI 48197	Email fmcullen@cityofypsilanti.com	
Request No: (1, 2, 3, etc.) 2	Payment Requested ☐ Partial ☒ Final, all work must be completed and the Grantee must submit the following: ☐ Final Compliance Onsite Inspection Form ☐ Picture(s) of installed plaque ☐ Picture(s) of scope item(s) ☐ Certificate of Final Electrical Inspection for electrical lighting projects (ballfields, tennis courts, etc.), if applicable. ☐ Certificate of Occupancy for public buildings & structures (including picnic pavilions and gazebos), if applicable. ☐ Copy of Recorded Declaration and Notice (Trust Fund & Land and Water Conservation Grants Only)	

SECTION 2 - EXPENDITURE DETAIL

A. Total Expenditures on Previous Requests	\$ 916,296.32
B. Total Expenditures This Request	\$ 93,589.98
C. Total Expenditures To Date (2A + 2B, should include all expenditures against project)	\$ 1,009,886.30
D. Fund Amount Requested (% of Expenditures Specified in Project Agreement X B)	\$ 28,940.00

SECTION 3 - DISBURSEMENT DETAIL

Use separate sheet(s) for documentation of use of force account labor and equipment. Two copies of all documentation such as canceled checks, invoices, payroll data, contractor's statement, etc., must be enclosed with each request for reimbursement. If more space is needed, attach additional sheet(s) using the format below.

Date of Check	Check No.	Invoice Amount	Vendor Name (Check Issued To)	Project Scope Item
			Please see attached detail and	
			summary of construction and	
			engineering costs	

SECTION 4 - GRANTEE CERTIFICATION

I hereby certify that the information is complete and accurate and all expenditures for which reimbursement is requested are for eligible scope items as defined in the Project Agreement for the above project, and that all expenditures have been made during the project period as listed in the Project Agreement, and are identified and filed according to accounting procedures set forth by the Michigan Department of Natural Resources. I also certify that contractors listed were selected according to the procedures outlined in the Development Project Procedures booklet.

Frances McMullan [Signature] Interim City Manager 8-17-2016
Grantee's Signature Title Date

SECTION 5 - PROFESSIONAL CERTIFICATION

I hereby certify that the plans and specifications for the above project were developed in accordance with the procedures set forth by the Michigan Department of Natural Resources and that all work and materials for which payment is requested conform to those plans and specifications and have been inspected by me or by a qualified person under my supervision. If this is a final request for reimbursement, I further certify that I have inspected all materials or items purchased as part of this project and the assembly and installation of these materials/items, and found them to be satisfactory.

Steve A. Bou [Signature] Senior Project Engineer 37563-MI 8-17-2016
Signature of Prime Professional Title - (Architect, Engineer, Landscape Architect) Registration No. & Issuing State Date
Signature - Other Professional (as required) Title - (Architect, Engineer, Landscape Architect) Registration No. & Issuing State Date

SECTION 6 - FOR DNR USE ONLY - AUDIT AND CERTIFICATION

Grant Amount \$ _____
Less Previous Payments () _____
Total Expenditures This Request _____
Less Ineligible Costs or Reductions () _____
% of Adjusted Expenditures _____
Less Audit Amount 10% (20% for "First & Final") () _____
TOTAL REIMBURSEMENT AMOUNT \$ _____

Payments will not be processed without expenditure documentation and the required signatures.

Return this completed request along with two (2) copies of all attachments to:

Grants Management
Michigan Department of Natural Resources
PO Box 30425
Lansing MI 48909-7925

Please make a copy for your records

Authorized DNR Grant Payment Officer Signature	Date	Authorized DNR Grant Coordinator Signature	Date	Authorized DNR Engineer Signature	Date
--	------	--	------	-----------------------------------	------



REQUEST FOR LEGISLATION

16 March 2017

From: Bonnie Wessler, City Planner

Subject: Zoning Ordinance: 2015-17 Update

SUMMARY & BACKGROUND:

The zoning ordinance underwent a significant overhaul in 2014, and was enacted in January 2015. One of the major changes as part of this was a shift away from a wholly use-based zoning code to a code that contained form-based elements. The new code retained the structure of the old code, which itself had been added to and modified throughout the years, resulting in duplicate or missing definitions, incorrect code references, and out-of-date illustrations. Although a number of those errors were addressed in the 2014 update, the update contained a number of bugs itself, and the old structure was not conducive to understanding the new code. In addition, in late 2015 the Supreme Court made a decision in the case of *Reed vs Town of Gilbert, Arizona* that greatly affected our sign code; the content or intent of the sign can no longer be a basis for regulation.

The draft code before Council is a significant improvement in organization and clarity. A summary of the changes are as follows, and included in the attached list of changes:

- All definitions are in one section for definitions, rather than being scattered throughout, which occasionally led to duplication and conflict.
- The sign code is reorganized, regulating by zoning district and use of the parcel, rather than by sign intent. Other types of district-specific requirements, such as fence heights, are now found in the zoning district section, rather than a separate section.
- Graphics have been updated or clarified as needed.
- Uses in the form-based districts that were intended to be linked to specific building types are now linked.
- Regulations where requirements were unclear have largely been clarified, such as when certain required elements could "stack" to satisfy two requirements, such as counting one tree for both screening requirements and parking lot landscaping requirements.
- Gendered language was removed, typos were corrected, and the numbering within the chapter has been made consistent.
- No changes to zoning district boundaries were made as part of this rezoning, and no additional nonconformities were created, with the possible exception of signs.
- This update includes the updated language for the one-and-two family rebuild clause in the PMD zoning district.
- Note: six changes were made between the February presentation and this presentation. Those changes are highlighted in yellow on the list of changes. Three of the changes were typo &/or copy-paste error/oversight corrections; one was a clarification of intent (HC parking); two were corrections of terms to new schema (signs, healthcare offices).

This update was reviewed by an outside zoning firm, Giffels-Webster (Clearzoning), enabled by technical grant assistance from MEDC as a result of our Redevelopment Ready status. Their feedback was incorporated into this update to the extent we were able; it did also include a

strong recommendation to update our "communication devices" section, which is out of step with the current regulatory environment. Our legal team also reviewed the draft; their feedback was also incorporated. Both reviews took place in August through November. A Planning Commission subcommittee was formed to review and solicit input throughout the process. The Planning Commission recommended that Council adopt this ordinance in August at public hearing, and again in December at public hearing, after the feedback from Giffels-Webster and legal was incorporated.

RECOMMENDED ACTION: Approval

ATTACHMENTS: Annotated Draft Zoning Ordinance (changes explained and all references highlighted) (AVAILABLE ONLINE)
Non-annotated Draft Zoning Ordinance (as would be posted) (AVAILABLE ONLINE)
Current Zoning Ordinance and Map (AVAILABLE ONLINE)
List of changes (in printed copies)
Memo on sign ordinance changes
Sign ordinance legal markup (Jan 2016)
Current sign ordinance
Proposed sign ordinance

CITY MANAGER APPROVAL: _____ COUNCIL AGENDA DATE: _____

CITY MANAGER COMMENTS: _____

FISCAL SERVICES DIRECTOR APPROVAL: _____



Resolution No. 2017- 068
21 March 2017

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

Whereas, The City of Ypsilanti has adopted a comprehensive Master Plan, "Shape Ypsi;" and

Whereas, the City of Ypsilanti is desirous of fulfilling the goals of the Master Plan; and

Whereas, the Zoning Ordinance will help to implement those goals of creating a safe, sustainable, and diverse Ypsilanti;

Now therefore be it resolved that the Ypsilanti City Council approve the amendments to Chapter 122 of the City's Code of Ordinances.

OFFERED BY: _____

SUPPORTED BY: _____

YES: NO: ABSENT: VOTE:

Ordinance No. 1284

An Ordinance Entitled "Zoning Ordinance Revision"

THE CITY OF YPSILANTI ORDAINS:

(see attachment – ZOUpdate- 03- ZO_BW20170315_plain.pdf)

MADE, PASSED, AND ADOPTED BY THE YPSILANTI CITY COUNCIL THIS _____
DAY OF _____, 2017

Andrew Hellenga, Interim City Clerk

Attest

I do hereby confirm that the above Ordinance No. _____ was published in the
Washtenaw Legal News on the _____ day of _____, 2017.

Andrew Hellenga, Interim City Clerk

CERTIFICATE OF ADOPTING

I hereby certify that the foregoing is a true copy of the Ordinance passed at the regular
meeting of the City Council held on the _____ day of _____, 2017.

Andrew Hellenga, Interim City Clerk

Notice Published: _____

First Reading: _____

Second Reading: _____

Published: _____

Effective Date: _____

new section number	original section number	title	change summary	rationale
101	277	steps for use of regulations	combined two "quick code guides"	ease of use, elimination of one of the branch paths. PC reviewed/approved July.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	brought in all definitions throughout code that were found to the definitions section	
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	combined duplicates ("signs," "building, completely enclosed/enclosed building," "setback / setback, front, side, and rear yard"	
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	bed and breakfast / inn combined to one listing	were always combined in permissible uses. Different only in who managed it (manager or owner-occupant). PC concurred.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"building code" generalized to ch 18, rather than ch 18, art III.	more useful in practice to refer to full chapter.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"change of use" changed	reflect how the term is actually used.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"condominium" changed	Regulatory language removed.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"condominium lot" changed	was listed as "lot" in the "site condominium" section. Altered to "condominium lot" when moved to definitions.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"mobile home condominium project" removed	completely unused in the text.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"building frontage" removed	was brought from signs definition. Strangely worded; obvious concept.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"private frontage" moved	was from 122-274. expanded, now absent that context.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"public frontage" added	term was used, but not defined. Definition from form-based code resource.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"garage" changed	removed regulatory language
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"hedge" removed	unused. Dictionary definition suffices.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"home occupation" changed	removed regulatory language
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"housing code" removed	under "building code" definition/ch 18
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"inn" removed	combined with b&b

new section number	original section number	title	change summary	rationale
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"medical or dental office" "medical or dental clinic" combined	differentiation was based on number of practitioners. Does not reflect current multi-practitioner/rotation practitioner model that is becoming popular. Combined into "medical or dental clinic or office"; removed # practitioner distinction. Size distinction made in each indiv district unless no size limits. PC concurred.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"microbrewer/small distiller/small wine maker" changed	portions redundant. Cleaned up.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"motor home" removed	defined under "vehicle, recreational"
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"mural" changed	had been defined as a sign. Changed to a style of ornamentation. PC concurred, legal concurred.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"parking, off-street" changed	removed regulatory language
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"passive solar structure" changed	now building, not structure; included "greenhouse," not just hoophouse. Simplified.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"personal service establishment" added	not previously defined, but used frequently. Combined several "such as"es from previous codes and simplified.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"planned unit development" changed	removed regulatory language
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"address sign" removed	gilbert v reed.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"building directory sign" removed	gilbert v reed.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"damaged sign" removed	dictionary definition suffices. Potential also to consider as "abandoned sign"
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"directional sign" removed	gilbert v reed.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"election sign" removed	gilbert v reed.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"flag" removed	gilbert v reed.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"hanging sign" removed	now a type of building-mounted sign
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"historical sign" removed	gilbert v reed.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"monument sign" removed	now a type of free-standing sign

new section number	original section number	title	change summary	rationale
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"nameplate" removed	gilbert v reed.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"nonconforming sign" removed	covered under nonconforming structure.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"off-premises sign" removed	gilbert v reed.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"on-premises sign" removed	gilbert v reed.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"opinion sign" removed	gilbert v reed.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"pole sign" removed	now a type of free-standing sign
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"portable sign" removed	considered a type of temporary sign
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"residential entry sign" removed	now a type of free-standing sign
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"seasonal display" removed	type of ornamentation, not regulated. Definition was content-based.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"special event sign" removed	gilbert v reed.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"sign, animated" changed	simplified. "visible from the exterior of the building" is implied
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"sign, billboard" changed	had been defined as an off-premises sign. Content-based.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"electronically illuminated message sign" changed	changed name only, to "sign, electronic message."
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"sign, historic marker" added	intent is to exempt from size/quantity limitations; applies to existing signs like YHF plaques, SHPO signs, MotorCities, etc
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"sign, marquee" removed	a type of building-mounted sign. Didn't contribute anything to the signs section.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"site plan" changed	simplified, removed regulatory language.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"solar roof paneling" removed	not used outside of definitions.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"special use" changed	removed regulatory language
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"street, primary" changed	didn't provide for which street is considered primary in the case of a tie.

new section number	original section number	title	change summary	rationale
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"swale, vegetated/rock" "swale, biofiltration" combined	effectively the same thing.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"tree" changed	removed deciduous/evergreen distinction. Kept overall definition because of "a well-defined central stem".
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"use, residential" added	is required to make some distinctions for site regulations. Was used, but not defined, in previous code.
203	2, 3, 4, 5; 863; 602; 274; 734	definitions	"use, commercial" added	is required to make some distinctions for site regulations. Was used, but not defined, in previous code.
307	122 + 123	Levels of Review	table updated	approving bodies remained the same. Made more clear what triggered what level of review. Formatting changes.
309	126	Site Plans	added section "t"	state law requires special uses to have site plans. Replace "sketch plan" requirement for certain special uses with some waivers of info/limited site plan. Per GW review.
303	35, 98, 135	Fees	combined all "fees" to one section	
327	168	Duration of special use approval	changed time limits per GW feedback	time-limited SUP approvals generally do not hold up in court. Made so that the expiration period lines up with site plan expiration period.
335	35	Temporary use permit requirements	removed duplicative language (centralized in beginning); changed extensively temporary mobile food establishments	TMFE: added a way to be placed on unpaved surfaces. Removed PC questions (PC never reviews). Lightened plan requirements (onerous). Removed spacing requirements (nigh impossible if we want them in CBDs).
	35	Temporary use permit requirements	removed "temporary businesses in vacant storefronts"	effectively makes it more difficult to do a pop-up business by limiting them to C, NC, GC. Doesn't address parking requirements (often most onerous). As written, doesn't actually promote pop-up businesses.
352	867(b)	Signs of local historic significance	moved "signs of local historic significance" to nonconformities	more logical place for such a regulation.
391	53	Duties and Responsibilities of the Planning Commission	simplified (10 to 8 sections); added in required Land division act.	
397	93	General Procedures	removed info on voting on use variances	use variances eliminated in 2014.
400	231	Establishment of Districts	renamed "walkable urban areas" to "walkable urban districts"	slightly easier to call out as a bloc in the code.
all districts	all districts	Stormwater Control	removed as permissible accessory use	noted in "landscaping" as permissible in all districts as a site design feature.

new section number	original section number	title	change summary	rationale
all districts	all districts	Food Concession Sales	changed to "mobile food establishments"	was meant to refer to those permitted in 335/35, but language inconsistent "food concession sales" not found elsewhere. Made language consistent.
all districts	all districts	Purpose	Simplified.	Most "purpose" statements were descriptive, wordy, jargony, and repetitive. They still are fairly descriptive, but less wordy.
421	252	Permissible uses	Primary and Secondary Schools; Post-secondary educational institutions; Religious Institution all size-capped	Had not been a size cap previously. These uses, when very large, tend to dominate a neighborhood. 15ksq is a cap, albeit a generous one.
421	252	Permissible uses	Added back in "garage sales" as a permissible use	Hadn't been listed; really should have been. The strictures of 524 still apply.
422(b)	253(a)	Non-use and dimensional regulations	Changed the front yard setback for established neighborhoods	v2014 and previous had "the depth of the front yard must not be less than the average depth of the front yards of the existing buildings on each side". Didn't actually keep the house "in line" with the others (keep character); allowed it to be further back. Now reads "the depth of the front yard must be within the range so established [by the existing houses]"
422, etc	753	"corner lots"	Moved "corner lots" to applicable site tables.	753 contained info re: corner lots specifically for R1 & MD districts. Moved to site reg tables for R1 and MD.
422	667(2)(c)	detached accessory structures	no longer permitted in the street side yard	Generally, front-yard regs have applied to street side yards; the "accessory structures and uses" section even noted that structures were not permitted to encroach on the street side yard setback or in the street side yard at all . It was a bit conflicting as far as wording; we went with the more conservative/restrictive standard.
426	262	Permissible uses	added: group residences in single-family building type only, special use	A trend in multifamily housing development is "garden style units" or "terrace style units" - single-family homes, rented out to 4-5 unrelated people. Currently could only be accommodated in CN with a special use.
426	262	Permissible uses	added: townhomes/rowhomes	Had been omitted before. TMA identified it as one of the "missing middle" of building types.
426	262	Permissible uses	added: indoor recreation (accessory only)	substantially similar to "social facility for multiple family dwellings and their guests" - but clearer. "social facility" remains.
426	262	Permissible uses	added garage sales	
427	263, 794	Non-use and dimensional regulations	incorporated 794 into table of regulations	Simplicity and clarity. 794(6) only applied in the MD district.

new section number	original section number	title	change summary	rationale
431	651	Permissible uses	Unclassified uses clarification	Strange point of conflict. 651 stated that "unclassified uses" could be permitted in any district (subject to special use); only PMD listed them as permitted. Chose the more conservative route (appears to be the intended route)- eliminated 651, only permitting unclassified uses in PMD.
431	292	Permissible uses	"business and professional offices and showrooms..."	B&P offices/showrooms were a "permitted" use only when ancillary to a primary use. Changed the listing to B&P offices/showrooms as an accessory use.
431	292	Permissible uses	"radio and TV towers..." and "utility buildings..." and "construction and landscaping..." made permitted rather than special use	Notes from GW noted that a *lot* of our special-use industrial uses were just basic industrial uses- or even heavy commercial- and to look at removing the SUP requirement for some of them. Did so.
432	293	Non-use and dimensional regulations	Added max impervious coverage	Was not specifically called out. Landscape regs say at least 10% must be landscaped, thus, 90% max.
432	293	Non-use and dimensional regulations	removed slightly different setback from non-commercial districts	25' had been called for. Standard is 20' rear, 15' side. Possibly an accidental omission? Screening requirements were relocated for clarity, had been in this line item. Corrected in version 2017-03-14 and subsequent.
432	293	Non-use and dimensional regulations	added in requirements for accessory buildings	Fencing contains an error. Bad copy-paste from another section. Corrected in version 2017-03-14 and subsequent.
441	272	Permissible uses (core nhoods)	added "single-family attached" in townhome building type only in CN and CN-Mid	"townhome" building type had been permitted in CN & CN-Mid. However, the use type "single-family attached" or even just "single-family" was not- only "single-family detached." this clarifies and permits.
441	272	Permissible uses (core nhoods)	added "indoor recreation"	was missing, but substantially similar to many other permitted uses. Outdoor recreation restrictions section talked about indoor recreation. Confusing.
441	272	Permissible uses (core nhoods)	added "garage sales"	was missing, yet permitted.
441	272	Permissible uses (core nhoods)	medical or dental offices: now limited to 5,000 sf	! Error from previous. Had edited the definition but not updated the size restriction in this category. Corrected in version 2017-03-14 and subsequent.
446	272	Permissible uses (center)	added single-family attached (only in townhome building type)	TH building type is permitted in certain areas in C (water street, south end), but the use type that goes with it was not. Corrected.

new section number	original section number	title	change summary	rationale
446	272	Permissible uses (center)	allowed multiple-family dwellings only in the Apartment Building type	This use was only intended to go with the AB building type. Caused confusion as to whether residences could be on the first floor, if there were more residences above/elsewhere/etc. Linked multifamily to the AB type.
447	no previous equivalent	Non-use and dimensional requirements for site improvements not regulated by building type.	Created standards for fences in C	ZO2014 had no fence standards for C. Previous had standards that matched other commercial & industrial (10' in rear, 6' in front). Established standards; no fence in front (unless PC waives or required for other reasons), up to 6' in rear.
451	272	Permissible uses (corridors)	added single-family attached (only in townhome building type)	"townhome" building type had been permitted in HC & NC. However, the use type "single-family attached" or even just "single-family" was not- only "single-family detached." this clarifies and permits.
461	272	permissible uses (HHS)	added single-family attached (only in townhome building type)	also added "townhome" building type. Few building sites for such a development, but would fit in the district and be on the lower-end of density.
465	275	building types	made the "IT" building type Limited in all districts	an "IT" building type had relatively relaxed standards for setbacks, etc. it could have been built anywhere, without special permissions. This is not as intended. It was intended to allow for "special" cases of buildings- religious buildings, municipal buildings, theaters, museums, etc, not "just because."
465	274(b)	new construction of limited building types	deleted	new construction of just about anything is required to go through full site plan review. This clause was redundant.
465	274	building heights	added flexibility in design	standards as given do not allow for "fun" things- mezzanines, atriums, etc. new standards allow for a bit more flexibility. Also added a reference to the standard height exceptions (chimneys, etc)
465	274	parking zones	clarified	removed redundant language.
465	274	private frontages	clarified	removed redundant language. Moved pieces to definitions.
465	274	historic structures	clarified	unnecessarily wordy, included prohibitions we don't need (we cannot meaningfully approve extensions onto another's property)
465	274	infill and redevelopment	clarified	wordiness obscured meaning.
465	274	lot requirements for new construction	clarified, removed "rental"	wordiness obscured meaning. Also, unnecessarily specified ownership of a building type.

new section number	original section number	title	change summary	rationale
465	274	Lot and Block Requirements for Existing Buildings.	clarified; was a formatting error + procedural issues.	Numbering was wrong; it should have gone with the numbered section below it in the original. Procedure was wrong: "...PD must determine if a waiver can be granted or require a review by PC." Generally waivers are only granted BY pc. Clarified that an admin waiver could be granted. CP generally has latitude to bump to PC at discretion.
all cutsheets	all cutsheets	formatting & order changes	reordered requirements; clarified diagrams; changed spacing so all text was visible.	Building type is decided by lot size; moved lot size to be first requirement. Some diagrams unclear/did not reflect text (ex, # stories); updated. Some descriptions had regulatory language; removed. Font sizes increased. All building types now have section numbers.
-use buildings	Commercial mixed-use buildings	height changed	CS- raised height to 5 stories	to match CM (@5)- avoid missing-teeth look in downtown infill &/or building new. CL still @ 8 stories.
511	773	AFC small homes, etc	removed parking requirements; added architectural compatibility (special use in all districts except HHS), removed mention of foster family homes; CN-Mid removed from location exclusion- is a special use in CN-Mid.	
514	812	Auction Houses	removed clause about outdoor activities, added it to owner statement.	
515	775	automobile filling stations	removed duplicative parking requirement	
518	781	automobile parking garages	removed design standards; added building type requirements	design standards only applied in the HD- didn't add anything to the existing HD review process. Also specifically allowed a sort of mixed use ("liner buildings") when there's nothing preventing such. Removed those clauses; added the IT when in WUDs.
519	782	automobile parking as principal use	removed adjacency requirement, added bike parking and barrier-free requirements	orig required that if it was meant to serve one use, had to serve all that use- removed, as didn't allow for overlap. Added in "extra" bike parking and "extra" barrier-free parking. Left out lighting plan; that's a gimme.

new section number	original section number	title	change summary	rationale
520	778	bed & breakfasts & inns	combined to one listing.	b&b had required that an owner be living there; inns did not. There were other (subtler) distinctions in the pre_2014 code; those were mainly lost when tiebarred (every zone where either is permitted, both are permitted). Now, owner-occupancy is only required in certain zones; other places can be a resident manager (with the same standards as resident managers elsewhere). Max # people per "room" was removed due to suites being more popular in B&Bs these days. Licensing provision removed because we don't do licensing anymore.
521	779	child care centers & group day care homes	removed parking requirements; removed info about drop-off centers.	Parking requirements covered elsewhere in chapter. Drop-off centers are not something licensed by the state, never had a request for them, don't know really how they differ from centers &/or group day care homes or what would be gained by regulating separately from other existing licensed facilities.
522	784, 783	Drive-through or drive-in facilities	combined into one; changes to requirements	Increased required distance from residential districts (100 from 50 or 60), called out residential districts; included walkability in C, HC, NC, GC; kept noise, stacking spaces, and major thoroughfare requirements.
529	802	Indoor and Outdoor Recreation and Gyms	Simplified; changed title to reflect uses permissible; changed setback requirements	This is an odd use and will require further/future review; possibly only apply for larger (>5,000sqft?) uses. Had differentiated between public, private, and private noncommercial- not legally defensible- so that clause was removed. Special setback requirements removed, as well as required building type- often, the district's setbacks would exceed those specified here. Mandating the IT type could rule out re-use of an existing building. Kept the potential to further reduce parking requirements.
534	794	Multiple-family dwellings containing more than six units	Split specific portions into the designated district (MD); removed duplicative	Removed: accessibility by emergency vehicles (a given), parking lot illumination (also given); split off portion that only applies to MD into the MD district.
535	795	Municipal, County, regional, and state service buildings and uses	Removed architecture requirement	Largely as a nod to the fact that we very likely will have only courtesy review of the buildings, if constructed by bodies other than the City. Not permissible in all districts; special use in some, by-right in some. Uneven.

new section number	original section number	title	change summary	rationale
538	798, 800	Open-front or open-air businesses; outdoor recreation/amusement facilities; outdoor sales of new or used automobiles, trucks and tractors, boats, etc.	Combined two v similar into one.	Needs future follow-up, look at with an eye to splitting off recreation. Combined, removed duplicates, removed things covered elsewhere (distance of drive from intersection, grading/drainage, tarping loose materials (covered under 539))
539	801	Outdoor storage of raw materials, supplies and products		Added the requirement for outdoor storage to comply with setbacks. NOTE: removed (3/15 & onward) duplicate requirement for tarping.
540	799	Outdoor cafés	added "seating areas" to the title	
541	786	Passenger terminals and stations	Changed title from "express and passenger terminals."	"express..." is not a term commonly found. Included also "stations," as terminal implies the end of a line.
543	780	Religious institutions and Private Assembly spaces, including social facilities	Small changes to comply better with RLUIPA	Will require additional work/deep-dive into uses specifically with an eye to RLUIPA. Parking requirements cleaned up. Description cleaned up.
545	805	Primary, secondary, and post-secondary schools (public & private)	removed duplicative parking requirement, simplified final clause	final clause specified that athletic fields & playgrounds must be shown on site plan; now specifies "all site improvements". Is still overkill, but better.
548	811	Supportive Housing	FHA issue addressed; duplicative requirements removed	Distance from other supportive housing and other uses removed (primary area of FHA issues). Site plan review was called for "under article IV," but article IV said that site plan was not necessary (barring an expansion or new build), so removed. Minimum lot size removed (as in many other uses). Required that recreational space be fenced/screened.
560-565	731-736	Definitions	moved all definitions to definitions, combined where feasible.	
570-576	681-687	Communication devices	No changes	This section must be updated in the near future. Federal and state regulations have changed substantially. Outside of the scope of this work.

new section number	original section number	title	change summary	rationale
607	636	Building Entrances, Rights of Way, and Easements	Allowed building on easements/rows with authorization of Council/easement-holder	It's happened.
609	641	Lighting	Clarified some discrepancies, added pieces for ornamental lighting.	Added quite a bit to even out some discrepancies (full cutoff vs dark sky); added a bit about ornamental uplighting (didn't have anything before, so a start- uplighting was defacto prohibited by "all lighting must be down-directed"); added a bit about motion-detection lights (had questions from applicants about it). NEON TUBING outlining windows: it was included in signs and prohibited. However, challenging to enforce. As you can see- proposing allowing it, at least for now.
613	new	Height Exceptions	Consolidated all the height exceptions into one passage	Same material was repeated alongside each height limitation (except for building types, which allowed no exceptions). Consolidated and made applicable to all, excepting those PMD-specific.
631	702	Landscape Plan Requirements	Included the word "not" in front of "necessarily"	As originally worded, allowed applicants to submit less but not be required to submit more if needed.
632	711	Landscape Elements	Added quantity/stacking requirements; limited berms; clarified/simplified minimum size requirements	Specified that requirements could only double-count when explicitly stated. Stated berms only allowed by discretion of PC. Extremely simplified size/spacing chart for new plantings.
634	703	Screening between Conflicting Land Uses	Clarified screening material/process, removed loc req, relocated PMD-only	Clarified *types* of screening permitted & allowed for more w/permission of PC; removed location requirement for screen & waiver capabilities (redundant); moved PMD-only requirement to PMD.
635	713	Fences and Walls	Relocated zone-specific requirements to those zones; changed duration of construction fencing	Duration of construction fencing now reflects duration of construction; construction fencing is a safety requirement during many types of construction.
636	704	Street Trees	removed spacing requirements; removed conformance to Urban Forestry Plan; allowed waiver w conditions.	Spacing requirements referenced were both too restrictive and removed. Removed reference to (2011) Urban Forestry Plan as likely will not be updated w/in five years; significant out of date data currently. Created alternatives to planting if planting in ROW not feasible.
637	707	Foundation Landscaping	removed from MD; made location requirements looser; specified min plant bed size	

new section number	original section number	title	change summary	rationale
n/a	709	residential development landscaping	removed. Was redundant.	
654	644	Porches, decks, balconies, fire escapes, and barrier-free access ramps	Clarified.	Was often a question as to front porches/decks/patios due to unintentional vagueness.
VI Div 5 (signs)	Article XIV	Signs	See memo for large-scale changes. Removed "master sign plan requirement" and "modification of sign standards".	removed "master sign plan" requirement. Was not found to be particularly useful. Removed "modification of sign standards"- was used only once since 2011; difficult to make content-neutral as was based on creativity. Potential to revisit in the future, or bring back "sign variance" (pre-2011).
664	865	Prohibited signs	"electronically illuminated message sign" updated to "sign, electronic message, excepting digital billboards"	! Changed 3/15 & subsequent. Updated wording to reflect new definition; also to distinguish prohibition against electronic message signs from digital billboards (2014 version, which prohibited electronic message signs entirely, did not distinguish the two well).
670	273	Circulation Standards	Simplified. Removed block plans.	Circulation/block plans were largely designed for larger-scale developments, and spoke more to policy than performance, including the creation of new public or private rights-of-way. Removed a great deal of redundancy between circ & block plans, left the majority of the requirements (block length, access) intact. Could likely benefit from more flexibility, but a variance or PUD could be used, depending on the site, if needed.
681	832	Scope	Added first-floor commercial uses in HC, when switching from existing commercial use	HC has many of the same spatial constraints and benefits that C does wrt parking & transportation. When going from one commercial use to another commercial use, adding parking would be difficult at best. NOTE: changed from blanket inclusion of HC properties to only those going from commercial to commercial, not from residential to commercial. Included in 3/15 changes & subsequent.
682	833(1)	Off-street parking layout and construction for one-and two- family dwellings	Split off from larger "off-street parking layout and construction" section	
683	833(2) & 835(1-9, 12-13)	Off street parking layout and construction for all other uses	Split from larger section. Added waivable parking setback. Combined 833(2) & 835.	

new section number	original section number	title	change summary	rationale
684	835	Parking screening and landscaping	Split off from remainder of 835 (all construction requirements for commercial off-street).	
685	834	Parking dimensions	Updated measurements to reflect smaller allowed parking spaces	Previous ordinance (pre-2014) had allowed for 10x20 spaces; current ordinance calls for 9x18.
691	836	Minimum and maximum number of parking spaces	Removed cap from residential parking; removed some use types that were duplicative and not removed from 2014; updated & combined religious uses/assembly spaces/recreation spaces; ensured callout to stacking spaces where needed	120% of 1.5 spaces/unit = still not enough for a 2-car garage AND a driveway; make parking regulations simpler to administer
692	837	Parking requirement reductions	Split car-sharing from electric vehicles; added seasonal bike parking; clarified the PC discretionary waiver	seasonal bike parking: up to 5% of the car spaces can be occupied by bike racks April -> October (mirrors ROW café season). PC waiver was intended to be "beyond" the other reductions, but was unclear.
701	572	Permitted Uses	Allowed PUD in CN-Mid; opened up GC to Unclassified uses as defined/used in PMD	CN-Mid includes Boys & Girls club property; is a hybrid between R3 and R2. Had been permitted in R3.
702	573	Requirements for Planned Unit Developments	Allowed 0.5 acre parcels in the WUDs	Walkable urban district parcels tend to be smaller than Use-based parcels; all Water Street parcels are in a WUD (C). Previously had allowed smaller parcels (down to 0.5ac) only if historical as determined by HDC.



Memo

To: City Council

From: Bonnie Wessler, City Planner

Date: March 16, 2017

Subject: Sign Regulation

Background

In 2015, the Supreme Court decided the case of *Reed vs the Town of Gilbert, AZ*, regarding sign regulation. The majority opinion established a new standard: if you have to read the message displayed to determine how a sign is regulated, then that regulation is content-based. Further, if the regulation is content-based, it is subject to strict scrutiny if challenged, meaning that it is presumed unconstitutional unless it is narrowly tailored to protect a significant government interest. An example would be a prohibition on signs that look like traffic control signs (ex., "stop," "speed limit," etc) erected not to control traffic (a valid public purpose), but to serve private interests (ex., "stop... for our low prices" designed to mimic a stop sign).

In January 2016, Planning asked Legal to review our existing ordinance and call out those provisions which would be unenforceable in light of the ruling. At least 9 sign "types" of 49 would not pass muster, with some doubt as to the legality of at least portions of others. Several sections would have to be struck entirely. This markup and related memo is attached. Given the significant scope of the changes, the thought at the time was to delay altering the code until other municipalities had done so, then review those new codes. However, as the year wore on, it appeared that many other municipalities were also taking a wait-and-see approach; it was decided mid-year to incorporate the sign ordinance changes into the reorganization of the code.

Process

After the sign types that were unenforceable were removed from the code, an effort was made to categorize, broadly, into physical types, rather than content-based types. Five initial categories were defined (freestanding permanent and temporary; building-mounted permanent and temporary, and billboards), and the existing "sign types" were broadly assigned one of the categories.

As several sign types (the "ground sign" category (122-866(a)), some "temporary signs" (122-866(c)(1), and many signs in the "table of allowable signage" (122-868)) were restricted by zoning district, and one of the aims of the code reorganization was to put district-specific information in each district, this list was broken out by district. Further, some types of sign (the "ground sign" category (122-866(a)), some "temporary signs" (122-866(c)(1), and many signs

in the “table of allowable signage” (122-868)) were further regulated by residential or non-residential uses, each district table was broken into “residential” and “non-residential” categories. Note that each district generally contains some residential and some non-residential uses, with the exception of Park. Note also that not all sign types in the 2011 code were broken into district &/or use-specific regulations, such as special event signs and the broad “temporary signs” in 122-868 (which was largely contradicted by the table found in 122-866(c)(1)).

The regulations for this first iteration of the draft were drawn from the existing code, but due to the gaps in the previous code, discretion was applied. These issues were discussed with Planning Commission in June, as well as other aspects of the zoning code update, and it was decided that a subcommittee would meet in early July to discuss staff’s first draft. The subcommittee’s work was presented to Planning Commission in July and approved.

Below, as an example, are the R1 regulations as proposed in the draft code before Council currently.

currently:

(d) SIGNS			
Also subject to Article VI, Div 5			
(1) Signs – Residential Uses			
(i) Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit not required.
	Maximum height	3 feet	
	All setbacks	0 feet Subject to §122-675	
(ii) Freestanding signs (permanent)	Not permitted		
(iii) Building-mounted signs (temporary)	Maximum area	0.5 square feet for each linear foot of building frontage or 12 square feet, whichever less	Permit not required.
(iv) Building-mounted signs (permanent)	Maximum area	1 sq ft	Permit not required.
(v) Billboards	Not permitted		
(2) Signs – Non-residential Uses			
(i) Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit not required.
	Maximum height	3 feet	
	All setbacks	0 feet Subject to §122-675	
(ii) Freestanding signs (permanent)	Maximum Area	16 sf	Permit required.
	Maximum Height	6 feet	
	Front Setback	3 feet Subject to §122-675	
	Side, street side, and rear setback	10 feet Subject to §122-675	
	Maximum number of signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	

(d) SIGNS*Also subject to Article VI, Div 5*

(iii) Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever less	Permit required.
(iv) Building-mounted signs (permanent)	Maximum Area	0.5 square feet for each linear foot of building frontage, or 12 square feet, whichever less	Permit required.
(v) Billboards	Not permitted		

There were other changes beyond the transfer of one regulation schema to another.

- Billboards are now permitted in the Park district, where “adjacent to and visible from I-94, as defined by the Highway Advertising Act of 1972.” This has the effect of permitting a billboard to be constructed, if State location and distance regulations are met, in the area south of I-94, west of Grove Road, formerly a wastewater treatment plant.
- The prohibition against outlining windows with lights has been removed, as there was persistent difficulty with enforcement. Should it be reinstated, it would likely fit better under the category of “lighting,” not signage, and have a lumen/footcandle restriction (ex, “strings or ropes of small lights outlining architectural features of buildings may not have a rated output of more than 800 lumens”, or something to that effect.)
- The ability to apply for “modification of sign standards” has been removed; it would be extraordinarily difficult to make such a provision content-neutral, and had been used only once since inception in 2011. Sign variances are still considered dimensional variances and permissible under the code.
- The requirement for a “master sign plan” has also been removed; it is exceedingly rare for an applicant to have all the requested information at time of site plan review, due to being relatively early in the development process for many applicants. As a result, we had only been asking for such at time of application for sign permits. In effect, the policy became “apply for all of your sign permits at once,” which is generally what well-prepared applicants tend to do anyway.
- The provision for nonconforming signs was removed. Section 122-352, Nonconforming Structures (formerly 208), now includes the phrase “including signs.” This was done largely to locate all provisions regarding nonconformities in the Nonconformities division.

Conclusion

As noted before, the changes to the sign ordinance are proposed to bring the ordinance into compliance with *Gilbert v Reed* and to make the regulatory framework more easily understood. The reaction to and application of the new code will be monitored closely over the coming year and will likely be revised further, especially as more municipalities adapt to *Gilbert v Reed* and case law evolves.

ATTACHMENTS: 2016 markup of existing zoning code per *Gilbert v Reed*
2014 Sign Ordinance (excerpt from Zoning Code, one section)
Draft Sign ordinance (excerpt, many sections, labelled)



**Barr,
Anhut &
Associates, P.C.**
ATTORNEYS AT LAW

105 Pearl Street
Ypsilanti, MI 48197
(734) 481-1234
Fax (734) 483-3871
www.barrlawfirm.com
e-mail: jbarr@barrlawfirm.com

John M. Barr
Karl A. Barr
Daniel J. DuChene

Jesse O'Jack ~ Of Counsel
William F. Anhut ~ Of Counsel - Retired
Jennifer A. Healy ~ Legal Assistant

MEMORANDUM

TO: Bonnie Wessler, City Planner
FROM: John M. Barr, Ypsilanti City Attorney
DATE: December 10, 2015
SUBJECT: Unenforceable Sign Ordinance Provisions

You have asked that I provide an opinion on provisions of the City's sign ordinance (Chapter 122, Article XIV of the City Code of Ordinances) that are unenforceable as a result of the recent U.S. Supreme Court decision of *Reed v Town of Gilbert*. It is my understanding that this memo will be used in the interim to ensure compliance with the U.S. Constitution while still enforcing City Code as much as possible until a more complete revision of the Code can be adopted.

The basic holding in this case was that a municipality may not regulate signs based on the message it contains, as it violates the First Amendment. Simply put, it is unconstitutional to regulate a sign if the government must look at the content of the sign in order to know which regulation to apply. I have reviewed the Code liberally and it is my opinion that the following provisions are unenforceable, or at least should be at this time until further review. I have also attached a red-line version of the Article for your review. For the purposes of permitting or enforcement, because these provisions are not enforceable they should be treated as if they do not currently exist in the Code.

- Of Sec. 122-862(f): The words "content," "context," and "coloring," wherever they appear, as well as the sentence: "No sign shall make use of the words 'stop,' 'look,' 'danger' or other word, phrase, or symbol in a manner that is confusing or misleading."
- Sec. 122-862(g) in its entirety.
- Of Sec. 122-863:
 - Under the definition of "Abandoned sign," the phrase: "directs attention to an object, product, place, activity, person, institution, organization or

cc: City Manager, Economic Development Director

f:\docs\city\memos\Sign Ordinance memo to Bonnie 121015.doc



- business which is no longer currently existing and is not maintained in accordance with the standards set forth in this chapter and"
- Under the definition of "Mural," the phrase: "that does not advertise a business, product, service or commercial activity."
- The definition of the word "Nameplate," in its entirety.
- The definition of the word "Seasonal display," in its entirety.
- Under the definition of the word "Signs:" subsections (1), (7), (9), (10), (14), (21), (26), (29), and (30) and in their entirety.
- Of Sec. 122-864(a), provisions of the schedule relating to barber pole, building director, menu, directional, historic designation, opinion, temporary signs, election signs, for sale or for lease, garage sale, special events, traffic control, and vehicle.
- Sec. 122-864(b)(3)(b) and (c), in their entirety.
- Sec. 122-866(a)(6) – (8), in their entirety.
- Sec. 122-866(b)(8) and (9), in their entirety.
- Sec. 122-866(c)(1) and (2), in their entirety.
- Sec. 122-866(c)(3)(k), in its entirety.
- Sec. 122-866(c)(4) and (5), in their entirety.
- Sec. 122-868, portion of the table relating to menus, direction, election, and opinion.

Sec. 122-861. - Purpose.

The purpose of this article shall be to permit such signs as will not, by reason of their size, location, construction or manner of display, endanger life or limb, confuse or mislead traffic, obstruct vision necessary for traffic safety or otherwise endanger the public morals, health or safety.

It is further the intent of this article to:

- (a) Maintain and enhance the aesthetic value of the city.
- (b) Encourage free expression of ideas and dissemination of messages, regardless of content, using signs that are compatible with their surroundings and legible under the circumstances in which they are seen.
- (c) Enhance pedestrian and vehicular traffic safety.
- (d) Minimize the adverse effects of signs on nearby public and private property.
- (e) Minimize driver distraction.
- (f) Protect and enhance economic vitality by assuring aesthetic appeal for residents and visitors.
- (g) Preserve property values.
- (h) Enhance the effectiveness of permitted signs and directional and warning signs.
- (i) Seek the removal of illegal signs and encourage the replacement or removal of nonconforming signs that are incompatible with the purpose of this article.

Sec. 122-862. - General requirements.

- (a) Building Permit Required. Except as provided in this, article XIV, no sign shall be constructed or erected prior to the issuance of a permit by the building department, and approval from other applicable reviewing bodies.
- (b) Historic district approval. Signs to be located in the historic district need approval by the historic district commission, excluding temporary signs.
- (c) Accessory to principal use. All signs shall be accessory to the primary use of the lot where the sign is located and shall comply with the applicable design standards set forth herein, with the exception of any sign specifically permitted by subsection 122-866(d)(2).
- (d) Public rights-of-way. Signs shall be expressly prohibited from locating in all public rights-of-way and dedicated public easements except as otherwise provided for in this ordinance, and as follows:
 - (1) Signs erected by the city or other governmental entities for public purposes are permitted.
 - (2) Building mounted signs may project over a public right-of-way or easement provided they comply with the applicable design standards for the specific type of sign and that they maintain a minimum clearance of eight feet.
 - (3) Overhead banners.
 - (4) Sidewalk signs.
- (e) Construction requirements.
 - (1) All signs shall conform to the city building code unless more stringent requirements are specified in this article. Signs and sign structures shall be designed and constructed to resist wind and seismic forces as specified in this section. All bracing systems shall be designed and constructed to transfer lateral forces to the foundation. For signs on building the dead and lateral loads shall be transmitted through the structural frame of the building to the ground in such a manner as not to overstress any of the elements thereof.

- (2) The overturning movement produced from lateral forces shall in no case exceed two-thirds of the deadload resisting movement. Uplift due to overturning shall be adequately resisted by proper anchorage to the ground or the structural frame of the building. The weight of earth imposed over footings may be used in determining the dead-load resisting movement. Such earth shall be carefully placed and thoroughly compacted.
- (3) Wind loads. For the purpose of design, wind pressure shall be taken upon the gross area of the vertical projection of all signs and sign structures at not less than 20 pounds per square foot for those portions less than 60 feet above the ground.
- (4) Allowable stresses. The design of wood, concrete or steel members shall conform to the requirements of the most recently adopted version of the Michigan Building Code, and loads, vertical and horizontal, exerted on the soil shall not produce stresses exceeding those specified therein. The working stresses of wire rope and its fastenings shall not exceed 25 percent of the ultimate strength of the rope or fasteners. Working stresses for wind or seismic loads combined with deadloads may be increased as specified in the Michigan Building Code.
- (5) Supports. The supports for all signs or sign structures shall be placed in or upon private property and shall be securely built, constructed and erected in conformance with the requirements of this chapter.
- (6) Fastenings. Signs attached to masonry, concrete or steel shall be safely and securely fastened thereto by means of metal anchors, bolts, or approved expansion screws of sufficient size and anchorage to support safely the loads applied. Anchors which attach signs to masonry surfaces shall be inserted into mortar joints.
- (f) Traffic and pedestrian hazards. The placement, size, ~~content, coloring~~ or manner of illumination of signs shall not create traffic or pedestrian hazards. ~~No sign shall make use of the words "stop," "look," "danger" or other word, phrase or symbol in a manner that is confusing or misleading.~~ No sign or flashing light shall be erected or maintained in any manner which, by reason of its size, location, ~~context, coloring~~ or manner of illumination, shall constitute a traffic hazard or which shall interfere with the visibility of any traffic control device.
- (g) Substitution. Notwithstanding anything herein to the contrary, noncommercial copy may be substituted for commercial copy on any lawful sign structure, and any sign permitted by this article may contain a non-commercial message.
- (h) Obstruction prohibited. No sign shall be placed so as to obstruct any fire escape, required exitway, window, or door opening used as a means of passage or as access for firefighting purposes.
- (i) Obstruction to ventilation. A sign shall not be attached in any form, shape or manner which will interfere with any opening required for ventilation by the building code; except that such signs may be erected in front of and may cover transom windows when not in violation of the provisions of this chapter.
- (j) Maintenance. All signs, sign frames, sign copy area, panels, structural elements, lamps and electrical hardware shall be maintained in good repair and working order, so as to present a neat and orderly appearance. Non-galvanized or corrosion-resistant materials shall be painted when necessary to prevent corrosion.
- (k) Authorized sign contractors. Every person before engaging or continuing in the business of constructing, repairing or dismantling signs, poster boards or other display signs in the city, shall first furnish the city a public liability insurance policy, approved by the city attorney, with minimum limits of \$300,000.00 combined single limit bodily injury and/or property damage, and the contractor agrees to indemnify the city from all damage suits or actions of every nature brought or claimed against the contractor for or on account of injuries to persons or damages to property received or sustained by any person or person through any act of omission or negligence of such erector, agents or employees in the erection, repair or dismantling of any sign, poster board or other display sign. Such policy shall contain a clause whereby such policy cannot be canceled until after a written notice of intention to cancel has been filed with the city clerk at least 30 days prior to the date of cancellation.

Comment [D1]: Not sure about this one.

- (l) Master sign plan in HHS, HC, NC, GC, C, PMD, and P districts and for non-residential uses in R1, CN-SF, CN-Mid, CN, MD districts.

All non-residential buildings shall submit a master sign plan as part of their sign permit application. The master sign plan shall identify size, location, and lighting of all existing and proposed signs located or to be located on the building.

- (m) Modification of standards. Upon receipt by of an application for a permit that includes a request to modify any of the standards in this chapter, the planning commission may, at any regular meeting or any special meeting duly called for that purpose, consider whether the proposed sign, if erected, will achieve the purposes of this chapter. The applicant shall demonstrate the following to the satisfaction of the planning commission:
- (1) Whether the structure, dimensions and placement of the proposed sign generally conform to the character of signs in the neighborhood or business district;
 - (2) Whether the proposed sign achieves the purposes of this chapter as described in section 122-861;
 - (3) Whether the proposed sign achieves another public purpose consistent with the purpose of this chapter or the city's master plan;
 - (4) Whether the proposed sign achieves innovation and variety in design and compatibility;
 - (5) The proposed sign shall be designed, constructed, operated and maintained to assure long-term compatibility with surrounding uses, buildings, and signs. Consideration shall be given to the placement, bulk, height and materials used in construction.
 - (6) The proposed sign shall promote the use of signage in a socially and economically desirable manner and not be detrimental, hazardous, or disturbing to existing or future neighboring uses, persons, property or public welfare.
 - (7) Appeals from the decision of the planning commission shall be heard by the zoning board of appeals.

Sec. 122-863. - Definitions.

The following words, terms and phrases when used in this article shall have the meanings ascribed to them in this section, except where the context clearly indicates a different meaning:

~~Abandoned sign means a sign which directs attention to an object, product, place, activity, person, institution, organization or business which is no longer currently existing and is not maintained in accordance with the standards set forth in this chapter and~~ contains or exhibits broken panels, visible rust, visible rot, damaged support structures, missing letters or which is otherwise dilapidated, unsightly, unkempt and for which the business or property owner is not accepting maintenance responsibility where such acts evidence an intent to abandon. Signs of local historical significance may not be considered abandoned

Building frontage means the outside perimeter measurements of the building wall on which wall the sign shall be placed.

Clearance means the vertical distance between the surface grade beneath the sign and the lowest point of the sign, including framework and embellishments.

Damaged sign means a sign or supporting structure which is torn, defaced, dented, smashed, broken, vandalized or destroyed.

Display surface means the sign area measured in square feet. Superficial ornamentation, trim or simple type appendages of non-message-bearing character shall not be included in determining display surfaces so long as they do not exceed 20 percent of sign area. The square footage of a two-, three- or four-faced sign shall mean the square footage of the largest face of the sign.

Flag means a flag bearing the official design of a nation, state, municipality, educational institution or organization.

Mechanical sign means any signs that have any visible moving parts, mechanical movement or other apparent visible movement achieved by electrical or mechanical means or action of normal wind currents.

Mural means a design or representation painted, drawn, or otherwise attached to the exterior surface of a structure ~~that does not advertise a business, product, service or commercial activity.~~

~~Nameplate means a sign identifying only the name, occupation, or profession and address of the business or occupant of the lot where the sign is placed.~~

Nonconforming sign means a sign which complied with the provisions of the chapter in effect at the time that it was erected but which does not conform to this article.

~~Seasonal display means decorations that do not convey a commercial message. These shall not be considered signage, and shall not require a permit.~~

Sign means a name, identification, description, announcement, display, illustration or insignia which is affixed to or painted or represented directly or indirectly upon a building, structure or piece of land, which directs attention to an object, product, place, authority, person, institution, organization or business and which is visible from any public street, right-of-way, sidewalk, alley, park or other places open to the public.

~~(1) Address sign means a numerical address with numbers no greater than eight inches in height.~~

(2) Animated sign means a sign that uses light emitting elements including but not limited to light bulbs, fixtures, LEDs, fiber optic lighting to create a continuously scrolling, flashing, or animated effect on any sign visible from the exterior of the building.

(3) Awning sign means a sign that is painted on, attached to, or an integral part of an awning or canopy.

(4) Banner means a sign, including inflatables, consisting of a large piece of cloth or similar flexible material, in public view, in front of a building or entranceway.

(5) Banner, overhead, means a sign consisting of a large piece of cloth or similar flexible material suspended by wires in public view across a street or other public space.

(6) Billboard means an off-premises sign.

~~(7) Building directory means a sign identifying multiple tenants in a single building located above the street-level façade (such as a multiple-story office or commercial building).~~

(8) Building-mounted sign means a display sign that is painted on, adjacent to or attached to a building wall, door, window or related architectural feature. Such signs include, but are not limited to awning, projecting, wall and window signs.

~~(9) Directional sign means a sign not exceeding two square feet which contain only noncommercial messages including designation of restrooms, telephone locations, restrictions on smoking, door openings, private control on premises vehicle or bicycle traffic and parking.~~

~~(10) Election sign means a sign advocating or opposing a candidate for public office or a position on an issue to be determined at an election, but does not advertise any products, goods, services or businesses.~~

(11) Electronically illuminated message sign means a sign with a message displayed on a surface with an electronically illuminated changeable copy area (often composed of LEDs).

(12) Ground sign means any freestanding sign, not attached to a building, including monument or pole signs.

(13) Hanging sign means a sign suspended under an awning, canopy, or marquee.

How to define sign vs ornamentation

~~(14) Historical sign means a sign designating a building as a historical structure, names of buildings, dates of construction, and other historic information.~~


(15) Illuminated sign means a sign that provides artificial light directly or through transparent or translucent material from a source connected to or within such a sign, on which is illuminated by a light so shielded as to prevent direct rays from being visible from the public right-of-way.

(16) Inflatable sign means a temporary sign that is intended to be expanded by air or other gas for its proper display or support.

(17) Marquee sign means a projecting sign that accommodates changeable copy.

(18) Monument sign means a freestanding sign supported by a pedestal or base, with permanent attachment to the ground.

Field Code Changed



(19) Off-premises sign means a sign not relating to the premises on which such sign is located.

(20) On-premises sign means a sign related to the premises on which such sign is located.

~~(21) Opinion sign means a sign advocating or opposing an opinion or point of view, but does not advertise any products, goods, services or businesses.~~

(22) Pole sign means a sign which is erected on a single freestanding mast or pole, not attached to a building.

Field Code Changed



- (23) Portable sign means a sign of a temporary nature, not securely anchored to the ground or to a building or structure, excluding sidewalk signs.
- (24) Projecting sign means a sign which is attached directly to the building wall, and which extends more than 18 inches from the face of the wall. A projecting sign shall project not more than four feet from the wall of a building and shall not project above the front wall of the building.

Field Code Changed



- (25) Public signs means a traffic or other governmentally erected notices, railroad crossing, danger and other temporary emergency signs, location of transit line, a railroad station or other public carrier or other non-advertising signs.

~~(26) Residential entry feature or sign means an architectural feature with signage at each entrance to a residential subdivision, neighborhood, apartment community, condominium development, or mobile home condominium project.~~

- (27) Roof sign means a sign which is constructed and maintained upon or above the roof of a building, marquee, or parapet wall and which is wholly or partially supported by such building.

(28) Sidewalk sign means a temporary sign placed within the right-of-way. These types of signs may include "A" frame, "T" frame or other temporary styles, which are not permanently affixed to the ground.

~~(29) Special-event sign means banners, pennants, balloons or festoons associated with a specific event and displayed for a specified and limited period of time, including commercial store sales, etc.~~


~~(30) Temporary sign means display signs, banners, balloons, festoons or other advertising devices constructed of cloth, canvas, fabric, plastic or other light temporary material, with or without a structural frame, or any other sign intended for a limited period of display, but not including decorative displays for holidays or public demonstration.~~

(31) Wall sign means a sign which is painted on or attached directly to the surface of masonry, concrete, frame or other approved building walls, and which extends not more than 18 inches from the face of the wall and which does not extend above the parapet, eaves or building facade.



(32) Window sign means any sign within a building placed within 12 inches of a window or upon a window pane and that is visible from the exterior of the building not including merchandise located in a window.

Sign area. The gross surface area within a single continuous perimeter enclosing the extreme limits of all sign copy or surface of any internally-illuminated sign, awning or canopy. Such perimeter shall not include any structural or framing elements lying outside the limits of such sign and not forming an integral part of the display. Where a sign has two or more faces, the sign area shall equal the total area of all sign faces, except where two faces are placed back to back and are at no point more than three feet apart, the sign area shall equal the area of the larger single sign face.

Field Code Changed



Sign Height. The vertical distance measured from the average grade at the sign location to the highest point of the sign.



Sign Height

Sign structure. Anything constructed or erected for the purpose of supporting a sign, the use of which requires permanent location on the ground or attachment to something having permanent location on the ground.

Sec. 122-864. - Sign permit requirements.

(a) Schedule of sign permit requirements.

It shall be unlawful for any persons to erect, alter or relocate within the city any sign or other advertising structure without first obtaining a permit as indicated in the following schedule:

Type of Sign*	Permit Required	Sign Standards
Animated	Prohibited	---
Barber Pole	N	---
Building Mounted Signs		122-866 (b)
Address Number/Nameplate	N	---

• Awning, Canopy	Y	122-866(b)(6)
• Building Directory	Y	122-866(b)(9)
• Menu	Y	122-866(b)(8)
• Projecting	Y	122-866(b)(7)
• Wall	Y	122-866(b)(5)
• Window	N	122-866(b)(10)
Directional	N	122-866(a)(6)
Flags	N	---
Ground (pole and monument)	Y	122-865(a)
• Billboards	Y	122-866(d)(2)
• Residential Entry Sign	Y	122-866(a)(8)
Historic Designation	N	---
Mural	Y	---
Opinion	N	122-866(e)(6)
Off-premises signs (except billboard)	Prohibited	---
Portable (except sidewalk signs)	Prohibited	---
Public	N	---
Roof	Prohibited	---
Temporary Signs		122-866(e)
• Banner	Y	122-866(c)(3)

• Overhead Banner	Y	122-866(c)(4)
• Construction - R1, MD, CN-SF, CN-Mid, CN and HHS	N	122-866(c)(1)
• Construction - All other districts	Y	122-866(c)(1)
• Election Sign	N	122-866(e)(5)
• For Sale, For Lease - Non-Residential	N	122-866(e)(1)
• For Sale, For Lease - Residential	N	122-866(e)(1)
• Garage Sale	N	—
• Inflatables	Y	122-866(c)(3)
• Special Events	Y	122-866(e)(1)
Sidewalk	Y	122-866(d)(3)
Traffic Control	N	—
Vehicle	N	—

(b) Application for permits; contents.

- (1) Application for sign permits shall be made upon forms provided by the building department.
- (2) Applications for signs other than overhead banners shall contain or have attached thereto the following information:
 - a. Name, telephone number and address of applicant.
 - b. Name, address and telephone number of owner or lessee of the premises upon which the sign is to be erected.
 - c. A written statement signed by the owner or lessee of the premises upon which the sign is to be erected, indicating his consent thereto, or the signed contract between the parties.
 - d. The address of the premises upon which the sign is to be attached or erected.
 - e. One set of plans showing the dimensions, materials, height and method of anchorage of the sign.
 - f. Position of the sign in relation to nearby buildings, structures and property lines.
 - g. Insurance policy or proof of financial security as required in section 122-862(k).

- h. On electrical signs, certification by Underwriters Laboratory or some other recognized testing laboratory. Electrical sign installations shall comply with article 600 of the National Electrical Code.
 - i. Such other information as deemed necessary to show compliance with this article.
- (3) Application for overhead banners shall contain or have attached thereto, the following information:
- a. The name of organization or group sponsoring the banner.
 - ~~b. A statement as to purpose of the banner.~~
 - ~~c. Phrase on the banner, and/or sketch of the content~~
 - d. Location where banner is to be erected.
 - e. The dates the banner will be hung.
 - f. The name, address and telephone number of the applicant.
 - g. Insurance policy or proof of financial security as required in section 122-862 (k).
 - h. Such other information as deemed necessary to show compliance with this article and with Act No. 200 of the Public Acts of Michigan of 1969 (MCL 247.321 et seq., MSA 9.140(21) et seq.), and R247.271—R247.279 of the Michigan Administrative Code, 1979.
- (4) Application for sidewalk signs shall include a sidewalk occupancy permit application.

Sec. 122-865. - Unsafe and prohibited signs.

The following signs are prohibited in all zoning districts:

- (a) Notice of unsafe and prohibited signs. When any sign or sign structure becomes insecure, in danger of falling, or otherwise unsafe, or if any sign or sign structure shall be unlawfully installed, erected, or maintained in violation of any of the provisions of this chapter, or prohibited signs, it shall be considered a nuisance per se. The owner or lessee shall, upon receipt of written notice of the building official, immediately in the case of an unsafe sign, and in any case within not more than ten days, make such sign conform to the provisions of this article or shall remove it. If, after ten days, the notice is not complied with, the building official may remove such sign at the expense of the owner or lessee after having obtained an order from the administrative hearings bureau. The cost, including actual attorney fees, shall be assessed against the property as provided in article VIII of the City Charter.
- (b) Prohibited signs.
 - (1) Abandoned signs.
 - (2) Signs not complying with sign schedules. Signs not complying with the requirements as set forth in schedules or tables contained in sections 122-866 and 122-868 respectively.
 - (3) Signs not specifically permitted. Signs which are not specifically permitted under the sections of this chapter.
 - (4) Signs located near overhead electrical conductors. Signs located with less than six feet horizontal clearance or 12 feet vertical clearance from overhead electrical conductors which are energized in excess of 250 volts.
 - (5) Animated signs.
 - (6) Portable signs, not including sidewalk signs.
 - (7) Roof signs.
 - (8) Obscene material. Display of obscene material upon any sign is prohibited.

(9) Mechanical signs.

(10) Electronically illuminated message sign.

Sec. 122-866. - Sign design standards.

(a) Ground signs.

Zoning District	Maximum		Sign Setback Requirements
	Sign Area	Sign Height	
R1 ¹ , CN-SF ¹	16 sq. ft.	6 ft.	Front yard - at least 3 feet from front property line, 10 feet from side or rear lot lines.
CN-Mid ¹ , CN ¹	16 sq. ft.	8 ft.	Front yard - at least 3 feet from front property line, 10 feet from side or rear lot lines.
MD ¹ , HHS, HC	32 sq. ft.	8 ft.	Front yard - at least 3 feet from front property line, 10 feet from side or rear lot lines.
NC	40 sq. ft.	10 ft.	Front yard - at least 3 feet from front property line, 10 feet from side or rear lot lines.
GC	100 sq. ft.	10 ft.	Front yard - at least 3 feet from front property line, 10 feet from side or rear lot lines.
C	Prohibited	Prohibited	—
P, PMD	100 sq. ft.	35 ft.	Front yard - at least 3 feet from front property line, 10 feet from side or rear lot lines

¹ For non-residential uses only

- (1) Number of signs. If permitted in a district, one monument or pole sign shall be allowed per lot or parcel. Lots that have more than 100 feet of frontage on two or more public streets shall be permitted one ground sign for each street frontage. A second ground signs shall have a maximum area of 50 percent of that otherwise permitted for a ground sign in the district.
- (2) Height requirement. No monument sign shall exceed ten feet in height.
- (3) Corner clearance. Signs shall be located outside of any corner clearance area as described in section 122-649 of this chapter.

- (4) Materials. Ground or pole signs shall be constructed out of decorative materials that complement the design of principal buildings within the development. Natural materials such as stone, decorative masonry, wood, or metal are preferred sign construction materials.
- (5) Landscaping. Low level landscaping shall be provided around the base of the ground sign, but shall not obscure any part of the sign message.

~~(6) Directional signs. Shall not exceed two square feet of sign area.~~

~~(7) Drive-through signs. Any use that includes a drive-through is permitted to have signs that relate to the drive-through facility, such as menu order board signs or information signs. The drive-through signs may have a maximum height of six feet and a maximum area of 32 square feet per drive-through use, and shall not be included in the computation of total sign area for the parcel unless such signs are legible from a point of observation off the premises.~~

~~(8) Residential entry signs shall be subject to the following standards:~~

- ~~a. Maximum of one sign on each side of the entrance from a major street.~~
- ~~b. May not exceed the maximum area permitted for a ground sign in the applicable district.~~

- (b) Building mounted signs. Building mounted signs, including wall, awning, projecting and window signs shall comply with the following requirements:

(1) Location.

- a. Building mounted signs may be located on any façade that faces a street, parking area, or vehicle circulation area that provides access to more than one parcel, or on a façade where a public entrance is located.
- b. Upper story tenants may only have window signs, except as allowed for in subpart d.
- c. Illuminated building mounted signs may not be located on a façade that faces a property line that abuts a residential zoning district unless the sign is set back at least 200 feet from the property line or screening is provided that will completely obscure the view of the sign from the adjacent residential district.
- d. In the case of a building that contains two or more businesses each business that is directly accessible from the exterior of the building may have a building mounted sign on the façade where the primary or main customer entrance is located. For the purposes of calculating sign area in such multi-tenant buildings, the frontage controlled by each tenant on the façade where the entrance is located shall be used to calculate linear frontage.

(2) Sign area.

- a. The total area of all building mounted signs, including wall, awning, projecting and window signs, shall not exceed three square feet for each one linear foot of building frontage on the side of the building the sign(s) are located on.

- (3) Minimum height. Awning and projecting signs shall maintain a minimum clearance of eight feet between the grade level below the sign and the lowest part of the sign (including sign support devices).

(4) Materials.

- a. Building mounted signs shall incorporate exterior materials, finishes and colors that are the same, similar, or complementary to those used on the principal building.
- b. Building mounted signs shall be professionally constructed using high-quality materials such as metal, stone, hard wood, or brass. The use of exposed neon tubing in conjunction with other types of materials to emphasize the business name or logo is permitted; however, neon tubing outlining windows or other architectural features is prohibited.
- c. Internally lit box signs are prohibited.

- d. External illumination of signs shall be limited to fully-shielded light fixtures with a maximum of 900 lumens. Such fixtures shall be mounted above the sign face with all light directed downward and concentrated on the area of the sign to prevent glare upon the street or adjacent property.
- e. To minimize damage to masonry, all mounting and supports should be inserted into mortar joints and not into the face of the masonry.

(5) Wall signs.

- a. No surface of a wall sign may project beyond or overhang any wall or permanent architectural feature by more than 18 inches.
- b. In non-residential districts wall signs cannot exceed one square foot for each linear foot of building frontage, or 100 square feet, whichever is less.
- c. In residential districts, residential uses including multiple family dwelling containing three or more units, sorority, or fraternity houses, wall signs cannot exceed one half square foot for each linear foot of building frontage, or 12 square feet.
- d. In residential districts, for non-residential uses, wall signs cannot exceed one square foot for each linear foot of building frontage or 100 square feet whichever is less.

(6) Awning signs.

- a. Sign lettering or logos may comprise up to 35 percent of the total exterior surface of an awning.
- b. A minimum vertical clearance of eight feet shall be provided between the lowest point of the awning and the sidewalk.
- c. Internal illumination of awning signs is permitted where the permitted awning sign area is illuminated through semi-opaque material and the remainder of the awning consists of opaque material.

(7) Projecting signs.

- a. Projecting signs shall be secured to the building by metal anchors, bolts, supports, rods or braces.
- b. Projecting signs are limited to 24 square feet of sign area per sign face.
- c. A minimum vertical clearance of eight feet shall be provided between the lowest point of the sign and the sidewalk.

~~(8) Menu signs. Menu signs shall be located in a permanently mounted display box on the surface of the building adjacent to the entry, and may have a maximum area of three square feet.~~

~~(9) Building directory signs.~~

- ~~a. The building directory sign shall be separate from any permitted signs accessory to the uses occupying the street level facade.~~
- ~~b. The maximum sign area of the building directory sign shall be equal to five percent of the total permitted building mounted sign area.~~

(10) Window signs. May not occupy more than 25 percent of the total transparent area of any individual window.

(c) Temporary signs.

(1) Schedule of regulations for temporary signs:

Temporary Signs	Maximum Size	Maximum Duration
-----------------	--------------	------------------

	(Square Feet)	
Banners	122-866(c)(3)	2 permits allowed per calendar year. Each permit expires after 30 days.
Overhead Banners	122-866(c)(4)	30 days
Construction signs, residential and office properties R1, CN-SF, CN-Mid, CN, MD and HHS	12	The earliest of the following: to issuance of certificate of occupancy, final inspection of permit, or 7 days after completion of work.
Construction all other zones	64	Within 7 days after completion of construction
Special Event signs	6	3 permits allowed per calendar year. Each permit expires after 3 days.
For sale, for rent, for lease, pertaining to real estate, residential properties (no permit required)	12	3 days after purpose of sign fulfilled
For sale, for rent, for lease, signs relating to real estate, nonresidential zones	64	10 days after purpose of sign fulfilled
Election signs (no permit required)	Maximum size allowed by district by sign type	10 days after final election

- (2) Temporary signs general. Temporary signs may be constructed of materials other than those specified in the chapter, with or without structural frames. Temporary signs not regulated by the schedule contained in section 122-866 (above) or which are listed in schedule and exceed 20 square feet in total size must conform to all standards that apply to permanent signs in the zoning district which the temporary sign is erected with the exception of the material specifications.
- The permit shall specify the time period for which the temporary sign is authorized.
 - Sizes of temporary signs shall conform to specifications in the schedule (c)(1) above.
 - The advertising message or copy contained on any permitted temporary sign shall pertain only to the business being currently conducted, or to be conducted on or within the

premises on which such sign is erected or maintained. This provision does not apply to signs of a civic nature.

Comment [D2]: This whole section needs to be reworked.

(3) Banners. Banner requirements shall be as follows:

- a. The banner must be made of nonflammable material that will not shred and has adequate air holes. For banners hanging overhead across a street, roadway or highway the banner must contain at least three air holes for every 40 feet.
- b. The building department shall be permitted to inspect the banner or a sample of material prior to it being erected.
- c. The banner must be securely attached, sufficient to withstand storms, including strong gusts of wind and continuous pounding by the elements. The manner of attachment shall first be submitted to the building department.
- d. If a banner becomes partially unsecured, it shall be immediately reattached or removed by the entity which erected it.
- e. If a banner begins to shred, it shall be immediately repaired or removed by the entity which erected it.
- f. If the entity which erected the banner fails to comply with the standards of subsection (c) or fails to remove the banner by the time the permit expires, the city shall remove the banner and shall charge the cost thereof to the entity erecting the banner.
- g. Any banner permit may be canceled by the city if the installation becomes dangerous to motorists or pedestrians, unduly interferes with free movement of traffic or otherwise endangers the health, safety or welfare of persons in the city.
- h. No banners shall be erected unless a permit having a maximum duration of 30 days is first obtained from the building department. Only two permits may be issued per year.
- i. Banners or inflatables shall be attached to the premises to which the message contained thereon pertains.
- j. Banners or inflatables may not be strung overhead across roads, streets or highways.
- k. ~~A banner shall not have displayed thereon any legion or symbol which is or purports to be an imitation of or resembles, or which may be mistaken for a traffic control device or which attempts to direct the movement of traffic.~~
- l. Banners or inflatables may not exceed 32 square feet.

(4) Overhead banners. Requirements for overhead banners shall be as follows:

- a. An overhead banner shall be permitted for city approved events or other city or governmental sponsored messages.
- b. The design, method of installation, and location of overhead banners shall not endanger persons using roads, streets or highways or unduly interfere with the free movement of traffic.
- c. An overhead banner shall have a minimum bottom height of 18 feet above the pavement, and shall not be placed closer than ten feet on either side of traffic signals, and shall not be placed so as to obstruct a clear view of traffic signals or other traffic control devices.
- d. An overhead banner shall:
 1. Not exceed two and one-half feet in height.
 2. Contain a snap top to permit a one-fourth-inch cable to run across the top.
- e. There shall be no more than two overhead banners placed at any time on a public road, street or highway with the exact location of such banners to be approved by the city

building department, police department and the department of public works. When the banner shall be hung over a state trunkline, prior approval from the state department of transportation must be obtained.

- f. All overhead banners permits shall have a maximum duration of 30 days.

~~(5) Election signs shall be subject to the following requirements;~~

- ~~a. At polling places, on Election Day only, erected no less than 100 feet from the entrance of the polling place. Such signs may be located on the city right-of-way (margin).~~
- ~~b. Such signs shall not be located on any city right-of-way except as permitted in subsection (5) of this section.~~

(d) Other signs.

(1) Billboards. Outdoor advertising billboards may be erected in PMD zoning district adjacent to and visible from I-94, subject to the following regulations:

- a. Billboards are permitted in the adjacent area along I-94 as defined by the Highway Advertising Act of 1972, and may be the principal or primary use on the parcel in which it is located, notwithstanding subsection 122-862 (c).
- b. Billboards must be located and oriented in such a fashion as to be visible from I-94.
- c. New billboard permits will be issued only in the following cases:
 1. For non-digital billboards, when one non-conforming billboard is removed
 2. For digital billboards, when two non-conforming billboards are removed.
- d. Digital billboards—The message displayed on electronic message billboards may change a maximum of once every six seconds (an exemption from subsection 122-866(d)(1)).
- e. Billboard structures shall not exceed 65 feet in height. All billboards must provide a setback from any adjacent residential zoning district equal to the height of the billboard.
- f. Billboard structures which have two or more panels stacked, one above the other, are not permitted.
- g. Double-faced billboard structures (two panels mounted on the same structure back-to-back) are permitted.
- h. Spacing between billboards shall be 1,000 feet as provided in the Highway Advertising Act of 1972, as amended.
- i. No more than the 672 square feet billboard shall be permitted regardless of land use zone, except when adjacent to a limited access highway and permitted by applicable state law.
- j. All billboard structures shall be of steel. No wood or other combustible material shall be permitted to support such signs.
- k. Billboards supported or maintained on the roof of a building are prohibited.
- l. Billboard structures shall be restricted to and used only with respect to interstate highways, freeways or primary highways as set forth in the Highway Advertising Act, Act No. 106 of the Public Acts of Michigan of 1972 (MCL 252.301 et seq., MSA 9.391(101) et seq.).

(2) Sidewalk signs.

- a. Sidewalk signs may have a maximum area of six square feet per side.
- b. Sidewalk signs may be located on the sidewalk adjacent to the use to which they are accessory. Sidewalk signs shall be located such that they will not impede pedestrian traffic on the sidewalk, and such that they will not present a hazard to vehicular traffic.
- c. Sidewalk signs may not be permanently affixed to any object, structure, or the ground.

Comment [D3]: This seems to be duplicative of the section above. Are we separating between City and non-City banners?

Formatted: list1

- d. Sidewalk signs may only be displayed during business hours and shall be removed when the business to which the sign is accessory is closed.
- e. Each business may have a maximum of one sidewalk sign.
- f. Sidewalk signs shall be made of durable materials with a finished appearance.
- g. Sidewalk signs made of decorative wood or decorative metal, that are architecturally compatible with the style, composition, materials, colors and details of the building may be increased to a maximum of eight square feet.

Sec. 122-867. - Nonconforming signs.

- (a) Nonconforming signs shall be permitted to continue as such until removed or altered, provided that such signs are maintained in accordance with the following requirements:
 - (1) Expansion or relocation prohibited. Nonconforming signs shall not be expanded or relocated.
 - (2) Servicing. Painting, servicing, cleaning, minor repairs, or changes in sign copy panel area (sign face changes) to a nonconforming sign structure shall be permitted, provided that the sign is restored to its original design and all work is in compliance with applicable structural and electrical codes and the requirements for all signs specified above.
 - (3) Alterations. Alterations or changes to the sign structure of a nonconforming sign shall be subject to the following conditions:
 - a. The sign shall be brought into compliance with the requirements for all signs specified above.
 - b. The sign shall be brought into compliance with all applicable sign height and sign area standards for the type of sign, as specified above.
 - c. Nonconformities caused by inadequate ground sign setback at a ground sign's current location may be permitted to continue so that the existing support structure and wiring may be re-used, provided that permitted alterations will not increase this nonconformity, and provided that the ground sign is located entirely outside of all street rights-of-way and corner clearance areas.
 - d. Approval of appropriate permits by the building official.
- (b) Signs of local historical significance. Non-conforming signs located in the historic district may be repaired, reconstructed, or relocated. For the purpose of this section, the applicant shall be required to provide the information under section 122-864 for review by the planning commission.
 - (1) The city council may approve and or amend a list of existing non-conforming signs deemed to be of local historical significance by the historic district commission. Signs deemed historically significant may be repaired, reconstructed, or relocated, subject to review by the building official.
- (c) Repair of signs. This section shall not be construed to prevent the repair or restoration to a safe condition of any part of any existing, conforming or nonconforming sign when damaged by storm or other accidental emergency. Such repair or restoration shall be affected within 60 days of the event which causes the damage, unless an extension has been obtained in advance from the building department.
- (d) Relocating signs. Any sign that is moved to another location on the same or other premises shall be considered a new sign, and a permit shall be secured for any work performed in connection therewith when required by this article.

Sec. 122-868. - Table of allowable signage.

Type of Sign	Zoning Districts	Area	Height
Animated	Prohibited	—	—
Billboards	PMD	—	35 ft
Building Mounted		3 sf/lf of building frontage	
• Awning/Canopy	HHS, HC, NC, GC, C, P, PMD	35% of canopy/awning area	8 ft. min clearance
• Address Number/Nameplate	All	2 sf	—
• Building Directory	HHS, HC, NC, GC, C, P, PMD	5% of building mounted sign area	—
• Menu	HHS, HC, NC, GC, C, P, PMD	3 sf	—
• Projecting	HHS, HC, NC, GC, C, P, PMD	24 sf per sign face	8 ft. min clearance
• Wall - residential	Residential	0.5 sf/lf of building frontage or 12 sf	—
• Wall - non-residential	HHS, HC, NC, GC, C, P, PMD	1 sf/lf or 100 sf	—
• Window	HHS, HC, NC, GC, C, P, PMD	25% of individual window area	—
Changeable Copy	HHS, HC, NC, GC, C, P, PMD	part of sign area	—
Directional	All	2	4
Election	All	Maximum size allowed in district by sign type	

Flags	All	—	—
Ground			
	R1, CN-SF	16 sf	6 ft
	CN-Mid, CN	16 sf	8 ft
	MD, HHS	32 sf	8 ft
	HC, NC	40 sf	10 ft
	GC	100 sf	10 ft
	C	Not Permitted	—
	P, PMD	100 sf	35 ft
Historic	All	—	—
Opinion	All	Maximum-size-allowed-in-district by-sign-type	
Public	All	—	—
Portable	Prohibited	—	—
Residential Entry Sign	R1, CN-SF	16 sf	6 ft
	CN-Mid, CN	16 sf	8 ft
	MD, HHS	32 sf	8 ft
Roof	Prohibited	—	—
Temporary Sign	All	122-866(c)(1)	
Traffic Control	All	—	—

Secs. 122-869—122-910. - Reserved.

ARTICLE XIV. SIGNS*

*Cross reference(s)--Businesses, ch. 22.

Sec. 122-861. Purpose.

The purpose of this article shall be to permit such signs as will not, by reason of their size, location, construction or manner of display, endanger life or limb, confuse or mislead traffic, obstruct vision necessary for traffic safety or otherwise endanger the public morals, health or safety.

It is further the intent of this article to:

- (a) Maintain and enhance the aesthetic value of the City.
- (b) Encourage free expression of ideas and dissemination of messages, regardless of content, using signs that are compatible with their surroundings and legible under the circumstances in which they are seen.
- (c) Enhance pedestrian and vehicular traffic safety.
- (d) Minimize the adverse effects of signs on nearby public and private property.
- (e) Minimize driver distraction.
- (f) Protect and enhance economic vitality by assuring aesthetic appeal for residents and visitors.
- (g) Preserve property values.
- (h) Enhance the effectiveness of permitted signs and directional and warning signs.
- (i) Seek the removal of illegal signs and encourage the replacement or removal of nonconforming signs that are incompatible with the purpose of this article.

Sec. 122-862. General Requirements.

- (a) *Building Permit Required.* Except as provided in this, Article XIV, no sign shall be constructed or erected prior to the issuance of a permit by the building department, and approval from other applicable reviewing bodies.
- (b) *Historic District Approval.* Signs to be located in the Historic District need approval by the Historic District Commission, excluding temporary signs.
- (c) *Accessory to Principal Use.* All signs shall be accessory to the primary use of the lot where the sign is located and shall comply with the applicable design standards set forth herein, with the exception of any sign specifically permitted by Section 122-866(d)(2).
- (d) *Public Rights-of-Way.* Signs shall be expressly prohibited from locating in all public rights-of-way and dedicated public easements except as otherwise provided for in this ordinance, and as follows:
 - (1) Signs erected by the City or other governmental entities for public purposes are permitted.
 - (2) Building mounted signs may project over a public right-of-way or easement provided they comply with the applicable design standards for the specific type of sign and that they maintain a minimum clearance of eight feet.
 - (3) Overhead banners
 - (4) Sidewalk signs
- (e) *Construction requirements.*
 - (1) All signs shall conform to the city building code unless more stringent requirements are specified in this article. Signs and sign structures shall be designed and constructed to resist wind and seismic forces as specified in this section. All bracing systems shall be designed and constructed to transfer lateral forces to the foundation. For signs on building the dead and lateral loads shall be transmitted through the structural frame of the building to the ground in such a manner as not to overstress any of the elements thereof.
 - (2) The overturning movement produced from lateral forces shall in no case exceed two-thirds of the deadload resisting movement. Uplift due to overturning shall be adequately resisted by proper anchorage to the ground or the structural frame of the building. The weight of earth imposed over footings may be used in

determining the dead-load resisting movement. Such earth shall be carefully placed and thoroughly compacted.

- (3) *Wind loads.* For the purpose of design, wind pressure shall be taken upon the gross area of the vertical projection of all signs and sign structures at not less than 20 pounds per square foot for those portions less than 60 feet above the ground.
- (4) *Allowable stresses.* The design of wood, concrete or steel members shall conform to the requirements of the most recently adopted version of the Michigan Building Code, and loads, vertical and horizontal, exerted on the soil shall not produce stresses exceeding those specified therein. The working stresses of wire rope and its fastenings shall not exceed 25 percent of the ultimate strength of the rope or fasteners. Working stresses for wind or seismic loads combined with deadloads may be increased as specified in the Michigan Building Code.
- (5) *Supports.* The supports for all signs or sign structures shall be placed in or upon private property and shall be securely built, constructed and erected in conformance with the requirements of this chapter.
- (6) *Fastenings.* Signs attached to masonry, concrete or steel shall be safely and securely fastened thereto by means of metal anchors, bolts, or approved expansion screws of sufficient size and anchorage to support safely the loads applied. Anchors which attach signs to masonry surfaces shall be inserted into mortar joints.
- (f) *Traffic and Pedestrian Hazards.* The placement, size, content, coloring or manner of illumination of signs shall not create traffic or pedestrian hazards. No sign shall make use of the words “stop,” “look,” “danger” or other word, phrase or symbol in a manner that is confusing or misleading. No sign or flashing light shall be erected or maintained in any manner which, by reason of its size, location, context, coloring or manner of illumination, shall constitute a traffic hazard or which shall interfere with the visibility of any traffic control device.
- (g) *Substitution.* Notwithstanding anything herein to the contrary, noncommercial copy may be substituted for commercial copy on any lawful sign structure, and any sign permitted by this article may contain a non-commercial message.
- (h) *Obstruction Prohibited.* No sign shall be placed so as to obstruct any fire escape, required exitway, window, or door opening used as a means of passage or as access for firefighting purposes.
- (i) *Obstruction to ventilation.* A sign shall not be attached in any form, shape or manner which will interfere with any opening required for ventilation by the building code; except that such signs may be erected in front of and may cover transom windows when not in violation of the provisions of this chapter.
- (j) *Maintenance.* All signs, sign frames, sign copy area, panels, structural elements, lamps and electrical hardware shall be maintained in good repair and working order, so as to present a neat and orderly appearance. Non-galvanized or corrosion-resistant materials shall be painted when necessary to prevent corrosion.
- (k) *Authorized sign contractors.* Every person before engaging or continuing in the business of constructing, repairing or dismantling signs, poster boards or other display signs in the city, shall first furnish the city a public liability insurance policy, approved by the city attorney, with minimum limits of \$300,000.00 combined single limit bodily injury and/or property damage, and the contractor agrees to indemnify the city from all damage suits or actions of every nature brought or claimed against the contractor for or on account of injuries to persons or damages to property received or sustained by any person or person through any act of omission or negligence of such erector, agents or employees in the erection, repair or dismantling of any sign, poster board or other display sign. Such policy shall contain a clause whereby such policy cannot be canceled until after a written notice of intention to cancel has been filed with the city clerk at least 30 days prior to the date of cancellation.
- (l) *Master Sign Plan* in HHS, HC, NC, GC, C, PMD, and P districts and for non-residential uses in R1, CN-SF, CN-Mid, CN, MD districts.

All non-residential buildings shall submit a master sign plan as part of their sign permit application. The master sign plan shall identify size, location, and lighting of all existing and proposed signs located or to be located on the building.

- (m) *Modification of standards:* Upon receipt by of an application for a permit that includes a request to modify any of the standards in this Chapter, the Planning Commission may, at any regular meeting or any special meeting duly called for that purpose, consider whether the proposed sign, if erected, will achieve the purposes of this Chapter. The applicant shall demonstrate the following to the satisfaction of the Planning Commission:

- (1) Whether the structure, dimensions and placement of the proposed sign generally conform to the character of signs in the neighborhood or business district;
- (2) Whether the proposed sign achieves the purposes of this Chapter as described in Section 122-861;
- (3) Whether the proposed sign achieves another public purpose consistent with the purpose of this Chapter or the City's Master Plan;
- (4) Whether the proposed sign achieves innovation and variety in design and compatibility;
- (5) The proposed sign shall be designed, constructed, operated and maintained to assure long-term compatibility with surrounding uses, buildings, and signs. Consideration shall be given to the placement, bulk, height and materials used in construction.
- (6) The proposed sign shall promote the use of signage in a socially and economically desirable manner and not be detrimental, hazardous, or disturbing to existing or future neighboring uses, persons, property or public welfare.
- (7) Appeals from the decision of the Planning Commission shall be heard by the zoning board of appeals.

Sec. 122-863. Definitions.

The following words, terms and phrases when used in this article shall have the meanings ascribed to them in this section, except where the context clearly indicates a different meaning:

Abandoned sign means a sign which directs attention to an object, product, place, activity, person, institution, organization or business which is no longer currently existing and is not maintained in accordance with the standards set forth in this chapter and contains or exhibits broken panels, visible rust, visible rot, damaged support structures, missing letters or which is otherwise dilapidated, unsightly, unkempt and for which the business or property owner is not accepting maintenance responsibility where such acts evidence an intent to abandon. Signs of local historical significance may not be considered abandoned

Building frontage means the outside perimeter measurements of the building wall on which wall the sign shall be placed.

Clearance. The vertical distance between the surface grade beneath the sign and the lowest point of the sign, including framework and embellishments.

Damaged sign means a sign or supporting structure which is torn, defaced, dented, smashed, broken, vandalized or destroyed.

Display surface means the sign area measured in square feet. Superficial ornamentation, trim or simple type appendages of non-message-bearing character shall not be included in determining display surfaces so long as they do not exceed 20 percent of sign area. The square footage of a two-, three- or four-faced sign shall mean the square footage of the largest face of the sign.

Flag means a flag bearing the official design of a nation, state, municipality, educational institution or organization.

Mechanical Sign means any signs that have any visible moving parts, mechanical movement or other apparent visible movement achieved by electrical or mechanical means or action of normal wind currents.

Mural means a design or representation painted, drawn, or otherwise attached to the exterior surface of a structure that does not advertise a business, product, service or commercial activity.

Nameplate means a sign identifying only the name, occupation, or profession and address of the business or occupant of the lot where the sign is placed.


Nonconforming sign means a sign which complied with the provisions of the chapter in effect at the time that it was erected but which does not conform to this article.

Seasonal display means decorations that do not convey a commercial message. These shall not be considered signage, and shall not require a permit.


Sign means a name, identification, description, announcement, display, illustration or insignia which is affixed to or painted or represented directly or indirectly upon a building, structure or piece of land, which directs attention to an object, product, place, authority, person, institution, organization or business and which is visible from any public street, right-of-way, sidewalk, alley, park or other places open to the public.

- (1) *Address sign* means a numerical address with numbers no greater than eight inches in height.


- (2) *Animated sign* means a sign that uses light emitting elements including but not limited to light bulbs, fixtures, LEDs, fiber optic lighting to create a continuously scrolling, flashing, or animated effect on any sign visible from the exterior of the building.
- (3) *Awning sign* means a sign that is painted on, attached to, or an integral part of an awning or canopy.
- (4) *Banner* means a sign, including inflatables, consisting of a large piece of cloth or similar flexible material, in public view, in front of a building or entranceway.
- (5) *Banner, overhead*, means a sign consisting of a large piece of cloth or similar flexible material suspended by wires in public view across a street or other public space.
- (6) *Billboard* means an off-premises sign.
- (7) *Building directory* means a sign identifying multiple tenants in a single building located above the street level façade (such as a multiple-story office or commercial building).
- (8) *Building-Mounted Sign* means a display sign that is painted on, adjacent to or attached to a building wall, door, window or related architectural feature. Such signs include, but are not limited to awning, projecting, wall and window signs.
- (9) *Directional sign* means a sign not exceeding two square feet which contain only noncommercial messages including designation of restrooms, telephone locations, restrictions on smoking, door openings, private control on premises vehicle or bicycle traffic and parking.
- (10) *Election sign* means a sign advocating or opposing a candidate for public office or a position on an issue to be determined at an election, but does not advertise any products, goods, services or businesses.
- (11) *Electronically illuminated message sign* means a sign with a message displayed on a surface with an electronically illuminated changeable copy area (often composed of LEDs).
- (12) *Ground sign* means any freestanding sign, not attached to a building, including monument or pole signs.
- (13) *Hanging sign* means a sign suspended under an awning, canopy, or marquee.
- (14) *Historical sign* means a sign designating a building as a historical structure, names of buildings, dates of construction, and other historic information.
- (15) *Illuminated sign* means a sign that provides artificial light directly or through transparent or translucent material from a source connected to or within such a sign, on which is illuminated by a light so shielded as to prevent direct rays from being visible from the public right-of-way.
- (16) *Inflatable sign* means a temporary sign that is intended to be expanded by air or other gas for its proper display or support.
- (17) *Marquee sign* means a projecting sign that accommodates changeable copy.
- (18) *Monument sign* means a freestanding sign supported by a pedestal or base, with permanent attachment to the ground.



- (19) *Off-premises sign* means a sign not relating to the premises on which such sign is located.
- (20) *On-premises sign* means a sign related to the premises on which such sign is located.
- (21) *Opinion sign* means a sign advocating or opposing an opinion or point of view, but does not advertise any products, goods, services or businesses.
- (22) *Pole sign* means a sign which is erected on a single freestanding mast or pole, not attached to a building.




- (23) *Portable sign* means a sign of a temporary nature, not securely anchored to the ground or to a building or structure, excluding sidewalk signs.
- (24) *Projecting sign* means a sign which is attached directly to the building wall, and which extends more than 18 inches from the face of the wall. A projecting sign shall project not more than four feet from the wall of a building and shall not project above the front wall of the building.




- (25) *Public signs* means a traffic or other governmentally erected notices, railroad crossing, danger and other temporary emergency signs, location of transit line, a railroad station or other public carrier or other non-advertising signs.
- (26) *Residential entry feature or sign* means an architectural feature with signage at each entrance to a residential subdivision, neighborhood, apartment community, condominium development, or mobile home condominium project.
- (27) *Roof sign* means a sign which is constructed and maintained upon or above the roof of a building, marquee, or parapet wall and which is wholly or partially supported by such building.
- (28) *Sidewalk sign* means a temporary sign placed within the right-of-way. These types of signs may include "A" Frame, "T" Frame or other temporary styles, which are not permanently affixed to the ground.
- (29) *Special Event Sign* means banners, pennants, balloons or festoons associated with a specific event and displayed for a specified and limited period of time, including commercial store sales, etc.
- (30) *Temporary Sign* means display signs, banners, balloons, festoons or other advertising devices constructed of cloth, canvas, fabric, plastic or other light temporary material, with or without a structural frame, or any other sign intended for a limited period of display, but not including decorative displays for holidays or public demonstration.
- (31) *Wall sign* means a sign which is painted on or attached directly to the surface of masonry, concrete, frame or other approved building walls, and which extends not more than 18 inches from the face of the wall and which does not extend above the parapet, eaves or building facade.

(32) *Window sign* means any sign within a building placed within 12 inches of a window or upon a window pane and that is visible from the exterior of the building not including merchandise located in a window.

Sign Area. The gross surface area within a single continuous perimeter enclosing the extreme limits of all sign copy or surface of any internally-illuminated sign, awning or canopy. Such perimeter shall not include any structural or framing elements lying outside the limits of such sign and not forming an integral part of the display. Where a sign has two (2) or more faces, the sign area shall equal the total area of all sign faces, except where two (2) faces are placed back to back and are at no point more than three feet (3') apart, the sign area shall equal the area of the larger single sign face.



Sign Height. The vertical distance measured from the average grade at the sign location to the highest point of the sign.



Sign Structure. Anything constructed or erected for the purpose of supporting a sign, the use of which requires permanent location on the ground or attachment to something having permanent location on the ground.

Sec. 122-864. Sign permit requirements.

a. Schedule of sign permit requirements

It shall be unlawful for any persons to erect, alter or relocate within the city any sign or other advertising structure without first obtaining a permit as indicated in the following schedule:

Type of Sign*	Permit Required	Sign Standards
Animated	Prohibited	---
Barber Pole	N	---
Building Mounted Signs		122-866 (b)
• Address Number/Nameplate	N	---
• Awning, Canopy	Y	122-866(b)(6)
• Building Directory	Y	122-866(b)(9)
• Menu	Y	122-866 (b)(8)
• Projecting	Y	122-866(b)(7)
• Wall	Y	122-866(b)(5)

Type of Sign*	Permit Required	Sign Standards
• Window	N	122-866(b)(10)
Directional	N	122-866(a)(6)
Flags	N	---
Ground (pole and monument)	Y	122-865(a)
• Billboards	Y	122-866(d)(2)
• Residential Entry Sign	Y	122-866(a)(8)
Historic Designation	N	---
Mural	Y	--
Opinion	N	122-866(c)(6)
Off-premises signs (except billboard)	Prohibited	---
Portable (except sidewalk signs)	Prohibited	---
Public	N	---
Roof	Prohibited	---
Temporary Signs		122-866(c)
• Banner	Y	122-866(c)(3)
• Overhead Banner	Y	122-866(c)(4)
• Construction – R1, MD, CN-SF, CN-Mid, CN and HHS	N	122-866(c)(1)
• Construction – All other districts	Y	122-866(c)(1)
• Election Sign	N	122-866(c)(5)
• For Sale, For Lease – Non-Residential	N	122-866(c)(1)
• For Sale, For Lease - Residential	N	122-866(c)(1)
• Garage Sale	N	---
• Inflatables	Y	122-866(c)(3)
• Special Events	Y	122-866(c)(1)
Sidewalk	Y	122-866(d)(3)
Traffic Control	N	---
Vehicle	N	---

(b) **Application for permits; contents.**

- (1) Application for sign permits shall be made upon forms provided by the building department.
- (2) Applications for signs other than overhead banners shall contain or have attached thereto the following information:
 - a. Name, telephone number and address of applicant.
 - b. Name, address and telephone number of owner or lessee of the premises upon which the sign is to be erected.
 - c. A written statement signed by the owner or lessee of the premises upon which the sign is to be erected, indicating his consent thereto, or the signed contract between the parties.
 - d. The address of the premises upon which the sign is to be attached or erected.
 - e. One set of plans showing the dimensions, materials, height and method of anchorage of the sign.
 - f. Position of the sign in relation to nearby buildings, structures and property lines.
 - g. Insurance policy or proof of financial security as required in section 122-862(k).
 - h. On electrical signs, certification by Underwriters Laboratory or some other recognized testing laboratory. Electrical sign installations shall comply with Article 600 of the National Electrical Code.
 - i. Such other information as deemed necessary to show compliance with this article.
- (3) Application for overhead banners shall contain or have attached thereto, the following information:
 - a. The name of organization or group sponsoring the banner.
 - b. A statement as to purpose of the banner.
 - c. Phrase on the banner, and/or sketch of the content
 - d. Location where banner is to be erected.

- e. The dates the banner will be hung.
- f. The name, address and telephone number of the applicant.
- g. Insurance policy or proof of financial security as required in section 122-862 (k).
- h. Such other information as deemed necessary to show compliance with this article and with Act No. 200 of the Public Acts of Michigan of 1969 (MCL 247.321 et seq., MSA 9.140(21) et seq.), and R247.271--R247.279 of the Michigan Administrative Code, 1979.

(4) Application for sidewalk signs shall include a sidewalk occupancy permit application.

Sec. 122-865. Unsafe and Prohibited signs

The following signs are prohibited in all zoning districts:

- (a) Notice of unsafe and prohibited signs. When any sign or sign structure becomes insecure, in danger of falling, or otherwise unsafe, or if any sign or sign structure shall be unlawfully installed, erected, or maintained in violation of any of the provisions of this chapter, or prohibited signs, it shall be considered a nuisance per se. The owner or lessee shall, upon receipt of written notice of the building official, immediately in the case of an unsafe sign, and in any case within not more than ten days, make such sign conform to the provisions of this article or shall remove it. If, after ten days, the notice is not complied with, the building official may remove such sign at the expense of the owner or lessee after having obtained an order from the administrative hearings bureau. The cost, including actual attorney fees, shall be assessed against the property as provided in Article VIII of the City Charter.
- (b) *Prohibited signs.*
 - (1) *Abandoned signs.*
 - (2) *Signs not complying with sign schedules.* Signs not complying with the requirements as set forth in schedules or tables contained in sections 122-866 and 122-868 respectively.
 - (3) *Signs not specifically permitted.* Signs which are not specifically permitted under the sections of this chapter.
 - (4) *Signs located near overhead electrical conductors.* Signs located with less than six feet horizontal clearance or 12 feet vertical clearance from overhead electrical conductors which are energized in excess of 250 volts.
 - (5) *Animated signs.*
 - (6) *Portable signs, not including sidewalk signs.*
 - (7) *Roof signs.*
 - (8) *Obscene Material.* Display of obscene material upon any sign is prohibited.
 - (9) *Mechanical Signs.*
 - (10) *Electronically illuminated message sign.*

Sec. 122-866. Sign Design Standards.

(a) Ground Signs

Zoning District	Maximum		Sign Setback Requirements
	Sign Area	Sign Height	
R1 ¹ , CN-SF ¹	16 sq. ft	6 ft.	Front yard – at least 3 feet from front property line. 10 feet from side or rear lot lines.
CN-Mid ¹ , CN ¹	16 sq. ft	8 ft.	Front yard – at least 3 feet from front property line. 10 feet from side or rear lot lines.
MD ¹ , HHS, HC	32 sq. ft	8 ft.	Front yard – at least 3 feet from front property line. 10 feet from side or rear lot lines.
NC	40 sq. ft	10 ft.	Front yard – at least 3 feet from front property line. 10 feet from side or rear lot lines.
GC	100 sq. ft	10 ft.	Front yard – at least 3 feet from front property line. 10 feet from side or rear lot lines.
C	Prohibited	Prohibited	--
P, PMD	100 sq. ft	35 ft	Front yard – at least 3 feet from front property line. 10 feet from side or rear lot lines

¹ For non-residential uses only

- (1.) *Number of Signs.* If permitted in a district, one monument or pole sign shall be allowed per lot or parcel. Lots that have more than 100 feet of frontage on two or more public streets shall be permitted one ground sign for each street frontage. A second ground signs shall have a maximum area of 50% of that otherwise permitted for a ground sign in the district .
 - (2.) *Height requirement* – no monument sign shall exceed 10 feet in height.
 - (3.) *Corner Clearance.* Signs shall be located outside of any corner clearance area as described in Section 122-649 of this Ordinance.
 - (4.) *Materials.* Ground or pole signs shall be constructed out of decorative materials that complement the design of principal buildings within the development. Natural materials such as stone, decorative masonry, wood, or metal are preferred sign construction materials.
 - (5.) *Landscaping.* Low level landscaping shall be provided around the base of the ground sign, but shall not obscure any part of the sign message.
 - (6.) *Directional Signs.* Shall not exceed 2 square feet of sign area.
 - (7.) *Drive-Through Signs.* Any use that includes a drive-through is permitted to have signs that relate to the drive-through facility, such as menu order board signs or information signs. The drive-through signs may have a maximum height of six feet and a maximum area of 32 sq. ft. per drive-through use, and shall not be included in the computation of total sign area for the parcel unless such signs are legible from a point of observation off the premises.
 - (8.) Residential entry signs shall be subject to the following standards;
 - a. Maximum of one (1) sign on each side of the entrance from a major street.
 - b. May not exceed the maximum area permitted for a ground sign in the applicable district.
- (b) *Building Mounted Signs.* Building mounted signs, including wall, awning, projecting and window signs shall comply with the following requirements:
- (1.) *Location.*
 - a. Building mounted signs may be located on any façade that faces a street, parking area, or vehicle circulation area that provides access to more than one parcel, or on a façade where a public entrance is located.
 - b. Upper story tenants may only have window signs, except as allowed for in subpart d.
 - c. Illuminated building mounted signs may not be located on a façade that faces a property line that abuts a residential zoning district unless the sign is set back at least 200 feet from the property line or

screening is provided that will completely obscure the view of the sign from the adjacent residential district.

- d. In the case of a building that contains two or more businesses each business that is directly accessible from the exterior of the building may have a building mounted sign on the façade where the primary or main customer entrance is located. For the purposes of calculating sign area in such multi-tenant buildings, the frontage controlled by each tenant on the façade where the entrance is located shall be used to calculate linear frontage.
- (2.) *Sign Area.*
- a. The total area of all building mounted signs, including wall, awning, projecting and window signs, shall not exceed three square feet for each one linear foot of building frontage on the side of the building the sign(s) are located on.
- (3.) *Minimum Height.* Awning and projecting signs shall maintain a minimum clearance of 8 feet between the grade level below the sign and the lowest part of the sign (including sign support devices).
- (4.) *Materials.*
- a. Building mounted signs shall incorporate exterior materials, finishes and colors that are the same, similar, or complementary to those used on the principal building.
 - b. Building mounted signs shall be professionally constructed using high-quality materials such as metal, stone, hard wood, or brass. The use of exposed neon tubing in conjunction with other types of materials to emphasize the business name or logo is permitted; however, neon tubing outlining windows or other architectural features is prohibited.
 - c. Internally lit box signs are prohibited.
 - d. External illumination of signs shall be limited to fully-shielded light fixtures with a maximum of 900 lumens. Such fixtures shall be mounted above the sign face with all light directed downward and concentrated on the area of the sign to prevent glare upon the street or adjacent property.
 - e. To minimize damage to masonry, all mounting and supports should be inserted into mortar joints and not into the face of the masonry.
- (5.) *Wall Signs.*
- a. No surface of a wall sign may project beyond or overhang any wall or permanent architectural feature by more than eighteen inches.
 - b. In non-residential districts wall signs cannot exceed 1 square foot for each linear foot of building frontage, or 100 square feet, whichever is less.
 - c. In residential districts, residential uses including multiple family dwelling containing 3 or more units, sorority, or fraternity houses, wall signs cannot exceed .5 square feet for each linear foot of building frontage, or 12 square feet.
 - d. In residential districts, for non-residential uses, wall signs cannot exceed 1 square foot for each linear foot of building frontage or 100 square feet whichever is less.
- (6.) *Awning Signs.*
- a. Sign lettering or logos may comprise up to 35% of the total exterior surface of an awning.
 - b. A minimum vertical clearance of 8 feet shall be provided between the lowest point of the awning and the sidewalk.
 - c. Internal illumination of awning signs is permitted where the permitted awning sign area is illuminated through semi-opaque material and the remainder of the awning consists of opaque material.
- (7.) *Projecting Signs.*
- a. Projecting signs shall be secured to the building by metal anchors, bolts, supports, rods or braces.
 - b. Projecting signs are limited to 24 square feet of sign area per sign face.
 - c. A minimum vertical clearance of eight feet shall be provided between the lowest point of the sign and the sidewalk.

(8.) *Menu Signs.* Menu signs shall be located in a permanently mounted display box on the surface of the building adjacent to the entry, and may have a maximum area of 3 square feet.

(9.) *Building Directory Signs.*

- a. The building directory sign shall be separate from any permitted signs accessory to the uses occupying the street level façade.
- b. The maximum sign area of the building directory sign shall be equal to five percent (5%) of the total permitted building mounted sign area.

(10.) *Window Signs.* May not occupy more than twenty-five percent (25 %) of the total transparent area of any individual window.

(c) *Temporary Signs.*

(1.) Schedule of regulations for temporary signs:

<i>Temporary Signs</i>	<i>Maximum Size (Square Feet)</i>	<i>Maximum Duration</i>
Banners	122-866(c)(3)	Two (2) permits allowed per calendar year. Each permit expires after 30 days.
Overhead Banners	122-866(c)(4)	30 days
Construction signs, residential and office properties R1, CN-SF, CN-Mid, CN, MD and HHS	12	The earliest of the following: to issuance of certificate of occupancy, final inspection of permit, or 7 days after completion of work.
Construction all other zones	64	Within 7 days after completion of construction
Special Event signs -	6	Three (3) permits allowed per calendar year. Each permit expires after 3 days.
For sale, for rent, for lease, pertaining to real estate, residential properties (no permit required)	12	3 days after purpose of sign fulfilled
For sale, for rent, for lease, signs relating to real estate, nonresidential zones	64	10 days after purpose of sign fulfilled
Election signs (no permit required)	Maximum size allowed by district by sign type	10 days after final election

(2.) *Temporary signs general.* Temporary signs may be constructed of materials other than those specified in the chapter, with or without structural frames. Temporary signs not regulated by the Schedule contained in section 122-866 (above) or which are listed in Schedule and exceed 20 square feet in total size must conform to all standards that apply to permanent signs in the zoning district which the temporary sign is erected with the exception of the material specifications.

- a. The permit shall specify the time period for which the temporary sign is authorized.
- b. Sizes of temporary signs shall conform to specifications in the Schedule (c) (1) above.
- c. The advertising message or copy contained on any permitted temporary sign shall pertain only to the business being currently conducted, or to be conducted on or within the premises on which such sign is erected or maintained. This provision does not apply to signs of a civic nature.

(3.) *Banners.* Banner requirements shall be as follows:

- a. The banner must be made of nonflammable material that will not shred and has adequate air holes. For banners hanging overhead across a street, roadway or highway the banner must contain at least three air holes for every 40 feet.
- b. The building department shall be permitted to inspect the banner or a sample of material prior to it being erected.
- c. The banner must be securely attached, sufficient to withstand storms, including strong gusts of wind and continuous pounding by the elements. The manner of attachment shall first be submitted to the building department.
- d. If a banner becomes partially unsecured, it shall be immediately reattached or removed by the entity which erected it.
- e. If a banner begins to shred, it shall be immediately repaired or removed by the entity which erected it.
- f. If the entity which erected the banner fails to comply with the standards of section(c) or fails to remove the banner by the time the permit expires, the city shall remove the banner and shall charge the cost thereof to the entity erecting the banner.
- g. Any banner permit may be canceled by the city if the installation becomes dangerous to motorists or pedestrians, unduly interferes with free movement of traffic or otherwise endangers the health, safety or welfare of persons in the city.
- h. No banners shall be erected unless a permit having a maximum duration of 30 days is first obtained from the building department. Only two permits may be issued per year.
- i. Banners or inflatables shall be attached to the premises to which the message contained thereon pertains.
- j. Banners or inflatables may not be strung overhead across roads, streets or highways.
- k. A banner shall not have displayed thereon any legion or symbol which is or purports to be an imitation of or resembles, or which may be mistaken for a traffic control device or which attempts to direct the movement of traffic.
- l. Banners or inflatables may not exceed 32 square feet.

(4.) *Overhead banners.* Requirements for overhead banners shall be as follows:

- a. An overhead banner shall be permitted for city approved events or other city or governmental sponsored messages
- b. The design, method of installation, and location of overhead banners shall not endanger persons using roads, streets or highways or unduly interfere with the free movement of traffic.
- c. An overhead banner shall have a minimum bottom height of 18 feet above the pavement, and shall not be placed closer than ten feet on either side of traffic signals, and shall not be placed so as to obstruct a clear view of traffic signals or other traffic control devices.
- d. An overhead banner shall:
 1. Not exceed 2.5 feet in height.
 2. Contain a snap top to permit a one-fourth-inch cable to run across the top.
- e. There shall be no more than two overhead banners placed at any time on a public road, street or highway with the exact location of such banners to be approved by the city building department, police department and the department of public works. When the banner shall be hung over a state trunkline, prior approval from the state department of transportation must be obtained.
- f. All overhead banners permits shall have a maximum duration of 30 days.

(5.) Election signs shall be subject to the following requirements;

- a. At polling places, on Election Day only, erected no less than 100 feet from the entrance of the polling place. Such signs may be located on the city right-of-way (margin).

- b. Such signs shall not be located on any city right-of-way except as permitted in subsection (5) of this section.

(d) *Other Signs.*

(1) *Billboards.* Outdoor advertising billboards may be erected in PMD zoning district adjacent to and visible from I-94, subject to the following regulations:

- a. Billboards are permitted in the adjacent area along I-94 as defined by the Highway Advertising Act of 1972, and may be the principal or primary use on the parcel in which it is located, notwithstanding Sec 122-862 (c).
- b. Billboards must be located and oriented in such a fashion as to be visible from I-94.
- c. New billboard permits will be issued only in the following cases:
 - 1. For non-digital billboards, when one non-conforming billboard is removed
 - 2. For digital billboards, when two non-conforming billboards are removed.
- d. Digital billboards - The message displayed on electronic message billboards may change a maximum of once every 6 seconds (an exemption from Sec. 122-866 (d) (1).
- e. Billboard structures shall not exceed 65 feet in height. All billboards must provide a setback from any adjacent residential zoning district equal to the height of the billboard.
- f. Billboard structures which have two or more panels stacked, one above the other, are not permitted.
- g. Double-faced billboard structures (two panels mounted on the same structure back-to-back) are permitted.
- h. Spacing between billboards shall be 1,000 feet as provided in the Highway Advertising Act of 1972, as amended.
- i. No more than the 672 square feet billboard shall be permitted regardless of land use zone, except when adjacent to a limited access highway and permitted by applicable state law.
- j. All billboard structures shall be of steel. No wood or other combustible material shall be permitted to support such signs.
- k. Billboards supported or maintained on the roof of a building are prohibited.
- l. Billboard structures shall be restricted to and used only with respect to interstate highways, freeways or primary highways as set forth in the Highway Advertising Act, Act No. 106 of the Public Acts of Michigan of 1972 (MCL 252.301 et seq., MSA 9.391(101) et seq.).

(2.) *Sidewalk Signs.*

- a. Sidewalk Signs may have a maximum area of 6 square feet per side.
- b. Sidewalk signs may be located on the sidewalk adjacent to the use to which they are accessory. Sidewalk signs shall be located such that they will not impede pedestrian traffic on the sidewalk, and such that they will not present a hazard to vehicular traffic.
- c. Sidewalk signs may not be permanently affixed to any object, structure, or the ground.
- d. Sidewalk signs may only be displayed during business hours and shall be removed when the business to which the sign is accessory is closed.
- e. Each business may have a maximum of one sidewalk sign.
- f. Sidewalk signs shall be made of durable materials with a finished appearance.
- g. Sidewalk signs made of decorative wood or decorative metal, that are architecturally compatible with the style, composition, materials, colors and details of the building may be increased to a maximum of 8 square feet.

Sec. 122-867. Nonconforming signs.

- (a) Nonconforming signs shall be permitted to continue as such until removed or altered, provided that such signs are maintained in accordance with the following requirements:
 - (1.) Expansion or relocation prohibited. Nonconforming signs shall not be expanded or relocated.
 - (2.) Servicing. Painting, servicing, cleaning, minor repairs, or changes in sign copy panel area (sign face changes) to a nonconforming sign structure shall be permitted, provided that the sign is restored to its original design and all work is in compliance with applicable structural and electrical codes and the requirements for all signs specified above.
 - (3.) Alterations. Alterations or changes to the sign structure of a nonconforming sign shall be subject to the following conditions:
 - a. The sign shall be brought into compliance with the requirements for all signs specified above.
 - b. The sign shall be brought into compliance with all applicable sign height and sign area standards for the type of sign, as specified above.
 - c. Nonconformities caused by inadequate ground sign setback at a ground sign's current location may be permitted to continue so that the existing support structure and wiring may be re-used, provided that permitted alterations will not increase this nonconformity, and provided that the ground sign is located entirely outside of all street rights-of-way and corner clearance areas.
 - d. Approval of appropriate permits by the Building Official.
- (b) *Signs of local historical significance.* Non-conforming signs located in the Historic District may be repaired, reconstructed, or relocated. For the purpose of this section, the applicant shall be required to provide the information under Section 122-864 for review by the Planning Commission.
 - (1.) The City Council may approve and or amend a list of existing non-conforming signs deemed to be of local historical significance by the Historic District Commission. Signs deemed historically significant may be repaired, reconstructed, or relocated, subject to review by the Building Official.
- (c) *Repair of signs.* This section shall not be construed to prevent the repair or restoration to a safe condition of any part of any existing, conforming or nonconforming sign when damaged by storm or other accidental emergency. Such repair or restoration shall be affected within 60 days of the event which causes the damage, unless an extension has been obtained in advance from the building department.
- (d) *Relocating signs.* Any sign that is moved to another location on the same or other premises shall be considered a new sign, and a permit shall be secured for any work performed in connection therewith when required by this article.

Sec. 122-868. Table of allowable signage

Type of Sign	Zoning Districts	Area	Height
Animated	Prohibited	--	---
Billboards	PMD	--	35 ft
Building Mounted		3sf/1lf of building frontage	
• Awning / Canopy	HHS, HC, NC, GC, C, P, PMD	35% of canopy/awning area	8 ft. min clearance
• Address Number/ Nameplate	All	2 sf	---
• Building Directory	HHS, HC, NC, GC, C, P, PMD	5% of building mounted sign area	---
• Menu	HHS, HC, NC, GC, C, P, PMD	3 sf	---
• Projecting	HHS, HC, NC, GC, C, P, PMD	24 sf per sign face	8 ft. min clearance
• Wall – residential	Residential	.5 sf/lf of building frontage or 12 sf	---
• Wall – non-residential	HHS, HC, NC, GC, C, P, PMD	1 sf/lf or 100 sf	---
• Window	HHS, HC, NC, GC, C, P, PMD	25% of individual window area	--
Changeable Copy	HHS, HC, NC, GC, C, P, PMD	part of sign area	--
Directional	All	2	4
Election	All	Maximum size allowed in district by sign type	
Flags	All	--	--
Ground			
	R1, CN-SF	16 sf	6 ft
	CN-Mid, CN	16 sf	8 ft
	MD, HHS	32 sf	8 ft
	HC, NC	40 sf	10 ft
	GC	100 sf	10 ft
	C	Not Permitted	---
	P, PMD	100 sf	35 ft
Historic	All	--	--
Opinion	All	Maximum size allowed in district by sign type	
Public	All	--	--
Portable	Prohibited	--	--
Residential Entry Sign	R1, CN-SF	16 sf	6 ft
	CN-Mid, CN	16 sf	8 ft
	MD, HHS	32 sf	8 ft
Roof	Prohibited	--	--
Temporary Sign	All	122-866(c)(1)	
Traffic Control	All	--	--

Secs. 122-869--122-910. Reserved.

DRAFT ORDINANCE 2017-03-16

SIGNS EXCERPT

DRAFT ORDINANCE 2017-03-16

SIGNS EXCERPT

DEFINITIONS

compensation or by prearrangement for definite periods of time, lodging or lodging and meals are provided for three or more unrelated persons, not living as group or household. The term "unit" as it refers to a roominghouse shall mean sleeping room, or a room which may be used as a sleeping room. (See "Sleeping room.") A boardinghouse or lodginghouse shall be deemed a roominghouse for the purposes of this chapter.

S

Satellite antenna means an accessory structure which at its widest dimension is in excess of 36 inches, capable of receiving signals from orbiting satellites and other extraterrestrial sources, together with other equipment related to such purposes.

1280 **Screen or screening** means a wall, non-wire fence, or combination of plantings of sufficient height, length, and opacity to form a visual barrier

Self-storage facility means a building or group of buildings in a controlled access compound that contains individual compartmentalized and controlled access stalls or lockers of no more than 500 square feet each for the dead storage of customers' goods or wares in enclosed buildings.

1290 **Setback** means the distance between a front, side, or rear lot line and the nearest supporting member of a structure on the lot. The "minimum required setback" is the minimum distance between a front, side, or rear lot line and the nearest supporting member of a structure (including, but not limited to, the foundation, bay windows or similar architectural features at the ground floor level supported by the building or the ground, and enclosed or covered porches) in order to conform to the required yard setback provisions of this chapter. For a site condominium, setbacks are measured from the respective front, side, and rear yard area lines associated with the condominium lot to the respective front, side, and rear of the condominium structure/building envelope.

1300 ORIGINAL: (one from standard definition, one from condo definition; combined.)
Setback means the distance between a front, side, or rear lot line and the nearest supporting member of a structure on the lot. The "minimum required setback" is the minimum distance between a front, side, or rear lot line and the nearest supporting member of a structure (including, but not limited to, the foundation, bay windows or similar architectural features at the ground floor level supported by the building or the ground, and enclosed) in order to conform to the required yard setback provisions of this chapter.
Setback, front, side and rear yard means the distance measured from the respective front, side, and rear yard area lines associated with the lot to the respective front, side, and rear of the condominium structure/building envelope.

SIGNS

Sign means any visual or graphic device designed to inform or attract attention and which is designed to be visible from outside any building or structure in which, upon which, or attached to which it may be located.

1310 ORIGINAL: combined two; edited to be slightly more content neutral.
Sign means a name, identification, description, announcement, display, illustration or insignia which is affixed to or painted or represented directly or indirectly upon a building, structure or piece of land, which directs attention to an object, product, place, authority, person, institution, organization or business and which is visible from any public street, right-of-way, sidewalk, alley, park or other places open to the public.
Sign means any visual or graphic device designed through the use of words, number, characters, or symbols to inform or attract attention and which is designed to be visible from outside any building or structure in which, upon which, or attached to which it may be located. Various types of signs and sign related terms are defined in section 122-863.

1320 REMOVED:

- Address sign.
- Building Directory sign.
- Damaged sign
- Directional sign
- Election sign
- Flag
- Hanging sign
- Historical sign
- Monument sign
- 1330 • Nameplate
- Nonconforming sign (covered under nonconforming structure)
- Off-premises sign

- On-premises sign
- Opinion sign
- Pole sign
- Portable sign
- Residential entry sign
- Seasonal display
- Special event sign.

1340

OTHER NOTES:

Added whether a sign was considered a freestanding or building-mounted sign, permanent or temporary, as applicable.
Many of these sign definitions have changed slightly or entirely due to the restrictions of Gilbert v Reed.

1350

Sign, abandoned means a sign that contains or exhibits broken panels, visible rust, visible rot, damaged support structures, or which is otherwise dilapidated, unsightly, or unkempt; and for which the business or property owner has not accepted maintenance responsibility or intentionally altered for a period of no less than 365 days, where such acts evidence an intent to abandon.

Sign, animated means a sign that uses light emitting elements including but not limited to light bulbs, fixtures, LEDs, fiber optic lighting to create a continuously scrolling, flashing, or animated effect.

ORIGINAL:

Animated sign means a sign that uses light emitting elements including but not limited to light bulbs, fixtures, LEDs, fiber optic lighting to create a continuously scrolling, flashing, or animated effect on any sign visible from the exterior of the building.

1360

Sign, awning means a sign that is painted on, attached to, or an integral part of an awning or canopy; considered a building-mounted sign.

Sign, banner means a sign consisting of a large piece of cloth or similar flexible material; considered a temporary sign.

Sign, billboard means any freestanding permanent sign that is more than ten feet tall and has an area of more than 300 sf, and as defined in the Highway Advertising Act of 1972, PA 106 of 1972, as amended.

1370

Sign, building-mounted means a sign that is attached to a building. Such signs may include, but are not limited to awning, projecting, wall, and window signs.

Sign, electronic message means a sign with a message displayed on a surface with an electronically illuminated changeable copy area, often composed of LEDs.

ORIGINAL: changed name only. Was "electronically illuminated message sign"

1380

Sign, freestanding means any sign not attached to a building, including monument or pole signs.


Sign, historic marker means a sign that is erected by a duly organized local historic preservation organization.

NEW DEFINITION. INTENT IS TO EXEMPT THESE SIGNS FROM MAX SIZES; INCLUDES THE MOTORCITIES SIGNS, YHF PLAQUES, BOULDER-MARKERS, ETC.

Sign, illuminated means a sign that provides artificial light directly or through transparent or translucent material from a source connected to or within such a sign, on which is illuminated by a light so shielded as to prevent direct rays from being visible from the public right-of-way.

1390

Sign, inflatable means a sign that is intended to be expanded by air or other gas for its proper display or support; considered a temporary sign.



REMOVED: sign, marquee. Didn't add anything.

Sign, mechanical means a sign that has any visible moving parts, mechanical movement or other apparent visible movement, achieved by electrical or mechanical means or action of normal wind currents.

Sign, overhead banner means a sign consisting of a large piece of cloth or similar flexible material suspended across a street or other public space and attached at each end; considered a temporary sign.

Sign, permanent means a sign that is securely anchored and affixed to the ground or a building in a manner such that it can remain in place without maintenance for an indefinite period of time, often one year or more.

Sign, projecting means a sign which is attached directly to the building wall or suspended under an awning, canopy, or marquee, and which extends more than 18 inches from the face of the wall; considered a building-mounted sign.

Sign, public means a sign erected or installed by a government entity.

Sign, roof means a sign which is constructed and maintained upon or above the roof of a building, marquee, or parapet wall and which is wholly or partially supported by such building; considered a type of building-mounted sign.

Sign, sidewalk means a temporary sign placed within the pedestrian right-of-way. These types of signs include "A" Frame and "T" Frame styles.


Sign, temporary means signs not permanently affixed to the ground or to a building, often constructed of cloth, canvas, fabric, plastic or other light temporary material, with or without a structural frame.

Sign, wall means a sign which is painted on or attached directly to a building wall that extends 18 inches or less from the face of the wall and which does not extend above the parapet, eaves, or building façade; considered a type of building-mounted sign.


Sign, window means any sign within a building placed within 12 inches of a window or upon a window pane and that is visible from the exterior of the building, not including merchandise located in a window.



Sign area means the gross surface area within a single continuous perimeter enclosing the extreme limits of all sign copy, or the surface of any internally-illuminated sign. Such perimeter does not include any structural or framing elements lying outside the limits of such sign and not forming an integral part of the display. Where a sign has two or more faces, the sign area shall equal the total area of all sign faces, except where two faces are placed back to back and are at no point more than three feet apart, in which case the sign area is considered to be the area of the larger face.



Sign height means the vertical distance measured from the average grade at the sign location to the highest point of the sign.



Sign structure means anything constructed or erected for the exclusive purpose of supporting a sign.

Site plan means a detailed plan showing all features of a proposed development so that the proposal may be evaluated to determine whether it meets the provisions of this chapter.

ORIGINAL: (simplified)

Site plan means a plan showing all features of a proposed development as required in Article IV of this chapter so that it may be evaluated to determine whether it meets the provisions of this chapter.

Sleeping room means a single room within a roominghouse which is usually individually rented and the entry door to the room is individually locked requiring the use of a key to gain access, and which is primarily used for sleeping purposes. The occupants may have direct access within the building to sanitary facilities, kitchen facilities and dining facilities or may share these facilities in common with other residents. See "Roominghouse."

Solar Collector means a device, substance, or element that relies upon sunshine to absorb and transform direct solar radiation through a medium to generate energy that can be used to heat or cool a building, heat or pump water, or generate electricity or other application that would otherwise require the use of a non-renewable energy source.

Solar Farm means large areas of land with several photovoltaic modules and inverters, or parabolic troughs placed on them for large scale energy generation.

REMOVED: Solar roof paneling. Not used outside of definitions.

Sorority house. See "Fraternity or sorority house."

Special use means a use that would be detrimental to other uses permitted in the same zoning district unless carefully controlled as to the number, area, size, exterior design, location, or relation to the adjacent properties and

DRAFT ORDINANCE 2017-03-16

SIGNS EXCERPT

NONCONFORMING STRUCTURES

- (4) A temporary class A nonconforming use designation shall be void after six months if any conditions imposed by the designation remain outstanding, unless the Planning Commission grants a written request for an extension of six months. No more than two extensions may be granted.
- (d) **Revocation.** Approval of a Class A designation may be revoked by the Planning Commission if the use and building is not in conformance with the approved plans, or if compliance with conditions has not been consistently demonstrated. In such case, the issue shall be placed on the agenda of the Planning Commission for consideration. Written notice must be given to the applicant not less than ten days prior to the meeting. The applicant must be given the opportunity to present information to the Planning Commission and answer questions. The Planning Commission may revoke the Class A designation if it finds that a violation of the conditions set forth by the Planning Commission in their initial decision exists and has not been remedied prior to the meeting.

Sec. 122-352. Nonconforming structures. (208)

- (a) A nonconforming building or structure is a structure, including a sign, which was lawful on the effective date of adoption or amendment of this chapter, but which does not conform to the new chapter regulations for building type, lot area, lot area per dwelling unit, lot width, lot coverage, floor area, height, screening, off-street parking, loading space, yard, or other requirements of the zoning district in which it is located.

NOTE: added "including a sign" clause when "nonconforming signs" category was removed.

- (b) Nonconforming buildings and structures may be re-used and occupied by new owners or tenants if all requirements of this Chapter are met and the restrictions below are met.
- (c) Nonconforming buildings and structures are subject to the following restrictions:
- (1) Expansion. Nonconforming structures may be expanded only in compliance with the following regulations:
 - (i) All nonconforming structures, in any zoning district, may only be expanded in such a way that does not increase a non-conforming characteristic.
 - (ii) All expansions must meet all requirements of the zoning district in which it is located, including lot coverage, heights, yard requirements, and off-street parking.
 - (iii) A non-conforming building type may not be expanded.
 - (2) Alterations. A nonconforming structure may be altered to decrease its nonconformity.
 - (3) Moving. A nonconforming structure which is moved within a site or to another site must conform to the regulations of the district in which it is located.
 - (4) Damage and removal. A nonconforming structure which is damaged by any means may be restored to its original conditions and location prior to such damage, provided such construction is completed within 18 months of the date of damage and is diligently pursued to completion. Failure to complete reconstruction results in the loss of legal nonconforming status.
 - (5) Restoration or repair.
 - (i) All repairs and maintenance work required to keep a nonconforming building in sound condition may be made, but such structure may not be structurally altered in a way inconsistent with the description and purpose of this article.
 - (ii) If a nonconforming structure or a structure housing a nonconforming use becomes physically unsafe or unlawful or poses a threat to the public health, safety, and welfare due to a lack of repairs or maintenance, the structure may be declared by the Building Department to be unsafe or unlawful by reason of physical condition. Such structure may not thereafter be restored, repaired, or rebuilt except in conformity with the provisions of this Chapter.
- (d) Restoration of Historic Structures. Restoration may be permitted of a legal nonconforming structure, designated as historic by the Ypsilanti Historic District Commission, which has been destroyed or abandoned, as defined in §122-349, provided the Planning Commission finds all of the following provisions are met:
- (1) The approved design of the restored building maintains the same design and historical character it had prior to the destruction or abandonment; or, in the case of a building that had been altered prior to destruction or abandonment, that the restored building more closely parallels the design of the original historic structure.
 - (2) All reasonable attempts at eliminating or reducing the nonconforming nature of the structure have been considered and are implemented in the restoration project.
- (e) Signs of Local Historic Significance. The City Council may approve and/or amend a list of existing nonconforming signs deemed to be of local historical significance by the Historic District Commission. Signs deemed historically significant may be repaired, reconstructed, or relocated, subject to review and approval by the Building Official.

Sec. 122-353. Acquisition of nonconformities. (209)

The City may acquire private property to remove a nonconformity, as provided in Act No. 207 of the Public Acts of Michigan of 1921 (MCL 125.581 et seq., MSA 5.2931 et seq.), as amended.

DRAFT ORDINANCE 2017-03-16

SIGNS EXCERPT

PARK DISTRICT

Sec. 122-417. Non-Use and Dimensional Regulations. (303)**(a) Minimum Lot Width**

Determined by the use and the required off-street parking, loading, screening, and yard setbacks.

(b) Minimum Lot Size

Determined by the use and the required off-street parking, loading, screening, and yard setbacks.

(c) Minimum Setbacks for Principal Structures and Attached Accessory Structures

Front yard	25 feet	Minimum setbacks increase by one foot for each foot a building or structure exceeds 30 feet in height.
Side yard	15 feet	
Street Side yard	25 feet	
Rear yard	20 feet	

(d) Height

Maximum height	Equal to that of adjacent zoning district or building type along the property line. If different heights abut, the largest setback is required.	Subject to §122-613.
----------------	---	----------------------

(e) Parking Setbacks

Front & street side yard	10 feet
Side & rear yards	10 feet

(f) Fences

Front Yard	No more than 4' in height and 50% opacity	• Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. • Subject to §122-635 • Subject to §122-675
Side, Street Side, and Rear Yards	No more than 6' in height, no opacity restriction	

(g) Signs

Freestanding Signs (temporary)	Maximum area	10 sf	Permit not required.
	Maximum height	3 feet	
	All setbacks:	0 feet Subject to §122-675	
Freestanding Signs (permanent)	Maximum area	100 sf	Permit required.
	Maximum height	35 feet	
	Front setback	3 feet Subject to §122-675	
	Side, street side, and rear setback	10 feet Subject to §122-675	
	Maximum # signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	

Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Billboards	Location	adjacent to and visible from I-94, as defined by the Highway Advertising Act of 1972.	Permit required.
	Maximum Area	672 sf	
	Maximum Height	65'	
	Other restrictions	Subject to §122-675	

(h) Other Accessory Structures

Subject to Article VI, Division 4, "Accessory Structures, Porches, and Decks"

Secs. 122-418 – 419. Reserved.

DRAFT ORDINANCE 2017-03-16

SIGNS EXCERPT

R-1 DISTRICT

(d) SIGNS*Also subject to Article VI, Div 5***(1) Signs – Residential Uses**

(i) Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit not required.
	Maximum height	3 feet	
	All setbacks	0 feet Subject to §122-675	
(ii) Freestanding signs (permanent)	Not permitted		
(iii) Building-mounted signs (temporary)	Maximum area	0.5 square feet for each linear foot of building frontage or 12 square feet, whichever less	Permit not required.
(iv) Building-mounted signs (permanent)	Maximum area	1 sq ft	Permit not required.
(v) Billboards	Not permitted		

(2) Signs – Non-residential Uses

(i) Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit not required.
	Maximum height	3 feet	
	All setbacks	0 feet Subject to §122-675	
(ii) Freestanding signs (permanent)	Maximum Area	16 sf	Permit required.
	Maximum Height	6 feet	
	Front Setback	3 feet Subject to §122-675	
	Side, street side, and rear setback	10 feet Subject to §122-675	
	Maximum number of signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	
(iii) Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever less	Permit required.
(iv) Building-mounted signs (permanent)	Maximum Area	0.5 square feet for each linear foot of building frontage, or 12 square feet, whichever less	Permit required.
(v) Billboards	Not permitted		

Secs. 122-423 – 424. Reserved.

(d) SIGNS*Also subject to Article VI, Division 5***Signs**

Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit not required.
	Maximum Height	3 feet	
	All setbacks	0 feet minimum Subject to §122-675	
Freestanding Signs (permanent)	Maximum Area	16 sf	Permit required.
	Maximum Height	6 feet	
	Front Setback	3 feet minimum Subject to §122-675	
	Side, street side, and rear setback	10 feet minimum Subject to §122-675	
	Maximum number of signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever less	Permit required.
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or up to 32 sf each face of the building façade that faces a street, parking area, or on a façade where a public entrance is located	Permit required.
Billboards	Not permitted		

Secs. 122-428 – 429. Reserved.

DRAFT ORDINANCE 2017-03-16

SIGNS EXCERPT

PMD DISTRICT

(d) SIGNS*Also subject to Article VI, Division 5***(1) Signs – Residential Uses**

Freestanding Signs (temporary)	Maximum Area	10 sf	Permit not required.
	Maximum height	3 feet	
	All Setbacks:	0 feet; Subject to §122-675	
Freestanding signs (permanent)	not permitted		n/a
Building-mounted signs (temporary)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit not required.
Building-mounted signs (permanent)	Maximum Area	1 sf	Permit not required.
Billboards	Location	adjacent to and visible from I-94, as defined by the Highway Advertising Act of 1972.	Permit required.
	Maximum Area	672 sf	
	Maximum Height	65'	
	Other restrictions	Subject to §122-675	

(2) Signs – Non-residential Uses & Group Living

Freestanding Signs (temporary)	Maximum Area	10 sf per sign	Permit required.
	Maximum height	8 feet	
	All setbacks:	0 feet; Subject to §122-675	
	max # signs	no more than 1 per 20' frontage on primary face and 1 per 50' on secondary face	
Freestanding Signs (permanent)	Maximum Area	16 sf	Permit required.
	Maximum Height	6 feet	
	Front Setback	3 feet; Subject to §122-675	
	Side, street side, and rear setback	10 feet; Subject to §122-675	
	Maximum # signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Billboards	Location	Must be adjacent to and visible from I-94, as	Permit required.

		defined by the Highway Advertising Act of 1972.	
	Maximum Area	672 sf	
	Maximum Height	65'	
	Other restrictions	Subject to §122-675	

Secs. 122-433 – 434. Reserved.

DRAFT ORDINANCE 2017-03-16

SIGNS EXCERPT

CORE NEIGHBORHOOD DISTRICTS

Sec. 122-442. Non-use and dimensional requirements for site improvements not regulated by building type.

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

(a) Outdoor Lighting

See [Section 122-609](#)

(b) Fences

Front Yard	No more than 4' height and 50% opacity	- Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. - Subject to §122-635 - Subject to §122-675
Side, Street Side, and Rear Yards	6' height max, no opacity restriction	

(c) Detached Accessory Buildings

No more than two detached accessory buildings are permitted per parcel.

(d) SIGNS

(1) Residential Uses

Freestanding Signs (temporary)	Maximum Area	10 sf	Permit not required.
	Maximum height	3 feet	
	All setbacks:	0 feet; Subject to §122-675	
Freestanding signs (permanent)	not permitted		n/a
Building-mounted signs (temporary)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit not required.
Building-mounted signs (permanent)	Maximum area	1 sf	Permit not required.
Billboards	not permitted		n/a

(2) Non-residential Uses & Group Living

Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit not required.
	Maximum height	3 feet	
	All setbacks:	0 feet; Subject to §122-675	
Freestanding Signs (permanent)	Maximum Area	16 sf	Permit required.
	Maximum Height	6 ft	
	Front Setback	3 feet; Subject to §122-675	
	Side, street side, and rear setback	10 feet; Subject to §122-675	

<i>For most non-use and dimensional requirements, see Subdivision V of this Division.</i>			
<i>Also subject to Article VI</i>			
	Maximum # signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Building-mounted signs (permanent)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit required.
Billboards	not permitted		n/a

Secs. 122-443 – 444. Reserved.

DRAFT ORDINANCE 2017-03-16

SIGNS EXCERPT

CENTER DISTRICT

Sec. 122-447. Non-use and dimensional requirements for site improvements not regulated by building type.

§ 122-609

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

(a) Outdoor Lighting			
See Section 122-609			
(b) Fences			
Front Yard & Street Side Yard	Not permitted, except for off-street parking screening or otherwise permitted by Planning Commission	- Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. - Subject to §122-635 - Subject to §122-675	
Side & Rear Yards	6' height max, no opacity restriction		
(c) Detached Accessory Buildings			
No more than two detached accessory buildings are permitted per parcel.			
(d) SIGNS			
(1) Residential Uses			
Freestanding Signs (temporary)	Maximum Area	10 sf	Permit not required .
	Maximum height	3 feet	
	All setbacks	0 feet Subject to §122-675	
Freestanding signs (permanent)	not permitted		N/A
Building-mounted signs (temporary)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit not required .
Building-mounted signs (permanent)	Maximum Area	1 sf	Permit not required .
Billboards	not permitted		n/a
(2) Non-residential Uses & Group Living			
Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit required .
	Maximum height	3 feet	
	All setbacks	0 feet Subject to §122-675	
Sidewalk Signs (freestanding temporary signs in the	Max size of 6sf per face, maximum 2 faces, max height of 4 feet.		Permit required .
	Must allow for a 5' clear path of travel on at least one side.		
	May only be displayed during business hours.		
	Sidewalk signs must be constructed of durable wood, metal,		

For most non-use and dimensional requirements, see Subdivision V of this Division.			
Also subject to Article VI			
public ROW)	or plastic. Any fabric shall be affixed in place on all sides.		
	Subject to §122-675		
	Maximum number of signs	one per business	
Freestanding Signs (permanent)	Not Permitted		
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required
Overhead banners (building-mounted signs that span a public right-of-way)	The design, method of installation, and location of overhead banners must not endanger persons using any part of the public right-of-way or unduly interfere with the movement of people.		Permit required
	Minimum height to bottom of banner is 18 feet.		
	Must not be located closer than 10 feet to an intersection.		
	Shall not be more than 4 feet in height.		
	No more than one overhead banner shall be placed per block at any given time.		
	Overhead banners may remain in place for no longer than thirty days.		
	When located spanning a State trunkline, must conform to PA 200 of 1969 and obtain a permit from MDOT.		
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required
Billboards	not permitted		

Secs. 122-448 – 449. Reserved.

DRAFT ORDINANCE 2017-03-16

SIGNS EXCERPT

CENTER DISTRICT

Sec. 122-452. Non-use and dimensional requirements for site improvements not regulated by building type.

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

(a) Outdoor Lighting

See Section 122-609

(b) Fences

Front Yard and Street Side Yard	No more than 6' height	- Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. - Subject to §122-635 - Subject to §122-675
Side and Rear Yards	10' height max	

(c) Detached Accessory Buildings

No more than two detached accessory buildings are permitted per parcel.

(d) SIGNS

(1) Residential Uses

Freestanding Signs (temporary)	Maximum Area	10 sf	Permit not required.
	Maximum height	3 feet	
	All setbacks	10 feet Subject to §122-675	
Freestanding signs (permanent)	not permitted		
Building-mounted signs (temporary)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit not required.
Building-mounted signs (permanent)	Maximum area	1 sf	Permit not required.
Billboards	not permitted		

(2) Non-residential Uses & Group Living

Freestanding Signs (temporary)	Maximum Area	10 sf per sign	Permit required.
	Maximum height	8 feet	
	All setbacks	10 feet Subject to §122-675	
	Maximum # of signs	No more than 1 per 20' of lot frontage on primary lot frontage and 1 per 50' on secondary lot frontage	
Sidewalk Signs (freestanding temporary signs in the	Not permitted in NC or GC.		Permit required.
	Max size of 6sf per face, maximum 2 faces, max height of 4 feet.		
	Must allow for a 5' clear path of travel on at least one side.		

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

public ROW)	May only be displayed during business hours.		
	Sidewalk signs must be constructed of durable wood, metal, or plastic. Any fabric shall be affixed in place on all sides.		
	Subject to §122-675		
	max # signs	1 per business	
Freestanding Signs (permanent)	Maximum Area	HC & NC: 20 sf; GC: 100 sf	Permit required.
	Maximum Height	10 feet	
	Front Setback	3 feet from lot line or 10 ft from back of curb, whichever greater distance from roadway. Subject to §122-675	
	Side, street side, and rear setback	10 feet Subject to §122-675	
	Maximum # signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 50% of the area of the sign on the primary face.	
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Overhead banners (building-mounted signs that span a public right-of-way)	Not permitted in NC or GC.		Permit required.
	The design, method of installation, and location of overhead banners must not endanger persons using any part of the public right-of-way or unduly interfere with the movement of people.		
	Minimum height to bottom of banner is 18 feet.		
	Must not be located closer than 10 feet to an intersection .		
	Shall not be more than 4 feet in height.		
	No more than one overhead banner shall be placed per block at any given time.		
	Overhead banners may remain in place for no longer than thirty days.		
	When located spanning a State trunkline, must conform to PA 200 of 1969 and obtain a permit from MDOT.		
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Billboards	not permitted		

Secs. 122-453 – 459. Reserved.

DRAFT ORDINANCE 2017-03-16

SIGNS EXCERPT

HEALTH & HUMAN SERVICES DISTRICT

Sec. 122-462. Non-use and dimensional requirements for site improvements not regulated by building type.

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

(a) Fences			
Front yard, street side yard	No more than 6' height and 50% opacity	Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. • Subject to §122-635 • Subject to §122-675	
Side, and rear yards	10' height max, no opacity restriction		
(b) Outdoor Lighting			
See Section 122-609			
(c) Detached Accessory Buildings			
No more than two detached accessory buildings are permitted per parcel.			
(d) SIGNS			
(1) Residential Uses			
Freestanding Signs (temporary)	Maximum Area	10 sf	Permit not required.
	Maximum height	3 feet	
	All setbacks	10 feet Subject to §122-675	
Freestanding signs (permanent)	not permitted		
Building-mounted signs (temporary)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit not required.
Building-mounted signs (permanent)	Maximum area	1 sf	Permit not required.
Billboards	not permitted		
(2) Non-Residential Uses & Group Living			
Freestanding Signs (temporary)	Maximum Area	10 sf per sign	Permit required.
	Maximum height	8 feet	
	All setbacks	10 feet Subject to §122-675	
	Maximum # of signs	No more than 1 per 20' of lot frontage on primary frontage and 1 per 50' on secondary frontage	

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

Sidewalk Signs (freestanding temporary signs in the public ROW)	not permitted		
Freestanding Signs (permanent)	Maximum Area	20 sf	Permit required.
	Maximum Height	10 feet	
	Front Setback	3 feet from lot line or 10 ft from back of curb, whichever greater distance from roadway; Subject to §122-675	
	Side, street side, and rear setback	10 feet; Subject to §122-675	
	max # signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 50% of the area of the sign on the primary face.	
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Overhead banners (building-mounted signs that span a public right-of-way)	Not permitted		
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Billboards	not permitted		

Secs. 122-463 – 464. Reserved.

DRAFT ORDINANCE 2017-03-16

SIGNS EXCERPT

GENERAL REQUIREMENTS

Division 5: Signs

ORIGINALLY ARTICLE XIV

Sec. 122-660. Purpose. (861) (690)

The purpose of this article shall be to permit such signs as will not, by reason of their size, location, construction or manner of display, endanger life or limb, interfere with traffic safety, or otherwise endanger the public morals, health or safety. It is further the intent of this article to:

- Maintain and enhance the aesthetic value of the City;
- Encourage free expression of ideas and dissemination of messages, regardless of content, using signs that are compatible with their surroundings and legible under the circumstances in which they are seen;
- Enhance pedestrian and vehicular traffic safety;
- Minimize the adverse effects of signs on nearby public and private property;
- Protect and enhance economic vitality by assuring aesthetic appeal for residents and visitors;
- Preserve property values;
- Enhance the effectiveness of permitted signs and directional and warning signs;
- Seek the removal of illegal signs and encourage the replacement or removal of nonconforming signs that are incompatible with the purpose of this article.

Sec. 122-661. Generally. (862) (691)

(a) **Building Permit Required.** Except as provided in this Chapter, no sign shall be constructed or erected prior to the issuance of a permit by the Building Department, and approval from other applicable reviewing bodies.

(b) **Public Rights-of-Way.** Signs shall be expressly prohibited from locating in all public rights-of-way and dedicated public easements except as otherwise provided for in this ordinance, and as follows:

- (1) Signs erected by the City or other governmental entities
- (2) Overhead banners
- (3) Sidewalk signs
- (4) Building mounted signs may project over a public right-of-way or easement provided they comply with the applicable design standards for the specific type of sign and that they maintain a minimum clearance of eight feet. A projecting sign shall project not more than four feet from the wall of a building and shall not project above the front wall of the building.

(c) **Signs exempted.**

- (1) Any sign required by City ordinance or State law, as applicable. This includes, but is not limited to, address signs, Fire Department Connection signs, or signs indicating barrier-free parking locations.
- (2) Any sign less than three square feet in area and five feet in height on the interior of a site placed so as to be oriented and clearly legible to persons on the site, provided that each sign be no closer than twenty feet to another such sign.
- (3) **Drive-Through Signs.** Any use that includes a drive-through is permitted to have signs up to a maximum height of six feet and a maximum area of 32 sq. ft. per drive-through use, located in the rear of the site, when placed so as to be oriented and clearly legible to persons on the site.

(d) **Traffic and Pedestrian Hazards.** The placement, size, content, coloring or manner of illumination of signs shall not create traffic or pedestrian hazards. No sign shall make use of the words “stop,” “look,” “danger” or other word, phrase or symbol in a manner that is confusing or misleading. No sign or flashing light shall be erected or maintained in any manner which, by reason of its size, location, context, coloring or manner of illumination, shall constitute a traffic hazard or which shall interfere with the visibility of any traffic control device.

(e) **Obstruction Prohibited.** No sign shall be placed so as to obstruct any fire escape, required exitway, window, or door opening used as a means of passage or as access for firefighting purposes.

(f) **Obstruction to ventilation.** A sign shall not be attached in any form, shape or manner which will interfere with any opening required for ventilation by the building code; except that such signs may be erected in front of and may cover transom windows when not in violation of the provisions of this chapter.

(g) **Maintenance.** All signs, sign frames, sign copy area, panels, structural elements, lamps and electrical hardware shall be maintained in good repair and working order, so as to present a neat and orderly appearance. Non-galvanized or corrosion-resistant materials shall be painted when necessary to prevent corrosion.

(h) **Authorized sign contractors.** Every person before engaging or continuing in the business of constructing, repairing or dismantling signs, poster boards or other display signs in the City, shall first furnish the City a public liability insurance policy, approved by the City attorney, with minimum limits of \$300,000.00 combined

single limit bodily injury and/or property damage, and the contractor agrees to indemnify the City from all damage suits or actions of every nature brought or claimed against the contractor for or on account of injuries to persons or damages to property received or sustained by any person or person through any act of omission or negligence of such erector, agents or employees in the erection, repair or dismantling of any sign, poster board or other display sign. Such policy shall contain a clause whereby such policy cannot be canceled until after a written notice of intention to cancel has been filed with the City clerk at least 30 days prior to the date of cancellation.

- (i) **Sign Area Calculation.** The square footage of a two-, three- or four-faced sign shall mean the square footage of the largest face of the sign.

DELETED: signage plan requirement. Not found to be useful.

DELETED: Modification of sign standards. Only used once; concerns about compatibility with GvR. May bring back as some sort of sign special use?

Sec. 122-662 Construction requirements. (orig part of 862) (692)

- (a) All signs shall conform to the City building code unless more stringent requirements are specified in this article. Signs and sign structures shall be designed and constructed to resist wind and seismic forces as specified in this section. All bracing systems shall be designed and constructed to transfer lateral forces to the foundation. For signs on building the dead and lateral loads shall be transmitted through the structural frame of the building to the ground in such a manner as not to overstress any of the elements thereof.
- (b) The overturning movement produced from lateral forces shall in no case exceed two-thirds of the deadload resisting movement. Uplift due to overturning shall be adequately resisted by proper anchorage to the ground or the structural frame of the building. The weight of earth imposed over footings may be used in determining the dead-load resisting movement. Such earth shall be carefully placed and thoroughly compacted.
- (c) Wind loads. For the purpose of design, wind pressure shall be taken upon the gross area of the vertical projection of all signs and sign structures at not less than 20 pounds per square foot for those portions less than 60 feet above the ground.
- (d) Allowable stresses. The design of wood, concrete or steel members shall conform to the requirements of the most recently adopted version of the Michigan Building Code, and loads, vertical and horizontal, exerted on the soil shall not produce stresses exceeding those specified therein. The working stresses of wire rope and its fastenings shall not exceed 25 percent of the ultimate strength of the rope or fasteners. Working stresses for wind or seismic loads combined with deadloads may be increased as specified in the Michigan Building Code.
- (e) Supports. The supports for all signs or sign structures shall be placed in or upon private property and shall be securely built, constructed and erected in conformance with the requirements of this chapter.
- (f) Fastenings. Signs attached to masonry, concrete or steel shall be safely and securely fastened thereto by means of metal anchors, bolts, or approved expansion screws of sufficient size and anchorage to support safely the loads applied. Anchors which attach signs to masonry surfaces shall be inserted into mortar joints.

Sec. 122-663. Sign permit requirements. (864) (693)

REMOVED: schedule of sign permit requirements. Incorporated into district-by-district tables.

- (a) Application for sign permits shall be made upon forms provided by the Building Department.
- (b) Applications for signs other than overhead banners shall contain or have attached thereto the following information:
- (1) Name, telephone number and address of applicant.
 - (2) Name, address and telephone number of owner or lessee of the premises upon which the sign is to be erected.
 - (3) A written statement signed by the owner or lessee of the premises upon which the sign is to be erected, indicating their consent thereto, or the signed contract between the parties.
 - (4) The address of the premises upon which the sign is to be attached or erected.
 - (5) One set of plans showing the dimensions, materials, height and method of anchorage of the sign.
 - (6) Position of the sign in relation to nearby buildings, structures and property lines.
 - (7) Insurance policy or proof of financial security as required in §122-661(h).
 - (8) On electrical signs, certification by Underwriters Laboratory or some other recognized testing laboratory. Electrical sign installations shall comply with Article 600 of the National Electrical Code.
 - (9) Such other information as deemed necessary to show compliance with this article.
- (c) Application for overhead banners shall contain or have attached thereto, the following information:
- (1) The name of organization or group sponsoring the banner.
 - (2) Phrase on the banner, and/or sketch of the content
 - (3) Location where banner is to be erected.

- (4) The dates the banner will be hung.
- (5) The name, address and telephone number of the applicant.
- 6030 (6) Insurance policy or proof of financial security as required in [§122-661\(h\)](#).
- (7) Such other information as deemed necessary to show compliance with this article and with Act No. 200 of the Public Acts of Michigan of 1969 (MCL 247.321 et seq., MSA 9.140(21) et seq.), and R247.271--R247.279 of the Michigan Administrative Code, 1979.
- (d) Application for sidewalk signs shall include a sidewalk occupancy permit application.

Sec. 122-664. Prohibited signs. (865) (694)

The following signs are prohibited in all zoning districts:

- (a) Unsafe signs. When any sign or sign structure becomes insecure, in danger of falling, or otherwise unsafe, or if any sign or sign structure shall be unlawfully installed, erected, or maintained in violation of any of the provisions of this chapter, or prohibited signs, it shall be considered a nuisance per se. The owner or lessee shall, upon receipt of written notice of the building official, immediately in the case of an unsafe sign-make such sign conform to the provisions of this article or shall remove it. If, after ten days, the notice is not complied with, the building official may remove such sign at the expense of the owner or lessee after having obtained an order from the administrative hearings bureau. The cost, including actual attorney fees, shall be assessed against the property as provided in [Article VIII of the City Charter](#).
- 6040
- (b) Prohibited signs.
- (1) Animated signs.
- (2) Portable signs, not including sidewalk signs.
- (3) Signs mounted upon a roof.
- 6050 (4) Signs containing obscene material. Signs containing symbols that area or purports to be an imitation of or resembles, or which may be mistaken for a traffic control device or that attempts to direct the movement of traffic.
- (5) Mechanical Signs.
- (6) Sign, electronic message, excepting digital billboards.
- (7) Signs not specifically permitted under the sections of this chapter.
- (8) Signs with less than six feet horizontal clearance or 12 feet vertical clearance from overhead electrical conductors which are energized in excess of 250 volts.

NOTE: changed (6) from "electronically illuminated message sign" to current; reflects new definition & also distinguishes prohibition of electronic message signs from digital billboards, a point of frequent confusion.

Sec. 122-665. Sign Design Standards. (866) (695)

(a) Freestanding Signs

- (1) **Materials.** Freestanding signs shall be constructed out of decorative materials that complement the design of principal buildings within the development. Natural materials such as stone, decorative masonry, wood, or metal are preferred sign construction materials. The use of exposed neon tubing in conjunction with other types of materials to emphasize the business name or logo is permitted.
- (2) **Billboards.** New billboard permits will be issued only in the following cases:
- (i) For non-digital billboards, when one non-conforming billboard is removed
- (ii) For digital billboards, when two non-conforming billboards are removed.
- (3) **Digital billboards.**
- 6070 (i) The message displayed on digital billboards may change a maximum of once every 6 seconds.
- (ii) All billboards must provide a setback from any adjacent residential zoning district equal to the height of the billboard.
- (iii) Billboard structures which have two or more panels stacked, one above the other, are not permitted.
- (iv) Double-faced billboard structures (two panels mounted on the same structure back-to-back) are permitted.
- (v) Spacing between billboards shall be 1,000 feet as provided in the Highway Advertising Act of 1972, as amended.
- (vi) All billboard structures shall be of steel. No wood or other combustible material shall be permitted to support such signs.
- 6080 (vii) Billboard structures shall be restricted to and used only with respect to interstate highways, freeways or primary highways as set forth in the Highway Advertising Act, Act No. 106 of the Public Acts of Michigan of 1972 (MCL 252.301 et seq., MSA 9.391(101) et seq.).
- (4) **Sidewalk Signs.**
- (i) Sidewalk Signs may have a maximum area of 6 square feet per side.

- (ii) Sidewalk signs may be located on the sidewalk adjacent to the applicant's business.
- (iii) Sidewalk signs shall be located such that they will not impede pedestrian traffic on the sidewalk, and such that they will not present a hazard to vehicular traffic.
- (iv) Sidewalk signs may not be permanently affixed to any object, structure, or the ground.
- (v) Sidewalk signs may only be displayed during business hours and shall be removed when the business to which the sign is accessory is closed.
- (vi) Each business may have a maximum of one sidewalk sign.
- (vii) Sidewalk signs shall be made of durable materials.

(b) Building Mounted Signs.

- (1) Location. Building mounted signs may be located on any façade that faces a street, parking area, alley, or on a façade where a public entrance is located.
 - (i) Illuminated building mounted signs may not be located on a façade that faces a property line that abuts a residential zoning district unless the sign is set back at least 200 feet from the property line or screening is provided that will completely obscure the view of the sign from the adjacent residential district.
- (2) Minimum Height. Signs that project more than eighteen inches into a right-of-way or over an entrance or other pedestrian or vehicular access point shall maintain a minimum clearance of 8 feet between the grade level below the sign and the lowest part of the sign, inclusive of sign structures and support devices.
- (3) Materials.
 - (i) Building mounted signs shall incorporate exterior materials, finishes and colors that are the same, similar, or complementary to those used on the principal building.
 - (ii) Building mounted signs shall be professionally constructed using high-quality materials such as metal, stone, hard wood, or brass. The use of exposed neon tubing is permitted.
 - (iii) External illumination of signs shall be limited to fully-shielded light fixtures with a maximum of 1000 lumens. Such fixtures shall be mounted above the sign face with all light directed downward and concentrated on the area of the sign to prevent glare upon the street or adjacent property.
- (4) Window Signs. May not occupy more than twenty-five percent (25 %) of the total transparent area of any individual window.
- (5) Banners. Banner requirements shall be as follows:
 - (i) The banner must be made of nonflammable material that will not shred and has adequate air holes. For banners hanging overhead across a street, roadway or highway the banner must contain at least three air holes for every 40 feet.
 - (ii) The Building Department shall be permitted to inspect the banner or a sample of material prior to it being erected.
 - (iii) The banner must be securely attached, sufficient to withstand storms, including strong gusts of wind and continuous pounding by the elements. The manner of attachment shall first be submitted to the Building Department.
 - (iv) If a banner becomes partially unsecured, it shall be immediately reattached or removed by the entity which erected it.
 - (v) If a banner begins to shred, it shall be immediately repaired or removed by the entity which erected it.
 - (vi) If the entity which erected the banner fails to comply with is the standards of [section \(iii\)](#) or fails to remove the banner by the time the permit expires, the City shall remove the banner and shall charge the cost thereof to the entity erecting the banner.
 - (vii) Any banner permit may be canceled by the City if the installation becomes dangerous to motorists or pedestrians, unduly interferes with free movement of traffic or otherwise endangers the health, safety or welfare of persons in the City.
 - (ix) A banner shall not have displayed thereon any symbol which is or purports to be an imitation of or resembles, or which may be mistaken for a traffic control device or which attempts to direct the movement of traffic.

Secs. 122-666 – 669. Reserved.

Date: February 16, 2017

From: Councilmember Pete Murdock

To: Mayor and City Council

ROAD FUNDING MEMO

Funds for maintaining our roads over the past years has failed to keep up with our normal maintenance needs. Our engineers estimate that we need \$1.2 to \$1.5 million annually to provide for the maintenance of our road infrastructure. In addition there is a growing need to address walkability, non-motorized and traffic calming issues.

After years of ignoring road funding needs the State Legislature in late 2015 finally adopted a road funding increase that, although inadequate to our needs, will generate significant dollars to the City of Ypsilanti – over \$750,000 annually when fully phased in.

This is an ideal time for the City to adopt a five year road funding plan that sets the parameters for road maintenance projects based upon asset management principles, non-motorized/traffic calming projects and ADA consent agreement. In addition consideration should be given to several road related grant projects in the works that will need some matching funds.

SOURCES OF ROAD SPECIFIC FUNDING

- Federal Aid to Highways Funds distributed through WATS – These can only be used for Eligible Streets (see list) and construction must meet Federal requirements.
- Act 51 – Funds from the Gas Tax and other sources distributed by the state by a formula and can be used for any streets (see Attachment)
- County Road Millage – .5 mils of which the City receives .4 mils (\$122,000) the other .1 mils goes to Wash. Co. Parks and Rec. These funds can be used on any streets with the stipulation that 50% of the projects must have non-motorized element in them. (see attachment)
- CDBG – \$50,000 annually has been committed to ADA ramps required by consent Decree. Can only be used in CDBG eligible census tracks.
- METRO FUNDS – A fee charged to telecommunication providers by the state and remitted to the City by a formula. Can only be used for projects in the Right of Way (ROW) (see attachment)

-OTHER GRANTS – Transportation Alternative Program (TAP), Critical Bridge, Congestion Mitigation and Air Quality (CMAC) for example – They all have their specific eligibility requirements and require some local match

RECOMMENDATIONS

Based upon a base budget of \$300,000 for road projects and \$50,000 for Non-motorized projects in FY 2016 and 2017 we budget the same amount for 2018 and then starting in FY 2019 we increase road funding by 80% of the projected increase in Act 51 funds and an \$10,000 additional each year for FY 2019, 2020 and 2021 for non-motorized/traffic calming projects. We would continue our ADA ramp consent projects using CDBG and Metro Funds.

This proposal commits us to utilizing increased funding for neglected road maintenance projects using asset management principles as well as increasing funding for non-motorized/traffic calming projects that are becoming more in demand. Funds designated – actual projects to be determined.

In addition there is flexibility to accommodate known TAP grant projects – Lane Reductions on Huron-Hamilton and the I-94 non-motorized crossing to be built in conjunction with MDOT's resurfacing of parts of M-17 and Bus U.S. 12 in FY 2021-22. A critical bridge grant should be applied for and local match provided for replacement of the Cross St bridge in FY 2020-21.

	2017	2018	2019	2020	2021	
Federal Highway Funds	\$470,000		\$390,000		\$1,100,000	
County - Roads	\$122,000	\$122,000	\$122,000	\$122,000	??	
Act 51 - Roads	\$0	\$300,000	\$300,000	\$300,000	\$300,000	
ACT 51 - Additional - 80% of increase	\$0		\$84,000	\$182,000	\$286,000	
Act 51 - Non-Motorized/Traffic Calming	\$50,000	\$50,000	\$60,000	\$70,000	\$80,000	
ADA Consent - CDBG & Metro Funds	\$100,000	\$100,000	\$100,000	\$100,000	\$100,000	
Road Totals	\$592,000	\$422,000	\$812,000	\$422,000	\$1,400,000	
Increase in Act 51 Funds over 2018 (est)			\$105,000	\$228,000	\$358,000	
80% of Increase			\$84,000	\$182,400	\$286,400	



WHEREAS, Maintaining the City's Infrastructure has long suffered from a lack of funding, AND

WHEREAS, Road funding has been particularly hard hit, AND

WHEREAS, the State finally increased road funding in December 2015, AND

WHEREAS, the increased road funding is phased in over five years. AND

WHEREAS, the City has adopted an Asset Management Approach to maintaining our roads and infrastructure, AND

WHEREAS, the City of Ypsilanti is committed to a creating a Walkable community through a Complete Streets approach.

NOW THEREFORE BE IT RESOLVED that the City of Ypsilanti adopt the attached framework for utilizing funding designated for roads including Federal Highway Funds, County Road Millage Funds, existing Act 51 Funds and increased state funding.

AND FURTHER RESOLVED that this framework includes the City's commitment to the I-94 Non-Motorized Crossing, the lane reductions of Huron/Hamilton, the redesign of the Huron/Cross Street intersection, and the replacement of the Cross Street Bridge.

OFFERED BY: _____

SUPPORTED BY: _____

YES: NO: ABSENT: VOTE:

FIVE YEAR ROAD FUNDING PLAN

	2017	2018	2019	2020	2021
Federal Highway Funds	\$470,000		\$390,000		\$1,100,000
County - Roads	\$122,000	\$122,000	\$122,000	\$122,000 ??	
Act 51 - Roads	\$0	\$300,000	\$300,000	\$300,000	\$300,000
ACT 51 - Additional - 80% of increase	\$0		\$84,000	\$182,000	\$286,000
Act 51 - Non-Motorized/Traffic Calming	\$50,000	\$50,000	\$60,000	\$70,000	\$80,000
ADA Consent - CDBG & Metro Funds	\$100,000	\$100,000	\$100,000	\$100,000	\$100,000
Road Totals	\$592,000	\$422,000	\$812,000	\$422,000	\$1,400,000
Increase in Act 51 Funds over 2018 (est)			\$105,000	\$228,000	\$358,000
80% of Increase			\$84,000	\$182,400	\$286,400
			105	315	
			87	192	315
			\$84,000	\$182,400	\$286,400

Introduction

With the passage of the Metropolitan Extension Telecommunication Rights-of-Way Oversight (METRO) Act (2002 PA 48), Michigan entered a new era in regard to deployment of telecommunications services, management of public rights-of-way, and compensation to local units of government.

The act is designed to bring substantial funds to assist in managing and maintaining your public rights-of-way and reduce conflicts with telecommunications providers. All providers will be subject to the fee. When fully implemented, providers will pay an annual maintenance fee of five cents per linear foot. These funds – estimated at between \$25 and \$30 million per year – will be distributed to local governments on a formula basis.

The METRO Act went into effect November 1, 2002. The deadline for cities and villages to opt in – and thereby receive funding – is December 31, 2003. However, the changes it will bring need to be understood much sooner. City and village officials will have the opportunity to learn more about the new act and what they need to do to implement it through the League's web site (www.mml.org) and Michigan Municipal League seminars.

Essential elements include:

- An annual maintenance fee will be assessed each year on all telecommunications providers. The fee will be two cents per linear foot of public right-of-way used for the first five months and five cents thereafter.
- Municipalities may decide to either “opt in” or “opt out” of the distribution provisions. A municipality that chooses to opt out may be able to continue to enforce its existing permit agreements with telecom providers. The choice to opt out, however, may be permanent. Those that elect to opt in must amend their existing permits/franchise agreements by December 31, 2003.
- Municipalities may use fees generated under the provisions of the act only for right-of-way purposes.
- Traditional cable franchise fees remain in place. (The Federal Communications Commission (FCC) recently ruled that cable modem service revenue should not be subject to a municipal cable franchise fee.)
- Standardized “safe harbor” permit and application forms must be used. Municipalities must act on a permit application within 45 days of application, as opposed to the previous 90-day limit. There is a one-time \$500 application fee that telecom providers who apply for a permit must pay. (This does not apply to SBC/Ameritech and some other phone companies.)
- Of the first \$30 million in fee revenue collected annually, 75 percent will be distributed to cities and villages using a distribution formula based on the same formula used for state trunk line highway funds (Act 51). The other 25 percent will be distributed to townships based on linear feet of public rights-of-way in each township. Revenues in excess of \$30 million per year, including as a result of construction of new facilities, will be distributed to local governments on the basis of new linear feet of rights-of-way used, but weighted to recognize underground lines and lines in population centers.
- Municipalities will have to implement financial systems to track the use and application of funds received from the METRO Authority, and be prepared to file an annual report.



ARCHITECTS. ENGINEERS. PLANNERS.

January 31, 2017

City of Ypsilanti
One South Huron St.
Ypsilanti, Michigan 48197

Attention: Mr. Stan Kirton
Department of Public Services Director

Regarding: **2017 Road Program**

Dear Mr. Kirton:

As you are aware, there is \$470,000 of Federal Aid programmed for the City of Ypsilanti in the 2017 FY Transportation Improvement Program (TIP). The use of this allocation requires a 20% local match. Therefore, in order to fully utilize the Federal Aid, the City will need to complete a \$590,000 construction project. The funding is programmed in the TIP as Preventative Maintenance / 3R, which allows the City to utilize the funds on any Federal Aid eligible streets that are appropriate candidates for rehabilitation techniques that utilize the asset management principles.

OHM has estimated the costs of the repairs that were identified as priorities by your office. The following work will fully utilize the Federal Aid, will impact over one mile of City Streets and will bring approximately 84 corner ramps into ADA compliance. Upon City approval, OHM can prepare the bid documents for submittal to MDOT in mid-March. This will put the City on track for an August bid opening and fall 2017 construction.

Proposed Projects					
Street	From	To	Work	Length (Ft)	Ramps
Congress	Elm	Ballard	Mill and Overlay	2,200	26
Summit	Washtenaw	Michigan Avenue	Mill and Overlay	2,650	40
Hamilton	Cross Street	Washtenaw Avenue	Mill and Overlay East Lane	800	16
Michigan Avenue (EB)	Fire Station	Senior Tower	Base Repair and Mill and Overlay	250	2
		Total		5,900	84

A detailed proposal for design services will be provided following the confirmation of the program.

Sincerely,

OHM Advisors

Marcus J McNamara

P:\0000_0100\0094160050_2017_Road_Program\PM\Scoping\2017_PM_Streets.docx

A RESOLUTION PLACING A 0.5-MILL ROAD LEVY ON THE
NOVEMBER 8, 2016 BALLOT AND CERTIFYING THE BALLOT QUESTION
FOR THIS PROPOSITION

WASHTENAW COUNTY BOARD OF COMMISSIONERS
July 6, 2016

WHEREAS, under Michigan law (Public Act 283 of 1909; MCLA 224.20), it is the duty of the Board of Commissioners (board) to raise a sufficient tax to keep any county roads or bridges already built in reasonable repair, and in condition reasonably safe and fit for public travel; and

WHEREAS, on October 1, 2014 and on September 16, 2015, pursuant to MCLA 224.20, the board levied an annual non-voter approved tax of 0.5 mills to keep public roads, streets, bridges and culverts already built in reasonable repair, and in condition reasonably safe and fit for public travel in the county's cities, villages and townships; and

WHEREAS, while those special levies yielded the improvement of over 120 miles of county roadways, their enactment must be approved by the board on an annual basis which inhibits longer-term planning; and

WHEREAS, in June, 2014, the Board of Commissioners approved Resolution #14-100 which created the "Roads Funding Committee" which was asked to explore immediate and long term road funding options; and

WHEREAS, in November, 2015, the Michigan Legislature enacted and the Governor signed, new road funding legislation which will not go into full effect until 2021; and

WHEREAS, the Washtenaw County Road Commission and the Roads Funding Committee has each reviewed a number of road funding options to fill the gap until such time as the new road funding legislation becomes fully effective; and

WHEREAS, on March 1, 2016 the Washtenaw County Road Commission formally requested that the Board of Commissioners place a 4-year, 0.5 mill road levy before the voters at the August 2016 primary election; and

WHEREAS, on March 31, 2016, the Road Funding Committee, rather than continue the process of an annual non-voter approved road levy enacted by the Board of Commissioners pursuant to MCLA 224.20, also recommended that a four-year 0.5 mill tax levy be presented to the electors of Washtenaw County at the August 2, 2016 primary election and that the Board of Commissioners approve the ballot language and certify it to the Washtenaw County Clerk; and

WHEREAS, poor roads can create unsafe conditions for motorists, cyclists, and pedestrians, hamper economic development, depress property values, and burden residents with unexpected vehicle repairs; and

WHEREAS, continued neglect of the county's road infrastructure increases the eventual cost of repair; and

WHEREAS, the Board of Commissioners agrees that the proper course of action is to request the voters of the county to levy 0.50 mills for maintenance, reconstruction, resurfacing, construction, or preservation of roads, streets, and paths, for four (4) years; and

WHEREAS, this matter has been reviewed by Corporation Counsel, the County Administrator's Office, and the Ways and Means Committee;

NOW, THEREFORE, BE IT RESOLVED BY THE WASHTENAW COUNTY BOARD OF COMMISSIONERS, State of Michigan, as follows:

1. There shall be submitted to the electors of the County of Washtenaw at the GENERAL ELECTION to be held on November 8, 2016 from 7:00 a.m. to 8:00 p.m. Eastern time, the following proposition:

"Shall the limitation on the amount of taxes which may be imposed each year for all purposes on real and tangible personal property in Washtenaw County, Michigan be increased as provided in Section 6, Article IX of the Michigan Constitution and the Board of Commissioners of the County be authorized to levy a tax not to exceed one half of one mill (\$0.50 per \$1,000 of state taxable valuation) for a period of four (4) years, beginning with the December 1, 2016 tax levy (which will generate estimate revenues of \$7,302,408 in the first year), to provide funding to the Washtenaw County Road Commission, Washtenaw County Parks and Recreation Commission, and the various cities, villages, and townships of Washtenaw County to maintain, construct, resurface, reconstruct, or preserve roads, bike lanes, streets, and paths in Washtenaw County?"

2. The election shall be held in accordance with Chapter XXVII of the general election laws of the State of Michigan
3. The Washtenaw County Clerk is hereby instructed to carry out all appropriate statutory duties as set forth in this Resolution and the general election laws of the State of Michigan so that the question of adoption may be submitted to the voters on November 8, 2016.
4. The Washtenaw County Board of Commissioners certifies to the County Clerk the following question as the appropriate ballot wording to be submitted to the voters in Washtenaw County at the primary election to be held on November 8, 2016 for the above-referenced proposition:

PROPOSITION TO AUTHORIZE THE LEVYING OF .50 MILLS TO PROVIDE FUNDING TO MAINTAIN, RECONSTRUCT, RESURFACE, OR PRESERVE ROADS, BIKE LANES, STREETS, AND PATHS.

"Shall the limitation on the amount of taxes which may be imposed each year for all purposes on real and tangible personal property in Washtenaw County, Michigan be increased as provided in Section 6, Article IX of the Michigan Constitution and the Board of Commissioners of the County be authorized to levy a tax not to exceed one half of one mill (\$0.50 per \$1,000 of state taxable valuation) for a period of four (4) years, beginning with the December 1, 2016 tax levy (which will generate estimated revenues of \$7,302,408 in the first year), to provide funding to the Washtenaw County Road Commission, Washtenaw County Parks and Recreation Commission, and the various cities, villages, and townships of Washtenaw County to maintain, construct, resurface, reconstruct, or preserve roads, bike lanes, streets, and paths in Washtenaw County?"

YES ()

NO ()

BE IT FURTHER RESOLVED that this levy be exempt from capture by TIF Districts or TIFAs to the greatest extent allowed by law.

BE IT FURTHER RESOLVED that 20% of the revenue in any year shall be used for non-motorized transportation throughout the county, and the non-motorized transportation funds shall be administered by the Washtenaw County Parks and Recreation Commission.

BE IT FURTHER RESOLVED that the portion of the remaining revenue, after the dedicated 20% allocations toward non-motorized transportation, shall be used for projects throughout the county's cities and villages in proportion to the revenue raised from those municipalities and shall be used as directed by the respective governing bodies with the requirement that no less than 50% of all projects funded by this millage within each municipality shall include a non-motorized component including but not limited to bike lanes, widened shoulders, lighted crosswalks and sidewalks.

BE IT FURTHER RESOLVED that the remaining revenue, after the dedicated 20% allocations toward non-motorized and city and village allocations, shall be used for projects throughout the county's townships based on use, need, and impact to the traveling public, as recommended by the Washtenaw County Road Commission upon consultation with the respective townships and with the requirement that no less than 25% of all projects funded by this millage shall include a non-motorized component including but not limited to bike lanes, widened shoulders, lighted crosswalks and sidewalks.

BE IT FURTHER RESOLVED that the Washtenaw County Road Commission shall compile and present a full four-year plan in consultation with the Washtenaw County Parks and Recreation Commission and the county's cities, villages, and townships at the September 7, 2016 Board of Commissioners meeting regarding expenditures of the money levied with this millage, should it pass.

COMMISSIONER	Y	N	A	COMMISSIONER	Y	N	A	COMMISSIONER	Y	N	A
Brabec		X		Ping	X			Dan Smith	X		
LaBarre		X		Rabhi	X						
Martinez-Kratz	X			Jamnick			X				
Peterson		X		Conan Smith	X						

CLERK/REGISTER'S CERTIFICATE - CERTIFIED COPY

ROLL CALL VOTE:

5 3 1

STATE OF MICHIGAN)

I, Lawrence Kestenbaum, Clerk/Register of said County of Washtenaw and Clerk of Circuit Court for said County, do hereby certify that the foregoing is a true and accurate copy of a resolution adopted by the Washtenaw County Board of Commissioners at a session held at the County Administration Building in the City of Ann Arbor, Michigan, on July 6th, 2016, as it appears of record in my office.

COUNTY OF WASHTENAW)^{SS.}

In Testimony Whereof, I have hereunto set my hand and affixed the seal of said Court at Ann Arbor, this 7th day of July, 2016.

LAWRENCE KESTENBAUM, Clerk/Register

BY: _____

Deputy Clerk



Res. No. 16-103

Estimated Distribution Schedule for Michigan Transportation Funding by City/Village within County

County with City/Village	Actual MTF Revenues Fiscal Year 2015	Estimated Additional** Revenues in FY 2017 Above 2015 Actual	Estimated Additional** Revenues in FY 2018 Above 2015 Actual	Estimated Additional** Revenues in FY 2019 Above 2015 Actual	Estimated Additional** Revenues in FY 2020 Above 2015 Actual	Estimated Additional** Revenues in FY 2021 Above 2015 Actual	Total Revenues in FY 2021
Bangor	163,280.99	38,071.22	50,186.81	64,955.44	82,111.81	108,907.60	272,188.59
Bloomington	53,960.30	12,284.51	16,193.86	20,959.28	26,495.15	35,141.40	89,101.70
Breedsville	31,525.03	7,185.33	9,471.96	12,259.30	15,497.29	20,554.56	52,079.59
Decatur	149,171.37	35,465.82	46,752.27	60,510.21	76,492.48	101,454.48	250,625.85
Gobles	70,529.39	16,633.93	21,927.43	28,380.08	35,875.98	47,583.48	118,112.87
Hartford	195,901.91	46,207.80	60,912.70	78,837.68	99,660.70	132,183.26	328,085.17
Lawrence	104,257.15	23,208.00	30,593.60	39,596.47	50,054.90	66,389.44	170,646.59
Lawton	165,417.88	39,014.04	51,429.65	66,564.03	84,145.26	111,604.61	277,022.49
Mattawan	196,253.13	46,379.89	61,139.57	79,131.30	100,031.88	132,675.56	328,928.69
Paw Paw	253,549.05	59,806.49	78,839.00	102,039.19	128,990.32	171,084.09	424,633.14
South Haven	395,631.64	93,307.94	123,001.75	159,197.87	201,246.05	266,919.23	662,550.87
County-Wide Total	\$8,073,048.51	\$1,916,852.42	\$2,528,769.57	\$3,271,810.73	\$4,136,264.30	\$5,486,365.92	\$13,559,414.43
Washtenaw	17,969,413.18	4,368,166.29	5,763,827.96	7,456,740.10	9,427,086.01	12,504,335.99	30,473,749.17
Ann Arbor	7,785,526.75	1,839,511.01	2,424,907.09	3,138,492.09	3,967,447.10	5,262,155.20	13,047,681.95
Barton Hills	12,641.25	2,982.80	3,932.03	5,089.12	6,433.28	8,532.68	21,173.93
Chelsea	332,628.63	78,820.67	103,904.13	134,480.33	169,999.98	225,476.54	558,105.17
Dexter	264,887.79	62,863.93	82,869.40	107,255.65	135,584.58	179,830.27	444,718.06
Manchester	173,049.56	40,815.31	53,804.17	69,637.28	88,030.24	116,757.41	289,806.97
Milan	393,621.97	92,848.60	122,396.24	158,414.16	200,255.34	265,605.23	659,227.20
Saline	567,707.12	133,915.07	176,531.50	228,479.96	288,827.30	383,081.11	950,788.23
Ypsilanti	1,152,027.26	271,761.21	358,245.04	463,666.91	586,133.06	777,407.48	1,929,434.74
County-Wide Total	\$28,651,503.51	\$6,891,684.89	\$9,090,417.56	\$11,762,255.60	\$14,869,796.89	\$19,723,181.91	\$48,374,685.42
Wayne	60,677,706.89	14,727,000.14	19,432,386.46	25,139,934.15	31,782,832.44	42,157,588.86	102,835,295.75
Allen Park	1,820,038.56	429,326.55	565,953.12	732,497.92	925,969.13	1,228,143.22	3,048,181.78
Belleville	226,436.49	53,417.82	70,417.19	91,139.09	115,211.22	152,808.42	379,244.91
Dearborn	6,737,738.41	1,589,240.04	2,094,991.24	2,711,490.85	3,427,664.07	4,546,223.28	11,283,961.69
Dearborn Heights	3,478,923.08	820,691.94	1,081,864.54	1,400,228.20	1,770,063.83	2,347,693.70	5,826,616.78
Detroit	56,018,315.17	13,198,683.20	17,398,961.00	22,519,007.69	28,466,846.34	37,756,511.87	93,774,827.04
Ecorse	568,432.95	134,094.91	176,768.55	228,786.80	289,215.15	383,595.55	952,028.50
Flat Rock	562,571.39	132,716.79	174,951.86	226,435.49	286,242.83	379,653.25	942,224.64
Garden City	1,713,285.30	404,163.95	532,782.91	689,566.60	871,698.56	1,156,162.40	2,869,447.70
Gibraltar	292,208.43	68,928.59	90,864.05	117,602.88	148,664.79	197,179.00	489,387.43
Grosse Pointe	333,332.44	78,631.29	103,654.49	134,157.21	169,591.53	224,934.81	558,267.25
Grosse Pointe Farms	588,277.05	138,773.99	182,936.68	236,770.02	299,306.96	396,980.63	985,257.68
Grosse Pointe Park	688,486.35	162,415.08	214,101.17	277,105.41	350,295.94	464,608.99	1,153,095.34
Grosse Pointe Shores	189,233.97	44,640.44	58,846.59	76,163.55	96,280.27	127,699.69	316,933.66
Grosse Pointe Woods	948,274.97	223,706.23	294,897.28	381,677.63	482,488.33	639,940.09	1,588,215.06
Hamtramck	1,224,464.90	288,861.56	380,787.32	492,842.79	623,015.00	826,325.23	2,050,790.13
Harper Woods	807,518.19	190,506.04	251,131.66	325,032.97	410,882.39	544,966.78	1,352,484.97
Highland Park	832,795.11	196,427.22	258,937.17	335,135.41	423,653.15	561,905.05	1,394,700.16



REQUEST FOR LEGISLATION
March 21, 2017

To: Mayor, Mayor Pro Tem, & City Councilpersons

From: Kimberly Jones, Interim HR Manager

Subject: City Manager MERS Defined Contribution Plan

SUMMARY & BACKGROUND:

The City Council at its meeting of January 17, 2017, approved an Employment Agreement ("the Agreement") between the City and Mr. Darwin D. P. McClary to serve as City Manager. The Agreement included a provision that requires the City to execute all necessary documents to provide for the participation of Mr. McClary in a Defined Contribution Plan ("the Plan") of the Municipal Employees' Retirement System ("MERS") of Michigan. The Agreement set forth specific provisions that are to be included in the subject Plan, including:

- Plan: MERS 401(a) Defined Contribution
- Vesting: 100% on the first day of employment
- City Contribution Rate: 9% of employee's base salary payable in biweekly installments

In order to create the subject plan for Mr. McClary, the City Council must adopt the attached MERS resolution.

ATTACHMENTS:

1. Council Resolution
2. Resolution for Adopting Municipal Employees' Retirement System of Michigan Defined Contribution Program

CITY MANAGER APPROVAL: _____ COUNCIL AGENDA DATE: _____

CITY MANAGER COMMENTS: _____

FISCAL SERVICES DIRECTOR APPROVAL: MUY 3-17-2017



Resolution No. 2017-070
March 21, 2017

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

WHEREAS, the City Council at its meeting of January 17, 2017, approved an Employment Agreement ("the Agreement") between the City and Mr. Darwin D. P. McClary to serve as City Manager; and

WHEREAS, the Agreement included a provision that requires the City to execute all necessary documents to provide for participation by Mr. McClary in a Defined Contribution Plan ("the Plan") of the Municipal Employees' Retirement System ("MERS") of Michigan; and

WHEREAS, in order to create the subject Plan for Mr. McClary, the City Council must adopt the attached MERS Resolution.

NOW THEREFORE BE IT RESOLVED THAT the Ypsilanti City Council does hereby approve and adopt the MERS Resolution for Adopting Municipal Employees' Retirement System of Michigan Defined Contribution Program, attached hereto and made a part hereof, and does further authorize and direct the Mayor and City Clerk to execute the subject MERS Resolution on behalf of the City.

OFFERED BY: _____

SUPPORTED BY: _____

YES: NO: ABSENT: VOTE:

Resolution Adopting the MERS Defined Contribution Plan



1134 Municipal Way Lansing, MI 48917 | 800.767.MERS (6377) | Fax 517.703.9711

www.mersofmich.com

This Resolution is entered into under the provisions of 1996 PA 220 and the Municipal Employees' Retirement System of Michigan ("MERS") Plan Document, as each may be amended.

WHEREAS, the participating entity desires to adopt the MERS Defined Contribution Plan for its designated employees;

WHEREAS, the participating entity has furnished MERS with required data regarding each eligible employee and retiree;

WHEREAS, as a condition of MERS membership, and pursuant to the MERS Retirement Board's power as plan administrator and trustee under Plan Document Section 71 and MCL 38.1536, as each may be amended, it is appropriate and necessary to enter into a binding agreement providing for the administration of the Defined Contribution Plan, the reporting of wages, and the payment of the required contributions of a participating entity and withholding of employee contributions; now, therefore,

IT IS HEREBY RESOLVED:

1. On behalf of the participating entity, the governing body of _____ adopts the MERS Defined Contribution Plan in accordance with Plan Section 4 for its eligible employees as described in the MERS Defined Contribution Adoption Agreement, subject to the MERS Plan Document and as authorized by 1996 PA 220, as both may be amended;
2. The governing body agrees to the terms of and authorizes (title) _____ to execute the initial MERS Defined Contribution Adoption Agreement, a copy of which is attached hereto and which is hereby incorporated by reference; and

I hereby certify that the above is a true copy of the Defined Contribution Resolution adopted at the official meeting held by the governing body of this municipality:

Dated: _____, 20____. _____
(Signature of Authorized Official)

This Resolution shall have no legal effect under the MERS Plan Document until a certified copy of this adopting Resolution is filed with MERS, MERS determines that all necessary requirements under the Plan Document, the Adoption Agreement, and this Resolution have been met, and MERS certifies the Resolution below.

Received and Approved by the Municipal Employees' Retirement System of Michigan:

Dated: _____, 20____. _____
(Authorized MERS Signatory)

MERS Defined Contribution Plan Adoption Agreement



1134 Municipal Way Lansing, MI 48917 | 800.767.MERS (6377) | Fax 517.703.9711

www.mersofmich.com

The Employer, a participating municipality or court within the state of Michigan that has adopted MERS coverage, hereby establishes the following Defined Contribution Plan provided by MERS of Michigan, as authorized by 1996 PA 220 in accordance with the MERS Plan Document.

I. Employer Name City of Ypsilanti Municipality #: 8101

If new to MERS, provide your municipality's/court's fiscal year: _____ through _____.
(Month) (Month)

II. Effective Date

Check one:

A. ☒ If this is the initial Adoption Agreement for this group, the effective date shall be the first day of February, 2017.

☐ This municipality or division is new to MERS, so vesting credit prior to the initial MERS effective date by each eligible participant shall be credited as follows (choose one):

☐ Vesting credit from date of hire ☐ No vesting credit

☒ This division is currently in the MERS Defined Benefit or Hybrid Plan and meets the applicable funding level requirements to adopt the MERS Defined Contribution Plan, as set forth in Plan Document Section 46. Unless otherwise specified, the standard transfer/rehire rules will apply.

* Closing this division will change future invoices to a flat dollar amount instead of a percentage of payroll, as provided in your most recent annual actuarial valuation. (The amount may be adjusted for any benefit modifications that may have taken place since then.)

☒ This division is for new hires, rehires, and transfers of current Defined Benefit division # 14 & 15 and/or current Hybrid division # _____

☐ Employees will have a one-time opportunity to convert from the existing plan into the new MERS Defined Contribution Plan (see attached MERS Defined Contribution Conversion Addendum incorporated herein by reference).

☐ The existing Defined Benefit Plan will be frozen (see attached Frozen Defined Benefit Addendum).

Review the projection study results

MERS recommends that your MERS representative presents the projection study results to your municipality/court before adopting MERS Defined Contribution.

☐ Our MERS representative presented and explained the projection study results to the _____ on _____.
(ex. Board, Finance Committee, etc.) (MM/DD/YYYY)

☐ As an authorized representative of this municipality/court, I

(Name) (Title) waive the right for a presentation of the projection study results.

B. ☐ If this is an amendment of an existing Adoption Agreement (existing division number _____), the effective date shall be the first day of _____, 20____. Please note: You only need to mark **changes** to your plan throughout the remainder of this Agreement.

MERS Defined Contribution Plan Adoption Agreement

- C. ☐ If this is to separate employees from an existing *Defined Contribution division* (existing division number(s) _____) into a new division, the effective date shall be the first day of _____, 20____.
- D. ☐ If this is to merge division(s) _____ into division(s) _____, the effective date shall be the first of _____, 20____.

III. Eligible Employees

Only those Employees eligible for MERS membership may participate in the MERS Defined Contribution Plan. A copy of ALL employee enrollment forms must be submitted to MERS. The following groups of employees are eligible to participate:

City Manager hired on or after February 1, 2017

(Name of Defined Contribution division – e.g. All Full Time Employees, or General After 7/01/13)

To further define eligibility, (check all that apply):

- ☐ **Probationary periods** are allowed in one-month increments, no longer than 12 months. During this introductory period the Employer will not report or make contributions for this period, including retroactively. Service will begin after the probationary period has been satisfied. The probationary period will be _____ month(s).
- ☐ **Temporary employees** in a position normally requiring less than a total of 12 whole months of work in the position may be *excluded* from membership. These employees must be notified in writing by the participating municipality that they are excluded from membership within 10 business days of date of hire or execution of this Agreement. The temporary exclusion period will be _____ month(s).

MERS Defined Contribution Plan Adoption Agreement

IV. Provisions

1. Vesting (Check one):

- ☒ Immediate
- ☐ Cliff Vesting (fully vested after below number years of service)
☐ 1 year ☐ 2 years ☐ 3 years ☐ 4 years ☐ 5 years
- ☐ Graded Vesting
_____ % after 1 year of service
_____ % after 2 years of service
_____ % after 3 years of service (min 25%)
_____ % after 4 years of service (min 50%)
_____ % after 5 years of service (min 75%)
_____ % after 6 years of service (min 100%)

Vesting will be credited using (check one):

- ☒ Elapsed time method – Participants will be credited with one vesting year for each 12 months of continuous employment from the date of hire.
- ☐ Hours reported method – Participants will be credited with one vesting year for each calendar year in which _____ hours are worked

In the event of disability or death, a participant's (or his/her beneficiary's) entire employer contribution account shall be 100% vested, to the extent that the balance of such account has not previously been forfeited.

Normal Retirement Age (presumed to be age 60 unless otherwise specified) _____

If an employee is still employed with the municipality at the age specified here, their entire employer contribution balance will become 100% vested regardless of years of service.

2. Contributions

a. Will be remitted (check one):

- ☐ Weekly ☒ Bi-Weekly ☐ Monthly

b. Employee/Employer contribution structure (subject to limitations of Section 415(c) of the Internal Revenue Code)

	Enter % or \$ for contribution amounts						
Employee Contribution	N/A						
Employer Contribution	9%						

☒ Direct mandatory employee contributions as pre-tax

c. Voluntary employee contributions may be made after-tax, subject to the Section 415(c) limitations of the Internal Revenue Code

MERS Defined Contribution Plan Adoption Agreement

3. Compensation:

Employers may designate the definition of compensation per division participating in Defined Contribution pursuant to section 49 of the MERS Plan Document (check one):

☒ Medicare taxable wages reported in Box 5 of Form W-2

☐ All income subject to income tax reported in Box 1 of Form W-2, plus elective deferrals.

NOTE: In either of the above elections, an employee's compensation shall not exceed the annual limit under section 401(a)(17) of the Internal Revenue Code.

4. Loans: ☐ shall be permitted ☒ shall not be permitted

If Loans are elected, please complete and attach the *MERS Defined Contribution Loan Addendum*.

5. Rollovers from qualified plans are permitted and the plan will account separately for pre-tax and post-tax contributions and earnings thereon.

V. Appointing MERS as the Plan Administrator

The Employer hereby agrees to the provisions of this *MERS Defined Contribution Plan Adoption Agreement* and appoints MERS as the Plan Administrator pursuant to the terms and conditions of the Plan. The Employer also agrees that in the event any conflict between MERS Plan Document and the MERS Defined Contribution Plan, the provisions of the Plan Document control.

VI. Modification of the terms of the Adoption Agreement

If the Employer desires to amend any of its elections contained in this Adoption Agreement, including attachments, the Governing Body or Chief Judge, by resolution or official action accepted by MERS, must adopt a new Adoption Agreement. The amendment of the new Agreement is not effective until approved by MERS.

VII. Enforcement

1. The Employer acknowledges that the Michigan Constitution of 1963, Article 9, Section 24, provides that accrued financial benefits arising under a public Employer's retirement plan are a contractual obligation of the Employer that may not be diminished or impaired.
2. The Employer agrees that, pursuant to the Michigan Constitution, its obligations to pay required contributions are contractual obligations to its employees and to MERS and may be enforced in a court of competent jurisdiction;
3. The Employer acknowledges that employee contributions (if any) and employer contributions must be submitted in accordance with the MERS Enforcement Procedure for Prompt Reporting and Payment, the terms of which are incorporated herein by reference;
4. The Employer acknowledges that late or missed contributions will be required to be made up, including any applicable gains, pursuant to the Internal Revenue Code;
5. Should the Employer fail to make its required contribution(s) when due, MERS may implement any applicable interest charges and penalties pursuant to the MERS Enforcement Procedure for Prompt Reporting and Payment and Plan Document Section 79, and take any appropriate legal action, including but not limited to filing a lawsuit and reporting the entity to the Treasurer of the State of Michigan in accordance with MCL 141.1544(d), Section 44 of PA 436 of 2012, as may be amended.

MERS Defined Contribution Plan Adoption Agreement

6. It is expressly agreed and understood as an integral and non-severable part of this Agreement that Section 43 of the Plan Document shall not apply to this Agreement and its administration or interpretation. In the event any alteration of the terms or conditions of this Agreement is made or occurs, under Section 43 or other plan provision or law, MERS and the Retirement Board, as sole trustee and fiduciary of the MERS plan and its trust reserves, and whose authority is non-delegable, shall have no obligation or duty to administer (or to have administered) the MERS Defined Contribution Plan, to authorize the transfer of any defined benefit assets to the MERS Defined Contribution Plan, or to continue administration by MERS or any third-party administrator of the MERS Defined Contribution Plan.

VIII. Execution

Authorized Designee of Governing Body of Municipality or Chief Judge of Court

The foregoing Adoption Agreement is hereby approved by the City of Ypsilanti on
the 17th day of March, 2017. (Name of Approving Employer)

Authorized signature: _____

Title: Interim HR Manager

Witness signature: _____

Received and Approved by the Municipal Employees' Retirement System of Michigan

Dated: _____, 20____ Signature: _____
(Authorized MERS Signatory)



REQUEST FOR LEGISLATION
March 21, 2017

To: Mayor and Council

From: Darwin D. P. McClary, City Manager

Subject: SCHEDULE WORK SESSION FOR CITY MANAGER PRIORITIES/EXPECTATIONS

SUMMARY & BACKGROUND: Council is being requested to schedule a work session to provide guidance to the new City Manager on the council's immediate priorities and expectations for the manager for the next several months. This guidance will assist the City Manager in prioritizing administrative work tasks. Each council member may wish to come to the work session with a list of 3 to 5 items he or she feels should be given priority so that the council can give approval to a list of priorities and expectations for the manager's attention.

RECOMMENDED ACTION: Schedule a date to hold a work session as soon as possible to discuss and approve the City Council's priorities and expectations for the City Manager for the next several months.

ATTACHMENTS:

CITY MANAGER APPROVAL: _____ COUNCIL AGENDA DATE: 03/21/17

CITY MANAGER COMMENTS: _____

FISCAL SERVICES DIRECTOR APPROVAL: _____



Resolution No. 2017 - 071
March 21, 2017

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

WHEREAS, the City of Ypsilanti's new City Manager, Darwin McClary, joined the city's management team on February 27, 2017; and

WHEREAS, the City Manager is requesting that the City Council schedule a work session to discuss and establish a list of priorities and expectations for the City Manager for the next several months to ensure that immediate legislative priorities of the council are addressed by administration; and

WHEREAS, the City Council desires to provide clear direction to the City Manager on its immediate legislative priorities;

NOW THEREFORE BE IT RESOLVED BY THE CITY OF YPSILANTI that the City Council does hereby schedule a work session of the council for _____, 2017, at _____ p.m. for the purpose of discussing and approving a list of legislative priorities and expectations for the City Manager for the next several months to ensure that immediate legislative priorities are addressed by administration; and

BE IT FURTHER RESOLVED BY THE CITY OF YPSILANTI that the City Council does hereby request that each council member prepare a list of 3 to 5 legislative priorities or expectations for the council to consider at the work session, with the lists to be submitted to the City Clerk on or before _____, 2017, for inclusion in the agenda packet in advance of the meeting.

OFFERED BY: _____

SUPPORTED BY: _____

YES: NO: ABSENT: VOTE:



Resolution No. 2017-073
March 21, 2017

WHEREAS, Line 5 is a set of twin, 64-year-old pipelines owned by Enbridge that carry light crude oil and natural gas under the Straits of Mackinac; and

WHEREAS, the currents in the Straits of Mackinac at peak volumetric transport can be more than 10 times greater than the flow of Niagara Falls and switch bi-directionally from east to west every few days, and according to a 2014 University of Michigan study are the "worst possible place" for an oil spill in the Great Lakes; and

WHEREAS, the Great Lakes contain 20 percent of the world's fresh, available, surface water and are a drinking water source for over 35 million people; and

WHEREAS, one out of every five jobs in Michigan is linked to the high quality and quantity of fresh water in the Great Lakes; and

WHEREAS, tourism is one of Michigan's largest income industries bringing in billions of travelers dollars spent each year; and

WHEREAS, agriculture, fisheries, shipping and industry depend on the health of the Great Lakes; and

WHEREAS, in 2009 the Great Lakes were linked to over 1.5 million jobs, with Michigan accounting for 35 percent of those jobs; and

WHEREAS, Enbridge has a shaky track record that includes 1,244 reportable spills, leaks and releases from 1996 to 2013; and

WHEREAS, Enbridge was in violation for their spacing requirements of its 1953 easement for Line 5 in 2014 and were responsible for a pinhole leak in a section of the pipeline north of the Straits in December 2014; and

WHEREAS, Enbridge was responsible for one of the worst and most expensive oils spills in U.S. history when Line 6b ruptured near Kalamazoo in 2010 allowing

almost 1 million gallons of tar sands oil to leak for 17 hours before shutting down the line; and

WHEREAS, corrosion is the number one reason that pipelines fail; and

WHEREAS, Line 5 was built before the Great Lakes Submerged Lands Act was adopted so it didn't have to obtain a permit and ensure that the pipeline wouldn't pose a threat to the waters or the public's use of the waters; and

WHEREAS, Michigan's Attorney General Bill Schuette has stated (in regards to Line 5) that the "pipeline wouldn't be built today" and that "the pipeline's days are numbered"; and

WHEREAS, the Coast Guard Commandant testified before congress in 2015 that the Coast Guard would be unable to respond effectively to an open water oil spill in the heart of the Great Lakes; and

WHEREAS, there is no plan for how to recover oil if there was a leak during the winter when the lakes are covered with ice; and

WHEREAS, as Michiganders we have a responsibility to be wise stewards of the waters of our state for generations to come; and

WHEREAS, protection of Michigan's water supplies and resources is better accomplished by prevention of contamination and environmental degradation, rather than attempting to clean up contamination and restore degraded environments after the fact;

NOW, THEREFORE, BE IT RESOLVED, that on the ____ day of ____ 2017, the City of Ypsilanti supports stopping the transportation of oil under the Great Lakes; and

BE IT FURTHER RESOLVED, that the City of Ypsilanti supports shutting down Line 5 and the flow of oil under the Great Lakes, and

AND BE IT FURTHER RESOLVED that the City of Ypsilanti will send a letter to Governor Rick Snyder, Attorney General Bill Schuette, our State Representatives, State Senators and U.S. Senators calling on them to take swift action to shut down Line 5.

PASSED, APPROVED, AND EFFECTIVE on this ____ day of ____, 2017.

ATTEST:

Mayor

Council President

PLEASE SEND A COPY OF THIS SIGNED RESOLUTION TO:

1. [Governor Rick Snyder]
2. [Attorney General Bill Schuette]
3. [State Representative Ronnie Peterson]
4. [State Senator Rebekah Warren]
5. [US Senators Debbie Stabenow and Gary Peters]



Resolution No. 2017-072
March 21, 2017

RESOLVED BY THE COUNCIL OF THE CITY OF YPSILANTI:

That the City Council Meeting be adjourned, on call, by the Mayor or two (2) members of Council.

OFFERED BY: _____

SUPPORTED BY: _____

YES: NO: ABSENT: VOTE:



Zoning Ordinance
Chapter 122

10

City of Ypsilanti, Michigan

20

BUGFIX AND STRUCTURE REVISION DRAFT ANNOTATED VERSION

Table of Contents

	Article I: Purpose And How To Use	4
	Article II: Definitions and Language.....	7
30	Article III: Development Procedures and Administration	41
	Division 1: Generally.....	41
	Division 2: Permits.....	43
	Subdivision I: Zoning Compliance.....	43
	Subdivision II: Special Land Uses.....	53
	Subdivision III: Temporary Use Permits.....	57
	Subdivision IV: Building Permits.....	61
	Division 3: Nonconformities.....	63
	Division 4: Amendments.....	69
	Division 5: Variances and Appeals.....	75
40	Division 6: Violations and Penalties.....	77
	Division 7: Authorities.....	79
	Subdivision I: Planning Commission.....	81
	Subdivision II: Zoning Board of Appeals.....	83
	Article IV: Districts.....	87
	Division 1: Generally.....	87
	Division 2: Use Based Districts.....	89
	Subdivision I: Park District (P).....	91
	Subdivision II: Single-Family Residential District (R1).....	95
	Subdivision III: Multiple Dwelling Residential District (MD).....	101
50	Subdivision IV: Production, Manufacturing And Distribution District (PMD).....	109
	Division 3: Walkable Urban Districts.....	119
	Subdivision I: Core Neighborhoods (CN-Sf, CN-Mid, CN).....	121
	Subdivision II: Center (C).....	127
	Subdivision III: Corridors (HC, NC, GC).....	133
	Subdivision IV: Health And Human Services (HHS).....	141
	Subdivision V: Building Types.....	147
	Article V: Use Regulations.....	171
	Division 1: Specific Standards For Certain Uses.....	173
	Division 2: Storage of Vehicles.....	193
60	Division 3: Communication Devices.....	195
	Article VI: Site Regulations	200
	Division 1: Generally.....	200
	Division 2: Yard, Area, and Lot Requirements	205
	Division 3: Landscaping and Screening	207
	Division 4: Accessory Structures, Porches, and Decks	215
	Division 5: Signs	217
	Division 6: Traffic	221
	Division 7: Off-Street Parking and Loading Requirements.....	225
	Division 8: Parking Types and Quantities	233
70	Article VII: Supplementary Regulations	241
	Division 1: Planned Unit Development.....	241
	Division 2: Site Condominium Subdivisions.....	247
	Division 3: Flood Damage Prevention.....	249

Article I: Purpose And How To Use

Sec. 122-100. Purpose. (1)

This Zoning Ordinance is based on the provisions, goals, and values as adopted in the City of Ypsilanti Master Plan, amendments to those plans, and similar adopted plans addressing future development patterns and goals. This Ordinance is intended to implement the Master Plan by regulating the use of land, buildings, and structures to promote the public health, safety, and welfare. In the interpretation and application of this chapter, the provisions of this chapter shall be held to be minimum requirements for the promotion of the public health, safety, and welfare.

The provisions of this chapter are intended to:

- create a safe, diverse, and sustainable city;
- meet the needs of the City's residents for food, fiber, energy, and other natural resources;
- guide the location of places of residence, recreation, industry, trade, service, and other uses of land;
- ensure that uses of the land shall be situated in appropriate locations and relationships;
- limit the inappropriate overcrowding of land and congestion of population and transportation systems and other public facilities;
- facilitate adequate and efficient provision for transportation systems, sewage disposal, water, energy, education, recreation, and other public service and facility needs;

and for those purposes, divide the City into districts and within those districts designate the uses for which buildings or structures may be erected or altered; provide regulations for land uses, activities, or special uses which may be permitted subject to approval and regulation; establish the height and bulk of buildings, the area of yards and other open spaces; restrict the maximum number of families which may be housed in dwellings; and impose regulations for land prone to flooding.

This Ordinance is further intended to enable, encourage, and qualify the implementation of the following policies regarding:

(a) The Districts

- (1) That neighborhoods should provide meaningful choices in living arrangements as manifested by distinct physical environments.
- (2) That the District descriptions in **Article IV** shall constitute the intent of this Code with regard to the general character of each of these environments.

(b) The block and the building

- (1) That buildings and landscaping should contribute to the physical definition of streets as civic places.
- (2) That development should create complete streets that adequately accommodate vehicles and bicycles while respecting the pedestrian and the spatial form of public areas.
- (3) That the design of streets and buildings should reinforce safe environments, but not at the expense of accessibility.
- (4) That architecture and landscape design should grow from local climate, topography, history, and building practice.
- (5) That buildings should provide the community with a clear sense of geography and climate through energy efficient methods.
- (6) That Institutional Buildings and public gathering places should be distinctive in appearance, conveying their role in community identity.
- (7) That Institutional Buildings should be distinctive and appropriate to a role more important than the other buildings that constitute the fabric of the City.
- (8) That the preservation and renewal of historic buildings should be facilitated, to affirm the continuity and evolution of society.
- (9) That the harmonious and orderly evolution of urban areas should be secured through codes that regulate both building type and land use.

Sec. 122-101. Steps for Use of Regulations. (277)

The table below illustrates the key steps an applicant would generally follow for development projects in the City. This is illustrative only and is not intended to set forth the administration and procedures, which are set in [Article III](#).

Instructions	Section	Title
Find the district for your parcel.	Zoning Map	Zoning Map
Confirm the proposed use(s) is allowed in this zoning district.	Article IV	Districts
Determine if your site is within the Historic District.	Chapter 55	Historic District
	See also the Historic District Map	
Determine if your site is within the floodplain or the floodway.	Article VII, Division 3	Flood Damage Prevention
	See also the adopted Flood Insurance Rate Map	
Determine the dimensional requirements for your building: - If your parcel is in GC, NC, HC, C, HHS, CN, CN-Mid, or CN-SF districts, using lot size, determine what "Building Type" your parcel is to determine design regulations; - If in another district, refer to the Non-Use and Dimensional Regulations table in each district section.	Article IV	Districts
Review the site design standards unique to the proposed use, as applicable.	Article V	Use Regulations
Review the site design standards general to all districts	Article VI	Site Regulations
Apply for zoning compliance	Article III, Division 2	Permits

Article II: Definitions and Language

ORIGINALLY 122-2, 4, 5, 3. Included also definitions from signs, site condominiums, and elsewhere in the ordinance.
(sections 122-8,6, and 9 are now 112, 111, and 110, respectively)
CHANGES TO DEFINITIONS SHOWN IN CALLOUT BOXES LIKE THIS. NOT NOTED WHEN RELOCATED FROM OTHER SECTIONS.
LETTER BREAKS ADDED (EG, "A", "B", "C" ETC)

Sec. 122-200. Interpretation of language. (2)

For the purpose of this chapter, the following rules of interpretation shall apply to the text of this chapter:

- (a) The particular shall control the general.
- (b) In the case of any difference of meaning or implication between the text of this chapter and any caption or illustration, the text shall control.
- (c) The word "shall" is always mandatory and not discretionary. The word "may" is permissive and discretionary.
- (d) Words used in the present tense shall include the future. Words used in the singular number shall include the plural, and the plural the singular, unless the context clearly indicates the contrary.
- (e) A "building" or "structure" includes any part thereof.
- (f) The phrase "used for" includes "arranged for," "designed for," "intended for," "maintained for," or "occupied for."
- (g) The word "person" includes an individual, a corporation, a partnership, a public utility, firm, an incorporated association, or any other similar entity.
- (h) Unless the context clearly indicates the contrary, or a regulation involves two or more items, conditions, provisions, or events connected by the conjunction "and," "or," "either . . . or," the conjunction shall be interpreted as follows:
 - (1) "And" indicates that all the connected items, conditions, provisions, or events shall apply.
 - (2) "Or" indicates that the connected items, conditions, or provisions, or events may apply singly or in any combination.
 - (3) "Either . . . or" indicates that the connected items, conditions, or provisions, or events may apply singly or in any combination.
- (i) Terms not defined in this chapter shall have the meaning customarily assigned to them.

Sec. 122-201. Interpretation and conflict. (4)

- (a) In interpreting and applying the provisions of this chapter, such provisions shall be held to be the minimum requirements adopted for the promotion of the public health, morals, safety, comfort, convenience, prosperity, and general welfare.
- (b) It is not intended by this chapter to repeal, abrogate, annul or in any way to impair or interfere with any existing provision of any law or ordinance other than the above described zoning ordinance, or with any rules, regulations, or permits previously adopted or issued or which shall be adopted or issued pursuant to the law relating to the use of the buildings or premises; provided, however, that where this chapter imposes a greater restriction than is required by an existing ordinance or by rules, regulations or permits, the provisions of this chapter shall control.

Sec. 122-202. Rule of construction. (5)

The rule that a penalty statute is to be strictly construed shall not apply to this chapter or any of the provisions thereof. All provisions of this chapter shall be construed according to the fair import of their terms, to promote justice, and to effect the objectives of this chapter.

Sec. 122-203. Definitions. (3)

The following words, terms and phrases when used in this chapter shall have the meanings ascribed to them in this section, except where the context clearly indicates a different meaning:

A

Abandon means, in relation to nonconformities, to refer to uses, businesses, or establishments which have ceased to operate or exist; or to buildings, structures, or properties which have ceased to be occupied or used or for which no owner can be found, for a period of 365 consecutive days where there is an intent demonstrated by the property owner to abandon the nonconforming use by action consistent with §122-348(a)(5) or §122-349(e).

Accessory use, building or structure means a use, building, or structure which is clearly incidental to, customarily found in connection with, subordinate to, and is located on the same zoning lot as the principal use or structure to which it is exclusively related.

Adjacent. See "Lot, adjacent."

Administrative officer means an employee of the City who is charged with administering a department or major function of the City, such as City Manager, City Clerk, City Treasurer, City Assessor, Police Chief, Fire Chief, City Planner, Community and Economic Development Director, or Building Inspection Supervisor.

Adult drop-in center means a facility offering counseling, recreation, supervision, education or a place to pass the day to physically, mentally, or emotionally impaired adult individuals who may stop at any time and stay an unspecified period of time during its business hours.

Adult foster care facility. A governmental or nongovernmental establishment having as its principal function the receiving of adults, 18 years of age or older, for foster care in accordance with Act No. 218 of the Public Acts of Michigan of 1979, and the adult foster care administrative rules as administered by the state department of social services. It includes facilities and foster care family homes for adults who are aged, emotionally disturbed, developmentally disabled, or physically handicapped who require continuous supervision on an ongoing basis but who do not require continuous nursing care. The following four types of adult foster care homes are provided for by these rules:

- (1) **Adult foster care family home.** A private residence with the approved capacity to receive not more than six adults who shall be provided foster care for five or more days a week and for two or more consecutive weeks. The adult foster care family home licensee shall be a member of the household and an occupant of the residence.
- (2) **Adult foster care small group home.** An adult foster care facility with the approved capacity of not more than 12 adults who shall be provided foster care. Conformance to local zoning is required only if seven or more residents will live in the home.
- (3) **Adult foster care large group home.** An adult foster care facility with the approved capacity to receive at least 13 but not more than 20 adults who shall be provided foster care. Conformance to local zoning is required.
- (4) **Adult foster care congregate facility.** An adult foster care facility with the approved capacity to receive more than 20 adults who shall be provided foster care. Conformance to local zoning is required.

Adult regulated uses. The following are classified as types of adult regulated uses.

- (1) **Adult book or supply store** means an establishment having 20 percent or more of its stock in trade or its sales devoted to the distribution, display, or storage of books, magazines, and other periodicals and/or photographs, drawings, slides, films, video tapes, recording tapes, and/or novelty items which are distinguished or characterized by their emphasis on matters depicting, describing, or relating to specified sexual activities or specified anatomical areas. Such establishment or the segment or section devoted to the sale or display of such material in an establishment is customarily not open to the public generally but only to one or more classes of the public, excluding any minor by reason of age.
- (2) **Adult mini-motion picture theater** means an enclosed building with a capacity for less than 50 persons used for presenting material distinguished or characterized by an emphasis on matter depicting, describing or relating to specified sexual activities or specified anatomical areas, for observation by patrons therein. Such establishment is customarily not open to the public generally, but only to one or more classes of the public, excluding any minor by reason of age.
- (3) **Adult motel/hotel** means a building in which lodging is provided or offered to the public for compensation and which is open to transient guests where the room charge is made by the hour, and/or in which books, magazines

and other periodicals or materials which are distinguished or characterized by their emphasis on matter depicting, describing or relating to specified sexual activities or specified anatomical areas, may be sold or rented, or where motion pictures or video tapes with an emphasis on specified sexual activities or specified anatomical areas are available for viewing on an in-room viewing screen or television monitor.

- (4) **Adult motion picture theater** or **adult live stage performing theater** means an enclosed building with a capacity of 50 or more persons used for presenting material distinguished or characterized by an emphasis on matter depicting, describing or relating to specified sexual activities or specified anatomical areas for observation by patrons therein. Such establishment is customarily not open to the public generally, but only to one or more classes of the public, excluding any minor by reason of age.
- (5) **Cabaret** means an establishment which features any of the following: topless dancers and/or bottomless dancers, strippers, or topless and/or bottomless waitpersons or employees or any other form of nude or partially nude service or entertainment.
- (6) **Massage parlor or massage establishment** means a place where manipulated massage or manipulated exercises are practiced for pay upon the human body by anyone using mechanical, therapeutic, or bathing devices or techniques, other than the following: a duly licensed massage therapist, physician, osteopath, or chiropractor; a registered or practical nurse operating under a physician's directions; or, registered physical or occupational therapists or speech pathologists who treat patients referred by a licensed physician and operate only under such physician's direction. A massage establishment may include, but is not limited to, establishments commonly known as massage parlors, health spas, sauna baths, turkish bathhouses, and steam baths. Massage establishments shall not include properly-licensed hospitals, offices of a duly licensed massage therapist, medical clinics, or nursing homes, or beauty salons or barbershops in which massages are administered only to the scalp, the face, the neck or the shoulders; or other establishments that offer massages performed by a duly licensed massage therapist.
- (7) **Specified anatomical areas** means portions of the human body defined as follows:
- (i) Less than completely and opaquely covered human genitals, pubic region, buttocks, or female breast below the point immediately above the top of the areola; and
 - (ii) Human male genitals in a discernibly turgid state, even if completely and opaquely covered.
- (8) **Specified sexual activities** means the explicit display of one or more of the following:
- (i) Human genitals in a state of sexual stimulation or arousal.
 - (ii) Acts of human masturbation, sexual intercourse, or sodomy.
 - (iii) Fondling or other erotic touching of human genitals, pubic region, buttocks, or female breast.

Alley means a public right-of-way which affords only a secondary means of access to abutting property and not intended for general vehicular traffic circulation.

Alternative energy means photovoltaic energy, solar thermal energy, geothermal energy, and wind energy production.

Alteration means any change, addition or modification in construction or type of occupancy; any change in the structural members of a building, such as walls, partitions, stairways, columns, beams, girders; any change in the width or number of exits; any substantial changes in the roof or exterior walls; any change in the location of a building; any change in the number of off-street parking spaces or loading areas or means of egress and ingress to the site; or any change which may be referred to as "altered" or "reconstructed" or "change of use."

Alternative paving means alternatives to traditional impervious asphalt or concrete paving techniques that save energy, decrease the heat island effect, and/or increase stormwater infiltration. This includes pervious paving and pavers and geogrid installations, but does not include loose gravel.

Antenna means the arrangement of wires or metal rods used in the sending and receiving of electromagnetic waves.

Antenna support structure means any mast, pole, tripod, tower, or similar structure used to support an antenna.

Antenna system means the combination of an antenna and antenna support structure.

Arts and crafts studios mean facilities that are used as work space for an artist or crafter or an instruction place for the study of an art or craft. Arts uses shall include, but are not limited to, the fine arts such as music, dance, film (except for adult regulated uses), and photography. Craft uses include the handmade production of articles other than food, such as pottery, glass items, neon sculpture, jewelry, silk screening, needle work, stone and wood work, metalworking or casting, and similar items.

Auction house means a permanent facility where items of merchandise are sold and physically conveyed to the highest bidder in an enclosed facility. This does not include on-line auction activities or temporary auctions.

Automobile means, unless specifically indicated otherwise, any vehicle including cars, trucks, pickups, vans, commercial vehicles, motorcycles, and the like.

300 **Automobile filling station** means any building, structure or land used for the retail sale of fuels, lubricants, and automobile accessories and the making of minor repairs to vehicles or parts thereof totally enclosed within a building. An automobile filling station shall not include engine and transmission rebuilding, reconditioning or general repairs; collision service such as body, frame or fender straightening or repair; steam cleaning, undercoating and rustproofing; painting and similar exterior detailing; machining; and similar servicing, rebuilding or repairs that normally require significant disassembly or storing the automobiles on the premises overnight.

Automobile repair means repair of automobiles including engine tune-ups and servicing of brakes, air conditioning, exhaust systems; oil change or lubrication; wheel alignment or balancing; or similar servicing, engine and transmission rebuilding, reconditioning or general repairs; collision service such as body, frame or fender straightening or repair; steam cleaning, undercoating and rustproofing; painting and similar exterior detailing; machining; and similar servicing, rebuilding or repairs.

310 **Automobile Share Organization** means a membership-based car-share service to the public and manages, maintains and insures motor vehicles for shared use 24-hours a day by individual and group members. This definition does not include automobile rental services where vehicles are leased by the day and vehicles are stored, washed and/or repaired in the same facility.

Automobile Share Parking means a parking space or spaces which it is located and dedicated for use by any automobile share organization through a deed restriction, condition of City approval, or license agreement.

320 **Automobile Wash/Detailing** means any building or premises or portions thereof used for washing and/or detailing motor vehicles and includes automatic, self-service and hand wash facilities.

Awning means a structure generally constructed so as to shade a window or door opening on a building, which is made of rigid or nonrigid materials stretched over a frame attached to a building and which may or may not be constructed so as to be raised or retracted to a position against the building when not in use.

B

330 **Bar/lounge** means an establishment which is operated primarily for the dispensing of alcoholic beverages, although the sale of prepared food or snacks may also be permitted. If an establishment includes a bar or lounge and a separate dining facility, the establishment shall be considered a bar/lounge if more than 50 percent of the usable floor area of the entire establishment is used for the bar/lounge. Brewpubs, as defined and licensed by the State of Michigan, shall be considered a bar/lounge.

Base flood means the flood having a one percent probability of being equaled or exceeded in any given year as determined by the Federal Insurance Administration and/or the U.S. Army Corps of Engineers; also referred to as the 100-year flood.

Base flood elevation means the height of the base flood in relation to the National Geodetic Vertical Datum of 1929.

340 **Basement.** See *Story, basement*.

Bed and breakfast lodging means a structure which was constructed for and is used for single-family residential purposes, but which may have as an accessory use a temporary lodging for travelers/guests where bedrooms are rented on a nightly basis with breakfast included in the price of the room.

*ORIGINAL: (changed because was always grouped with inns, which didn't have the owner restriction. Also removed the regulatory language; bad practice to have in definitions.)
Bed and breakfast lodging means a structure which was constructed for and is used for single-family residential purposes occupied by the owner but which may have as an accessory use a*

350 temporary lodging for travelers/guests where bedrooms are rented on a nightly basis with breakfast included in the price of the room, subject to the limitations outlined in this chapter

Bedroom means any private room in a dwelling unit suitable for regular use for sleeping purposes, as defined in the Building Code. Bedrooms can include rooms designated on development floor plans as dens, studies, or libraries but not living rooms, family rooms, dining rooms, kitchens, bathrooms, laundry rooms, and mud rooms. Any room designated as other than a bedroom but which in the judgment of the City Planner and the Building Official or Planning Commission could normally be usable for sleeping purposes shall be considered a bedroom. Any bedroom designed for occupation shall have minimum space requirements as established by the Building Code for existing structures or as established by the building code adopted by the this Code for new construction, additions or repairs.

360 **Berm** means a continuous, raised earthen mound with a flattened top and sloped sides, capable of supporting live landscaping materials, and with a height and width that complies with the requirements of this chapter.

Board of Appeals means the Zoning Board of Appeals of the City, created pursuant to the provisions of Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.), as amended.

Boardinghouse. See "Roominghouse."

370 **Body art facility** means any location that provides, as a primary function, tattooing, branding, body-piercing, or similar body modification for a non-medical purpose. Body art facilities shall be regulated as required by State of Michigan Act 149 of the Public Acts of 2007, as amended, and shall comply with all inspections, licensing, and other procedures required by that act or by regulations established by Washtenaw County.

Brewer/distiller/wine maker means a facility in which beer, wine or other alcoholic beverages are brewed, fermented, or distilled and then packaged and stored for distribution and, if allowed by licenses and zoning, consumption; and for possesses the appropriate license(s) from the State of Michigan and the federal government. Accessory uses to the facility, if allowed by the state license, such as direct to consumer sales, tasting rooms and restaurants are regulated by zoning district.

380 **Building** means any temporary or permanent structure, having a roof or other covering, used or built for the support, enclosure, shelter, or protection of persons, animals, chattel or property of any kind, designed primarily for shelter rather than as a means of conveyance. A building shall not include such structures as signs, fences or smokestacks.

Building code means chapter 18 of this Code.


ORIGINAL (overly specific)
Building code means chapter 18, Article III of this Code.

Building, completely enclosed means a building separated on all sides from the adjacent open space or from other building or structures by a permanent roof and exterior walls having only window and normal entrance or exit doors.


390 ORIGINAL: two definitions; one in "definitions" and one in 122-734, "unlicensed, untitled, and inoperable motor vehicles, and disassembled parts of motor vehicles." Removed 122-734 and kept regular definition; duplicative and overly specific.

122-734: "Enclosed building" means a garage or other permanent structure which has four walls, a roof, and a means of access for ingress and egress, i.e., doors large enough to accommodate ingress and egress, and is constructed in compliance with the applicable building codes. The placement of a tarpaulin or other covering over such vehicle does not meet the criteria for being within an enclosed building.

Building height means the vertical distance from the established grade of the center of the front of the building to the highest point of the roof surface of a flat roof; to the deck line of mansard roof; to the mean height level between the eaves and ridge for a hip, gambrel or gabled roof; and 75 percent of the height of "A" frame. Chimneys, spires, antenna, and similar projections other than signs shall not be included in calculating building height.



Building line means a line parallel to the front lot line that separates all parts of a building from the open spaces adjacent thereto on the same lot. For the purposes of this chapter, a minimum building line is the same as a required front yard setback line.



410 **Building, principal** means a building or group of buildings in which is conducted the main or principal use of the lot on which the building is situated. See "Accessory use, building, or structure" and "Use, principal."

Building, temporary means a building which is not permanently affixed to the property, and is permitted to exist for a specific reason for a specific period of time. An example of temporary building is a trailer used on a construction site.

Bulk means a composite characteristic of a given building as located upon a given lot; not definable as a single quantity, but involving all of the following characteristics:

- 420 (1) Size and height of the building;
(2) Location of exterior walls at all levels in relation to lot lines, streets, or to other buildings;
(3) Gross floor area of the building in relation to lot area;
(4) All open spaces allocated to the building; and
(5) Amount of lot area provided per dwelling unit.

C

430 **Canopy** means a roof-like structure, other than an awning, made of rigid and durable materials with frames attached to and made a part of the building and further supported by a frame to the ground or sidewalk; or in the case of an automobile filling station or automobile repair garage that sells fuels, a canopy is a roof-like structure that is supported mainly by vertical support beams and not walls, it may or may not be attached to the principal building, and is designed to shelter the fuel pumps.

Carport means a structure consisting of a roof supported by posts which is otherwise open to the elements on at least two sides, which is mainly used for storage of automobiles.

Change of Use constitutes the conversion of an existing structure from one class or type of use to another. Such a change may or may not include exterior building alterations.

440 ORIGINAL: doesn't reflect how it's actually used in the ordinance. Change of use, per the rest of the ordinance, could trigger those things &/or could be more intense, but is not necessarily so.
Change of Use constitutes the conversion of an existing structure from one permitted use to another. Such a change may not include exterior building alterations, but due to a use intensity, requires additional off-street parking and modification to interior circulation or landscaping.

Child care means the following:

- 450 (1) **Family day care home** means a private home, licensed by the state, in which one but less than seven minor children are received for care and supervision for periods of less than 24 hours a day, unattended by a parent or legal guardian, except children related to an adult member of the family by blood, marriage, or adoption. Family day care home includes a home that gives care to an unrelated minor child for more than four weeks during a calendar year.
- (2) **Group day care home** means a private home, licensed by the state, in which more than six but not more than 12 minor children are given care and supervision for periods of less than 24 hours a day unattended by a parent or legal guardian, except children related to an adult member of the family by blood, marriage or adoption. Group day care home includes a home that gives care to an unrelated minor child for more than four weeks during a calendar year.
- 460 (3) **Child care center or day care center** means a commercial facility, licensed by the state, receiving one or more children for care for periods of less than 24 hours a day, and where the parents or guardians are not immediately available to the child. Child care center or day care center includes a facility which provides care for not less than two consecutive weeks, regardless of the number of hours of care per day. The facility is generally described as a child care center, day care center, day nursery, nursery school, parent cooperative preschool, play group, or drop-in center. Child care center or day care center does not include a Sunday school, a vacation Bible school, or a religious instructional class that is conducted by a religious organization where children are in attendance for not more than three hours per day for an indefinite period or not more than eight hours per day for a period not to exceed four weeks during a 12-month period, or a facility operated by a religious organization where children are cared for not more than three hours while persons responsible for the children are attending religious services. State law reference(s)--Child care organizations, defined, MCL 722.111, MSA 25.358(11).

Cistern means a storage container that capture a larger volume of runoff stormwater than a rain barrel.

City means the City of Ypsilanti, Washtenaw County, Michigan.

470

City Council means the City Council of Ypsilanti, Washtenaw County, Michigan.

Club or lodge, private means a nonprofit association of persons who are bona fide dues paying members which owns or leases premises, the use of which is restricted to members and their guests. The facilities owned or used by such organization may be referred to as a "club" or "lodge" in this chapter.

Coin-operated amusement device means any mechanical or electrical device which provides amusement or entertainment which may be operated or set in motion upon the insertion of a coin or token, or payment of a fee. This definition shall not include juke boxes, music machines, telephone devices, machines which dispense merchandise or machines or devices that provide film or video tape presentations to a customer/user who is merely a passive spectator of such presentation. This exclusion shall not be deemed to exclude any machines or devices in which the customer/user is engaged in a form of competition against the machine or another customer/user.

480

Commission means the Planning Commission of the City of Ypsilanti, Michigan.

Communication device means an apparatus such as an antenna system or satellite dish stations of which the principal function is to send or receive television, radio, or data microwave signals.

Communication Facilities, Mobile mean and include all structures and accessory facilities relating to the use of the radio frequency spectrum for the purpose of transmitting or receiving radio signals. This may include, but not be limited to, cellular telephone towers, radio towers, television towers, telephone devices and exchanges, micro-wave relay towers, telephone transmission equipment building and commercial mobile radio service facilities. Not included within this definition are: citizen band radio facilities; short wave facilities; ham, amateur radio facilities; satellite dishes; and, governmental facilities which are subject to state or federal law or regulations which preempt municipal regulatory authority.

490

Communications Facilities, Mobile Attached means mobile communication Facilities that are affixed to existing structures, such as existing buildings, towers, water tanks, utility poles, and the like. A wireless communication support structure proposed to be newly established shall not be included within this definition.

500

Communication Support Structures, Mobile means structures erected or modified to support wireless communication antennas. Support structures within this definition include, but not be limited to, monopoles, lattice towers, light poles, wood poles and guyed towers, or other structures which appear to be something other than a mere support structure.

Communication facility, Co-location means the location by two or more wireless communication providers of mobile communication towers on a common structure, tower, or building, with the view toward reducing the overall number of structures required to support wireless communication antennas within the community.

Condominium means ownership in common with others of a parcel of land and certain parts of a building thereon which would normally be used by all of the occupants, such as yards, foundations, basements, floors, walls, hallways, stairways, elevators and all other related common elements, together with individual ownership in fee of a particular dwelling unit in such building.

510

ORIGINAL: (removed regulatory language)
Condominium means ownership in common with others of a parcel of land and certain parts of a building thereon which would normally be used by all of the occupants, such as yards, foundations, basements, floors, walls, hallways, stairways, elevators and all other related common elements, together with individual ownership in fee of a particular dwelling unit in such building. Condominiums shall be subject to the regulations set forth in Act No. 59 of the Public Acts of Michigan of 1978 (MCL 559.101 et seq., MSA 26.50(101) et seq.), as amended.

520

Condominium Act means Act No. 59 of the Public Acts of Michigan of 1978 (MCL 559.101 et seq., MSA 26.50(101) et seq.), as amended.

Condominium Lot means that portion of a condominium project designed and intended for separate ownership and/or exclusive use, as described in the master deed. Condominium lot is further defined as:

- (1) A condominium unit consisting of the area under a building envelope and the contiguous area around the building envelope which, by itself, meets the minimum area and yard requirements for lots within each zoning district.
- 530 (2) The contiguous limited common element under and surrounding a condominium unit that is or will be assigned to the owner of the condominium unit, for the owner's exclusive use, and which, together with the condominium unit, meets the minimum area and yard requirements for lots within each zoning district.

ORIGINAL: (brought from 602, along with most other "condominium" related definitions)

Lot means the same as building site and is that portion of the condominium project designed and intended for separate ownership and/or exclusive use, as described in the master deed. Lot must be further defined as:

- 540 (1) A condominium unit consisting of the area under a building envelope and the contiguous area around the building envelope which, by itself, meets the minimum area and yard requirements for lots within each zoning district.
- (2) The contiguous limited common element under and surrounding a condominium unit that is or must be assigned to the owner of the condominium unit, for the owner exclusive use, and which, together with the condominium unit, meets the minimum area and yard requirements for lots within each zoning district.

Condominium structure or building envelope means the principal building or structure intended for or constructed upon a lot or building site, together with any attached accessory structures. For example, in a residential development, the condominium structure or building envelope would refer to the house and any attached garage.

550 **Condominium unit** means that portion of the condominium project designed and intended for separate ownership and use, as described in the master deed, regardless of whether it is intended for residential, office, industrial, business, or recreational use as a time-share unit, or any other type of use.

REMOVED: no references elsewhere in the code.

Mobile home condominium project means a condominium project in which mobile homes are intended to be located upon separate sites which constitute individual condominium units.

Cooperative housing means a multiple dwelling owned by a corporation which leases its units to stockholders/shareholders on a proprietary lease arrangement.

560 **Correctional facility** means a place of confinement for persons who have broken the law, are awaiting trial, and/or have been convicted of criminal offenses.

Curb cut means the entrance to or exit from a property provided for vehicular traffic to or from a public or private thoroughfare.

Craft Manufacturing means establishments manufacturing and/or assembling products primarily by hand or with hand tools and/or domestic mechanical equipment. Items produced may include, but are not limited to, custom furniture and woodworking, ceramics and glass, items intended for consumption, personal care products, candle making, jewelry making, custom textile manufacturing and crafts production.

570 **D**

Department of Community and Economic Development means the City department which reviews site plans, variance applications, proposed planned unit developments, and other applications associated with this chapter in order to provide information and recommendations that will assist the Planning Commission and Zoning Board of Appeals in their determinations.

District means a portion of the City within which, on a uniform basis, certain uses of land and/or buildings are permitted and within which certain regulations and requirements apply under the provisions of this chapter, such as building type, building height, building setback, and intensity of use.

580 **Dormitory** means those facilities used for housing students, which are owned and controlled by an educational institution and which are to be distinguished from hotels, motels, and boardinghouses. The terms "dormitory" and "residence hall" are to be used synonymously.

Drive-through service means a business activity so developed that its retail or service character provides a driveway approach and waiting spaces for motor vehicles so as to serve patrons while seated in their motor vehicle. An automatic teller machine or similar device shall not be included in this definition, provided that the device is not

staffed and does not use any type of amplification device.

590 **Dwelling** means a building or portion thereof, containing sleeping, kitchen, and bathroom facilities designed for and occupied by one family, excluding hotels, motels, and inns. In no case shall a travel trailer, motor home, automobile, tent, or other portable building defined as a recreational vehicle be considered a dwelling. In the case of mixed occupancy where a building is occupied in part as a dwelling unit, the part so occupied shall be deemed a dwelling unit for the purposes of this chapter.

Dwelling, accessory means living or sleeping quarters, temporary or permanent, in an accessory building. Accessory dwelling units are prohibited in travel trailers, motor homes, or other recreational vehicle, auto chassis, boat, or portable building.

600 **Dwelling, manufactured** (also known as a "mobile home") means a vehicular, portable structure built on a chassis and designed to be used without a permanent foundation as a dwelling when connected to required utilities and which is, or is intended to be, attached to the ground, to another structure, or to a utility system on the same premises for more than 30 consecutive days. The unit shall be labeled as prescribed under the provisions of the Mobile Homes Construction Safety Standards as promulgated by the United States Department of Housing and Urban Development being 24 CFR 3280. Recreational vehicles as described and regulated shall not be considered "mobile homes" for the purpose of this chapter. *See also "Dwelling, one-family or single-family."*

610 **Dwelling, premanufactured** means an assembly of materials or products intended to comprise all or part of a building or structure, and that is assembled, at other than the final location of the unit of the building or structure, by a repetitive process under circumstances intended to ensure uniformity of quality and material content. The unit shall be labeled as prescribed in R408.31137 of the Michigan Department of Labor, Construction Code Commission Administrative Rules Part 11. *See also "Dwelling, one-family or single-family."*

Dwelling, multiple means a building designed for and occupied by three or more families living independently with separate housekeeping, cooking, and bathroom facilities for each. Multiple dwelling units include the following:

- 620 (1) **Apartment.** An apartment is an attached dwelling unit with party walls, contained in a building with other apartment units which are reached from a common stair landing or walkway, or are accessed directly from the outside.
- (2) **Efficiency unit or studio apartment.** An efficiency unit or studio apartment is a type of multiple-family or apartment unit consisting of one principal room with sleeping facilities, plus bathroom and kitchen facilities, hallways, closets, and/or a dining alcove located directly off the principal room. Sleeping facilities may also be separated from the principal living space by dividers or lofts.

Dwelling, one-family or single-family means a detached building containing not more than one dwelling unit designed for residential use.

Dwelling, two-family or duplex means a detached building, designed exclusively to be occupied by two families living independently of each other, with separate housekeeping, cooking, and bathroom facilities for each.

630 **Dwelling unit, single-family attached or townhouse** means an attached single-family dwelling unit with party walls, designed as part of a series of three or more dwellings, with its own front door which opens to the outdoors at front level, and typically with its own basement utility connections, and front and rear yards. A townhouse may be located on its own lot, or may be located on land commonly owned by a condominium association or similar association. Townhouses are also commonly known as rowhouses.

E

Easement means a grant of one or more of the property rights by the property owner to and/or for the use by the public, a corporation, or another person or entity. The term "easement" often applies to public or private rights-of-way and to "utility easements" which give utility companies the right to use land for the construction and maintenance of utilities.

640 **Encroachment** means any construction, structure, filling grading, or deposition of materials in, upon, across or projecting into a floodplain, channel, or floodway.

Erected means built, constructed, reconstructed, moved upon, or any physical operations on land required for the

building. Excavations, fill, drainage, and installation of utilities shall be considered part of erected.

Essential services means the erection, construction, alteration, or maintenance by public utilities or municipal departments or City licensed cable television companies or underground, surface, or overhead gas, steam, electrical, fuel or water systems for the purposes of transmission, distribution, collection, communication, supply or disposal; including towers, poles, boxes, wires, mains, drains, sewers, pipes, conduits, cables, fire alarm and police call boxes, traffic signals, hydrants, and similar equipment, which are necessary for the furnishing of adequate service by such utilities or municipal departments for the general health, safety, and welfare of the public. The location, size, and intensity of essential services shall be regulated by the standards of this chapter. Essential services shall also not include communication providers when there is more than one entity servicing a geographic area and which are not regulated by the state public service commission.

Excavation means the removal or movement of soil, sand, stone, gravel, or fill dirt, except for common household gardening, farming, and general ground care.

F

Family means:

- (1) One individual;
- (2) A group of two or more persons related by blood, marriage or adoption, together with foster children; together with:
 - (i) No more than two domestic workers employed by the household; OR
 - (ii) No more than two additional unrelated persons occupying the unit as boarders, roomers, or guests; All of whom are domiciled together as a common, domestic, household in a single dwelling unit;
- (3) A group of persons, none of whom are related to each other by blood, marriage, or adoption, who reside together in a single dwelling unit, provided that the total number of occupants in such group shall not exceed three, except in the MD district and in any permitted residential uses in any corridor district the total number of occupants in this group shall not exceed four, unless otherwise provided for in this chapter; or
- (4) A collective number of individuals living together in one dwelling unit, whose relationship is of a continuing, nontransient, domestic character, and who are cooking and living as a single, nonprofit housekeeping unit. This definition shall not include any society, club, fraternity, sorority, association, lodge, coterie, organization, or group of students or other individuals whose domestic relationship is of a transitory or seasonal nature or for an anticipated limited duration of a school term or terms or other similar determinable period.

Family day care home. See “Child Care.”

Farmers’ market means an indoor or outdoor market open to the public offering for sale at retail vegetables, produce, other farm products, and value-added food products, occurring in a pre-designated area, where the vendors are individuals who have grown or produced the food products or have taken the same on consignment for retail sale.

FBFM means the flood boundary and floodway map, used as a floodplain management map that depicts, based on detailed analyses, the boundaries of the 100-year and SOO-year floods and the 100-year floodway. For the purposes of this chapter, the FBFM is the map titled Flood Insurance Rate Map(s) (FIRMS) Washtenaw County (All Jurisdictions) panel number(s) of 26161C; 00269E, 0288E, 0407E, and 0426E dated 4/3/12.

Fence means a permanent or temporary unroofed barrier enclosing or bordering a plot of land or portion thereof composed of wood, shrubs or suitable manmade materials for the purpose of preventing or controlling entrance, confining within, screening, or marking a boundary.

Fill means the deposit or dumping of any matter onto or into the ground, except for common household gardening, farming, and general ground care.

FIRM means the flood insurance rate map titled Flood Insurance Rate Map(s) (FIRMS) Washtenaw County (All Jurisdictions) panel number(s) of 26161C; 00269E, 0288E, 0407E, and 0426E dated 4/3/12.

Flood means a temporary increase in the stage of a river or stream resulting in the inundation of lands not normally covered by water.

Flood insurance study means the engineering study performed by FEMA to identify flood-prone areas, insurance

risk zones, and other flood data and contained in a document titled, Flood Insurance Study, Washtenaw County (All Jurisdictions) Community Number 260216, dated April 3, 2012.


Floodplain means that area of land adjoining a river or stream which will be inundated by a 100-year flood.

Floodway means the channel of a river, stream, creek, or other watercourse and the adjacent land areas that must be reserved in order to discharge the base flood without cumulatively increasing the water surface elevation more than one foot. In the City, the floodway includes the Huron River and Paint Creek along with the adjoining land, as shown on the Federal Emergency Management Agency insurance maps.

710

Floor area, gross means the total area of a building measured by taking the outside dimensions of the building at each floor level intended for occupancy or storage, not including any uncovered or unenclosed porches, patios, or decks.

Floor area, usable nonresidential means the sum of the horizontal areas of each floor, measured from the interior faces of the exterior walls, including all areas used for, intended to be used for, and accessible for the sale of merchandise, provision of services, or service to patrons, clients or customers. Floor area which is used for or intended to be used for the storage or processing of merchandise, or for utilities shall be excluded from the computations of usable nonresidential floor area. If precise floor plans are not available for calculations, usable nonresidential floor area shall be 80 percent of gross nonresidential floor area.



Floor area, usable residential means the gross floor area minus area in basements, unfinished attics, attic floor area with less than five feet vertical distance from floor to finished ceiling, attached garages, uncovered or enclosed porches, patios, terraces, carports, breezeways, decks, or verandas.

Foster family home. A private residence, licensed by the state, that houses four or fewer foster children, up to age 19, under constant child care and supervision. Under Act No. 116 of the Public Acts of Michigan of 1973 (MCL 722.111 et seq., MSA 25.358(11) et seq.), a foster family home does not require local zoning approval before being licensed by the state department of social services.

Foster family group home. A private residence, licensed by the state, that houses five or six foster children, up to age 19, under constant care and supervision. Under Act No. 116 of the Public Acts of Michigan of 1973 (MCL 722.111 et seq., MSA 25.358(11) et seq.), a foster family group home shall be considered a residential use of property for the purposes of zoning and permitted use in all residential zones and is not subject to a special use permit or procedure different from those required for other dwellings of similar density in the same zone.

Fraternity or sorority house means a building, rented, occupied or owned by a national or local chapter of some regularly organized college fraternity or sorority which is officially recognized by a college or university, or by or on its behalf by a building corporation or association composed of members of such fraternity or sorority, as a place of residence.

REMOVED: (from signs; was fairly self-explanatory but definition managed to confuse; term was used slightly differently (didn't contradict what the definition was trying to say, confused, though, by what it *actually* said.)
Building frontage means the outside perimeter measurements of the building wall on which wall the sign shall be placed.

Frontage, Private refers to the side of the building that faces the primary street, and includes the area between the building façade and the lot line.

ORIGINAL: (IN 122-274(C)(6))

Private frontages, refers to the area that is attached or integrated into the primary building.

Frontage, Public means between the face of the curb and the back of the sidewalk. It includes the sidewalk, street trees, street lighting, and any landscaped planting strips that there may be. The public frontage is the crucial area where pedestrians circulate and access property and buildings. It serves as the walkable urban districts' primary source of public open spaces, where people often mingle, converse, play, and eat. The public frontage is both an important part of the transportation system and of the social and economic fabric.

NEW DEFINITION

G

Garage means an accessory building or portion of a principal building used or designed to be used primarily for the storage of motor vehicles, boats, or trailers owned and used by the occupants of the building to which it is accessory.

ORIGINAL: (removed regulatory language)

Garage means an accessory building or portion of a principal building used or designed to be used primarily for the storage of motor vehicles, boats, or trailers owned and used by the occupants of the building to which it is accessory. Private garages shall not have public repair facilities.

Garden/Community Garden means land used to grow and harvest food or non-food crops for personal or group use. The products of gardens/community gardens may or may not be for commercial purposes.

Gas station. See "Automobile filling station."

Geothermal Energy means power extracted from heat stored in the earth. Geothermal resources include: all products of geothermal processes embracing indigenous steam, hot water and hot brines; steam and other gases, hot water and brines resulting from water, other fluids or gas artificially introduced into geothermal formations; heat or other associated energy found in geothermal formations, including any artificial stimulation or induction thereof; and, any mineral or minerals, exclusive of fossil fuels and helium gas, which may be present in solution or in association with geothermal steam, water or brines.

Grade means the average level of the finished surface of the ground adjacent to the exterior walls of the building or

structure.

810 **Greenbelt** means a strip of land of definite width and location reserved for the planting of a combination of shrubs, trees, and ground cover to serve as an obscuring screen or buffer for noise or visual enhancement, in accordance with the requirements of this chapter.

Greenhouse, commercial means a space, building, structure, or combination thereof, where live trees, shrubs, and other plants used in gardening and landscaping are propagated, stored, and/or offered for sale on the premises. *If business is conducted primarily outdoors, see "Open air business."*

820 **Group residence** means a building used as a residence by a group of persons who are not a family on a weekly or longer basis. Typical uses include cooperatives, sororities and fraternities. This definition does not include boarding houses, roominghouses or other group living more specifically defined in this Chapter, specifically any group living or care facility licensed by the State of Michigan.

Ground cover means low-growing plants that form a dense, extensive growth after one complete growing season, and tend to prevent weeds and soil erosion.

H

REMOVED: Hedge. Obvious and unused.

830 **Home occupation** means an occupation or profession carried on by a member or members of the immediate family residing on the premises which use is clearly incidental and secondary to the use of the dwelling for dwelling purposes; does not change the character thereof; and which does not endanger the health, safety, and welfare of any other persons residing in that area by reason of noise, noxious odors, unsanitary or unsightly conditions, fire hazards and the like.

ORIGINAL: (removed regulatory language)
Home occupation means an occupation or profession carried on by a member or members of the immediate family residing on the premises which use is clearly incidental and secondary to the use of the dwelling for dwelling purposes; does not change the character thereof; which does not endanger the health, safety, and welfare of any other persons residing in that area by reason of noise, noxious odors, unsanitary or unsightly conditions, fire hazards and the like; and which meets the requirements of section 122-669

840

Homeless Shelter means a facility which provides congregate style temporary lodging with or without meals and supportive services on the premises to primarily the homeless for more than four (4) weeks in any calendar year. A shelter does not provide such lodging to any individual (1) who is required because of age, mental disability or other reason to reside either in a public or private institution or (2) who is imprisoned or otherwise detained pursuant to either federal or state law. A shelter for the homeless is considered a different land use than adult foster care facilities, supportive housing, nursing homes, temporary emergency shelters, or warming centers.

850 **Hospital** means an institution which is licensed by the state department of health to provide in-patient and out-patient medical and major surgical services for the sick and injured, and which may include such related facilities as laboratories, medical testing services, central service facilities, and staff offices.

Hotel or motel means a building in which lodging is provided and offered to the public for compensation, which is open to transient guests generally on a per-day basis and not for long-term lodging, in distinction from a roominghouse, bed and breakfast lodging, or inn. Hotels or motels customarily provide services such as desk service, maid service, laundering of linens, the use of furniture, etc. No kitchen or cooking facilities are to be provided, with the exception of units for use of the manager or caretaker; unless approved by the Planning Commission as a special use.

860 REMOVED: Housing Code. Now incorporated into Building Code def (ch 18).

I

Ingress and egress means, and is generally used in reference to a driveway which allows vehicles to enter or leave a parcel of property, or to a sidewalk or entranceway which allows pedestrians to enter or leave a parcel of property, a

building, or another location.

Indoor recreation means recreation uses occurring entirely inside a building including bowling alleys, gymnasiums or court sports facilities, tennis clubs, roller or ice skating rinks, recreation centers, personal fitness centers, and similar recreation use.

870 **Inn.** See “Bed and Breakfast.”

ORIGINAL: COMBINED W/BED AND BREAKFAST AS WERE TIEBARRED.

Inn means a structure, originally constructed for residential purposes and used as temporary lodging for travelers and guests where bedrooms are rented on a nightly basis and managed either by an owner/occupant or resident manager.

J

Junk means any motor vehicles, machinery, appliances, products or merchandise with parts missing, or other scrap materials that are damaged, deteriorated, or are in a condition which prevents their use for the purpose for which the product was manufactured.

880 **Junkyard** means an area where waste and used or secondhand materials are bought and sold, exchanged, stored, baled, packed, disassembled, or handled including, but not limited to: junk, scrap iron, metals, paper, rags, tires, bottles, and automobiles.

K

Kennel means any lot or premises on which four or more dogs, cats, or other domestic animals six months or older are kept, either permanently or temporarily, either for sale, breeding, boarding, training, hobby, protection, grooming or as pet; and may offer provision for minor medical treatment, including animal shelters.

L

Laboratory means a place devoted to experimental, routine, or basic study such as testing and analytical operations and in which the manufacturing of products, except prototypes, is not performed.

890

Landscaping means the treatment of the ground surface with live plant materials such as, but not limited to, grass, ground cover, trees, shrubs, vines, edible plants, and flowers. A landscape design may include other decorative manmade materials such as wood chips, crushed stone, boulder, raised garden beds, or mulch. Structural features such as fountains, pools, statues, and benches may also be considered a part of landscaping, but only if provided in combination with live plant material. Artificial plant materials shall not be counted towards meeting the requirements for landscaping.

Loading space, off-street means an off-street space of definite size and dimensions in accordance with the requirements of this chapter, which is safely and conveniently located on the same lot as the building or buildings being served, for the temporary parking of delivery vehicles while loading and unloading merchandise and materials.

900

Lot (or zoning lot or parcel) means a piece of land under one ownership and control that is at least sufficient in size to meet the minimum requirements for use, coverage, area, setbacks, parking, and open space as required by this chapter. A lot shall have frontage on a street. A lot may consist of the following:

- (1) A single lot of record (See "Lot of record").
- (2) A portion of a lot of record.
- (3) A combination of complete lots of record, or portion thereof.
- (4) A piece of land described by metes and bounds.

910

Lot, abutting means lots which share a common interior lot line and which are not separated by a public or private right-of-way or easement.

Lot, adjacent means lots which adjoin each other or which are separated only by a public or private right-of-way or easement.

Lot, contiguous means lots adjoining each other.

Lot, corner means a lot of which at least two adjacent sides abut their full length upon a street, provided that such two sides intersect at an angle of not more than 135 degrees. Where a lot is on a curve, if the tangents through the extreme point of the street lines of such lot make an interior angle of not more than 135 degrees, it shall be considered a corner lot. In the case of a corner lot with a curved street line, the corner is that point on the street lot line nearest to the point of intersection of the tangents described above. Tangents are straight lines extended from the outer edges of a curve which intersect to form a corner.

Lot, double frontage means a lot other than a corner lot having frontage on two more or less parallel streets. Also called a through lot. In the case of a row of double frontage lots, one street shall be designated as the front street for all lots in the plat. If there are existing buildings in the same block fronting on one or both of the streets, the required minimum front yard setback shall be observed on the street where buildings presently front.

Lot, interior means a lot other than a corner lot.


Lot area means the total horizontal area within the lot lines of a lot, exclusive of any abutting public street right-of-way or private road easements, or the area of any lake, except that any lot which abuts an alley, may include the area of half the width of such alley where it abuts the lot in determining the total area of that lot.

Lot coverage means the part or percent of the lot that is occupied by buildings or structures.

Lot depth means the horizontal distance between the front and rear lot lines, measured along the midpoint between the side lot lines.

Lot line means any line separating a parcel of land from another. Lot lines are further defined as follows:

- (1) **Front lot line** means, in the case of an interior lot abutting on one public or private street, the line separating the lot from such street right-of-way. In the case of a corner or double frontage lot, the front lot line shall be that line separating such lot from the street which is designated as the front street in the plat and/or in the request for a building permit.
- (2) **Rear lot line** means the lot line which is opposite and most distant from the front lot line. In the case of irregular, triangular, wedge shaped, or lots that are pointed in the rear, the rear lot line shall be an imaginary line parallel to the front lot line, not less than ten feet in length, lying farthest from the front lot line and wholly within the lot.



(3) **Side lot line** means any lot line other than the front or rear lot lines. A side lot line separating a lot from a street is a street side lot line. A side lot line separating a lot from another lot or lots is an interior side lot line.


(4) **Interior lot line** means any lot line which does not separate a lot from a street right-of-way. A lot line which separates a lot from an alley right-of-way shall be considered an interior lot line.

Lot of record means a lot or parcel of land, the deed of which has been recorded in the office of the registrar of deeds of the county.

Lot split or consolidation means the dividing or uniting of lots by virtue of changes in the deeds in the office of the county registrar of deeds and/or the City treasurer.

Lot, through see “Lot, double-frontage.”

Lot width means the straight line distance between the side lot lines, measured at the two points where the minimum front yard setback line intersects the side lot lines.



M

Major thoroughfare. See “Street.”

Massage parlor or **massage establishment**; see “Adult Regulated Uses.”

Massage therapist means an office where massage is performed for financial compensation only by individuals who satisfy the requirements of the Massage Therapy Licensing Act (PA 471 of 2008) as amended.

Master deed means the legal document prepared and recorded pursuant to Act No. 59 of the Public Acts of Michigan of 1978 (MCL 559.101 et seq., MSA 26.50(101) et seq.), as amended, to which is attached as exhibits and incorporated by reference the approved bylaws for the project and the approved condominium subdivision plan for the project.

Master plan means a document which is prepared under the guidance of the City Planning Commission and consists of graphic and written materials which indicate the general location for streets, parks, schools, public buildings, and all physical development of the City. The master plan is intended as a guide for all development within the City, and is used to guide the Zoning Board of Appeals and the Planning Commission in all decisions before those bodies. The master plan is updated periodically.

Medical or dental clinic or office means an office of physicians, dentists, massage therapists, or similar professionals or which is staffed on a rotational basis with personnel from an area hospital, where persons are examined or treated on an outpatient basis only, including outpatient surgery.

ORIGINAL: (combined, because size restriction accommodates uses that have a rotating staff and is more in line with how uses are divided currently)

EDITED: *Medical or dental clinic* means an office of five or more physicians, dentists, massage therapists, or similar professionals or which is staffed on a rotational basis with personnel from an area hospital, where persons are examined or treated on an outpatient basis only, including outpatient surgery.

REMOVED: *Medical or dental office* means the office of not more than four physicians, dentists, massage therapists, or similar professionals, where persons are examined or treated on an outpatient basis only, including outpatient surgery.

Medical marijuana dispensary means a facility, including a membership club, where primary caregivers who are

legally registered by the Michigan Department of Community Health (MDCH) may lawfully assist qualifying patients to whom the primary caregiver is connected through the state registration process and who are also legally registered by the MDCH with the medical use of marijuana in accordance with the Michigan Medical Marijuana Act, as amended. A use which purports to have engaged in the medical use of marijuana either prior to enactment of said Act, or after enactment of said Act but without being legally registered by the MDCH, shall be deemed to not be a legally established use, and therefore not entitled to legal nonconforming status under the provisions of this Ordinance and/or State Law.

Medical Marijuana Growing/Manufacturing Facility. A facility for the cultivation and processing of medical marijuana into a usable form by primary caregivers who are legally registered by the Michigan Department of Community Health (MDCH) in accordance with the Michigan Medical Marijuana Act, as amended. A use which purports to have engaged in the cultivation and processing of medical marijuana into a usable form either prior to enactment of said Act, or after enactment of said Act but without being legally registered by the MDCH, shall be deemed to not be a legally established use, and therefore not entitled to legal nonconforming status under the provisions of this Ordinance and/or State Law. A maximum of five (5) primary caregivers may operate at a medical marijuana growing/manufacturing facility, provided all applicable zoning ordinance standards can be met.

Medical Marijuana Home Occupation means the cultivation of medical marijuana by a registered primary caregiver as defined in Sec. 3 of the Act, MCL §333.26423(g), in compliance with the General Rules of the Michigan Department of Community Health, the Michigan Medical Marijuana Act, Initiated Law 1 of 2008, MCL §333.26423(e), within a single family dwelling that is the registered primary caregiver's primary residence and which cultivation is in conformity with the restrictions and regulations contained in the Act and in the State Regulations developed by the Michigan Department of Community Health (MCDH). Medical Marijuana Home Use does not include any multi-family dwelling.
(State Law reference(s))--Michigan Medical Marijuana Act, Initiated Law 1 of 2008, MCL §333.264 et seq)

Mezzanine. See *Story, mezzanine*.

Microbrewer/small distiller/small wine maker means a facility in which a limited amount beer, wine or other alcoholic beverages, defined by the State of Michigan Liquor Control Commission, are brewed, fermented, or distilled and then packaged and stored for distribution.

ORIGINAL: (removed portions because redundant)
Microbrewer/small distiller/small wine maker means a facility in which a limited amount beer, wine or other alcoholic beverages, defined by the State of Michigan Liquor Control Commission, are brewed, fermented, or distilled and then packaged and stored for distribution and, if allowed by licenses and zoning, consumption; and possesses the appropriate license(s) from the State of Michigan and the federal government. Accessory uses to the facility, if allowed by the state license, such as direct to consumer sales, tasting rooms and restaurants are regulated by zoning district.

Motel. See "Hotel or motel."

REMOVED: defined elsewhere (vehicle, recreational)
Motor home means a motorized vehicular unit primarily designed for travel and/or recreational usage, which may also contain facilities for overnight lodging. This term does not apply to mobile homes.

Municipality means the City.

Mural means a hand-produced work of visual art that is tiled or painted directly upon, or affixed directly to, an exterior wall of a building; considered ornamentation.

ORIGINAL: changed b/c gilbert v reed, excluded from sign regulation.
Mural means a design or representation painted, drawn, or otherwise attached to the exterior surface of a structure that does not advertise a business, product, service or commercial activity.

N

Nonconforming lot means a lot which was lawfully in existence at the effective date of the ordinance from which this chapter is derived, or amendments thereto, and which does not now conform to the lot size, lot width, or other provisions of this chapter for the zoning district in which it is located.

Nonconforming structure means a building or structure which was lawful on the effective date of adoption or

amendment of this chapter, but which does not conform to the new chapter regulations for lot area, lot area per dwelling unit, lot width, lot coverage, floor area, height, greenbelts or screening, off-street parking, loading space, yard, or other requirements of the zoning district in which it is located.

- 1100 **Nonconforming use** means a use which was lawfully in existence at the effective date of the ordinance from which this chapter is derived, or amendment thereto, and which does not now conform to the use regulations of this chapter for the zoning district in which it is now located. A nonconforming use may include a use that requires a Special Use Permit under current regulations contained in this chapter, where under previous regulations a Special Use Permit was not required or granted.

Nuisance means any offensive, annoying, or disturbing practice or object, which prevents the free use of one's property, or which renders its ordinary use or physical occupation uncomfortable. A nuisance commonly involves continuous or recurrent acts which give offense to the senses, violate the laws of decency, obstruct reasonable and comfortable use of property, or endanger life and health.

1110

Nursery, day nursery, or nursery school. See "Child care center."

Nursing home, convalescent home, or rest home means a home for the care of the aged, infirm, or those suffering from physical or mental disorders, wherein two or more persons are housed or lodged and furnished with nursing care. Such facilities are licensed in accordance with Act No. 368 of the Public Acts of Michigan of 1978 (MCL 333.20101 et seq., MSA 14.15(20101) et seq.), as amended.

O

- 1120 **Occupancy, change of** means an abandonment of an existing use and the substitution of a use of a different kind or class, or the expansion of a use.

Occupied means used in any way at the time in question.

Open air business means any business that is conducted primarily out-of-doors. Unless otherwise specified, open air businesses shall include, but are not limited to:

- 1130 (1) Retail sales of garden supplies and equipment, including but not limited to: trees, shrubbery, plants, flowers, seed, topsoil, trellises, and lawn furniture.
(2) Roadside stands for the sale of agricultural products, including fruits, vegetables, and Christmas trees.
(3) Outdoor display and sale of model garages, swimming pools, playground equipment, and similar uses.

Open space means that part of a lot, including courts and/or yards, which is open and unobstructed from its lowest level to the sky, and is accessible to all occupants upon the zoning lot.

Ownership, change in means whenever the title to the property is transferred to another person, including purchase by land contract.

P

Parcel. See "Lot."

- 1140 **Park** means either a publicly owned and designated park, or an amenity provided and maintained by a property owner for public use.

Parking garage means a building for the storage only of noncommercial vehicles of occupants in the same block or abutting blocks and providing no service to vehicles stored therein.

Parking lot, community means a parking lot on public or privately-owned property which provides parking with or without compensation for uses located in the general area in which it is situated.

- 1150 **Parking, off-street** means an area not located within a public right-of-way which provides vehicular parking spaces along with adequate drives and aisles for maneuvering so as to provide for safe and convenient ingress and egress to the parking area.

ORIGINAL: (took away regulatory language)

Parking, off-street means an area not located within a public right-of-way which provides vehicular parking spaces along with adequate drives and aisles for maneuvering so as to provide for safe and convenient ingress and egress to the parking area, in accordance with the provisions of Article XIII of this chapter.

Parking space means an area, enclosed or unenclosed, of definite length and width as designated in this chapter, to store one automobile or other vehicle which is fully accessible by a driveway connecting the parking space with a street, road or alley and permitting ingress and egress of an automobile. The term "parking space" is exclusive of the access drives and aisles thereto.

Party wall means a wall starting from the foundation and extending continuously through all stories to or above the roof that separates one building from another and that is in joint use by each building.

Passive solar building means a building with walls and roof that are predominantly transparent or translucent and does not have a foundation or permanent electrical utilities. Primarily used to grow plants. It may also be called a hoophouse or greenhouse.

ORIGINAL: *Passive solar structure* is a building that collects, stores, and distributes solar energy to grow plants; it does not have a foundation or electrical utilities. It may also be called a hoophouse.
NOTES: changed because (1), it's a building (enclosed), not a structure (maybe not enclosed); (2) all the mentions of "passive solar structure" said "such as a hoophouse or greenhouse"; (3) sounded way more complex than it should have.

Performance standard means a criteria or limit relating to nuisance elements which a particular use or operation may not exceed. Performance standards are typically established to control noise, odor, smoke, toxic or noxious matter, vibration, fire and explosive hazards, glare, heat, or other effects.

Person means an individual, trustee, executor, fiduciary, corporation, firm, partnership, association, organization, sole proprietor, or other legal entity acting as a unit.

Personal service establishment means a retail, office, or service business that is characterized by a one-on-one interaction between a customer and a proprietor or employee of the business. Includes but is not limited to the following types of establishments: tailor, beauty salon &/or barber, cobbler, locksmith, small appliance repair, graphic design or printmaking services, or postal center.

NEW DEFINITION. Previously undefined but often used. Combined several "such as"es from this and other editions of the code to arrive at this definition.

Planned unit development (PUD) means an area planned and developed as a single entity containing one or more residential clusters or planned unit residential developments or one or more public, quasi-public, commercial or industrial areas.

ORIGINAL: (took away regulatory language)
Planned unit development (PUD) means an area of minimum contiguous size, as specified in Article IX of this chapter, to be planned and developed as a single entity containing one or more residential clusters or planned unit residential developments or one or more public, quasi-public, commercial or industrial areas.

Planning Commission means the City Planning Commission, created pursuant to the provision of Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.).

Porous paving means systems that allow water to pass freely through interstitial space ingrained throughout the paving matrix, thereby transforming traditionally impervious surfaces such as pervious concrete and asphalt, interlocking pavers, reinforced gravel and grass paving.

Principal use. See "Use, principal."

Private street or road. See "Street."

Public utility means any persons, firm, corporation, municipal department, or board, duly authorized through government rate regulation (such as by the state public utilities commission or the City) to furnish to the public under government regulations any of the following: electricity, gas, steam, communications services, cable television services, transportation services, water, sewer service, or sewage treatment.

Premises means a lot or property together with all buildings or structures thereon.

R

Rain gardens mean landscaped depressions that can be built to any size or shape. Also known as ‘bio-retention cells’, they are designed to allow water to settle and infiltrate into the soil.

1220 **Recycling center** means an enclosed area or storage facility where area residents can drop off recyclable household wastes such as newspapers, cans, bottles, plastics, and cardboard which may be sorted and stored for short periods of time on the site until hauled away to another location for processing, reuse, or safe disposal.

Religious Institution means any structure wherein persons regularly assemble for religious activity or worship, including such uses normally accessory thereto, such as a fellowship hall, religious classrooms, parsonages or rectories, and offices. Where a group of persons, who are affiliated with a religious organization, reside together within a dwelling which is the principal building on a site, such dwelling shall not be considered a religious institution.

1230 **Refuse** means the miscellaneous waste materials resulting from housekeeping, mercantile enterprises, trades, manufacturing and office, including other waste matter such as slag, stone, broken concrete, fly ash, sashes, tin cans, glass, scrap metal, rubber, paper, rags, chemicals, or any similar or related combinations thereof.

Research use means facilities for scientific research, and the design, development and testing of electrical, electronic, magnetic, optical and computer and telecommunications components in advance of product manufacturing, and the assembly of related products from parts produced offsite, where the manufacturing activity is secondary to the research and development activities, and includes pharmaceutical, chemical, and biotechnology research and development.

1240 **Restaurant** means any establishment whose principal business is the sale of food and beverages to the customer in a ready-to-consume state, and whose method of operation is characteristic of a carry-out, drive-in, drive-through, fast food, or sit-down restaurant, as defined below. Any restaurant which combines elements of two or more of the following types of restaurants shall be subject to the regulations of the most restrictive restaurant type employed:

- (1) **Restaurant, carry-out.** A restaurant whose method of operation involves the sale of food, beverages, and/or frozen desserts in disposable or edible containers or wrappers in a ready-to-consume state for consumption off the premises, typically from a counter or window inside the building. Indoor seating for consumption on the premises is typically not present.
- (2) **Restaurant, drive-in.** A restaurant whose method of operation involves delivery of prepared food so as to allow its consumption in a motor vehicle or elsewhere on the premises, but outside of an enclosed building.
- 1250 (3) **Restaurant, drive-through.** A restaurant whose method of operation involves the delivery of the prepared food to the customer in a motor vehicle, typically through a drive-through window, for consumption off the premises. Indoor seating for consumption on the premises is typically not present.
- (4) **Restaurant, fast food.** A restaurant whose method of operation involves minimum waiting for delivery of ready-to-consume food to the customer at a counter for consumption at tables, booths, or stands inside the structure or out, or for consumption off the premises, but not in a motor vehicle at the site.
- (5) **Restaurant, sit-down.** A restaurant whose method of operation involves either:
 - (i) The delivery of prepared food by servers (waitpersons) to customers seated at tables within a completely enclosed building; or
 - 1260 (ii) The prepared food is acquired by customers at a cafeteria line or ordering counter and is subsequently consumed by the customers at tables within a completely enclosed building.

Right-of-way means a right-of-way dedicated to or owned by a public body and available for use by the general public. In the case of public streets, the right-of-way often includes curbs, lawn strips (also referred to as the margin or parkway), sidewalks, and lighting and drainage facilities.

Room, for the purpose of determining lot area requirements and density in a multi-family district, means a living room, dining room, or bedroom, and any other room equal to at least eighty (80) square feet in area. A room shall not include the area in kitchen, sanitary facilities, utility provisions, corridors, hallways and storage.

1270 **Roominghouse** means a building, other than a hotel or motel, bed and breakfast lodging, or inn, where for

compensation or by prearrangement for definite periods of time, lodging or lodging and meals are provided for three or more unrelated persons, not living as group or household. The term "unit" as it refers to a roominghouse shall mean sleeping room, or a room which may be used as a sleeping room. (See "Sleeping room.") A boardinghouse or lodginghouse shall be deemed a roominghouse for the purposes of this chapter.

S

Satellite antenna means an accessory structure which at its widest dimension is in excess of 36 inches, capable of receiving signals from orbiting satellites and other extraterrestrial sources, together with other equipment related to such purposes.

1280 **Screen or screening** means a wall, non-wire fence, or combination of plantings of sufficient height, length, and opacity to form a visual barrier

Self-storage facility means a building or group of buildings in a controlled access compound that contains individual compartmentalized and controlled access stalls or lockers of no more than 500 square feet each for the dead storage of customers' goods or wares in enclosed buildings.

1290 **Setback** means the distance between a front, side, or rear lot line and the nearest supporting member of a structure on the lot. The "minimum required setback" is the minimum distance between a front, side, or rear lot line and the nearest supporting member of a structure (including, but not limited to, the foundation, bay windows or similar architectural features at the ground floor level supported by the building or the ground, and enclosed or covered porches) in order to conform to the required yard setback provisions of this chapter. For a site condominium, setbacks are measured from the respective front, side, and rear yard area lines associated with the condominium lot to the respective front, side, and rear of the condominium structure/building envelope.

1300 ORIGINAL: (one from standard definition, one from condo definition; combined.)
Setback means the distance between a front, side, or rear lot line and the nearest supporting member of a structure on the lot. The "minimum required setback" is the minimum distance between a front, side, or rear lot line and the nearest supporting member of a structure (including, but not limited to, the foundation, bay windows or similar architectural features at the ground floor level supported by the building or the ground, and enclosed) in order to conform to the required yard setback provisions of this chapter.
Setback, front, side and rear yard means the distance measured from the respective front, side, and rear yard area lines associated with the lot to the respective front, side, and rear of the condominium structure/building envelope.

SIGNS

Sign means any visual or graphic device designed to inform or attract attention and which is designed to be visible from outside any building or structure in which, upon which, or attached to which it may be located.

1310 ORIGINAL: combined two; edited to be slightly more content neutral.
Sign means a name, identification, description, announcement, display, illustration or insignia which is affixed to or painted or represented directly or indirectly upon a building, structure or piece of land, which directs attention to an object, product, place, authority, person, institution, organization or business and which is visible from any public street, right-of-way, sidewalk, alley, park or other places open to the public.
Sign means any visual or graphic device designed through the use of words, number, characters, or symbols to inform or attract attention and which is designed to be visible from outside any building or structure in which, upon which, or attached to which it may be located. Various types of signs and sign related terms are defined in section 122-863.

1320 REMOVED:

- Address sign.
- Building Directory sign.
- Damaged sign
- Directional sign
- Election sign
- Flag
- Hanging sign
- Historical sign
- Monument sign
- Nameplate
- Nonconforming sign (covered under nonconforming structure)
- Off-premises sign

1330

- On-premises sign
- Opinion sign
- Pole sign
- Portable sign
- Residential entry sign
- Seasonal display
- Special event sign.

1340

OTHER NOTES:

Added whether a sign was considered a freestanding or building-mounted sign, permanent or temporary, as applicable.
Many of these sign definitions have changed slightly or entirely due to the restrictions of Gilbert v Reed.

1350

Sign, abandoned means a sign that contains or exhibits broken panels, visible rust, visible rot, damaged support structures, or which is otherwise dilapidated, unsightly, or unkempt; and for which the business or property owner has not accepted maintenance responsibility or intentionally altered for a period of no less than 365 days, where such acts evidence an intent to abandon.

Sign, animated means a sign that uses light emitting elements including but not limited to light bulbs, fixtures, LEDs, fiber optic lighting to create a continuously scrolling, flashing, or animated effect.

ORIGINAL:

Animated sign means a sign that uses light emitting elements including but not limited to light bulbs, fixtures, LEDs, fiber optic lighting to create a continuously scrolling, flashing, or animated effect on any sign visible from the exterior of the building.

1360

Sign, awning means a sign that is painted on, attached to, or an integral part of an awning or canopy; considered a building-mounted sign.

Sign, banner means a sign consisting of a large piece of cloth or similar flexible material; considered a temporary sign.

Sign, billboard means any freestanding permanent sign that is more than ten feet tall and has an area of more than 300 sf, and as defined in the Highway Advertising Act of 1972, PA 106 of 1972, as amended.

1370

Sign, building-mounted means a sign that is attached to a building. Such signs may include, but are not limited to awning, projecting, wall, and window signs.

Sign, electronic message means a sign with a message displayed on a surface with an electronically illuminated changeable copy area, often composed of LEDs.

ORIGINAL: changed name only. Was "electronically illuminated message sign"

1380

Sign, freestanding means any sign not attached to a building, including monument or pole signs.


Sign, historic marker means a sign that is erected by a duly organized local historic preservation organization.

NEW DEFINITION. INTENT IS TO EXEMPT THESE SIGNS FROM MAX SIZES; INCLUDES THE MOTORCITIES SIGNS, YHF PLAQUES, BOULDER-MARKERS, ETC.

Sign, illuminated means a sign that provides artificial light directly or through transparent or translucent material from a source connected to or within such a sign, on which is illuminated by a light so shielded as to prevent direct rays from being visible from the public right-of-way.

1390

Sign, inflatable means a sign that is intended to be expanded by air or other gas for its proper display or support; considered a temporary sign.



REMOVED: sign, marquee. Didn't add anything.

Sign, mechanical means a sign that has any visible moving parts, mechanical movement or other apparent visible movement, achieved by electrical or mechanical means or action of normal wind currents.

1400 **Sign, overhead banner** means a sign consisting of a large piece of cloth or similar flexible material suspended across a street or other public space and attached at each end; considered a temporary sign.

Sign, permanent means a sign that is securely anchored and affixed to the ground or a building in a manner such that it can remain in place without maintenance for an indefinite period of time, often one year or more.

Sign, projecting means a sign which is attached directly to the building wall or suspended under an awning, canopy, or marquee, and which extends more than 18 inches from the face of the wall; considered a building-mounted sign.

1410 **Sign, public** means a sign erected or installed by a government entity.

Sign, roof means a sign which is constructed and maintained upon or above the roof of a building, marquee, or parapet wall and which is wholly or partially supported by such building; considered a type of building-mounted sign.

Sign, sidewalk means a temporary sign placed within the pedestrian right-of-way. These types of signs include "A" Frame and "T" Frame styles.


1420 **Sign, temporary** means signs not permanently affixed to the ground or to a building, often constructed of cloth, canvas, fabric, plastic or other light temporary material, with or without a structural frame.

Sign, wall means a sign which is painted on or attached directly to a building wall that extends 18 inches or less from the face of the wall and which does not extend above the parapet, eaves, or building façade; considered a type of building-mounted sign.


1430 **Sign, window** means any sign within a building placed within 12 inches of a window or upon a window pane and that is visible from the exterior of the building, not including merchandise located in a window.



Sign area means the gross surface area within a single continuous perimeter enclosing the extreme limits of all sign copy, or the surface of any internally-illuminated sign. Such perimeter does not include any structural or framing elements lying outside the limits of such sign and not forming an integral part of the display. Where a sign has two or more faces, the sign area shall equal the total area of all sign faces, except where two faces are placed back to back and are at no point more than three feet apart, in which case the sign area is considered to be the area of the larger face.



Sign height means the vertical distance measured from the average grade at the sign location to the highest point of the sign.



Sign structure means anything constructed or erected for the exclusive purpose of supporting a sign.

Site plan means a detailed plan showing all features of a proposed development so that the proposal may be evaluated to determine whether it meets the provisions of this chapter.

ORIGINAL: (simplified)

Site plan means a plan showing all features of a proposed development as required in Article IV of this chapter so that it may be evaluated to determine whether it meets the provisions of this chapter.

Sleeping room means a single room within a roominghouse which is usually individually rented and the entry door to the room is individually locked requiring the use of a key to gain access, and which is primarily used for sleeping purposes. The occupants may have direct access within the building to sanitary facilities, kitchen facilities and dining facilities or may share these facilities in common with other residents. See "Roominghouse."

Solar Collector means a device, substance, or element that relies upon sunshine to absorb and transform direct solar radiation through a medium to generate energy that can be used to heat or cool a building, heat or pump water, or generate electricity or other application that would otherwise require the use of a non-renewable energy source.

Solar Farm means large areas of land with several photovoltaic modules and inverters, or parabolic troughs placed on them for large scale energy generation.

REMOVED: Solar roof paneling. Not used outside of definitions.

Sorority house. See "Fraternity or sorority house."

Special use means a use that would be detrimental to other uses permitted in the same zoning district unless carefully controlled as to the number, area, size, exterior design, location, or relation to the adjacent properties and


to the neighborhood or City as a whole, and may be permitted if the proper safeguards are taken. Formerly called conditional use.

ORIGINAL: (removed regulatory language)

Special use means a use that would be detrimental to other uses permitted in the same zoning district unless carefully controlled as to the number, area, size, exterior design, location, or relation to the adjacent properties and to the neighborhood or city as a whole and may be permitted if the proper safeguards are taken. Such uses may be permitted in a zoning district after a public hearing and approval by the Planning Commission, if specific provision is made in this chapter. Formerly called conditional use.

Story means that portion of a building included between the upper surface of any floor and the upper surface of the next floor above it, or any portion of a building between the topmost floor and the roof having a usable floor area which exceeds two-thirds of the usable floor area of the floor immediately below it. Mezzanines and basements shall be deemed full stories as specified within their definitions.

- (1) A *mezzanine* shall be deemed a full story when it covers more than one-third of the area of the story underneath such mezzanine, or if the vertical distance from the floor next below the mezzanine to the floor next above it is 24 feet or more.
- (2) A *basement* shall be considered a story above grade where the finished surface of the floor above the basement is:
 - (i) More than six feet above grade plane;
 - (ii) More than six feet above the finished ground level for more than 50 percent of the total building perimeter; or
 - (iii) More than 12 feet above the finished ground level at any point.
- (3) *Story, first* means the lowest story of the ground story of any building that is not a basement, except that any basement or cellar used for residential purposes shall be deemed the first story.
- (4) *Story, half* means a partial story under a gable, hip or gambrel roof, the usable floor area which does not exceed two-thirds of the floor area of the uppermost full story.



Street means a public or private street, road, or thoroughfare intended primarily to provide vehicular circulation and access to abutting property. Various types of streets are defined as follows:

- (1) *Collector street* means a street whose principal function is to carry traffic between local or minor streets and major streets but may also provide direct access to abutting properties.
- (2) *Cul-de-sac* means a street that terminates in a vehicular turnaround.
- (3) *Local or minor street* means a street whose function is to provide access to abutting properties.
- (4) *Major thoroughfare* means a street that carries high volumes of traffic and serves as a main avenue through or around the City. Major thoroughfares may also be referred to as major streets or arterial streets. For the purposes of this chapter, major thoroughfares shall include those streets designated as "state trunkline," "county primary," or "major street" on the most recently approved City of Ypsilanti Act 51 map (P.A. 1951).

Street line means a dividing line between a street and a lot, also known as the right-of-way line.

Street, primary means the street to which a property is addressed; if a property has more than one address, then the primary street is the one that has the higher National Functional Classification (NFC); if the property has more than one address and the NFC levels are equal, then the primary street is the one that has more frontage.

1560

ORIGINAL: (122-274(C)(5) - didn't provide for ties.

Primary streets are streets that are addressed to the parcel of land.

Street, private means a street or road under private ownership which has been constructed for the purposes of providing access to adjoining property and which is normally open to the public so that persons other than the occupants of adjoining property may travel thereon, but which has not been accepted for maintenance by the City, county, state, or federal government.

Street, public means a street or road, the right-of-way and improvements of which have been accepted for maintenance by the City, county, state or federal government.

1570

Structure means anything constructed or erected in, on, over or below the ground. All buildings are structures, however, not all structures are buildings. Structures include, but are not limited to, principal and accessory buildings, tower, decks, fences, privacy screens, wall, antennae, swimming pools, and sign structures.

Structure, accessory. See "Accessory use, building, or structure."

Subdivision plat means the division of a tract of land into two or more lots, building sites, or other divisions for the purpose of sale or building development, in accordance with the land division act, Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101 et seq., MSA 26.430(101) et seq.), as amended.

1580

Substance abuse treatment facility means:

- (1) *Boarding.* Any facility providing substance abuse treatment or preventive or addictive counseling, including the dispensing of or distribution of drugs as part of the treatment, where individuals receiving the treatment live on the premises for a period of time, including overnight stays.
- (2) *Walk-in.* Any facility providing substance abuse treatment or preventive or addictive counseling, including the dispensing or distribution of drugs as part of the treatment plan, where no one resides on the premises overnight.

Supportive Housing means a facility that provides housing for twenty-four (24) hours per day and supportive services designed to assist residents with improving daily living skills, securing employment, rehabilitation, or obtaining permanent, independent housing. Supportive housing is not intended for short-term, emergency housing and care, but rather longer periods ranging from a few months to a few years. Supportive housing is distinguished from a hospital or other health care environment, and facilities regulated by the State of Michigan as State licensed residential facilities. This definition shall not include fraternities, sororities, dormitories, adult foster care facilities, group homes, nursing homes, substance abuse treatment facilities, emergency shelters, individuals utilizing tenant-based or homeownership-based voucher funding through the U.S. Department of Housing and Urban Development, community correctional facilities, and housing for the rehabilitation of former occupants of correctional facilities.

1590

Supportive Services are services provided to residents of supportive housing for the purpose of facilitating the independence of residents, and may be provided on the premises, or off-site. Some examples are case management, medical or psychological counseling and supervision, child care, transportation, and job training.

1600

Swale, biofiltration means shallow drainage ways with low-pitched side slopes that detain, evaporate, and/or infiltrate the runoff associated with a storm event. They are designed to remove silt and sediment-associated pollutants before discharging to storm sewers and to reduce volume if soils allow for infiltration. Swales may be rock-lined or vegetated.

REMOVED/COMBINED: swale, vegetated/rock with swale, biofiltration. Same thing.

Swale, vegetated/rock means a densely vegetated or rock lined drainage ways with low-pitched side slopes that detain, evaporate, and/or infiltrate the runoff associated with a storm event.

1610

Swimming pool means any structure or container located either above or below grade designed to hold water to a depth of greater than two feet when filled, and intended for swimming, bathing, or aquatic recreation. A swimming pool does not include plastic, canvas, or rubber portable pools temporarily erected upon the ground holding less than 300 gallons of water nor decorative pools with less than two feet of water depth.

T

Temporary use or building. See "Building, temporary" or "Use, temporary."

Theater means an enclosed building used for presenting performances or motion pictures which are observed by paying patrons from seats situated within the building.

1620 **Townhouse.** See "Dwelling unit, single-family attached or townhouse."

Toxic or hazardous waste means waste or a combination of waste and other discarded material including solid, liquid, semi-solid or contained gaseous material which because of its quantity, concentration, or physical, chemical, or infectious characteristics may cause or significantly contribute to the following if improperly treated, stored, transported, disposed of, or otherwise managed:

- (1) An increase in mortality;
- (2) An increase in serious irreversible illness;
- (3) Serious incapacitating, but reversible illness; or
- (4) Substantial present or potential hazard to human health or the environment.

1630 **Tree** means a self-supporting woody, deciduous or evergreen plant with a well-defined central stem which normally grows to a mature height of 15 feet or more in the county.

ORIGINAL: (deciduous/evergreen are common enough to not define.)

Tree means a self-supporting woody, deciduous or evergreen plant with a well-defined central stem which normally grows to a mature height of 15 feet or more in the county.

a. Deciduous tree means a variety of tree that has foliage that is shed at the end of the growing season.

b. Evergreen tree means a variety of tree that has foliage that persists and remains green throughout the year.

1640

U

Use means the purpose for which land, lots, or building thereon is designed, arranged, or intended, or for which it is occupied, maintained, or leased.

Use, accessory. See "Accessory use, building, or structure."

Use, nonconforming. See "Nonconforming use."

1650 **Use, permitted** means a use which may be lawfully established in a particular district or districts provided it conforms with all requirements, regulations, and standards of such district.

Use, principal means the main use of land and/or buildings and the main purpose for which land and buildings exist.

Use, special. See "Special use."

Use, temporary means a use permitted to exist during a specified period of time under conditions and procedures as provided in this chapter.

1660 **Use, unclassified** means a use that is not specifically or implicitly addressed in this Chapter, often due to emerging technologies or omissions within this chapter. Such uses are so differentiated from uses or categories specified in this chapter that the standards of this chapter cannot be reasonably applied to them.

Use, Residential means a use classified as residential under the Building Code, generally including single-family residences, one- and two-family homes and group living. For the purposes of the Zoning Ordinance, this shall not include hotels or bed and breakfasts.

NEW DEFINITION

1670 **Use, Non-residential** means any use not classified as residential under the Building Code. For the purposes of the Zoning Ordinance, this includes hotels and bed and breakfasts.

NEW DEFINITION

V

Variance means a modification of the literal provisions of this chapter in accordance with the provisions of this chapter in cases where strict enforcement would cause undue hardship as a result of special circumstances affecting an individual property that do not generally affect other properties in the same zoning district.

1680 **Vehicle storage facility** means a building or portion thereof or an outdoor controlled-access compound, designed or used exclusively for long-term or seasonal storage of four or more automobiles, trucks, tractors, boats, mobile homes, recreational vehicles and trailers, and other types of vehicles. A vehicle storage facility may be combined with a self-storage facility.

Vehicle, Commercial means a truck or motor vehicle with cab and chassis and with a stake, rack, body, dump body, wrecker body, tanker body or any other body, the mounted height of which exceeds the height of the cab roof more than eight inches. Any truck or motor vehicle which has a commercial license plate and is designed to accommodate a body length in excess of nine feet. Commercial vehicles shall not include motor homes or recreational vehicles, but shall include construction equipment such as backhoes, power shovels, bulldozers, earth moving equipment, semi trucks, tractors and trailers.

1690 **Vehicle, Inoperable** means any motor vehicle which, by reason of dismantling, disrepair, or other causes, is incapable of being propelled under its own power or any motor vehicle which meets any of the three (3) of the following requirements: Has any missing or broken windows; Has a missing hood.; Has a missing door.; Has missing or flat tires; Has missing trunk lid; Has a missing engine, or any substantial part thereof; Is inoperable because of missing or defective steering mechanism; Does not have any or all of the following: operable head lights, parking lights, clearance lights, tail lights, stop lights.

Vehicle, Motor means any wheeled vehicle which is self-propelled or intended to be self-propelled.

1700 **Vehicle, Recreational** means a boat, snowmobile, off-road vehicle, camper travel trailer, motor home, pick-up camper, trailer which is designed for private recreational or recreational travel use. Any trailer which is principally used for transporting any of the above shall also be considered a recreational vehicle.

Vehicle, Unlicensed means any motor vehicle that does not have lawfully affixed to it a valid, unexpired license plate.

Vehicle, Untitled means any motor vehicle which has not been titled in accordance with the law.

1710 **Vegetated roof** means the roof of a building that is partially or completely covered with vegetation, including for food production, and a growing medium, planted over a waterproofing membrane.

Veterinary clinic or hospital means a place for the care, diagnosis, and treatment of sick or injured animals, or those in need of medical or minor surgical attention. A veterinary clinic or hospital may include customary pens, animal runs, or cages enclosed within the walls of the clinic building.

W

Warehouse means an enclosed building used for the storage of commercial goods or wares which are intended for sale, transfer or processing.

Y


1720

Yard means an open space between a building and the adjoining lot lines, unoccupied and unobstructed by any portion of a structure from the ground upward, except as otherwise provided in this chapter. The minimum required setback is the minimum depth of a front, rear, or side yard necessary to conform to the required yard setback provision of this chapter.

1730

- (1) **Yard, front** means a yard extending across the front of a lot and being the minimum horizontal distance between the street line and the principal building or any projections thereof other than projection of uncovered steps, unenclosed balconies or unenclosed porches.
- (2) **Yard, rear** means a yard extending across the full width of the lot between the rear lot line and the nearest point of the principal building. On all lots, the rear yard shall be opposite the front yard.
- (3) **Yard, side** means a yard between a principal building and the side lot line, extending from the front yard to the rear yard, the width of which shall be the horizontal distance from the nearest point of the side lot line to the nearest point on the principal building.
- (4) **Yard, street side** means a yard between the principal building and the street side lot line on a corner lot, extending from the front yard rearward to the rear lot line, the width of which shall be the horizontal distance of the side lot line to the nearest point on the principal building.

1740



Z

Zoning Map means the Zoning Map of the City together with all amendments subsequently adopted.

Secs. 122-204 – 299. Reserved.

Article III: Development Procedures and Administration

HOLD ON NUMBERING PENDING PUBLIC HEARING AND FEES CONSOLIDATIONS

Division 1: Generally.

Sec. 122-300. Eligibility for zoning authorization. (9)

- 1750 (a) If a person, firm, or corporation is delinquent in paying a civil fine, costs, or a justice system assessment imposed by the City of Ypsilanti's Administrative Hearings Bureau, that person is not eligible to apply for any zoning authorization under the City of Ypsilanti's Zoning Ordinance, including but not limited to, the following zoning authorizations:
- (1) A zoning amendment under Article III "Development Procedures and Administration," Division 4 "Amendments."
 - (2) A variance under Article III "Development Procedures and Administration," Division 5 "Variances and Appeals."
 - (3) Site plan review or amendment to an approved site plan under Article III "Development Procedures and Administration," Division 2 "Permits," Subdivision I, "Zoning Compliance."
 - 1760 (4) A special use permit or to amend a special land use under Article III "Development Procedures and Administration," Division 2 "Permits," Subdivision II, "Special Land Uses."
 - (5) A planned unit development under Article VII, Division 1 "Planned Unit Development."
 - (6) A site condominium subdivision project under Article VII, Division 2 "Site Condominium Subdivisions."
 - (7) An application for occupation, construction or substantial improvement in a floodplain under Article VII, Division 3 "Flood Damage Prevention."
- (b) Subsection (a) above does not apply if:
- (1) If the applicant for zoning authorization became the owner of the property by foreclosure or by taking a deed in lieu of foreclosure and is one (1) of the following:
 - 1770 (i) A government-sponsored enterprise. As used in this subsection, "government-sponsored enterprise" means the term as defined in 2 USC 622(8), or the Michigan state housing development authority created under the state housing development authority act of 1966, 1966 PA 346, MCL 125.1401 to 125.1499c.
 - (ii) A financial institution. As used in this subsection, "financial institution" means that term as defined in section 4(c) of the Michigan strategic fund act, 1984 PA 270, MCL 125.2004.
 - (iii) A mortgage servicer. As used in this subsection, "mortgage servicer" means that term as defined in section 1a of the mortgage brokers, lenders, and servicers licensing act, 1987 PA 173, MCL 445.1651a, that is subject to the mortgage brokers, lenders, and servicers licensing act, 1987 PA 173, MCL 445.1651 to 445.1684.
 - (iv) A credit union service organization that is organized under the laws of this state or the United States.
 - 1780 (2) If the application for zoning authorization will correct, in whole or in part, the blight violation that was the subject of the delinquent payment referred to in subsection (a).

Sec. 122-301. Administrative liability. (6)

No officer, agent, employee, or member of the City Council, Planning Commission, or Zoning Board of Appeals shall render themselves personally liable for any damage that may accrue to any person as the result of any act, decision, or other consequence or occurrence arising out of the discharge of their duties and responsibilities pursuant to this chapter.

Sec. 122-302. Vested right. (7)

- 1790 It is hereby expressly declared that nothing in this chapter shall be interpreted or construed to give or grant to any person, firm or corporation any vested right, license, or privilege in the continuation of any particular use, zoning classification or any permissible activities therein. Such provisions are hereby declared to be subject to subsequent amendment, change or modification as may be necessary for the preservation or protection of public health, safety and welfare.

Sec. 122-303. Fees. (98, 135, 35)

Fees for the review of applications and inspections, where required by this Chapter, shall be established and may be amended by resolution of City Council. Such fees are nonrefundable unless noted otherwise.

Sec. 122-304. Reserved.

DRAFT 03-16-2017

Division 2: Permits.

Subdivision I: Zoning Compliance.

Sec. 122-305. Purpose. (121)

- 1800 (a) The purposes of development review are as follows:
- (1) To determine compliance with the provisions of this chapter;
 - (2) To promote the orderly development of the City, to prevent the depreciation of land values through uses or structures which do not give proper attention to site or area protection; and
 - (3) To provide consultation and cooperation between the applicant and the City in order to accomplish the developer's objectives in harmony with the spirit and intent of this chapter.
- (b) The development review procedures and standards in this article are intended to provide a consistent and uniform method of review of proposed development plans. The application of these regulations, consistent with the Master Plan, will ensure orderly and favorable development and redevelopment within the City.

Sec. 122-306. Application procedure; contents. (125)

- 1810 (a) An application for development review shall be made to the City Planner along with a fee as required by the City Council. The application shall, at a minimum, contain the following information:
- (1) The applicant's name, address and phone number.
 - (2) Proof that the applicant is the owner of the property or has a legal or financial interest in the property, such as a purchase agreement, or a signed, notarized statement from the property owner authorizing such application.
 - (3) The name, address and phone number of the owner of record if different from the applicant.
 - (4) The address and/or parcel number of the property.
 - (5) Brief project description, including number of structures and dwelling units, square footage of each building, number of parking spaces, estimated number of employees, and any unique features of the site or proposed development.
- 1820 (6) Area of the parcel in acres, excluding street rights-of-way.
- (b) The City Planner shall review all application materials. If such materials are incomplete, they shall be returned to the applicant.

Sec. 122-307. Levels of Review. (122 + 123)

- (a) Review is required for the activities or uses as listed in the table below. Applications submitted for review may be required to submit a sketch or site plan, as well as additional documentation. The City Planner may defer approval of any application to the Planning Commission. The Planning Commission or City Council shall have the authority to review and to approve, approve with conditions, or deny applications as provided in this Ordinance, when an "X" is in the table below. Any decision made by the City Council shall be based upon recommendation by the Planning Commission.
- (b) Planning Commission review. The Planning Commission in its entirety may review and approve site plans, or the Planning Commission may designate a subcommittee of no less than three of its members to review and/or approve site plans.

(c) Levels of Review Table				
Activities or uses	Type of plan required	City Planner	Planning Commission	City Council
(1) New Construction				
Single or two-family dwelling on individual lot	Sketch	X		
Accessory dwelling unit or accessory building to single or two-family use	Sketch	X		
Essential services, electrical substations, private utilities and similar uses	Site	X		
Non-residential	Site	Review & recommend to PC	X	
Special Land Use or Limited Building Type	Site or Limited Site, at Planner discretion	Review & recommend to PC	X	
Subdivisions (both site condominiums & plats)	Site	Review & recommend to PC	Review & Recommend to City Council	X
Rezoning, including conditional rezonings	Site	Review & recommend to PC	Review & Recommend to City Council	X
Planned Unit Development (PUDs)	Site	Review & recommend to PC	Review & Recommend to City Council	X
(2) Expansion / Modification to Existing Buildings				
Single or two family dwelling on individual lot	Sketch	X		
Accessory dwelling unit	Sketch	X		

(c) Levels of Review Table				
Activities or uses	Type of plan required	City Planner	Planning Commission	City Council
Where no requests for exceptions as allowed by this Chapter are made, and the proposed expansion/modification does not exceed 25% of the existing total gross floor area of the building (up to a maximum of 5,000 square feet), or 500 square feet, whichever is greater.	Site	X		
Where a building encroaches into the required setback from a planned easement; or area of expansion exceeds the threshold permitted for administrative review; or when waivers are requested.	Site	Review & recommend to PC	X	
Expansion or intensification of a Special Land Use	Site	Review & recommend to PC	X	
(3) Change in Use				
Temporary uses, buildings & structures	Sketch	X		
Change in use to a new Special Land Use with <i>no</i> requests for waivers as provided in this chapter and no proposed changes to the site or building footprint	Limited Site	Review & recommend to PC	X	
Change to an equally or less intense use, as determined by the City Planner, that does not involve substantial change in parking, traffic flow, hours of operation, public services, effluent discharge, or substantial alteration of the physical character of the site	Sketch	X		
Change to a more intense use, as determined by the City Planner, that may involve substantial change in parking, traffic flow, hours of operation, public services, effluent discharge, or substantial alteration of the physical character of the site	Site	Review & recommend to PC	X	
(4) Accessory Structures & Site Improvements				

(c) Levels of Review Table				
Activities or uses	Type of plan required	City Planner	Planning Commission	City Council
Accessory buildings, structures, and off-street parking for single and two-family dwelling units on individual lots	Sketch	X		
Accessory buildings less than 250 square feet	Sketch	X		
Accessory buildings, except when accessory to single and two-family dwellings, 250 square feet or more	Site	X		
New parking lot and/or garage, except when accessory to single and two-family dwellings, with no requests for waivers allowed in this Chapter	Site	X		
Expand or modify an existing parking lot that results in drainage alterations, changes in circulation patterns or access, or addition or replacement of base or subgrade, with no requests for waivers allowed in this Chapter	Site	X		
New parking lot and/or garage, or expand/modify existing parking lot, with requests for waivers allowed in this Chapter	Site	Review & recommend to PC	X	
(5) Other uses or site improvements				
Community garden as principal use	Sketch	X		
Infrastructure and paving improvements including sidewalks, bicycle facilities, and pathways on private property in excess of 500 sq ft, excluding parking areas and driveways; with no requests for waivers allowed in this chapter	Sketch	X		
Construction, relocation or erection of structures including signs, screening walls, trash receptacles, fences, walls, lights, poles, cooling/heating or other mechanical equipment	Sketch	X		
Swimming pools	Sketch	X		

Sec. 122-308. Sketch Plans. (126 (19))

A sketch plan may be submitted for administrative reviews or as noted elsewhere in this Ordinance. A sketch plan is a scaled drawing based on a legal survey containing less information than a site plan, drawn in compliance with this Ordinance but not required to be prepared by a licensed professional. Sketch plans shall contain the following information:

- 1840 (a) Address of project, scale, north arrow, date of original drawing, and date of any revisions.
- (b) Name, address and phone number of the site owner, developer, and/or plan designer.
- (c) The area of the site in square feet or acres, excluding all existing and proposed rights-of-way.
- (d) Location and setbacks of existing and proposed buildings; their intended use; the length, width and height of each building; and the square footage of each building. The location and dimensions of any open air uses shall also be provided, such as recreational fields, outdoor cafes, or open air sales areas.
- (e) Parking areas and access drives, showing the number and size of spaces, aisles, loading areas, and barrier-free access ramps, and type of surfacing.
- (f) Landscape plan showing type, size, and location of all plant material. Existing vegetation which is to be retained on the site shall be illustrated.
- 1850 (g) Location of all proposed and existing accessory structures, including fences or walls, outdoor lighting fixtures, outdoor communication devices, flagpoles, storage sheds, transformers, dumpsters or trash removal areas, and signs. Also show the location of all sidewalks or pathways, fire hydrants, and utility poles.
- (h) Location of all outdoor storage areas for materials and the manner in which materials shall be screened and/or covered.
- (i) Notation of any variances or special use permits which are required, any legal nonconforming uses or structures, and any state or federal permits which have been secured or may be necessary to secure.

Sec. 122-309. Site Plans. (126)

Each site plan submitted for review under this chapter shall be drawn at a minimum scale of one inch equals 200 feet and shall contain the following information:

- 1860 (a) Name of development, scale, north arrow, date of original drawing and any revisions, and general location map showing major thoroughfares and site location.
- (b) Name, address and phone number of the site owner, developer and plan designer, and the professional seal of the designer.
- (c) The area of the site in square feet and acres, excluding all existing and proposed rights-of-way. Property lines, dimensions, and building setback distances and dimensions of all structures and lot lines within 50 feet of the site shall also be indicated. If the parcel is a part of a larger parcel, boundaries of the total land holding shall be shown.
- (d) Existing zoning of the site and all adjacent properties.
- (e) Direction of stormwater drainage, ground elevations of all existing buildings, drives and parking lots, and any unusual surface conditions shall be provided. Indicate any areas located within floodplains.
- 1870 (f) Location of existing and proposed buildings; their intended use; the length, width and height of each building; and the square footage of each building. The location and dimensions of any open air uses shall also be provided, such as recreational fields, outdoor cafes, or open air sales areas.
- (g) Location of abutting streets, existing and proposed rights-of-way, service drives, curb cuts, and access easements serving the site, as well as driveways opposite the site and all driveways within 100 feet of the site. The centerline of road rights-of-way shall be shown.
- (h) Proposed parking areas and access drives, showing the number and size of spaces, aisles, loading areas, and handicapped access ramps. Also, the proposed method of surfacing such areas shall be noted.
- (i) Building floor plans and architectural wall elevations. The height of all buildings or structures shall be indicated.
- 1880 (j) Landscape plan in accordance with **Article VI, Division 3 "Landscaping and Screening,"** which indicates type and size of all plant material, including all areas to be sod or seeded for grass. Existing vegetation which is to be retained on the site shall be illustrated.
- (k) Location of all proposed accessory structures, including fences or walls; outdoor lighting fixtures, including photometric study to demonstrate compliance with **§122-609**, outdoor communication devices, flagpoles, storage sheds, transformers, dumpsters or trash removal enclosures, and signs. Also show the location of all sidewalks or pathways, fire hydrants, existing and proposed utility poles, utility easements, and drainways.
- (l) Location of all outdoor storage areas for materials and the manner in which materials shall be screened and/or covered.
- 1890 (m) Location and specifications for any existing or proposed above or below ground storage facilities for any chemicals, salts, flammable materials, or hazardous materials as well as any containment structures or clear zones required by this chapter or other state or federal agencies.
- (n) If phased construction is to be used, each phase must be noted and each phase must stand on its own.
- (o) Notation of any variances or special use permits which are required, any legal nonconforming uses or structures, and any state or federal permits which have been secured or may be necessary to secure.
- (p) Locations of all planned easements for non-motorized pathways in the City of Ypsilanti's Non-Motorized Plan, a 50 to 100 foot conservation and /or access easement along any Huron River frontage, and any planned road

easement expansions approved by City Council.

- 1900 (q) For proposals in the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, the following information shall be provided:
- (1) The building type;
 - (2) For proposed development of one acre or more, a circulation plan shall be submitted that identifies potential cross-and joint-access to adjacent parcels and the existing block layout. All contiguous lots shall be considered to be part of a block for this purpose. Pedestrian accommodations and alternative transportation modes shall be reflected in the submitted circulation plan, as required by §122-672.
- (r) Other data which the Planning Commission, City Planner, or consulting engineer may deem reasonably necessary for adequate review.
- 1910 (s) The approving body, Planning Commission or City Planner, may grant waivers of data requirements when specific data is deemed unnecessary in determining compliance of a site plan with the regulations or standards of this chapter.
- (t) In cases when a Special Use permit is being applied for, the City Planner may grant waivers of the standard site plan data requirements when specific data is deemed unnecessary in determining compliance of a site plan with the regulations or standards of this chapter. In no case shall less information be required for this Limited Site Plan than for a Sketch Plan. The submitted drawings shall be referred to as a Limited Site Plan.

SUBSECTION (t) IS NEW 11/18/16 PER GIFFELS-WEBSTER FEEDBACK. ALIGNMENT W MZEA WORDING.

Sec. 122-310. Review procedure and authorization. (127)

All applications required under this article shall be subject to review as follows:

- 1920 (a) **Pre-application conference required for new construction.** For any new construction, the applicant/property owner must attend a pre-application conference to be coordinated by the City Planner. This meeting may include the Building Official, City Attorney, City Engineer, Fire Inspector, Police Chief, City Manager, Economic Development Official, Planning Commission member(s) and City Council member(s) and any other government official deemed applicable. The City Planner may consult with any of the above offices and share input at the conference. The applicant shall not be bound by the plan reviewed in a pre-application conference, nor shall the any approving authority be bound by any such conference.
- (b) **Distribution of plans.** Upon submission of all required application materials, the site plan proposal shall, when applicable, be placed on the Planning Commission agenda for review. Before the Planning Commission meeting, the site plan and application shall be reviewed for comment by the City Department of Community and Economic Development and any other City officials deemed necessary. The plan may also be submitted to the City Engineer or City Attorney for review.
- 1930 (c) **Authorization.** The City Planner or the Planning Commission, as applicable, shall have the power to approve, approve subject to conditions, or deny any site plan submitted to it under this chapter. The Planning Commission may also table consideration of a site plan until a later meeting. The applicant shall be advised of any action in writing. A building permit shall not be issued until a site plan has been approved as required in this chapter.
- (d) **Review period.** The City Planner or Planning Commission shall render a decision on a site plan within 65 days of its initial review of the site plan, unless an extension of time is agreed to by the City Planner or Planning Commission and the applicant.
- 1940 (e) **Review standards.** The City Planner or Planning Commission shall review each development proposal according to the standards for site plan review as contained in §122-311 and any other applicable regulations of this chapter. In addition, the City Planner or Planning Commission shall consider the findings and recommendations of the Department of Community and Economic Development, and is empowered to seek the review and recommendation of appropriate county, state or federal agencies, or other professionals, consultants, or agencies deemed necessary to assist in the review.
- (f) **Signature of approval.** Upon approval of a development proposal, three paper copies of the plan shall be signed and dated by the City Planner or the chair of the Planning Commission. If approval is subject to conditions, such conditions shall also be written on each of the site plans. One paper copy of the plan shall be retained by the applicant, one paper copy of the plan shall be retained by the City Planner's office, and one paper and one electronic copy of the plan shall be submitted to the Building Department as part of the building permit review process.
- 1950 (g) **Effect of approval.** Approval of a development proposal authorizes issuance of a certificate of zoning compliance and issuance of a building permit, provided all other requirements for a building permit have been met. In the case of uses without buildings or structures, approval of a final site plan authorizes issuance of a certificate of zoning compliance and issuance of a certificate of occupancy, provided all other requirements for such certificates have been met.
- (h) **Expiration of approval.** Approval of a development proposal shall expire and be of no effect unless a building

permit has been issued within one (1) year of the date of the approval. Approval of a development proposal shall expire and be of no effect two years following the date of approval unless construction has begun on the property and is diligently pursued to completion in conformance with the approved site plan.

Sec. 122-311. Standards for site plan and sketch plan review. (128)

1960 Plans shall be reviewed for compliance with the following general standards:

- (a) The applicant is eligible to legally apply, and all required information has been provided.
- (b) The development proposal conforms with all the provisions and requirements, as well as the spirit and intent of this chapter and the Master Plan. The proposed development will meet all the regulations of the zoning district in which it is located.
- (c) All elements of the site or sketch plan is harmoniously and efficiently organized in relation to the character of the proposed use, the size and type of lot, the size and type of buildings, and the character of the adjoining property. The site shall be so developed as not to impede the normal and orderly development or improvement of surrounding property for uses permitted in this chapter.
- (d) With respect to vehicular and pedestrian circulation on the site, including walkways, interior drives, and parking; circulation shall to the extent possible create potential cross-and joint-access to adjacent parcels and the existing block layout. Special attention shall be given to the location, number and spacing of ingress and egress points; general interior circulation including turnaround areas; adequate provisions for delivery of services (trash removal, school buses, mail and parcel delivery); separation of pedestrian and vehicular traffic; avoidance of building corners next to access drives; identification of addresses; storage of plowed snow; and arrangement of parking areas that are safe and convenient, and insofar as practicable, do not detract from the design of the proposed buildings and structures, neighboring properties, pedestrian and bicyclist safety, access to transit and flow of traffic on adjacent streets. All buildings or groups of buildings shall be so arranged as to permit adequate access by emergency vehicles as required by the City building code.
- (e) Streets are designed in context with the urban form and continue the established pattern of the surrounding area.

1970
1980 (f) Adequate services and utilities including sanitary sewers shall be available or provided, with sufficient capacity to properly serve the development. Appropriate measures will be taken to ensure that site drainage will not adversely affect adjoining properties or the capacity of the public storm drainage system, or nearby bodies of water. Provisions shall be made to accommodate stormwater and prevent soil erosion. All stormwater management facilities, including but not limited to storm sewers and detention/retention facilities, shall be designed in accordance with the "Rules of the Washtenaw County Water Resources Commissioner," together with any special provisions established by the City.

(g) Natural resources will be protected to the maximum feasible extent. The proposed development will not cause soil erosion or sedimentation problems, and will respect floodways or floodplains on or in the vicinity of the subject property.

1990 (h) The plan shall provide reasonable visual and sound privacy for all dwelling units on or adjacent to the property. Fences, walks, barriers, and landscaping shall be used, as appropriate, for protection and enhancement of the property. All outdoor storage of materials, loading and unloading areas, and refuse containers shall be screened or located so as not to be a nuisance. Outdoor lighting shall be shielded so as to not adversely affect neighboring properties or traffic on adjacent streets.

(i) Separate phases of development shall be in logical sequence, and each phase shall stand alone so that no one phase will depend upon a subsequent phase for adequate access, public utility services, drainage, or other improvements.

2000 (j) Plans shall conform to all applicable requirements of state and federal statutes, including health and pollution laws, fire or explosion hazards, toxic and hazardous materials, fair housing, and barrier-free requirements. Site plan approval may be conditioned on the applicant receiving necessary county, state, or federal permits before a local building permit or occupancy permit is granted.

(k) An objective of plan review shall be to protect and promote public health, safety, sustainability and general welfare. It is also the intent of plan review to improve the quality of existing developments as they are expanded, contracted, or redeveloped in keeping with sound site development standards of this chapter and the City master plan.

Sec. 122-312. Issuance of building permit. (129)

The Building Department shall, upon receipt of notice of approval from the Planning Commission or City Planner and upon application by the applicant, issue a building permit provided all other applicable City regulations have been met.

2010 **Sec. 122-313. Amendment of approved site plan. (130)**

(a) A site plan may be amended upon application and in accordance with the procedures and requirements provided

in §122-306.

- (b) Minor changes to a site plan may be made without following the procedures of §122-306 at the discretion of the City Planner. The original approving body shall have the authority to determine if a proposed change is minor or major and if such change requires an amendment to an approved site plan. A sketch plan, meeting the requirements of §122-308 may be allowed by the original approving body for submission for review for a minor or major revision.
- (c) Major revisions would include, but not be limited to, increases in scope or density of use, land area, or building size; the addition of uses not authorized by the original site plan approval; the rearrangement or relocation of buildings or structures; changes in the character or function of drives, parking areas, and landscaping; or changes in the concept of the development.
- (d) A record of such determinations and reasons for allowing any minor amendment shall be recorded in writing. In the case of minor changes to an approved site plan, two paper copies and one electronic copy of the revised site plan or sketch plan drawing shall be submitted by the applicant showing such minor changes for purposes of City record.

Sec. 122-314. Modification of plan during construction. (131)

All site improvements shall conform to the approved site plan. If the applicant makes any changes during construction in the development in relation to the approved site plan, such changes shall be made at the applicant's risk, without any assurance that the Planning Commission or City Planner will approve the changes. It shall be the responsibility of the applicant to notify the City Building Department and the City Planner of any changes. The Building Department, the City Planner, or the Planning Commission, whichever is applicable, may require the applicant to correct the changes so as to conform to the approved site plan.

Sec. 122-315. As-built drawings. (132)

Upon completion of the installation of required improvements as shown on an approved site plan, the property owner shall submit to the Building Department an electronic and paper "as-built" site plan, certified by an engineer or architect, at least one week prior to the anticipated occupancy of any building. A Certificate of Occupancy shall be withheld by the Building Department in any case where the site plan and major conditions as approved by the Planning Commission or City Planner have not been complied with and a performance guarantee has not been issued for incomplete improvements in accordance with §122-317.

Sec. 122-316. Phasing of development. (133)

- (a) The applicant may divide the proposed development into two or more phases. In such case, the site plan shall show the entire property involved and shall clearly indicate the location, size, and character of each phase. However, complete site plans for all phases of a project need not be provided at once. Subsequent site plans may be submitted for review and approval for each phase as the project proceeds.
- (b) Each phase of a project shall stand on its own. No phase shall rely on the completion of any subsequent phases of the project for parking, utilities, landscaping, or any other element required by this chapter.

Sec. 122-317. Performance guarantee. (134)

- (a) **Purpose.** To ensure faithful compliance with the provisions of this chapter and any conditions imposed thereunder, a performance guarantee may be required by City staff, the Planning Commission, or when appropriate the City Council to be deposited with the City. Improvements for which a performance guarantee may be required include, but are not limited to, landscaping, berms, screening, lighting, surfacing of drives, parking, traffic control devices, water or sewer line expansions, sidewalks, drainage, and other improvements.
- (b) **General requirements.** A performance guarantee may be in the form of a bond, irrevocable bank letter of credit, cash deposit, or other form of security. Such guarantee shall be provided to the City clerk, and shall be provided any time after a site plan has been approved.
- (c) **Amount.** The amount of the performance guarantee shall be 100% of the cost of the improvements associated with the performance guarantee. Accordingly, the applicant shall provide an itemized cost estimate of the improvements, and such estimate shall be verified by the Building Department. The form of the guarantee shall be approved by the City attorney.
- (d) **Failure to complete improvements.** If the applicant should fail to provide any of the site improvements according to the approved site plans within the time period specified in the guarantee, the performance guarantee shall be forfeited. The City shall rebate a proportional share of cash deposits only when requested by the depositor, based on the percent of improvements completed, as attested to by the depositor and verified by the Building Department. In cases where the provisions of this article have not been met, the amount of the aforementioned performance guarantee shall be used by the City to complete the required improvements and the

balance, if any, shall be returned to the applicant.

2070

REMOVED: moved fees to one section in "generally." (303)
Sec. 122-318. Fees. (135)
Fees for the review of site plans and inspections as required by this article shall be established and may be amended by resolution of the City Council.

Sec. 122-318. Record of approval. (136)

An approved site plan shall become part of the record of approval, and subsequent action relating to a site in question shall be consistent with the approved site plan, unless the City Planner, or Planning Commission, as applicable, agrees to such changes as provided in this article. Any violation of the provisions of this article, including any improvement not in conformance with the approved final site plan, shall be deemed a violation of this chapter and shall be subject to all penalties therein.

Sec. 122-319. Reserved.

Subdivision II: Special Land Uses.

Sec. 122-320. Statement of intent. (161)

- (a) The formulation and execution of this chapter is based upon the division of the City into districts, within each of which certain specified, mutually compatible uses are permitted by right, and the bulk and location of buildings and structures are substantially uniform. It is recognized, however, that there are certain uses which, because of their unique characteristics, cannot be properly classified in any particular district without special consideration. Such uses are essential or desirable for the welfare of the community and are essentially appropriate and not incompatible with the uses permitted by right in a zoning district; but not at every location therein, or without restrictions or conditions being imposed by reason of special problems presented by the use or its particular location in relation to neighboring properties.
- (b) This article requires special approval of such uses. The procedures and standards in this article are intended to provide a consistent and uniform method for review of proposed plans for special land uses.

Sec. 122-321. Authority to grant permits. (162)

The City Planning Commission shall have the authority to approve special uses and to attach conditions to any approved special use. Only those uses specifically listed as special uses in this chapter shall be considered for special use review and approval, except as provided for unclassified uses in §122-431(c).

Sec. 122-322. Application; contents. (163)

- (a) An application for a special use permit shall be made by filing an application form, containing the required information, and fee with the City Planner's office. The fee shall be set by resolution of the City Council. No part of the fee shall be returnable to the applicant. An application for a special use permit shall contain the following information:
- (1) The applicant's name, address, and telephone number; and the names and addresses of all record owners and proof of ownership.
 - (2) The applicant's interest in the property and, if not the fee simple owner, a signed authorization from the owner for the application.
 - (3) Legal description and address of the property.
 - (4) Reference to the section of this chapter under which the special land use permit is sought.
 - (5) A description of the proposed use of the property.
 - (6) A site plan, which shall include all of the information required by this chapter in §122-309. For special land uses to occupy an existing building with no building additions, the City Planner may allow a limited site plan drawn in accordance with §122-309(t).
- (b) A public hearing by the Planning Commission shall be scheduled for within 65 days of the filing date of an application for a special use permit. The applicant or designated representative shall be present at the public hearing and any other scheduled review meetings on the proposal. Otherwise, consideration of the proposal may be tabled due to lack of representation.

Sec. 122-323. Public hearing. (164)

- (a) Notification requirements. A notice of a public hearing shall be published in a newspaper of general circulation in the City and shall be sent by mail or personal delivery to the owners of property for which approval is being considered, to all persons to whom real property is assessed within 300 feet of the boundary of the property in question, and to the occupants of all structures within 300 feet. The notice shall be given not less than 15 days before the date of the public hearing. If the name of an occupant is not known, the term "occupant" may be used in making notification. Notification need not be given to more than one occupant of a structure, except if a structure contains more than one dwelling unit or spatial area owned or leased by different individuals, partnerships, businesses, or organizations, one occupant of each unit or spatial area shall receive notice. In case of a single structure containing more than four dwelling units or other distinct spatial areas owned or leased by different individuals, partnerships, businesses, or organization, notice may be given to the manager or owner of the structure who shall be requested to post the notice at the primary entrance to the structure.
- (b) Contents of notification. The notice shall include the following:
- (1) Description of the nature of the special use request.
 - (2) A legal description or address of the property which is the subject of the special use request.
 - (3) Statement of when and where the public hearing will be held.
 - (4) Statement of when and where comments will be received concerning the request.

Sec. 122-324. Standards for reviewing special use requests. (165)

- (a) Following the public hearing, the Planning Commission shall review the application for the special land use proposal, together with the public hearing findings and any reports or recommendations of the City Planner, Department of Community and Economic Development, City attorney, City building inspector, or other reviewing agencies.
- (b) Approval of a special land use permit shall be based on the determination that the following standards are met:
- (1) The proposed use conforms with all the provisions and requirements of this chapter, including site plan or sketch plan review standards, as applicable, and the applicable site development standards for the specific use, as well as the spirit and intent of this chapter and the Master Plan. The location, scale, and intensity of the proposed use shall be compatible with adjacent uses and the zoning of the land. Height, location and size of buildings shall be compatible with uses and buildings on adjacent properties. The intensity of the proposed use, such as volume, frequency and times of operation, and its compatibility shall be considered. If nonconformities are present, all reasonable effort has been made to eliminate them.
 - (2) The proposed use shall promote the use of land in a socially and economically sustainable manner and shall not be detrimental, hazardous, or disturbing to existing or future neighboring uses, persons, property or public welfare. Noise, odor, smoke and potential contamination of air, soil and water and its potential effect on neighboring uses, persons and property, as well as public welfare, shall be considered.
 - (3) The proposed special land use shall be designed, constructed, operated and maintained to assure long-term compatibility with surrounding land uses. Consideration shall be given to the placement, bulk, and height of structures; materials used in construction; location and screening of parking areas, driveways, outdoor storage areas, outdoor activity areas, and mechanical equipment; nature of landscaping and fencing; and hours of operation.
 - (4) The proposed special land use shall not present unreasonable adverse impacts on the transportation system. Consideration shall be given to the estimated pedestrian, bicycle and vehicular traffic generated by such use, access to transit, proximity to major thoroughfares, proximity to intersections, required vehicular turning movements, and provisions for pedestrian and bicycle traffic.
 - (5) The proposed use shall not create additional requirements at public cost for public facilities and services that will be detrimental to the economic sustainability of the community.
 - (6) Within the MD district, the proposed special land use will help to allow residents to access everyday needs by foot, if a similar service is not currently provided within a quarter mile walking distance.

Sec. 122-325. Planning Commission action. (166)

The Planning Commission must approve, approve with conditions, or deny a special use permit application. The Planning Commission's decision, the basis for the decision, and all conditions imposed, must be described in a written statement which must be made a part of the record of the meeting.

Sec. 122-326. Conditions of approval. (167)

- (a) Reasonable conditions may be required in conjunction with an approval. The conditions may include conditions necessary to ensure that public services and facilities affected by a proposed land use or activity will be capable of accommodating increased service and facility loads caused by the land use or activity, to conserve natural resources and energy, to ensure compatibility with adjacent uses of land, and to promote the use of land in a socially and economically desirable manner. Conditions imposed must do all of the following:
- (1) Be designed to protect natural resources, the health, safety, and welfare, as well as the social and economic well-being.
 - (2) Be related to the valid exercise of police power and purposes which are affected by the proposed use or activity.
 - (3) Be necessary to meet the intent and purposes of this chapter, be related to standards established in this chapter, and be necessary to ensure compliance with those standards.
- (b) Failure by an applicant to comply with any such conditions is considered a violation of this chapter and grounds for Special Use Permit revocation. Conditions of approval must remain unchanged except upon mutual consent of the City Planning Commission and the landowner. Any such changes must be recorded in the minutes of the City Planning Commission meeting at which the action occurred.

Sec. 122-327. Duration of special use approval. (168)

ORIGINAL: removed (a) so that Approvals will expire in accordance with 310 (127). Just (b) now, so removed numbering. (b) altered to remove ability to time-limit special uses per Giffels-Webster feedback; temp permit/temp SUP permit doesn't make sense (SUPs are for when a use is a bit more intense and needs to be mitigated somehow, generally) and approval process that is required by State for SUP doesn't make sense for a time-limited use.

“(a) Approval of a Special Use Permit must expire and be of no effect unless a building permit

- 2190 has been issued within six months of the date of approval, and unless construction has begun within two years of the date of approval and diligently pursued to completion in conformance with all approved plans and conditions attached thereto. Expiration of a special use permit may be extended one time by the Planning Commission for a period of six months; otherwise, a new application for an expired special use permit must be filed.
- (b) Once a special use is established, special use permits must run with the land and must not be issued for specified periods, unless the use is clearly temporary or time-related in nature. Special Use Permits may be revoked by the Planning Commission in accordance with Section 122-170."

Once a special use is established, Special Use Permits run with the land, and cannot be issued for specified periods. Special Use Permits may be revoked by the Planning Commission in accordance with [§122-329](#).

Sec. 122-328. Amendments to special land uses. (169)

- 2200 When an application is received to expand the use, change the traffic pattern, or otherwise alter elements of a special land use, the application is subject to the same procedures followed for an original approval of special land use.

Sec. 122-329. Revocation of special land use approval. (170)

Approval of a special land use permit may be revoked by the Planning Commission if construction is not in conformance with the approved plans, or if compliance with Special Use Permit conditions has not been consistently demonstrated. In such case, the issue must be placed on the agenda of the Planning Commission for consideration. Written notice must be given to the applicant not less than ten days prior to the meeting. The applicant must be given the opportunity to present information to the Planning Commission and answer questions. The Planning Commission may revoke the special use permit if it finds that a site plan or special use permit violation exists and has not been remedied prior to the meeting.

- 2210 **Sec. 122-330. Appeals. (171)**

Any decision of the Planning Commission regarding a special use permit must not be appealed to the City Zoning Board of Appeals. Such appeals must be taken to the circuit court.

Sec. 122-331. Reapplication. (172)

No application for a Special Use Permit which has been denied wholly or in part by the Planning Commission shall be resubmitted for a period of 365 days from the date of such denial, except on grounds of new evidence or proof of changed conditions found by the Planning Commission to be valid.

Secs. 122-332--122-334. Reserved.

Subdivision III: Temporary Use Permits.

Sec. 122-335. Requirements. (35)

The Building Department, unless otherwise indicated, may issue temporary use permits for the uses listed below in any district, unless otherwise indicated, after determining that such uses will meet the standards under subsection (h) of this section and review standards for that specific use included in this section. A second temporary use permit may be issued by the Building Department at the end of such time limit for good cause shown. A third temporary use permit may only be authorized by the Planning Commission, following the noticing procedures outlined in §122-323. The Building Department, at its discretion, may refer any request for a temporary use permit to the Planning Commission.

NOTE: each section hereunder made mention of "...by the building department." Took out-duplicative.

Also, original "A third temporary special use permit may only be authorized by the Planning Commission as a special use under the procedures of Article V of this chapter." Changed to instead ensure similar noticing procedures followed.

- (a) **Temporary dwellings.** An individual mobile home, private garage, basement, or other temporary structure may be used as temporary living quarters for up to 60 days while a dwelling or structure is being constructed on the same premises. A temporary use permit must be issued prior to any such use.
- (b) **Construction buildings.** Temporary buildings for uses incidental to construction work may be authorized for a period of up to 12 months. Such buildings shall be removed within 15 days after completion or abandonment of construction work.
- (c) **Signs and supplies.** The storage of building supplies and machinery; temporary storage buildings; the assembly of materials and customary trade; and contractor, architect, and identification signs in connection with a construction project may be authorized by the Building Department for a period of up to 12 months. All signs shall meet the provisions under Article VI, Division 5, as well as district-specific regulations.
- (d) **Seasonal uses.** Seasonal temporary uses or unusual, nonrecurrent temporary uses, and associated signs may be authorized for up to 30 days. All signs shall meet the provisions under Article VI, Division 5, as well as district-specific regulations.
- (e) **Temporary mobile food establishments.** The City Planner may authorize a temporary special permit to temporary mobile food establishments for no more than 200 consecutive days in one calendar year, with the following standards:
 - (1) Permits expire on December 31st of each year.
 - (2) Temporary mobile food establishments are only permitted in Center, Parks, General Corridor, Neighborhood Corridor, and Health and Human Services zoning districts.
 - (3) The area occupied by temporary mobile food establishments and their accessory materials may not occupy more than 20% of the required parking spaces for the principal/permanent use(s) of the site. This requirement does not apply in Center or in Historic Corridor zoning districts.
 - (4) Evidence of approval or exemption from the Washtenaw County Health Department and/or the Michigan Department of Agriculture and Rural Development, as applicable, shall be provided.
 - (5) Sanitary facilities shall be provided if seating is provided. This requirement may be met via a temporary sanitary facility such as a port-a-john or via an agreement with a neighboring establishment with the same operating hours as the temporary food establishment.
 - (6) Operating hours shall be no later than 10pm Sunday through Thursday, and 11pm Friday and Saturday; nor any earlier than 7am on any day of the week.
 - (7) No outdoor amplified music, sound, or noise shall be permitted. Outdoor generators shall be identified on the sketch plan; no outdoor generators shall be permitted within 200 feet of a property that is not zoned Center, Parks, General Corridor, Neighborhood Corridor, or Health and Human Services zoning district.
 - (8) All outdoor lighting shall be down-directed and fully shielded.
 - (9) The temporary mobile food establishment and all accessory materials shall be located on a paved surface, or evidence submitted that placement on an unpaved surface will not increase stormwater runoff or pose an accessibility challenge for patrons who may use a mobility assistance device, such as a wheelchair or walker.

CHANGED FROM 7/22: added a way for unpaved surfaces to be considered.

- (10) A sketch plan of the proposed location shall be provided; location of any seating, waste containers, fuel storage, sanitary facilities, lighting, generators, or other accessory materials shall be shown.
- (11) The standards in subsection (h) of this section also apply to temporary mobile food establishments.

ORIGINAL: (7) Food Concession Sales. The provisions of this section are intended to allow food vending opportunities that can add vitality to vacant parking lots and

underutilized sites and provide food access, employment and entrepreneurship opportunities while preventing predatory practices on brick-and-mortar restaurants. These provisions shall apply to businesses engaged in the cooking, preparation, and distribution of food or beverage on properties located outside of the public right-of-way. This section does not apply to mobile vendors that move from place to place and are stationary in the same location for no more than thirty (30) minutes at a time or special event vendors. Temporary concession sales, including those conducted outdoors, or in stands, trailers, wagons, or vehicles shall be permitted subject to the following requirements:

- a. Districts Allowed. Food concessions are only allowed as temporary uses in the following districts: Center, Parks, General Corridor, Neighborhood Corridor, and Health and Human Services.
- b. Principal Use. Concession sales as a principal use on a vacant lot or as part of a group of retail business buildings approved under a single approved plan shall be subject to Special Land Use approval in the Center, General Corridor, and Health and Human Services Districts.
- c. Accessory Use. Temporary concession sales may be permitted as an accessory use to the principal permitted use and business on the lot, approved by the City Planner per item s of this sub-section.
- d. Co-Location. Where concession sales have been approved on a lot as a principal use, the Planning Commission may allow locating additional concession sales on the same lot with a sketch plan meeting the requirements of item q of this sub-section.
- e. Approvals. In addition to satisfying the requirements of this section, evidence of approval from the Washtenaw County Health Department and/or Michigan Department of Agriculture and Rural Development, as applicable, shall be provided for all concession sales. A Transient Merchant License or a Special Peddler's license must also be obtained from the Office of the City Clerk, as applicable.
- f. Outdoor Cooking. With the exception of the Center District, outdoor food preparation and cooking is prohibited within two hundred (200) feet of a first-floor residential use.
- g. Active Use. Any stand, trailer, wagon, or vehicle that is located on a property for the purposes of concession sales shall maintain regular business hours at least two days a week so long as the premises is occupied. If the business closes, ceases to operate, or fails to keep regular business hours then the temporary use permit may be revoked and the stand, trailer, wagon or vehicle shall be immediately removed from the property.
- h. Maximum Duration. Permits may be issued for no more than two hundred (200) consecutive days over a period of twelve (12) calendar months. Permits will be issued annually upon application.
- i. Placement. Concession sales shall be located within the building envelope for the district in which it is located.
- j. Parking Area. The area occupied by accessory concession sales shall be no more than twenty (20) percent of any required parking spaces or area. Sufficient on-site or district parking shall be provided for each stand, trailer, wagon, or vehicle on a lot; this shall be in addition to any other required parking for retail business buildings located on the same parcel.
- k. Pedestrian Space. A minimum pedestrian clear space of five (5) feet is required along all public walkways
- l. Traffic Visibility. Concession sales shall not be located in the public right-of-way or on public property unless otherwise approved, and shall be outside of traffic visibility areas in compliance with Section 122-649.
- m. Outdoor Seating: If provided, all outdoor seating must be in compliance with Section 122-799. Outdoor cafes, restaurants and beer gardens.
- n. Sanitary Facilities. Sanitary facilities shall be provided if seating is present for the convenience of guests. The City Planner may waive this requirement if alternative arrangements are made and documentation is provided.
- o. Hours of Operation. Operating hours shall be no later than 10 p.m. Sunday through Thursday and 11:00 p.m. on Friday and Saturday, unless otherwise approved by the Planning Commission.
- p. Sound. No outdoor amplified music, sound, or noise shall be permitted. Outdoor generators that provide power shall be identified; such generators may be prohibited if it is anticipated that such an operation will create a nuisance to neighbors due to noise, exhaust or vibration.
- q. Required Site Information. A sketch plan shall be submitted that includes:

- i. location and dimensions of any stand, trailer, wagon or vehicle, and any other outdoor activity associated with concession sales;
- ii. site dimensions of any existing buildings on the lot including building setbacks;
- iii. existing public improvements, such as fire hydrants, bus shelters, trees and tree grates and parking meters;
- iv. surface type of the lot (e.g. unimproved/paved);
- v. a parking plan, including traffic circulation patterns;
- vi. location of trash receptacles;
- vii. location of on-site water, generator, and/or electric utilities that will serve concession vendor(s);

2350	viii. location of sanitary facilities; ix. map identifying existing restaurants located within buildings, as well as other concession sales locations within three-hundred (300) feet; x. Photographs of the area xi. Required Concession Sales Facilities Information. A narrative with elevation drawings shall be submitted that describe/show: the nature of proposed concession sales, include food and/or beverage types; vehicle or structure type; site signage; duration that sales will occur on the site; and hours of operation.
2360	r. Food Concession Sales Permit Required. A temporary use permit shall be obtained by each concession sales vendor on a property. The vendor shall adhere to all regulations and requirements of this section and any conditions imposed by the Planning Commission. The Planning Director shall apply the Review Standards of this section to insure that the proposed concession sales will not be in conflict with these standards in the issuance of a temporary use permit. s. Permit Approval and Administration. The City Planner will review and approve food concession sales permits if all requirements of this sub-section and Section 122-(9) are met. t. Review Standards. The following considerations shall be used by the Planning Commission and the City Planner in the deliberation and approval of a concession sales request for the site and/or vendor(s):
2370	i. Will the use contribute to the vitality and experience of the surrounding area? ii. Will the use support or draw new attention to existing brick and mortar establishments? iii. Is there an appropriate separation distance between temporary and permanent uses so as to not impair the long-term viability of nearby businesses? iv. Will the use add variety to the types of food or beverage offerings in the district? v. Will the proposed stand, trailer, wagon or vehicle contribute to the general aesthetic of the business district?
2380	(f) Parking areas. Temporary special permits may be issued for the use of unimproved areas for parking for a period of up to 30 days. (g) Sales office for subdivision. Temporary special permits may be issued for a period of up to six months for a temporary office which is both incidental and necessary for the sale or rental of property in a new subdivision or housing project.
2390	REMOVED. Literally makes it more difficult- one more hoop- to authorize pop-up shops. Maybe meant to not require a site plan? But doesn't make sense- esp in Center. Also effectively prohibits such in HC. (h) Temporary Businesses in Vacant Storefronts. In the Center, General Corridor and Neighborhood Corridor Districts, the City Planner may authorize a temporary use permit for a business to occupy a vacant storefront for less than 3 months if the following standards are met: (1) The proposed use is a permitted use in that district. Special uses shall not be given temporary use permits. (2) All building and fire code requirements are met.
2400	(h) Standards. No temporary structure or use permit shall be authorized until the following additional standards are met: (1) The location and erection of any temporary structure shall conform to all of the regulations of the zoning district in which it is situated and all other applicable regulations of this chapter. (2) If an open-air use, it must be located on a fully paved surface, unless otherwise indicated. (3) The location of such use shall not be injurious to adjacent properties or the surrounding neighborhood. (4) The water supply and sanitary facilities of any temporary dwelling shall conform to all applicable requirements of the state health department, the county health department, and City codes and other regulations. (5) The following shall be taken into consideration: (i) The reasons and necessity for the temporary use or structure. (ii) The nature of the use or structure. (iii) The proposed location of the use or structure. (6) If not required above, the approving body may request a sketch plan, drawn to scale no smaller than one inch equals 50 feet, showing the location of the temporary use in relation to the lot lines and other structures.
2410	(7) Reasonable conditions may be required with the approval of a temporary special permit by the approving body. The conditions may include, but are not limited to, conditions necessary to ensure that public services and facilities are not adversely affected, to protect the natural environment and conserve natural resources and energy, to ensure compatibility with adjacent uses of land, and to promote the use of land in a socially and economically desirable manner.
DELETED: see new 122-303. Fees for everyone.	

(j) **Fees.** A fee for a temporary use permit shall be paid in accordance with a fee schedule established by the City Council.

Secs. 122-336--122-339. Reserved.

Subdivision IV: Building Permits.

Sec. 122-340 Requirements; Duration. (33)

- 2420 (a) **Permit requirement.** No building or structure within the City shall hereafter be erected, moved, repaired, altered or razed, nor shall any work be started to erect, move, repair, alter, or raze until a building permit has been issued in accordance with the building regulations of this Code. No building permit shall be issued unless it is in conformity with the provisions of this chapter and all amendments hereto.
- (b) **Application requirements.** All applications for building permits shall be submitted to the Building Department. The application shall be accompanied by a site plan approved by the Planning Commission or City Planner, where applicable, when required under **Article III, Division 2 "Permits," Subdivision 1 "Zoning Compliance."**
- (c) **Cancellation of permits.** The Building Department shall have the power to revoke and cancel any permit in the event of failure or neglect to comply with all of the terms and provisions of this chapter.
- 2430 (d) **Expiration of permit.** All building permits shall expire six months from their date of issuance if construction has not been begun and diligently pursued. The Building Department may, upon a showing of due cause, extend the permit for one additional time as the building department determines to be reasonably necessary for completion. Thereafter, the applicant shall file a new building permit application, accompanied by the required fee.

Sec. 122-341. Certificate of occupancy. (34)

- (a) **Certificate required.** No dwelling, building, structure or land shall be occupied or used until a certificate of occupancy has been issued for such occupancy or use, which occupancy or use shall be in compliance with this chapter, including approved site plans as applicable. No structure or land shall be occupied by a changed use or occupancy until a certificate of occupancy for the changed use has been issued.
- 2440 (b) **Temporary certificate of occupancy.** If the applicant can show prior substantial compliance with this chapter and can demonstrate need, the building department may issue a temporary certificate of occupancy for a period of not more than six months.

Secs. 122-342--122-344. Reserved.

Division 3: Nonconformities.

RENUMBERED; HAD BEEN WHOLE OF ARTICLE VI (sections 201 to 211)
ADDED SECTION FOR "SIGNS OF LOCAL HISTORIC SIGNIFICANCE" UNDER "NONCONFORMING STRUCTURES."

Sec. 122-345. Purpose. (201)

- 2450 (a) It is recognized that there exists within the districts established by this chapter uses of land which were lawful before this chapter was passed or amended, but which would be prohibited or restricted under the terms of this chapter.
- (b) It is the intent of this chapter to permit these nonconformities to continue until they are removed, abandoned, or brought into compliance with this chapter but not to encourage their survival. Such uses are declared by this chapter to be incompatible with permitted uses in the districts. It is further the intent of this chapter that nonconforming buildings, structures, or lots shall not be enlarged upon, expanded or extended, nor be used as grounds for adding other structures or uses prohibited in the district.
- 2460 (c) It is further recognized that certain nonconforming uses are not necessarily contrary to the public health, safety and welfare and that such uses were lawful at the time of their inception, and that no useful purpose would be served by the strict application of the elimination of lawful nonconforming use status. Therefore, two classes of nonconforming uses are designated, being class A and class B. All nonconforming uses are classified as class B nonconforming uses unless designated class A nonconforming uses.

Sec. 122-346. Authority to continue class B nonconforming. (202)

Any class B nonconforming use which existed lawfully at the time of the adoption of the ordinance from which this chapter derives and which remains nonconforming and any such use which becomes nonconforming upon the adoption of this article, or of any subsequent amendments thereto, may be continued, subject to the regulations in this article.

Sec. 122-347. Nonconforming lots. (203)

A nonconforming lot is a lot of record or a lot described in a deed or land contract existing at the effective date of the ordinance from which this chapter derives that does not meet the minimum area or lot dimensional requirements of the district in which the lot is located. The following regulations must apply to any nonconforming lot:

- 2470 (a) Use of nonconforming lot. Any nonconforming lot must be used only for a use permitted in the district in which it is located.
- (b) Single lot of record. A principal structure and customary accessory structures may be erected on any single lot of record at the effective date of adoption or amendment of this chapter, notwithstanding limitations imposed by other provisions of this chapter. Such lot must be in separate ownership and not of continuous frontage with other lots in the same ownership. This provision must apply even though such lot fails to meet the requirements for area or width or both, that are generally applicable in the district, provided that yard setback dimensions and requirements other than those applying to area or width of the lot must conform to the regulations for the district in which such lot is located. However, no more than one dwelling unit must occupy any lot except in conformance with the provisions of this chapter for required lot area for each dwelling unit.
- 2480 (c) Variance from yard or other requirements. If the use of a legal nonconforming lot requires a variation from any yard or other requirements, other than lot area or width, then such variance must be obtained from the Zoning Board of Appeals.
- (d) Contiguous lots in same ownership. When two or more contiguous nonconforming lots or parts of nonconforming lots are in a single ownership at the time of, or subsequent to the adoption or amendment of this chapter, such lots must be considered to be a single lot for the purposes of this chapter, and no portion of such lot must be used, occupied, divided, or sold in any manner which would diminish compliance with minimum lot width and area requirements of this chapter.

Sec. 122-348. Nonconforming use of land. (204)

2490 A nonconforming use of land occurs when property is used for a purpose or in a manner which was lawfully in existence before this chapter was adopted, but has become nonconforming under the terms of this chapter or its amendments.

- (a) The nonconforming use of land not involving a building or structure, or in connection with which any building or structure thereon is incidental or accessory to the principal use of the land, may be continued subject to the regulations which follow:
- (1) **Change.** The nonconforming use of land must not be changed to any other use except to a use permitted in the district in which the land is located.

- (2) **Expansion.** A nonconforming use of land must not be expanded or extended beyond the area it occupies.
- (3) **Moving.** No such nonconforming use must be moved in whole or in part to any other portion of the lot or parcel occupied by such use at the effective date of adoption or amendment of this chapter.
- 2500 (4) **Change in occupancy or ownership.** A change in occupancy or ownership shall not constitute a change in use.
- (5) **Abandonment.** If the nonconforming use of land is discontinued for a period of 365 consecutive days, where there is an intent demonstrated by the property owner to abandon the nonconforming use, such use shall not be renewed, and any subsequent use of the land must conform to the regulations of the district in which the land is located. A nonconforming use may be determined to be abandoned if the use has ceased and one (1) or more of the following conditions exist, that said condition(s) demonstrating intent on the part of the property owner to abandon the nonconforming use:
- 2510 (i) One (1) or more utility meters, such as water, gas and electricity to the property, have been removed;
- (ii) The property, buildings and/or grounds are unsafe or unsanitary, as described in Chapter 18, Article V;
- (iii) Cessation of business operations;
- (iv) Receipt of a written declaration by the property owner.
- (v) Signs or other indications of the existence of the nonconforming use have been removed;
- (vi) Removal of equipment or fixtures that are necessary for the operation of the nonconforming use;
- (vii) Failure to maintain current licenses, certificates, permits, registrations or other appropriate documentation for the nonconforming use;
- (viii) Bank or tax foreclosure;
- (ix) Operation or maintenance of a permitted or different use at the property; or
- (x) Other actions or omissions, which in the opinion of the Planning or Building Department(s), evidence an intention of the part of the property owner to abandon the nonconforming use.
- 2520 (b) A nonconforming use of land is not eligible for class A nonconforming designation.

Sec. 122-349. Class B nonconforming uses of buildings. (205)

All nonconforming uses of buildings not designated class A shall be class B nonconforming uses of buildings. Class B nonconforming uses of buildings shall comply with all the provisions of this article relative to nonconforming uses of buildings. The class B nonconforming use of a building, or building and lot in combination, may be continued subject to the following provisions:

- (a) **Change in use.** The nonconforming use of a building may not be changed to a different use unless the new use is permitted in that same district. Any building, or building and lot in combination, in or on which a nonconforming use is replaced by a permitted use, must thereafter conform to the regulations of the district in which it is located and the nonconforming use may thereafter not be resumed.
- 2530 (1) A building or structure used for residential purposes which is nonconforming due to the number of dwelling units contained therein may only be changed so that the number of dwelling units is decreased, or so that the use is brought into conformity with this chapter.
- (2) Notwithstanding the above, a nonconforming use of a building or structure may be changed to another nonconforming use so that the degree of nonconformity is lessened when authorized by the planning commission after a public notice and hearing in accordance with [§122-323](#). In considering such authorization, the planning commission must consider the following:
- 2540 (i) Whether the proposed use is equally or more appropriate than the present nonconforming zoning district in which the building, structure or land is located. No change to a less appropriate use may be authorized by the Planning Commission.
- (ii) Whether the proposed use will interfere to a lesser extent with the use of adjoining lands or other properties in the surrounding neighborhood for the uses for which they have been zoned pursuant to the provisions of this chapter.
- (iii) The effect of the proposed use on adjoining lands and the surrounding neighborhood.
- (iv) In permitting such change, the Planning Commission may require appropriate conditions and safeguards in accord with the purpose and intent of this chapter.
- (v) Where a nonconforming use of a structure, or structure and land, is hereafter changed to a more conforming use, it must not thereafter be changed to a less conforming use.
- (b) **Expansion of class B nonconforming use.**
- 2550 (1) The nonconforming use of any part of a building or structure must not be expanded or extended into any other portion of such building or structure.
- (2) No visible structural alteration must be made to the building or structure devoted to a nonconforming use, except repairs and maintenance work which are required to keep such building in sound condition or as required by law.
- (3) An existing structure containing a nonconforming use shall not be enlarged, constructed, reconstructed,

moved or structurally altered or extended, unless the use is changed to a use which is permitted in the district in which the structure is located.

(c) **Change in occupancy or ownership.** A change of occupancy or ownership shall not constitute a change in use.

(d) **Removal or destruction.** If a building or structure in which a nonconforming use is being conducted is removed, destroyed, or severely damaged to the extent that the cost of restoration of the structure exceeds 100 percent of the state equalized value (SEV) or 50 percent of a higher value established by the most recent appraisal of the structure exclusive of the foundation and land, the nonconforming use shall not be renewed, and any subsequent use of the premises must conform to the use regulations of the district in which the premises are located. Single-family homes on individual lots that are considered a non-conforming use in the NC, Neighborhood Corridor Zoning District, shall be allowed to be rebuilt regardless of the amount of damage done to the structure so long as the rebuilt building is not enlarged or expanded. Single-family and two-family homes on individual lots that are considered a non-conforming use in the PMD, Production, Manufacturing, and Distribution Zoning District, shall be allowed to be rebuilt regardless of the amount of damage done to the structure so long as the rebuilt building is not enlarged or expanded.

For the purpose of calculating a fair and equitable cost of restoration regulated by this section, the average of two bid estimates from licensed contractors must be used. All work requiring permits under state and local regulations, and materials necessary to bring the structure up to current code must be included. Clean up costs, demolition, furnishings, appliances, and site work, i.e. landscaping, fencing, paving, shall not be included. The actual repair and reconstruction may be done by the owner or contractor of their choice.

(e) **Abandonment.** If the nonconforming use of land is discontinued for a period of 365 consecutive days, where there is an intent demonstrated by the property owner to abandon the nonconforming use, it must not thereafter be renewed, and any subsequent use of the land must conform to the regulations of the district in which the land is located. A nonconforming use must be determined to be abandoned if the use has ceased and one (1) or more of the following conditions exist, that said condition(s) being deemed to demonstrate intent on the part of the property owner to abandon the nonconforming use:

- (1) One (1) or more utility meters, such as water, gas and electricity to the property, have been removed;
- (2) The property, buildings and/or grounds are unsafe or unsanitary, as described in Chapter 18, Article V;
- (3) Cessation of business operations;
- (4) Receipt of a written declaration by the property owner.
- (5) Signs or other indications of the existence of the nonconforming use have been removed;
- (6) Removal of equipment or fixtures that are necessary for the operation of the nonconforming use;
- (7) Failure to maintain current licenses, certificates, permits, registrations or other appropriate documentation for the nonconforming use;
- (8) Bank or tax foreclosure;
- (9) Operation or maintenance of a permitted use or different use at the property; or
- (10) Other actions or omissions, which in the opinion of the Planning or Building Department(s), evidence an intention of the part of the property owner to abandon the nonconforming use.

Sec. 122-350. Class A nonconforming uses of buildings. (206)

Nonconforming uses of buildings shall be designated Class A provided that the Planning Commission finds all of the following exists with respect to the use or structure:

- (a) The use of structure was lawful at its inception.
- (b) The decision to continue the nonconforming use, if granted, will not alter the essential character of the area or neighborhood.
- (c) Continuance of the use or structure would not be contrary to the public health, safety, or welfare or the spirit of the chapter.

(d) No useful purpose would be served by strict application of the provisions of this chapter with which the use or structure does not conform.

(e) Nonconforming uses of buildings are subject to the following restrictions:

- (1) Change in use. The nonconforming use of a building may not be changed to a different use unless the new use is permitted in that same district. Any building, or building and lot in combination, in or on which a nonconforming use is replaced by a permitted use, must thereafter conform to the regulations of the district in which it is located and the nonconforming use may thereafter not be resumed.
- (2) A building or structure used for residential purposes which is nonconforming due to the number of dwelling units contained therein may only be changed so that the number of dwelling units is decreased, or so that the use is brought into conformity with this chapter.
- (3) Notwithstanding the above, a nonconforming use of a building or structure may be changed to another nonconforming use so that the degree of nonconformity is lessened when authorized by the Planning Commission after a public notice and hearing in accordance with [§122-323](#). In considering such

authorization, the Planning Commission must consider the following:

- (i) Whether the proposed use is equally or more appropriate than the present nonconforming zoning district in which the building, structure or land is located. No change to a less appropriate use may be authorized by the Planning Commission.
- (ii) Whether the proposed use will interfere to a lesser extent with the use of adjoining lands or other properties in the surrounding neighborhood for the uses for which they have been zoned pursuant to the provisions of this chapter.
- (iii) The effect of the proposed use on adjoining lands and the surrounding neighborhood.
- (iv) In permitting such change, the Planning Commission may require appropriate conditions and safeguards in accord with the purpose and intent of this chapter.
- (v) Where a nonconforming use of a structure, or structure and land, is hereafter changed to a more conforming use, it must not thereafter be changed to a less conforming use.
- (f) Removal or destruction. If a class A nonconforming structure is destroyed, or severely damaged, it may be restored in conformance with the plans submitted when the status was conferred.
- (g) This designation shall run with the land.

Sec. 122-351. Class A Conditions. (207)

The decision to grant a class A designation shall be made by the Planning Commission in writing, setting forth its findings of fact and basis for the designation. Only multiple family dwellings and/or group residence uses in R1 and CN-Mid shall be eligible for this designation. For changes or improvements to a class A use, site plans shall be required.

(a) Application. An application for class A nonconforming status shall be filed with the City Planner's office by the record owner of the property in question or by a person authorized to act on the record owner's behalf. The application shall consist of a completed application form, fee, and the following information:

- (1) Name, address, and telephone number of the applicant and property owner; and the interest of the applicant in the property.
- (2) Legal description, address, and tax parcel number of the subject property.
- (3) An accurate, scaled drawing of the property, showing all property lines and dimensions correlated with the legal description; the location and dimensions of all existing and proposed structures and uses on the property; any roads, alleys, easements, drains, or waterways which traverse or abut the property; and the lot area and setback dimensions necessary to show compliance with the regulations of this chapter. In most cases, a site plan or survey will meet this requirement.
- (4) The applicant shall show compliance with all applicable conditions of the City of Ypsilanti Code of Ordinances, and all applicable conditions of the International Property Maintenance Code, as adopted under Chapter 18 of the City of Ypsilanti Code of Ordinances.
- (5) Other reasonable information deemed necessary by the Planning Commission in order to make a proper decision.
- (6) No application for Class A designation shall be accepted after such time as the building has been destroyed as described in §122-349(d) or the use abandoned as described in §122-349(e).

(b) Conditions. The Planning Commission may condition its approval on the following:

- (1) Screening and landscaping in keeping with community standards to ensure compatibility with adjacent uses.
- (2) Restrictions on lighting, noise, odor, or visual impact.
- (3) Signage must comply with current zoning district requirements. Existing nonconforming signs may be required to be eliminated or reduced in size and number.
- (4) Replacement of a building must not create a more nonconforming yard setback condition which would impact on conforming properties in the immediate vicinity.
- (5) Other reasonable safeguards and improvements may be imposed by the Planning Commission to protect conforming uses in the surrounding area.

(c) Procedure. By the following procedure, the Planning Commission shall assure the public health, safety and welfare, and the spirit and purpose of this chapter:

- (1) A class A designation shall be deemed temporary until the Planning Commission has received written verification from the building official that the party requesting the class A designation has complied with all of the conditions set forth by the Planning Commission.
- (2) Once the Planning Commission has received written verification from the building director that the party requesting the class A designation has complied with said conditions, the class A designation shall become final, subject to other provisions of this chapter as hereafter prescribed.
- (3) No class A nonconforming use shall be resumed if it has been abandoned as defined in §122-349(e). No class A nonconforming use shall be used, altered, or enlarged in violation of any conditions imposed in its designation.

- (4) A temporary class A nonconforming use designation shall be void after six months if any conditions imposed by the designation remain outstanding, unless the Planning Commission grants a written request for an extension of six months. No more than two extensions may be granted.
- (d) **Revocation.** Approval of a Class A designation may be revoked by the Planning Commission if the use and building is not in conformance with the approved plans, or if compliance with conditions has not been consistently demonstrated. In such case, the issue shall be placed on the agenda of the Planning Commission for consideration. Written notice must be given to the applicant not less than ten days prior to the meeting. The applicant must be given the opportunity to present information to the Planning Commission and answer questions. The Planning Commission may revoke the Class A designation if it finds that a violation of the conditions set forth by the Planning Commission in their initial decision exists and has not been remedied prior to the meeting.

Sec. 122-352. Nonconforming structures. (208)

- (a) A nonconforming building or structure is a structure, including a sign, which was lawful on the effective date of adoption or amendment of this chapter, but which does not conform to the new chapter regulations for building type, lot area, lot area per dwelling unit, lot width, lot coverage, floor area, height, screening, off-street parking, loading space, yard, or other requirements of the zoning district in which it is located.

NOTE: added "including a sign" clause when "nonconforming signs" category was removed.

- (b) Nonconforming buildings and structures may be re-used and occupied by new owners or tenants if all requirements of this Chapter are met and the restrictions below are met.
- (c) Nonconforming buildings and structures are subject to the following restrictions:
- (1) Expansion. Nonconforming structures may be expanded only in compliance with the following regulations:
- (i) All nonconforming structures, in any zoning district, may only be expanded in such a way that does not increase a non-conforming characteristic.
- (ii) All expansions must meet all requirements of the zoning district in which it is located, including lot coverage, heights, yard requirements, and off-street parking.
- (iii) A non-conforming building type may not be expanded.
- (2) Alterations. A nonconforming structure may be altered to decrease its nonconformity.
- (3) Moving. A nonconforming structure which is moved within a site or to another site must conform to the regulations of the district in which it is located.
- (4) Damage and removal. A nonconforming structure which is damaged by any means may be restored to its original conditions and location prior to such damage, provided such construction is completed within 18 months of the date of damage and is diligently pursued to completion. Failure to complete reconstruction results in the loss of legal nonconforming status.
- (5) Restoration or repair.
- (i) All repairs and maintenance work required to keep a nonconforming building in sound condition may be made, but such structure may not be structurally altered in a way inconsistent with the description and purpose of this article.
- (ii) If a nonconforming structure or a structure housing a nonconforming use becomes physically unsafe or unlawful or poses a threat to the public health, safety, and welfare due to a lack of repairs or maintenance, the structure may be declared by the Building Department to be unsafe or unlawful by reason of physical condition. Such structure may not thereafter be restored, repaired, or rebuilt except in conformity with the provisions of this Chapter.
- (d) Restoration of Historic Structures. Restoration may be permitted of a legal nonconforming structure, designated as historic by the Ypsilanti Historic District Commission, which has been destroyed or abandoned, as defined in §122-349, provided the Planning Commission finds all of the following provisions are met:
- (1) The approved design of the restored building maintains the same design and historical character it had prior to the destruction or abandonment; or, in the case of a building that had been altered prior to destruction or abandonment, that the restored building more closely parallels the design of the original historic structure.
- (2) All reasonable attempts at eliminating or reducing the nonconforming nature of the structure have been considered and are implemented in the restoration project.
- (e) Signs of Local Historic Significance. The City Council may approve and/or amend a list of existing nonconforming signs deemed to be of local historical significance by the Historic District Commission. Signs deemed historically significant may be repaired, reconstructed, or relocated, subject to review and approval by the Building Official.

Sec. 122-353. Acquisition of nonconformities. (209)

The City may acquire private property to remove a nonconformity, as provided in Act No. 207 of the Public Acts of Michigan of 1921 (MCL 125.581 et seq., MSA 5.2931 et seq.), as amended.

Sec. 122-354. Building or structure under construction on effective date of the ordinance from which this chapter is derived. (210)

Any building or structure must be considered existing and lawful for the purposes of this article if, on the effective date of the ordinance from which this chapter is derived, a building permit has been obtained therefore, if required; or if no building permit is required, a substantial start has been made toward construction and construction is thereafter pursued diligently to conclusion.

Sec. 122-355. Unlawful nonconformities. (211)

- (a) No nonconformity shall be permitted to continue in existence if it was unlawful at the time it was established.
- (b) The City shall maintain records of nonconforming uses and structures as accurate as is feasible for determining legal nonconforming uses and structures in existence on the effective date of the ordinance from which this chapter is derived. However, failure on the part of a property owner to provide the City with necessary information to determine legal nonconforming status may result in denial of a required or requested permit.

Secs. 122-356—122-359. Reserved.

Division 4: Amendments.

THIS SECTION UNCHANGED; JUST RENUMBERED. FORMERLY 122-61 THRU 66. (ADMIN>AMENDMENTS)

Sec. 122-360. General requirements. (61)

- (a) The City Council shall have authority to amend, supplement, or change zoning district boundaries or the provisions and regulations of this chapter, pursuant to the authority and procedures set forth in Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.), as amended.
- (b) Text amendments to this chapter may be initiated by a motion of the City Council or the Planning Commission, or by the filing of an application by any interested person or organization. Changes in district boundaries may be initiated by a motion of the City Council or the Planning Commission, or by the filing of an application by any person having a freehold interest in the subject property or by such person's designated agent.
- (c) The owner of land who has filed an application for changes in district boundaries may voluntarily offer with conditions relating to the use and/or development of land, either at the time the application is filed or may be made at a later time during the approval process. The City Council may establish a period of time during which the conditions apply to the land. No employee or official of the City of Ypsilanti shall require an owner to offer conditions as a requirement for rezoning. The lack of an offer of conditions shall not affect an owner's rights under this Ordinance.
- (d) All proposed amendments shall be referred to the Planning Commission for a public hearing, review and recommendation, before action may be taken thereon by the City Council.

Sec. 122-361. Amendment procedures. (62)

- (a) **Application.** Applications for amendments to this chapter shall be filed with the City Planner's office on an appropriate form provided by the City and accompanied by the required fee. No fee shall be required if a proposed amendment was initiated by the City Council or Planning Commission. All applications for amendments to this chapter shall, at a minimum, include the following:
 - (1) The applicant's name, address, and interest in the application; and the name, address, and interest of every person having a legal or equitable interest in any land which is to be rezoned. The application shall be signed by both the landowner and the applicant, if not the same.
 - (2) The nature and effect of the proposed amendment.
 - (3) If the proposed amendment would require a change in the Zoning Map, a boundary change and/or a change in building type allowed on a site designated on the Zoning Map, a fully dimensioned map showing the boundaries of land which would be affected by the proposed amendment, a legal description of the entire land area, a legal description of each subarea owned by a different person or organization, the present zoning of the land, the zoning of all adjacent lands, existing uses and structures on the subject property and adjacent properties, and all public and private rights-of-way and easements bounding or intersecting the land to be rezoned.
 - (4) If the proposed Zoning Map amendment includes voluntary conditions set forth by the owner of the property, a written statement of those voluntary conditions shall be included. The "Statement of Conditions" shall:
 - (i) Be in a form recordable with the Washtenaw County Register of Deeds or, in the alternative, be accompanied by a recordable Affidavit or Memorandum prepared and signed by the owner giving notice of the "Statement of Conditions" in a manner acceptable to the City Attorney.
 - (ii) Contain a legal description of the land to which it pertains.
 - (iii) Contain a statement acknowledging that the "Statement of Conditions" runs with the land and is binding upon successor owners of the land.
 - (iv) Incorporate by attachment or reference any site plan, diagram, or other documents submitted or approved by the owner that are necessary to illustrate the implementation of the "Statement of Conditions". If any such documents are incorporated by reference, the reference shall specify where the document may be examined.
 - (v) Contain a statement acknowledging that the "Statement of Conditions" or an Affidavit or Memorandum giving notice thereof may be recorded by the Township with the Washtenaw County Register of Deeds.
 - (vi) Contain the notarized signatures of all of the owners of the subject land preceded by a statement attesting to the fact that they voluntarily offer and consent to the provisions contained within the "Statement of Conditions".
 - (5) If the application is for an amendment to this chapter text, a description of the proposed change, with a detailed explanation as to why the proposed amendment is needed.

- (6) All other circumstances, factors, and reasons which the petitioner offers in support of the proposed amendment.

(b) **Public hearing.**

- (1) At least one public hearing on a proposed amendment shall be held by the Planning Commission. Notice of such public hearing shall be published at least once in a newspaper of general circulation in the City, not less than 15 days prior to the date set for the public hearing. The contents of the notice shall include the following.

(2) Time and place of the public hearing.

(3) A description of the proposed amendment.

(4) The street address and legal description of any property for which a zoning change is requested, the present zoning of that property, and the proposed new zoning designation. If 11 or more adjacent properties are proposed for rezoning, individual addresses and legal descriptions are not required.

(5) Not less than 15 days' notice of the public hearing shall be given by mail to each public utility company and railroad company owning or operating any public utility or railroad within the zoning district affected by the proposed amendment that registers its name and address with the City for the purpose of receiving such notice.

(6) If an individual property or up to 10 adjacent properties are proposed for rezoning, written notice of the public hearing shall be given the owner of the property in question, and to all owners of real property and occupants of structures within 300 feet of the property in question. The notice shall be mailed or delivered not less than 15 days before the public hearing.

(7) Any notices served by mail require an affidavit of mailing to be filed with the Planning Commission prior to the public hearing.

(c) **Planning Commission recommendation.** Following the public hearing, the Planning Commission shall prepare a report of its recommendations regarding the proposed amendment, and transmit such report to the City Council. The Planning Commission may recommend changes in the amendment in order to reflect objections raised at the hearing or to correct typographical or grammatical errors. The Planning Commission may reduce the area of land to be rezoned as described in the public hearing notice, but may not enlarge the area of land to be rezoned.

(d) **City Council action.** After the Planning Commission has held a public hearing and has made a written report to the City Council indicating their recommendation on the proposed amendment, the City Council may adopt the proposed amendment, decline to adopt the proposed amendment, or may adopt it in whole or part with or without additional changes. The City Council may also hold a public hearing on the proposed amendment or refer the proposed amendment back to the Planning Commission for further study and review or for additional public hearings. Upon the presentation of a protest petition meeting the requirements of section-4 403 of Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.) an amendment to this chapter or Zoning Map which is the object of such petition shall be passed by an affirmative vote of not less than two-thirds members of the City Council.

(e) **Publication.** Following adoption of an amendment to this chapter by the City Council, a notice of adoption shall be published in a newspaper of general circulation in the City within 15 days after adoption. The notice shall include the following information:

(1) Either a summary of the regulatory effect of the amendment including the geographic area affected, or the text of the amendment.

(2) The effective date of the amendment.

(3) The place and time where a copy of the amendment may be purchased or inspected.

Sec. 122-362. Standards for Amendments. (63)

(a) **Text Amendment.** For a change to the text of the Zoning Ordinance, the Planning Commission shall consider and the City Council may consider, whether the proposed amendment meets the following standards:

(1) The proposed amendment is consistent with the guiding values of the Master Plan; and

(2) The rezoning is consistent with description and purpose of the proposed district, and.

(3) The proposed amendment is consistent with the intent of this Zoning Ordinance; and

(4) The proposed amendment will enhance the functionality, transportation network or character of the future development in the City; and

(5) The proposed amendment will preserve the historic nature of the surrounding area and of the City; and

(6) The proposed amendment will enhance the natural features and environmental sustainability of the City; and

(7) The proposed amendment will protect the health, safety, and general welfare of the public; or

(8) The proposed amendment is needed to correct an error or omission in the original text; or

(9) The proposed amendment will address a community need in physical or economic conditions or

- development practices; and
- (10) The proposed amendment will not result in the creation of significant nonconformities in the City.
- (b) **Zoning Map Amendment.** For a change in the Zoning Map, the Planning Commission shall consider and the City Council may consider, whether the proposed rezoning meets the following standards:
- (1) The rezoning is consistent with the policies, guiding values and City Framework (Future Land Use Map) of the Master Plan, including any subarea or corridor studies. If conditions have changed since the current Master Plan was adopted, the consistency with recent development trends in the area.
 - (2) The rezoning sustains the site's physical, geological, hydrological and other environmental features with the potential uses allowed in the proposed zoning district.
 - (3) The property proposed to be re-zoned can accommodate the requirements of the proposed zoning district.
 - (4) All the potential uses and building types allowed in the proposed zoning district are compatible with surrounding uses, buildings, and zoning in terms of land suitability, impacts on the environment, impacts on the transportation network, density, nature of use, aesthetics, infrastructure and potential influence on property values.
 - (5) The capacity of City infrastructure and services sufficient to accommodate the uses permitted in the requested district without compromising the health, safety, sustainability and welfare of the City.
 - (6) The rezoning will not be detrimental to the financial stability and economic welfare of the City.
 - (7) The rezoning not would negatively impact the condition of any nearby parcels considering existing vacancy rates, current per-square-foot lease or sale rates, and other impacts.
 - (8) The rezoning is consistent with the trend of development in the neighborhood or surrounding area.
 - (9) The property in question was improperly zoned or classified when this Chapter was adopted or amended.
 - (10) Where a rezoning is reasonable given the above criteria, a determination shall be made that the requested zoning district is more appropriate than another district or than amending the list of permitted or special land uses within a district.
- (c) **Conditional Zoning Map Amendment.** For a change in the Zoning Map with voluntary conditions, the Planning Commission shall consider and the City Council may consider, whether the proposed rezoning and voluntary conditions meet the following conditions:
- (1) The voluntary conditions are first offered and heard at a public meeting.
 - (2) The rezoning and voluntary conditions are consistent with the policies, guiding values and City Framework (Future Land Use Map) of the Master Plan, including any subarea or corridor studies. If conditions have changed since the current Master Plan was adopted, the consistency with recent development trends in the area.
 - (3) The rezoning and voluntary conditions are consistent with the description and purpose of the district of the property.
 - (4) The rezoning and voluntary conditions sustains the site's physical, geological, hydrological and other environmental features with the potential uses allowed in the proposed zoning district.
 - (5) The property proposed to be re-zoned can accommodate the requirements of the proposed zoning district and voluntary conditions.
 - (6) All the potential uses and building types allowed in the proposed zoning district under the voluntary conditions are compatible with surrounding uses, buildings, and zoning in terms of land suitability, impacts on the environment, impacts on the transportation network, density, nature of use, aesthetics, infrastructure and potential influence on property values.
 - (7) The capacity of City infrastructure and services are sufficient to accommodate the uses permitted in the requested district under the voluntary conditions without compromising the health, safety, sustainability and welfare of the City.
 - (8) The rezoning and voluntary conditions will not be detrimental to the financial stability and economic welfare of the City.
 - (8) The rezoning and voluntary conditions will not negatively impact the condition of any nearby parcels considering existing vacancy rates, current per-square-foot lease or sale rates, and other impacts.
 - (9) The rezoning and voluntary conditions are consistent with the trend of development in the neighborhood or surrounding area.
 - (10) The voluntary conditions bear a reasonable and rational relationship to the property for which rezoning is requested.
 - (11) The voluntary conditions shall run with the land, and may only be removed or changed through another act of rezoning.
- (d) **Building Type Designation on Zoning Map.** For a change in building type designation on the Zoning Map, the Planning Commission shall consider and the City Council may consider, whether the proposed amendment meets the following conditions:
- (1) The building type change is consistent with the policies, guiding values and City Framework (Future Land

Use Map) of the Master Plan, including any subarea or corridor studies. If conditions have changed since the current Master Plan was adopted, the building type change is consistent with recent development trends in the area.

- (2) The building type sustains the site's physical, geological, hydrological and other environmental features with the potential uses allowed on the proposed property and surrounding property.
- (3) The building type change is consistent with the size, scale and character desired within the zoning district.
- (4) The property can accommodate the requirements of the proposed building type change.
- (5) The building type change is compatible with surrounding uses, buildings, and zoning in terms of land suitability, impacts on the environment, impacts on the transportation network, density, nature of use, aesthetics, infrastructure and potential influence on property values.
- (6) The capacity of City infrastructure and services sufficient to accommodate the building type change on the property in question without compromising the health, safety, sustainability and welfare of the City.
- (7) The building type change will not be detrimental to the financial stability and economic welfare of the City.
- (8) The building type change will not would negatively impact the condition of any nearby parcels considering existing vacancy rates, current per-square-foot lease or sale rates, and other impacts.
- (9) The building type change is consistent with the trend of development in the neighborhood or surrounding area.
- (10) The building type change on the property in question is consistent with the description and purpose of the district of the property.
- (11) In cases where requested building type is designed to accommodate commercial uses on the first floor in the Core Neighborhood, Core Neighborhood-Mid, or Core Neighborhood Single Family districts, the parcel must be located on a corner of two or more streets.

Sec. 122-363. Protests. (64)

- (a) In case a protest against a proposed rezoning is presented, duly signed by the owners, or part owners, of 20 percent of the area of land proposed to be altered, or by the owners of at least 20 percent of the area of land included with the area extending outward 100 feet from any point on the boundary of the land included in the proposed change, such amendment shall not be passed except by a two-thirds vote of the City Council. The protest petition shall be presented to the City Council before final City Council action on the amendment.
- (b) For purposes of the protest, publicly-owned land shall be excluded in calculating the 20 percent land area requirement.

Sec. 122-364. Conditional Zoning Map Amendment Administration. (65)

- (a) **Zoning Map.** Upon a conditional Zoning Map amendment taking effect, the Zoning Map shall be amended to reflect the new zoning classification along with a designation that the land was rezoned with a "Statement of Conditions". The Planning Department shall maintain a listing of all lands rezoned with a "Statement of Conditions".
- (b) **Statement of Conditions.** The approved "Statement of Conditions" shall be approved by the City Attorney and then filed by the City of Ypsilanti with the Washtenaw County Register of Deeds. If a time period for compliance with conditions has been required by City Council, the time period must be included in the document approved and filed with the Washtenaw County Registrar of Deeds. The City Council shall have authority to waive this requirement if it determines that, given the nature of the conditions and/or the time frame within which the conditions are to be satisfied, the recording of such a document would be of no material benefit to the City or to any subsequent owner of the land.
- (c) **Compliance with Conditions.** Upon a conditional Zoning Map amendment taking effect, the use of the land shall conform thereafter to all of the requirements regulating use and development within the new zoning district as modified by any more restrictive provisions contained in the "Statement of Conditions". Any person who establishes a development or commences a use upon land that has been rezoned with conditions shall continuously operate and maintain the development or use in compliance with all of the conditions set forth in the "Statement of Conditions". Any failure to comply with a condition contained within the "Statement of Conditions" shall constitute a violation of this Ordinance. Additionally, any such violation shall be deemed a nuisance per se and subject to judicial abatement as provided by law. No permit or approval shall be granted under this Ordinance for any use or development that is contrary to an applicable "Statement of Conditions".
- (d) **Time period for conditions.** If approved with a time period for conditions, the City of Ypsilanti shall not add or alter the conditions during that time period. The landowner may request an extension of the time period from the City Council. Except if an extension is granted, the land shall revert to its former zoning classification if conditions are not satisfied within the approved time period.

Sec. 122-365. Resubmitted amendments. (66)

2970 No petition for an amendment which has been disapproved by the City Council shall be resubmitted for a period of one year from the date of disapproval, except as may be permitted by the Planning Commission after new and significant facts or conditions have been offered which might result in favorable action upon resubmission.

Secs. 122-366 – 369. Reserved.

Division 5: Variances and Appeals.

RENUMBERED. formerly 122-94 thru 95. split from zba section.
(admin>zba)

Sec. 122-370. Variances. (94)

(a) **Application.** An application for a variance to the provisions of this chapter shall be filed with the City Planner's office by the record owner of the property in question or by a person authorized to act on the record owner's behalf. The application shall consist of a completed application form, fee, and the following information:

- (1) Name, address, and telephone number of the applicant and property owner; and the interest of the applicant in the property.
- (2) Legal description, address, and tax parcel number of the subject property.
- (3) An accurate, scaled drawing of the property, showing all property lines and dimensions correlated with the legal description; the location and dimensions of all existing and proposed structures and uses on the property; any roads, alleys, easements, drains, or waterways which traverse or abut the property; and the lot area and setback dimensions necessary to show compliance with the regulations of this chapter. In most cases, a site plan or sketch plan will meet this requirement.
- (4) Other reasonable information deemed necessary by the Zoning Board of Appeals in order to make a proper decision.

(b) **Standards for variances.** A variance from the literal enforcement of this chapter may be granted by the Zoning Board of Appeals only if all of the following standards are met:

- (1) Literal enforcement of this chapter will pose practical difficulties to the applicant because of special conditions or circumstances which are unique to the specific property such as: exceptional shallowness or shape of the property, exceptional topographic conditions, extraordinary situation of a building or structure, use or development of an adjacent property, or difficulties relating to construction or structural changes on the site. Mere inconvenience or a desire to attain higher financial return shall not itself be deemed sufficient to warrant a variance.
- (2) Such variance is necessary for the preservation and enjoyment of a substantial property right enjoyed by other property owners in the same district under the terms of this chapter. Granting of the variance shall not confer upon the applicant any special privilege that is denied by this chapter to other lands, structures, or buildings in the same district.
- (3) The alleged practical difficulties on which the variance request is based have not been created by any person presently having an interest in the property.
- (4) The granting of the variance will not be detrimental to the public welfare or injurious to other property or improvements in the neighborhood in which the property is located.
- (5) The allowance of the variance will result in substantial justice being done, considering the public benefits intended to be secured by this chapter, the individual hardships that will be suffered by a failure of the Zoning Board of Appeals to grant the variance, and the rights of others whose property would be affected by the allowance of the variance.
- (6) A variance granted shall be the minimum variance that will make possible a reasonable use of the land, buildings, or structure.

(c) **Variances; reapplication.** An application for a variance which has been denied wholly or in part by the Zoning Board of Appeals shall not be resubmitted for a period of one year from the date of denial, except on grounds of new evidence of changed conditions found by the Zoning Board of Appeals to be valid. The Zoning Board of Appeals shall review any subsequent application for a variance on the conditions and circumstances which exist at the time of the subsequent application.

(d) **Variance to run with land.** A variance shall run with the land and shall not become void if property is sold to a new owner. However, a variance shall become null and void if no building permit or no construction is started within one year of the approval date of the variance.

Sec. 122-371. Appeals. (95)

(a) **Questions first go to administrative official.** All questions concerning administrative decisions under this chapter shall first be presented to the applicable City official or agency. Such questions shall be presented to the Zoning Board of Appeals only on appeal from the decisions of the applicable City official or agency.

(b) **Filing appeal.** Appeals may be commenced by a person aggrieved by the decision of any officer, department, board, agency, or bureau of the City, county, state, or federal governments by filing a notice of appeal with the City Planner's office. The notice of appeal shall be signed, shall specify the requirement or decision from which the appeal is made, and shall state the specific grounds on which the appeal is based. The applicable fee shall be

submitted with the notice of appeal; such fee shall be nonrefundable. Appeals shall be filed within 60 days of the decision in question.

- 3030 (c) **Stay of action.** An appeal stays all proceedings in the furtherance of the action appealed from unless the Building Department certifies to the Zoning Board of Appeals after the notice is filed that, by reason of facts stated in the certificate, a stay would cause imminent peril to life or property. In such case, proceedings shall not be stayed other than by a restraining order which may be granted by the Zoning Board of Appeals or by circuit court, following written request, notice to the officer or body from whom the appeal is taken, and due cause shown.
- (d) **Power to subpoena.** The Zoning Board of Appeals shall have the power to subpoena witnesses; administer oaths; compel testimony; and require the production of reports, papers, files, and other evidence pertinent to the matters before it.
- 3040 (e) **Decisions regarding appeals.** The Zoning Board of Appeals may, so long as such action is in conformity with the terms of this chapter, reverse or affirm, wholly or partly, or may modify the order, requirement, decision, or determination from which an appeal is sought. To that end, the Zoning Board of Appeals shall have the powers of the public official or body from whom the appeal is taken.

Secs. 122-372 – 374. Reserved.

Division 6: Violations and Penalties.

RENUMBERED . FORMERLY 122-8 .
(GENERAL)

Sec. 122-375. Violations and Penalties. (8)

- 3050 (a) **Public nuisance.** Any building or structure which is erected, altered, converted, or used, or any use of premises or land which is begun or changed subsequent to the passage of this chapter and in violation of any of the provisions of this chapter is hereby declared to be a public nuisance per se, and may be abated by order of the City Council, subject to appeal to any court of competent jurisdiction.
- (b) **Blight Violation.** A person who violates any provision of this chapter is responsible for a blight violation, subject to payment of a civil fine and costs as set forth in section 71-73. Repeat offenses under this chapter shall be subject to increased fines and costs as set forth in section 71-73. A person who violates this chapter is also subject to enforcement by the procedures, costs, and penalties set forth in Section 1-15 of the Ypsilanti City Code for blight violations.
- 3060 (c) **Owner responsibility.** The owner of any building, structure or premises or part thereof, where any condition in violation of this chapter shall exist or shall be created, and who has assisted knowingly in the commission of such violation, shall be guilty of a separate offense and upon conviction thereof shall be liable for the fines provided in this chapter.
- (d) **Each day separate offense.** Each and every day during which a violation of this chapter shall exist shall constitute a separate offense.
- (e) **Rights and remedies are cumulative.** The rights and remedies provided in this chapter are cumulative and are in addition to any other remedies provided by law.
- (f) **Rights and remedies preserved, no waiver.** Any failure or omission to enforce the provisions of this chapter, and any failure or omission to prosecute any violations of this chapter, shall not constitute a waiver of any rights and remedies provided by this chapter or by law, and shall not constitute a waiver of nor prevent any further prosecution of violations of this chapter.
- 3070 (g) **Money received from penalties.** All money received from penalties assessed shall be placed in the City's general fund.

Secs. 122-376 – 122-379. Reserved.

Division 7: Authorities.

RENUMBERED. Originally 122-31 & 32

Sec. 122-380. Establishment of administrative officers. (31)

The provisions of this chapter shall be administered and enforced by the City Manager or by such person or persons, such as the City Planner or Building Inspector, that the City Manager may delegate to enforce the provisions of this chapter. All departments, officials and public employees of the City vested with the duty or authority to issue permits or licenses shall conform to the provisions of this chapter.

Sec. 122-381. Duties and enforcement powers. (32)

Typical duties and powers of the City Manager, or such person or persons the City Manager may delegate to act as Building Inspector, City Planner or other agents to enforce this chapter, shall include, but not be limited, to the following:

- (a) The Building Inspector, or such person or persons as the City Manager may delegate, shall have the power to:
 - (1) Make inspections of buildings and premises necessary to carry out the duties of enforcement of this chapter.
 - (2) Issue building permits.
 - (3) Issue certificates of occupancy.
 - (4c) Conduct surveillance and issue notices of violation pursuant to this chapter.
- (b) Adequate records of permits and applications issued, inspections, violations, nonconformities, variances, construction plans, fees collected, etc., shall be maintained. Public notices shall be published as necessary.
- (c) Persons who have zoning questions shall be assisted, and when applicable, such questions shall be brought before the Planning Commission or Zoning Board of Appeals.
- (d) Advice may be provided to the City Council, Planning Commission or Zoning Board of Appeals on petitions and applications that come before these bodies.
- (e) It shall be unlawful for the City Manager or their delegate to approve any permits or Certificates of Occupancy for any excavation or development proposal until such plans have been inspected in detail and found to conform with this chapter, or when applicable, site plan approval has been obtained.
- (f) Under no circumstances shall the City Manager or their delegate be permitted to make changes to this chapter nor vary the terms of this chapter in carrying out duties in administering and enforcing this chapter.
- (g) The City Manager or their delegate shall not refuse to issue a permit when the conditions imposed by this chapter are complied with by the applicant, despite violations of any contract such as covenants or private agreements which may occur upon granting of such permit.

Secs. 122-382 – 122-384. Reserved.

Subdivision I: Planning Commission.

ORIGINALLY 122-46 THRU 48; 50-54. 49 HAD BEEN RESERVED/BLANK. CHANGES MADE TO 53/246: SEE NOTES.

Sec. 122-385. Authority. (46)

3110 This ordinance is adopted pursuant to the authority granted the City Council under the Michigan Planning Enabling Act, Public Act 33 of 2008, MCL 125.3801 et seq., and the Michigan Zoning Enabling Act, Public Act 110 of 2006, MCL 125.3101 et seq., as amended, to establish a Planning Commission with the powers, duties and limitations provided by those Acts.

Sec. 122-386. Purpose. (47)

The purpose of this ordinance is for the City Council to confirm the establishment, under the Michigan Planning Enabling Act, Public Act 33 of 2008, MCL 125.3801 et seq., of the City Planning Commission, formerly established under the Municipal Planning Act, MCL 125.31 et seq., to establish the appointments, terms, and membership of the Planning Commission; to identify the officers and the minimum number of meetings per year of the Planning Commission; and to prescribe the authority, powers and duties of the Planning Commission as provided in and subject to the terms and conditions of this ordinance.

Sec. 122-387. Establishment. (48)

3120 There shall be a City Planning Commission in accordance with the Michigan Planning Enabling Act, Public Act 33 of 2008, as amended, with the powers and duties as therein set forth and as hereinafter provided.

Sec. 122-388. Zoning Board of Appeals member of the Planning Commission. (50)

As provided in the Michigan Zoning Enabling Act, MCL 125.3601, one member of the Planning Commission may be appointed by the City Council to serve on the Zoning Board of Appeals, with the term of that appointment to correspondence to that member's term as a Planning Commission member.

Sec. 122-389. Procedures of the Planning Commission. (51)

- 3130
- (a) The Planning Commission shall adopt bylaws for the transaction of business and shall keep a public record of its resolutions, transactions, findings, and determinations.
 - (b) The Planning Commission's procedures shall be in conformity with applicable ordinances, resolutions and policies adopted by the City Council.

Sec. 122-390. Meetings of the Planning Commission. (52)

- 3140
- (a) The Planning Commission shall hold not less than four (4) regular meetings each year. At its first meeting of the calendar year, the Planning Commission shall adopt and provide notice of its regular meetings for the ensuing year in accordance with the Open Meeting Act, Public Act 267 of 1976, as amended; provided, however, that a meeting need not be held if pending matters do not warrant a meeting.
 - (b) Special meetings may be called by the chairperson or upon written request to the secretary by at least two members of the Planning Commission. Unless the Planning Commission bylaws provide otherwise, the secretary shall send written notice of a special meeting to Planning Commission members not less than 48 hours before the meeting. All costs of special meetings held to consider requests of applicants for approvals under the zoning ordinance (or for such other purposes as may be necessary) shall be paid by the applicant for such requests.
 - (c) The business that the Planning Commission may perform shall be conducted at a public meeting held in compliance with the Open Meetings Act, Public Act 267 of 1976, as amended.

Sec. 122-391. Duties and responsibilities of the Planning Commission. (53)

The members of the Planning Commission shall have the following principal duties and responsibilities, among others:

- 3150
- (a) Prepare, consider, and approve a master plan as a guide for development within the City's planning jurisdiction. An update shall be considered no less frequently than every five (5) years; upon which consideration a determination shall be made as to the necessity of such a revision.
 - (b) Review and advise upon plans for capital improvements, such as construction, expansion, removal, or vacating of public lands, buildings, or right-of-ways. This review should focus on consistency with adopted plans of the City and other governmental units. This may be done by an annual review of the City's Capital Improvement Plan prior to adoption by City Council, rather than of each project individually.

- (c) Take such action on petitions, staff proposals, and City Council requests for amendments to the zoning ordinance as required.
- (d) Review subdivision and condominium proposals and recommend appropriate actions to the City Council, in accordance with the Land Division Act, Public Act 288 of 1967.
- (e) Prepare special studies and plans, as deemed necessary by the Planning Commission or City Council, for which appropriations of funds have been approved by the City Council, as needed.
- 3160 (f) Prepare an annual written report to the City Council concerning its operations and the status of planning activities, including recommendations regarding actions by the City Council related to planning and development, with the report to be presented within 90 days of the beginning of each calendar year.
- (g) Promote understanding of and interest in the master plan and the City zoning ordinance.
- (h) Carry out duties and responsibilities as required by and in accordance with the Michigan Zoning Enabling Act, Public Act 110 of 2006, as amended, and the Michigan Planning Enabling Act, Public Act 33 of 2008, as amended.

3170 ORIGINAL: (REVISED TO REMOVE DUPLICATES (MASTER PLAN, STATE ACTS); ADDED IN LAND DIVISION ACT)
Sec. 122-53. Duties and responsibilities of the Planning Commission.
The members of the Planning Commission shall have the following principal duties and responsibilities, among others:

- (a) Prepare, review and update a master plan as a guide for development within the city's planning jurisdiction.
- (b) Take such action on petitions, staff proposals and City Council requests for amendments to the zoning ordinance as required.
- (c) In accordance with the Michigan Planning Enabling Act, Public Act 33 of 2008, as amended, consider, no less frequently than every five (5) years, whether a revision of the master plan or updated amendments in the master plan are needed and prepare, consider and approve any such revisions or amendments.
- 3180 (d) Take such actions as are required by the Michigan Zoning Enabling Act, Public Act 110 of 2006, as amended, and the Michigan Planning Enabling Act, Public Act 33 of 2008, as amended.
- (e) Review subdivision and condominium proposals and recommend appropriate actions to the City Council.
- (f) Prepare special studies and plans, as deemed necessary by the Planning Commission or City Council for which appropriations of funds have been approved by the City Council, as needed.
- (g) Prepare an annual written report to the City Council concerning its operations and the status of planning activities, including recommendations regarding actions by the City Council related to planning and development, with the report to be presented within 90 days of the beginning of each calendar year.
- 3190 (h) Promote understanding of and interest in the master plan and the city zoning ordinance.
- (i) The Commission shall review and advise upon plans for capital improvements, such as construction, expansion, removal, or vacating of public lands, buildings, or right-of-ways. This review should focus on consistency with adopted plans of the City and other governmental units. This may be done by an annual review of the City's Capital Improvement Plan prior to adoption by City Council, rather than of each project individually.
- (i) Carry out other duties and responsibilities as set forth in the Michigan Planning Enabling Act, Public Act 33 of 2008.

Sec. 122-392. Approval, ratification and reconfirmation. (54)

3200 All official actions taken by the City Planning Commission preceding the Planning Commission established by this ordinance are hereby approved, ratified, and reconfirmed. Any project, review, or process taking place at the effective date of this ordinance shall continue with the Planning Commission created by this ordinance, subject to other requirements of this ordinance, and shall be deemed a continuation of any previous City Planning Commission. This ordinance shall be in full force and effect from and after its adoption and publication.

Secs. 122-393 – 122-394. Reserved.

Subdivision II: Zoning Board of Appeals.

ORIGINALLY 122-91 THRU 93, 96-98. (94= VARIANCES, 95 APPEALS.)

Sec. 122-395. Establishment and membership. (91)

- 3210 (a) **Established.** There is hereby established a Zoning Board of Appeals, which shall perform its duties and powers in accordance with Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.), as amended, and in such a way that the objectives of this chapter shall be observed, public safety secured, and substantial justice done.
- (b) **Membership.** The Zoning Board of Appeals shall consist of five members appointed by the Mayor with the City Council's consent. The members of the Zoning Board of Appeals shall be residents of the City. No employee or contractor of the City Council may sit on the Zoning Board of Appeals. One member of the Zoning Board of Appeals shall also sit on the City Planning Commission. Each member of the Zoning Board of Appeals shall hold office for a term of three years. Terms shall be staggered to provide for as nearly as possible the appointment of an equal number of members each year. Those persons now serving as members of the Zoning Board of Appeals shall serve the balance of the terms for which they were appointed. All vacancies for unexpired terms shall be filled for the remainder of the term.
- 3220 (c) **Officers.** The Zoning Board of Appeals shall annually elect its own chairperson and vice-chairperson. The terms of the chairperson and vice-chairperson shall be for a period of one year.
- (d) **Alternate members.** The mayor, with the City Council's consent, shall appoint two alternate members for the Zoning Board of Appeals to sit as regular members of the Zoning Board of Appeals in the absence of a regular member. If a regular member is absent from or unable to attend one or more consecutive meetings of the Zoning Board of Appeals or for a period of more than 30 consecutive days, then alternate members may be called on a rotating basis to serve in the place of a regular member. For the purpose of reaching a decision on a case in which the regular member has abstained for reasons of conflict of interest, an alternate member may also be called. The alternate member having been appointed shall serve in the case until a final decision has been made. The alternate member shall have the same voting rights as a regular member of the Zoning Board of Appeals.
- 3230 (e) **Meetings.** All meetings of the Zoning Board of Appeals shall be held at the call of the chairperson and at such times as the Zoning Board of Appeals may determine. All hearings conducted by the Zoning Board of Appeals shall be open to the public. Minutes shall be kept of each meeting and the Zoning Board of Appeals shall record into the minutes all findings, conditions of approval, facts, and other relevant factors, and all its official actions. The vote of each member upon a question, or absence or abstention, shall be recorded into the minutes of the meeting.
- (f) **Rules and procedures.** The Zoning Board of Appeals shall adopt general rules and regulations governing its procedure and may make rules for the filing of appeals and other matters requiring its attention which shall not cause reasonable delays in the transaction of its business.
- 3240 (g) **Abstention.** A member of the Zoning Board of Appeals shall abstain from voting on any question on which they have a conflict of interest. Failure of a member to abstain in such cases shall constitute misconduct of office.
- (h) **Resignations.** When Zoning Board of Appeals members propose to resign, if reasonably feasible, they shall give notice of their intent in writing to the chairperson, and make the date of resignation effective in such a manner as to allow time for appointment of replacements. Failure to attend three consecutive regular meetings, or three of seven consecutive meetings, without recorded consent of the chairperson shall be construed as resignation from the Zoning Board of Appeals by absence. When a member dies or resigns (including resignation by absence), the chairperson shall promptly notify the mayor that a vacancy exists.

Sec. 122-396. Powers and duties. (92)

- 3250 (a) The board of appeals shall hear and decide all questions and decisions regarding the following:
- (1) Interpretation of the official Zoning Map, including the interpretation of the location of zoning district boundaries when in doubt.
 - (2) The interpretation of the language of this chapter when its meaning is unclear, or when there is uncertainty as to whether the language applies to a particular situation.
 - (3) The hearing of requests for nonuse variances from the strict application of the provisions of this chapter in accordance with [§122-370](#).
 - (4) The hearing of requests for appeals from any order, requirement, decisions, or determination made by an administrative body or official charged with the enforcement of this chapter in accordance with [§122-371](#).
 - (5) Hear and decide on any other matters referred to the Zoning Board of Appeals or upon which the Zoning Board of Appeals is required to pass under the terms of this chapter.

- 3260 (b) The Zoning Board of Appeals shall not change the zoning district classification of any property or make any change in the terms of this chapter, and shall not take any action which would, as a result, make legislative changes in or negate any provisions of this chapter.
- (c) The Zoning Board of Appeals shall not have authority to hear appeals on decisions made by the Planning Commission or City Council regarding planned unit developments.
- (d) The Zoning Board of Appeals shall not have the authority to grant a use variance.

Sec. 122-397. General procedures. (93)

- 3270 (a) **Hearings.** The Zoning Board of Appeals shall hold a public hearing on each question submitted to it for decision. Such hearing shall be set within a reasonable time, not to exceed 45 days from the filing date of an appeal or variance request. Written notice of such hearing including the date, time, and place of the public hearing; the nature of the appeal; and a description of any property in question; shall be given to the appellant, if different than owner(s) of the property, to persons to whom real property is assessed within 300 feet of the boundary of the property subject to the request, regardless of whether the property or occupant is located within the boundaries of the City of Ypsilanti, and to the occupants of all structures within 300 feet of the premises. The notice shall be delivered personally or by mail, addressed to the respective owners and tenants at the address given in the last assessment roll. If a tenant's name is not known, the term "occupant" may be used. Notification need not be given to more than one (1) occupant of a structure, except that if a structure contains more than one (1) dwelling unit or spatial area owned or leased by different individuals, partnerships, businesses, or organizations, one (1) occupant of each unit or spatial area shall receive notice. In the case of a single structure containing more than four (4) dwelling units or other distinct spatial areas owned or leased by different individuals, partnerships, businesses or organizations, notice may be given to the manager or owner of the structure who shall be requested to post the notice at the primary entrance to the structure. The notice shall also be published in a newspaper of general circulation in the City. All notices shall be given at least 15 days prior to the public hearing. An affidavit of mailing shall be filed with the Zoning Board of Appeals prior to the public hearing. The Zoning Board of Appeals may recess a hearing to gather additional information, to make site inspections, or to engage in other activities as may be necessary to make a proper decision. The Zoning Board of Appeals shall reconvene the hearing within 35 days of the original hearing date. The reconvened hearing date shall be announced at the original hearing and this announcement shall constitute proper public notification.
- 3280 (b) **Decisions by the Board of Appeals.** The concurring vote of a majority of the entire membership of the Zoning Board of Appeals (three votes) shall be necessary to reverse any order, requirement, or decision of any administrative official; to effect any variance in the non-use terms of this chapter; or to decide any matter upon which the Zoning Board of Appeals is required to pass by this chapter.
- 3290

REMOVED: (no more use variances 12/14/2016)

The concurring vote of two-thirds of the entire membership of the Zoning Board of Appeals (four votes) shall be necessary to effect any variance from uses of the land permitted in this chapter.

- (c) **Time limit.** The Zoning Board of Appeals shall decide upon all matters within 90 days from the filing date. The time limit may be extended by written agreement between the applicant or appellant and the Zoning Board of Appeals.
- 3300 (d) **Representation.** Any person may appear on their own behalf at a hearing or may be represented by an agent or attorney.
- (e) **Conditions of approval.** The Zoning Board of Appeals may attach conditions to any affirmative action as it deems reasonable to minimize any detrimental effects of its decisions and to promote the purposes of this chapter. Such conditions shall be in accordance with [§122-326](#) and Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.), as amended. A performance guarantee may be required as a condition of an affirmative action when in accordance with [§122-317](#).
- 3310 (f) **Official record.** The decisions and orders of the Zoning Board of Appeals in disposing of an appeal or a request for a variance, along with any conditions attached, shall be entered into the official record for each case. Such record shall include the reasons for a determination, a summary of the evidence introduced, and the reasons for any conditions imposed.

Sec. 122-398. Decisions final. (96)

All decisions of the Zoning Board of Appeals are final. However, a person having an interest aggrieved by a decision may appeal to the circuit courts, as provided in Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.), as amended. Such an appeal must be filed within 30 days after the Zoning Board of Appeals certifies its decision in writing or approves the minutes of its decision.

Sec. 122-399. Time limitations. (97)

If a variance or other requested action is granted or authorized, the necessary permits shall be obtained and any authorized actions shall be begun within one year following the date of such variance or authorization and shall be completed as authorized by the permit or elsewhere in this chapter. Should the applicant/appellant fail to obtain such permits or fail to commence work within such subsequent period, it shall be presumed that the applicant/appellant has waived, withdrawn, or abandoned their appeal; and all permissions, authorizations, variances, and permits shall be deemed to be rescinded.

REMOVED: now only one fees section in 303.

Sec. 122-445. Fees. (98)

The City Council may prescribe and amend by resolution a reasonable schedule of fees to be charged to applicants for appeals or variances requested from Zoning Board of Appeals. Fees shall be paid at the time of application and shall be nonrefundable. Fees shall be placed in the general revenue fund of the City.

Article IV: Districts

Division 1: Generally

ORIGINAL: 231-238

Sec. 122-400. Establishment of Districts. (231)

Ypsilanti's Master Plan classifies the City into neighborhoods, corridors, centers, and special districts. These classifications are the basis for the regulation of these areas.

For the purposes of this chapter, the City is hereby divided into the following zoning districts having the names and symbols here shown:

Use-Based Districts

- P, Parks
- R1, Single-family residential district
- MD, Multiple dwelling residential district
- PMD, Production, Manufacturing and Distribution

Walkable Urban Districts

ORIGINAL: "walkable urban areas". This makes it easier (more specific) to call out in the code. Many times in the code where the list of these districts has been spelled out, or the previous phrase used, it has been replaced with this phrase.

- CN-SF, Core Neighborhood Single Family
- CN-Mid, Core Neighborhood Mid
- CN, Core Neighborhood
- C, Center
- HC, Historic Corridor
- NC, Neighborhood Corridor
- GC, General Corridor
- HHS, Health and Human Services

Sec. 122-401. Zoning Map. (232)

- (a) The locations and boundaries of the zoning districts are hereby established as shown on a map adopted by the City Council. The map is entitled the "Zoning Map, City of Ypsilanti, Washtenaw County, Michigan," and must bear the date adopted or amended. It is the duty of the City mayor and clerk to authenticate such records by placing their official signatures thereon. Such map with all accompanying explanatory matter is hereby made a part of this chapter as if the matters and information set forth thereon were all fully described in this chapter.
- (b) In the Walkable Urban Districts the Zoning Map contains notations on property where building types noted in §122-465 are allowed in certain areas and required street construction or connections.
- (c) A copy of the Zoning Map shall be available for sale or distribution to the public. The Zoning Map shall be updated regularly.

Sec. 122-402. Application of chapter. (233)

- (a) Land uses are permitted specifically in the various zoning districts of this chapter. Where not specifically permitted, uses are thereby specifically prohibited unless construed to be similar to a use expressly permitted.
- (b) Except as otherwise provided in this chapter, erection of buildings and uses of land must conform to the specific provisions for the zoning districts involved. No land shall be redeveloped or a use commenced, expanded or continued within the City except as specifically, or by necessary implication, authorized by this chapter.
- (c) Lawful nonconforming structures and uses existing at the time of passage of this chapter are specifically governed by Article III, Division 3 "Nonconformities," and generally governed by this chapter.

Sec. 122-403. Interpretation of district boundaries. (234)

Where uncertainty exists with respect to the boundaries of the various districts as shown on the Zoning Map, the following rules apply:

- (a) Boundaries indicated as approximately following lot lines, the centerlines of streets or alleys, and City limits

must be construed as following such lines.

- (b) Boundaries indicated as parallel to or extension of features indicated in subsection (a) of this section shall be so construed. Distances not specifically indicated on the official Zoning Map are determined by the scale of the map.
- (c) Where physical or natural features existing on the ground are at variance with those shown on the Zoning Map, or in other circumstances not covered above, the Zoning Board of Appeals must interpret the district boundaries.
- (d) Where one parcel is divided into two or more portions by reason of different zoning district classifications, each of these portions must be used independently of the others in respective zoning classifications; and for the purposes of applying the regulations of this chapter, each such portion must be considered as if in separate and different ownership. However, if the Zoning Board of Appeals finds that any portion of a lot so divided is inadequate in area for a viable use, such portion may be combined with an adjacent lot and/or rezoned as appropriate.

Sec. 122-404. Uses permitted as a right. (235)

Permitted uses, as identified in the divisions covering each district, are recognized as uses of land and buildings in certain districts which are harmonious with other such uses which may lawfully exist within the same district. A permitted use is subject to the general provisions, parking regulations, district intent, permit, certificate and site plan requirements found elsewhere in this chapter, but otherwise is considered to be a lawful use not requiring special or extraordinary controls or conditions, unless otherwise indicated in this chapter.

Sec. 122-405. Uses permitted under special approval. (236)

The uses identified as special uses in divisions covering each district are recognized as possessing characteristics of such unique and special nature (relative to location, off-site impacts, design, size, public service and utility needs, and other similar characteristics) as necessitating individual standards and conditions in order to safeguard the general health, safety and welfare of the community. **Article III, Division 2 "Permits," Subdivision II "Special Land Uses,"** regarding procedure and requirements for special uses, applies to these uses.

Sec. 122-406. Zoning of vacated land. (237)

Vacated streets or alleys, or the divided portions thereof, are automatically given the same zoning classification as the private property to which they are attached upon vacation.

Sec. 122-407. Zoning of annexed land. (238)

Property duly annexed to the City will be zoned R1, single-family residential, upon annexation. However, the City Council may, in the annexation ordinance, designate an appropriate zoning designation upon annexation, based upon existing use of the property, the City's adopted master plan, or the use of surrounding properties.

Secs. 122-408 – 409. Reserved.

Division 2: Use Based Districts

"purpose" drawn from 122-231 in previous code.
--

Sec. 122-410. Purpose. (split from 231)

3420

Outlying neighborhoods (outlying residential and multiple-family) and special districts (parks and production, manufacturing, and distribution) are areas where regulation by use and intensity is appropriate. These districts were primarily constructed after the Second World War, were developed with the automobile in mind as much as the individual, and generally were developed well after the advent of zoning regulations. These neighborhoods tend to be less dense and have stronger separation between commercial, residential, and industrial uses than do areas developed prior to the 1940s. The regulations set forth herein continue the separation of uses where prudent, enable the continuing integration of the automobile into daily life while maintaining transportation choices, reinforce connections between these and other neighborhoods, and respect the history of the neighborhoods.

Secs. 122-411 – 414. Reserved.

Subdivision I: Park District (P)

ORIGINAL: 301-303

3430 Sec. 122-415. Purpose. (301)

The Park (P) district is designed to preserve green space for recreation and for preservation of natural resources. Temporary uses may be allowed to encourage use and vitality of these areas.

ORIGINAL: (wordy.)

The P Park district is designed to preserve publicly and privately owned green space, including parks and cemeteries. When embedded in R-1, CN-SF, CN-Mid, CN, MD and HHS districts, the district is intended to provide the essential green space for urban neighborhoods. When on the outskirts of the city, the district maintains large green spaces, such as cemeteries. Along the Huron River, the district provides recreation as well as environmental protections. Temporary uses may be allowed to encourage use and vitality of these areas.

3440 Sec. 122-416. Permissible Uses. (302)

In the Parks district, no uses shall be permitted except the following.

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES		NOTES	SPECIFIC REGULATIONS
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES			
Park	P		
Outdoor and indoor education areas	P		
Outdoor recreation areas such as swimming pools, tennis courts, and performance venues	P		
Conservation areas, wildlife preserves, forests preserves, arboreta, botanical or zoological gardens, public tree or plant nurseries	P		
Privately owned or operated uses accessory to City parks	S	Includes but not limited to concession stands, canoe liveries, or bicycle liveries.	
INFRASTRUCTURE			
Essential Services	P		Section 122-523
Solar Farms	S		Section 122-513
Alternative Energy	A		Section 122-513
SERVICES			
Cemetery	P		
Crematory	S		All principal buildings must be set back at least 75 feet from all property lines.
TEMPORARY USES			
Mobile food establishments	P		Section 122-335
URBAN AGRICULTURE			
Community Gardens	P		Section 122-525
Passive solar building	P		

Sec. 122-417. Non-Use and Dimensional Regulations. (303)**(a) Minimum Lot Width**

Determined by the use and the required off-street parking, loading, screening, and yard setbacks.

(b) Minimum Lot Size

Determined by the use and the required off-street parking, loading, screening, and yard setbacks.

(c) Minimum Setbacks for Principal Structures and Attached Accessory Structures

Front yard	25 feet	Minimum setbacks increase by one foot for each foot a building or structure exceeds 30 feet in height.
Side yard	15 feet	
Street Side yard	25 feet	
Rear yard	20 feet	

(d) Height

Maximum height	Equal to that of adjacent zoning district or building type along the property line. If different heights abut, the largest setback is required.	Subject to §122-613 .
----------------	---	---------------------------------------

(e) Parking Setbacks

Front & street side yard	10 feet
Side & rear yards	10 feet

(f) Fences

Front Yard	No more than 4' in height and 50% opacity	• Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. • Subject to §122-635 • Subject to §122-675
Side, Street Side, and Rear Yards	No more than 6' in height, no opacity restriction	

(g) Signs

Freestanding Signs (temporary)	Maximum area	10 sf	Permit not required.
	Maximum height	3 feet	
	All setbacks:	0 feet Subject to §122-675	
Freestanding Signs (permanent)	Maximum area	100 sf	Permit required.
	Maximum height	35 feet	
	Front setback	3 feet Subject to §122-675	
	Side, street side, and rear setback	10 feet Subject to §122-675	
	Maximum # signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	

Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Billboards	Location	adjacent to and visible from I-94, as defined by the Highway Advertising Act of 1972.	Permit required.
	Maximum Area	672 sf	
	Maximum Height	65'	
	Other restrictions	Subject to §122-675	

(h) Other Accessory Structures

Subject to Article VI, Division 4, "Accessory Structures, Porches, and Decks"

Secs. 122-418 – 419. Reserved.

Subdivision II. Single-Family Residential District (R1)

ORIGINAL: 251-253

Sec. 122-420. Purpose. (251)

The Single-Family Residential (R1) district is designed to provide an environment of predominantly low-density, single-family detached dwellings, along with related facilities such as schools and religious institutions.

ORIGINAL: (wordy.)

The R1 single-family district is designed to provide an environment of predominantly low-density, single-family detached dwellings, along with other related facilities such as schools and religious institutions. The purpose of the R1 single-family district to encourage the preservation and the continuation of the long-standing residential fabric in existing neighborhoods of predominantly single-family dwellings. Multiple-family, business, or industrial uses which would substantially interfere with the development or continuation of single-family dwellings in the district are prohibited.

Sec. 122-421. Permissible Uses. (252)

In the Single-Family Residential (R1) district, no uses shall be permitted except the following.

NOTE:

added a flag statement to schools- "public schools are only subject to state regulations regarding location and construction." Courts have ruled repeatedly and consistently that local gov't (zoning and building particularly) has no jurisdiction over public schools (including charters).

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	R1	NOTES	SPECIFIC REGULATIONS
RESIDENTIAL			
Single-Family Detached Dwelling	P	Manufactured and premanufactured dwellings may be located and installed according to same standards that would apply to a site-built single-family dwelling on the same lot.	
Home Occupation	A		Section 122-527
Family Child Care Home	A	1-6 children	Must be licensed by the state and must comply with the minimum state standards for such facilities.
Group Child Care Home	S	6-12 children	Section 122-521
Adult foster care family homes	A	1-6 adults, excludes facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities.	Must be licensed by the state and must comply with the minimum state standards for such facilities.
RECREATION, EDUCATION & PUBLIC ASSEMBLY			
Park	P		
Primary & Secondary Schools (public & private), less than 15,000 square foot footprint	S	Public schools are only subject to State regulations regarding location and construction.	Section 122-545
Post-secondary educational institutions (public & private), less than 15,000 square foot footprint	S	Public schools are only subject to State regulations regarding location and construction.	Section 122-545
Religious institution, less than 15,000 square foot footprint	S		Section 122-543
Municipal, county, regional & state service uses	S		Section 122-535

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	R1	NOTES	SPECIFIC REGULATIONS
SERVICES			
Bed & Breakfast or Inn	S		Section 122-520
Farmers' Market	A		When accessory to a nonresidential use. Temporary use only.
Garage Sales	A		Section 122-524
INFRASTRUCTURE			
Essential Services	P		Section 122-523
Communication Devices	A		Article V, Division 3
Alternative Energy	A		Section 122-513
GARDENS/COMMUNITY GARDENS			
Community Gardens	P		Exempt from area regulations in §122-422 . Subject to §122-525
Toolhouses, sheds, garages, and other similar buildings for the storage of domestic supplies	A		Must meet accessory structure regulations for lot coverage and maximum floor area. Rear or side yard only.
Passive solar building	A		Must meet accessory structure regulations for lot coverage. Rear or side yard only. Must meet regulations in §122-422 , with an exception for an up to 200 sq ft passive solar building if floor area of existing detached accessory structures are less than 200 sq ft or equal to the gross floor area of the ground floor of the principal structure. Maximum square footage is 800 sq ft.

Sec. 122-422. Non-Use and Dimensional Regulations. (253)**NOTES:**

In the front yard average setback section, changed so that the existing max & min now establish a range for the front yard setback, rather than an average creating a minimum. Better maintain existing neighborhood character.

(a) OVERALL SITE REGULATIONS**(1) Maximum Lot Coverage**

Residential Uses	35%
Non-residential Uses	50%

(2) Parking Setbacks *(non-residential uses only; residential uses covered by §122-682)*

Front & side street yard	Not allowed
Side and rear yards	10 feet

(3) Minimum Lot Width

Lot width	45 ft.
-----------	--------

(4) Outdoor Lighting

See §122-609

(b) PRINCIPAL AND ATTACHED ACCESSORY STRUCTURES*Also subject to Article VI, Division 4***(1) Height**

Maximum height	30 feet or 2.5 stories	See exceptions in §122-613
----------------	------------------------	----------------------------

(2) Residential Uses

Lot size, minimum	5,000 square feet	
Front yard setback, minimum	25 feet	Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.
Side yard setback, minimum	4 feet	
Side yards (combined) setback, minimum	12 feet	
Street Side yard setback, minimum	8 feet	
Rear yard setback, minimum	25 feet	
Corner Lots	Platted or of record after August 8, 1984	Front yard regulations apply to each street side of the corner lot. The rear yard requirements for a corner lot apply to the open space which is opposite and most distant from the front lot line as designated in the plat and/or in the request for a building permit.
	Platted or of record prior to August 8, 1984	Front yard regulations apply only along the front lot line as designated in the plat and/or in the request for a building permit. The yard along the second street must meet the requirements for side yards on corner lots as specified in the district regulations.
Usable floor area, minimum	500 sf	

(3) Non-residential uses

(b) PRINCIPAL AND ATTACHED ACCESSORY STRUCTURES*Also subject to Article VI, Division 4*

Front yard minimum	25 feet	Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.
Side yard minimum	8 feet	
Side yards (combined) minimum	Equal to the height of the structure or the setbacks required for residential uses, whichever is greater.	
Street side yard minimum	8 feet	
Rear yard minimum	25 feet	
Corner Lots	Platted or of record after August 8, 1984	Front yard regulations apply to each street side of the corner lot. The rear yard requirements for a corner lot apply to the open space which is opposite and most distant from the front lot line as designated in the plat and/or in the request for a building permit.
	Platted or of record prior to August 8, 1984	Front yard regulations apply only along the front lot line as designated in the plat and/or in the request for a building permit. The yard along the second street must meet the requirements for side yards on corner lots as specified in the district regulations.

(c) DETACHED ACCESSORY STRUCTURES

Also subject to Article VI, Division 4

(1) Height

Maximum height	15 feet
----------------	---------

(2) Size of Accessory Buildings

Maximum Floor Area	The gross ground floor area of all accessory buildings must not exceed gross floor area of the ground floor of the principal structure, nor cause lot coverage regulations for all buildings and paved surfaces on-site to be exceeded.
--------------------	---

(3) Fences

Front Yard	No more than 4' height and 50% opacity	• Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. • Subject to §122-635 • Subject to §122-675
Side, Street Side, and Rear Yards	6' height max, no opacity restriction	

(4) Buildings Accessory to Residential Uses

Front yard	Not allowed	
Side yard minimum	3 feet	1 foot if lot line abuts an alley
Street Side yard	Not allowed	
Rear yard minimum	3 feet	1 foot if lot line abuts an alley, 12 feet for a through lot
Distance from principal structure, minimum	7 feet	Minimum distance to comply with fire regulations and/or building code, if greater than minimum listed. An attached enclosure or roof over a pathway between buildings on a lot, such as a breezeway, is exempt from this setback provided it is 8 feet or less in width and 15 feet or less in height.

(5) Buildings Accessory to Non-residential uses

Front yard	Not allowed	
Side yard minimum	3 feet	1 foot if lot line abuts an alley
Street Side yard minimum	8 feet	
Rear yard minimum	3 feet	1 foot if lot line abuts an alley, 12 feet for a through lot
Distance from principal structure minimum	5 feet or minimum to comply with fire regulations and building code, whichever greater.	

(d) SIGNS*Also subject to Article VI, Div 5***(1) Signs – Residential Uses**

(i) Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit not required.
	Maximum height	3 feet	
	All setbacks	0 feet Subject to §122-675	
(ii) Freestanding signs (permanent)	Not permitted		
(iii) Building-mounted signs (temporary)	Maximum area	0.5 square feet for each linear foot of building frontage or 12 square feet, whichever less	Permit not required.
(iv) Building-mounted signs (permanent)	Maximum area	1 sq ft	Permit not required.
(v) Billboards	Not permitted		

(2) Signs – Non-residential Uses

(i) Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit not required.
	Maximum height	3 feet	
	All setbacks	0 feet Subject to §122-675	
(ii) Freestanding signs (permanent)	Maximum Area	16 sf	Permit required.
	Maximum Height	6 feet	
	Front Setback	3 feet Subject to §122-675	
	Side, street side, and rear setback	10 feet Subject to §122-675	
	Maximum number of signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	
(iii) Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever less	Permit required.
(iv) Building-mounted signs (permanent)	Maximum Area	0.5 square feet for each linear foot of building frontage, or 12 square feet, whichever less	Permit required.
(v) Billboards	Not permitted		

Secs. 122-423 – 424. Reserved.

Subdivision III: Multiple Dwelling Residential District (MD)

3480

ORIGINALLY 261-263

Sec. 122-425. Purpose. (261)

The multiple-family residential district is located adjacent to high traffic generators and major thoroughfares and corridors, and can serve as zones of transition between nonresidential districts and neighborhoods. It is designed to allow a multiple-family residential development, rental or owner-occupied, designed specifically for apartments, townhouses, and/or other housing types. It is further designed to insure sound development policies for areas having a concentration of multifamily units, while assuring an adequate supply of multiple-family living units in the housing mix of the City overall. Recreation, service, and retail uses are permissible as special land uses to allow residents to access everyday needs by foot, if they are not already within a quarter-mile walking distance.

Sec. 122-426. Permissible Uses. (262)

3490

In the Multiple Dwelling (MD) district, no uses shall be permitted except the following.

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	MD	NOTES	SPECIFIC REGULATIONS
RESIDENTIAL			
Group Residences	S		Single-family building type only.
Townhomes/rowhomes	P		
Two-Family Dwelling	P		
Multiple Family Dwellings, maximum of 6 units per building	P		Responsible party for management must be on file with the City.
Multiple Family Dwellings, more than 6 units per building	S		Responsible party for management must be on file with the City.
Home Occupation	A		Section 122-527
Family Child Care Home	A	1-6 children	Must be licensed by the state and must comply with the minimum state standards for such facilities.
Group Child Care Home	S	6-12 children	Section 122-521
Group living with support staff, not licensed by State of Michigan	S	Includes supportive housing, rehabilitation housing, or dormitories.	
Adult foster care family homes	A	1-6 adults, day care and 24 hour care, excludes facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities.	Must be licensed by the state and must comply with the minimum state standards for such facilities.
Adult foster care small & group homes, adult congregate facilities	S	7 or more adults, licensed by State of Michigan	Section 122-511
Adult foster care facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities.	S		
RECREATION, EDUCATION & PUBLIC ASSEMBLY			
Park	P		
Indoor recreation	A		Section 122-529

USES	MD	NOTES	SPECIFIC REGULATIONS
Social facility for multiple dwelling residents and their guests	A		
Primary & Secondary Schools (public & private)	S	Public schools are subject to State regulations regarding location and construction.	Section 122-545
Post-secondary educational institutions (public & private)	S	Public schools are subject to State regulations regarding location and construction.	Section 122-545
Religious institution	S		Section 122-543
Municipal, county, regional & state service uses	S		Section 122-535
SERVICES			
Bed & Breakfast or Inn	S		Section 122-520
Child care centers and day care centers	S		Section 122-521
Nursing homes	S		Section 122-536
Medical or Dental Clinics, less than 5,000 square feet	S		
Financial services, including banks	S		Drive through facilities are not allowed in MD
Personal service establishments	A		
COMMERCIAL			
Food stores, excluding sale of alcohol, less than 15,000 square feet	S		
Farmers' Market	A		
Garage Sales	A		Section 122-524
RESTAURANTS			
Carry-out and/or delivery restaurant	S		Drive through facilities are not allowed in MD
Café or coffee shop	S		Drive through facilities are not allowed in MD
INFRASTRUCTURE			
Essential Services	P		Section 122-523
Communication Devices	A		Article V, Division 3
Alternative Energy	A		Section 122-513
Automobile Share Parking	A		
GARDENS/COMMUNITY GARDENS			
Community Gardens	P		Exempt from area regulations in §122-427 , subject to §122-525
Toolhouses, sheds and other similar buildings for the storage of domestic supplies	A		- Must meet accessory structure regulations for lot coverage and maximum floor area. - Rear or side yard only.

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	MD	NOTES	SPECIFIC REGULATIONS
Passive solar building	A		• Must meet accessory structure regulations for lot coverage and maximum floor area. • Rear or side yard only. • Maximum square footage is 800 square feet.

Sec. 122-427. Non-Use and Dimensional Regulations. (263)**(a) OVERALL SITE REGULATIONS***Also subject to Article VI***(1) Maximum Impervious Surface Lot Coverage**

Residential Uses	45%
Non-residential Uses	50%

(2) Parking Location and Setbacks

Front & side street yard	Not permitted.
Side and rear yards	10 feet

(3) Minimum Lot Width

Lot width for all buildings	45 ft.
-----------------------------	--------

(4) Outdoor LightingSee [Section 122-609](#)**(b) PRINCIPAL AND ATTACHED ACCESSORY STRUCTURES***Also subject to Article VI, Division 4***(1) Height**

Maximum height	65 feet or 6 stories	See exceptions in §122-613 .
----------------	----------------------	--

(2) Residential and Multifamily Uses

Minimum Lot Area	Two-family dwelling	6,000 sq. ft.
	Group living	6,000 sq. ft.
	Multiple-family	8,000 sq. ft.
	Ratio of Lot Size to Number of Rooms	The total number of rooms in a multiple dwelling structure may not be more than the area of the parcel in square feet divided by 1,400 square feet, exclusive of right-of-way.
Outdoor Space	A total of one hundred thirty (130) square feet of outdoor living space must be provided for each bedroom or studio/efficiency unit. Porches, balconies and improved roof areas may count toward the required outdoor living space, provided no such area is less than five (5) feet in width. Such outdoor areas must be buffered from streets and parking lots. Off-street parking areas, driveways, and accessory uses may not be counted as required open space.	
Front yard setback	25 feet	
Side yard setback	4 feet	For buildings with more than 6 units, 6 feet.
Side yard setback when abutting an R1 district	25 feet	
Side yard setback (combined)	12 feet	For buildings with more than 6 units, 14 feet
Street Side yard setback	8 feet	For buildings with more than 6 units, 15 feet
Rear yard setback	25 feet	
Distance between buildings	20 feet	
Corner Lots	Platted or of record after August 8, 1984	Front yard regulations apply to each street side of the corner lot. The rear yard requirements for a corner lot apply to the open space which is opposite and most distant from the front lot line as designated in the plat and/or in the request for a building permit.

(b) PRINCIPAL AND ATTACHED ACCESSORY STRUCTURES*Also subject to Article VI, Division 4*

	Platted or of record prior to August 8, 1984	Front yard regulations apply only along the front lot line as designated in the plat and/or in the request for a building permit. The yard along the second street must meet the requirements for side yards on corner lots as specified in the district regulations.
Usable floor area, minimum	1 Bedroom	600 sf
	2 Bedroom	800 sf
	3+ Bedroom	1,000 sf

(3) All Other Uses

Front yard setback	25 feet	
Side yard setback	6 feet	
Side yard setback (combined)	14 feet	
Street side yard setback	15 feet	
Rear yard setback	25 feet	
Corner Lots	Platted or of record after August 8, 1984	front yard regulations apply to each street side of the corner lot. The rear yard requirements for a corner lot apply to the open space which is opposite and most distant from the front lot line as designated in the plat and/or in the request for a building permit
	Platted or of record prior to August 8, 1984	front yard regulations apply only along the front lot line as designated in the plat and/or in the request for a building permit. The yard along the second street must meet the requirements for side yards on corner lots as specified in the district regulations.

(c) DETACHED ACCESSORY STRUCTURES

Also subject to Article VI, Division 4

(1) Height

Maximum height	15 feet
----------------	---------

(2) Size of Accessory Buildings

Maximum Floor Area	No limitations other than maximum impervious surface lot coverage.
--------------------	--

(3) Fences

Front Yard	No more than 4' height and 50% opacity	- Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. - Subject to §122-635 - Subject to §122-675
Side, Street Side, and Rear Yards	6' height max, no opacity restriction	

(4) Buildings Accessory to Residential Uses

Front yard	Not allowed	
Side yard	3 feet minimum	1 foot if lot line abuts an alley
Street Side yard	8 feet minimum	
Rear yard	3 feet minimum	1 foot if lot line abuts an alley, 12 feet for a through lot
Distance from principal structure	7 feet minimum	Minimum distance to comply with fire regulations and/or building code, if greater than 7 feet. An attached enclosure or roof over a pathway between structures on a lot, such as a breezeway, is exempt from this setback provided it is 8 feet or less in width and 15 feet or less in height.

(5) Buildings Accessory to Non-Residential Uses

Front yard	Not allowed	
Side yard	3 feet minimum	1 foot if lot line abuts an alley
Street Side yard	8 feet minimum	
Rear yard	3 feet minimum	1 foot if lot line abuts an alley, 12 feet for a through lot
Distance from principal structure	5 feet, or minimum to comply with fire regulations and building code, whichever greater.	

(d) SIGNS*Also subject to Article VI, Division 5***Signs**

Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit not required.
	Maximum Height	3 feet	
	All setbacks	0 feet minimum Subject to §122-675	
Freestanding Signs (permanent)	Maximum Area	16 sf	Permit required.
	Maximum Height	6 feet	
	Front Setback	3 feet minimum Subject to §122-675	
	Side, street side, and rear setback	10 feet minimum Subject to §122-675	
	Maximum number of signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever less	Permit required.
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or up to 32 sf each face of the building façade that faces a street, parking area, or on a façade where a public entrance is located	Permit required.
Billboards	Not permitted		

Secs. 122-428 – 429. Reserved.

Subdivision IV: Production, Manufacturing And Distribution District (PMD)

3500

ORIGINAL: 291-293

Sec. 122-430. Purpose. (291)

The Production, Manufacturing and Distribution (PMD) district is designed to create and sustain producing, manufacturing, storing, and distributing goods. These districts are generally located where buildings can be on large plots of contiguous land, serviced by railroad lines or major thoroughfares, and adequately served by required utilities and services. Uses are expected to generate waste, noise, odor, and truck traffic; however, uses should produce minimal external impacts that are detrimental in any way to other uses in the district or to properties in adjoining districts. Special uses are expected to produce undesirable external impacts and should, therefore, be located only where such impacts will not be detrimental to other uses in the PMD district or to properties in adjoining districts.

3510

Sec. 122-431. Permissible Uses and Use-based Regulations. (292)

- (a) **Deleterious operations.** No activity, operation, or use is permitted on any property which by reason of the emission of odor, fumes, smoke, vibration, radiation, heat, glare, dust, soot, noise, or disposal of waste is deleterious to other permitted activities in the zoning district or is obnoxious or offensive to uses permitted in neighboring districts, or is harmful to the general health, safety, or welfare, of the community.
- (b) **Enclosed buildings.** All manufacturing, compounding, assembling, processing, packaging, or other industrial or business activity in must be conducted within a completely enclosed building, except as otherwise specified.
- (c) **Unclassified Uses.** Any unclassified use may be permitted as a Special Use by determination of the City Council after having been recommended by the Planning Commission. The City Council may impose any required setback and/or performance standards above and beyond the requirements of this chapter so as to insure public health, safety and general welfare.

3520

ORIGINAL: unclassified uses was listed as a use in the table. But it didn't really fit. "Vehicle Wrecking, Salvage, Storage of Inoperable Vehicles" was listed separately from "junkyards," but the junkyard definition encompassed "Vehicle Wrecking, Salvage, Storage of Inoperable Vehicles," so combined the two.

<i>P=Principal; A=Accessory; S/Res= Special Land Use when adjacent to R-1, CN, CN-Mid, CN-SF, or MD zoning, otherwise permitted; S=Special Land Use</i>			
USES	PMD	NOTES	SPECIFIC REGULATIONS
INFRASTRUCTURE			
Essential Services	P		Section 122-523
Communication Devices	A		Article V, Division 3
Radio & Television Studios or Stations	P		
Radio and television towers, public utility microwaves, and public utility television transmitting towers, mobile communications towers, cellular phone towers and their accessory facilities	P		Section 122-566
Utility buildings including electric and gas service buildings and yards, telephone exchange buildings, electrical transformer stations and substations, gas regulator stations, and water and propane tank holders.	P		
Railroad yards not including manufacture and repair	S/Res		
Energy, electricity and heat generation plants	S	Includes solar farms and geothermal plants	Section 122-513
Landfill	S	May include anaerobic digester.	
Water or sewage treatment plant	S		

*P=Principal; A=Accessory;
S/Res= Special Land Use when adjacent to R-1, CN, CN-Mid, CN-SF, or MD zoning,
otherwise permitted;
S=Special Land Use*

USES	PMD	NOTES	SPECIFIC REGULATIONS
Biofiltration Facility	P		
Alternative Energy	A		Section 122-513
SERVICES			
Business and professional offices and services, 15,000 square feet or more	P		
Business and professional offices and showrooms	A		
Kennels, commercial	S/Res		Section 122-531
Offices for skilled trade services including but not limited to plumbing, electric, heating, and painting establishments	P		
Repair of appliances, machines or vehicles	P		
Self-storage facilities	P		
Printing services, including but not limited to: publishing, engraving, photo development, lithographing, silk screening and three-dimensional printing	P		Section 122-542
Construction and Landscape Contractors, contractor's yards, equipment and materials storage	P		
Recycling centers	S		
Adult Regulated Uses	S		Section 122-512
AUTO-ORIENTED			
Automobile Wash & Detailing	P		
Automobile Share Parking	A		
Truck Wash	S		
Automobile Repair	P		Section 122-515
Automobile rental (parking, storage, wash & repair)	P		
Vehicle &/or Recreational Vehicle Storage and Towing	S/Res		No storage of vehicles is permitted in setback from R-1, CN-SF, CN-Mid, CN, MD district.
Junkyards; Vehicle Wrecking, Salvage, Storage of Inoperable Vehicles	S		Section 122-530
RESEARCH			
Laboratories	S/Res		
Development & Research	S/Res		
PRODUCTION, MANUFACTURING & DISTRIBUTION			
Manufacture or processing of food products including brewing & distilling	P		
Craft manufacturing	P		

<i>P=Principal; A=Accessory; S/Res= Special Land Use when adjacent to R-1, CN, CN-Mid, CN-SF, or MD zoning, otherwise permitted; S=Special Land Use</i>			
USES	PMD	NOTES	SPECIFIC REGULATIONS
Medical Marijuana Growing/Manufacturing Facility	S		Section 122-533
Storage, warehousing, and wholesale distribution	S/Res	Outdoor storage is a special land use subject to section 122-539	
Central dry cleaning plants	S		
Clothing production	P		
Software, film, music, television and radio, and video game development & physical production	S/Res	Adult regulated uses are special land uses.	
Assembly and production, from prefabricated parts, of household appliances, electronic products, hardware products, and similar products	S/Res		
Processing or assembling of parts for production of finished equipment	S/Res		
Dry cleaning plants or laundries	S		
Manufacturing, Compounding, Processing, packing or treatment of such products as candy, cosmetics, drugs, perfumes, pharmaceuticals, and toiletries, except the rendering or refining of fats and oils	S/Res		
Manufacturing of alcohol; ammonia; bleaching powder or chlorine; asphalt, including refining; brick, tile or terra cotta; chemicals; concrete or cement products; lampblack; oil cloth or linoleum; paint, oil, shellac, turpentine, lacquer or varnish; petroleum products; plastics; soap; sodium compounds; tar distillation or tar products	S		
Manufacturing of machine tools, machinery, vehicles of all types, machine or vehicle components or that requires metal plating or galvanizing, plastic extrusion or molding or similar process	S		
Metal Foundry or fabricating plant and heavyweight casting	S		
Manufacture of construction materials	S		
Manufacturing of textiles, rubber or synthetic treated products	S		
Manufacture and repair of train cars, locomotives and track	S		
Animal slaughter and processing	S	Does not include aquaculture and aquaponics.	All activities must take place inside a fully enclosed building.
Ethanol, petroleum and fuel production, refining and storage	S		
Passive solar building	P		

<i>P=Principal; A=Accessory; S/Res= Special Land Use when adjacent to R-1, CN, CN-Mid, CN-SF, or MD zoning, otherwise permitted; S=Special Land Use</i>			
USES	PMD	NOTES	SPECIFIC REGULATIONS
Hydroponics, aquaculture, aquaponics, and similar raising of food	P		All activities must take place inside a fully enclosed building.
STORAGE			
Outdoor storage	S/Res		Section 122-539
Storage of liquid and solid fuels	S		Section 122-652

Sec. 122-432. Non-use and Dimensional Regulations. (293)

(a) OVERALL SITE REGULATIONS			Also subject to Article VI
(1) Maximum Lot Coverage			
All impervious surfaces		90%	
(2) Parking Location and Setbacks			
Front & street side yard		10 feet	
Side and rear yards		10 feet	
From adjacent R-1, CN-SF, CN-Mid, CN, MD districts		15 feet	
(3) Minimum Lot Width			
Determined by the use and the required off-street parking, loading, screening and yard setbacks			
(4) Minimum Lot Area			
Determined by the use and the required off-street parking, loading, screening and yard setbacks			
(5) Outdoor Lighting			
See Section 122-609			
(6) Landscaping			
See section Article VI, Division 3 for additional guidelines regarding landscaping.			
Conflicting Land Use Screening	From adjacent R-1, CN-SF, CN-Mid, CN, MD, HHS districts	Section 122-634. Screening must be a solid wall or fence constructed of face brick, poured-in-place simulated face brick, precast brick face panels having simulated face brick, stone, or wood.	
Greenbelt	• Must be provided along the front yard and any street side yard. • Must be landscaped with a minimum of one (1) tree for every thirty (30) feet of frontage. No evergreens. • No less than 10' deep • Remainder must be landscaped in grass, ground cover, shrubs and other natural landscape materials. • Access drives from public rights-of-way through required greenbelts are permitted, but such drives may not be subtracted from the dimension used to determine the minimum number of trees required.		

3530

(b) PRINCIPAL STRUCTURES AND ATTACHED ACCESSORY STRUCTURES*Also subject to Article VI***Height**

Maximum height	60 feet	See exceptions in §122-613 .
----------------	---------	--

Minimum Setbacks

Front yard	25 feet	Minimum setbacks increase by one foot for each foot a building or structure exceeds 30 feet in height.
Side yard	15 feet	
Street Side yard	15 feet	
Rear yard	20 feet	
From adjacent R-1, CN-SF, CN-Mid, CN, MD, HHS	25 feet	

(c) DETACHED ACCESSORY STRUCTURES*Also subject to Article VI, Division 4***(1) Height**

Maximum height	60 feet	Subject to §122-613
----------------	---------	---------------------

(2) Size of Accessory Buildings

Maximum Floor Area	No limitations other than maximum lot coverage.
--------------------	---

(3) Fences

Front Yard	No more than 6' height and 50% opacity	• Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. • Subject to §122-635 • Subject to §122-675
Side, Street Side, and Rear Yards	10' height max, no opacity restriction	

(4) Minimum Setbacks

Front yard	25 feet	Minimum setbacks increase by one foot for each foot a building or structure exceeds 30 feet in height.
Side yard	15 feet	
Street Side yard	15 feet	
Rear yard	20 feet	
From adjacent R-1, CN-SF, CN-Mid, CN, MD, HHS	25 feet	

(d) SIGNS			
Also subject to Article VI, Division 5			
(1) Signs – Residential Uses			
Freestanding Signs (temporary)	Maximum Area	10 sf	Permit not required.
	Maximum height	3 feet	
	All Setbacks:	0 feet; Subject to §122-675	
Freestanding signs (permanent)	not permitted		n/a
Building-mounted signs (temporary)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit not required.
Building-mounted signs (permanent)	Maximum Area	1 sf	Permit not required.
Billboards	Location	adjacent to and visible from I-94, as defined by the Highway Advertising Act of 1972.	Permit required.
	Maximum Area	672 sf	
	Maximum Height	65'	
	Other restrictions	Subject to §122-675	
(2) Signs – Non-residential Uses & Group Living			
Freestanding Signs (temporary)	Maximum Area	10 sf per sign	Permit required.
	Maximum height	8 feet	
	All setbacks:	0 feet; Subject to §122-675	
	max # signs	no more than 1 per 20' frontage on primary face and 1 per 50' on secondary face	
Freestanding Signs (permanent)	Maximum Area	16 sf	Permit required.
	Maximum Height	6 feet	
	Front Setback	3 feet; Subject to §122-675	
	Side, street side, and rear setback	10 feet; Subject to §122-675	
	Maximum # signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Billboards	Location	Must be adjacent to and visible from I-94, as	Permit required.

		defined by the Highway Advertising Act of 1972.	
	Maximum Area	672 sf	
	Maximum Height	65'	
	Other restrictions	Subject to §122-675	

Secs. 122-433 – 434. Reserved.

Division 3: Walkable Urban Districts

3540

ORIGINAL: sections 271 thru 272.
"purpose" drawn from 122-231 in previous code.

Sec. 122-435. Purpose. (271)

3550

Core neighborhoods, corridors, and centers are classified as walkable urban places, where the regulations go beyond use or intensity to reinforce the context of the built environment through form and scale. The office district as laid out in the Master Plan, included here as Health and Human Services, has been classified as a walkable urban area because it is surrounded by Neighborhoods, Centers, and Corridors, and has an underlying street network and mixture of uses. These districts were primarily developed prior to the 1940s, and around the concept that individuals would not be driving in the course of daily business. These districts are still places where a person can walk, bike, or ride transit to work and to fulfill most shopping and recreation needs; they allow for the use of automobiles and freight vehicles, but do not require them. They are largely supported through a network of interconnected, tree-lined streets, diverse housing choices, a mix of commercial and residential uses, and public transit. The regulations set forth herein are meant to encourage a sensible mix of compatible uses, to enable residents to live without a personal vehicle, and to respect the history of the neighborhoods.

Secs. 122-436 – 439. Reserved.

Subdivision I: Core Neighborhoods (CN-Sf, CN-Mid, CN)

ORIGINAL: numbered as 272. The description was drawn from 271; renumbered so it matched the order (low-intensity to higher-intensity). Added "specific regulations" to differentiate the descriptive from the regulatory

Sec. 122-440. Purpose. (from 271)

Core neighborhoods are built on a grid street network connected to the adjacent business districts. They border center districts or other core neighborhoods. These neighborhoods have a range of residential building types, with religious institutions, schools, stores and automobile filling stations intermixed. There are three types of core neighborhoods:

- (a) Core Neighborhood Single Family (CN-SF). These neighborhoods are east of Depot Town and north of Michigan Avenue, known as the historic eastside. Housing types include mansions, estates, houses, and cottages. Residential uses are restricted to single-family; neighborhood businesses are limited.
- (b) Core Neighborhood Mid (CN-Mid). These neighborhoods generally abut the Core Neighborhoods, and offer a less dense and less intense residential area with opportunities for accessibly-placed low-intensity walkable, neighborhood businesses. Housing types range from mansions to cottages, with multiple-family and single-family uses. This zoning may also be used as a transition zone between single-family districts and mixed use districts.
- (c) Core Neighborhoods (CN). These neighborhoods directly border center districts and have a variety of housing types, ranging from cottages to apartment buildings. This district affords opportunities for accessibly-placed walkable, neighborhood businesses.

Sec. 122-441. Permissible Uses. (272)

In the Core Neighborhood districts, no uses shall be permitted except the following.

<i>P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted</i>					
USES	CN-SF	CN-MID	CN	NOTES	SPECIFIC REGULATIONS
RESIDENTIAL					
Single-Family Detached Dwelling	P	P	P		
Single-Family Attached Dwellings		P	P		In "townhome" building type only
Accessory Dwelling Unit	--	A	A		
Two-family dwelling units	--	P	P		
Multiple Family Dwellings, maximum of 4 units per building	--	S	P		
Multiple Family Dwellings, more than 4 units per building	--	--	S		
Apartments located above ground floor of permitted nonresidential uses	--	--	P		
Home Occupation	A	A	A		Section 122-527
Family Child Care Home	A	A	A	1-6 children	Must be licensed by the state and must comply with the minimum state standards for such facilities.
Group Child Care Home	S	S	S	6-12 children	Section 122-521
Adult foster care family homes	A	A	A	1-6 adults, day care and 24 hour care	Must be licensed by the state and must comply with the minimum state standards for such facilities.
Group residence	--	--	S		Section 122-526
Roominghouse	--	--	S		

Group living with support staff, not licensed by State of Michigan	--	--	S	Includes supportive housing, rehabilitation housing or dormitories.	Section 122-548
Adult foster care small & group homes, adult congregate facilities	--	S	S	7 or more adults. Licensed by State of Michigan.	Section 122-511
Adult foster care facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities.	--	--	S		
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES					
Park	P	P	P		
Indoor recreation	--	--	A		Section 122-529
Primary & Secondary Schools (public & private)	S	S	S	Public schools are only subject to State regulations regarding location and construction.	Section 122-545
Post-secondary educational institutions (public & private)	S	S	S	Public schools are only subject to State regulations regarding location and construction.	Section 122-545
Religious institution	S	S	S		Section 122-543
Private assembly, including banquet hall	--	--	S		
Municipal, county, regional, & state service uses	S	S	S		Section 122-535
Public Art	A	A	A		
SERVICES					
Bed & Breakfast or Inn	S	S	S		Section 122-520
Funeral Homes	--	S	S		
Nursing Homes	--	S	S		Section 122-536
Medical or Dental Offices, less than 5,000 square feet	--	S	S		
COMMERCIAL					
Arts & crafts studios	--	--	S		
Food stores, excluding sale of alcohol, less than 15,000 square feet	S	S	S		
Farmers' Market	A	A	A		When accessory to a non-residential use.
Garage Sales	A	A	A		Section 122-524
RESTAURANTS					
Carry-out and/or delivery restaurant	--	--	S		

Café or coffee shop	--	--	S		
AUTO-ORIENTED					
Automobile Filling Station - no repair	S	S	S		Section 122-516
Automobile Share Parking	--	--	A		
INFRASTRUCTURE					
Essential Services	P	P	P		Section 122-523
Communication Devices	A	A	A		Article V, Division 3
Alternative Energy	A	A	A		Section 122-513
GARDENS/COMMUNITY GARDENS					
Community gardens	P	P	P		Section 122-525
Passive solar building	A	A	A		• Must meet accessory building regulations for building type. • Maximum square footage is 800 square feet.
Toolhouses, sheds, and other similar buildings for the storage of domestic supplies	A	A	A		Must meet accessory building regulations for building type.

Sec. 122-442. Non-use and dimensional requirements for site improvements not regulated by building type.

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

(a) Outdoor Lighting

See [Section 122-609](#)

(b) Fences

Front Yard	No more than 4' height and 50% opacity	- Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. - Subject to §122-635 - Subject to §122-675
Side, Street Side, and Rear Yards	6' height max, no opacity restriction	

(c) Detached Accessory Buildings

No more than two detached accessory buildings are permitted per parcel.

(d) SIGNS

(1) Residential Uses

Freestanding Signs (temporary)	Maximum Area	10 sf	Permit not required.
	Maximum height	3 feet	
	All setbacks:	0 feet; Subject to §122-675	
Freestanding signs (permanent)	not permitted		n/a
Building-mounted signs (temporary)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit not required.
Building-mounted signs (permanent)	Maximum area	1 sf	Permit not required.
Billboards	not permitted		n/a

(2) Non-residential Uses & Group Living

Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit not required.
	Maximum height	3 feet	
	All setbacks:	0 feet; Subject to §122-675	
Freestanding Signs (permanent)	Maximum Area	16 sf	Permit required.
	Maximum Height	6 ft	
	Front Setback	3 feet; Subject to §122-675	
	Side, street side, and rear setback	10 feet; Subject to §122-675	

<i>For most non-use and dimensional requirements, see Subdivision V of this Division.</i>			
<i>Also subject to Article VI</i>			
	Maximum # signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Building-mounted signs (permanent)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit required.
Billboards	not permitted		n/a

Secs. 122-443 – 444. Reserved.

Subdivision II: Center (C)

Sec. 122-445. Purpose. (271)

These are mixed-use areas with historic buildings. These are the places where people shop, go to school, live, come to work, visit, drop by City Hall, eat, gather and have fun. They host events that bring thousands of visitors each year and bring the City together as a community. The intent of the zoning district is preserve the urban form, walkable nature and vibrant mix of uses in these areas.

Sec. 122-446. Permissible Uses. (272)

In the Center district, no uses shall be permitted except the following.

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	C	NOTES	SPECIFIC REGULATIONS
RESIDENTIAL			
Single-family attached dwellings	P		In "Townhome" building type only
Multiple Family Dwellings	P		In "Apartment Building" building type only
Apartments located above ground floor of permitted nonresidential uses	P		
Home Occupation	A		Section 122-527
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES			
Museums & libraries	P		
Parks	P		
Public Art	A		
Indoor recreation	P		
Performance venues/theaters	P		
Municipal, county, regional & state service uses	P	Only subject to State regulations regarding location and construction.	Section 122-535
Post-secondary educational institutions (public & private)	P	Public schools are only subject to State regulations regarding location and construction.	Section 122-545
INFRASTRUCTURE			
Essential Services	P		Section 122-523
Communication Devices	A		Article V, Division 3
Alternative Energy	A		Section 122-513
Public & Private Transportation Passenger Terminals	S		Section 122-541
SERVICES			
Business and professional offices and services	P		
Financial services, including banks	P		No drive through or drive-in facilities are permitted in C.
Personal service establishments	P		
Body Art Facilities	P		

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	C	NOTES	SPECIFIC REGULATIONS
Printing services, including but not limited to: publishing, engraving, photo development, lithographing, silk screening and three-dimensional printing	S		
Hotels & motels	P		
Child Care Centers	P		Section 122-521
Laundromats and dry cleaners	P		No dry cleaning on premises.
Medical or dental clinics	P		
Medical Marijuana Dispensary	P		Section 122-532
Catering services	A		
Self-storage	S		Section 122-546
COMMERCIAL			
Retail stores	P		
Resale stores	P		
Arts & crafts studios	P		
Food stores, excluding sale of alcohol	P		
Food stores less than 15,000 square feet, with sale of alcohol	S		
Food stores greater than 15,000 square feet, with sale of alcohol	P		
Farmers' market and other open-air markets	P		
Auction houses	P		Section 122-514
RESTAURANTS			
Carry-out and/or delivery restaurant	P		
Café or coffee shop	P		
Sit-down	P		
Bar/Lounge	P		
Tasting room and/or restaurant	A		Carry-out sales allowed with proper licenses.
Outdoor cafes	A		Section 122-540
Fast Food	P		No drive through or drive-in facilities are permitted in C.
AUTO-ORIENTED			
Parking lot	S	Permitted as an accessory use without special use permit.	Section 122-519
Parking Garage	S		Section 122-518
Automobile Share Parking	A		
PRODUCTION, MANUFACTURING & DISTRIBUTION			

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	C	NOTES	SPECIFIC REGULATIONS
Microbrewer/ small distiller /small wine maker	P		Carry-out sales allowed with proper licenses.
TEMPORARY USES			
Mobile Food Establishments	P		Section 122-335
PERFORMANCE OR STRUCTURES REQUIRING SPECIAL LAND USE			
Operation between 2 a.m. and 6 a.m. during any 24-hour period	P		
Sale of alcoholic beverages for consumption off the premises, not otherwise specified above.	S		

Sec. 122-447. Non-use and dimensional requirements for site improvements not regulated by building type.

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

(a) Outdoor Lighting			
See Section 122-609			
(b) Fences			
Front Yard & Street Side Yard	Not permitted, except for off-street parking screening or otherwise permitted by Planning Commission	- Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. - Subject to §122-635 - Subject to §122-675	
Side & Rear Yards	6' height max, no opacity restriction		
(c) Detached Accessory Buildings			
No more than two detached accessory buildings are permitted per parcel.			
(d) SIGNS			
(1) Residential Uses			
Freestanding Signs (temporary)	Maximum Area	10 sf	Permit not required
	Maximum height	3 feet	
	All setbacks	0 feet Subject to §122-675	
Freestanding signs (permanent)	not permitted		N/A
Building-mounted signs (temporary)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit not required
Building-mounted signs (permanent)	Maximum Area	1 sf	Permit not required
Billboards	not permitted		n/a
(2) Non-residential Uses & Group Living			
Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit required
	Maximum height	3 feet	
	All setbacks	0 feet Subject to §122-675	
Sidewalk Signs (freestanding temporary signs in the	Max size of 6sf per face, maximum 2 faces, max height of 4 feet.		Permit required
	Must allow for a 5' clear path of travel on at least one side.		
	May only be displayed during business hours.		
	Sidewalk signs must be constructed of durable wood, metal,		

For most non-use and dimensional requirements, see Subdivision V of this Division.			
Also subject to Article VI			
public ROW)	or plastic. Any fabric shall be affixed in place on all sides.		
	Subject to §122-675		
	Maximum number of signs	one per business	
Freestanding Signs (permanent)	Not Permitted		
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required
Overhead banners (building-mounted signs that span a public right-of-way)	The design, method of installation, and location of overhead banners must not endanger persons using any part of the public right-of-way or unduly interfere with the movement of people.		Permit required
	Minimum height to bottom of banner is 18 feet.		
	Must not be located closer than 10 feet to an intersection.		
	Shall not be more than 4 feet in height.		
	No more than one overhead banner shall be placed per block at any given time.		
	Overhead banners may remain in place for no longer than thirty days.		
	When located spanning a State trunkline, must conform to PA 200 of 1969 and obtain a permit from MDOT.		
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required
Billboards	not permitted		

Secs. 122-448 – 449. Reserved.

Subdivision III: Corridors (HC, NC, GC)

Sec. 122-450. Purpose. (271)

Corridors are mixed-use and commercial areas located along the arteries of the City, such as Washtenaw, Huron, Hamilton, Michigan, Harriet, and River.

- (a) Historic Corridor (HC). Historic corridors are located primarily in the Historic District, and are on Cross Street, Huron Street, Hamilton Street, and River Street. These corridors are lined with historic buildings and are integrated into the adjacent neighborhoods and centers. The intent of this district is to preserve the walkability, character and historic nature of these streets, while allowing for adaptive re-use of historic buildings.
- (b) Neighborhood Corridor (NC). Neighborhood corridors have a linear land pattern and are adjacent to residential neighborhoods. The size, form and scale of buildings and the type and intensity of uses should be complementary to abutting single-family or core neighborhoods, including less intense multiple-family residential building types and uses.
- (c) General Corridor (GC). General corridors are located along roads with heavy traffic and have commercial establishments, restaurants, offices, and other businesses that are geared toward automobile traffic. Multiple-family residential building types and uses are appropriate in this district.

Sec. 122-451. Permissible Uses. (272)

In the Corridor districts, no uses shall be permitted except the following.

<i>P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted</i>					
USES	HC	NC	GC	NOTES	SPECIFIC REGULATIONS
RESIDENTIAL					
Single-Family Detached Dwelling	P	--	--		
Single-Family Attached Dwelling	--	P	P		In "Townhome" building type only
Accessory Dwelling Unit	A	--	--		
Two-family dwelling units	P	P	P		
Multiple Family Dwellings, maximum of 4 units per building	P	P	P		
Multiple Family Dwellings, more than 4 units per building	S	S	P		Section 122-534
Apartments located above ground floor of permitted nonresidential uses	P	P	P		
Home Occupation	A	A	A		Section 122-527
Family Child Care Home	A	A	A	1-6 children	Must be licensed by the state and must comply with the minimum state standards for such facilities.
Group Child Care Home	A	A	A	6-12 children	Section 122-521
Adult foster care family homes	A	A	A	1-6 adults	Must be licensed by the state and must comply with the minimum state standards for such facilities.
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES					
Parks	P	P	P		

<i>P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted</i>					
USES	HC	NC	GC	NOTES	SPECIFIC REGULATIONS
Outdoor recreation	--	S	P		Section 122-529
Museums & libraries, less than 15,000 square feet	P	P	--		
Museums & libraries 15,000 square feet or more	S	S	--		
Primary & Secondary Schools (public & private)	S	S	--	Public schools are only subject to State regulations regarding location and construction.	Section 122-545
Post-secondary educational institutions (public & private)	S	S	--	Public schools are only subject to State regulations regarding location and construction.	Section 122-545
Religious institution	S	S	--		Section 122-543
Private assembly, including banquet halls	S	S	--		
Indoor recreation less than 15,000 square feet	--	P	P		
Indoor recreation 15,000 square feet or more	--	--	P		
Municipal, county, regional & state service uses	S	P	P		Section 122-535
Public Art	A	A	A		
SERVICES					
Business and professional offices, less than 15,000 square feet	P	P	P		
Business and professional offices, 15,000 square feet or more	--	S	P		
Financial services, including banks, less than 15,000 square feet	P	P	P		Drive through or drive-in facilities require special land use
Financial services, including banks, 15,000 square feet or more	--	S	P		Drive through or drive-in facilities require special land use.
Homeless Shelter	--	--	P		Section 122-528
Personal service establishments, less than 15,000 square feet	P	P	P		
Personal service establishments, 15,000 square feet or more	--	--	P		
Body art facilities	--	--	P		
Offices for skilled trade services including but not limited to plumbing, electric, heating, and painting establishments	--	S	P		Section 122-537

<i>P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted</i>					
USES	HC	NC	GC	NOTES	SPECIFIC REGULATIONS
Printing services, including but not limited to: publishing, engraving, photo development, lithographing, silk screening and three-dimensional printing	--	S	S		Section 122-542
Bed & Breakfast or Inn	P	S	--		Section 122-520
Hotels & motels	--	--	P		
Child Care Centers	S	P	P		Section 122-521
Funeral homes	S	S	S		
Laundromats and dry cleaners, less than 15,000 square feet	--	P	P		No dry cleaning on premises.
Laundromats and dry cleaners, 15,000 square feet or more	--	--	P		No dry cleaning on premises.
Nursing Homes	S	--	S		Section 122-536
Medical or dental clinics, less than 10,000 square feet	P	P	P		
Medical or dental clinics, 10,000 square feet or more	S	S	P		
Veterinary hospitals and clinics	--	S	S		Section 122-549
Kennels, commercial	--	--	S		Section 122-531
Substance abuse treatment facilities	--	--	S		Section 122-547
Catering services, less than 15,000 square feet	P	P	P		
Catering services, 15,000 square feet or more	--	--	P		
Self-storage	--	--	P		Section 122-546
COMMERCIAL					
Retail stores, less than 15,000 square feet	S	P	P		
Retail stores, greater than 15,000 square feet	--	--	P		
Resale stores	--	P	P		
Arts & crafts studios	P	P	P		
Food stores, excluding sale of alcohol, less than 15,000 square feet	S	P	P		
Food stores, with sale of alcohol, less than 15,000 square feet	--	S	P		
Food stores greater than 15,000 square feet with or without sale of alcohol	--	--	P		
Commercial Greenhouse			P		
Farmers' market and other open-air markets	--	P	P		

<i>P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted</i>					
USES	HC	NC	GC	NOTES	SPECIFIC REGULATIONS
Outdoor retail sales	--	S	S		Section 122-538
RESTAURANTS					
Carry-out and/or delivery restaurant	--	P	P		
Café or coffee shop	P	P	P		
Sit-down, with seating limit of 50 seats	P	P	P		
Sit-down, no seating limit	--	--	P		
Bar/Lounge	--	S	P		
Tasting room and accessory to microbrewer/ small distiller/ small wine maker	--	S	P		Carry-out sales allowed with proper licenses.
Fast Food	--	S	P		Must be located on major thoroughfare. Drive through or drive-in facilities require special land use.
Drive through restaurant of any type	--	--	S		Section 122-522
Outdoor cafes	A	A	A		Section 122-540
AUTO-ORIENTED					
Parking lot	--	--	S	Permitted as an accessory use without special use permit.	Section 122-519
Parking Garage	--	--	S		Section 122-518
Automobile Sales	--	--	S		
Automobile Filling Station - no repair	--	S	S		Section 122-516
Automobile Filling Station with repair	--	--	S		Sections 122-516 and 122-515
Automobile Wash & Detailing	--	--	S		
Automobile Repair	--	--	S		Section 122-515
Automobile Share Parking	A	A	A		
Automobile rental or share organization (parking, storage, wash & repair)	--	--	S		
Vehicle, Recreational Vehicle, Storage and Towing	--	--	S		
RESEARCH					
Laboratories	--	--	S		
Research & Development	--	--	S		
PRODUCTION, MANUFACTURING & DISTRIBUTION					
Craft production, clothing production or food production, less than 16,000 square feet	--	P	P		

<i>P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted</i>					
USES	HC	NC	GC	NOTES	SPECIFIC REGULATIONS
Craft production, clothing production or food production, 16,000 square feet or greater	--	--	S		
Microbrewer/ small distiller /small wine maker, less than 16,000 square feet	--	P	P		
Microbrewer/ small distiller /small wine maker, 16,000 square feet or greater	--	--	S		Carry-out sales allowed with proper licenses.
Wholesale or distribution facility with total gross floor area of less than 16,000 square feet	S	S	P		
Wholesale or distribution facility with total gross floor area 16,000 square feet or greater	--	--	S		
Medical Marijuana Growing/Manufacturing Facility	--	--	S		Section 122-533
TEMPORARY USES					
Mobile Food Establishments	--	P	P		Section 122-335
INFRASTRUCTURE					
Essential Services	P	P	P		Section 122-523
Communication Devices	A	A	A		Article V, Division 3
Alternative Energy	A	A	A		Section 122-513
GARDENS/COMMUNITY GARDENS					
Passive solar building	A	A	A		Must meet accessory structure regulations for building type. Maximum square footage is 800 square feet in the HC zoning district.
Community gardens	--	A	A		Section 122-525
PERFORMANCE OR STRUCTURES REQUIRING SPECIAL LAND USE					
Operation between 2 a.m. and 6 a.m. during any 24-hour period	--	S	S		
Drive through facilities	--	S	S		Section 122-522
Ongoing outdoor retail sales or display	--	S	S		Section 122-538
Outdoor storage	--	S	S		Section 122-539

Sec. 122-452. Non-use and dimensional requirements for site improvements not regulated by building type.

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

(a) Outdoor Lighting			
See Section 122-609			
(b) Fences			
Front Yard and Street Side Yard	No more than 6' height	- Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. - Subject to §122-635 - Subject to §122-675	
Side and Rear Yards	10' height max		
(c) Detached Accessory Buildings			
No more than two detached accessory buildings are permitted per parcel.			
(d) SIGNS			
(1) Residential Uses			
Freestanding Signs (temporary)	Maximum Area	10 sf	Permit not required.
	Maximum height	3 feet	
	All setbacks	10 feet Subject to §122-675	
Freestanding signs (permanent)	not permitted		
Building-mounted signs (temporary)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit not required.
Building-mounted signs (permanent)	Maximum area	1 sf	Permit not required.
Billboards	not permitted		
(2) Non-residential Uses & Group Living			
Freestanding Signs (temporary)	Maximum Area	10 sf per sign	Permit required.
	Maximum height	8 feet	
	All setbacks	10 feet Subject to §122-675	
	Maximum # of signs	No more than 1 per 20' of lot frontage on primary lot frontage and 1 per 50' on secondary lot frontage	
Sidewalk Signs (freestanding temporary signs in the	Not permitted in NC or GC.		Permit required.
	Max size of 6sf per face, maximum 2 faces, max height of 4 feet.		
	Must allow for a 5' clear path of travel on at least one side.		

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

public ROW)	May only be displayed during business hours.		
	Sidewalk signs must be constructed of durable wood, metal, or plastic. Any fabric shall be affixed in place on all sides.		
	Subject to §122-675		
	max # signs	1 per business	
Freestanding Signs (permanent)	Maximum Area	HC & NC: 20 sf; GC: 100 sf	Permit required.
	Maximum Height	10 feet	
	Front Setback	3 feet from lot line or 10 ft from back of curb, whichever greater distance from roadway. Subject to §122-675	
	Side, street side, and rear setback	10 feet Subject to §122-675	
	Maximum # signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 50% of the area of the sign on the primary face.	
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Overhead banners (building-mounted signs that span a public right-of-way)	Not permitted in NC or GC.		Permit required.
	The design, method of installation, and location of overhead banners must not endanger persons using any part of the public right-of-way or unduly interfere with the movement of people.		
	Minimum height to bottom of banner is 18 feet.		
	Must not be located closer than 10 feet to an intersection .		
	Shall not be more than 4 feet in height.		
	No more than one overhead banner shall be placed per block at any given time.		
	Overhead banners may remain in place for no longer than thirty days.		
	When located spanning a State trunkline, must conform to PA 200 of 1969 and obtain a permit from MDOT.		
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Billboards	not permitted		

Secs. 122-453 – 459. Reserved.

Subdivision IV: Health And Human Services (HHS)

Sec. 122-460. Purpose. (271)

The Health and Human Services district is located on either side of Towner between Prospect and Arnet Streets. A cluster of office, health and human service uses are in this district. The intent of the district is to require a more urban form through redevelopment of parking lots and reconnecting the street grid and circulation system.

Sec. 122-461. Permissible Uses. (272)

In the Health and Human Services district, no uses shall be permitted except the following.

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	HHS	NOTES	SPECIFIC REGULATIONS
RESIDENTIAL			
Single-Family Attached Dwelling	P		In "Townhome" building type only
Two-family dwelling	P		
Multiple Family Dwellings, maximum of 6 units per building	P		
Multiple Family Dwellings, more than 6 units per building	S		Section 122-534
Apartments located above ground floor of permitted nonresidential uses	P		
Home Occupation	A		Section 122-527
Group living with support staff, not licensed by State of Michigan	P	Includes supportive housing, rehabilitation housing or dormitories.	Section 122-548
Family Child Care Home	A	1-6 children	Must be licensed by the state and must comply with the minimum state standards for such facilities.
Group Child Care Home	A	6-12 children	Section 122-521
Adult foster care family homes	A	1-6 adults, day care and 24 hour care Excludes facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities.	Must be licensed by the state and must comply with the minimum state standards for such facilities.
GROUP LIVING			
Group residence, maximum of 6 residents	P		Section 122-526
Group residence with 7 or more residents	S		Section 122-526
Adult foster care small & group homes, adult congregate facilities	P	7 or more adults, licensed by State of Michigan	Section 122-511
Adult foster care facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities.	S		
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES			
Parks	P		

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	HHS	NOTES	SPECIFIC REGULATIONS
Public Art	A		
Indoor recreation	P		
Municipal, county, regional & state service uses	P		Section 122-535
Post-secondary educational institutions (public & private)	S		Section 122-545
Outdoor recreation	A		Section 122-529
INFRASTRUCTURE			
Essential Services	P		Section 122-523
Communication Devices	A		Article V, Division 3
Alternative Energy	A		Section 122-513
SERVICES			
Business and professional offices and services	P		
Financial services, including banks	P		Drive through or drive-in facilities require special land use
Adult drop-in center	P		Section 122-510
Homeless Shelter	P		Section 122-528
Personal service establishments	P		
Child Care Centers	P		Section 122-521
Funeral homes	S		
Nursing Homes	P		Section 122-536
Medical or dental clinics	P		
Hospitals	P		
Substance abuse treatment facilities	S		Section 122-547
Catering services	P		
COMMERCIAL			
Retail stores less than 15,000 square feet	P		
Food stores, excluding sale of alcohol	P		
Farmers' market and other organized markets	P		
RESTAURANTS			
Carry-out and/or delivery restaurant	P		
Café or coffee shop	P		
Cafeteria	A		
AUTO-ORIENTED			
Parking Garage	S		Section 122-518
Automobile Share Parking	A		
RESEARCH			
Laboratories	P		
TEMPORARY USES			

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	HHS	NOTES	SPECIFIC REGULATIONS
Food concession sales	P		Section 122-335
URBAN AGRICULTURE			
Community gardens	A		Exempt from area regulations in §122-462, subject to §122-525
Toolhouses, sheds and other similar buildings for the storage of domestic supplies	A		Must meet accessory structure regulations for building type.
Passive solar building	A		Must meet accessory structure regulations for building type.
PERFORMANCE OR STRUCTURES REQUIRING SPECIAL LAND USE			
Operation between 2 a.m. and 6 a.m. during any 24-hour period	S		

Sec. 122-462. Non-use and dimensional requirements for site improvements not regulated by building type.

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

(a) Fences			
Front yard, street side yard	No more than 6' height and 50% opacity	Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. • Subject to §122-635 • Subject to §122-675	
Side, and rear yards	10' height max, no opacity restriction		
(b) Outdoor Lighting			
See Section §122-609			
(c) Detached Accessory Buildings			
No more than two detached accessory buildings are permitted per parcel.			
(d) SIGNS			
(1) Residential Uses			
Freestanding Signs (temporary)	Maximum Area	10 sf	Permit not required.
	Maximum height	3 feet	
	All setbacks	10 feet Subject to §122-675	
Freestanding signs (permanent)	not permitted		
Building-mounted signs (temporary)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit not required.
Building-mounted signs (permanent)	Maximum area	1 sf	Permit not required.
Billboards	not permitted		
(2) Non-Residential Uses & Group Living			
Freestanding Signs (temporary)	Maximum Area	10 sf per sign	Permit required.
	Maximum height	8 feet	
	All setbacks	10 feet Subject to §122-675	
	Maximum # of signs	No more than 1 per 20' of lot frontage on primary frontage and 1 per 50' on secondary frontage	

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

Sidewalk Signs (freestanding temporary signs in the public ROW)	not permitted		
Freestanding Signs (permanent)	Maximum Area	20 sf	Permit required.
	Maximum Height	10 feet	
	Front Setback	3 feet from lot line or 10 ft from back of curb, whichever greater distance from roadway; Subject to §122-675	
	Side, street side, and rear setback	10 feet; Subject to §122-675	
	max # signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 50% of the area of the sign on the primary face.	
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Overhead banners (building-mounted signs that span a public right-of-way)	Not permitted		
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Billboards	not permitted		

Secs. 122-463 – 464. Reserved.

Subdivision V: Building Types

Sec. 122-465. Building Types. (274)

Building types are specific sets of height, bulk, and setback regulations, dictated by district and lot size and dimension. Building Types only apply in Walkable Urban Districts, and apply to any new construction or expansion in those districts. The building types are consistent with the size, scale and character desired within each zoning district.

3640

ORIGINAL: (simplified)

Building types are permitted by Core Neighborhoods, Centers, Corridors and Health and Human Services District(s) as identified in Sec. 122-271 when any new and/or redevelopment occurs on any parcel within these Districts. The building typologies are consistent with the size, scale and character desired within each Neighborhoods, Centers, Corridors and Health and Human Services District.

- (a) **Building Types by Neighborhoods, Centers, Corridors and Health and Human Services District.** The following building types are allowed in Neighborhoods, Centers, Corridors and Health and Human Services districts as shown in the table below. “P” stands for permitted building types, “L” stands for building types allowed in special locations shown on the Zoning Map.

3650

BUILDING TYPE		CN-SF	CN-MID	CN	C	HC	NC	GC	HHS
MA	Mansion	L	L	L	--	L	--	--	--
ES	Estate	P	P	P	--	P	P	--	--
HS	House	P	P	P	--	P	P	--	P
CO	Cottage	P	P	P	--	--	--	--	--
TH	Townhouse	--	P	P	L	--	P	--	P
AH	Apartment House	--	P	P	P	P	P	--	P
CA	Courtyard Apartment	--	--	P	L	P	P	P	--
AB	Apartment Building	--	--	P	L	L	P	P	--
CS	Commercial/Mixed-Use Small	--	--	L	P	P	P	P	--
CM	Commercial/Mixed Use Medium	--	--	--	P	P	P	P	--
CL	Commercial/Mixed Use Large	--	--	--	P	--	--	P	P
SC	Single Story Commercial Building	L	L	L	--	L	P	P	--
LS	Large Single Story Commercial Building	--	--	--	--	--	--	P	P
MB	Multiple Story	--	--	--	P	--	--	P	P
IT	Institutional	L	L	L	L	L	L	L	L

-made IT building types Limited - only available with a rezoning.

-reordered columns to reflect order in chapter.

DELETED:

New Construction of Limited Building Types requires Site Plan Approval by Planning Commission.

All new construction of limited building types must be subject to site plan review with approval by the Planning Commission per Section 122-123.

- (b) **How to Read Building Type Diagrams.** The following categories are included in each building type diagram. Each standard is labeled by a letter; that letter corresponds to a location on an illustration of the standard. Each standard is described as follows:

3660

- (1) **Building Type Parameters.** The diagrams and text that follow provide the building parameters by building type. Building types must be consistently applied by District and not permitted a variance or waiver to increase in lot size.
- (2) **Lot Size determines Building Type.** The size of the lot determines what type of building may be placed on

a lot. For instance, a cottage or a house building type may be constructed on 5,000 square foot lot, since all of the those building types fit within the allowed lot size for those building types, but an estate building type is not allowed. Maximum lot depth and width do not determine building types, but all building types must meet the minimum lot width, depth and size.

- (3) Lot requirements. Lists the minimum and maximum lot width, lot depth, and lot size; also the maximum lot coverage.
- (4) Building envelope. Lists the minimum and maximum setbacks for street, side, and rear setbacks, as well as the required frontage buildout.
- (5) Accessory Structure Envelope. Lists the setbacks and maximum building footprint permitted for accessory structures.
- (6) Building height. Lists permitted heights in stories.
- (i) First or Ground Story. The minimum height for all first stories is twelve (12) feet. For the MA, ES, HS, CO, TH, CA, and AB building types the maximum height for the first story shall be fourteen (14) feet; for all others, the maximum height for the first floor shall be twenty (20) feet. Institutional building types, however, have no maximum height for the first floor. This shall not be construed as limiting multi-story or open foyers or lobbies.
- (ii) Subsequent stories. The minimum height for second story and above is ten (10) feet; the maximum height for second story and higher must not exceed twelve (12) feet. However, the top story of any building has a minimum height of ten (10) feet, but no maximum height.
- (iii) Basements. There are no required maximum or minimum heights for basements outside of that required under Building Code.
- (iv) Exceptions to Height Requirements. See exceptions in §122-613.

ORIGINAL:

- Changed IT first floor height exception from being a waiver- can't grant a waiver without findings, and findings on this would be weird and likely end up related to use- too much margin for error. Also, had specifically referenced the specific standards for religious institutions, not other types of uses, which is just not good practice.

-Added the bit about foyers because foyers are generally good features- and encourage builders to have a bit of a grand entrance that translates to a better presence on the street.

-Removed the limit on top-story floor height to enable things like cathedral ceilings.

-added basements for completeness' sake.

Building height: Provisions for permitted heights in stories. The minimum height for all first floors is twelve (12) feet. The maximum height for first floor residential development must be fourteen (14) feet and twenty (20) feet for nonresidential. Institutional building types may receive a waiver from the Planning Commission (see IT institutional building type and Section 122-780). The minimum height for second story and higher is ten (10) feet. The maximum height for second story and higher must not exceed twelve (12) feet. Each building lot typology provides the range of height appropriate for the building type. Height must be measured from finished floor.

12/19: Added exceptions to height requirements here to match use-based. Refers to things like chimneys, towers, etc.

- (7) **Parking zones.** The amount of parking is determined by Article VI, Division 8 "Parking Types and Quantities," but the area in which parking may be provided is determined by building type. Driveways are permitted in any zone, provided all other requirements of this chapter have been met. The diagrams illustrate a corner lot on a primary and non-primary street. Zones are the lot area between the principal building and:
- Zone 1: the right-of-way of any primary street;
- Zone 2: any common interior lot line;
- Zone 3: any rear lot line;
- Zone 4: the right-of-way of any non-primary street.

ORIGINAL:


Parking provisions: The amount of parking must be determined by Article XIII of this Chapter. Parking provisions provide zones where parking is permitted. The parking zone refers to any uncovered parking area located on the parcel. Driveways are permitted in any zone provided the frontage requirements have been met as required by provided the frontage requirements have been met as required by building type. The diagram illustrates a Primary and Secondary street. Primary streets are streets that are addressed to the parcel of land. Secondary streets may or may not have access to the parcel. Zones are defined and illustrated by the lot area between the principal building frontage and:

Zone 1: the right-of-way of any primary street.

Zone 2: any common interior lot line.

Zone 3: any rear lot line.

Zone 4: the right-of-way of any secondary street.



- (8) **Private frontages.** The private frontage style may be noted as “required” or as “preferred.” If there are multiple frontages provided in the table, the applicant may choose which to provide per building.

ORIGINAL: (brought pieces to definitions. Bit about “frontage buildout” is obvious.) Private frontages, refers to the area that is attached or integrated into the primary building. The building types are either required or preferred. If there are multiple frontages provided in the table, the applicant may choose what private frontage to provide per building. The private frontage area may count towards the calculation of the frontage build out requirement under the “Building Envelope” category.

- (9) **Exceptions to Setbacks.** The following exceptions apply to setbacks for all building types:

- (i) **Historic Structure.** A structure may encroach up to within five feet of a required front or rear yard setback, or within three feet of a side yard setback, upon a recommendation from the Historic District Commission that contains a finding that such setbacks allow for the restoration of a historic feature and with Planning Commission approval.

ORIGINAL: “a) *Historic Structure Front and Rear Yard.* With Planning Commission approval, a structure, if deemed historic by the Ypsilanti Historic District Commission, may encroach up to within five feet of a required front or rear yard or within three feet within a side yard in order to allow the re-use of an existing historic structure or to enhance the authenticity of an historic site; provided that no part of any structure is located on or over any adjacent property.”

- (ii) **Accessory Structure Adjacent to Alley or Railroad.** Any setback for an accessory structure adjacent to an alley or railroad right-of-way is one foot.

- (10) **Double Frontage Lots.** In the case of a row of double frontage lots, one street must be designated as the front street for all lots in the row, with rear setbacks applying to the yards fronting the other street. If there are existing buildings in the same block fronting on one or both of the streets, the required minimum front yard setback must be observed on the street where buildings presently front.

- (c) **Infill and Redevelopment.** Additions, renovations, and new buildings on existing built parcels may require the assembly of building types. The building types are outlined by lot size, and can often fit within existing lots. For instance, an addition to an existing building that meets the setbacks for their building type, but is on a lot deeper than the maximum, does not need to adjust lot lines.

ORIGINAL: (clarified, hopefully) Infill and Redevelopment. Additions, renovations and new buildings on existing built parcels, will require the assembly of building types. The building types are outlined by lot size and will not necessarily need to be replatted or divided to meet the standards. For instance, an addition to an existing building that meets the setbacks in the following table but is on a lot larger than the maximum size does not need to adjust lot lines.

- (1) **Lot Requirements For New Construction.** Several buildings of either one type or multiple types are permitted on one lot, provided that each building type is provided at least the minimum area required by building type, and other requirements of this chapter are met. There is no requirement to plat or divide land to create lots on the existing parcel site. For example, a multiple-story building and a commercial mixed use building can be built on the same parcel, without any changes to the lot line locations or a lot split, as long as the other lot requirements for the district can be met. In a single-building type example, two rows of townhouses can be built on a single parcel, without changes or splits of the lot, as long as the width of each unit meets the lot requirements and the distance between the two buildings meets the side or rear yard setback for both buildings, whichever is applicable.

ORIGINAL: (clarified, hopefully) Lot Requirements For New And Infill Development. Lot requirements for parcels that may fit more than one building type or several buildings of the same type are permitted.

There is no requirement to plat or divide land to create lots on the existing parcel site. However, the building type's lot requirements as outlined in the table below must be met. For example, a multiple-story building and a commercial mixed use building can be built on the same parcel, without any changes to the lot line locations or a lot split, as long as the other lot requirements for the district can be met. In terms of buildings of a single type, two rows of rental townhouses can be built on a single parcel, without changes or splits of the lot, as long as the width of each unit met the lot requirements and the distance between the two buildings met the side or rear yard setback for both buildings, whichever is applicable.

(2) Lot and Block Requirements for Existing Buildings. In the event when an addition is proposed for an existing building, and the existing building exceeds the height requirements or encroaches on the setbacks for the building type, the City Planner must determine if an administrative waiver can be granted, or if it should require a review by the Planning Commission. An administrative waiver can be issued with a finding that the existing building with proposed additions will not cause the block perimeter to exceed a total length of 1,600 feet in the C, CN, CN-Mid, and CN-SF districts or 2,000 feet in the HC, NC, GC, and HHS districts; or a block side length of 400 feet in the C, CN, CN-Mid, and CN-SF districts or 500 feet in the HC, NC, GC, and HHS districts.

If the proposed additions to an existing building exceed the block requirements, the applicant is subject to review by the Planning Commission.

ORIGINAL: "In the event an existing building exceeds the lot requirements, the Planning Director must determine if a waiver can be granted or require a review by the Planning Commission. A waiver can be issued if the existing and or proposed additions do not exceed the District's block area and perimeter defined in subsection 122-273(d)5.
4. If the proposed additions to an existing building exceed the block requirements, the applicant may be subject to review by the Planning Commission."

MA MANSION

Mansions are generally very large buildings originally built as residences, located on very large lots that distinguish the building from others nearby with expansive yards. They generally have a single primary entrance.

This building type is only permitted as a Limited building type.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	14,440	--
B	Lot width (ft)	120	--
C	Lot depth (ft)	120	--
D	Lot coverage (%)	--	30
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	30 ⁽¹⁾	--
F	Side setback (interior lot line) (ft)	25	--
G	Rear setback (ft)	40	--
H	Frontage buildout (%)	--	--
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	5	--
K	Rear setback (ft)	5	--
L	Building footprint (sf)	--	1,200
Note: there is a maximum of two accessory buildings.			
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	3
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the front, side, street-side, and rear yards.	

(1) Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



ES ESTATE

Large buildings, built as residences, located on large lots that accommodate large yards. They generally have distinguishing architectural features and one primary entrance.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	9,600	21,780
B	Lot width (ft)	80	120
C	Lot depth (ft)	120	--
D	Lot coverage (%)	--	30
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	20 ⁽¹⁾	--
F	Side setback (interior lot line) (ft)	10	--
G	Rear setback (ft)	25	--
H	Frontage buildout (%)	--	80
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	5	--
K	Rear setback (ft)	5	--
L	Building footprint (sf)	--	950
Note: there is a maximum of two accessory buildings.			
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	3
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side, street-side, and rear yards.	
PRIVATE FRONTAGES		Porch or Stoop required.	

(1) Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



HS HOUSE

Houses are detached, generally single-family dwelling units. They are located on lots that accommodate a primary building with small side yards and relatively large rear or front yards. They generally have one primary entrance.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	4,000	12,000
B	Lot width (ft)	35	80
C	Lot depth (ft)	100	--
D	Lot coverage (%)	--	60
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	15 ⁽¹⁾	25
F	Side setback (interior lot line) (ft)	5	--
G	Rear setback (ft)	20	--
H	Frontage buildout (%)	60	80
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	5	--
K	Rear setback (ft)	5	--
L	Building footprint (sf)	--	800
Note: there is a maximum of two accessory buildings.			
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	3
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side, street-side, and rear yards.	
PRIVATE FRONTAGES		Porch or Stoop required.	

(1) Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



CO COTTAGE

Cottages are generally small residential buildings, sized for a single dwelling, located on lots that accommodate a detached primary building with small yards. They are generally a single-story building or bungalow with a single primary entrance.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	2,500	6,300
B	Lot width (ft)	25	35
C	Lot depth (ft)	50	150
D	Lot coverage (%)	--	70
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	10 ⁽¹⁾	20
F	Side setback (interior lot line) (ft)	3	--
G	Rear setback (ft)	10	--
H	Frontage buildout (%)	70	90
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	5	--
K	Rear setback (ft)	5	--
L	Building footprint (sf)	--	500
Note: there is a maximum of two accessory buildings.			
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	2
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side, street side, and rear yards.	
PRIVATE FRONTAGES		Porch or Stoop required.	

(1) Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



TH TOWNHOUSE

Townhouses consist of rows of attached residential buildings. They are located on lots which accommodate a building with more than one dwelling unit, party walls, and a private back yard. Each dwelling has its own entrance to the street.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	1,200	3,000
B	Lot width (ft)	15	25 ⁽²⁾
C	Lot depth (ft)	80	120
D	Lot coverage (%)	--	60
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	10 ⁽¹⁾	20 ⁽²⁾
F	Side setback (interior lot line) (ft)	0 ⁽²⁾	--
G	Rear setback (ft)	15	--
H	Frontage buildout (%)	90	100
Note: A maximum of six units may be provided in a row.			
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	5	--
K	Rear setback (ft)	5	--
L	Building footprint (sf)	--	800
Note: there is a maximum of two accessory buildings.			
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	3
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the rear yard.	
PRIVATE FRONTAGES		Porch or Stoop required.	

- (1) Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.
- (2) End unit lot may be up to ten feet larger.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



AH APARTMENT HOUSE

Apartment Houses may be buildings converted from single-family detached buildings or built to resemble them that contain two or more dwelling units, with lots that accommodate the parking and outdoor living areas for several dwellings.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	4,000	18,000
B	Lot width (ft)	40	120
C	Lot depth (ft)	100	150
D	Lot coverage (%)	--	50
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	15 ⁽¹⁾⁽²⁾	25
F	Side setback (interior lot line) (ft)	5	--
G	Rear setback (ft)	20	--
H	Frontage buildout (%)	60	80
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30 ⁽¹⁾	--
J	Side setback (ft)	5	--
K	Rear setback (ft)	5	--
L	Building footprint (sf)	--	800
Note: there is a maximum of two accessory buildings.			
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	3
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side, street side, and rear yards.	
PRIVATE FRONTAGES		Porch or Stoop required.	

- (1) Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.
- (2) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



CA COURTYARD APARTMENT

A Courtyard Apartment is generally a grouping of apartment buildings arranged around and fronting on a central courtyard that may be partially or wholly open to the street, on a lot that accommodates the associated parking and outdoor living areas. Each dwelling may have its own entrance.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	6,400	20,000
B	Lot width (ft)	80	200
C	Lot depth (ft)	80	180
D	Lot coverage (%)	--	80
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	10(1)	20
F	Side setback (interior lot line) (ft)	0	10
G	Rear setback (ft)	10	--
H	Frontage buildout (%)	50	75
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	5	--
K	Rear setback (ft)	5	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	2	4
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side and rear yards.	
PRIVATE FRONTAGES		Forecourt required.	

(1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



AB APARTMENT BUILDING

Apartment Buildings are generally multiple-story multifamily residential buildings, located on lots that may be as large as a city block and can accommodate two or more buildings and accessory parking, waste disposal, and outdoor living areas.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	4,000	90,000
B	Lot width (ft)	30	300
C	Lot depth (ft)	100	300
D	Lot coverage (%)	--	80
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	10 ⁽¹⁾	25 ⁽¹⁾
F	Side setback (interior lot line) (ft)	5	--
G	Rear setback (ft)	15 ⁽²⁾	--
H	Frontage buildout (%)	60	80
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	10	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	2	6
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side and rear yards.	
PRIVATE FRONTAGES		Porch, Stoop, or Forecourt required.	

- (1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.
 (2) When adjacent to existing detached single-family homes, the rear setback shall be a minimum of 25 feet.



EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



CS COMMERCIAL/ MIXED-USE - SMALL

These are generally small multiple-story buildings designed for commercial uses on the ground floor and dwellings or offices above, located on lots that can accommodate a building that is less than 20% of that block's width.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	1,800	7,200
B	Lot width (ft)	15	60
C	Lot depth (ft)	80	120
D	Lot coverage (%)	--	90
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	0 ⁽¹⁾	15 ⁽¹⁾
F	Side setback (interior lot line) (ft)	0	--
G	Rear setback (ft)	5	--
H	Frontage buildout (%)	80	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	3	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	2	5
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side and rear yards.	
PRIVATE FRONTAGES		Commercial required.	

(1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



CM**COMMERCIAL/
MIXED-USE - MEDIUM**





These are generally moderately-sized multiple-story buildings designed for commercial uses on the ground floor and dwellings or offices above, located on lots that can accommodate a building that spans 20-40% of that block's width.

LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	--	60,000
B	Lot width (ft)	60	120
C	Lot depth (ft)	--	500
D	Lot coverage (%)	--	90
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	0 ⁽¹⁾	15 ⁽¹⁾
F	Side setback (interior lot line) (ft)	0	--
G	Rear setback (ft)	10 ⁽²⁾	--
H	Frontage buildout (%)	90	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	10	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	2	5
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side and rear yards.	
PRIVATE FRONTAGES		Commercial required.	

- (1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.
 (2) When adjacent to existing detached single-family homes, the rear setback shall be a minimum of 25 feet.



EXAMPLE

LOT REQUIREMENTS AND BUILDING ENVELOPE**ACCESSORY BUILDING ENVELOPE****BUILDING HEIGHT****PARKING LOCATION**

CL COMMERCIAL/ MIXED-USE - LARGE

These are generally large multiple-story buildings designed for commercial uses on the ground floor and dwellings or offices above, located on lots that can accommodate a building that spans up to an entire block's width.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	--	150,000
B	Lot width (ft)	120	300
C	Lot depth (ft)	--	500
D	Lot coverage (%)	--	90
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	0 ⁽¹⁾	15 ⁽¹⁾
F	Side setback (interior lot line) (ft)	0	--
G	Rear setback (ft)	10 ⁽²⁾	--
H	Frontage buildout (%)	90	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	10	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	2	8
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION			
Permitted in the side and rear yards.			
PRIVATE FRONTAGES			
Commercial required.			

- (1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.
 (2) When adjacent to existing detached single-family homes, the rear setback shall be a minimum of 25 feet.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



SC SINGLE STORY COMMERCIAL BUILDING			
These are generally designed for a single commercial use, located in lots that accommodate accessory parking, loading, and waste disposal areas.			
LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	7,500	90,000
B	Lot width (ft)	50	300
C	Lot depth (ft)	100	300
D	Lot coverage (%)	--	60
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	5 ⁽¹⁾	15 ⁽¹⁾
F	Side setback (interior lot line) (ft)	0	--
G	Rear setback (ft)	15 ⁽²⁾	--
H	Frontage buildout (%)	50	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	10	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	1
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION			
Permitted in the side, street side, and rear yards.			
PRIVATE FRONTAGES			
Commercial required.			


(1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.

(2) When adjacent to existing detached single-family homes, the rear setback shall be a minimum of 25 feet.




EXAMPLE

LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



LS

LARGE SINGLE STORY COMMERCIAL BUILDING

These are generally designed for more than one commercial use, each generally with its own entrance, located in lots that accommodate accessory parking, loading, and waste disposal areas.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	90,000	--
B	Lot width (ft)	300	block
C	Lot depth (ft)	300	block
D	Lot coverage (%)	45	80
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	5 ⁽¹⁾	15 ⁽¹⁾
F	Side setback (interior lot line) (ft)	0	--
G	Rear setback (ft)	10 ⁽²⁾	--
H	Frontage buildout (%)	50	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	10	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	1
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side, street side, and rear yards.	
PRIVATE FRONTAGES		Commercial required.	

- (1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.
 (2) When adjacent to existing detached single-family homes, the rear setback shall be a minimum of 25 feet.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



MB MULTIPLE STORY BUILDING

These are generally designed for more than one commercial use or user, with a common entrance on the ground floor. They are located on lots that accommodate accessory parking, loading, and waste disposal areas, spanning up to an entire block width.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	--	150,000
B	Lot width (ft)	120	block
C	Lot depth (ft)	--	500
D	Lot coverage (%)	--	90
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	5 ⁽¹⁾	25 ⁽¹⁾
F	Side setback (interior lot line) (ft)	0	--
G	Rear setback (ft)	10 ⁽²⁾	--
H	Frontage buildout (%)	50	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	10	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	2	6
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side, street side, and rear yards.	
PRIVATE FRONTAGES		Commercial required.	

- (1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.
 (2) When adjacent to existing detached single-family homes, the rear setback shall be a minimum of 25 feet.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



IT INSTITUTIONAL

These buildings are generally designed to house government, assembly, or institutional uses, on lots that can accommodate the primary building, associated parking, loading, waste disposal areas, and outdoor space.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	5,000	--
B	Lot width (ft)	50	block
C	Lot depth (ft)	100	block
D	Lot coverage (%)	--	60
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	15 ⁽¹⁾	--
F	Side setback (interior lot line) (ft)	0	--
G	Rear setback (ft)	15	--
H	Frontage buildout (%)	50	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	10	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	4 ⁽²⁾
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side, street side, and rear yards.	
PRIVATE FRONTAGES		None required.	

- (1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.
 (2) Additional height may be permitted by Planning Commission with a finding that the additional height is consistent with other buildings in that block.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION




Sec. 122-481. Porch

P **PORCH**

The façade is set back from the front lot line per applicable street setback requirements. The façade includes an attached front porch structure. A wide variety of porch designs are possible. Unenclosed porches can project up to ten feet into the required front yard.

PORCH DIMENSIONS		MIN	MAX
A	Clear span width (ft)	10	--
B	Depth (ft)	5	--
C	Height (ft)	7	--
YARD REQUIREMENTS			
D	Must be landscaped/pervious, with a path at least 3 feet wide connecting the porch to the sidewalk.		




Sec. 122-482. Stoop

S STOOP

The building façade is set back from the front lot line per applicable street setback requirements. The façade includes an attached entry stoop (an elevated landing with stairs) that is placed at or near the front lot line. The ground floor is elevated to provide privacy. The stoop may include a roof.

STOOP DIMENSIONS		MIN	MAX
A	Clear span width (ft)	5	8
B	Depth (ft)	3	8
C	Height (ft)	7	--
YARD REQUIREMENTS			
D	Must be landscaped/pervious, with a path at least 3 feet wide connecting the porch to the sidewalk.		




Sec. 122-483. Forecourt

F FORECOURT

The façade is set back from the front lot line per applicable street setback requirements. A portion of the façade is recessed to form an uncovered court. The court is suitable for outdoor dining, gardens, formal entries etc.. A fence, wall, or landscaping may be used to define the private space of the court. The court may be elevated behind a retaining wall at or near the front lot line with entry steps to the court.

FORECOURT DIMENSIONS		MIN	MAX
A	Clear span width (ft)	12	--
B	Depth (ft)	12	50
YARD REQUIREMENTS			
C	Must be landscaped/pervious, with a path at least 6 feet wide connecting the building entrance to the sidewalk.		




Sec. 122-484. Commercial

C COMMERCIAL

The façade is set back from the front lot line per applicable street setback requirements, typically at or near the front lot line with the entrance at sidewalk grade. The façade may include an awning, shed roof, or gallery (a lightweight colonnade with no habitable building space above it) that covers the sidewalk and may extend into the right-of-way. The facade has a substantial amount of glazing at the sidewalk level. Recessed entrances are acceptable.

FAÇADE DIMENSIONS		MIN	MAX
A	Distance between openings (ft)	--	2
B	Door recess (ft)	--	5
C	Ground floor transparency (%)	60	--
D	Height to bottom of window (ft)	--	2.5
YARD REQUIREMENTS			
E	Must be landscaped/pervious, with a path at least 6 feet wide connecting the building entrance to the sidewalk.		
OPTIONAL AWNING OR GALLERY			
F	Setback from curb (ft)	2	--
G	Clear depth - awning (ft)	4	10
	Clear depth - gallery (ft)	8	10
H	Clear height (ft)	8	--



Secs. 122-485 – 499. Reserved.

Article V: Use Regulations

ORIGINAL: article xii, specific standards for certain uses. 122-771 thru 830.

122-500. Purpose. (771)

It is recognized that there are certain uses that, due to size, location, use, or intensity, may adversely impact surrounding properties if not regulated. Such uses are generally listed within this chapter as special uses within specified zoning districts. This article states specific standards for approval of such uses in order to eliminate or mitigate any potential adverse impacts these uses may have on surrounding properties.

122-501. Compliance with article. (772)

3860 The uses in this article, whether specifically allowed as permitted uses, permitted accessory uses, or special uses in any zoning district, may only be approved, established, operated, used, expanded or enlarged in accordance with the specific provisions listed in this article.

Secs. 122-502 – 509. Reserved.

Division 1: Specific Standards For Certain Uses

OVERALL: redundancies (specific callouts to things like lighting that are a given; a separate parking requirement) have generally been removed. Please flag if you see any that remain. References to signage have also been removed.

A

Sec. 122-510. Adult drop-in centers or neighborhood counseling centers. (793)

- 3870 Adult drop-in centers or neighborhood counseling centers are subject to the conditions hereinafter imposed:
- (a) Access to and from the site must be directly to a major street as defined in §122-673, or to a major street through an HHS or a nonresidential district. In no event may access be through an R1, MD, CN, CN-Mid, or CN-SF district.
 - (b) Social services, such as food and/or clothing distribution or other similar services, are permitted only if the Planning Commission should find that adequate ingress and egress, parking, and indoor waiting and storage areas are provided.

Sec. 122-511. Adult foster care small homes with more than six persons for whom care is being provided, adult foster care large group homes, and adult foster care congregate facilities. (773)

- 3880 Adult foster care small homes with more than six persons for whom care is being provided, adult foster care large group homes, and adult foster care congregate facilities are subject to the conditions hereinafter imposed:
- (a) All such facilities must be registered with or licensed by the state and must comply with the minimum state standards for such facilities and the Building Code.
 - (b) For each adult cared for, the square footage of outdoor recreation or relaxation area required by the Building Code and licensing agency must be provided in the rear, side, or street side yard. Such outdoor space must be fenced and screened from any adjacent lot.
 - (c) If the owner of the property does not reside on the premises, the owner must appoint a resident manager, who must reside on the premises. The property owner must provide the name and contact information of this person to the Building Department, and keep such information up-to-date.
 - (d) Uses must not be located within 200 feet of property zoned R1 or CN-SF.
 - 3890 (e) All new construction or additions to existing buildings shall be compatible with the scale and character of the surroundings, and exterior building materials shall be harmonious with other buildings in the neighborhood.
 - (f) Screening in accordance with §122-634 shall be provided along all rear and side yard boundaries between the proposed use and property either zoned or used for single-family and two-family purposes.

ORIGINAL: removed parking requirements. Added in architectural compatibility. Removed foster family group homes- not permitted nor acceptable practice to regulate. CN-Mid removed from location exclusion because is a special use in CN-Mid.

DISCUSS: Consider reducing or removing location exclusion overall.

Sec. 122-773. Adult foster care small and large group homes, adult foster care congregate facilities and foster family group homes.

- 3900 Adult foster care small and large group homes, adult foster care congregate facilities and foster family group homes must be permitted subject to the conditions hereinafter imposed:

- (1) All such facilities must be registered with or licensed by the state and must comply with the minimum state standards for such facilities and the city housing code.
- (2) For each adult cared for, the square footage of outdoor recreation or relaxation area required by the Building Code and licensing agency must be provided. Such outdoor space must be fenced and screened from any adjacent lot located within a residential district.
- (3) At least one off-street parking space must be provided for each caregiver working at the facility.
- (4) A resident manager must be employed or appointed if the owner does not live in the house.
- 3910 (5) Uses other than family day care homes, adult foster care family homes, foster family homes and foster family group homes, must not be located within 200 feet of property zoned R1 or CN-Mid and CN-SF.

Sec. 122-512. Adult regulated uses. (774)

- (a) In the development and execution of this section, it is recognized that there are certain uses, which by their very nature are recognized as having serious objectionable operational characteristics, particularly when several of them are concentrated in a small area, thereby having a deleterious effect on surrounding neighborhoods. Regulation of the location of these uses is necessary to ensure that the adverse effects of such businesses will not cause or contribute to the blighting or downgrading of the City's residential neighborhoods or commercial centers. It is the intent of this section to provide reasonable regulations for the establishment of adult regulated

- 3920 uses in a viable, accessible location where the adverse impact of their operations may be minimized. Uses subject to these regulations and the requirements of **Article V of Chapter 10** are as follows:
- (1) Adult: Adult book or supply store, adult hotels or motels, adult motion picture theater/adult live stage performing theater, and adult mini-motion picture theater.
 - (2) Cabarets.
 - (3) Massage parlors and massage establishments.
 - (4) Pawnshops.
- 3930 (b) No adult regulated use may be permitted within 1,000 feet of any other adult regulated use. Measurement of the 1,000-foot radius must be made from the outermost boundaries of the lot or parcel on which the adult regulated use is proposed. The Planning Commission may waive this requirement for pawnshops if the following findings are made that:
- (1) The proposed use will not be contrary to the public interest or injurious to nearby properties, and that the spirit and intent of this article is observed.
 - (2) The proposed regulated use will not enlarge or encourage the development of a "skid-row" or blighted area.
 - (3) The establishment of an additional adult regulated use in the area will not be contrary to any program of neighborhood conservation nor will it interfere with any program of urban revitalization.
 - (4) All applicable regulations of this chapter will be observed.
- The Planning Commission may not waive this locational requirement for adult uses, cabarets, massage parlors, or massage establishments.
- 3940 (c) No adult regulated use may be permitted within 500 feet of any R1, HHS, P, MD, CN, CN-Mid and CN-SF district; nor may any adult regulated use be permitted within 500 feet of any school, park, library, playground, movie theater, licensed child care facility, or any other area or use where minor children are likely to congregate; nor may any adult regulated use be permitted within 500 feet of any religious institution. Measurement must be from the outermost boundaries of the lot or parcel on which the adult regulated use is proposed to be located. This prohibition may be waived if the Planning Commission is presented with a validated petition requesting such waiver, signed by two-thirds of all persons owning, residing in, or doing business in the area within 500 feet of the proposed adult regulated use. The circulator of the petition must sign an affidavit attesting that the circulator personally witnessed the signatures and the signatures were affixed to the petition by the person whose name appears thereon. The signatures must be validated by the community economic development department. The Planning Commission cannot consider the waiver of the locational requirements until the required petition has been duly filed and verified. Pawnshops are not be subject to these locational requirements.
- 3950 (d) The building and premises must be designed and constructed so that material depicting, describing, or relating to specified sexual activities or specified anatomical areas, cannot be observed by pedestrians or from vehicles on any public right-of-way. This provision must apply to any display, decoration, sign, show window, or other opening.
- (e) No person may reside in or permit any person to reside in the premises of an adult regulated use.
- (f) Such uses must comply with all applicable federal, state, and local licensing regulations. Initial and annual proof of such compliance must be a condition of special use approval and the continuance thereof.
- 3960 (g) Upon finding that any condition, safeguard, or requirement has been breached, the Building Department can revoke any occupancy permit. All operations must cease 14 days following such notification of revocation by the Building Department, unless such violations are corrected. Also, if violations are not corrected within 14 days, reinstatement of a revoked permit must require a new special use application and approval thereof.

Sec. 122-513. Alternative Energy. (788)

Alternative energy production is subject to the conditions hereinafter imposed:

- (a) Photovoltaic Production
- (1) Attached accessory photovoltaic structures are permitted in all zoning districts when meeting the following requirements:
 - (i) Positioning. All attached photovoltaic structures positioning and attachment must meet Building Department requirements for snow loads and wind loads.
 - 3970 (ii) Height. All attached photovoltaic structures must meet the following height regulations by type:
 - (a) Maximum. The maximum height of photovoltaic roof paneling installed on a sloped roof or flat roof of a building is ten feet above the maximum building height allowed for that zoning district or building type . Photovoltaic panels attached to the side of a structure must not project vertically above the building height allowed for that zoning district or building type.
 - (2) Detached accessory photovoltaic structures, when mounted top-of-pole for outdoor lights, are permitted in all zoning districts. In no instance may such panels exceed 20 feet in height.
 - (3) Solar farms. On sites where the primary use is photovoltaic energy production, all structures must meet the

height requirement of the zoning district.

- 3980 (i) Abandonment. Any freestanding photovoltaic system which is not used for six (6) months will be deemed to be abandoned. The applicant/permit holder will be so notified in writing by the municipality and requested to dismantle the site and return it to its original state. If there are mitigating circumstances as to why the site has not been used, the applicant/permit holder may contact the municipality and request a three-month extension. If a site has been deemed abandoned and no request for an extension is received, the applicant/permit holder will again be notified to dismantle the site and return it to its original state. If the applicant/permit holder does not do this, the municipality will have the removal and restoration done at the owner/applicant's expense. Removal will include removing posts, equipment, panels, foundations and other items so that the ground is restored to its preconstruction state and is ready for development as another land use.
- 3990 (b) Solar water heating. Attached accessory solar water heating systems are permitted in all zoning districts. Solar collectors installed on a sloped roof of a building must not project vertically above the peak of the roof. Solar collectors attached to a flat roof must not project vertically more than 10 feet above the roof. Solar panels attached to the side of a structure must not project vertically above the building height allowed for that zoning district or building type.
- (c) Wind energy production. Attached accessory wind energy production structures are permitted in all zoning districts, subject to height limitations.
- (d) Geothermal energy production. Attached accessory geothermal energy production systems are permitted in all zoning districts.
- (e) Other methods. Other methods of alternative energy production may be submitted to the City Planner and, at their discretion, may be approved, approved subject to another City department(s) review, approved subject to Planning Commission review, or denied
- 4000

Sec. 122-514. Auction House. (812)

Auction Houses are subject to the conditions hereinafter imposed:

(a) The applicant shall provide a use statement with the following information:

- The maximum capacity of the facility;
- Number and frequency of the auctions;
- Method for providing parking during auctions;
- An acknowledgement that any outdoor activities are subject to the requirements for open-front or open-air businesses, and that such are only permitted in certain zoning districts and may have additional requirements.

4010 REMOVED: (redundant)

Any outdoor activities are subject to the requirements for open-front or open-air businesses (section 122-798) and are only permitted in those districts that permit open-front businesses as a permitted or special use subject to the standards for those districts.
Added that fourth clause instead.

Sec. 122-515. Automobile service or repair. (775)

Automobile service and repair are subject to the conditions hereinafter imposed:

- (a) All lubrication equipment, hoists, and pits must be enclosed entirely within a building. All repair operations must take place within a completely enclosed building, and such building must not be located within 100 feet of any interior lot line abutting a residentially zoned district.
- 4020 (b) The entire lot, excluding areas occupied by landscaping and building, must be hard-surfaced with concrete or plant-mixed bituminous material. Curbs of at least six inches in height must be installed around the perimeter of all surfaced areas. Drainage must be provided in accordance with [§122-683](#).
- (c) The storage, sale or rental of new or used automobiles, trucks, trailers, and any other vehicles on the premises is prohibited. Vehicles awaiting repair, or inoperable, wrecked, or partially dismantled vehicles, must not be stored or parked outside for a period exceeding seven days.

REMOVED (D): duplicates existing requirements in parking quantity sections.

Sec. 122-516. Automobile filling stations. (776)

Automobile filling stations are subject to the conditions hereinafter imposed:

- 4030 (a) The curb cuts are not permitted at such locations that will tend to create traffic hazards in the streets immediately adjacent thereto. Entrances must be no less than 25 feet from a street intersection (measured along the road right-of-way). Drives must be no less than 20 feet wide, nor wider than 30 feet at the right-of-way line. No more than one such drive or curb opening may be permitted for every 75 feet of frontage along any street or in accordance with county or state requirements, whichever is greater.

- (b) The entire lot, excluding areas occupied by landscaping and building, must be hard-surfaced with concrete or plant-mixed bituminous material. Curbs of at least six inches in height must be installed around the perimeter of all surfaced areas. Drainage must be provided in accordance with §122-683.
- (c) All fuel pumps must be located not less than 15 feet from any lot line; provided however, that fuel pumps may not be located less than 40 feet from any interior lot line which abuts residentially zoned property, nor closer than 100 feet from any religious institution, theater, hall, or other place of public assembly.
- 4040 (d) A rigid canopy which covers the fuel dispensing area is permitted provided that the lowest edge of such canopy must be a minimum of 14 feet above grade. All support structures for canopies must be located so as not to obscure the vision of motorists using any nearby streets, driveways, or maneuvering aisles.
 - (1) For service stations located within a NC zoning district, the nearest edge of any canopy must be set back a minimum of 10 feet from any lot line.
 - (2) For service stations located within a GC zoning district, the nearest edge of any canopy must be set back a minimum of 15 feet from any lot line.
- (e) The storage, sale, or rental of new or used automobiles, trucks, trailers, or any other vehicles on the premises is prohibited. Inoperable, wrecked or partially dismantled vehicles must not be stored or parked outside for a period exceeding two days.

4050 **Sec. 122-517. Automobile wash establishments. (777)**

Automobile wash establishments are subject to the conditions hereinafter imposed:

- (a) All washing activities must be carried out within a building. Vacuuming activities may be permitted outdoors, provided such activities are located at least 50 feet from adjacent R1, P, MD, CN, CN-Mid and CN-SF districts or property with first-floor residential uses.
- (b) The entire lot, excluding areas occupied by landscaping and building, must be hard surfaced with concrete or plant-mixed bituminous material. Curbs of at least six inches in height must be installed around the perimeter of all surfaced areas. Drainage must be provided in accordance with §122-683.
- 4060 (c) Sufficient space must be provided on the lot so that vehicles do not enter or exit the wash building directly from an adjacent street or alley. All maneuvering areas, stacking lanes, and exit aprons must be located on the car wash parcel itself. Streets and alleys may not be used for maneuvering or parking by vehicles to be serviced by the automobile wash.

Sec. 122-518. Automobile parking garages. (781)

Automobile parking garages are permitted subject to the conditions hereinafter imposed:

- (a) Such use must not be located within 100 feet of an R1, CN-Mid or CN-SF district.
- (b) All parking garages in the Walkable Urban Districts shall be constructed under the IT building type.
- (c) The architectural style and facade of the structure must be in keeping with the character of surrounding residential and business uses.
- (d) All areas not used for parking or vehicular maneuvering must be landscaped and maintained in good condition.
- 4070 (e) No access from a major thoroughfare is permitted. The vehicle entrances to structured parking should be from side streets and/or access roads.
- (f) Direct pedestrian access from parking garages to any adjacent street must be provided.
- (g) The exterior facades of all parking garages fronting on any street must be designed to achieve an architectural unity with the block.
- (h) The parking garage must have sheltered bicycle and motorcycle parking areas within 25 feet of the vehicular entrance.

REMOVED: I think it was trying to say "zero lot line in the HD"- but there are other locations where we'd want that, too..

"Parking garages must comply with all building design standards for building façade, scale, building features and lighting, compatibility, and placement on the site when located in the Historic District."

And

"The City may approve other design alternatives, such as liner buildings around the outer edge of the garage."

ADDED: walkable urban district IT type.

Sec. 122-519. Automobile parking lot as principal use. (782)

A parking lot as a principal use is permitted subject to the conditions hereinafter imposed:

- (a) Parking lots must meet all dimensional requirements for off-street parking in accordance with Article VI, Division 7 of this chapter.
- 4090 (b) Parking lots must contain an amount of bicycle spaces equal to 5% of the number of vehicle spaces year-round;

another 5% must be provided April-October, with that area being used for snow storage or additional vehicle parking during the winter months.

- (c) Parking lots must contain twice the number of barrier-free parking spaces as would be required under Michigan Barrier-Free code, with no fewer than two barrier-free spaces being provided.

ORIGINAL:

A parking lot as a principal use is permitted subject to the conditions hereinafter imposed:

- (1) If the lot is located on or adjacent to a permitted or special use which it is intended to serve, the minimum number of parking spaces intended to serve that use must be provided.
- (2) A lighting plan must be submitted for lots which contain more than 20 spaces, which must be approved by the Planning Commission during site plan review.
- (3) Parking lots must meet all requirements for off-street parking in accordance with Article XIII of this chapter.

B

Sec. 122-520. Bed and breakfasts and inns. (778)

Bed and breakfast lodgings and inns are subject to the conditions hereinafter imposed:

- (a) When located within the CN, CN-Mid, CN-SF, or R1 zoning districts the structure to be used as a bed and breakfast lodging must be the principal residence of the owner/operator; in all other zoning districts, it must be the principal residence of the owner/operator or a resident manager. In either case, such party must live on the premises when the bed and breakfast lodging is in operation. A minimum of 450 square feet of living space must be reserved for the owner/operator's or resident manager's quarters.
- (b) If the owner of the property does not reside on the premises, the property owner must provide the name and contact information of resident manager to the Building Department, and keep such information up-to-date.

ADDED 12/15/2016 to be in line with other "resident manager" provisions.

- (c) Rooms used for sleeping must have a minimum of 100 square feet for two occupants, plus an additional 50 square feet for each additional occupant.
- (d) When located within the CN, CN-Mid, CN-SF, or R1 zoning districts, food may only be served to guests staying at the bed and breakfast lodging. There may not be separate cooking facilities for the bed and breakfast lodging other than those which serve the principal residence. In other districts, the establishment may operate a restaurant on the premises, provided that all requirements of this chapter related to restaurants, as well as any other applicable regulations, are met; and provided that no expansion of the residential building in order to accommodate a restaurant is made.

ORIGINAL: B&Bs/inns had been two separate things in the longago code, the merge wasn't clean. Cleaned up; removed the (duplicative) parking requirements, removed the bit about structure/roominghouseness (not necessary), removed licensing (we don't), and removed inspections (covered under separate ordinance)

- (1) The structure to be used as a bed and breakfast lodging must be the principal residence of the owner/operator and such owner/operator must live on the premises when the bed and breakfast lodging is in operation. In the case of an inn, the owner may reside elsewhere so long as a resident manager is employed and lives on the premises. A minimum of 450 square feet of living space must be preserved for the owner/operator's quarters.
- 2) Rooms used for sleeping must have a minimum of 100 square feet for two occupants, plus an additional 50 square feet for each additional occupant. Rooms must be designed to accommodate no more than four occupants.
- (3) Food may only be served to guests staying at the bed and breakfast lodging. There may not be separate cooking facilities for the bed and breakfast lodging other than those which serve the principal residence. An inn may operate a restaurant on the premises, provided that all requirements of this chapter related to restaurants, as well as any other applicable regulations, are met; and provided that no expansion of the residential building in order to accommodate a restaurant is permitted.
- (4) Two off-street parking spaces must be provided plus one additional space per room to be rented. An inn which operates a restaurant must also meet the parking requirements for the restaurant, in addition to the above requirement.
- (5) Changes to the building structure must not be made that would prevent the structure from being reverted in the future to any residential use permitted in the zoning district. Bed and breakfast lodgings or inns may not be converted to a roominghouse unless a special use permit is approved by the Planning Commission in accordance with Article V of this chapter.
- (6) Bed and breakfast lodgings and inns are subject to city licensing provisions, and must be inspected every two years for compliance with this chapter and the city building code.

C

Sec. 122-521. Child care centers and group day care homes. (779)

Child care centers and group day care homes are subject to the conditions hereinafter imposed:

- (a) All child care centers and, group day care homes must be registered with or licensed by the state department of social services and must comply with the minimum state standards for such facilities.
- (b) The square footage of outdoor recreation area required by the Building Code and licensing agency must be provided in the rear, side, or street side yard. Such outdoor space must be fenced and screened from any adjacent lot.

4160

ORIGINAL:

Removed parking requirement - duplicative. Removed drop-off centers because state does not define them separately (or at all- and nor did we, nor could we figure out what it meant)

Child care centers, child drop-off centers or group day care homes (not including dormitories) are permitted subject to the conditions hereinafter imposed:

- (1) All child care centers, child drop-off centers and group day care homes must be registered with or licensed by the state department of social services and must comply with the minimum state standards for such facilities.
- (2) The square footage of outdoor recreation required by the Building Code and licensing agency must be provided and maintained. Such space must be fenced and screened from any adjoining lot in any residential district.
- (3) At least one off-street parking space for each care giver must be provided. Additional off-street or on-street spaces must be made available for the safe drop-off and pick-up of persons being cared for at the facility. Such drop-off-sites must not obstruct the flow of traffic along any public thoroughfare.
- (4) Child drop-off centers care for minor children for longer periods than four (4) hours.

4170

D

Sec. 122-522. Drive-through or drive-in facilities. (784&783)

Drive-through or drive-in facilities in combination with any kind of other use are subject to the conditions hereinafter imposed:

- (a) Uses must not be located within 100 feet of property zoned CN, CN-Mid, CN-SF, or R1 district, measured from the lot line.
- (b) Off-street loading and stacking spaces must be provided in accordance with §122-694.
- (c) Canopies and support structures associated with drive-through facilities must meet all minimum yard setback requirements for principal buildings.. The lowest edge of a canopy must be at least 12 feet above grade.
- (d) The sound from amplification equipment must not be audible beyond the boundaries of the site.
- (e) Uses must have direct access to a major thoroughfare in accordance with §122-673. Ingress and egress curb cuts to the site must be located at least 60 feet from the intersection of any two streets, measured along the nearest right-of-way line.
- (f) Any drive-through or drive-in facilities in C, HC, NC, GC must also provide for walk-up and bicycle users.

4190

ORIGINAL: was two sections- 783 & 784.

Combined and kind of split the baby- "drive through facilities" was less restrictive, but very seldom used.

Drive-through facilities in combination with any kind of store, financial institution, or personal service business are permitted subject to the conditions hereinafter imposed:

- (1) Drive-through windows or other facilities and stacking spaces must not be located within 50 feet of a residentially-zoned district. Off-street stacking spaces must be provided in accordance with section 122-840. Canopies and support structures associated with drive-through facilities must meet all minimum yard setback requirements.
- (2) All drive-in facilities must have direct access to a major thoroughfare in accordance with section 122- 642. Ingress and egress curb cuts to the site must be located at least 60 feet from the intersection of any two streets, measured along the nearest right-of-way line.
- (3) Devices for the transmission of voices must not be audible beyond the boundaries of the site.

4200

E

Sec. 122-523. Essential services. (637)

- (a) *General provisions.* Essential services which are located underground or involve the customary placing of utility poles in public rights-of-way or public easements or the placing of utility boxes in the rear of private properties,

4210

and which are reasonably necessary for the furnishing of adequate services for the public health, safety, or welfare must be permitted as authorized and regulated by law and other ordinances of the City in any zoning district.

- (b) *Public utility buildings.* The Planning Commission may authorize the erection, maintenance, and use of a building, or an alteration or addition to an existing building by a public utility as a special use and after site plan review in any zoning district, including a building with a height greater than otherwise permitted in the zoning district; provided that the Planning Commission finds that such building is necessary at a selected location, will not be injurious to the surrounding neighborhood, and is not contrary to the spirit or purpose of this chapter. Where possible, such buildings must be located in predominantly non-residential areas, rather than predominantly residential or multifamily areas.

4220

F

G

Sec. 122-524. Garage sales, rummage sales, yard sales, and owner-made craft sales. (670)

- (a) Duration. Each occasion may not take place for a period of time longer than 12 hours per day for a maximum of three consecutive days.
- (b) Number. There must be no more than three occasions per year on any premises.
- (c) Hours. All articles or property that are offered for sale must be totally enclosed within a lawful structure or building between the hours of dusk to dawn.

Sec. 122-525. Gardens/Community Gardens (815)

4230

The goal of this standard is to clarify within existing districts that gardening is allowed as an accessory use and to allow for interim or long term low-intensity gardens and/or community gardens on vacant lots in R1, CN, CN-Mid, and CN-SF districts-as long as the use provides minimal impacts to residential character, and minimal increase in traffic in and around related parcels.

Furthermore, the City of Ypsilanti is an urban environment, and while these provisions are intended to support the local food system, it is not the intent of these standards to create agricultural districts within the City. Additionally, if any gardening or related use invokes the State Right-to-Farm Act, then this section and related sections in this Chapter are to become null and void.

4240

- (a) All principal use gardens/community gardens in R1, CN, CN-Mid, and CN-SF districts must maintain a 3 foot setback on street frontages as well as meet traffic visibility regulations detailed in [§122-675](#). Further, they shall not encroach onto adjacent parcels or sights-of-way.
- (b) Sale of goods grown in a garden/community garden is prohibited on garden sites in residential districts. Sales of goods from greenhouse in business or other districts are subject to underlying district requirements.
- (c) The property shall be maintained in an orderly and neat condition and shall not be detrimental to the physical environment or to public health and general welfare, and remains subject to compliance with the Property Maintenance Code, noise ordinance, and related ordinances.
- (d) The property shall be maintained so as to prevent the free flow of storm water, irrigation water, chemicals, dirt, or mud across or onto adjacent lots, properties, public streets, or alleys.
- (e) Motorized equipment within a residential zoning district or residential planned unit development district shall be restricted to hours beginning at 8:00 a.m. and ending at 8:00 p.m.
- (f) Compost piles may only be used for waste generated on site, and are subject to accessory structure setbacks.
- (g) Gardens shall use integrated pest management techniques and best practices in accordance with [Chapter 110, Article IV of this Ordinance](#).

4250

Sec. 122-526. Group Residences and Roominghouses. (804)

Group residences and roominghouses are permitted subject to the following conditions:

- (a) The minimum usable floor area of the structure, size of common interior living space, and kitchen facilities must comply with the applicable Building Codes and Fire Codes adopted by the City of Ypsilanti. Kitchen facilities shall be provided on the premises for the residents therein.
- (b) Rooms for sleeping shall have a minimum square footage as required by the Building Code.
- (c) If the owner of the property does not reside on the premises, the owner must appoint a resident manager, who must reside on the premises. The property owner must provide the name and contact information of this person

4260

to the Building Department, and keep such information up-to-date.

- (d) A roominghouse or group residence permitted as a special use shall not be located within 200 feet of an R1 or CN-SF district.
- (e) For roominghouses or group residences permitted as a special land use access to and from the site shall be directly to a major street or to a major street through a CN, CN-Mid or nonresidential district. In no event shall access be through an R1 or CN-SF district.

H

Sec. 122-527. Home occupations. (669)

- 4270 (a) **Prohibited home occupations.** The following are not permitted as home occupations: animal grooming establishments, barber shops or beauty parlors with more than one stylist or chair, medical clinics or hospitals with more than one practitioner and one non-practicing staff, commercial stables, day care centers, kennels, real estate offices, restaurants, vehicle repair or painting, retail or wholesale sales of any items stocked on the premises, landscape installation and maintenance businesses, construction contractors, snow removal, funeral homes, nursing homes, antique shops, bed and breakfast establishments, private clubs, trailer rentals, adult regulated uses, millinery and other apparel shops, veterinarian's office, clinic or hospital, or any use that endangers the health, safety, and welfare of any other persons residing in that area by reason of noise, noxious odors, unsanitary or unsightly conditions, fire hazards and the like. This section is not intended to prohibit offices related to the administration of construction contracting, landscaping, maintenance, or snow removal businesses.
- 4280 (b) **Permitted home occupations.** Any home occupation that is not specifically prohibited by subsection (a) of this section must be permitted if it meets the following standards:
 - (1) All home occupations must obtain a business license from the City Assessor; if the occupant is not the owner of the premises then consent must be obtained from the property owner to ensure the owner's knowledge of the use.
 - (2) The home occupation must not change the outside appearance of the dwelling nor alter the residential character of the structure.
 - (3) The home occupation must not be visible from the street.
 - (4) The home occupation must be owned and operated only by a member or members of the immediate family residing on the premises.
 - 4290 (5) No more than one other person may be employed or involved with such activity on premises other than a member of the immediate family residing in the dwelling unit.
 - (6) All wholesale, jobbing or retail business must be conducted entirely by mail, telephone, electronically or by delivery.
 - (7) Services and transactions must be conducted by appointment only, walk-in trade is prohibited.
 - (8) The maximum area for home occupations must be calculated as 25 percent of the usable residential floor area of a dwelling unit or 300 feet whichever is less. Areas designated for home occupations may be located in any useable area of the home, the basement, or any accessory building.
 - (9) No motor power other than electrically operated motors may be utilized. No single electrical motor used in the home occupation may exceed one horsepower. All electrical motors and equipment used in the conduct of the home occupation must be shielded so as not to cause radio or television interference for adjoining properties.
 - 4300 (10) A home occupation must not create noise, dust, vibration, smell, smoke, glare, electrical interference, fire hazards, or any other hazard or nuisance to any greater or more frequent extent than would normally be generated in the zoning district in which it is located.
 - (11) In no case may a home occupation be open to the public earlier than 7:00 a.m. nor later than 9:00 p.m.
 - (12) There must be no deliveries to or from the home occupation with a vehicle having more than two axles.
 - (13) No merchandise or articles for sale may be displayed on the lot used for the home occupation.
 - 4310 (14) The home occupation may increase vehicular traffic flow and parking by no more than two additional vehicles at a time.
- (c) **Medical Marijuana Home Occupation.** In addition to the requirements in [§122-527](#), Medical marijuana home occupations must be subject to the following requirements:
 - (1) The medical use of marijuana must comply at all times and in all circumstances with the Michigan Medical Marihuana Act and the General Rules of the Michigan Department of Community Health, as they may be amended from time to time.
 - (2) A registered primary caregiver operating a medical marijuana home occupation must not be located within

1,000 feet of a school, as measured from the outermost boundaries of the lot or parcel on which the home occupation and school is located.

4320

- (3) Not more than one (1) primary caregiver per parcel may be permitted to grow or cultivate medical marijuana.
- (4) Not more than five (5) qualifying patients may be assisted with the medical use of marijuana within any given calendar week.
- (5) All medical marijuana must be contained within an enclosed, locked facility inside a primary or accessory building.
- (6) All necessary building, electrical, plumbing and mechanical permits must be obtained for any portion of the building in which electrical wiring, lighting and/or watering devices that support the cultivation, growing or harvesting of marijuana are located.
- (7) If a room with windows is utilized as a growing location, any lighting methods that exceed usual residential periods between the hours of 11pm and 7am must employ shielding methods, without alteration to the exterior of the residence, to prevent ambient light spillage that may create a distraction for adjacent residential properties.
- (8) That portion of the building where energy usage and heat exceeds typical residential use, such as grow room, and the storage of any chemicals such as herbicides, pesticides, and fertilizers must be subject to inspection and approval by the Ypsilanti Fire Department to insure compliance with the Michigan Fire Protection Code.
- (9) The premises must be open for inspection upon request by the Building Official, the Fire Department and law enforcement officials for compliance with all applicable laws and rules, during the stated hours of operation/use and as such other times as anyone is present on the premises.

4330

Sec. 122-528. Homeless Shelter. (785)

4340

Shelters for the homeless are permitted subject to the conditions hereinafter imposed:

- (a) The facility must be operated by a recognized human service agency, incorporated by the state, and which is not for profit.
- (b) Resident manager and support services must be provided 24 hours a day, 7 days a week.
- (c) No such facility may be located within 1,000 feet of a similar facility.

I

Sec. 122-529. Indoor and Outdoor Recreation and Gyms. (802)

Indoor and Outdoor recreation and gyms are subject to the conditions hereinafter imposed:

4350

- (a) If the proposed use would attract persons from, or is intended to serve areas beyond the immediate neighborhood, the site shall have direct access to a major thoroughfare in accordance with §122-673.
- (b) The Planning Commission may reduce the number of off-street parking spaces required as specified in §122-692 in those instances with a finding that the users will originate from the immediately adjacent areas and will therefore be pedestrian.

4360

ORIGINAL: (changed to align title and to remove building restrictions; they do not apply to many of today's indoor rec facilities)

Sec. 122-802. Private noncommercial recreational areas or social facilities; institutional or community recreational centers; nonprofit swimming pool or tennis club. Private noncommercial recreational areas or social facilities, institutional or community recreational centers, and nonprofit swimming pool or tennis club shall be permitted subject to the conditions hereinafter imposed:

4370

- (1) If the proposed use would attract persons from, or is intended to serve areas beyond the immediate neighborhood, the site shall have direct access to a major thoroughfare in accordance with section 122- 642.
- (2) Except in the Neighborhoods, Centers, Corridors and Health and Human Services districts, front, side, and rear yards shall be at least eight feet wide, and shall be landscaped in trees, shrubs, and grass. All such landscaping shall be maintained in a healthy condition. In the Neighborhoods, Centers, Corridors and Health and Human Services districts, any buildings shall comply with the IT institutional building type.
- (3) The Planning Commission may reduce the number of off-street parking spaces required as specified in section 122-837 in those instances where it is specifically determined that the users will originate from the immediately adjacent areas and will therefore be pedestrian.

J

Sec. 122-530. Junkyards. (790)

Junkyards are permitted subject to the conditions hereinafter imposed:

- (a) The minimum lot size must be one acre.
- (b) No junkyard may be located within 300 feet of a R1, HHS, P, MD, CN, CN-Mid and CN-SF district.
- (c) A minimum setback of 50 feet must be maintained between the front property line and the portion of the property on which junk materials are placed or stored. Outdoor storage areas must also conform to all other setback requirements for principal buildings.
- 4380 (d) All outdoor storage areas for junkyards must be screened by a six-to eight-foot obscuring wall constructed of masonry, concrete or other similar material.
- (e) All roads, driveways, parking lots, and loading and unloading areas must be paved or treated in a manner approved by the City Building Department so as to confine any wind-borne dust to within the boundaries of the site.
- (f) Proper access to all parts of the storage areas must be provided for fire and emergency services, as required by the Building Code.

K

Sec. 122-531. Kennels, commercial. (791)

Commercial kennels are permitted subject to the conditions hereinafter imposed:

- 4390 (a) Any such kennel must be subject to all permit and operational requirements established by City, county, and state regulatory agencies.
- (b) Buildings in which animals are kept, animal runs, and exercise areas must not be located in any required yard setback areas, and must be located at least 300 feet from any dwellings and 100 feet from any buildings used by the public.
- (c) All outdoor animal runs or exercise areas must be fenced and secured at all times so that no animal contained therein may escape such enclosure.

L

M

Sec. 122-532. Medical Marijuana Dispensaries. (813)

- 4400 (a) The intent of the Zoning Ordinance is to regulate medical marijuana dispensaries and growing/manufacturing facilities by providing for regulations and fees in a manner that promotes and protects the public health, safety and welfare, mitigates potential impacts on surrounding properties and persons, and that conforms with the policies and requirements of the Michigan Medical Marijuana Act, MCL 333.26421, et seq (hereinafter "Act"). Nothing in this Chapter, or in any companion regulatory provision adopted in any other provision of this Code, is intended to grant, nor shall they be construed as granting, immunity from criminal prosecution for growing, sale, consumption, use, distribution, or possession of marijuana not in strict compliance with the Act or the General Rules. Also, since Federal law is not affected by the Act or the General Rules, nothing in this Chapter, or in any companion regulatory provision adopted in any other provision of this Code, is intended to grant, nor shall they be construed as granting, immunity from criminal prosecution under Federal law. The Act does not protect users, caregivers or the owners of properties on which the medical use of marijuana is occurring from Federal Prosecution, or from having their property seized by Federal authorities under the Federal Control Substances Act.
- 4410 (b) The following Standards for Medical Marijuana Dispensaries shall apply:
 - (1) The medical use of marijuana shall comply at all times and in all circumstances with the Michigan Medical Marijuana Act and the General Rules of the Michigan Department of Community Health, as they may be amended from time to time;
 - (2) The dispensary shall not be located within one thousand (1,000) feet of a school, as measured from the outermost boundaries of the lot or parcel on which the dispensary and school are located;
 - 4420 (3) The dispensary shall not be located within a five hundred (500) feet of a lawfully existing medical marijuana dispensary or growing/manufacturing facility as measured from the outermost boundaries of the lot or parcel on which the proposed dispensary and lawfully existing dispensary or growing/manufacturing facility is located;
 - (4) Smoking and/or use of medical marijuana shall be prohibited at the dispensary;
 - (5) All activity related to the dispensary shall be done indoors;

- 4430 (6) The premises shall be open for inspection upon request by the Building Official the Fire Department and law enforcement officials for compliance with all applicable laws and rules, during the stated hours of operation/use and as such other times as anyone is present on the premises.
- (7) Quarterly inspections may be made by the City Official's designee to confirm the dispensary or growing/manufacturing facility is operating in accordance with applicable laws including, but not limited to, State Law and City Ordinances;
- (8) Any medical marijuana dispensary shall maintain a log book and/or database identifying by date the amount of medical marijuana on the premises for each qualifying patient/caregiver, keeping the qualifying patient and caregiver information confidential. This log shall be available to law enforcement personnel to confirm that the medical marihuana dispensary does not have more medical marijuana than authorized at the location and shall not be used to disclose more information than is reasonably necessary to verify the lawful amount of medical marijuana at the facility. The facility shall maintain the confidentiality of qualifying patients in compliance with the Michigan Medical Marijuana Act, as amended.
- (9) If the dispensary ceases operation for a length of time of sixty (60) days or greater, the permit shall expire;
- 4440 (10) Dispensary drive-through facilities shall be prohibited;
- (11) All medical marijuana shall be contained within the main building in an enclosed, locked facility in accordance with the Michigan Medical Marijuana Act, as amended;
- (12) Application for a Medical Marijuana Dispensary License shall be made to the City Clerk upon application forms provided by the Clerk for Medical Marijuana Dispensary and signed by the applicant verifying the truth and accuracy of all information and representations in the application. Applications including information and documentation provided pursuant to an application shall be subject to the confidentiality rules under the Act. In addition to information and submittals, the application shall include payment of application fee in an amount set by the City Council;
- (13) The police department shall review the proposed application to operate a dispensary regarding public health, safety, and welfare concerns of the proposal;
- 4450 (14) Growing or cultivation of medical marijuana in a dispensary is prohibited.

Sec. 122-533. Medical Marijuana Growing/Manufacturing Facility. (814)

- 4460 (a) The intent of the Zoning Ordinance is to regulate medical marijuana dispensaries and growing/manufacturing facilities by providing for regulations and fees in a manner that promotes and protects the public health, safety and welfare, mitigates potential impacts on surrounding properties and persons, and that conforms with the policies and requirements of the Michigan Medical Marijuana Act, MCL 333.26421, et seq (hereinafter "Act"). Nothing in this Chapter, or in any companion regulatory provision adopted in any other provision of this Code, is intended to grant, nor shall they be construed as granting, immunity from criminal prosecution for growing, sale, consumption, use, distribution, or possession of marijuana not in strict compliance with the Act or the General Rules,. Also, since Federal law is not affected by the Act or the General Rules, nothing in this Chapter, or in any companion regulatory provision adopted in any other provision of this Code, is intended to grant, nor shall they be construed as granting, immunity from criminal prosecution under Federal law. The Act does not protect users, caregivers or the owners of properties on which the medical use of marijuana is occurring from Federal Prosecution, or from having their property seized by Federal authorities under the Federal Control Substances Act.
- (b) The following standards for Medical Marijuana Growing/Manufacturing Facilities shall apply:
- (1) The medical use of marijuana shall comply at all times and in all circumstances with the Michigan Medical Marihuana Act and the General Rules of the Michigan Department of Community Health, as they may be amended from time to time;
- 4470 (2) The growing/manufacturing facility site shall not be located within one thousand (1,000) feet of a school, as measured from the outermost boundaries of the lot or parcel on which the growing/manufacturing facility and school are located;
- (3) The growing/manufacturing facility site shall not be located within a five hundred (500) feet of a lawfully existing medical marijuana dispensary and/or lawfully existing growing/manufacturing facility as measured from the outermost boundaries of the lot or parcel on which the proposed growing/manufacturing facility and lawfully existing dispensary or growing/manufacturing facility is located;
- (4) Smoking and/or use of medical marijuana shall be prohibited at the growing/manufacturing facility;
- (5) All activity related to the growing/manufacturing facility shall be done indoors;
- 4480 (6) The premises shall be open for inspection upon request by the Building Official the Fire Department and law enforcement officials for compliance with all applicable laws and rules, during the stated hours of operation/use and as such other times as anyone is present on the premises.
- (7) Quarterly inspections may be made by the City Official's designee to confirm the growing/manufacturing facility is operating in accordance with applicable laws including, but not limited to, State Law and City

Ordinances;

- 4490
- (8) Any medical marijuana growing/manufacturing facility shall maintain a log book and/or database identifying by date the amount of medical marijuana on the premises for each qualifying patient/caregiver, keeping the qualifying patient and caregiver information confidential. This log shall be available to law enforcement personnel to confirm that the medical marihuana dispensary or growing/manufacturing facility does not have more medical marijuana than authorized at the location and shall not be used to disclose more information than is reasonably necessary to verify the lawful amount of medical marijuana at the facility. The facility shall maintain the confidentiality of qualifying patients in compliance with the Michigan Medical Marijuana Act, as amended.
- (9) If the growing/manufacturing facility ceases operation for a length of time of sixty (60) days or greater, the permit shall expire;
- (10) Growing/manufacturing facility drive-through facilities shall be prohibited;
- (11) All medical marijuana shall be contained within the main building in an enclosed, locked facility in accordance with the Michigan Medical Marijuana Act, as amended;
- (12) All necessary building, electrical, plumbing and mechanical permits shall be obtained for any portion of the structure in which electrical wiring, lighting and/or watering devices that support the cultivation, growing or harvesting of marijuana are located;
- 4500
- (13) That portion of the structure where the storage of any chemicals such as herbicides, pesticides, and fertilizers shall be subject to inspection and approval by the Ypsilanti Fire Department to insure compliance with the Michigan Fire Protection Code;
- (14) Application for a Medical Marijuana Growing/Manufacturing Facility License shall be made to the City Clerk upon application forms provided by the Clerk for Medical Marijuana Growing/Manufacturing Facility License and signed by the applicant verifying the truth and accuracy of all information and representations in the application. Applications including information and documentation provided pursuant to an application shall be subject to the confidentiality rules under the Act. In addition to information and submittals, the application shall include payment of application fee in an amount set by the City Council;
- 4510
- (15) The police department shall review the proposed application to operate a dispensary or growing/manufacturing facility regarding public health, safety, and welfare concerns of the proposal;
- (16) The dispensing of medical marijuana at the medical marijuana growing/manufacturing facility shall be prohibited.
- (17) There shall be no other accessory uses permitted within the same building.

Sec. 122-534. Multiple-family dwellings containing more than six units. (794)

Multiple family dwellings containing more than six units are subject to the conditions hereinafter imposed:

- (a) Access to the site from a major thoroughfare must not traverse through or abut an R1, CN-SF or CN-Mid district, unless access is directly from a major thoroughfare.
- 4520
- (b) Access drives, parking areas, and maneuvering lanes must be located to encourage pedestrian and vehicular safety and convenience and to minimize their conflict with buildings and outdoor living areas. Sidewalks for convenient pedestrian flow between buildings, parking areas, outdoor living areas, and public rights-of-way must be provided.
- (c) The required parking spaces must be as conveniently located in close proximity to the dwellings they are intended to serve as is practicable. In no case may any parking space be located further than three hundred (300) feet from the nearest entrance to the building.

ORIGINAL: (split off into the district; removed duplicative stuff)

Sec. 122-794. Multiple-family dwellings containing seven or more units.

Multiple family dwellings containing seven (7) or more units:

- 4530
- (1) Access to the site from a major thoroughfare must not traverse through or abut an R1, CN-SF or CN-Mid district, unless access is directly from a major thoroughfare.
- (2) Access drives, parking areas, and maneuvering lanes must be located to minimize their conflict with buildings and outdoor living areas and to encourage pedestrian and vehicular safety and convenience. Sidewalks for convenient pedestrian flow between buildings, parking areas, outdoor living areas, and public rights-of-way must be provided. In the Neighborhoods, Centers, Corridors and Health and Human Services zoning districts, all circulation standards must be met.
- (3) The required parking spaces must be as conveniently located in close proximity to the dwellings they are intended to serve as is practicable. In no case may any parking space be located further than three hundred (300) feet from the nearest entrance to the building.
- 4540
- (4) All dwelling units must be readily accessible by fire and emergency vehicles. Fire lanes must be paved and posted as required in the Building Code adopted by the City of Ypsilanti. Emergency vehicle turn-around areas must be provided where there is no driveway outlet.
- (5) All parking areas, building entrances, and sidewalks must be illuminated for safety and security.
- (6) The following regulations apply to the MD district only:

- a. A total of one hundred thirty (130) square feet of outdoor living space must be provided for each bedroom or studio/efficiency unit. Porches, balconies and improved roof areas may count toward the required outdoor living space, provided no such area is less than five (5) feet in width. Such outdoor areas must be buffered from streets and parking lots. Off-street parking areas, driveways, and accessory uses may not be counted as required open space.
- b. The total number of rooms in a multiple apartment dwelling structure must not be more than the area of the parcel in square feet divided by 1,400 square feet. The required minimum floor area per unit type is as follows:

Unit Type	Required Min. Square Footage
1 Bedroom	600
2 Bedroom	800
3+ Bedroom	1,000

Sec. 122-535. Municipal, county, regional, and state service buildings and uses. (795)

Municipal, county, regional, and state service buildings and uses are permitted subject to the conditions hereinafter imposed:

- (a) For such uses proposed to be located within an R1, MD, CN, CN-SF, CN-Mid district, operating requirements must necessitate that the facility be located within that district in order to serve the immediate vicinity. Where possible such facilities must be located in another zoning district. Storage yards, sales or business offices, commercial buildings or activities, sanitary landfills, or water or sewage treatment plants are prohibited in the R1, MD, CN, CN-SF, and CN-Mid districts.
- (b) Public buildings and utility uses must not include any outdoor storage of materials or vehicles, unless as permitted within the PMD district.

ORIGINAL:

Sec. 122-795. Municipal, county, regional, and state service buildings and uses.

Municipal, county, regional, and state service buildings and uses are permitted subject to the conditions hereinafter imposed:

- (1) For such uses proposed to be located within an R1, MD, CN, CN-SF, CN-Mid district, operating requirements must necessitate that the facility be located within that district in order to serve the immediate vicinity. Where possible such facilities must be located in an HHS or a nonresidential district. Storage yards, sales or business offices, commercial buildings or activities, sanitary landfills, or water or sewage treatment plants are prohibited in the R1, MD, CN, CN-SF, and CN-Mid districts.
- (2) Public buildings and utility uses must not include any outdoor storage of materials or vehicles, unless as permitted within the PMD district.
- (3) The architecture and construction materials must be in character with the surrounding residential area.

N

Sec. 122-536. Nursing homes, convalescent homes and rest homes. (796)

Nursing homes, convalescent homes, and rest homes are subject to the conditions hereinafter imposed:

- (a) Such facilities must be constructed, maintained, and operated in conformance with applicable state and federal laws.
- (b) Such facility must provide the square footage of outdoor open space required by the Building Code and licensing agency. The open space must be landscaped, buffered from streets and parking lots, and include places for walking and sitting. Off-street parking areas, driveways, and accessory uses or areas may not be counted as required open space.

O

Sec. 122-537. Offices and showrooms for skilled trade services. (797)

Offices and showrooms of a skilled trade service are subject to the conditions hereinafter imposed:

- (a) Any fabrication, repair, cleaning or other processing of goods must conform to fire and building code.
- (b) Those areas of the ground floor which face upon or are visible from any adjacent streets must be used only for entrances, offices, sales, or display.
- (c) There must be no outside storage of materials or goods of any kind.
- (d) Storage of commercial and other vehicles inside the building is permitted, pursuant to building and fire code.

Sec. 122-538. Open-front or open-air businesses; outdoor recreation/amusement facilities; outdoor sales of new or used automobiles, trucks and tractors, boats, etc. (798, 800)

Open-front or open-air businesses; outdoor recreation/amusement facilities; and outdoor sales or rentals of new or used automobiles, trucks and tractors, boats, mobile homes, recreational vehicles and trailers are subject to the conditions hereinafter imposed:

- (a) All loading and parking areas for open air businesses shall be confined within the boundaries of the site, and shall not be permitted to spill over onto adjacent public rights-of-way. Curbs or wheel stops shall separate parking areas from all sidewalks.
- (b) All areas of a front yard or street side yard which are not landscaped, shall be paved in accordance with adopted engineering standards. .
- (c) The location, layout, design, or operation of the outdoor business shall not impair the continued enjoyment, use, and future development of nearby properties. The use shall not generate excessive noise, odors, dust, or other impacts. The Planning Commission may specify hours of operation and stricter screening mechanisms to assure compatibility with adjacent uses.

- 4610 (d) In the case of automotive, commercial vehicle, or recreational vehicle sales lots, no major repair or major refinishing is permitted outside a fully enclosed building.
- (e) Outdoor sales, storage, and display areas shall comply with all minimum setback requirements for the zoning district or building type.
- (f) In the case of uses other than automotive, commercial vehicle, or recreational vehicle sales lots, all items offered for sale must be totally enclosed within a lawful structure or building, or otherwise safely and securely stored, between the hours of dusk to dawn.

4620	ORIGINAL: Sec. 122-800. Outdoor retail sales of plant materials, lawn furniture, playground equipment, garden supplies, etc. Outdoor retail sales of plant materials, lawn furniture and decorations, playground equipment, and home and garden supplies shall be permitted subject to the conditions hereinafter imposed:
	(1) Plant storage and display areas shall comply with all minimum setback requirements for the zoning district. (2) The storage of soil, fertilizer, and similar loosely packaged materials shall be contained and covered to prevent it from blowing onto adjacent properties. Sec. 122-801. Outdoor storage of raw materials, supplies and products. Outdoor storage of raw materials and supplies or finished or semi-finished products shall be permitted subject to the conditions hereinafter imposed:
4630	(1) All such storage shall be located within a rear yard and screened with fencing in accordance with section 122-703. No material shall be stored above the height of the screening. (2) All storage areas shall conform to all district setback requirements for principal uses, but in no case shall outside storage be located closer than 50 feet to residentially zoned property. (3) Property access to all parts of the storage areas shall be provided for fire and emergency services as provided in the city building code. (4) All loosely packed materials such as sand, topsoil, dirt, etc., shall be covered and contained to prevent them from being blown or washed off of the site. (5) No materials which give off noxious odors shall be stored outdoors.
4640	AND Sec. 122-798. Open-front or open-air businesses; outdoor recreation/amusement facilities; outdoor sales of new or used automobiles, trucks and tractors, boats, etc. Open-front or open-air businesses; outdoor recreation/amusement facilities; and outdoor sales of new or used automobiles, trucks and tractors, boats, mobile homes, recreational vehicles and trailers are permitted subject to the conditions hereinafter imposed:
4650	(1) All loading and parking areas for open air businesses shall be confined within the boundaries of the site, and shall not be permitted to spill over onto adjacent public rights-of-way. Curbs or wheel stops shall separate parking areas from all sidewalks. (2) All areas of a front yard or street side yard which are not landscaped, shall be provided with a concrete or plant-mixed bituminous surface, and shall be graded and drained so as to dispose of all surface water accumulated within the area. (3) Driveway access to the outdoor business area shall be at least 50 feet from the intersection of any two streets. (4) The location, layout, design, or operation of the outdoor business shall not impair the continued enjoyment, use, and future development of nearby properties. The use shall not generate excessive noise, odors, dust, or other impacts. The Planning Commission may specify hours of operation and stricter screening mechanisms to assure compatibility with adjacent uses. (5) No major repair or major refinishing is permitted on the outdoor sales lot. (6) All lighting shall be shielded from adjacent residential properties and public rights-of-way.
4660	

Sec. 122-539. Outdoor storage of raw materials, supplies and products. (801)

Outdoor storage of raw materials and supplies or finished or semi-finished products shall be subject to the conditions hereinafter imposed:

- (a) All such storage shall be located within a rear yard and screened with fencing in accordance with §122-634. No material shall be stored above the height of the screening.
- (b) All storage areas shall conform to all district setback requirements for principal uses, but in no case shall outside storage be located closer than 50 feet to residentially zoned property.
- (c) Property access to all parts of the storage areas shall be provided for fire and emergency services.
- 4670 (d) All loosely packed materials such as sand, topsoil, dirt, fertilizer, etc., shall be covered and contained to prevent them from being blown or washed off of the site.
- (e) No materials which give off noxious odors shall be stored outdoors.
- (f) Outdoor storage and display areas shall comply with all minimum setback requirements for the zoning district or building type.

Original:
 Sec. 122-801. Outdoor storage of raw materials, supplies and products.
 Outdoor storage of raw materials and supplies or finished or semi-finished products shall be permitted subject to the conditions hereinafter imposed:

- 4680
- (1) All such storage shall be located within a rear yard and screened with fencing in accordance with section 122-703. No material shall be stored above the height of the screening.
 - (2) All storage areas shall conform to all district setback requirements for principal uses, but in no case shall outside storage be located closer than 50 feet to residentially zoned property.
 - (3) Property access to all parts of the storage areas shall be provided for fire and emergency services as provided in the city building code.
 - (4) All loosely packed materials such as sand, topsoil, dirt, etc., shall be covered and contained to prevent them from being blown or washed off of the site.
 - (5) No materials which give off noxious odors shall be stored outdoors.

Sec. 122-540. Outdoor cafes, restaurants, seating areas, and beer gardens. (799)

4690 Outdoor cafes, restaurants, seating areas, and beer gardens shall be permitted subject to the conditions hereinafter imposed:

- (a) All outdoor seating areas at grade level must be accessory to business which provides indoor seating or food concession. All storage, preparation and cooking of food and all vending machines shall be within an enclosed building or food concession.
- (b) The outdoor seating area shall be separated from all parking areas by means of a minimum three-foot high planting, wall, or other architectural feature delineating the space.
- (c) The outdoor seating area shall not be located within 50 feet of any properties zoned R1, MD, CN, CN-Mid, or CN-SF.
- (d) All outdoor areas shall be kept clean and void of litter at all times.

- 4700 ORIGINAL:
Outdoor cafes, restaurants and beer gardens shall be permitted subject to the conditions hereinafter imposed:
- (1) All outdoor seating areas at grade level must be accessory to business which provides indoor seating or food concession. All storage, preparation and cooking of food and all vending machines shall be within an enclosed building or food concession.
 - (2) The outdoor seating area shall be separated from all parking areas by means of a minimum three-foot high planting, wall or other architectural feature delineating the space.
 - (3) The outdoor seating area shall not be located within 50 feet of any properties zoned R1, MD, CN, CN-Mid, or CN-SF.
 - (4) All outdoor seating areas shall be kept clean and void of litter at all times.
- 4710

P

Sec. 122-541. Passenger terminals and stations. (786)

Passenger terminals and stations are permitted subject to the conditions hereinafter imposed:

- (a) All ticket booths, waiting areas, and other passenger facilities must be wholly contained within an enclosed building.
 - (b) Stopping and stacking spaces for buses or taxis must not encumber traffic nor present a safety hazard for vehicles or pedestrians on public rights-of-way.
 - (c) Curb cuts must not be permitted at such locations that will tend to create traffic hazards in the streets immediately thereto. No drives may be wider than 30 feet at the right-of-way line, and no more than one such drive or curb cut may be permitted for every 50 feet of frontage along any street.
- 4720

CHANGED FROM "EXPRESS AND PASSENGER TERMINALS" to "PASSENGER TERMINALS AND STATIONS" - express terminal is not a term used commonly; nor found elsewhere in the ordinance.

Sec. 122-542. Printing services. (810)

Printing services shall be permitted subject to the conditions hereinafter imposed:

- (a) All principal use activities, including storage of equipment and chemicals, shall be conducted within a totally enclosed building.
- (b) No exterior windows shall be oriented towards single-family residential uses.
- (c) Such uses shall not create a nuisance to adjacent residences through excessive noises or the smell of chemicals.

4730 **Q**

R

Sec. 122-543. Religious Institutions and Private Assembly spaces, including social facilities. (780)

Religious institutions, private assembly spaces, and social clubs, including accessory offices, meeting rooms, and athletic facilities are subject to the conditions hereinafter imposed:

- (a) When located within the R-1 and MD districts, parking areas are prohibited in the required front yard. Parking areas must be screened in accordance with §122-684.
- (b) Buildings of greater than the maximum height allowed in the zoning district may be permitted by the Planning Commission with the condition that the front, side, and rear yards are increased beyond the minimum required yards by one foot for each foot of building height that exceeds the maximum height allowed. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, the Planning Commission may grant exceptions based on maximum compliance possible with the IT institutional building type.
- (c) Related uses such as social centers, social service centers, child care centers, and rental banquet facilities are prohibited except in accordance with the underlying zoning district.

ORIGINAL: Sec. 122-780. Religious Institutions and Services. Religious institutions and services, including accessory offices, rectories or parsonages, meeting rooms, and classrooms for religious instruction only are permitted subject to the conditions hereinafter imposed:

- (1) For religious institutions located within the R-1 and MD districts, parking areas must be prohibited in the required front yard or street side yard setback areas. Parking areas which are located behind the required setback area adjacent to a street right-of-way must be screened in accordance with subsection 122- 835(11).
- (2) Buildings of greater than the maximum height allowed in the zoning district may be permitted by exception approved by the Planning Commission provided that the front, side, and rear yards are increased beyond the minimum required yards by one foot for each foot of building height that exceeds the maximum height allowed. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, the Planning Commission may grant exceptions based on maximum compliance possible with the IT institutional building type.
- (3) Related uses such as social centers, social service centers, child care centers, and rental banquet facilities are prohibited unless the Planning Commission finds that any adverse impacts on surrounding properties and traffic will be mitigated.

Sec. 122-544. Recycling centers. (803)

Recycling centers for discarded items shall be permitted subject to the conditions hereinafter imposed:

- (a) Such use shall be located no closer than 300 feet to property zoned R1, CN-SF, CN-Mid, CN, or MD.
- (b) All separation and storage areas shall conform to the setback requirements for buildings in the PMD district and screened with fencing in accordance with §122-634.
- (c) Access to such site shall not be through or abut property zoned R1, CN-SF, CN-Mid, CN, or MD.
- (d) Proper access to all parts of the storage areas shall be provided for fire and emergency access as provided by the City building code.
- (e) Recycling drop-off centers shall not occupy more than 6,000 square feet of area; shall not handle vegetative yard wastes (grass clippings, leaves, brush, etc.) or industrial, toxic, or liquid wastes; and shall not be involved in the compounding, washing or cleaning, treating, or composting of any materials.

S

Sec. 122-545. Primary, Secondary and Post-Secondary Schools (public & private). (805)

Elementary, junior, senior high, and post-secondary schools, public and private schools (but not regulating home schooling as defined by the state department of education) shall be subject to the conditions hereinafter imposed:

- (a) Staff and curriculum must meet the educational qualifications established by the state.
- (b) All buildings must meet the building and fire safety qualifications as established by the state.
- (c) Except in the CN, CN-SF, CN-Mid, C, HC, NC, GC, and HHS districts, the minimum lot area shall be 13,000 square feet. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, and HHS districts, the minimum lot area is determined by the IT institutional building type.
- (d) The site shall have direct access to a major thoroughfare, as provided in §122-673.
- (e) Except in the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, buildings of greater than the maximum height allowed within a given zoning district may be allowed provided that the front, side, and rear yards are increased above the minimum required yards by one foot for each foot of building height that exceeds the maximum height allowed. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, the maximum height is determined by the IT institutional building type.
- (f) Except in the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, off-street parking shall be prohibited in the required front yard setback area. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, parking location is determined by the IT institutional building type. In the case any off-street parking area abuts a lot in any residential district, screening must be provided as provided in §122-634.

- (g) If bus transportation is to be provided, documentation that adequate ingress and egress for bus traffic to the site shall be provided. If public bus transportation is utilized, a bus drop-off point within 250 feet of the school shall be available.
- (h) All site improvements shall be shown on the site plan.

ORIGINAL

Elementary, junior, senior high, and post-secondary schools, public and private schools (but not regulating home schooling as defined by the state department of education) shall be permitted subject to the conditions hereinafter imposed:

- (1) Staff and curriculum must meet the educational qualifications established by the state.
- (2) All buildings must meet the building and fire safety qualifications as established by the state.
- (3) Except in the CN, CN-SF, CN-Mid, C, HC, NC, GC, and HHS districts, the minimum lot area shall be 13,000 square feet. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, and HHS districts, the minimum lot area is determined by the IT institutional building type.
- (4) The site shall have direct access to a major thoroughfare, as provided in section 122-642.
- (5) Except in the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, buildings of greater than the maximum height allowed within a given zoning district may be allowed provided that the front, side, and rear yards are increased above the minimum required yards by one foot for each foot of building height that exceeds the maximum height allowed. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, the maximum height is determined by the IT institutional building type.
- (6) Except in the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, off-street parking shall be prohibited in the required front yard setback area. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, parking location is determined by the IT institutional building type. In the case any off-street parking area abuts a lot in any residential district, screening must be provided as provided in section 122-703.
- (7) For primary and secondary schools, the developer of the site shall document that a minimum of two off-street or on-street parking spaces shall be available for drop-off and pick-up of children, plus one additional drop-off/pick-up space for each 100 children that the facility has in attendance.
- (8) If bus transportation is to be provided, documentation that adequate ingress and egress for bus traffic to the site shall be provided. If public bus transportation is utilized, a bus drop-off point within 250 feet of the school shall be available.
- (9) Athletic fields and playgrounds accessory to educational facilities shall be shown on the approved site plan shared with the city

Sec. 122-546. Self-storage facilities and vehicle storage facilities. (806)

Self-storage facilities and vehicle storage facilities shall be subject to the conditions hereinafter imposed:

- (a) In the C, NC and GC districts, self-storage and vehicle storage facilities must comply with the regulations for building types. In all other districts, the facility shall be surrounded by a six-foot high solid obscuring fence, except for entrance gates. Required fencing near ingress and egress driveways may be lowered to permit adequate sight distances for vehicles entering and exiting the facility.
- (b) No single storage space shall exceed 500 square feet, except for vehicle storage facilities.
- (c) Only vehicles may be stored in vehicle storage facilities.
- (d) Adequate security shall be provided and maintained.
- (e) A single residential unit, to be occupied only by a residential manager and their family, with a floor area not exceeding 1,500 square feet, is permitted.

Sec. 122-547. Substance abuse treatment facilities. (808)

Substance abuse treatment facilities shall be subject to the conditions hereinafter imposed:

- (a) Such facilities shall have direct access to a major thoroughfare, in accordance with §122-673.
- (b) Such uses shall not be located within 1,000 feet of an R1, CN-Mid, or CN-SF district or of another such facility.

Sec. 122-548. Supportive Housing. (811)

Supportive housing shall be subject to the conditions hereinafter imposed:

- (a) The maximum number of persons served per the facility shall not exceed 8.
- (b) On-site services shall be for residents of the facility only.
- (c) If the owner of the property does not reside on the premises, the owner must appoint a resident manager, who resides on the premises. The property owner must provide the name and contact information of this person upon request by the City.
- (d) For each adult cared for, the square footage of outdoor recreation or relaxation area required by the Building Code must be provided in the rear, side, or street side yard. Such outdoor space must be fenced and screened from any adjacent lot.
- (e) All new construction or additions to existing buildings shall be compatible with the scale and character of the surroundings, and exterior building materials shall be harmonious with other buildings in the neighborhood.

- (f) Screening in accordance with §122-634 shall be provided along all rear and side yard boundaries between the proposed use and property either zoned or used for single-family and two-family purposes.

Original:

Modified because of Fair Housing concerns (exclusionary); repetitiveness

Sec. 122-811. Supportive Housing.

Supportive Housing where listed in residential districts shall be permitted after Special Use review and approval, and shall be subject to the conditions hereinafter imposed:

1- Supportive Housing shall be located at least 750 feet from all existing supportive housing, measured in a radius from the outermost boundaries of the lot or parcel on which the use is proposed, as well as all of the following uses:

a- State licensed residential facility, not including all home-based facilities serving 6 or fewer individuals and Day Care Group Homes serving 12 or fewer individuals.

b- Nursing homes

c- Substance Abuse Treatment Facility

d- Homeless Shelter

e- Drop-in center

f- Correctional facility

2- Site Plan Review in accordance with Article IV shall be required.

3- A minimum lot area of 8,000 square feet shall be provided.

4- The maximum number of persons served per the facility shall not exceed 8.

5- On-site services shall be for residents of the facility only.

6- All new construction or additions to existing buildings shall be compatible with the scale and character of the surroundings, and exterior building materials shall be harmonious with other buildings in the neighborhood.

7- Screening in accordance with 122-703 shall be provided along all boundaries between the proposed use and property either zoned or used for single-family and two-family purposes.

T

U

V

Sec. 122-549. Veterinary hospitals and clinics. (809)

Veterinary hospitals and clinics shall be permitted subject to the conditions hereinafter imposed:

(a) All principal use activities, including animal boarding, shall be conducted within a totally enclosed building.

(b) Buildings used for such purposes within 500 feet of a residential zoning district shall construct those indoor areas used for animal boarding an exercise in accordance with the soundproofing guidelines for dwelling units set forth in Section 1207.2 of the Michigan Building Code (2006).

(c) A veterinary hospital or clinic shall be subject to the requirements, limitations, and regulations listed in Chapter 14, Division 4, of this Code.

W

X

Y

Z

Secs. 122-550 – 559. Reserved.

Division 2: Storage of Vehicles

ORIGINAL: 731-736. May contain some items to follow-up on in the long term.

Sec. 122-560. General prohibition. (731)

Except as otherwise provided in this chapter, no vehicles may be parked or stored on any residentially-zoned lot except for operable passenger automobiles, pickup trucks, vans, or motorcycles which are personally owned by the persons residing on the premises, or their guests.

Sec. 122-561. Commercial vehicles in residential areas. (732)

The parking or storage of a commercial vehicle over a two ton capacity is prohibited on any residential lot.

4910 However, this section does not apply to commercial vehicles temporarily parked less than eight hours in a residential area in conjunction with maintenance or service to a residential property.

Sec. 122-562. Recreational vehicles. (733)

(a) The parking or storage of recreational vehicles, whether or not the recreational vehicle is mounted upon or hitched to another vehicle, including vacant mobile homes, antique or racing automobiles, or any other vehicles of a similar nature and related equipment, is prohibited on any lot in an R1, CN-SF, CN-Mid, CN, MD or HHS zoning district unless parked within a completely enclosed building or within a rear or side yard other than within a required yard setback area. Such vehicles stored in a side yard must be screened from view from the street and the adjacent property by an acceptable fence or landscaped screen, in accordance with §122-634 of this chapter. Notwithstanding the above, no recreational vehicle may be parked or stored on any indoor or outdoor parking space which is required to meet the minimum parking space requirement in an CN, MD or HHS district.

4920

(b) No more than two recreational vehicles per dwelling unit may be stored outdoors at one time. The size of recreational vehicles kept or stored outdoors may not exceed eight feet in width, ten feet in height, or 32 feet in length.

(c) Trailer coaches, motor homes, and other vehicles or equipment designed or adaptable for sleeping purposes must remain unoccupied and must not be connected to sanitary sewer facilities, or to electricity, water, or gas.

Sec. 122-563. Unlicensed, untitled, and inoperable motor vehicles, and disassembled parts of motor vehicles. (734)

No unlicensed, untitled, or inoperable motor vehicles, or disassembled parts of motor vehicles may be kept on any property within the City except as follows:

4930

(a) Contained entirely within a completely enclosed building so long as any indoor parking spaces, necessary for meeting minimum space requirements, must not be used for the storage of unlicensed or inoperable vehicles and so long as the storage is not otherwise prohibited.

(b) The storage of vehicles as is specifically authorized in PMD and GC districts.

(c) Minor repairs, such as changing flat tires, of vehicles where the repairs will be completed within 24 hours.

Sec. 122-564. Responsibility for violations. (736)

In any proceeding for violation of any provision of this division, both the person to whom a vehicle is registered as determined from the registration plate displayed on such motor vehicle, and the owner of the property on which the vehicle is stored, will be presumed to be persons who committed the violation charged. In the case of unlicensed vehicles, the owner of the property on which the vehicle is located will be considered to be the person responsible for the violation charged.

4940

Secs. 122-565 – 569. Reserved.

Division 3: Communication Devices

ORIGINAL: 681-687

Sec. 122-570. Intent. (681)

It is the intent of this division to provide reasonable regulations for the mounting of private communication antennas. The objectives of this division are to promote safety and prevent injury to persons and property, to maintain and promote the aesthetic and architectural quality of properties, to preserve property values, to balance the City's authority and duty to regulate the placement of communication devices in relation to the right to construct and use communication devices without reasonable restrictions, and to conditionally exclude from regulation by this division certain VHF and UHF television antennas meeting the criteria of §122-572(a).

Sec. 122-561. General standards. (682)

- (a) Permits. All applicants proposing to erect any communication device in any zoning district, except as excluded under §122-572(a), must be required to obtain a building permit and make payment of required fees.
- (b) Plot plan and mounting detail. Prior to issuance of a building permit for the erection of a communication device in any zoning district, the applicant must submit a plot plan showing to scale the precise proposed location of the communication device; its relative location to buildings on the site, adjoining properties, roads, landscaping, and natural features; the height and design of the structure; and foundation and/or mounting detail as appropriate for the Building Department to determine safety and building code compliance.
- (c) Standards. All communication devices must be installed, maintained, and grounded according to the standards as stated in the building code and must also meet wind and ice loads as specified in the building code.
- (d) Restrictions. All communication devices are subject to the following restrictions:
 - (1) Protrusion. Communication devices must not protrude or overhang in any way over any public right-of-way or adjoining property.
 - (2) Location. Communication devices must not be located in front yards or in the street side yard of corner lots.
 - (3) Advertising, symbols, lighting. No portion of any communication device may display any advertising message or other graphic representation other than a manufacturer's logo or nameplate or warning signs; provided such logo or letters are of a size and character that is not legible from adjacent properties. Except as required by the Federal Communications Commission, no communication device may be illuminated by direct or indirect lighting.
 - (4) Color and texture. All communication devices must be of a color and texture so as not to be conspicuous and to promote its visual blending into the adjacent background.
 - (5) Wood construction prohibited. Communications devices must not be constructed of wood.
 - (6) Ground mounted devices. All communication devices not mounted on a principal or accessory building must be permanently anchored to a foundation located on the ground. No ground mounted device may be located closer to a property line than its height as measured from the ground elevation at the base of the antenna structure.
 - (7) Roof mounted devices. All communication devices mounted on the roof of a building must be located on that portion of the building located adjacent to the rear of the property, unless it can be demonstrated that an alternative location is as safe or safer, and the visibility of the antenna from the adjacent properties and by pedestrian or vehicular passers-by is reduced or equal in comparison to a rear yard orientation/location.

Sec. 122-572. Antenna systems. (683)

In addition to the foregoing general standards of this division, the following standards must apply to antenna systems:

- (a) Conventional VHF and/or UHF television antennas which have width and height dimensions of not more than 135 inches and ten feet respectively, which are situated on the portion of the roof adjacent to the rear yard on the property, and which do not extend higher than ten feet above the ridge and/or peak of the roof, must be exempt from the requirements of applying for and receiving approval under this division. Exemption of such VHF and UHF television antennas from this division is based upon the following findings: there is relatively small concern for wind and snow load issues, there has been a long demonstrated safety record, there has been an historical acceptance of such facilities from an architectural and aesthetic standpoint, and the cost of compliance with the procedure for application and review would be great in relation to the cost of purchasing and installing such antennas.
- (b) Antenna systems which do not meet the criteria and condition of subsection (1) of this section must be regulated as follows:
 - (1) The antenna system must be located in a fenced or walled enclosure, so as to deter any person from

climbing the tower, except for service or repair.

- (2) The antenna system must be of a self-supporting design.
- (3) Proof of liability insurance in the amount of \$100,000.00 must be submitted indicating protection of all adjacent property owners within a radius equal to 1½ times the height of the tower. This must include any City-owned property or right-of-way.
- (4) The antenna system must be used only for legal, amateur or commercial receiving and transmitting, as licensed by the Federal Communications Commission.

Sec. 122-573. Satellite dish stations. (684)

In addition to the general standards of §122-571, the following must apply to all satellite dish antennas:

- (a) Permit applications must contain the following additional information:
 - (1) In the case of a satellite dish proposed to be mounted on a roof in a commercial or manufacturing district, a detailed plan showing the exact location of the antenna on the roof.
 - (2) A picture, sketch, or catalog cut of the proposed installation, including the proposed coloration of the satellite dish.
 - (3) Proof of liability insurance in a minimum amount of \$100,000.00.
 - (4) Such other pertinent information as may be required by the Building Department.
- (b) No more than one satellite dish installation may be permitted on any single lot of record.
- (c) The satellite dish and all structural supports must be of noncombustible and corrosive resistant material.
- (d) Each satellite dish installation must be designed to withstand a wind force of 75 miles per hour without the use of any supporting guide wires.
- (e) Any driving motor must be limited to 100-volt maximum power design and be encased in protective guards. Any motor with operating voltage of more than 50-volt A.C. nominal must comply with Article 430 of the National Electrical Code.
- (f) A satellite dish antenna must be permanently mounted. A satellite dish antenna may only be on wheels or temporarily installed when used to demonstrate and/or test the feasibility of use.

Sec. 122-574. Communication devices in residential districts. (685)

In addition to the foregoing provisions, the following requirements apply to all communication devices in the R1, MD, CN, CN-Mid, CN-SF and HHS zoning districts:

- (a) Antenna systems.
 - (1) Ground mounted restrictions. Ground mounted antenna systems must not exceed a height of 75 feet, or a height equal to the distance from the base of the antenna system to the nearest property line whichever is less. There must be no more than one ground mounted antenna system on a single zoning lot.
 - (2) Roof mounted height restrictions. Roof mounted antenna systems must not exceed in height the lesser of the height of the roof plus ten feet, or the distance from the base of the antenna tower system (at its connection point with the roof) to the nearest property line.
- (b) Satellite dish stations.
 - (1) Height. No part of any satellite dish station may exceed 12 feet in height.
 - (2) Size. The diameter or any exterior dimension of any satellite dish station must not exceed ten feet.
 - (3) Location. All satellite dish stations in residential districts must be located in a rear yard and comply with the minimum distance requirements for detached accessory structures, as stated in §122-651, however, a satellite dish station may be located on the roof of a building under the following conditions:
 - (i) In the R1, CN-SF and CN-Mid zoning district, a satellite dish station may be located on the roof of a building associated with nonresidential use (i.e. school, religious institution or public service building), provided that the satellite dish station is located toward the rear of the building and is entirely screened from view from any public streets, pedestrian rights-of-way, or adjoining properties.
 - (ii) In the MD, or CN zoning districts, a satellite dish station may be located on any roof; provided the satellite dish station is located toward the rear of the building, no portion of the dish station extends higher than four feet above the ridge or peak of the building's roof, and the dish station is entirely screened from view from any public street or pedestrian right-of-way.
 - (iii) Screening. Conflicting land use screening must be installed around a ground mounted satellite dish antenna so as to reasonably conceal the view of the satellite dish antenna from adjacent public rights-of-way.

Sec. 122-575. Communication devices in C, HC, NC and GC districts. (686)

The following requirements must apply to all communication devices in the C, HC, NC, and GC zoning district.

- (a) Antenna systems.
 - (1) Ground mounted height restrictions. Ground mounted antenna systems must not exceed in height the lesser

- of 75 feet, or the distance from the base of the antenna system to the nearest property line.
- (2) Roof mounted height restrictions. Roof mounted antenna systems must not exceed in height the lesser of the height of the roof plus 40 feet, or the distance from the base of the antenna tower system (at its connection point with the roof) to the nearest property line.

(b) Satellite dish stations.

- (1) Ground mounted height restrictions. No part of any ground mounted satellite dish station may exceed 15 feet above ground level.
- (2) Roof mounted height restrictions. Roof installations are permitted only on a building where the height of the roof surface where the satellite dish is to be mounted is at least 15 feet in height. No part of any satellite dish station may exceed higher than four feet above the ridge or peak of the building's roof, unless enclosed by an opaque screen not less in height than the satellite dish station. The design of the screening device must be compatible with the architectural design of the building upon which it is located.
- (3) Size. The diameter or any exterior dimension of any satellite dish station must not exceed 15 feet.
- (4) Location. All ground mounted satellite dish stations must be located in rear yards and comply with minimum distance requirements for accessory structures, as stated in [§122-651](#).
- (5) Screening. Conflicting land use screening must be installed around a ground mounted satellite dish antenna so as to reasonably conceal the view of the satellite dish antenna from public rights-of-way.

Sec. 122-576. Communication devices in the PMD zoning district. (687)

- (a) Intent. The intent of this Section is to permit the location of mobile communication facilities within the PMD zoning district and while protecting the safety and character of nearby residential areas and the City. It is further the intent of this Section to require co-location of transmission and receiving apparatus on existing structures or facilities, unless it can be demonstrated by the applicant that co-location is not technically feasible.

(b) Definitions.

- (1) **Mobile Communication Facilities** mean and include all structures and accessory facilities relating to the use of the radio frequency spectrum for the purpose of transmitting or receiving radio signals. This may include, but not be limited to, cellular telephone towers, radio towers, television towers, telephone devices and exchanges, micro-wave relay towers, telephone transmission equipment building and commercial mobile radio service facilities. Not included within this definition are: citizen band radio facilities; short wave facilities; ham, amateur radio facilities; satellite dishes; and, governmental facilities which are subject to state or federal law or regulations which preempt municipal regulatory authority.
- (2) **Attached Mobile Communications Facilities** means mobile communication Facilities that are affixed to existing structures, such as existing buildings, towers, water tanks, utility poles, and the like. A wireless communication support structure proposed to be newly established shall not be included within this definition.
- (3) **Mobile Communication Support Structures** means structures erected or modified to support wireless communication antennas. Support structures within this definition include, but not be limited to, monopoles, lattice towers, light poles, wood poles and guyed towers, or other structures which appear to be something other than a mere support structure.
- (4) **Co-location** means the location by two or more wireless communication providers of mobile communication towers on a common structure, tower, or building, with the view toward reducing the overall number of structures required to support wireless communication antennas within the community.

(c) Locational Factors.

- (1) The applicant must demonstrate the need for the proposed facility to be located as proposed based upon the presence of one or more of the following factors:
- (i) Proximity to a major thoroughfare.
 - (ii) Areas of population concentration.
 - (iii) Concentration of commercial, industrial, and/or other business centers.
 - (iv) Areas where signal interference has occurred due to tall buildings, masses of trees, or other obstructions.
 - (v) Topography of the proposed facility location in relation to other facilities with which the proposed facility is to operate.
- (2) It is the policy of the City to minimize the overall number of newly established locations for mobile communication Facilities and encourage the use of existing structures.
- (i) Co-location must be deemed to be "feasible" for purposes of this section where all of the following are met:
- The wireless communication provider entity under consideration for co-location will undertake to pay market rent or other market compensation for co-location.
 - The site on which co-location is being considered, taking into consideration reasonable

modification or replacement of a facility, is able to provide structural support.

- The co-location being considered is technologically reasonable, e.g., the co-location will not result in unreasonable interference, given appropriate physical and other adjustment in relation to the structure, antennas, and the like.
- The height of the structure necessary for co-location will not be increased beyond a point deemed to be permissible by the City, taking into consideration the standards set forth in this section.

(ii) Requirements for Co-location:

- Approval for the construction and use of a new wireless communication facility must not be granted unless and until the applicant demonstrates that a feasible co-location is not available for the coverage area and capacity needs.
- All new and modified mobile communication facilities must be designed and constructed so as to accommodate co-location.
- If a party who owns or otherwise controls a facility fails or refuses to alter a structure so as to accommodate a proposed and otherwise feasible co-location, such facility will thereupon and thereafter be deemed to be a nonconforming structure and use, and must not be altered, expanded or extended in any respect.

(d) Application Requirements.

- (1) A site plan prepared in accordance with **Article III, Division 2 "Permits," Subdivision I "Zoning Compliance."** The site plan must also include a detailed landscaping plan illustrating screening and aesthetic enhancement for the structure base, accessory buildings and enclosure.
- (2) The application must include a signed certification by a State of Michigan licensed professional engineer with regard to the manner in which the proposed structure will fall, which certification will be utilized, along with other criteria such as applicable regulations for the district in question, in determining the appropriate setback to be required for the structure and other facilities.
- (3) The application must include a description of security to be posted at the time of receiving a building permit for the facility to ensure removal of the facility when it has been abandoned or is no longer needed (see **§122-576(f)**). In this regard, the security must, at the election of the applicant, be in the form of: (1) cash; (2) surety bond; (3) letter of credit; or, (4) an agreement in a form approved by the City Attorney and recordable at the office of the Register of Deeds, establishing a promise of the applicant and owner of the property to timely remove the facility as required under this section of the ordinance, with the further provision that the applicant and owner must be responsible for the payment of any costs and attorneys' fees incurred by the City in securing removal.
- (4) The application must include a map showing existing and known proposed mobile communication facilities within the City, and further showing existing and known proposed mobile communication facilities within areas surrounding the borders of the City in the location, and in the area, which are relevant in terms of potential co-location or in demonstrating the need for the proposed facility. If and to the extent the information in question is on file with the community, the applicant is required only to update as needed. Any proprietary information may be submitted with a request for confidentiality in connection with the development of governmental policy, in accordance with MCL 15.243(1)G. This ordinance serves as the promise to maintain confidentiality to the extent permitted by law. The request for confidentiality must be prominently stated in order to bring it to the attention of the City.
- (5) The name, address and phone number of the person to contact for engineering, maintenance and other notice purposes. This information must be continuously updated during all times the facility is on the premises.

(e) General Regulations.

- (1) Towers must not exceed 140 feet in height when measured at grade level. This requirement may be waived in the sole discretion of the City based upon a consideration of the following standards.
 - (i) The tower is to be used by no less than one additional co-locator.
 - (ii) The topography of the site in relationship to the immediate surrounding area necessitates a tower of increased height.
 - (iii) The screening capabilities of the site provide adequate mitigation of the obtrusive visual effects of the tower.
 - (iv) The land use characteristics of the area surrounding the subject site are compatible with a tower of increased height.
 - (v) There is no feasible and prudent alternative to a tower of increased height based upon the opinion of an independent expert.
- (2) The accessory building contemplated to enclose switching equipment must be limited to fifteen (15) feet in height.
- (3) The setback of the support structure from any residential district must be no less than double the height of

the structure. The setback of the support structure from an existing or proposed rights-of-way or other publicly traveled roads must be no less than the height of the structure.

- (4) Where the proposed support structure abuts a parcel of land zoned from other than residential purposes, the minimum setback of the structure and accessory structures must be in accordance with the required setbacks from the main or principal buildings as provided in the schedule of regulations for the zoning district in which the support structure is located.

- (5) There must be an unobstructed paved access drive to the support structure for operation, maintenance, repair and inspection purposes, which may be provided through or over an easement. This access drive must be a minimum of fourteen (14) feet in width.

- 5180 (6) Where a wireless communication facility is proposed on a roof of a building, the equipment enclosure is not permitted as a roof appliance or penthouse on the building. The equipment enclosure may be located within the principal building or may be an accessory building, providing that as an accessory building it conforms with all district requirements for principal buildings, including yard setback and building height.

- (7) The support structure must be constructed in accordance with all applicable building codes and must include the submission of a soils report from a soils engineer, licensed in the State of Michigan. This soils report must include soil borings and statements indicating the suitability of soil conditions for the proposed use. The clearance requirements of the Federal Aviation Administration and Federal Communications Commission must be noted.

- 5190 (8) No wireless communication tower may be located within three thousand (3,000) feet of another wireless communication tower. This requirement may be waived at the sole discretion of the City if one of the following conditions are met:

- (i) The communication apparatus is located on an existing tower or other structure capable of accommodating such apparatus.
- (ii) The tower/facility is of an exceptional design so as to create a positive architectural and/or environmental feature which is compatible with the character of the surrounding area and community.
- (iii) The tower is intended to serve solely a governmental agency.

- (9) The tower and appurtenant apparatus building must be secured by fencing a minimum of six (6) feet in height. Conflicting land use screening of the apparatus building must be provided.

- (10) The applicant must submit details of tower lighting approved by the Federal Aviation Administration.

- 5200 (11) A maintenance plan must be presented as part of the site plan for the proposed facility.

- (12) The name, address and phone number of the person to contact for engineering, maintenance and other notice purposes must be posted on the perimeter fencing, and must be continuously updated during all times the facility is on the premises.

- (13) The proposed tower or wireless communication facility must be located within 500 feet of the Interstate 94 right-of-way. This does not apply to collocation of wireless communication antenna on existing towers, buildings, or other existing structure.

(f) Removal.

- (1) The City reserves the right to request evidence of ongoing operation at any time after the construction of an approved tower.

- 5210 (2) A condition of every approval of a wireless communication facility must be adequate provision for removal of all or part of the facility by users and owners when the facility has not been used for 180 days or more.

- (3) The situations in which removal of the facility is required, the removal of antennas or other equipment from the facility, or the cessation of operations (transmission and/or reception of radio signals) must be considered as the beginning of a period of nonuse.

- (4) Upon the determination that a facility must be removed, the property owner or persons who had used the facility must immediately apply or secure the application for any required demolition or removal permits, and immediately proceed with and complete the demolition/removal, restoring the premises to an acceptable condition as reasonably determined by the Zoning Administrator.

- 5220 (5) If the required removal of a facility or a portion thereof has not been lawfully completed within sixty (60) days of the applicable deadline, and after at least thirty (30) days written notice, the City may remove or secure the removal of the facility or required portions thereof, with its actual cost and reasonable administrative charge to be drawn or collected from the security posted at the time application was made for establishing the facility.

Secs. 122-577 – 599. Reserved.

Article VI: Site Regulations

Division 1: Generally

ORIGINALLY: ARTICLE XI, DIV 1.-

Sec. 122-600. Scope. (631)

5230 The provisions of this chapter apply to all lots and parcels of land and to every building, structure, or use, and extends vertically. No lot, building, structure, or part thereof, must hereafter be located, erected, altered, occupied, or used except in conformity with the provisions of this chapter. The general provisions of this article apply unless specifically stated otherwise.

Sec. 122-601. Control of heat, glare, fumes, dust, noise, etc. (632)

Every use must be so conducted and operated that it is not obnoxious or dangerous by reason of heat, glare, fumes, dust, noise, radiation, vibration, or odors beyond the lot on which the use is located. Furthermore, it shall be unlawful for any person to create, assist in creating, permit, continue, or permit the continuance of any public nuisance as defined and regulated under Article II of chapter 42.

Sec. 122-602. Damaged or destroyed buildings. (633)

- 5240 (a) The owner of any building or structure which has been damaged or destroyed by fire, windstorm, or other casualty must repair such damage within six months after its occurrence. However, nonconforming buildings and structures may only be repaired when in conformance with [Article III, Division 3 "Nonconformities."](#)
- (b) In the event the building or structure is damaged beyond repair, or repairs are not permitted by the terms of this chapter, then any part left standing after such damage or destruction must be demolished within six months of its occurrence pursuant to a permit granted by the City Building Department.

Sec. 122-603. Moving of buildings or structures. (643)

The moving of a building or structure to a different location must be considered as the erection of a new building and all provisions, regulations, and requirements relative to the erection of a new building must be applicable thereto. A performance guarantee may be required prior to such moving as provided in [§122-317.](#)

Sec. 122-604. Dumping on land prohibited. (634)

5250 The use of land for the dumping or disposal of scrap metal, junk, junk cars, parts of automobiles, trucks, and boats; tires, garbage, rubbish, or other refuse; or of ashes, slag, or other wastes or by-products; is not permitted in any zoning district.

Sec. 122-605. Depositing or burying garbage; excavation or filling. (638)

- 5260 (a) The deposit or burying of garbage anywhere in the City is expressly prohibited.
- (b) The removal or filling of topsoil, sand, gravel or other material from or on the land is not permitted in any zoning district unless a site plan for such excavation or filling has first been approved by the Planning Commission and a permit is issued by the Building Department. Before approving such plan, the Planning Commission must determine that such removal will not cause standing water to collect or, at the expiration date of such permit, leave the surface of the land in an unsuitable condition or unfit for other land uses permitted in the district in which the removal or filling occurs; and that such fill or removal will not cause water or other materials to encroach on any public street, sidewalk, or adjacent property not owned by the applicant. When appropriate, the City may require that such fill or excavation areas are protected with fencing, rail guards, and warning signs.
- (c) This section does not apply to the normal removal or filling of soil for the construction of an approved building or structure when such plans have received site plan approval and a permit for such construction has been issued by the Building Department, or for the demolition of such when such demolition has received a permit from the Building Department.
- 5270 (d) This section is also not intended to regulate common household gardening, household composting, or general ground care.

Sec. 122-606. Dwelling on rear of lot. (635)

- (a) No building on the same lot and in the rear of a principal building may be used as a dwelling, nor may any building be located in front of a building used as a dwelling on the same lot, except as provided by this chapter, as legal accessory dwelling unit, or within an approved planned unit development.

- (b) The only exceptions to this requirement are dormitories, rectories, convents, or similar living quarters operated and maintained in connection with a religious institution, school, hospital, or similar institution.

Sec. 122-607. Building Entrances, Rights of Way, and Easements. (636)

- (a) **Building entrance must face street.** No principal building can be placed on a lot unless the building is situated in such a manner that the front entry into the building faces the street to which the property is addressed.
- (b) **Construction of permanent structure over right of way or easement unlawful.** It is unlawful for any person to install, erect, cause or permit the installation of a permanent structure (such as a garage, building, swimming pool, fence, or tree) on or across an easement of record which will prevent or interfere with the free right or opportunity to use or make accessible such easement for its proper use, without prior authorization by City Council and/or the holder of such easement.


ADDED: UNLESS AUTHORIZED BY CITY COUNCIL 12/15/2016. It's happened that we've granted people licenses before.

- (c) **Planned easements.** All site plans must show planned easements for non-motorized pathways in the City of Ypsilanti's Non-Motorized Plan, a 50 to 100 foot conservation and /or access easement along any Huron River frontage, the ReImagine Washtenaw Corridor Improvement Study and any planned road easement expansions approved by City Council. A proposed expansion of a structure or new building where the building or structure encroaches from the required setback from a planned easement for a street must be approved by the Planning Commission.

Sec. 122-608. Trash receptacles and dumpsters. (650) (637)

Any new or altered commercial use, including residential uses with three or more units, which requires zoning compliance review and has an outdoor trash storage area must comply with the following requirements:

- (a) No outdoor trash storage area may be located in any front yard or any required side yard setback which is adjacent to a street, unless there is no alternative as established by the City Planner or the Planning Commission. In no instance may any trash receptacle or dumpster be located within or block a designated parking space.
- (b) Any outdoor trash storage area must be limited to normal refuse which is collected on a regular basis and must be maintained in a neat, orderly and sanitary condition. This maintenance is the responsibility of the owner of the premises on which the containers are placed.
- (c) Adequate vehicular access must be provided to such containers for truck pickup either via a public alley or vehicular access aisle which does not conflict with the use of off-street parking spaces or entrances to or exits from principal buildings nearby.
- (d) All trash storage areas must be on a paved pad, and must be screened with an enclosure at least one (1) foot taller than the dumpster.
- (f) Where a dumpster is the primary means of collecting refuse, the trash storage area must be on a concrete pad, and screened with an enclosure at least six feet in height. The enclosure must be of a solid brick or masonry wall on three sides with an 80% opacity wooden swing door on the fourth side.



Sec. 122-609. Lighting. (641) (638)

- (a) Parking and loading facilities, building entrances, and building exits used during night-time hours shall be artificially illuminated.
- (b) All outdoor lighting must be so designed and arranged so as not to shine on adjacent properties or occupied

dwellings, or adversely impact vehicular or pedestrian traffic on nearby streets, drives, walkways, or general rights-of-way.

(1) Outdoor lighting originating on a site may not exceed one-half (0.5) footcandle at the lot line.

(2) Light fixtures must be full cutoff.

(c) Outdoor lighting fixtures must not exceed 30 feet in height or the height of the principal building on the site, whichever is less. For development sites abutting lots zoned for one and two-family residential uses, lights must not exceed a height of 16 ft. The Planning Commission may modify the height restrictions in commercial and industrial districts, based on consideration of the following: the position and height of buildings, the character of the proposed use; and the character of surrounding land uses.

5340 (d) Where outdoor lighting is required by this chapter, the light intensity provided at ground level must be a minimum of one-third (0.3) footcandle anywhere in the area to be illuminated. Light intensity must average a minimum of one-half (0.5) footcandle over the entire area, measured five feet above the surface. Motion-activated lights are permitted, provided that the maximum levels are not exceeded and the lighting is kept in good working order.

(e) Ornamental lighting.

(1) Lighting placed inside a building but designed to be seen from the exterior, such as neon tubing outlining windows, is permitted; however, flashing or "chasing" effects are prohibited.

(2) Uplighting intended to highlight ornamental features of a building or landscape is permitted, subject to the Building Code, provided that light output is not designed to exceed 400 lumens per fixture nor a color temperature of 3000K.

5350

ORIGINAL: (added quite a bit to even out some discrepancies (full cutoff vs dark sky)); added a bit about ornamental uplighting (didn't have anything before, so here's a start- uplighting was defacto prohibited by "all lighting must be down-directed"); added a bit about motion-detection lights (had questions from applicants about it). NEON TUBING, fyi, was a weird hot-button. It was included in signs and *prohibited*. However, incredibly challenging to enforce. As you can see- proposing allowing it, at least for now.

Sec. 122-641. Outdoor lighting.

5360

(a) All outdoor lighting must be so designed and arranged so as not to shine on adjacent properties or occupied dwellings, or adversely impact vehicular or pedestrian traffic on nearby streets, drives, walkways, or general rights-of-way. Outdoor lighting originating on a site must not exceed one-half (0.5) footcandle at the lot line. Proposed light fixtures must be Dark Sky compliant. Lights may be required to be full cutoff where they may impact residential uses.

(b) Outdoor lighting fixtures must not exceed 30 feet in height or the height of the principal building on the site, whichever is less. For development sites abutting lots used or zoned for one and two-family residential uses, lights must not exceed a height of 16 ft. The Planning Commission may modify the height restrictions in commercial and industrial districts, based on consideration of the following: the position and height of buildings, the character of the proposed use; and the character of surrounding land uses.

5370

(c) Where outdoor lighting is required by this chapter, the light intensity provided at ground level must be a minimum of one-third (0.3) footcandle anywhere in the area to be illuminated. Light intensity must average a minimum of one-half (0.5) footcandle over the entire area, measured five feet above the surface.

Sec. 122-610. Grades; elevation differentials. (639)

The grading of all building lots must be such as to divert water away from buildings and to prevent standing water and soil saturation detrimental to structures, lot use, and surrounding property.

Sec. 122-611. Steep slopes protection. (640)

This section is intended to protect resources in environmentally sensitive areas to ensure that development does not result in erosion and in flooding during site preparation and the development process. Site alterations, re-grading, filling or the clearing of vegetation, or any other activity deemed detrimental to any environmentally sensitive area or resource prior to the submission of plans for subdivision or land development are a violation of this Ordinance.

5380

(a) General Design Standards. Structures must be designed in a manner that requires a minimum amount of alteration to the steep slope and that otherwise complies with the grading standards in item b of this section, except where a geologic hazard investigation report recommends otherwise, multi-level building design and/or terracing must be used. Otherwise, structures must be sited on existing level areas of the site. Particular caution must be taken to prevent increases in the rate of stormwater runoff and erosion downslope of any steep slope development site.

(b) Specific Design Standards. The following specific design standards must be met on sites with steep slopes:

(1) Any site disturbance of slopes exceeding twelve (12%) percent must be minimized.

(2) No site disturbance must be allowed on slopes exceeding fifteen (15%) percent, except under the following circumstances.

5390

(i) Grading for a portion of a driveway accessing a single family dwelling when it can be demonstrated

that no other routing which avoids slopes exceeding fifteen (15%) percent is possible.

- (ii) Upon submission of a report by a certified soil or geotechnical engineer indicating that the steep slope may be safely developed and execution of a provision agreeing to hold the City of Ypsilanti harmless from any claims of damages due to approval of such development. If development is allowed to proceed under this subsection, no more than (15%) percent of such areas must be developed and/or re-graded or stripped of vegetation.
- (iii) Finished slopes of all cuts and fills must not exceed three-to-one (3:1 or 33%), unless the applicant can demonstrate that steeper slopes can be stabilized and maintained adequately.

5400 **Sec. 122-612. Retaining walls. (646) (641)**

Retaining walls in excess of one foot in height require a building permit. All retaining walls must be designed and built so as to safely resist lateral pressures of soil behind them and be safely supported by soil beneath them. Additionally, retaining walls must be maintained in structurally sound and safe repair and must not impair drainage or create negative impacts on any other lot.

Sec. 122-613. Height exceptions (NEW) (642)

- (a) The height requirements of all zoning districts may be exceeded by chimneys, flagpoles, church spires, belfries, cupolas, domes, or other similar architectural embellishments, roof mounted communication antennas, water towers, observation towers, power transmission towers, radio towers, masts, smokestacks, ventilators, skylights, derricks, conveyors, cooling towers, and other similar and necessary mechanical appurtenances pertaining to the permitted uses of the districts in which they are located; provided that they do not exceed the maximum permitted height for buildings in a given district by more than ten feet.
- (b) In the PMD district, chimneys, cooling and fire towers, elevator buildings, parapets, roof storage tanks, communication towers and other necessary appurtenances are permitted to heights greater than ten feet above the maximum permitted building height; provided such appurtenances are located at least the same distance from any adjoining property line as their height.

Discussion: section (A) was found in tables in each zoning district. In the pre-2014 Z0, it was a separate section, referred to by each zoning district. Section (B) is probably something to look at bringing back (originally in M2)- don't think it's been a thing that's come up.

Secs. 122-614 – 619. Reserved.

Division 2: Yard, Area, and Lot Requirements

ORIGINALLY: ARTICLE XI, DIV 1.- 751 thru 756. Untouched.

Sec. 122-620. Altered land parcel. (751) (650)

- (a) No lot or parcel of land may be divided, altered or reduced by sale, gift, or other disposition so that the yards, parking area, or other open spaces, or the land area thereof is less than the minimum requirements of this chapter.
- (b) No lot, parcel of land, parking area, or other open space may be reduced so as to increase its noncompliance with the minimum requirements of this chapter.

Sec. 122-621. Area requirements. (752) (651)

In determining lot, land, yard, parking area or other open space requirements, no area may serve to meet such requirements for more than one principal building or use, and no area necessary for compliance with the space requirements for one principal building or use be included in the calculation of the space requirements for any other building, structure, or use.

Sec. 122-623. Lots adjoining alleys. (753) (652)

In calculating the area of a lot that adjoins an alley for the purpose of applying lot area requirements of this chapter, one-half the width of such alley abutting the lot is considered as part of such lot.

Sec. 122-624. Determinations by Zoning Board of Appeals. (754) (653)

When yard regulations cannot reasonably be complied with, or where their application cannot be determined on lots of peculiar shape, topography or due to architectural or site arrangement, such regulations may be modified or determined by the Zoning Board of Appeals.

Sec. 122-625. Land division. (755) (654)

- (a) Lot split or consolidation. The division of lots must take place in accordance with the land division act, Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101 et seq., MSA 26.430(101) et seq.), as amended. Pursuant to the authority granted the City to regulate the division of a lot or parcel of land in a recorded plat, the division of a lot or other parcel of land in a recorded plat is prohibited unless first approved by the City assessor and City Planner in accordance with the land division act, Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101 et seq., MSA 26.430(101) et seq.).
- (b) Subdivision plats. The subdivision of a tract of land into two or more lots, building sites, or other divisions for the purpose of sale or building development, must take place in accordance with the land division act, Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101 et seq., MSA 26.430(101) et seq.), as amended.

Secs. 122-626 – 629. Reserved.

Division 3: Landscaping and Screening

ORIGINALLY: 701-714

Sec. 122-630. Purpose. (701) (660)

The intent of this section is to:

- protect and preserve the appearance, character, and value of the community;
- minimize noise, air, soil, groundwater, surface water and visual pollution;
- minimize soil erosion and runoff, provide protection from wind and sun, mitigate the heat island effect and promote energy conservation;
- improve the overall aesthetics and appearance, divide the expanse of pavement, and define parking areas and vehicular circulation within off-street parking lots and other off-street parking facilities;
- buffer residential areas and lower-intensity land uses from more intense land uses;
- encourage an appropriate mixture of plant material, such as evergreen and deciduous trees and shrubs, to protect against disease infestation and produce a more aesthetic and cohesive design;
- encourage the integration of existing vegetation in landscape plans and preservation of specimen trees.

Sec. 122-631. Landscape plan requirements. (702) (661)

A separate detailed landscape and tree protection plan at a scale of not greater than 1"=50' must be submitted to the City as part of the site plan review or tentative preliminary plat review. The landscape/tree protection plan must demonstrate that all requirements of this Division are met and must include, but not necessarily be limited to, the following items:

- (a) Location, spacing, size (caliper), root type (shallow or deep) and descriptions for each plant type (deciduous, evergreen, annual, or perennial) to be planted.
- (b) Location, size (caliper), root type (shallow or deep), health and species name of all trees and plants to remain on the site. If trees or plants are proposed to be remain, information showing how these trees and plants will be protected during construction must be shown.
- (c) Typical straight cross section including slope, height, and width of berms.
- (d) Typical construction details to resolve specific site conditions, such as landscape walls and tree wells used to preserve existing trees or maintain natural grade.
- (e) Details in either text or drawing form to ensure proper installation and establishment of proposed plant materials as prescribed by the American Standard for Nursery Stock.
- (f) Identification and description of grass and other ground cover to be planted and method of planting (sod, plugs, sprigs or seeds).
- (g) Identification of landscape maintenance program in accordance with §122-633.

ORIGINAL:

Sec. 122-702. Landscape plan requirements.

A separate detailed landscape/tree protection plan at a scale of not greater than 1"=50' must be submitted to the City as part of the site plan review or tentative preliminary plat review. The landscape/tree protection plan must demonstrate that all requirements of this Section are met and must include, but necessarily be limited to, the following items:

Location, spacing, size (caliper), root type (shallow or deep) and descriptions for each plant type (deciduous, conifer, annual, or perennial) to be planted.

Location, size (caliper), root type (shallow or deep), health and species name of all trees and plants to remain on the site. If trees or plants are proposed to be remain, information showing how these trees and plants will be protected during construction must be shown.

Typical straight cross section including slope, height, and width of berms.

Typical construction details to resolve specific site conditions, such as landscape walls and tree wells used to preserve existing trees or maintain natural grade.

Details in either text or drawing form to ensure proper installation and establishment of proposed plant materials as prescribed by the American Standard for Nursery Stock.

Identification and description of grass and other ground cover to be planted and method of planting (sod, plugs, sprigs or seeds).

Identification of landscape maintenance program in accordance with Section 122-712

Sec. 122-632. Landscape elements. (711) (662)

The following minimum standards apply:

- (a) **Quality.** Plant materials must be of generally acceptable varieties and species that are not invasive, free from insects and diseases, hardy to Washtenaw County, conform to the current minimum standard of the American Standard for Nursery Stock, and must have proof of any required governmental regulations and/or inspections.
- (b) **Composition.** A mixture of plant material and species, such as evergreen deciduous trees and shrubs, is

recommended as a protective measure against insect and disease infestation. A limited mixture of hardy species is recommended rather than a large quantity of different species to produce a more aesthetic, cohesive design and avoid a disorderly appearing arrangement.

- (c) **Quantity.** Plant quantities may not count to satisfy more than one requirement, unless otherwise stated within the requirement.
- (d) **Berms.** Berms are only permitted at the discretion of the Planning Commission. If permitted, they must be constructed with slopes not to exceed a 1:3 gradient, and protected with sod, seed, or other form of natural ground cover.
- (e) **Tree Species.** All trees must be a species on a list of approved trees maintained by the City of Ypsilanti, with the exception of fruit-bearing trees. Fruit-bearing trees are allowed in yard areas where they do not overhang sidewalks, walkways, or parking lots. The Planning Commission may allow species not on list of approved trees, with a finding that the species is appropriate to the circumstance.
- (f) **Minimum Size-Requirements.** Where landscaping is required the following schedule sets forth minimum size requirements for representative landscape materials:

Plant Material	Minimum Size
Trees	2.5" in caliper
Shrubs	24" in height

- (g) **Credit for Existing Vegetation.** The preservation and incorporation of existing trees and shrubs is encouraged. Existing shrubs and trees may be used to satisfy the requirements of this section, if all of the following requirements apply:

- (1) Paving or other impervious site improvements do not encroach upon the drip line of the existing tree(s) to be preserved.
- (2) If existing plant material is labeled "To Remain" on site plans by the applicant or required by the City, protective techniques must be installed during construction. No vehicle or other construction equipment may be parked or stored within the drip line of any plant material intended to be saved.
- (3) The shrubs and/or trees are in good health. In the event that healthy shrubs or trees which are used to meet the minimum requirements of this Ordinance or those labeled to remain are cut down, destroyed, damaged, or excavated at the drip line, as determined by the City, the applicant must replace them with trees which meet Ordinance requirements.
- (4) The trees or shrubs proposed for credit are not a species that is invasive, brittle, susceptible to disease and insects, has a root structure that will interfere with underground utilities, drops excessive litter or other undesirable characteristics. Species ineligible for credit include but are not limited to: Ash (*Fraxinus*), Black Locust (*Robinia spp.*), Black Walnut (*Juglans nigra*), Siberian Elm (*Ulmus pumila*); Box Elder (*Acer negundo*), Tree-of-Heaven (*Ailanthus spp*), and Gingko Female (*Gingko biloba*).
- (5) The shrubs and/or trees meet the following minimum sizes and may receive credit in lieu of new plantings based on size shown in the table below:

Plant Material	Minimum Size	Size	Credit
Trees	2.5" in caliper	2.5"-8"	1
		8"-12"	2
		12"-20"	3
		Over 20"	5
Shrubs	24" in height	All sizes	1

ORIGINAL. Altered for clarity and ease of use.

Sec. 122-711. Landscape elements.

The following minimum standards must apply:

- a. **Quality.** Plant materials must be of generally acceptable varieties and species that are not invasive, free from insects and diseases, hardy to Washtenaw County, conform to the current minimum standard of the American Standard for Nursery Stock, and must have proof of any required governmental regulations and/or inspections.
- b. **Composition.** A mixture of plant material, such as evergreen deciduous trees and shrubs, is recommended as a protective measure against insect and disease infestation. A limited mixture of hardy species is recommended rather than a large quantity of different species to produce a more aesthetic, cohesive design and avoid a disorderly appearing arrangement.
- c. **Berms.** Berms must be constructed with slopes not to exceed a 1:3 gradient. Berm slopes must be protected with sod, seed, or other form of natural ground cover.
- d. **Credit for Existing Vegetation.** The preservation and incorporation of existing shrubs and trees is encouraged. Existing shrubs and trees may be used to satisfy the requirements of this section, if all of the following requirements apply:

1. Paving, or other site improvements, must not encroach upon the drip line of the existing tree(s) to be preserved.
2. If existing plant material is labeled "To Remain" on site plans by the applicant or required by the City, protective techniques, must be installed during construction. No vehicle or other construction equipment may be parked or stored within the drip line of any plant material intended to be saved.
3. The shrubs and/or trees are in good health. In the event that healthy shrubs or trees which are used to meet the minimum requirements of this Ordinance or those labeled to remain are cut down, destroyed, damaged, or excavated at the drip line, as determined by the City, the contractor must replace them with trees which meet Ordinance requirements.
4. The trees or shrubs proposed for credit are not a species that is invasive, brittle, susceptible to disease and insects, has a root structure that will interfere with underground utilities, drops excessive litter or other undesirable characteristics. Species include but are not limited to: Ash (*Fraxinus*), Black Locust (*Robinia* spp.), Black Walnut (*Juglans nigra*), Siberian Elm (*Ulmus pumila*); Box Elder (*Acer negundo*), and Gingko Female (*Gingko biloba*).
5. The shrubs and/or trees meet the following minimum sizes and must receive credit based on size shown in the table below:

Shrub or Tree Type	Minimum Size	Size	Credit
Trees	2.5" in caliper	2.5"-8"	1
		8"-12"	2
		12"-20"	3
		Over 20"	5
Shrubs	24" in height	All sizes	1

Minimum Size and Spacing Requirements. Where landscaping is required the following schedule sets forth minimum size and spacing requirements; for representative landscape materials:

	Small Trees	Medium Trees	Large Trees
Mature Height	10' - 25'	25' - 50'	> 50'
Growing Space	4'	6' - 8'	8' +
Spacing Apart	20'	30'	40'
Distance from Existing Trees on Abutting Lots	30'	30'	30'
Distance from Street Corners	35'	35'	35'
Distance from Driveway Cuts and Alleys	15'	15'	15'
Distance from Overhead Utilities	None	20' - 40'	40' +
Distance from Street Lights	15'	15'	15'

- f. Tree Species. All trees must be a species on the Approved Trees List maintained by the City of Ypsilanti, with the exception of fruit-bearing trees. Fruit-bearing trees are allowed in yard areas where they do not overhang sidewalks, walkways or parking lots. The Planning Commission may allow species not on the Approved Trees List, with a finding that the species is appropriate to the circumstance.

Sec. 122-633. Installation, maintenance, and completion. (712) (663)

- (a) All required landscaping must be planted before obtaining a Certificate of Occupancy, or a Temporary Certificate of Occupancy may be issued once the appropriate financial guarantee as set forth in §122-317 is placed in escrow in the amount of the cost of landscaping, to be released only after landscaping is completed.
- (b) All landscaping and landscape elements must be planted, and earth moving or grading performed, in a sound and professional manner, according to accepted planting and grading procedures.
- (c) All plant material must be maintained in good condition so as to present a healthy, neat and orderly appearance and must be trimmed or pruned in such a manner so as to not alter their natural growth potential.

- (d) The owner of property required to be landscaped by this Ordinance must maintain such landscaping in a strong and healthy condition, free from physical damage or injury arising from lack of water, chemical damage, insects, diseases, blight or other causes. All materials used to satisfy the requirements of this Ordinance which become unhealthy or dead must be replaced within six (6) months of damage or death or the next appropriate planting period, whichever comes first.
- (e) All landscaped areas must be provided with a readily available and acceptable water supply. Underground sprinkler systems may be installed, utilized and maintained in order to insure the proper watering of all plant materials on the sites.

Sec. 122-634. Screening between conflicting land uses. (703) (664)

(a) Screening between land uses is required when:

- Required elsewhere in this Chapter;
- When a PMD zoning district abuts any other zoning district;
- When a HHS, HC, NC, or GC zoning district abuts a R-1, CN-SF, CN-Mid, CN, or MD zoning district;
- When a non-residential use abuts a property where a residential use occupies the first floor of the principal structure;
- Any building with three dwelling units or more abuts an a building with an equal or lesser number of dwelling units in the R-1, CN-SF, or CN-Mid zoning districts.

(b) The quantities of plant material required by this section may not count for the quantities required elsewhere in this ordinance.

(c) Location. Screening must be provided along all lot lines between conflicting land uses when required by this section. The Planning Commission may approve a waiver for the location of the screen upon a finding that the location of utilities interfere with the proposed location; it may also approve a waiver upon a finding that the height of the screening must conform with [§122-635](#).

(d) Construction. Screens must be a wall, fence, or landscape buffer at least six (6) feet in height.

- (1) A wall or fence must be at least 80% opaque and may be constructed of face brick, poured-in-place simulated face brick, precast brick face panels having simulated face brick, stone, wood, or other durable material, subject to discretionary approval of the approving body . Wire or chainlink fencing with slats is not permitted.

ORIGINAL: (modified 12/14/16 to anticipate future materials.)

A wall or fence must be at least 80% opaque and may be constructed of face brick, poured-in-place simulated face brick, precast brick face panels having simulated face brick, stone or wood. Wire or chainlink fencing with slats is not permitted.

- (2) A landscape buffer must consist of evergreen trees and evergreen shrubbery to maintain a minimum opacity of at least eighty (80) percent. To achieve effective screening, landscape materials must be planted in a staggered manner.

ORIGINAL:

Sec. 122-703. Screening between land uses.

a. Upon any improvement for which a site plan is required, a visual screen at least six (6) feet in height must be constructed along all boundaries between land uses when required by this section. If the screen is composed of nonliving material, such material must be compatible with materials used in construction of the main building but in no case may include wire fencing. Such screen is required when:

- 1. Required elsewhere in this Chapter;
- 2. When a PMD zoning district abuts any other zoning district;
- 3. When a HHS, HC, NC or GC zoning district abuts a R-1, CN-SF, CN-Mid, CN, MD zoning district;
- 4. When a non-residential use abuts a property where a residential use occupies the first floor of the principal structure;
- 5. Any multiple-dwelling use abuts an R-1, CN-SF, CN-Mid, or CN zoning district.

b. Screens must be a wall, fence or landscape buffer. A wall or fence must be 80% opaque and may be constructed of face brick, poured-in-place simulated face brick, precast brick face panels having simulated face brick, stone or wood.

A landscape buffer must consist of evergreen trees and shrubbery to maintain a minimum opacity of at least eighty (80) percent and be no more than four (4) feet in width. To achieve effective screening, landscape materials must be planted in a staggered manner meeting the minimum opacity standard based upon reasonably anticipated growth over a period of three (3) years. The Planning Commission may approve a waiver when the design and placement of the screen meets the intent of the zoning district. A required screen must be located on the lot line except where underground utilities interfere and except in instances where this Zoning Ordinance requires conformity with front yard setback requirements; the Planning Commission may approve a waiver for an alternate location in such instances.

c. PMD district. In the PMD zoning district, where there is a need to provide a greater noise or dust barrier or to screen more intense development, a solid wall or fence be required by the city planner or Planning Commission. The wall or fence must be constructed of face brick,

poured-in-place simulated face brick, precast brick face panels having simulated face brick, stone or wood.

Sec. 122-635. Fences and walls. (713) (665)

Except as otherwise required by this Ordinance, the following regulations apply:

- (a) The use of barbed wire, spikes, nails, or any other sharp point or instrument of any kind on top or on the sides of any fence is prohibited. Planning Commission may waive this restriction with a finding that such materials are in the interest of public safety.
- (b) No fence may be constructed or maintained which is charged or connected with an electrical current.
- (c) Retaining walls must be designed and constructed in accordance with applicable Building Code requirements and the requirements of §122-612.
- (d) Temporary construction fences and fences required for protection around excavations must comply with the Building Code. Such fences must be removed upon the issuance of a Certificate of Occupancy.

ORIGINAL: a-b, moved to the districts. Changed construction fence removal timeline.
Except as otherwise required by this Ordinance, the following regulations must apply:

- a. In a P, R-1, CN-SF, CN-Mid, CN, MD district, fences must not exceed six (6) feet in height. However, fences in the required front yard must not exceed four (4) feet in height and fifty (50%) percent opacity. Opacity is the degree to which a fence is impervious to rays of light. This condition is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence.
- b. In a HHS, HC, NC, GC or PMD district, no fence, wall, or other screening structure shall exceed ten (10) feet in height, and must be constructed in the side or rear yard. Fences a maximum of six (6) feet in height may be permitted in the front yard, in accordance with corner visibility standards, when required by this chapter to screen residential used or zoned property. In such cases, the required front setback for the fence must be the same as for the structure or use which it is intended to buffer.
- c. The use of barbed wire, spikes, nails, or any other sharp point or instrument of any kind on top or on the sides of any fence is prohibited. Barbed wire cradles may be placed on top of fences enclosing public utility buildings or wherever deemed necessary in the interests of public safety.
- d. No fence may be constructed or maintained which is charged or connected with an electrical current.
- e. Retaining walls must be designed and constructed in accordance with applicable Building Code requirements.
- f. Temporary construction fences and fences required for protection around excavations must comply with the Building Code. Such fences must not remain in place for a period greater than a year.

Sec. 122-636. Street Trees (704) (666)

The frontage of all public or private streets for any new or altered use which requires site plan review must be landscaped with street trees as follows:

- (a) Location. The street trees must be centered between the sidewalk and the back of street curb. Planning Commission may grant a waiver of this condition with a finding that utilities necessitate a different location, or that the proposed location of the trees will align with already-established street trees along the same block face, provided that said existing trees are to remain.
- (b) Quantity. A minimum of one (1) tree for every thirty (30) lineal feet of frontage, inclusive of proposed or existing access drives. Existing trees in good health to be preserved may count towards the street tree requirements.
- (c) Planting Area Size. Tree pits provided for street trees must be sufficient for the species of tree provided. Where no sufficient planting bed exists or can be provided for street trees within the right-of-way, the applicant may choose to either plant and maintain the required trees within the front yard; or to provide a fee in lieu of planting in the amount of 100% of the materials and installation cost.

ORIGINAL:

The frontage of all public or private streets for any new or altered use which requires site plan review must be landscaped with street trees as follows:

- (a) A minimum of one (1) tree for every thirty (30) lineal feet on of frontage (the frontage measurement includes proposed or existing access drives). Such street trees must meet the minimum size and spacing requirements set forth in 122-711(e). Existing trees in good health to be preserved may count towards the street tree requirements.
- (b) The street trees must be centered between the sidewalk and the back of street curb.
- c. When potential tree planting site or sites within the right of way has been identified by the City, street trees must be planted in accordance with the Urban Forestry Plan. If additional street trees are required, the thirty foot measurement for other planting locations must be taken from the potential tree planting site(s).
- d. All street tree species must be listed on the Approved Trees List maintained by the City

Sec. 122-637. Foundation landscaping. (707) (667)

Foundation plantings are required in the MD zoning districts and in the GC and NC zoning districts for the Single Story Commercial Building and Large Footprint Single Story Commercial Building building types, and must meet the following standards:

- (a) **Location:** Foundation plantings must be provided along the front or sides of any buildings which face a public road and/or is adjacent to a parking lot or other area which provides access to the building(s) by the general public. Foundation planting areas must be between the front or sides of the building and any paved area, adjacent to the building.
- (b) **Quantity.** Foundation planting areas must contain a minimum of six (6) shrubs per thirty (30) lineal feet of applicable building frontage.
- (c) **Planting Area Size.** Individual planting areas must be of a size appropriate to the proposed plantings, but no less than four feet in depth, measured perpendicular from the building.

ORIGINAL:

Foundation plantings must be provided in the MD and PMD zoning districts and the Single Story Commercial Building and Large Footprint Single Story Commercial Building building types. They must meet the following standards:

Location: Foundation plantings must be provided along the front or sides of any buildings which face a public road and/or is adjacent to a parking lot or other area which provides access to the building(s) by the general public. Foundation planting areas must be integrated into the sidewalk system (between the front or sides of the building and the parking area and/or associated driveways) adjacent to the building.

Foundation planting areas must contain a minimum of six (6) shrubs per thirty (30) lineal feet of applicable building frontage. Individual planting areas must be a minimum of six (6) feet in width.

Planting Area Width. Individual planting areas must be a minimum of six (6) feet in width. At the discretion of the Planning Commission, the minimum width requirements may be reduced.

Sec. 122-638. Site landscaping. (708) (668)

Inclusive of any landscaping required by this section, at least ten percent (10%) of the site area, excluding existing public rights-of-way, must be landscaped. Such site area landscaping may include a combination of the preservation of existing tree cover, planting of new trees and plant material, landscape plazas, gardens, vegetated roofs, and foundation landscaping beds.

REMOVED: largely redundant.

Sec. 122-709. Residential development landscaping.

Landscaping for residential development projects must be provided in accordance with the following requirements:

Other Site Improvements. A landscape plan for a subdivision or site condominium development must include landscaping details of the entrance to the development, provisions for maintaining the natural water run-off, storm water retention and/or detention areas, community buildings and other recreational areas, and any other site improvement which would be enhanced through the addition of landscaping.

Sec. 122-639. Accessory Stormwater Control Features (789) (669)

- (a) **Swales.** Biofiltration swales are permitted in all districts.
- (b) **Pervious paving.** Pervious paving is permitted in all districts, subject to adopted engineering standards.
- (c) **Rain gardens.** Rain gardens installed accessory to one- or two-family uses in the R-1 district or the Townhouse, Cottage, or House building types in the CN, CN-Mid, CN-SF districts do not require engineering review.
- (d) **Rain barrels or cisterns.** Rain barrels or cisterns are permitted in all districts.
 - (1) Underground cisterns or rain barrels are subject to engineering review and constructed in accordance with the State Building Code.
 - (2) Aboveground rain barrel or cistern systems in excess of 250 gallons accessory to the Mansion, Estate, Apartment House, Courtyard Apartment, Apartment Building, Commercial/Mixed-Use Small, Commercial/Mixed-Use Medium, Commercial/Mixed-Use Large, Single-story Commercial Building, Large Footprint Single Story Commercial Building, Multiple Story, or Institutional building types; or in excess of 250 gallons and located in the R-1 district not accessory to a single-family use; or in excess of 250 gallons and located in the MD or PMD districts, must conform to the accessory building standards in place for those building types and be subject to engineering review and constructed in accordance with the Building Code.

- (e) **Vegetated roofs.** Vegetated roof systems are permitted in all districts in accordance with the Building Code.
- 5780 (f) **Other methods.** Other methods of onsite stormwater control may be submitted to the City Planner and, at their discretion, may be approved, approved subject to another City department(s) review, approved subject to Planning Commission review, or denied.
- (g) The plant material required by this section may be used to meet plant material quantity and placement requirements of this Chapter, provided that Planning Commission or other approving body finds that the intent of this Chapter is met.

Sec. 122-640. Screening of electrical equipment and transformers. (710) (670)

- (a) Transformers that may be visible from any primary visual exposure area must be screened with either plantings or a durable non-combustible enclosure which are unified and harmonious with the overall architectural theme, and meet utility provider standards for location and maintenance.
- 5790 (b) Utility equipment must be mounted on the side of a building wherever possible, and must be located where it is substantially screened from public view.

Sec. 122-641. Modifications or exceptions to requirements. (714) (671)

- (a) Buildings Abutting Property Lines. Required screening may be omitted along any lot line where a building wall exists immediately abutting the lot line.
- (b) Location Adjustments. Where property line screening is required, the location may be adjusted at the discretion of the Planning Commission so that the screening may be constructed at or within the setback area, provided the areas between the screening and the property lines are landscaped or retain their natural vegetative state.
- (c) Planning Commission Modifications. Any other requirements of this Section may be waived or modified through site plan approval, provided the Planning Commission first makes a finding that:
 - 5800 (1) That the topographic features or special characteristics of the site create conditions so that the strict application of the provisions of this Section will result in less effective screening and landscaping than alternative landscape designs; or
 - (2) That the public benefit intended to be secured by this Section will exist with less than the required landscaping or screening; or
 - (3) The historic district designation on the property precludes the ability to require any or all of the landscape requirements.
- (d) In the case of conflicting land use screening, with the finding that the design and placement of the screen meets the intent of the zoning ordinance in general and the zoning district in particular.

Secs. 122-642 – 649. Reserved.

Division 4: Accessory Structures, Porches, and Decks

Sec. 122-650. Purpose. (666) (680)

The intent of this division is to regulate accessory structures and uses in order to preserve adequate open spaces and separation between uses which may impact adjacent properties. Accessory uses and structures are generally permitted uses in their respective zoning districts, subject to the provisions of the this division.

Sec. 122-651. General standards for accessory structures. (667) (681)

- (a) Attached Accessory Structures. Where an accessory structure is attached to and made a part of the principal building (excluding breezeways or canopies), such accessory structure must comply in all respects with the requirements of this chapter applicable to the principal building.
- (b) Detached Accessory Structures. The following standards, unless otherwise stated in this chapter, govern all detached accessory structures. A "detached accessory structure" is one which is not attached to the principal structure; however, a breezeway or other enclosed or roofed over connecting way may connect the principal structure to an accessory structure provided that such breezeway or connecting way does not exceed eight feet in width and does not exceed the height of the accessory structure. Detached accessory structures include, but are not limited to, garages, sheds, toolhouses, swimming pools, tennis or basketball courts or other recreational equipment.
 - (1) Building permit. No accessory structure may be erected, moved, altered, or razed until a building permit has been obtained from the Building Department.
 - (2) Height. The maximum height for a detached accessory structure must be 15 feet; except in the PMD district, in which accessory structures may be constructed equal to the permitted maximum height of structures in such district, subject to Planning Commission review and approval.
 - (3) Location. All detached accessory structures must be located in rear yards or side yards. On corner lots, detached accessory structures cannot be located in the required street side yard setback. In no instance may an accessory structure be located within a dedicated easement.
 - (4) Setback and ground coverage requirements. All detached accessory structures must meet the setback and ground coverage regulations for the underlying zoning district and, if applicable, building type.
 - (5) Architecture/siding. The architectural character of all accessory buildings must be compatible with that of the principal building. All accessory buildings in all zones except the PMD district, must be sided and roofed with materials which are complementary with the principal building.
 - (6) Sleeping quarters. The use of any accessory building for the overnight housing of persons is prohibited, unless expressly permitted by this chapter or this Code.
 - (7) Mobile homes. Mobile homes are not permitted as an accessory use to a permitted principal use.
 - (8) Subdivision of lots. No parcel or lot may be subdivided unless and until all detached accessory buildings comply with this chapter with respect to allowable size and setback requirements for the proposed lot on which the buildings are to be located.

Sec. 122-652. Enclosed storage of liquid and solid fuels. (807) (682)

Storage within enclosures of liquid and solid fuels shall be permitted subject to the conditions hereinafter imposed:

- (a) All storage tanks and the handling of all flammable liquids shall be in compliance with the building code as adopted by this Code.
- (b) Below-ground storage tanks shall be located no closer than 50 feet from any property line and, when required, shall be registered with the state fire marshal.

Sec. 122-653. Swimming pools. (668) (683)

Prior to the issuance of a building permit for the construction of an outdoor swimming pool in any zoning district, the following provisions must be satisfied:

- (a) An application for a building permit must be accompanied by a complete and detailed set of plans and specifications for the swimming pool, including type of construction, size, location on lot in relation to lot lines and buildings on the site, fencing, and related equipment, which show that the following minimum standards will be met.
- (b) The swimming pool must be located no closer than ten feet to any side or rear lot line, and no part of any pool may be constructed within a front yard or required side yard setback adjacent to a street.
- (c) Swimming pools must be located a minimum of four feet from any building on the same parcel and a minimum

of 25 feet from any dwelling on an adjoining lot which is located within an R1, MD, CN-SF, CN-Mid or CN district.

- (d) All pool associated wiring and wiring in, around, over or under the pool must comply with the latest edition of the National Electrical Code as adopted by this Code.
- (e) All swimming pools must be enclosed by a fence of a type not readily climbed by children which must be at least five feet in height from the ground level. However, if the entire yard of the residence is enclosed, then this provision may be waived by the Building Department upon inspection and approval of the yard's enclosure; or if the pool is of a portable or above ground type, with a wall height of at least five feet above the surrounding ground surface, and of such construction as not to be readily climbed by children, then the ends of the fence may be attached to the pool structure and the fence need be erected only around the immediate area of the ladder and other means of access to the pool. Gates must be of self-closing latch type with the latch on the inside of the gate, not readily available for children to open. Gates must be securely locked when the pool is not in use. Pools must be enclosed by such fence before water is placed in pool. All fences are subject to the requirements of §122-635.
- (f) Water retained in any pool regardless of depth must be maintained clean and sanitary as provided in the Building Code, water treatment standards.
- (g) The Building Department has the right at any reasonable hour to inspect any swimming pool for the purpose of determining that all the provisions of this chapter are fulfilled and complied with. Any outdoor swimming pool installed, operated or maintained in violation of the provision of this section constitutes a nuisance, and the City may, in addition to the penalties set forth in §122-375, maintain any proper action for the abatement of such nuisance.

Sec. 122-654. Porches, decks, balconies, fire escapes, and barrier-free access ramps. (644) (684)

(a) Porches, decks, terraces and balconies.

- (1) An open or unenclosed porch or terrace may project into a required front yard setback for not more than ten feet, unless otherwise regulated within this chapter. An open, unenclosed terrace or patio flush with the ground is not subject to this restriction.
- (2) An open or unenclosed porch or terrace over nine inches in height must meet all side and rear yard setback requirements.
- (3) An open or unenclosed balcony may project into a required front yard setback for not more than ten feet, but must meet all side and rear yard requirements.
- (4) All enclosed porches, decks, or balconies are an integral part of a building and must meet all yard setback requirements of that structure.

ORIGINAL: (modified 12/14/16)

- (1) An open or unenclosed porch or terrace may project into a front yard for not more than ten feet, unless otherwise regulated within this chapter.
- (2) Open, unenclosed or uncovered porches, decks, terraces, and walkways over nine inches in height must meet all side and rear yard setback requirements.
- (3) Unenclosed balconies may project into a front yard for not more than ten feet, but must meet all side and rear yard requirements.
- (4) All enclosed porches, decks or balconies are an integral part of a building and must meet all yard setback requirements of that structure.

- (b) **Fire escapes.** No fire escape can be located within any front yard. All fire escapes must meet all side and rear yard setback requirements.
- (c) **Barrier-free access ramps.** Barrier-free access ramps may be located within any front, side or rear yard, provided that no portion of the ramp which exceeds over 36 inches in height is located within any required minimum yard setback area. This provision may be waived by the Building Department for a temporary barrier-free access ramp to a single-or two-family dwelling, provided that the Building Department finds that such proposed barrier-free ramp will not pose a fire or safety hazard, and will not obstruct traffic vision. A temporary barrier-free access ramp must be removed within 14 days after the person needing the ramp ceases to occupy a dwelling.
- (d) **Architectural features.** Window sills, cornices, eaves, bay windows, and other architectural features may project into a required side yard not more than two inches for each one foot of width of such side yard; and may extend into any front or rear yard not more than three feet.

Secs. 122-655 – 659. Reserved.

Division 5: Signs

ORIGINALLY ARTICLE XIV

Sec. 122-660. Purpose. (861) (690)

The purpose of this article shall be to permit such signs as will not, by reason of their size, location, construction or manner of display, endanger life or limb, interfere with traffic safety, or otherwise endanger the public morals, health or safety. It is further the intent of this article to:

- Maintain and enhance the aesthetic value of the City;
- Encourage free expression of ideas and dissemination of messages, regardless of content, using signs that are compatible with their surroundings and legible under the circumstances in which they are seen;
- Enhance pedestrian and vehicular traffic safety;
- Minimize the adverse effects of signs on nearby public and private property;
- Protect and enhance economic vitality by assuring aesthetic appeal for residents and visitors;
- Preserve property values;
- Enhance the effectiveness of permitted signs and directional and warning signs;
- Seek the removal of illegal signs and encourage the replacement or removal of nonconforming signs that are incompatible with the purpose of this article.

Sec. 122-661. Generally. (862) (691)

(a) **Building Permit Required.** Except as provided in this Chapter, no sign shall be constructed or erected prior to the issuance of a permit by the Building Department, and approval from other applicable reviewing bodies.

(b) **Public Rights-of-Way.** Signs shall be expressly prohibited from locating in all public rights-of-way and dedicated public easements except as otherwise provided for in this ordinance, and as follows:

- (1) Signs erected by the City or other governmental entities
- (2) Overhead banners
- (3) Sidewalk signs
- (4) Building mounted signs may project over a public right-of-way or easement provided they comply with the applicable design standards for the specific type of sign and that they maintain a minimum clearance of eight feet. A projecting sign shall project not more than four feet from the wall of a building and shall not project above the front wall of the building.

(c) **Signs exempted.**

- (1) Any sign required by City ordinance or State law, as applicable. This includes, but is not limited to, address signs, Fire Department Connection signs, or signs indicating barrier-free parking locations.
- (2) Any sign less than three square feet in area and five feet in height on the interior of a site placed so as to be oriented and clearly legible to persons on the site, provided that each sign be no closer than twenty feet to another such sign.
- (3) **Drive-Through Signs.** Any use that includes a drive-through is permitted to have signs up to a maximum height of six feet and a maximum area of 32 sq. ft. per drive-through use, located in the rear of the site, when placed so as to be oriented and clearly legible to persons on the site.

(d) **Traffic and Pedestrian Hazards.** The placement, size, content, coloring or manner of illumination of signs shall not create traffic or pedestrian hazards. No sign shall make use of the words “stop,” “look,” “danger” or other word, phrase or symbol in a manner that is confusing or misleading. No sign or flashing light shall be erected or maintained in any manner which, by reason of its size, location, context, coloring or manner of illumination, shall constitute a traffic hazard or which shall interfere with the visibility of any traffic control device.

(e) **Obstruction Prohibited.** No sign shall be placed so as to obstruct any fire escape, required exitway, window, or door opening used as a means of passage or as access for firefighting purposes.

(f) **Obstruction to ventilation.** A sign shall not be attached in any form, shape or manner which will interfere with any opening required for ventilation by the building code; except that such signs may be erected in front of and may cover transom windows when not in violation of the provisions of this chapter.

(g) **Maintenance.** All signs, sign frames, sign copy area, panels, structural elements, lamps and electrical hardware shall be maintained in good repair and working order, so as to present a neat and orderly appearance. Non-galvanized or corrosion-resistant materials shall be painted when necessary to prevent corrosion.

(h) **Authorized sign contractors.** Every person before engaging or continuing in the business of constructing, repairing or dismantling signs, poster boards or other display signs in the City, shall first furnish the City a public liability insurance policy, approved by the City attorney, with minimum limits of \$300,000.00 combined

single limit bodily injury and/or property damage, and the contractor agrees to indemnify the City from all damage suits or actions of every nature brought or claimed against the contractor for or on account of injuries to persons or damages to property received or sustained by any person or person through any act of omission or negligence of such erector, agents or employees in the erection, repair or dismantling of any sign, poster board or other display sign. Such policy shall contain a clause whereby such policy cannot be canceled until after a written notice of intention to cancel has been filed with the City clerk at least 30 days prior to the date of cancellation.

- (i) **Sign Area Calculation.** The square footage of a two-, three- or four-faced sign shall mean the square footage of the largest face of the sign.

DELETED: signage plan requirement. Not found to be useful.

DELETED: Modification of sign standards. Only used once; concerns about compatibility with GvR. May bring back as some sort of sign special use?

Sec. 122-662 Construction requirements. (orig part of 862) (692)

- (a) All signs shall conform to the City building code unless more stringent requirements are specified in this article. Signs and sign structures shall be designed and constructed to resist wind and seismic forces as specified in this section. All bracing systems shall be designed and constructed to transfer lateral forces to the foundation. For signs on building the dead and lateral loads shall be transmitted through the structural frame of the building to the ground in such a manner as not to overstress any of the elements thereof.
- (b) The overturning movement produced from lateral forces shall in no case exceed two-thirds of the deadload resisting movement. Uplift due to overturning shall be adequately resisted by proper anchorage to the ground or the structural frame of the building. The weight of earth imposed over footings may be used in determining the dead-load resisting movement. Such earth shall be carefully placed and thoroughly compacted.
- (c) Wind loads. For the purpose of design, wind pressure shall be taken upon the gross area of the vertical projection of all signs and sign structures at not less than 20 pounds per square foot for those portions less than 60 feet above the ground.
- (d) Allowable stresses. The design of wood, concrete or steel members shall conform to the requirements of the most recently adopted version of the Michigan Building Code, and loads, vertical and horizontal, exerted on the soil shall not produce stresses exceeding those specified therein. The working stresses of wire rope and its fastenings shall not exceed 25 percent of the ultimate strength of the rope or fasteners. Working stresses for wind or seismic loads combined with deadloads may be increased as specified in the Michigan Building Code.
- (e) Supports. The supports for all signs or sign structures shall be placed in or upon private property and shall be securely built, constructed and erected in conformance with the requirements of this chapter.
- (f) Fastenings. Signs attached to masonry, concrete or steel shall be safely and securely fastened thereto by means of metal anchors, bolts, or approved expansion screws of sufficient size and anchorage to support safely the loads applied. Anchors which attach signs to masonry surfaces shall be inserted into mortar joints.

Sec. 122-663. Sign permit requirements. (864) (693)

REMOVED: schedule of sign permit requirements. Incorporated into district-by-district tables.

- (a) Application for sign permits shall be made upon forms provided by the Building Department.
- (b) Applications for signs other than overhead banners shall contain or have attached thereto the following information:
- (1) Name, telephone number and address of applicant.
 - (2) Name, address and telephone number of owner or lessee of the premises upon which the sign is to be erected.
 - (3) A written statement signed by the owner or lessee of the premises upon which the sign is to be erected, indicating their consent thereto, or the signed contract between the parties.
 - (4) The address of the premises upon which the sign is to be attached or erected.
 - (5) One set of plans showing the dimensions, materials, height and method of anchorage of the sign.
 - (6) Position of the sign in relation to nearby buildings, structures and property lines.
 - (7) Insurance policy or proof of financial security as required in [§122-661\(h\)](#).
 - (8) On electrical signs, certification by Underwriters Laboratory or some other recognized testing laboratory. Electrical sign installations shall comply with Article 600 of the National Electrical Code.
 - (9) Such other information as deemed necessary to show compliance with this article.
- (c) Application for overhead banners shall contain or have attached thereto, the following information:
- (1) The name of organization or group sponsoring the banner.
 - (2) Phrase on the banner, and/or sketch of the content
 - (3) Location where banner is to be erected.

- (4) The dates the banner will be hung.
- (5) The name, address and telephone number of the applicant.
- 6030 (6) Insurance policy or proof of financial security as required in §122-661(h).
- (7) Such other information as deemed necessary to show compliance with this article and with Act No. 200 of the Public Acts of Michigan of 1969 (MCL 247.321 et seq., MSA 9.140(21) et seq.), and R247.271--R247.279 of the Michigan Administrative Code, 1979.
- (d) Application for sidewalk signs shall include a sidewalk occupancy permit application.

Sec. 122-664. Prohibited signs. (865) (694)

The following signs are prohibited in all zoning districts:

- (a) Unsafe signs. When any sign or sign structure becomes insecure, in danger of falling, or otherwise unsafe, or if any sign or sign structure shall be unlawfully installed, erected, or maintained in violation of any of the provisions of this chapter, or prohibited signs, it shall be considered a nuisance per se. The owner or lessee shall, upon receipt of written notice of the building official, immediately in the case of an unsafe sign-make such sign conform to the provisions of this article or shall remove it. If, after ten days, the notice is not complied with, the building official may remove such sign at the expense of the owner or lessee after having obtained an order from the administrative hearings bureau. The cost, including actual attorney fees, shall be assessed against the property as provided in Article VIII of the City Charter.
- 6040
- (b) Prohibited signs.
- (1) Animated signs.
- (2) Portable signs, not including sidewalk signs.
- (3) Signs mounted upon a roof.
- 6050 (4) Signs containing obscene material. Signs containing symbols that area or purports to be an imitation of or resembles, or which may be mistaken for a traffic control device or that attempts to direct the movement of traffic.
- (5) Mechanical Signs.
- (6) Sign, electronic message, excepting digital billboards.
- (7) Signs not specifically permitted under the sections of this chapter.
- (8) Signs with less than six feet horizontal clearance or 12 feet vertical clearance from overhead electrical conductors which are energized in excess of 250 volts.

NOTE: changed (6) from "electronically illuminated message sign" to current; reflects new definition & also distinguishes prohibition of electronic message signs from digital billboards, a point of frequent confusion.

Sec. 122-665. Sign Design Standards. (866) (695)

(a) Freestanding Signs

- (1) **Materials.** Freestanding signs shall be constructed out of decorative materials that complement the design of principal buildings within the development. Natural materials such as stone, decorative masonry, wood, or metal are preferred sign construction materials. The use of exposed neon tubing in conjunction with other types of materials to emphasize the business name or logo is permitted.
- (2) **Billboards.** New billboard permits will be issued only in the following cases:
- (i) For non-digital billboards, when one non-conforming billboard is removed
- (ii) For digital billboards, when two non-conforming billboards are removed.
- (3) **Digital billboards.**
- 6070 (i) The message displayed on digital billboards may change a maximum of once every 6 seconds.
- (ii) All billboards must provide a setback from any adjacent residential zoning district equal to the height of the billboard.
- (iii) Billboard structures which have two or more panels stacked, one above the other, are not permitted.
- (iv) Double-faced billboard structures (two panels mounted on the same structure back-to-back) are permitted.
- (v) Spacing between billboards shall be 1,000 feet as provided in the Highway Advertising Act of 1972, as amended.
- (vi) All billboard structures shall be of steel. No wood or other combustible material shall be permitted to support such signs.
- 6080 (vii) Billboard structures shall be restricted to and used only with respect to interstate highways, freeways or primary highways as set forth in the Highway Advertising Act, Act No. 106 of the Public Acts of Michigan of 1972 (MCL 252.301 et seq., MSA 9.391(101) et seq.).
- (4) **Sidewalk Signs.**
- (i) Sidewalk Signs may have a maximum area of 6 square feet per side.

- (ii) Sidewalk signs may be located on the sidewalk adjacent to the applicant's business.
- (iii) Sidewalk signs shall be located such that they will not impede pedestrian traffic on the sidewalk, and such that they will not present a hazard to vehicular traffic.
- (iv) Sidewalk signs may not be permanently affixed to any object, structure, or the ground.
- (v) Sidewalk signs may only be displayed during business hours and shall be removed when the business to which the sign is accessory is closed.
- (vi) Each business may have a maximum of one sidewalk sign.
- (vii) Sidewalk signs shall be made of durable materials.

(b) Building Mounted Signs.

- (1) Location. Building mounted signs may be located on any façade that faces a street, parking area, alley, or on a façade where a public entrance is located.
 - (i) Illuminated building mounted signs may not be located on a façade that faces a property line that abuts a residential zoning district unless the sign is set back at least 200 feet from the property line or screening is provided that will completely obscure the view of the sign from the adjacent residential district.
- (2) Minimum Height. Signs that project more than eighteen inches into a right-of-way or over an entrance or other pedestrian or vehicular access point shall maintain a minimum clearance of 8 feet between the grade level below the sign and the lowest part of the sign, inclusive of sign structures and support devices.
- (3) Materials.
 - (i) Building mounted signs shall incorporate exterior materials, finishes and colors that are the same, similar, or complementary to those used on the principal building.
 - (ii) Building mounted signs shall be professionally constructed using high-quality materials such as metal, stone, hard wood, or brass. The use of exposed neon tubing is permitted.
 - (iii) External illumination of signs shall be limited to fully-shielded light fixtures with a maximum of 1000 lumens. Such fixtures shall be mounted above the sign face with all light directed downward and concentrated on the area of the sign to prevent glare upon the street or adjacent property.
- (4) Window Signs. May not occupy more than twenty-five percent (25 %) of the total transparent area of any individual window.
- (5) Banners. Banner requirements shall be as follows:
 - (i) The banner must be made of nonflammable material that will not shred and has adequate air holes. For banners hanging overhead across a street, roadway or highway the banner must contain at least three air holes for every 40 feet.
 - (ii) The Building Department shall be permitted to inspect the banner or a sample of material prior to it being erected.
 - (iii) The banner must be securely attached, sufficient to withstand storms, including strong gusts of wind and continuous pounding by the elements. The manner of attachment shall first be submitted to the Building Department.
 - (iv) If a banner becomes partially unsecured, it shall be immediately reattached or removed by the entity which erected it.
 - (v) If a banner begins to shred, it shall be immediately repaired or removed by the entity which erected it.
 - (vi) If the entity which erected the banner fails to comply with is the standards of [section \(iii\)](#) or fails to remove the banner by the time the permit expires, the City shall remove the banner and shall charge the cost thereof to the entity erecting the banner.
 - (vii) Any banner permit may be canceled by the City if the installation becomes dangerous to motorists or pedestrians, unduly interferes with free movement of traffic or otherwise endangers the health, safety or welfare of persons in the City.
 - (ix) A banner shall not have displayed thereon any symbol which is or purports to be an imitation of or resembles, or which may be mistaken for a traffic control device or which attempts to direct the movement of traffic.

Secs. 122-666 – 669. Reserved.

Division 6: Traffic

Sec. 122-670. Circulation Standards. (273) (700)

Circulation Standards are intended to preserve and improve walkability and pedestrian/bicyclist safety within the walkable urban districts, while maintaining adequate vehicular access.

(a) *General*

- (1) Streets are intended for use by vehicular and pedestrian traffic and to provide access to parcels.
- (2) Streets generally consist of vehicular travel and/or parking lanes and public frontages.
- (3) Streets must be designed in context with the urban form and desired design speed of the districts through which they pass. The public frontages of streets that pass from one district to another must be adjusted accordingly or, alternatively, the district may follow the alignment of the street to the depth of one lot, retaining a single public frontage throughout its trajectory.
- (4) Pedestrian comfort and safety is the primary consideration of the public frontage. Design conflict between vehicular and pedestrian movement generally must be decided in favor of the pedestrian.
- (5) Each lot must front a street, pedestrian passage, and/or civic space, such as a park. An entrance to the building with required frontage must face the street or, if a street is not present, the Planning Commission may approve an entrance on the pedestrian passage or civic space.
- (6) All circulation plans must include the easements for non-motorized pathways in the City of Ypsilanti's Non-Motorized Plan, the ReImagine Washtenaw Corridor Improvement Study, and any planned road easement expansions approved by City Council.

(b) *Vehicular access for infill and new development.* A system of joint use driveways and cross access easements must be established wherever feasible and the building site must incorporate the following:

- (1) An alley or system of alleys extending the entire length of each parcel served to provide for driveway separation consistent with access management classification system and standards.
- (2) Stub-outs and other design features to make it visually obvious that the abutting properties may be tied in to provide cross access via a service drive;
- (3) A unified access and circulation system plan that includes coordinated or shared parking areas is encouraged wherever feasible.

(c) *Access for sites comprised of more than one building type, under the same ownership*

- (1) In the interest of promoting unified access and circulation systems, development sites under the same ownership or consolidated for the purposes of development and comprised of more than one building site are not considered separate properties in relation to the access standards of this code.
- (2) The number of connections permitted must be the minimum number necessary to provide reasonable access to these properties, not the maximum permitted for that frontage. All necessary easements, agreements, and stipulations required under joint use driveways and cross access easements must be met. This also applies to phased development plans.
- (3) The street network shall be designed to define blocks as established by district. The block perimeter is measured as the sum of lot frontage lines. Block perimeter at the edge of the development parcel is subject to approval by the Planning Commission.
 - (i) Centers and Core Neighborhoods (C, CN, CN-SF, CN-Mid): Block perimeter must not exceed a total length of 1600 feet and the maximum block length shall generally be 400 feet.
 - (ii) Corridors and Health and Human Services (HC, NC, GC, HHS): Block perimeter must not exceed a total length of 2,000 feet and the maximum block length shall generally be 500 feet.
- (4) In Center Districts, a continuous network of rear and side alleys or lanes must serve as the primary means of vehicular ingress to individual lots whenever possible. Alley or lane entrances should generally align so as to provide ease of access for service vehicles.
- (5) All streets must terminate at other streets, forming a network. Internal streets must connect wherever possible to those on adjacent sites. Cul-de-sacs are subject to approval by the Planning Commission to accommodate specific site conditions only.

ORIGINAL:

Sec. 122-273. Circulation Standards.

Circulation Standards will apply to redevelopment and new development of parcels within the walkable urban districts.

General

1. Streets are intended for use by vehicular and pedestrian traffic and to provide access to lots and open spaces.
2. Streets must generally consist of vehicular lanes and public frontages.
3. Streets must be designed in context with the urban form and desired design speed of the districts through which they pass. The public frontages of streets that pass from one district to

another must be adjusted accordingly or, alternatively, the district may follow the alignment of the street to the depth of one lot, retaining a single public frontage throughout its trajectory.

4. Within all the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS Districts, pedestrian comfort must be a primary consideration of the street. Design conflict between vehicular and pedestrian movement generally must be decided in favor of the pedestrian.

5. The street network must be designed to define blocks as established by district. The perimeter must be measured as the sum of lot frontage lines. Block perimeter at the edge of the development parcel must be subject to approval by the Planning Commission.

6. All streets must terminate at other streets, forming a network. Internal streets must connect wherever possible to those on adjacent sites. Cul-de-sacs must be subject to approval by the Planning Commission to accommodate specific site conditions only.

7. Each lot must front a street, pedestrian passage, and/or civic space, such as a park. An entrance to the building with required frontage must face the street or, if a street is not present, the Planning Commission may approve an entrance on the pedestrian passage or civic space.

8. All circulation and block plans must include the easements for non-motorized pathways in the City of Ypsilanti's Non-Motorized Plan, the ReImagine Washtenaw Corridor Improvement Study and any planned road easement expansions approved by City Council.

Circulation plan required with site plan for proposal less than 3 acres. For proposed development that is less than three acres in size, a circulation plan must be submitted which identifies potential cross-and joint-access to adjacent parcels, the existing Block Layout. The Block must be defined as lots and/or all contiguous lots must be considered to be part of a block for this purpose. Pedestrian accommodations and alternative transportation modes must be reflected in the submitted circulation plan. The streetside zone parameters, as outlined Article XI, Division 4 of this Ordinance will also be required to be applied to existing streets. The measurement of the streetside zone, must be from the edge of curb.

Block plan required with site plan for proposal greater than 3 acres. When a proposed development is three acres or greater, a block plan must be required as part of the proposed development which requires the proposed development to construct a block assembly as part of the development as outlined in sub-section d of this Section: Circulation standards for new streets. An applicant must submit the block length, block perimeter and the street type that will be constructed for the development. Streets must be designed to allow for adjacent parcels to connect to existing streets.

Circulation standards.
Streets are intended for use by vehicular and pedestrian traffic and to provide access to lots and open spaces.
Circulation standards must generally consist of vehicular lanes, parking, bicycle lanes, landscape, sidewalks, and outdoor seating.
Streets must be designed in context with the urban form and desired design speed of the districts through which they pass. Circulation that pass from one districts to another must be adjusted accordingly or, alternatively, the district may follow the alignment of the street to the depth of one lot, retaining a single public frontage throughout its trajectory.
Within all the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, pedestrian comfort must be a primary consideration of the street. Design conflict between vehicular and pedestrian movement generally must be decided in favor of the pedestrian.

Block Perimeter and Block Size. The street network must be designed around a series of blocks. In order to create a system of land subdivision and development which links one area to another, land should be organized by development blocks to the maximum extent feasible given the topography and physical characteristics of each individual site. A block perimeter must be measured as the sum of lot frontages. Each district is regulated by a varying block size and perimeter:

a. Centers and Core Neighborhoods (C, CN, CN-SF, CN-Mid): Block perimeter must not exceed a total length of 1600 feet and the maximum block length must generally be 400 feet.

b. Corridors and Health and Human Services (HC, NC, GC, HHS): Block perimeter must not exceed a total length of 2,000 feet and the maximum block length must generally be 500 feet.

All Streets must terminate at other streets, in order to form a network. Internal streets must connect wherever possible to those on adjacent sites. Cul-de-sacs must be subject to approval by the Planning Commission to accommodate specific site conditions only.

Each lot must front a street, pedestrian passage, or civic space.
A continuous network of rear and side alleys or lanes, must serve as the primary means of vehicular ingress to individual lots, when possible within Center Districts. Alley or lane entrances should generally align so as to provide ease of ingress for service vehicles.

Vehicular access for infill and new development. New development and redevelopment for joint use driveways and cross access easements. A system of joint use driveways and cross access easements must be established wherever feasible and the building site must incorporate the following:
A continuous service drive or cross access extending the entire length of each parcel served to provide for driveway separation consistent with access management classification system and standards.
Stub-outs and other design features to make it visually obvious that the butting properties may be tied in to provide cross access via a service drive;
A unified access and circulation system plan that includes coordinated or shared parking areas is encouraged wherever feasible.

Access for outparcels and phased development plans
In the interest of promoting unified access and circulation systems, development sites under the same ownership or consolidated for the purposes of development and comprised of more than one

building site must not be considered separate properties in relation to the access standards of this code. The number of connections permitted must be the minimum number necessary to provide reasonable access to these properties, not the maximum permitted for that frontage. All necessary easements, agreements, and stipulations required under joint use driveways and cross access easements must be met. This must also apply to phased development plans.

2. All access to outparcels must be internalized using the shared circulation system of the principal development. Access to outparcels must be designed to avoid excessive movement across parking aisles and queuing across surrounding parking and driving aisles

Sec. 122-671. Public service access. (645) (701)

All buildings and structures must be provided with adequate access for fire, police, sanitation, and public works vehicles. The Planning Commission may require paved turnaround areas to allow adequate maneuverability for public service vehicles on a site.

Sec. 122-672. Sidewalks. (647) (702)

- (a) For all development projects, either a new public sidewalk or if necessary the reconstruction of existing sidewalks, must be provided along the perimeter of the lot which abuts any street. New or reconstructed sidewalks must be aligned with existing or proposed sidewalks and must be constructed to City standards and subject to Chapter 94 of the City Code of Ordinances.
- (b) This requirement may be modified by the Planning Commission as follows:
 - (1) A shared-use path may be provided in lieu of a sidewalk, upon a finding that any portion of the perimeter of a lot is planned to be part of an area-wide non-motorized network that requires such a facility.
 - (2) A fee in lieu of construction may be provided by the development in the amount of 100% of the construction cost, upon a finding that any portion of the perimeter of a lot is included in a transportation project programmed in the City's 5-year Capital Improvement Plan, or with a finding that sidewalk construction at this location is impractical due to lack of connectivity. Any fee paid for this purpose is reserved for non-motorized improvements as a part of the identified transportation project or for path and sidewalk construction throughout the City, respectively.
 - (3) Any easement required for the construction, maintenance, or operation of a modified facility must be included on the site plan at the time the modification is requested.

Sec. 122-673. Direct access to major thoroughfare. (642) (703)

Whenever this chapter requires that direct access to a major thoroughfare be provided, one of the following provisions must be met:

- (a) Direct driveway ingress and egress is provided from the site directly to a major thoroughfare.
- (b) Access to the site from a major thoroughfare does not traverse through or abut any land zoned R1, MD, CN-SF, CN-Mid, and CN.


Sec. 122-674. Street frontage requirements. (643) (704)

No lot can contain any building used in whole or in part for any purpose unless such lot abuts the minimum lot width of the building type or zoning district on at least one street; or unless it has an exclusive, unobstructed private easement of access or right-of-way of at least 50 feet wide to a street. No more than one single-family dwelling or one nonresidential land use for such frontage or easement will be permitted.

Sec. 122-675. Traffic visibility. (649) (705)

- (a) No structure, wall, fence, vehicle, shrubbery, or trees can be erected, parked, planted or maintained on any lot which will obstruct the view of the driver of a vehicle approaching an intersection or maneuvering from a driveway. Provided, shrubbery and low fences or walls not exceeding 30 inches in height above the curb level and branches of trees not less than eight (8) feet above the street level will be permitted.

- (b) This means, in the case of an intersection, that there must be provided an unobstructed triangular area formed by the street property lines and a line connecting them at points 25 feet from the intersection of the pavement edge lines, or in the case of a rounded corner, from the intersection of the street property lines extended. In the case of a driveway, there must be provided an unobstructed triangular area formed by the street right-of-way line, the edge of the driveway, and a line connecting them at points ten (10) feet from the intersection of the street right-of-way line and driveway edge.



Secs. 122-676 – 679. Reserved.

Division 7: Off-Street Parking and Loading Requirements

Sec. 122-680. Purpose. (831) (710)

The purpose of this Division is to recognize that motor vehicles, while part of the social and economic well-being of the community, can cause conditions and problems of parking and storage which can have a negative impact on the safety, appearance, health and welfare of the community. It is the intent of this article to provide standards for the parking and storage of motor vehicles in order to ensure that off-street parking facilities are in harmony with the use of surrounding properties and all modes of transportation; maintain barrier-free pedestrian access, ensure adequate accessibility to the off-street parking facilities from City street; and to set standards for design and construction of parking facilities compatible with the health, safety and general welfare of the community.

Sec. 122-681. Scope. (832) (711)

In all zoning districts, off-street parking facilities shall be provided for the storage and parking of motor vehicles and bicycles for the use of occupants, employees, and patrons of all buildings, structures, residences, businesses, or establishments erected, altered, constructed, changed in use, or commenced after the effective date of the ordinance from which this chapter derives. Such space (or spaces) shall be maintained and not be encroached upon, unless an equivalent number of such spaces are provided elsewhere, in conformance with this chapter.

- (a) New or altered buildings. No building or structure shall hereafter be erected, and no existing structure may be so altered that it is increased in size or intensity of use, unless adequate parking space, as required by the provisions of this article, is provided for the entire building or structure as erected or altered.
- (b) Change in use. The use of any building or structure shall not be changed if additional parking space would be required as a result of the change in use, unless the minimum parking space as required by the provisions of this article is provided for the entire building.
- (c) Areas excepted. The provisions of this article regarding quantity of spaces provided shall not apply to uses in the Center District or existing commercial uses in the Historic Corridor zoning districts, except those spaces required for upper-story dwellings. A fee in lieu of providing off-street parking for upper-story units in the Center or Historic Corridor is permitted in accordance with [§122-697](#).

ADDED HISTORIC CORRIDOR

Sec. 122-682. Off-street parking layout and construction for one- and two-family dwellings. (833(1)) (712)

Off-street parking facilities required for one- and two-family dwellings shall consist of a parking strip, apron, driveway, garage, carport, or combination thereof and shall be located on the premises they are intended to serve subject to the provisions of [§122-651](#). Further, parking areas serving one- and two-family dwellings shall be subject to the following:

- (a) **Ingress and egress.** No individual curb cut to a street or alley for a single driveway shall exceed 20 feet in width. The total width of all curb cuts shall not exceed 35 feet on all property lines. On lots with a lot width of 60 feet or less, no more than one curb cut to a single street is permitted. All curb cuts accessing Washtenaw Avenue (M-17) must comply with the Michigan Department of Transportation M-17 Access Management Plan.
- (b) **Driveways.** On lots used for one-family or two-family residential purposes, maneuvering or backing of vehicles into a street or alley is permitted. Driveways may cross the required front yard, or the required street side yard on a corner lot, provided that the total area of the driveway do not exceed 30 percent of the area of such required yard. Driveways may have no less than 9 feet of clear width.
- (c) **Surfacing.** Parking areas and driveways shall be surfaced with crushed limestone or similar gravel material, or shall be hard surfaced with asphalt, concrete, or similar bonded material. Porous paving is also allowed. However, parking areas which are designed for five or more spaces must meet the requirements of [§122-683](#). That portion of the driveway between the lot line and the public way shall be paved with concrete a minimum of six inches thick for residential occupancies. Curb cuts along state trunk lines shall comply with the requirements of the state department of transportation. All other curb cuts shall comply with adopted standards of the Department of Public Works.
- (d) **Parking in yards.** No parking shall be permitted in the front yard, or in the street side yard on a corner lot, except on a driveway which leads to a parking area that is beyond the front line of the structure and the space is in compliance with [§122-685](#).

Sec. 122-683. Off-street Parking layout and construction for all other uses. (833(2) & 835(1-9, 12, 13)) (713)

Off-street parking facilities required for multiple-family and nonresidential uses shall be located on the same lot or parcel as the building or use they are intended to serve, or within 300 feet of such building or use, measured from the nearest point of the building to the nearest point of the off-street parking lot. A shared parking agreement or use easement for the land intended for shared parking must be on file with the county register of deeds, in order for the shared parking spaces to satisfy the quantity requirement. Parking spaces may be located within buildings or structures consistent with the Building Code.

- (a) **Review and approval requirements.** Except for off-street parking accessory to single- or two-family dwelling units, review and approval is required for off-street parking areas in accordance with [Article III](#) of this chapter.
- (b) **Ingress and egress.** Adequate ingress and egress to such parking lot shall be provided by means of clearly defined and limited drives having a minimum width of 20 feet for two-way traffic and 10 feet for one-way traffic, with a maximum of 30 feet. All such drives shall be located so as to minimize traffic congestion.
 - (1) On lots with a lot width of 100 feet or less, no more than one curb cut to a single street is permitted.
 - (2) All curb cuts accessing Washtenaw Avenue (M-17) must comply with the Michigan Department of Transportation M-17 Access Management Plan and the ReImagine Washtenaw Corridor Improvement Study.
 - (3) All curb cuts and approaches to such parking lots shall comply with adopted City standards for curb cuts.
 - (4) Ingress and egress for the parking area in an area zoned CN-Mid, CN, HC, NC, GC, C, HHS, PMD shall not cross land zoned for P, R1 or CN-SF.
 - (5) Parking lot driveways shall be situated so as to minimize vehicle headlights from shining on residential dwellings.
 - (6) Where possible, curb cuts shall be located across from any existing curb cuts on the opposite side of the street, or shall be offset from any opposite-side curb cuts by at least 25 feet.
 - (7) No curb cut for a parking lot may be closer than 50 feet to the intersection of any two streets as measured along the street right-of-way line. However, the Planning Commission may allow a curb cut for a parking lot situated on a small land parcel located no closer than 20 feet to the intersection of any two streets, upon finding that no other access points in compliance with City Ordinances is possible due to the size of the parcel.
- (c) **Access.** All parking spaces shall be provided adequate access by pedestrians and vehicles:
 - (1) Walkways in Parking Lots. Paved walkways a minimum of 5 feet in width shall be provided for access to adjacent parks, commercial areas, transit stops, anticipated walkways and institutions. Pedestrian movement shall be accommodated within parking lots through raised walkways, marked crosswalks or similar methods.
 - (2) Vehicular Access. All parking spaces must be accessible to vehicles by means of maneuvering aisles. Except for one- and two-family uses, maneuvering or backing from a parking space directly onto a street or walkway shall be prohibited, and all parking spaces shall be designed so that any motor vehicle may be parked or unparked without moving another vehicle.
- (d) **Maneuvering drives.** Each driveway providing access to an off-street parking lot containing five or more parking spaces shall be a minimum of ten feet in width. Where a turning radius is necessary, it shall be an arc that allows unobstructed vehicle flow.
- (e) **Surfacing.** All parking and loading facilities and access drives shall be paved with a durable bonded material in accordance with accepted engineering standards, or alternative surfacing materials to minimize impervious surface and stormwater runoff, employ environmental and other best practices, and achieve low impact design, at the discretion of the City Engineer. Use of pervious alternative surfaces is encouraged in proximity to the Huron River and Paint Creek. Paving materials proposed to improve aesthetics may also be considered by the City Planner and the Planning Commission. Alternative surfaces proposed shall be reviewed by the City's consulting engineer.
- (f) **Drainage.** All off-street parking and loading areas shall be graded and drained to public storm sewers. As an alternative, if in the opinion of the City's consulting engineer, the soils are of a type which will allow for efficient drainage, the use of drywells, infiltration trenches, swales, bio-retention or other best management practices for controlling urban runoff quality are permitted. No surface water shall be permitted to drain onto adjoining properties, unless there is a common engineered drainage system shared with the adjoining property or an appropriate watershed easement has been obtained. No surface water drainage from an off-street parking lot shall be permitted to drain across a public sidewalk.
- (c) **Setback from street.** Parking lot setbacks are designated by the zoning district in which they are located. An allowed exception are circular drives, which may be located in a required minimum front yard or street side yard, provided that such drives shall be designed so that no parking space is located closer than 25 feet to any street right-of-way line.
- (d) **Setback from adjacent lot.** Parking areas are required to be 10' from any adjacent lot. Planning Commission may waive this requirement in whole or in part with a finding that the lot shares a common access and common

parking with the adjoining lot, or that stormwater, landscaping, and other similar concerns have been adequately addressed with other methods.

NEW for 2016: (d), the setback from adjacent lot. Hopefully will help to improve snow storage, drainage, neighbor relations.
COMBINED: 833(2) & 835. DUPLICATIVE.

- (g) **Striping.** For parking lots containing five or more spaces, all spaces shall be outlined with three-inch wide strips of white or yellow paint, except that barrier-free spaces shall be blue, with a symbol of compliance in blue, and signed in accordance with the State Barrier-Free Code.
- (h) **Wheel stops.** For parking lots containing five or more spaces or accessory to commercial uses, wheel stops or curbing shall be provided for all parking spaces to prevent any vehicle from projecting beyond the parking lot area, bumping any wall or fence, or encroaching upon any landscaping. In all cases where parking lots abut public or private sidewalks, continuous concrete curbing or bumper stops, at least six inches high, shall be placed so that a motor vehicle cannot be driven or parked on, or hang over, any part of any sidewalk.
- (i) **Lighting.** With the exception of multiple-family dwellings on individual lots containing no more than four units, parking and loading facilities utilized during night-time hours shall be artificially illuminated. All such outdoor lighting shall meet the requirements of [§122-609](#).
- (j) **Maintenance.** All off-street parking areas, including striping, shall be maintained in good usable condition, and when necessary shall be treated to prevent dust or other nuisances. Such parking areas and drives shall also be kept free of litter, debris, and refuse.
- (k) **Additional requirements.** In addition to the above requirements, parking areas shall comply with additional requirements or conditions which may be deemed as reasonably necessary by the Planning Commission for the protection of abutting lots.

PREVIOUSLY: 833(1), 833(2), AND 835(1-9, 12, 13)

Sec. 122-833. General requirements.

Any person, organization, or establishment who has any ownership interest in or the control of any real estate within the city is required to provide and maintain in a usable condition off-street parking spaces as follows:

- (1) *Off-street parking for one- and two-family dwellings.* Off-street parking facilities required for one- and two-family dwellings shall consist of a parking strip, apron, driveway, garage, carport, or combination thereof and shall be located on the premises they are intended to serve subject to the provisions of section 122-667. Further, parking areas serving one- and two-family dwellings shall be subject to the following:

- a. *Driveways.* On lots used for one-family or two-family residential purposes, maneuvering or backing of vehicles into a street or alley is permitted. Driveways may cross the required front yard, or the required street side yard on a corner lot, provided that the total area of the driveway do not exceed 30 percent of the area of such required yard.
- b. *Ingress and egress.* No individual curb cut to a street or alley for a single driveway shall exceed 20 feet in width. The total width of all curb cuts shall not exceed 35 feet on all property lines. On lots with a lot width of 60 feet or less, no more than one curb cut to a single street is permitted. All curb cuts accessing Washtenaw Avenue (M-17) must comply with the Michigan Department of Transportation M-17 Access Management Plan.
- c. *Surfacing.* Parking areas and driveways shall be surfaced with crushed limestone or similar gravel material, or shall be hard surfaced with asphalt, concrete, or similar bonded material. Porous paving is also allowed. However, parking areas which are designed for five or more spaces must meet the requirements of subsection 122-835(5). That portion of the driveway between the lot line and the public way, shall be paved with concrete a minimum of six inches thick for residential occupancies and eight inches thick for commercial occupancies. Curb cuts along state trunk lines shall comply with the requirements of the state department of transportation. All other curb cuts shall comply with adopted standards of the Department of Public Works.
- d. *Parking in yards.* No parking shall be permitted in the required front yard, or in the required street side yard on a corner lot, except on a driveway which leads to a parking area that is beyond the front line of the structure and the space is in compliance with section 122-834.

- (2) *Off-street parking for multiple-family and nonresidential uses.* Off-street parking facilities required for multiple-family and nonresidential uses shall be located on the same lot or parcel as the building or use they are intended to serve, or within 300 feet of such building or use, measured from the nearest point of the building to the nearest point of the off-street parking lot. A shared parking agreement or use easement for the land intended for shared parking must be on file with the county register of deeds, in order for the shared parking spaces to satisfy requirement parking.

Sec. 122-835. Parking layout and construction.

Off-street parking facilities shall be designed, constructed, and maintained in accordance with the following requirements.

(1) *Review and approval requirements.* Except for off-street parking accessory to single-or two-family dwelling units, review and approval is required for off-street parking areas in accordance with Article IV of this chapter.

- a. Plans for parking lots shall be drawn at scale, showing existing and proposed grades, drainage, sewers, type of surfacing, proposed parking layout, striping, signage, and related landscaping or screening.
- b. Upon completion of construction, a parking lot must be inspected and approved before a certificate of occupancy can be issued for the parking lot or for the building or use for which the parking is intended to serve.
- c. In the event that required parking cannot be constructed because of cold or inclement weather, a temporary certificate of occupancy may be issued by the building department, provided the applicant first deposits a performance guarantee with the city in accordance with section 122-134.

(2) *Access.* All parking spaces shall be provided adequate access by pedestrians and vehicles:

- a. *Walkways in Parking Lots.* Paved walkways a minimum of 5 feet in width shall be provided for access to adjacent parks, commercial areas, transit stops, anticipated walkways and institutions. Pedestrian movement shall be accommodated within parking lots through raised walkways, marked crosswalks or similar methods.
- b. *Vehicular Access.* All parking spaces must be accessible to vehicles by means of maneuvering aisles. Except for one-and two-family uses, maneuvering or backing from a parking space directly onto a street or walkway shall be prohibited, and all parking spaces shall be designed so that any motor vehicle may be parked or unparked without moving another vehicle.

(3) *Ingress and egress.* For parking lots containing five or more spaces, adequate ingress and egress to such parking lot shall be provided by means of clearly defined and limited drives having a minimum width of 20 feet, with a maximum of 30 feet. All such drives shall be located so as to minimize traffic congestion. All curb cuts and approaches to such parking lots shall comply with adopted city standards for curb cuts. Ingress and egress for the parking area in an area zoned CN-Mid, CN, HC, NC, GC, C, HHS, PMD shall not cross land zoned for P, R1 or CN-SF. Parking lot driveways shall be situated so as to minimize vehicle headlights from shining on residential dwellings. Where possible, curb cuts shall be located across from any existing curb cuts on the opposite side of the street, or shall be offset from any opposite-side curb cuts by at least 25 feet. No curb cut for a parking lot may be closer than 50 feet to the intersection of any two streets as measured along the street right-of-way line. However, the Planning Commission may allow a curb cut for a parking lot situated on a small land parcel located no closer than 20 feet to the intersection of any two streets, upon finding no other access points in compliance with City Ordinances is possible due to the size of the parcel.

(4) *Internal maneuvering drives.* Each driveway providing access to an off-street parking lot containing five or more parking spaces shall be a minimum of ten feet in width. Where a turning radius is necessary, it shall be an arc that allows unobstructed vehicle flow.

(5) *Surfacing.* All parking and loading facilities and access drives shall be paved with a durable bonded material in accordance with accepted engineering standards. Alternative surfacing materials may be considered in order to minimize impervious surface and stormwater runoff, employ environmental and other best practices, and achieve low impact design. Use of pervious alternative surfaces is encouraged in proximity to the Huron River. Paving materials proposed to improve aesthetics may also be considered by the City Planner and the Planning Commission. Alternative surfaces proposed shall be reviewed by the City's consulting engineer. Consideration of alternative surfacing in accordance with best management practices will be given by the Planning Commission for off-street parking lots of five to ten parking spaces serving residential uses. In R-1, CN-SF, CN-Mid, and CN, paving shall not be required for off-street parking areas of four spaces or less, in which case the spaces shall be surfaced with gravel or similar material and so laid out as to clearly indicate that the spaces are reserved for parking of motor vehicles.

(6) *Drainage.* All off-street parking and loading areas shall be graded and drained to public storm sewers. As an alternative, if in the opinion of the City's consulting engineer, the soils are of a type which will allow for efficient drainage, the use of drywells, infiltration trenches, swales, bio-retention or other best management practices for controlling urban runoff quality are permitted. No surface water shall be permitted to drain onto adjoining properties, unless there is a common engineered drainage system shared with the adjoining property or an appropriate watershed easement has been obtained. No surface water drainage from an off-street parking lot shall be permitted to drain across a public sidewalk.

(7) *Striping.* For parking lots containing five or more spaces, all spaces shall be outlined with three-inch wide strips of white or yellow paint, except that barrier-free spaces shall be blue, with a symbol of compliance in blue. An exception to this requirement are parking lots which are surfaced with gravel for historic preservation purposes in accordance with Article VIII, division 2, of this chapter.

(8) *Wheel stops.* For parking lots containing five or more spaces, wheel stops or curbing shall be provided for all parking spaces to prevent any vehicle from projecting beyond the parking lot area, bumping any wall or fence, or encroaching upon any landscaping. In all cases where parking lots abut public or private sidewalks, continuous concrete curbing or bumper stops, at least six inches high, shall be placed so that a motor vehicle cannot be driven or parked on, or hang over, any part of any sidewalk.

(9) *Lighting.* With the exception of facilities for one-and two-family dwellings and for multiple-family dwellings on individual lots containing no more than four units, parking and loading facilities utilized during night-time hours shall be artificially illuminated. All such outdoor lighting shall meet the requirements of section 122-641.

(12) *Maintenance.* All off-street parking areas, including striping, shall be maintained in good usable condition, and when necessary shall be treated to prevent dust or other nuisances. Such parking areas and drives shall also be kept free of litter, debris, and refuse.

(13) *Additional requirements.* In addition to the above requirements, parking areas shall comply with additional requirements or conditions which may be deemed as reasonably necessary by the Planning Commission for the protection of abutting lots.


Sec. 122-684. Parking screening and landscaping. (835) (714)

- (a) Intent. Separate landscape areas shall be provided within parking lots so as to break up the broad expanse of pavement, mitigate heat island effect, support storm water management, and guide the circulation of vehicular and pedestrian traffic.
- (b) Required landscaping within off-street parking areas. Separate landscape areas shall be provided within off-street parking areas in accordance with the following requirements:

- (1) There shall be a minimum of one (1) tree for every eight (8) parking spaces, provided that a landscape island shall be provided for no more than sixteen (16) continuous spaces.
- (2) Landscape islands must meet the following size requirements:
 - (i) Landscape islands containing a tree shall be a minimum of 160 square feet and a minimum of nine (9) feet wide.
 - (ii) Landscape islands containing a pedestrian pathway shall be a minimum of eleven (11) feet wide, with a pathway of a minimum width of five (5) feet and minimum three (3) feet wide landscape area on both sides.


(iii) If landscaped islands are not used for storm water infiltration, the islands must be raised and curbed.

- (3) The ends of all parking aisles and corners shall be protected with a curbed island.
 - (4) A minimum distance of three (3) feet from the backside of the curb and the proposed landscape plantings shall be provided. Where vehicles overhang a landscape island or strip, a minimum distance of five (5) feet from the backside of the curb and the proposed landscape plantings shall be provided.
 - (5) Shrubs and/or ground covers which will not impede vehicular visibility in accordance with this Ordinance may also be included.
- (c) Required Landscaping at the Perimeter of Off-Street Parking Areas, Loading Zones, and Access Drives. Separate landscape areas shall be provided at the perimeter of off-street parking areas in accordance with the following requirements. This landscaping cannot be counted toward any other landscaping requirement except for the “site landscaping” minimum percentage.
- (1) Off-street parking areas in the side and rear yard which abut a R-1, MD, CN, CN-Mid, CN-SF zoning district must be screened in accordance with [§122-634](#).
 - (2) All off-street parking areas that are visible from a public road shall be screened from view with a solid wall or landscape planting achieving at least 80% opacity year-round at least three (3) feet in height but no more than four (4) feet in height, in conformance with [§122-675](#).
 - (3) All land between a parking lot and any street right-of-way shall be kept free from refuse and debris and must be landscaped. The ground area shall be planted in lawn or other live ground covering. All such landscaping and plantings shall be maintained in a healthy, growing condition, neat and orderly in appearance.
- (d) Landscaped areas, walls, structures, and walks shall be properly protected from vehicular encroachment or overhang through appropriate wheel stops or curbs, as well as a distance of at least 3 feet.



Sec. 122-685. Parking dimensions. (834) (715)

- (a) All off-street parking facilities required by this chapter shall be of adequate size and design to provide safe and reasonably direct ingress and egress from an alley or street. All parking spaces shall be adequate for parking a motor vehicle with room for opening doors on both sides.
- (b) Parking spaces required by this article shall be at least 9 feet wide and 18 feet long (16 feet long if 2 feet of overhang is provided when parking against a curb). Spaces directly adjacent to a fence, wall or enclosure shall be increased by 1 foot in width. Barrier free parking spaces must be designed as required by and in conformity with state law.
- (c) Up to 20% of the parking spaces may be designated as small car spaces, which shall be at least 8 feet wide and 16 feet long and clearly signed for "compact cars."
- (d) Up to 10% of the parking spaces may be designated as motorcycle spaces, which shall be at least 5 feet wide and clearly signed for "motorcycles."
- (e) Minimum Standards. The minimum standards for parking spaces and aisles are indicated in the table below.



Standard Vehicle Parking Dimensions					
Parking Patterns (Degrees)	Space Width (Feet)	Space Length (Feet)	Maneuvering Lane Width (Feet)	Total Width of One Tier of Spaces Plus Maneuvering Lane (Feet)	Total Width of Two Tiers of Spaces Plus Maneuvering Lane (Feet)
0 (parallel)	9	22	12 if one-way 10 if two-way	21 one-way 19 two-way	30 one-way 28 two-way
30 to 53	9	18	13	36	53
54 to 74	9	18	16	38	59
75 to 90	9	18	22	40	62
Compact Vehicle Parking Dimensions					
Parking Patterns (Degrees)	Space Width (Feet)	Space Length (Feet)	Maneuvering Lane Width (Feet)	Total Width of One Tier of Spaces Plus Maneuvering Lane (Feet)	Total Width of Two Tiers of Spaces Plus Maneuvering Lane (Feet)
0 (parallel)	8	18	12	20 one-way 32 two-way	28 one-way 40 two-way
30 to 53	8	17	13	36	53
54 to 74	8	17' 5"	16	38	59
75 to 90	8	16	22	42	62
Motorcycle Vehicle Parking Dimensions					
All motorcycle parking spaces shall be a minimum of five feet by eight feet.					

Sec. 122-686. Barrier-free parking spaces. (839) (716)

Off-street parking facilities as required under this chapter shall include parking spaces which are reserved for physically handicapped persons in accordance with the state barrier free design requirement of the state building code.

Secs. 122-687 – 689. Reserved.

Division 8: Parking Types and Quantities

Sec. 122-690. Generally. (833 - portion) (720)

Any person, organization, or establishment who has any ownership interest in or the control of any real estate within the City is required to provide and maintain in a usable condition off-street parking spaces as follows:

- (a) **Repair prohibited.** No repairs or service to vehicles shall be permitted on areas designated as required off-street parking.
- (b) **Display of vehicles for sale.** The parking of motor vehicles, recreational vehicles, and trailers which are possessed expressly and solely for sale by persons or businesses licensed by the state for such sales are permitted only when in accordance with the requirements of each respective zoning district and the specific provisions of §122-538 regarding the outdoor sales of vehicles. Otherwise, the display of vehicles for sale in designated off-street parking areas is prohibited.
- (c) **Use of loading space.** Loading spaces, as required under §122-695, shall not be counted or used for required parking.
- (d) **Usable floor area and gross floor area.** For the purpose of computing the number of parking spaces required, the definitions for "usable floor area" and "gross floor area" in §122-203 shall apply.
- (e) **Fractional requirements.** When units or measurements determining number of required parking spaces result in requirement of a fractional space, any fraction up to one-half shall be disregarded and fractions including and over one-half shall require one parking space.
- (f) **Uses not specified.** For those uses not specifically mentioned under §122-691, the requirements for off-street parking facilities shall be in accord with a use which the City Planner considers similar in type.
- (g) **Nonoverlapping operating hours.** In the instance of land uses requiring off-street parking spaces where operating hours of the uses do not overlap, the City Planner may grant exception to the individual parking requirements of §122-691.
- (h) **Use of parking lots for storage.**
 - (1) Except as provided under subsection (h)2 of this section, a parking lot may not be used for the storage or parking of trailers, mobile homes, travel trailers, boats, boat trailers, or junked or wrecked vehicles of any type; for the storage of merchandise or industrial equipment or materials; or as a dump for refuse of any description.
 - (2) The parking out-of-doors of motor vehicles which are used as part of a permitted commercial or industrial use, including automobiles, trucks, or trailers, are permitted on off-street parking lots outside normal business hours of such commercial or industrial use; provided no more than a total of five automobiles and three commercial trucks or trailers each weighing less than 10,000 pounds shall be permitted. The outdoor storage of more than five automobiles and three trucks or trailers shall be permitted only after Special Use approval by the Planning Commission in accordance with the provisions of Article III, Division 2, Subdivision III of this chapter.

Sec. 122-691. Minimum and maximum number of parking spaces. (836) (721)

The minimum number of off-street parking spaces by type of use in all zoning district shall be determined in accordance with the following schedule. The maximum number of off-street parking spaces must not exceed 120% of the required parking spaces, except for those uses in the "Residential" category, which are not subject to a maximum. The Planning Commission may grant waivers as noted in [§122-692](#).

USE	AUTOMOBILE SPACES PER UNIT OF MEASURE
RESIDENTIAL	
Single-family detached dwellings and two-family dwellings	1 space per unit
Multiple-family dwellings, including townhouses	1.5 for each dwelling unit, plus 1 for each 10 dwelling units for guest parking.
Upper-story residential units in C, HC, NC, GC, and HHS districts	1 for each dwelling unit.
Group living with support staff, not licensed by State of Michigan	1 for each 3 beds, plus 1 per employee on an average employment shift.
Group residence & roominghouse	1 for each bedroom or sleeping room, plus 1 for each employee or the largest employment shift.
Adult Foster Care	1 for each 3 beds, plus 1 for each employee an average employment shift.
Accessory Dwelling Unit	1 for each dwelling unit
Family Child Care Home	Minimum of 1 and a maximum of 3 child-care drop off spaces.
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES	
Religious institutions; private assembly (such as catering or clubs); performance venues & theaters; libraries, museums, and cultural or community centers; or similar facilities	1 for each 500 square feet of usable floor area, excluding area devoted to storage.
Indoor recreation, including swimming pools	1 for each 3 persons who may be legally admitted at one time based on the occupancy load established by local, county, or state fire, building, or health codes, plus 1 for each employee on an average employment shift.
Primary and secondary schools, public and private	1 for each teacher, employee or administrator, plus 1 for each 10 students
Post-secondary educational institutions (public & private)	1 for each teacher, employee or administrator and 1 for each 5 students.
Municipal, county, regional & state service uses	1 for each 1,000 square feet of usable floor area.
Child care centers	1 off-street parking space per caregiver required to staff facility at the state-licensed capacity, plus 1 space for every 20 children the facility is licensed to care for.
Outdoor recreation and fields	1 for each 1,000 square feet of recreation space.
Stadiums, sports arenas, or similar places of outdoor assembly	1 for each 4 seats or 8 feet of linear bench space.
INFRASTRUCTURE	
Radio & Television Studios or Stations	1 per each 500 square feet of gross floor area.
Utility buildings	1 for each employee on an average employment shift.
Energy, electricity, heat generation, or sewage plants	1 for each employee on an average employment shift.
SERVICES	
Bed & Breakfasts or Inns	1 per occupancy unit plus 1 per employee on an average employment shift.
Motels, hotels or other commercial lodging establishments	1 per occupancy unit plus 1 per employee on an average employment shift; plus extra spaces for dining rooms, ballrooms, or meeting rooms as required.
Business and professional offices and services	1 per 300 square feet of usable floor area.

USE	AUTOMOBILE SPACES PER UNIT OF MEASURE
Funeral homes	1 per 50 square feet of assembly room, parlor and slumber room.
Laundromats	1 per 3 washing machines.
Financial service, including banks	1 per 300 square feet of usable floor area, plus stacking spaces for each drive-through transaction station as required under §122-694 .
Nursing Homes	1 per 3 beds.
Hospitals	1 for each 4 patient beds, plus 1 for every 200 square feet of out-patient service area
Medical or dental offices or clinics, substance abuse treatment facilities	1 for each 300 square feet of usable floor area in waiting rooms, plus 1 for each examining room, dental chair, or similar use area.
Personal service establishments	2 spaces for each of the first 2 beauty or barber chairs, and 1½ spaces for each additional chair, or 1 for each 300 square feet of useable floor area whichever is greater.
Self-storage facilities	1 per 200 storage units, plus 1 per 300 square feet of usable floor area of office space, plus 1 for residence, if provided.
Catering service	1 per 600 square feet of usable floor area.
All other service uses not elsewhere specified	1 for each 300 square feet of gross floor area.
COMMERCIAL	
Furniture and appliances, household equipment; repair shops; showrooms of a plumber, decorator, electrician or similar trade; and other similar uses	1 for each 600 square feet of usable floor area.
Open air businesses	1 for each 600 square feet of lot area used for open air business, plus extra spaces for indoor sales or office space as required.
Shopping centers or clustered commercial centers over 100,000 square feet in gross floor area	1 for each 300 square feet of gross floor area.
Arts & crafts studios	1 per 1,000 square feet plus 1 per classroom.
All other retail uses not elsewhere specified	1 for each 250 square feet of gross floor area.
RESTAURANTS	
Café, coffee shop, restaurants, tasting rooms or bar/lounge, and other establishments where food, beverages, or refreshments are sold primarily for consumption on the premises	1 for each 100 square feet of usable floor area, or 1 for each 3 persons allowed within the maximum occupancy load as established by local, county, or state fire, building or health codes; whichever is greater.
Restaurant, fast food, drive-in or drive-through	1 for each 50 square feet of customer waiting and eating areas, plus 1 for each employee in the largest employment shift, plus 8 stacking spaces for each drive-in or drive-through transaction station.
AUTO-ORIENTED	
Automobile filling stations	1 for each employee, plus spaces required for other uses within the station, such as the retail floor area, carryout restaurants, subtracted by one half space for each automobile fueling position.
Automobile repair	1 for each employee in the largest employment shift, plus 1 space for each auto service stall. In addition, stacking spaces for automobiles awaiting entrance to a service stall shall be provided as required under §122-694 .

USE	AUTOMOBILE SPACES PER UNIT OF MEASURE
Automobile wash (automatic and self-serve) and detailing	1 for each employee in the largest employment shift. In addition, stacking spaces for automobiles awaiting entrance to the wash facility must be provided as required under §122-694 .
Motor vehicle sales and service establishments, trailer sales and rental, and boat showrooms	1 for each 500 square feet of usable floor space of sales room, plus 1 for every 500 square feet of outdoor sales area, plus 1 for each 1 auto service stall in service areas, plus 1 space per employee on the largest employment shift.
Automobile rental (parking, storage, wash & repair)	
Vehicle, Recreational Vehicle, Storage and Towing	1 for 300 square feet of office space, plus 1 space per employee on the largest employment shift.
RESEARCH	
Laboratories or research establishments	5 plus 1 for every 1.5 employees in the largest working shift; or 1 space per each 1,000 square feet of gross floor area for storage areas, and 1 space per 300 square feet of office area; whichever is greater.
PRODUCTION, MANUFACTURING & DISTRIBUTION	
Craft production	1 per 1,000 square feet
Wholesale or distribution facility	5 plus 1 for every employee in the largest working shift; or 1 for every 1,700 square feet of gross floor area, plus 1 for each 300 square feet of office area. Spaces shall also be provided for any retail or service area in addition to the above.
Assembly, processing or manufacturing	5 plus 1 for every 1½ employees in the largest working shift; or 1 space per each 1,000 square feet of gross floor area for assembly, processing and manufacturing and storage areas, and 1 space per 300 square feet of office area.
URBAN AGRICULTURE	
Community garden	None
Hydroponics, aquaculture and aquaponics and similar raising of food	5 plus 1 for every employee in the largest working shift; or 1 for every 1,700 square feet of gross floor area, plus 1 for each 300 square feet of office area. Spaces shall also be provided for any retail or service area shall be in addition to the above.

Sec. 122-692. Parking Requirement Reductions. (837) (722)

Off-street parking requirements may be reduced subject to the following regulations.

- (a) **Transit.** Parking requirements may be reduced by up to 20 percent for buildings, structures, or uses within three hundred (300) feet of a commuter rail station or bus transit center or within one hundred (100) feet of a transit stop. In situations where this would result in a discount of more than 10 spaces, a traffic study may be required to demonstrate that a sufficient number of vehicle drivers would immediately opt for transit, and therefore would not result in adverse parking impacts on surrounding properties. The Ride shall verify that the transit station or transit stop is in a is not scheduled to move in the 5-year plan for the Ride.
- (b) **Car-sharing and carpooling spaces.** Parking spaces reserved, signed, and enforced for hourly car rental/car-sharing services may count as four (4) regular parking spaces. Parking spaces reserved, signed, and enforced for carpooling or vanpooling services may count as two (2) regular parking spaces.
- (c) **Electric car parking/charging spaces.** Electric car spaces shall include a power outlet for use by the parked car. Such spaces should be closest to the main entrance (exclusive of barrier-free spaces). Parking spaces reserved, signed, and enforced for electric car charging stations may count as two (2) regular parking spaces.
- (d) **Bicycle spaces.** Parking requirements may be reduced by one (1) space for every four (4) covered, secure bicycle parking spaces provided on site. Parking requirements may be further reduced by four (4) spaces where free showers are available for employee use within the building.
- (e) **Seasonal bicycle parking.** Up to 5% of vehicle parking spaces may be occupied by bike racks April through October in the Walkable Urban Districts.
- (f) **Planning Commission Authority.** The Planning Commission shall have the authority to waive the number of required off-street parking spaces, in addition to the reductions above, by up to 20%, with a finding that there is a special circumstance that particularly relates to the size of an existing parcel and building in combination, and/or character of the proposed use.

Sec. 122-693. Required Bicycle Parking. (838) (723)

Any development requiring vehicle parking spaces shall be required to provide bicycle parking. Off-street parking areas shall contain at least one (1) bicycle parking space for every five (5) spaces provided for motor vehicles, or fraction thereof, with a minimum of two (2) bicycle parking spaces provided. In the Center, Historic Corridor, and Neighborhood Corridor Districts, bicycle facilities provided in the public right-of-way may be used in parking calculations.

ADDED: in center, NC, and historic corridor stipulation 12/14/2016
--

Sec. 122-694. Off-street stacking spaces for drive-through facilities. (840) (724)

- (a) **Drive-in or drive-through windows.** On the same premises with every building, structure, or part thereof, erected or occupied for the purpose of serving customers in their automobiles by means of a service window or similar arrangement, such as drive-in banks, restaurants, or cleaning establishments, there shall be provided two off-street stacking spaces for each service window or transaction station in compliance with subsection (c) of this section. Six off-street stacking spaces shall be provided for each drive-through transaction station of a restaurant.
- (b) **Automobile servicing.** Self-service automobile and car wash establishments shall provide three off-street stacking spaces for each washing stall. Quick oil change facilities shall provide three off-street stacking spaces per each oil change service bay. Automobile and car wash establishments, other than self-service, shall provide stacking spaces equal in number to four times the maximum capacity of the motor vehicle wash for automobiles awaiting entrance. The term "maximum capacity" shall mean the greatest number of possible automobiles undergoing some phase of washing at the same time.
- (c) **Stacking space dimensions.** Each stacking space shall be a minimum dimension of ten feet in width and 20 feet in length.

Sec. 122-695. Off-street loading space requirements. (841) (725)

With the exception of uses located within the Center district, there shall be provided and maintained on the same premises with every building, structure, or part thereof involving the receipt or distribution of vehicles or materials or merchandise, including but not limited to retail stores, wholesale stores, markets, hotels, hospitals, offices, and laundries, adequate space for standing, loading, and unloading in order to avoid undue interference with public use of dedicated rights-of-way and vehicular circulation on the site.

- (a) Such off-street loading spaces shall be provided as specified in the table below. The Planning Commission may modify these requirements upon making the determination that another standard would be more appropriate because of the number or type of deliveries experienced by a particular business or use.

Off-Street Loading Space Requirements			
Use	Gross Floor Area (In Square Feet)	Size and Quantity	
		10' X 25' Space	10' X 50' Space
Office	0--99,999	--	--
	100,000--149,000	--	1
	150,000 and over	--	2
Commercial, Industrial. or Institutional	0-- 1,999	--	--
	2,000-- 4,999	1	--
	5,000--19,999	--	1
	20,000--49,999	--	2
	50,000--79,999	--	3
	80,000--99,999	--	4
	100,000--149,999	--	5
	150,000 and over	--	5, plus one additional space for each 50,000 square feet of floor area in excess of 150,000 square feet

- (b) All loading spaces shall be located within a nonrequired rear yard, or a nonrequired side yard which does not abut or lie across a street from a residential zoning district; but in no case shall loading spaces be permitted in a front yard. Loading spaces shall be subject to primary building setbacks.
- (c) No loading space shall be located closer than 50 feet to any R1, MD, CN-SF, CN-Mid, CN, or HHS district, unless located within a completely enclosed building or enclosed on all sides facing the district by a solid concrete or masonry wall not less than six feet in height.
- (d) Loading space areas shall be provided with a paved surface having an asphaltic or Portland cement binder so as to provide a permanent, durable and dustless surface. All loading spaces shall have a minimum 14-foot high clearance.
- (e) Loading areas shall not utilize any area required for the maneuvering of vehicles into parking spaces or block general vehicular circulation on a site.
- (f) A truck turning plan must be provided.

Sec. 122-696. Special assessment districts. (842) (726)

When a property is located within a special assessment district created for the purpose of constructing a municipal parking lot or structure, and an assessment has been levied against the entire building site, the owner of such property may petition the Planning Commission for approval of substituting such public parking for all or a portion of the required off-street parking spaces. The Planning Commission shall determine that the petitioner's property is adequately served by the public parking facility in such a way that the objectives and intent of this article shall be secured. To accomplish this end, the Planning Commission shall have the power to require such conditions as deemed appropriate. The Planning Commission shall consider the assessment of benefits in the special assessment district in determining the adequacy of service by the public facility.

Sec. 122-697. Fee in lieu of providing off-street parking. (843) (727)

- (a) Intent. The intent of the fee in lieu of providing off-street parking is to encourage the development of apartment units above ground floor commercial uses, in existing buildings, in the Center District. It is recognized that many structures in these business districts were constructed at zero lot lines, and often the structure covers the lot completely. Therefore, parking spaces on the lot or contiguous to the lot cannot be provided. For those building owners who cannot provide the amount of required parking pursuant to this chapter, and whose upper floor space has not been legally occupied within one year of their application for payment of such a fee in lieu

of parking, they shall be charged a fee according to the number of bedrooms in the residential units. Upon payment of this fee, the owner or applicant will be permitted to develop or rehabilitate these residential units without providing the parking required by this chapter. The fee will be held by the City for parking capital improvements, which will be used to provide increased parking and transportation infrastructure such as transit stops, bicycle facilities, and pedestrian pathways for the areas where these buildings are located.

- (b) Condition for allowing payment of fee in lieu of providing off-street parking. Property owners who meet all of the following requirements shall be entitled to apply for payment of fee in lieu of providing off-street parking:
 - (1) They are the owner, or have permission of the owner, of a building which can provide residential units above ground floor commercial uses.
 - (2) The building is located in the Center District within the City.
 - (3) The property, by virtue of its construction, cannot meet parking requirements in the district.
 - (4) The residential unit or units have not been legally occupied within one year prior to making application.
- (c) Application.
 - (1) An application for permission to use such payment in lieu of providing off-street parking shall be made as part of an application to the City Planner.
 - (2) The permit shall contain the following information:
 - (i) Name, address and phone number of property owner and name, address and phone number of applicant, if different than owner.
 - (ii) Address of property requiring fee in lieu of providing off-street parking.
 - (iii) Plan showing the layout of the proposed residential units, including size of rooms and identification of bedroom space.
 - (iv) Description of commercial use on ground floor level.
 - (v) A site plan which shall include:
 - (a) Dimensions and size of parcel.
 - (b) Location of structure on parcel.
 - (c) If any parking is available on the site, its location must be indicated, including access, stall size, etc.
 - (d) Description of location of parking to be used by tenants.
 - (3) Application fee. An application fee shall be paid at the time of submitting the application to the City Planner.
- (d) Approval procedures.
 - (1) The City Planner shall consider the following in making his/her determination:
 - (i) Whether the owner can provide on-site parking that meets ordinance standards.
 - (ii) Whether the owner can modify available parking space, or loading space, located on-site to meet ordinance standards.
 - (2) If the City Planner determines that the owner cannot provide on-site parking to meet ordinance standards, or can only provide partial on-site parking to meet ordinance standards, and the other requirements of this article are met, then he/she shall make a specific finding regarding the number of spaces which are required for the residential units, which shall allow the City Treasurer to compute the amount of fee in lieu of parking.
- (e) Condition. The off-street parking requirement satisfied by fee in lieu of parking shall run with the land. If any subsequent change in use should occur, which requires additional parking, then the owner shall make a new application to the City pursuant to this chapter for such additional parking. An additional application fee shall be paid when such application is submitted. An additional fee shall be due prior to the issuance of a building permit to allow the additional modifications.

Secs. 122-698 – 699. Reserved.

Article VII: Supplementary Regulations

Division 1: Planned Unit Development

Sec. 122-700. Description and purpose. (571) (750)

- (a) It is the purpose of this article to provide guidelines for development or redevelopment which is planned as a unit. Toward this end, it is the intent of these regulations to allow flexibility in the regulation of land development; encourage innovation in land use and variety in design, layout, and type of structures constructed; achieve economy and efficiency in the use of land, energy, public services, and utilities; encourage useful open space; provide better housing, employment, shopping opportunities, compatibility of design, and use between neighboring properties; facilitate the preservation and reuse of historic structures; and encourage development that is consistent with the City's master land use plan.
- (b) The approval of a planned unit development application requires an amendment to this chapter to revise the Zoning Map and designate the subject property as "PUD, planned unit development." An approval granted under this article, including all aspects of the final site development plan and conditions imposed on it, constitutes an inseparable part of this chapter.
- (c) The provisions of this article are not intended as a device for ignoring this chapter, the specific standards set forth in this chapter, or the planning upon which it has been based. Provisions of this article are intended to result in land development substantially consistent with the zoning standards generally applied to the proposed uses, allowing for modifications and departures from generally applicable standards in accordance with the guidelines of this article to insure appropriate, fair, and consistent decision-making.

Sec. 122-701. Permitted uses. (572) (751)

In a planned unit development, the principal uses which are permitted are based on the underlying zoning district. City Council may also consider, upon Planning Commission recommendation, the City of Ypsilanti Master Plan as a basis for principal uses permitted in a planned unit development.

Underlying Zoning District	Permitted Uses under Planned Unit Development
R1, CN-SF, P	Planned unit developments are not permitted in these districts, except as provided for under §122-703.
CN, CN-Mid, MD	Any combination of uses permitted in the CN, CN-Mid, and MD zoning districts. Limited commercial, service, and office uses may be permitted if in combination with and related to residential uses.
HHS, HC, NC, C	Any combination of uses permitted in the HHS, HC, NC, or C zoning districts.
GC	All uses permitted under GC, plus Unclassified Uses as defined in §122-431(c). ORIGINAL: (changed to have as much flexibility in use as the underlying district- as intended- plus additional, if thought appropriate.) All commercial, service, and office uses or any combination of such uses may be permitted. Limited light industrial uses may be permitted if in combination with such commercial or office uses.
PMD	All industrial and office uses and any combination of such uses. Limited commercial and service uses may be permitted if in combination with industrial uses. Residential uses are not permitted.

Sec. 122-702. Requirements for planned unit developments. (573) (752)

The following requirements must apply to all planned unit developments:

- (a) Unified control. The proposed development must be under single ownership or control such that there is a single person or entity having responsibility for completing the project in conformity with this chapter. The applicant must provide legal documentation of a single ownership or control in the form of agreements, contracts, covenants, and deed restrictions which indicate that the development can be completed as shown on the plans, and further, that all portions of the development that are not to be maintained or operated at public expense will continue to be operated and maintained by the developers or their successors.
- (b) Minimum size. The minimum size of a planned unit development in the Walkable Urban Districts is one half-

acre of contiguous land. The minimum size of a planned unit development in the Use Based Districts is one acre of contiguous land.

ORIGINAL: (makes process smoother: parcels in WUDs are smaller than UBDs and generally have historical impact/context- ex, Thompson Block. Saves devs a step.)
The minimum size of a planned unit development is one acre of contiguous land. The City Council may approve a planned unit development for a parcel as small as one-half acre if the proposal involves the preservation and/or adaptive reuse of a historically significant structure. The historical significance must be determined by the city historic district commission.

- (c) Applicable base regulations. Unless waived or modified in accordance with the procedures and standards set forth in this article, the yard, bulk, parking, loading, landscaping, lighting, general provisions, and all other standards set forth in this chapter for the uses listed below must be applicable for uses proposed as part of a planned unit development:
- (1) Multiple-family residential uses must comply with the regulations applicable in the MD multiple dwelling residential district.
 - (2) Commercial and office uses must comply with the regulations applicable in the C - Center district.
 - (3) Manufacturing uses must comply with the regulations applicable in the PMD - Production, Manufacturing, and Distribution district.
 - (4) Mixed uses must comply with the regulations applicable for each individual use, as outlined above, except that if conflicts exist between provisions, the regulations applicable to the most dominant use must apply.
 - (5) To encourage flexibility and creativity in development consistent with the planned development concept, departures from compliance with the base regulations may be granted by the City Council, upon recommendation of the Planning Commission, as a part of the approval of the planned development. For example, such departures may include modifications of lot dimensional standards, setback requirements, density standards, parking and landscaping requirements, and similar requirements. Such departures may be approved only on the condition that they will result in a higher quality of development than would be possible using conventional zoning standards.
- (d) Street access. Each lot, main building, and principal use within a planned development district must have vehicular access to a public street. Adequate provision must be made for dedications of land for streets and essential services.
- (e) Usable open space. The proposed development must contain at least as much open space as would otherwise be required by the existing underlying zoning.
- (f) Landscaping and maintenance of common areas. All required yards and common areas must be landscaped and adequately and permanently maintained by the property owner, tenant, or organization responsible for maintaining common areas. Through an irrevocable conveyance, such as deed restrictions or covenants that run with the land, the developer must assure that all yards and common areas will be developed in accordance to the site plan and not changed to another use.
- (g) Additional considerations. During review of a proposed planned development, the Planning Commission must take into account the following considerations which may be relevant to a particular project: perimeter setbacks and screening; thoroughfares, drainage, as provided for in best management practices as appropriate, and utility design; underground installation of utilities; insulating pedestrian circulation from vehicular thoroughfares and ways; achievement of an integrated development with respect to signage, lighting, landscaping and building materials; and noise reduction mechanisms, particularly in cases where nonresidential uses adjoin off-site residentially-zoned property.

Sec. 122-703. Planned adaptive reuse projects. (574) (753)

A planned unit development that involves adaptive reuse of an existing structure that is located in a residential zoning district, but that was originally constructed for non-residential use, may be reviewed as a planned adaptive reuse project at the request of the applicant. The following requirements must apply to a planned adaptive reuse project in addition to the requirements applied to all planned unit developments:

- (a) Eligibility. The project must involve the reuse of an existing structure that is located in a residential zoning district, that was constructed for non-residential use.
- (b) Minimum size. Notwithstanding §122-702(b), no minimum size is required for a planned adaptive reuse project.
- (c) Permitted uses. Notwithstanding §122-701, a planned adaptive reuse project may include any uses determined by the City Council, upon Planning Commission recommendation, to be appropriate for the site and compatible with adjacent uses and zoning districts, with the master plan, and with any subarea plans.

Sec. 122-704. Application requirements. (575) (754)

An application for a planned unit development must contain the following:

- (a) Cover letter signed by the applicant and owner holding an equitable interest in the property.

- (b) Legal description showing the location and acreage of the property.
- (c) General description of proposed development, including a timetable of development and a list of departures from the regulations of this chapter which will be required.
- (d) Site plan at a scale of one inch equals 50 feet or larger, prepared in accordance with [§122-309](#). Additional information on the site plan must include:
 - (1) A schedule of total land areas devoted to each type of use, useable floor areas, density calculations, number and types of units, and building ground coverage.
 - (2) Open space areas, indicating the proposed uses and improvements for such areas.
 - (3) Architectural sketches showing building heights, external wall finishes, location of building entry ways, lighting elements, and other architectural features.
 - (4) Copy of agreements, covenants, or deed restrictions which will assure that the development will be completed and maintained as shown on the plans by the developer and successive owners.
 - (5) Other information deemed pertinent to the proposed development by the Planning Commission or City Council.
- (e) A fee for the processing of the planned development application, as established by the City Council.

Sec. 122-705. Review procedures. (576) (755)

The review and approval process for planned unit developments must be as follows:

- (a) Preapplication conference.
 - (1) In order to facilitate review of a planned unit development proposal in a timely manner, the applicant may request an informal preapplication conference with City staff. The purpose of such a conference is to exchange information and provide guidance to the applicant that will assist in preparation of application materials.
 - (2) The applicant must present at such a conference, at a minimum, a concept plan of the proposed planned unit development (drawn to scale), a legal description of the property in question, the total land areas of the project, the approximate number of residential units to be constructed, the floor area of nonresidential uses, and areas to be designated as common areas or open space.
 - (3) No formal action must be taken at a preapplication conference. There must be no fee for a preapplication conference. Statements made at the preapplication conference must not be legally binding commitments.
- (b) Public hearing. After a formal application has been filed for a planned unit development, it must be reviewed by the City Planner and planning and development department for completeness and submitted to the Planning Commission. A public hearing on the proposed planned unit development must be scheduled. Notice of the public hearing must be published in a newspaper of general circulation in the City, and sent by mail or personal delivery to the owners of property for which approval is being considered, to all persons to whom real estate property is assessed within 300 feet of the boundary of the property in question, and to the occupants of all structures within 300 feet. Such notice must be given not less than 15 days before the public hearing scheduled. Such notification must contain the following information:
 - (1) Nature of the planned unit development project requested.
 - (2) Boundaries of the property which is the subject of the request.
 - (3) Date and time of the public hearing.
 - (4) Location and times that written comments will be received concerning the request.
- (c) Planning Commission recommendations. Within a reasonable time not to exceed 90 days following the public hearing, the Planning Commission must make its final consideration of the request, and must recommend to the City Council denial, approval, or approval with conditions, of the request. The Planning Commission must have prepared a report stating its conclusions, the basis for its recommendations, and any conditions relating to an affirmative recommendation.
- (d) City council action.
 - (1) The City Council must be provided with a copy of the Planning Commission's report, a summary of comments received at the public hearing, minutes of all proceedings, and all documents related to the planned unit development. Within a reasonable time, not to exceed 60 days, after the action of the Planning Commission, the City Council must deny, approve, or approve with conditions, the request.
 - (2) The City Council may require that a performance guarantee be deposited with the City to insure faithful completion of improvements, in accordance with [§122-317](#). Unapproved deviations or delays in construction may result in a loss of all or a portion of the performance guarantee.
 - (3) The City Council may also impose other conditions to ensure that a planned unit development is constructed in an orderly manner, consistent with the spirit and intent of this chapter; and that the planned unit approach is not used as a means of circumventing restrictions on the location or quantity of certain types of land uses.
- (e) Effect of approval.

- (1) Approval of a planned unit development proposal must constitute an amendment to this chapter. All improvements to and use of the site must be in conformity with the approved planned unit development site plan and any conditions imposed.
- (2) Within three business days of official approval of the application and site plan by the City Council, the City clerk must attest the planned unit development designation for the land in question on the Zoning Map.
- (3) Notice of the adoption of the planned unit development designation must be published in a newspaper of general circulation within the City within 15 days after approval in accordance with §122-361.
- (f) Recorded with register of deeds. The applicant must record with the county register of deeds within ten days of approval of the application the following: a legal description of the project site, the approved site plan and an affidavit declaring that all future improvements will be made in accordance with the approved planned unit development.

Sec. 122-706. Standards for approval. (577) (756)

In considering any application for a planned unit development, the Planning Commission and City Council must make their determinations based on the standards for site plan approval in §122-311 and the following standards:

- (a) Conformance with the planned development concept. The overall design and all uses proposed in connection with a planned unit development must be consistent with and promote the intent of this article, as well as with specific project design standards set forth in this chapter.
- (b) Recognizable benefits. The planned development will result in recognizable and substantial benefits to the ultimate users of the project and to the community in general where such benefits would otherwise be unfeasible or unlikely to be achieved.
- (c) Compatibility with adjacent uses. The proposed planned unit development must be designed with due regard to its relationship with development on surrounding properties and uses thereon, including building heights, setbacks, density, parking, circulation, landscaping, views, and other layout features. In particular, consideration must be given to the following:
 - (1) The bulk, placement, architecture, and types of materials used in construction of proposed structures.
 - (2) The location and screening of vehicular circulation and parking areas in relation to surrounding development.
 - (3) The location and screening of outdoor storage, outdoor activity or work areas, and mechanical equipment in relation to surrounding development.
 - (4) The hours of operation of the proposed uses.
 - (5) Landscaping, preservation of historic features, and other site amenities.
- (d) Impact of traffic. The planned development must be designed to minimize any adverse impact of traffic generated by the proposed development. Consideration must be given to the following:
 - (1) Estimated traffic to be generated by the proposed development.
 - (2) Access to major thoroughfares.
 - (3) Proximity and relation to intersections.
 - (4) Adequacy of driver sight distances.
 - (5) Location of and access to off-street parking.
 - (6) Required vehicular turning movements.
 - (7) Provisions for pedestrian traffic.
 - (8) Access to loading and unloading areas.
- (e) Public services. The proposed type and density of use must not result in a material increase in the need for public services, facilities, and utilities; including but not necessarily limited to water and sewer services, public roads, fire and police protection, and schools. The proposal must not place an undue burden upon the subject or surrounding land or property owners and occupants or the natural environment.
- (f) Compatibility with master plan and this chapter. The proposed development must be compatible with the adopted City master plan and with the spirit and intent of this chapter.
- (g) Economic impact. The proposed development must not result in an unreasonable negative economic impact upon surrounding properties.
- (h) Compliance with applicable regulations. The proposed development must be in compliance with all applicable federal, state, county, and local laws and regulations.
- (i) Phasing. Where a project is proposed for construction in phases, the project must be so designed that each phase, when completed, must be capable of standing on its own in terms of the presence of services, facilities, and open space; and must contain the necessary components to ensure protection of natural resources and the health, safety, and welfare of the users of the planned unit development and the occupants of the surrounding area.

Sec. 122-707. Expiration of approval. (578) (757)

- (a) Approval of the planned unit development must expire and be of no effect unless construction must have commenced within one year of the date of the approval. An extension for a specified period may be granted by the City Council upon good cause shown, if such request is made to the City Council prior to the expiration period.
- (b) In the event an approved planned unit development has expired, the City Council may rezone the property in any reasonable manner following Planning Commission recommendation and a public hearing in accordance with **Article III, Division 4** of this chapter. If, at the discretion of the City Council, the property remains classified as a planned unit development, a new application is required and will be reviewed in light of the prevailing conditions, applicable laws, and ordinance provisions.

Sec. 122-708. Revision of approved plans. (579) (758)

- (a) General revisions. Approved final plans for a planned unit development may be revised in accordance with the procedures set forth in **§122-705**. Major revisions would include, but must not be limited to, increases in scope or density of use, land area, or building size; the addition of uses not authorized by the original planned unit development approval; the rearrangement of lots or building tracts; changes in the character or function of drives; or changes in the concept of the development.
- (b) Minor changes. Notwithstanding subsection (a) of this section, minor changes may be permitted by the Planning Commission following normal site plan review procedures outlined in **Article III** of this chapter, subject to its finding of the following:
 - (1) Such changes will not adversely affect the initial basis for granting approval; and
 - (2) Such minor changes will comply with all applicable requirements of this chapter and other local, state, and federal laws; and will not adversely affect the overall planned unit development in light of the intent and purpose of such development as set forth in this article.

Sec. 122-709. Appeals and variances. (580) (759)

The Zoning Board of Appeals is without jurisdiction to accept appeals or grant variances with respect to an approved planned unit development.

Division 2: Site Condominium Subdivisions

Sec. 122-710. Purpose and scope. (601) (760)

Site condominium subdivisions are developments utilizing the technique of land division on the basis of condominium ownership. As such, site condominium subdivisions are not subject to the provisions of the land division act, Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101 et seq.), MSA 26.430(101) et seq.), as amended. This section requires the submittal and review of site condominium subdivision plans under this chapter to ensure that such developments are accomplished with the same results as if the improvements were being proposed pursuant to the land division act, including, without limitation, conformance with all requirements of the applicable regulations contained in this chapter. Site condominium subdivision projects may be approved in any zoning district as a special use under the provisions of [Article III, Division 2, Subdivision II](#) of this chapter, or where divergence from the use, height, area, and placement regulations of this chapter is desired, the provisions of [Article VII, Division 1](#) of this chapter.

Sec. 122-711. Zoning compliance. (603) (761)

All site condominium subdivisions and structures therein must comply with all the use, size, height, area, setback, sign, and all other regulations of the zoning district in which the subdivision is located unless modified through the provisions of [Article VII, Division 1](#) of this chapter regarding planned unit developments.

Sec. 122-712. Review and approval procedures. (604) (762)

Application for review and approval of site condominium subdivision projects shall be made pursuant to the provisions of [Article III, Division 2, Subdivision II](#) or [Article VI, Division 1](#) of this chapter.

Sec. 122-713. Effect of approval. (605) (763)

Approval of a site condominium subdivision project serves as authorization to proceed with the division of the land on the basis of condominium ownership and the construction of required improvements to the land. However, unless specifically addressed and authorized, site condominium subdivision approval does not serve as the authorization of land uses on individual lots within the subdivision. All uses are subject to the provisions of this chapter otherwise applicable to the specific zoning district and use in question.

Sec. 122-714. Site plans. (606) (764)

The site plan submitted for a site condominium subdivision must be consistent with the requirements outlined in [§122-309](#) showing the location, size, shape, area, and width of all lots, all general and limited common elements, and street and utility layout. In addition, the following must be included as part of the application for special land use approval:

- (a) The use and occupancy restrictions as will be contained in the master deed.
- (b) A "consent to submission of real property to condominium project," listing all parties which have ownership interest in the proposed site condominium subdivision, or evidence of authority or right that the developer has a legal option to purchase the subject property from the owner of record.

Sec. 122-715. Layout, design and required improvements. (607) (765)

Site condominium subdivision plans must conform to the design, layout, and improvement standards as may be promulgated by the City Council by ordinance. Any such standards and regulations are hereby incorporated by reference in this article.

- (a) Streets. If a site condominium subdivision is proposed to have public streets, the streets must be paved and developed to the minimum design, construction, inspection, approval, and maintenance requirements for public streets as adopted by the City.
- (b) Utilities. Extension and provision of utilities must be provided as may be required by the City as conditions of approval.
- (c) Drainage. Procedures and design criteria for drainage must be as provided in the rules of the county drain commissioner, pursuant to section 105(c) of Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101(c), MSA 26.430(101), (c)), as amended.

Sec. 122-716. Master deed contents. (608) (766)

All provisions of the site condominium plans which are approved by the City pursuant to this article must be incorporated, as approved, in the master deed for the site condominium subdivision. Any proposed changes to the

approved site condominium plans must be received and approved by the City pursuant to the procedure set forth in §122-712 for the approval of site condominium plans. A copy of the master deed as filed with the county register of deeds for recording must be provided to the City Clerk within ten days after such filing with the County.

Secs. 122-717 – 719. Reserved.

Division 3: Flood Damage Prevention

Sec. 122-720. Flood hazard findings. (911) (770)

The flood hazard areas of the City are subject to periodic inundation which may result in safety hazards, loss of life, property and health, disruption of commerce and governmental services, extraordinary public expenditures for flood protection and relief, and impairment of the tax base, all of which adversely affect the public health, safety and welfare. The flood losses are caused by the cumulative effects of obstructions in floodplains causing increased flood heights and velocities, and by the occupancy in flood hazard areas by uses vulnerable to floods or hazardous to other lands which are inadequately elevated, floodproofed or otherwise protected from flood damages.

Sec. 122-721. Purpose. (912) (771)

It is the purpose of this article to protect the general public and all land within the City subject to flood losses by provisions designed to do the following:

- (a) Restrict or prohibit uses which are dangerous to health, safety and property in times of flood or which cause excessive increases in flood flow heights or velocities.
- (b) Require that uses vulnerable to floods, including facilities which serve such uses, be protected against flood damage at the time of initial construction.
- (c) Control the alteration of natural floodplains, stream channels and natural protective barriers which are involved in the accommodation of floodwaters.
- (d) Control filling, grading, dredging and other development which may increase erosion or flood damage.
- (e) Prevent or regulate the construction of flood barriers which will unnaturally divert floodwaters or which may increase flood hazards to other lands.

Sec. 122-722. Scope. (913) (772)

This article shall apply to all flood hazard areas. The boundaries of the flood hazard areas shall coincide with the boundaries of the areas indicated as within the limits of the 100 year flood in the report entitled Flood Insurance Study, Washtenaw County (All Jurisdictions) Community Number 260216, dated April 3, 2012, with accompanying Flood Insurance Rate maps and Flood Boundary and Floodway maps. Within the flood hazard area zone, a regulatory floodway shall be designated. The boundaries of the regulatory floodway shall coincide with the floodway boundaries indicated on the flood boundary and floodway maps. The study and accompanying maps are adopted by reference, appended, and declared to be a part of this chapter. The term flood hazard area, as used in this chapter, shall mean flood hazard area zone and the term floodway, shall mean the designated regulatory floodway.

- (a) AGENCY DESIGNATED. Pursuant to the provisions of the state construction code, in accordance with Section 8b(6) of Act 230, of the Public Acts of 1972, as amended, the Building Official of the City of Ypsilanti is hereby designated as the enforcing agency to discharge the responsibility of the City of Ypsilanti under Act 230, of the Public Acts of 1972, as amended, State of Michigan. The City of Ypsilanti assumes responsibility for the administration and enforcement of said Act throughout the corporate limits of the community adopting this ordinance.
- (b) CODE APPENDIX ENFORCED. Pursuant to the provisions of the state construction code, in accordance with Section 8b(6) of Act 230, of the Public Acts of 1972, as amended, Appendix G of the Michigan Building Code shall be enforced by the enforcing agency within the City of Ypsilanti.
- (c) DESIGNATION OF REGULATED FLOOD PRONE HAZARD AREAS. The Federal Emergency Management Agency (FEMA) Flood Insurance Study (FIS) Entitled Washtenaw County, Michigan (All Jurisdictions) and dated April 3, 2012 and the Flood Insurance Rate Map(s) (FIRMS) panel number(s) of 26161C; 00269E, 0288E, 0407E, and 0426E dated April 3, 2012 are adopted by reference for the purposes of administration of the Michigan Construction Code, and declared to be a part of Section 1612.3 of the Michigan Building Code, and to provide the content of the "Flood Hazards" section of Table R301.2(1) of the Michigan Residential Code.

Sec. 122-723. Regulation of uses in floodplain areas. (914) (773)

Any proposed occupation, structure, excavation, fill, extraction, grading or scraping and any substantial improvement to an occupation, structure or area shall be reviewed and approved by the Planning Commission.

"Substantial improvement" means any repair, reconstruction or improvement of an occupation, structure or area, the cost of which equals or exceeds 50 percent of the market value of the structure either, (i) before the improvement or repair is started or (ii) if the occupation, structure or area has been damaged and is being restored, before the damage occurred. For the purpose of this definition, "substantial improvement" is considered to occur when the first alteration of any wall, ceiling, floor or other structural member commences, whether or not that alteration affects the

external dimensions of the structure or area. The term does not, however, include either (i) any project for improvement of a structure to comply with state or local health, sanitary or safety code specifications which are solely necessary to assure safe living conditions, or (ii) any alteration of a structure listed on the National Register of Historic Places or state register of historic places.

(a) Permitted uses. The following uses may be permitted in those portions of the floodplain which are not a floodway, to the extent that they are allowed uses within a given zoning district and subject to the construction standards of building code in effect for the City at the time of construction:

- (1) Residential and nonresidential structures provided that the building official certifies to the Planning Commission that the proposed provisions for flood resistant construction, flood proofing or elevation meet or exceed the standards set forth in the City's building code.
- (2) Recreational uses such as parks, swimming areas, picnic grounds, ball fields, hiking or biking trails, and wildlife and nature preserves.
- (3) Residential support uses such as lawns, gardens, play areas, and parking areas which do not result in the filling in of floodplain areas.
- (4) Industrial and commercial support uses which are open in nature such as loading areas or parking areas which do not result in the filling in of any floodplain areas.
- (5) Utility facilities such as power plants, transmission lines, pipelines not crossing a lake or waterway, lighting facilities, and navigational and drainage aids.
- (6) Piers, boat ramps, bridges, and other such water related uses subject to approval by the water resources commission of the state department of natural resources.
- (7) Fencing of any type, provided that such fencing shall not be located in that portion of the floodplain that is a floodway or other areas essential to the conveyance of floodwaters.
- (8) Sidewalks, driveways, patios, and similar structures when constructed at grade.
- (9) Fill or removal of topsoil, sand, and gravel or other extraction operations, in that portion of a floodplain which is not a floodway provided the following conditions are met:
 - (i) Proof that proper long term maintenance will be provided so that the flood-carrying capacity is not diminished.
 - (ii) Any fill or excavated area shall be protected from erosion during and after operations by rip-rap, vegetative cover, bulk-heading, or other approved means.
 - (iii) The proposed filling in of land, provided that material equal to 110 percent of the fill volume is removed elsewhere from such premises and adjusted to be capable of storing floodwaters. Structures and parking areas may be permitted on such filled land provided the elevation of the filled land is at least one foot above the base flood elevation. A permit issued by the state department of natural resources under the state's floodplain regulatory authority, Act No. 451 of the Public Acts of Michigan of 1994 (MCL 324.3101 et seq., MSA 13A.3101 et seq.), shall be obtained prior to the filling of land in the floodplain. A copy of the state department of natural resources permit shall be provided to the City building inspection division prior to the issuance of a building permit.
- (10) Streets, railroads, and other rights-of-way.
- (11) Pavilions, open amphitheaters, detached garages, raised patios and decks, and other accessory structures provided they are properly anchored and made flood resistant and are not located in a floodway or other area essential to the conveyance of floodwaters.
- (12) Facilities for the storage and detention/retention of stormwater.
- (13) Storage yards for heavy equipment, materials, or machinery.

(b) Prohibited uses. The following uses are not allowed in a floodplain area under any circumstances:

- (1) New residential construction or occupation, including mobile homes, manufactured homes or pre-manufactured homes, are specifically prohibited in that portion of the floodplain that is a floodway. Other types of construction and occupation may be allowed in that portion of the floodplain that is a floodway; however, a hydraulic analysis shall be required which demonstrates that occupation and resulting obstruction of the floodway will not restrict the flood carrying capacity of the watercourse.
- (2) A landfill, dump, junkyard, recycling center or hazardous waste storage or treatment facility are expressly prohibited in a floodplain area.
- (3) The storage or processing of materials which in time of flooding become buoyant, flammable, explosive or otherwise injurious to public health, is expressly prohibited within a floodplain area.
- (4) On-site sewage disposal systems shall be permitted within a floodplain area.
- (5) Any encroachment which would cause any increase in the base flood level.

Sec. 122-724. Review procedures. (915) (774)

(a) Site plan review. All development, construction, occupation or substantial improvement proposals located within a floodplain area shall be reviewed by the City Planner or Planning Commission in accordance with the

site plan review procedures of [Article III](#) of this chapter, and the "Rules of the Washtenaw County Water Resources Commissioner." The City Planner or Planning Commission, when reviewing an application for occupation, construction or substantial improvement in a floodplain, shall consider the following standards before rendering a decision:

- (1) Any possible danger to life and property as a result of increased flood heights or velocities caused by encroachments on the floodplain.
 - (2) The danger that materials may be swept to other lands or downstream to the injury or property loss of others.
 - (3) The susceptibility of the proposed development and its contents to flood damage.
 - (4) The importance of the services provided by the development to the community.
 - (5) The requirement of the proposed development for a waterfront location and the availability of alternate locations not subject to flooding.
 - (6) The compatibility of the proposed use with existing and anticipated development of the surrounding area and the floodplain management program of the area.
 - (7) The safety of access to the property in times of flood for ordinary and emergency vehicles.
 - (8) The measures taken to assure adequate drainage so as to reduce exposure to flood hazards.
 - (9) The Planning Commission may attach certain conditions to an approval such as limitations on period of use and operation; imposition of operational controls, deed restrictions, performance bonds, and covenants; or requirements for construction of dikes, levees, and other protection measures.
- (b) Building official's responsibility. Prior to site plans being submitted to the Planning Commission the building official shall:
- (1) Certify that the proposed construction, occupation or substantial improvement complies with the City building code adopted in [Chapter 18](#).
 - (2) Where permits are required by other state or federal agencies, a copy of the approved permit shall be provided, by the applicant, prior to review by the Planning Commission.
 - (3) Cause to be verified and recorded on the site plan and building plans, the actual elevation (in relation to mean sea level) of the lowest floor (including basement) of all new or substantially improved structures.
 - (4) Cause to be verified and recorded on the site plan and building plan, the actual elevation (in relation to mean sea level) to which the new or substantially improved structures have or will be floodproofed.
 - (5) Require that all site plans and building plans for occupation, construction or substantial improvement within the floodplain have been prepared under the supervision of a registered professional engineer or architect. All site plans and building plans shall be signed by the registered professional engineer or architect.
 - (6) Certify that notification has been made to adjacent communities and the state flood control coordinator of a proposed development, construction, occupation, substantial improvement alteration or relocation of a watercourse, and submit evidence of such notification to the Federal Insurance Administration and the Planning Commission.
 - (7) Be available at the meeting of the Planning Commission when such plans are reviewed to answer any questions relative to the floodplain or construction standards.

Sec. 122-725. Building permit requirements. (916) (775)

No occupation, building or structure within a floodplain area shall be erected, moved, repaired, altered, or razed until a building permit shall have been obtained from the building official in accordance with the customary building permit requirements under [Chapter 18](#). For structures located within a floodplain, the following additional information shall be included with the building permit, and shall become a condition of the permit. All plans, specifications and conditions approved by the Planning Commission. The plans shall include all of the information required by [§122-724](#).

Sec. 122-726. Appeals, variances. (917) (776)

The Zoning Board of Appeals shall hear and decide appeals and requests for variances from the requirements of this article, in accordance with the procedures and conditions set forth in this article. Prior to hearing of the appeal, the City Planner shall certify to the Zoning Board of Appeals that notices as required under this article have been made. Further, the City Planner shall certify to the Zoning Board of Appeals that the immediate downstream community's chief elected official and the state flood control coordinator have been notified of the request for appeals or variance and of the public hearing. Appeals or variances relating to the construction standards as set forth in the building code, shall be heard by the construction board of appeals as outlined in [Chapter 18](#). In addition, the following conditions shall be applied to variances granted from the floodplain regulations of this article:

- (a) Variances shall be issued upon a determination that the granting of a variance will not result in increased flood heights, additional threats to public safety, extraordinary public expense, public nuisances, or cause fraud on or victimization of the public.

- (b) Any applicant to whom a variance is granted shall be given a written notice specifying the difference between the base flood elevation and the elevation at which a structure is being built, and a statement that the cost of flood insurance will be commensurate with the increased risk resulting from the reduced lowest floor elevation.
- (c) All such variances to this article shall be maintained in a record and reported to the Federal Insurance Administration and the state flood control coordinator upon request.

Sec. 122-727. Disclaimer of liability. (918) (777)

The degree of flood protection required by this article is considered the minimum necessary and reasonable for regulatory purposes. Larger floods may occur at any time, and excessive floodwater heights may be experienced due to manmade and natural causes. This article does not imply that areas outside the special flood hazard areas, or uses permitted within such areas, shall remain free from flooding or flood damages. This article shall not create a liability on the part of the City or any officer or employee thereof for any flood damage that results from compliance with or reliance upon this article or any administrative decision lawfully made thereunder.

Secs. 122-728 – 999. Reserved.



Zoning Ordinance
Chapter 122

10

City of Ypsilanti, Michigan

20

BUGFIX AND STRUCTURE REVISION DRAFT UN-ANNOTATED VERSION

Table of Contents

	Article I: Purpose And How To Use.....	4
	Article II: Definitions and Language.....	7
30	Article III: Development Procedures and Administration	37
	Division 1: Generally.....	37
	Division 2: Permits.....	39
	Subdivision I: Zoning Compliance.....	39
	Subdivision II: Special Land Uses.....	49
	Subdivision III: Temporary Use Permits.....	53
	Subdivision IV: Building Permits.....	55
	Division 3: Nonconformities.....	57
	Division 4: Amendments.....	63
	Division 5: Variances and Appeals.....	69
40	Division 6: Violations and Penalties.....	71
	Division 7: Authorities.....	73
	Subdivision I: Planning Commission.....	75
	Subdivision II: Zoning Board of Appeals.....	77
	Article IV: Districts.....	81
	Division 1: Generally.....	81
	Division 2: Use Based Districts.....	83
	Subdivision I: Park District (P).....	85
	Subdivision II: Single-Family Residential District (R1).....	89
	Subdivision III: Multiple Dwelling Residential District (MD).....	95
50	Subdivision IV: Production, Manufacturing And Distribution District (PMD).....	103
	Division 3: Walkable Urban Districts.....	113
	Subdivision I: Core Neighborhoods (CN-Sf, CN-Mid, CN).....	115
	Subdivision II: Center (C).....	121
	Subdivision III: Corridors (HC, NC, GC).....	127
	Subdivision IV: Health And Human Services (HHS).....	135
	Subdivision V: Building Types.....	141
	Article V: Use Regulations.....	163
	Division 1: Specific Standards For Certain Uses.....	165
	Division 2: Storage of Vehicles.....	179
60	Division 3: Communication Devices.....	181
	Article VI: Site Regulations	186
	Division 1: Generally.....	186
	Division 2: Yard, Area, and Lot Requirements	191
	Division 3: Landscaping and Screening	193
	Division 4: Accessory Structures, Porches, and Decks	197
	Division 5: Signs	199
	Division 6: Traffic	203
	Division 7: Off-Street Parking and Loading Requirements.....	207
	Division 8: Parking Types and Quantities	213
70	Article VII: Supplementary Regulations	221
	Division 1: Planned Unit Development.....	221
	Division 2: Site Condominium Subdivisions.....	227
	Division 3: Flood Damage Prevention.....	229

Article I: Purpose And How To Use

Sec. 122-100. Purpose.

This Zoning Ordinance is based on the provisions, goals, and values as adopted in the City of Ypsilanti Master Plan, amendments to those plans, and similar adopted plans addressing future development patterns and goals. This Ordinance is intended to implement the Master Plan by regulating the use of land, buildings, and structures to promote the public health, safety, and welfare. In the interpretation and application of this chapter, the provisions of this chapter shall be held to be minimum requirements for the promotion of the public health, safety, and welfare.

The provisions of this chapter are intended to:

- create a safe, diverse, and sustainable city;
- meet the needs of the City's residents for food, fiber, energy, and other natural resources;
- guide the location of places of residence, recreation, industry, trade, service, and other uses of land;
- ensure that uses of the land shall be situated in appropriate locations and relationships;
- limit the inappropriate overcrowding of land and congestion of population and transportation systems and other public facilities;
- facilitate adequate and efficient provision for transportation systems, sewage disposal, water, energy, education, recreation, and other public service and facility needs;

and for those purposes, divide the City into districts and within those districts designate the uses for which buildings or structures may be erected or altered; provide regulations for land uses, activities, or special uses which may be permitted subject to approval and regulation; establish the height and bulk of buildings, the area of yards and other open spaces; restrict the maximum number of families which may be housed in dwellings; and impose regulations for land prone to flooding.

This Ordinance is further intended to enable, encourage, and qualify the implementation of the following policies regarding:

(a) The Districts

- (1) That neighborhoods should provide meaningful choices in living arrangements as manifested by distinct physical environments.
- (2) That the District descriptions in **Article IV** shall constitute the intent of this Code with regard to the general character of each of these environments.

(b) The block and the building

- (1) That buildings and landscaping should contribute to the physical definition of streets as civic places.
- (2) That development should create complete streets that adequately accommodate vehicles and bicycles while respecting the pedestrian and the spatial form of public areas.
- (3) That the design of streets and buildings should reinforce safe environments, but not at the expense of accessibility.
- (4) That architecture and landscape design should grow from local climate, topography, history, and building practice.
- (5) That buildings should provide the community with a clear sense of geography and climate through energy efficient methods.
- (6) That Institutional Buildings and public gathering places should be distinctive in appearance, conveying their role in community identity.
- (7) That Institutional Buildings should be distinctive and appropriate to a role more important than the other buildings that constitute the fabric of the City.
- (8) That the preservation and renewal of historic buildings should be facilitated, to affirm the continuity and evolution of society.
- (9) That the harmonious and orderly evolution of urban areas should be secured through codes that regulate both building type and land use.

Sec. 122-101. Steps for Use of Regulations.

The table below illustrates the key steps an applicant would generally follow for development projects in the City. This is illustrative only and is not intended to set forth the administration and procedures, which are set in [Article III](#).

Instructions	Section	Title
Find the district for your parcel.	Zoning Map	Zoning Map
Confirm the proposed use(s) is allowed in this zoning district.	Article IV	Districts
Determine if your site is within the Historic District.	Chapter 55	Historic District
	See also the Historic District Map	
Determine if your site is within the floodplain or the floodway.	Article VII, Division 3	Flood Damage Prevention
	See also the adopted Flood Insurance Rate Map	
Determine the dimensional requirements for your building: • If your parcel is in GC, NC, HC, C, HHS, CN, CN-Mid, or CN-SF districts, using lot size, determine what "Building Type" your parcel is to determine design regulations; • If in another district, refer to the Non-Use and Dimensional Regulations table in each district section.	Article IV	Districts
Review the site design standards unique to the proposed use, as applicable.	Article V	Use Regulations
Review the site design standards general to all districts	Article VI	Site Regulations
Apply for zoning compliance	Article III, Division 2	Permits

Article II: Definitions and Language

Sec. 122-200. Interpretation of language.

For the purpose of this chapter, the following rules of interpretation shall apply to the text of this chapter:

- (a) The particular shall control the general.
- (b) In the case of any difference of meaning or implication between the text of this chapter and any caption or illustration, the text shall control.
- (c) The word "shall" is always mandatory and not discretionary. The word "may" is permissive and discretionary.
- (d) Words used in the present tense shall include the future. Words used in the singular number shall include the plural, and the plural the singular, unless the context clearly indicates the contrary.
- 140 (e) A "building" or "structure" includes any part thereof.
- (f) The phrase "used for" includes "arranged for," "designed for," "intended for," "maintained for," or "occupied for."
- (g) The word "person" includes an individual, a corporation, a partnership, a public utility, firm, an incorporated association, or any other similar entity.
- (h) Unless the context clearly indicates the contrary, or a regulation involves two or more items, conditions, provisions, or events connected by the conjunction "and," "or," "either . . . or," the conjunction shall be interpreted as follows:
 - (1) "And" indicates that all the connected items, conditions, provisions, or events shall apply.
 - 150 (2) "Or" indicates that the connected items, conditions, or provisions, or events may apply singly or in any combination.
 - (3) "Either . . . or" indicates that the connected items, conditions, or provisions, or events may apply singly or in any combination.
- (i) Terms not defined in this chapter shall have the meaning customarily assigned to them.

Sec. 122-201. Interpretation and conflict.

- (a) In interpreting and applying the provisions of this chapter, such provisions shall be held to be the minimum requirements adopted for the promotion of the public health, morals, safety, comfort, convenience, prosperity, and general welfare.
- (b) It is not intended by this chapter to repeal, abrogate, annul or in any way to impair or interfere with any existing provision of any law or ordinance other than the above described zoning ordinance, or with any rules, regulations, or permits previously adopted or issued or which shall be adopted or issued pursuant to the law relating to the use of the buildings or premises; provided, however, that where this chapter imposes a greater restriction than is required by an existing ordinance or by rules, regulations or permits, the provisions of this chapter shall control.
- 160

Sec. 122-202. Rule of construction. (5)

The rule that a penalty statute is to be strictly construed shall not apply to this chapter or any of the provisions thereof. All provisions of this chapter shall be construed according to the fair import of their terms, to promote justice, and to effect the objectives of this chapter.

Sec. 122-203. Definitions.

The following words, terms and phrases when used in this chapter shall have the meanings ascribed to them in this section, except where the context clearly indicates a different meaning:

A

Abandon means, in relation to nonconformities, to refer to uses, businesses, or establishments which have ceased to operate or exist; or to buildings, structures, or properties which have ceased to be occupied or used or for which no owner can be found, for a period of 365 consecutive days where there is an intent demonstrated by the property owner to abandon the nonconforming use by action consistent with §122-348(a)(5) or §122-349(e).

Accessory use, building or structure means a use, building, or structure which is clearly incidental to, customarily found in connection with, subordinate to, and is located on the same zoning lot as the principal use or structure to which it is exclusively related.

Adjacent. See "Lot, adjacent."

Administrative officer means an employee of the City who is charged with administering a department or major function of the City, such as City Manager, City Clerk, City Treasurer, City Assessor, Police Chief, Fire Chief, City Planner, Community and Economic Development Director, or Building Inspection Supervisor.

Adult drop-in center means a facility offering counseling, recreation, supervision, education or a place to pass the day to physically, mentally, or emotionally impaired adult individuals who may stop at any time and stay an unspecified period of time during its business hours.

Adult foster care facility. A governmental or nongovernmental establishment having as its principal function the receiving of adults, 18 years of age or older, for foster care in accordance with Act No. 218 of the Public Acts of Michigan of 1979, and the adult foster care administrative rules as administered by the state department of social services. It includes facilities and foster care family homes for adults who are aged, emotionally disturbed, developmentally disabled, or physically handicapped who require continuous supervision on an ongoing basis but who do not require continuous nursing care. The following four types of adult foster care homes are provided for by these rules:

- (1) **Adult foster care family home.** A private residence with the approved capacity to receive not more than six adults who shall be provided foster care for five or more days a week and for two or more consecutive weeks. The adult foster care family home licensee shall be a member of the household and an occupant of the residence.
- (2) **Adult foster care small group home.** An adult foster care facility with the approved capacity of not more than 12 adults who shall be provided foster care. Conformance to local zoning is required only if seven or more residents will live in the home.
- (3) **Adult foster care large group home.** An adult foster care facility with the approved capacity to receive at least 13 but not more than 20 adults who shall be provided foster care. Conformance to local zoning is required.
- (4) **Adult foster care congregate facility.** An adult foster care facility with the approved capacity to receive more than 20 adults who shall be provided foster care. Conformance to local zoning is required.

Adult regulated uses. The following are classified as types of adult regulated uses.

- (1) **Adult book or supply store** means an establishment having 20 percent or more of its stock in trade or its sales devoted to the distribution, display, or storage of books, magazines, and other periodicals and/or photographs, drawings, slides, films, video tapes, recording tapes, and/or novelty items which are distinguished or characterized by their emphasis on matters depicting, describing, or relating to specified sexual activities or specified anatomical areas. Such establishment or the segment or section devoted to the sale or display of such material in an establishment is customarily not open to the public generally but only to one or more classes of the public, excluding any minor by reason of age.
- (2) **Adult mini-motion picture theater** means an enclosed building with a capacity for less than 50 persons used for presenting material distinguished or characterized by an emphasis on matter depicting, describing or relating to specified sexual activities or specified anatomical areas, for observation by patrons therein. Such establishment is customarily not open to the public generally, but only to one or more classes of the public, excluding any minor by reason of age.
- (3) **Adult motel/hotel** means a building in which lodging is provided or offered to the public for compensation and which is open to transient guests where the room charge is made by the hour, and/or in which books, magazines

and other periodicals or materials which are distinguished or characterized by their emphasis on matter depicting, describing or relating to specified sexual activities or specified anatomical areas, may be sold or rented, or where motion pictures or video tapes with an emphasis on specified sexual activities or specified anatomical areas are available for viewing on an in-room viewing screen or television monitor.

- 230 (4) **Adult motion picture theater** or **adult live stage performing theater** means an enclosed building with a capacity of 50 or more persons used for presenting material distinguished or characterized by an emphasis on matter depicting, describing or relating to specified sexual activities or specified anatomical areas for observation by patrons therein. Such establishment is customarily not open to the public generally, but only to one or more classes of the public, excluding any minor by reason of age.
- (5) **Cabaret** means an establishment which features any of the following: topless dancers and/or bottomless dancers, strippers, or topless and/or bottomless waitpersons or employees or any other form of nude or partially nude service or entertainment.
- 240 (6) **Massage parlor or massage establishment** means a place where manipulated massage or manipulated exercises are practiced for pay upon the human body by anyone using mechanical, therapeutic, or bathing devices or techniques, other than the following: a duly licensed massage therapist, physician, osteopath, or chiropractor; a registered or practical nurse operating under a physician's directions; or, registered physical or occupational therapists or speech pathologists who treat patients referred by a licensed physician and operate only under such physician's direction. A massage establishment may include, but is not limited to, establishments commonly known as massage parlors, health spas, sauna baths, turkish bathhouses, and steam baths. Massage establishments shall not include properly-licensed hospitals, offices of a duly licensed massage therapist, medical clinics, or nursing homes, or beauty salons or barbershops in which massages are administered only to the scalp, the face, the neck or the shoulders; or other establishments that offer massages performed by a duly licensed massage therapist.
- 250 (7) **Specified anatomical areas** means portions of the human body defined as follows:
- (i) Less than completely and opaquely covered human genitals, pubic region, buttocks, or female breast below the point immediately above the top of the areola; and
 - (ii) Human male genitals in a discernibly turgid state, even if completely and opaquely covered.
- (8) **Specified sexual activities** means the explicit display of one or more of the following:
- (i) Human genitals in a state of sexual stimulation or arousal.
 - (ii) Acts of human masturbation, sexual intercourse, or sodomy.
 - (iii) Fondling or other erotic touching of human genitals, pubic region, buttocks, or female breast.

Alley means a public right-of-way which affords only a secondary means of access to abutting property and not intended for general vehicular traffic circulation.

260

Alternative energy means photovoltaic energy, solar thermal energy, geothermal energy, and wind energy production.

Alteration means any change, addition or modification in construction or type of occupancy; any change in the structural members of a building, such as walls, partitions, stairways, columns, beams, girders; any change in the width or number of exits; any substantial changes in the roof or exterior walls; any change in the location of a building; any change in the number of off-street parking spaces or loading areas or means of egress and ingress to the site; or any change which may be referred to as "altered" or "reconstructed" or "change of use."

270

Alternative paving means alternatives to traditional impervious asphalt or concrete paving techniques that save energy, decrease the heat island effect, and/or increase stormwater infiltration. This includes pervious paving and pavers and geogrid installations, but does not include loose gravel.

Antenna means the arrangement of wires or metal rods used in the sending and receiving of electromagnetic waves.

Antenna support structure means any mast, pole, tripod, tower, or similar structure used to support an antenna.

Antenna system means the combination of an antenna and antenna support structure.

280

Arts and crafts studios mean facilities that are used as work space for an artist or crafter or an instruction place for the study of an art or craft. Arts uses shall include, but are not limited to, the fine arts such as music, dance, film (except for adult regulated uses), and photography. Craft uses include the handmade production of articles other than food, such as pottery, glass items, neon sculpture, jewelry, silk screening, needle work, stone and wood work, metalworking or casting, and similar items.

Auction house means a permanent facility where items of merchandise are sold and physically conveyed to the highest bidder in an enclosed facility. This does not include on-line auction activities or temporary auctions.

290 **Automobile** means, unless specifically indicated otherwise, any vehicle including cars, trucks, pickups, vans, commercial vehicles, motorcycles, and the like.

Automobile filling station means any building, structure or land used for the retail sale of fuels, lubricants, and automobile accessories and the making of minor repairs to vehicles or parts thereof totally enclosed within a building. An automobile filling station shall not include engine and transmission rebuilding, reconditioning or general repairs; collision service such as body, frame or fender straightening or repair; steam cleaning, undercoating and rustproofing; painting and similar exterior detailing; machining; and similar servicing, rebuilding or repairs that normally require significant disassembly or storing the automobiles on the premises overnight.

300 **Automobile repair** means repair of automobiles including engine tune-ups and servicing of brakes, air conditioning, exhaust systems; oil change or lubrication; wheel alignment or balancing; or similar servicing, engine and transmission rebuilding, reconditioning or general repairs; collision service such as body, frame or fender straightening or repair; steam cleaning, undercoating and rustproofing; painting and similar exterior detailing; machining; and similar servicing, rebuilding or repairs.

Automobile Share Organization means a membership-based car-share service to the public and manages, maintains and insures motor vehicles for shared use 24-hours a day by individual and group members. This definition does not include automobile rental services where vehicles are leased by the day and vehicles are stored, washed and/or repaired in the same facility.

310 **Automobile Share Parking** means a parking space or spaces which it is located and dedicated for use by any automobile share organization through a deed restriction, condition of City approval, or license agreement.

Automobile Wash/Detailing means any building or premises or portions thereof used for washing and/or detailing motor vehicles and includes automatic, self-service and hand wash facilities.

Awning means a structure generally constructed so as to shade a window or door opening on a building, which is made of rigid or nonrigid materials stretched over a frame attached to a building and which may or may not be constructed so as to be raised or retracted to a position against the building when not in use.

B

320 **Bar/lounge** means an establishment which is operated primarily for the dispensing of alcoholic beverages, although the sale of prepared food or snacks may also be permitted. If an establishment includes a bar or lounge and a separate dining facility, the establishment shall be considered a bar/lounge if more than 50 percent of the usable floor area of the entire establishment is used for the bar/lounge. Brewpubs, as defined and licensed by the State of Michigan, shall be considered a bar/lounge.

Base flood means the flood having a one percent probability of being equaled or exceeded in any given year as determined by the Federal Insurance Administration and/or the U.S. Army Corps of Engineers; also referred to as the 100-year flood.

330 **Base flood elevation** means the height of the base flood in relation to the National Geodetic Vertical Datum of 1929.

Basement. See *Story, basement*.

Bed and breakfast lodging means a structure which was constructed for and is used for single-family residential purposes, but which may have as an accessory use a temporary lodging for travelers/guests where bedrooms are rented on a nightly basis with breakfast included in the price of the room.

340 **Bedroom** means any private room in a dwelling unit suitable for regular use for sleeping purposes, as defined in the Building Code. Bedrooms can include rooms designated on development floor plans as dens, studies, or libraries but not living rooms, family rooms, dining rooms, kitchens, bathrooms, laundry rooms, and mud rooms. Any room

designated as other than a bedroom but which in the judgment of the City Planner and the Building Official or Planning Commission could normally be usable for sleeping purposes shall be considered a bedroom. Any bedroom designed for occupation shall have minimum space requirements as established by the Building Code for existing structures or as established by the building code adopted by the this Code for new construction, additions or repairs.

Berm means a continuous, raised earthen mound with a flattened top and sloped sides, capable of supporting live landscaping materials, and with a height and width that complies with the requirements of this chapter.

350 **Board of Appeals** means the Zoning Board of Appeals of the City, created pursuant to the provisions of Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.), as amended.

Boardinghouse. See "Roominghouse."

Body art facility means any location that provides, as a primary function, tattooing, branding, body-piercing, or similar body modification for a non-medical purpose. Body art facilities shall be regulated as required by State of Michigan Act 149 of the Public Acts of 2007, as amended, and shall comply with all inspections, licensing, and other procedures required by that act or by regulations established by Washtenaw County.


360 **Brewer/distiller/wine maker** means a facility in which beer, wine or other alcoholic beverages are brewed, fermented, or distilled and then packaged and stored for distribution and, if allowed by licenses and zoning, consumption; and for possesses the appropriate license(s) from the State of Michigan and the federal government. Accessory uses to the facility, if allowed by the state license, such as direct to consumer sales, tasting rooms and restaurants are regulated by zoning district.

Building means any temporary or permanent structure, having a roof or other covering, used or built for the support, enclosure, shelter, or protection of persons, animals, chattel or property of any kind, designed primarily for shelter rather than as a means of conveyance. A building shall not include such structures as signs, fences or smokestacks.


370 **Building code** means chapter 18 of this Code.

Building, completely enclosed means a building separated on all sides from the adjacent open space or from other building or structures by a permanent roof and exterior walls having only window and normal entrance or exit doors.

Building height means the vertical distance from the established grade of the center of the front of the building to the highest point of the roof surface of a flat roof; to the deck line of mansard roof; to the mean height level between the eaves and ridge for a hip, gambrel or gabled roof; and 75 percent of the height of "A" frame. Chimneys, spires, antenna, and similar projections other than signs shall not be included in calculating building height.



Building line means a line parallel to the front lot line that separates all parts of a building from the open spaces adjacent thereto on the same lot. For the purposes of this chapter, a minimum building line is the same as a required front yard setback line.



Building, principal means a building or group of buildings in which is conducted the main or principal use of the lot on which the building is situated. See "Accessory use, building, or structure" and "Use, principal."

390 **Building, temporary** means a building which is not permanently affixed to the property, and is permitted to exist for a specific reason for a specific period of time. An example of temporary building is a trailer used on a construction site.

Bulk means a composite characteristic of a given building as located upon a given lot; not definable as a single quantity, but involving all of the following characteristics:

- (1) Size and height of the building;
- (2) Location of exterior walls at all levels in relation to lot lines, streets, or to other buildings;
- (3) Gross floor area of the building in relation to lot area;
- (4) All open spaces allocated to the building; and
- (5) Amount of lot area provided per dwelling unit.

400 **C**

Canopy means a roof-like structure, other than an awning, made of rigid and durable materials with frames attached to and made a part of the building and further supported by a frame to the ground or sidewalk; or in the case of an automobile filling station or automobile repair garage that sells fuels, a canopy is a roof-like structure that is supported mainly by vertical support beams and not walls, it may or may not be attached to the principal building, and is designed to shelter the fuel pumps.

Carport means a structure consisting of a roof supported by posts which is otherwise open to the elements on at least two sides, which is mainly used for storage of automobiles.

410 **Change of Use** constitutes the conversion of an existing structure from one class or type of use to another. Such a change may or may not include exterior building alterations.

Child care means the following:

- (1) **Family day care home** means a private home, licensed by the state, in which one but less than seven minor children are received for care and supervision for periods of less than 24 hours a day, unattended by a parent or legal guardian, except children related to an adult member of the family by blood, marriage, or adoption. Family day care home includes a home that gives care to an unrelated minor child for more than four weeks during a calendar year.
- 420 (2) **Group day care home** means a private home, licensed by the state, in which more than six but not more than 12 minor children are given care and supervision for periods of less than 24 hours a day unattended by a parent or legal guardian, except children related to an adult member of the family by blood, marriage or adoption. Group day care home includes a home that gives care to an unrelated minor child for more than four weeks during a calendar year.
- 430 (3) **Child care center or day care center** means a commercial facility, licensed by the state, receiving one or more children for care for periods of less than 24 hours a day, and where the parents or guardians are not immediately available to the child. Child care center or day care center includes a facility which provides care for not less than two consecutive weeks, regardless of the number of hours of care per day. The facility is generally described as a child care center, day care center, day nursery, nursery school, parent cooperative preschool, play group, or drop-in center. Child care center or day care center does not include a Sunday school, a vacation Bible school, or a religious instructional class that is conducted by a religious organization where children are in attendance for not more than three hours per day for an indefinite period or not more than eight hours per day for a period not to exceed four weeks during a 12-month period, or a facility operated by a religious organization where children are cared for not more than three hours while persons responsible for the children are attending religious services. State law reference(s)--Child care organizations, defined, MCL 722.111, MSA 25.358(11).

Cistern means a storage container that capture a larger volume of runoff stormwater than a rain barrel.

440 **City** means the City of Ypsilanti, Washtenaw County, Michigan.

City Council means the City Council of Ypsilanti, Washtenaw County, Michigan.

Club or lodge, private means a nonprofit association of persons who are bona fide dues paying members which owns or leases premises, the use of which is restricted to members and their guests. The facilities owned or used by such organization may be referred to as a "club" or "lodge" in this chapter.

450 **Coin-operated amusement device** means any mechanical or electrical device which provides amusement or entertainment which may be operated or set in motion upon the insertion of a coin or token, or payment of a fee. This definition shall not include juke boxes, music machines, telephone devices, machines which dispense merchandise or machines or devices that provide film or video tape presentations to a customer/user who is merely a passive spectator of such presentation. This exclusion shall not be deemed to exclude any machines or devices in which the customer/user is engaged in a form of competition against the machine or another customer/user.

Commission means the Planning Commission of the City of Ypsilanti, Michigan.

Communication device means an apparatus such as an antenna system or satellite dish stations of which the principal function is to send or receive television, radio, or data microwave signals.

460 **Communication Facilities, Mobile** mean and include all structures and accessory facilities relating to the use of the radio frequency spectrum for the purpose of transmitting or receiving radio signals. This may include, but not be limited to, cellular telephone towers, radio towers, television towers, telephone devices and exchanges, micro-wave relay towers, telephone transmission equipment building and commercial mobile radio service facilities. Not included within this definition are: citizen band radio facilities; short wave facilities; ham, amateur radio facilities; satellite dishes; and, governmental facilities which are subject to state or federal law or regulations which preempt municipal regulatory authority.

470 **Communications Facilities, Mobile Attached** means mobile communication Facilities that are affixed to existing structures, such as existing buildings, towers, water tanks, utility poles, and the like. A wireless communication support structure proposed to be newly established shall not be included within this definition.

Communication Support Structures, Mobile means structures erected or modified to support wireless communication antennas. Support structures within this definition include, but not be limited to, monopoles, lattice towers, light poles, wood poles and guyed towers, or other structures which appear to be something other than a mere support structure.

Communication facility, Co-location means the location by two or more wireless communication providers of mobile communication towers on a common structure, tower, or building, with the view toward reducing the overall number of structures required to support wireless communication antennas within the community.

480 **Condominium** means ownership in common with others of a parcel of land and certain parts of a building thereon which would normally be used by all of the occupants, such as yards, foundations, basements, floors, walls, hallways, stairways, elevators and all other related common elements, together with individual ownership in fee of a particular dwelling unit in such building.

Condominium Act means Act No. 59 of the Public Acts of Michigan of 1978 (MCL 559.101 et seq., MSA 26.50(101) et seq.), as amended.

490 **Condominium Lot** means that portion of a condominium project designed and intended for separate ownership and/or exclusive use, as described in the master deed. Condominium lot is further defined as:

- (1) A condominium unit consisting of the area under a building envelope and the contiguous area around the building envelope which, by itself, meets the minimum area and yard requirements for lots within each zoning district.
- (2) The contiguous limited common element under and surrounding a condominium unit that is or will be assigned to the owner of the condominium unit, for the owner's exclusive use, and which, together with the condominium unit, meets the minimum area and yard requirements for lots within each zoning district.

500 **Condominium structure or building envelope** means the principal building or structure intended for or constructed upon a lot or building site, together with any attached accessory structures. For example, in a residential development, the condominium structure or building envelope would refer to the house and any attached garage.

Condominium unit means that portion of the condominium project designed and intended for separate ownership

and use, as described in the master deed, regardless of whether it is intended for residential, office, industrial, business, or recreational use as a time-share unit, or any other type of use.

Cooperative housing means a multiple dwelling owned by a corporation which leases its units to stockholders/shareholders on a proprietary lease arrangement.

Correctional facility means a place of confinement for persons who have broken the law, are awaiting trial, and/or have been convicted of criminal offenses.

Curb cut means the entrance to or exit from a property provided for vehicular traffic to or from a public or private thoroughfare.

Craft Manufacturing means establishments manufacturing and/or assembling products primarily by hand or with hand tools and/or domestic mechanical equipment. Items produced may include, but are not limited to, custom furniture and woodworking, ceramics and glass, items intended for consumption, personal care products, candle making, jewelry making, custom textile manufacturing and crafts production.

D

Department of Community and Economic Development means the City department which reviews site plans, variance applications, proposed planned unit developments, and other applications associated with this chapter in order to provide information and recommendations that will assist the Planning Commission and Zoning Board of Appeals in their determinations.

District means a portion of the City within which, on a uniform basis, certain uses of land and/or buildings are permitted and within which certain regulations and requirements apply under the provisions of this chapter, such as building type, building height, building setback, and intensity of use.

Dormitory means those facilities used for housing students, which are owned and controlled by an educational institution and which are to be distinguished from hotels, motels, and boardinghouses. The terms "dormitory" and "residence hall" are to be used synonymously.

Drive-through service means a business activity so developed that its retail or service character provides a driveway approach and waiting spaces for motor vehicles so as to serve patrons while seated in their motor vehicle. An automatic teller machine or similar device shall not be included in this definition, provided that the device is not staffed and does not use any type of amplification device.

Dwelling means a building or portion thereof, containing sleeping, kitchen, and bathroom facilities designed for and occupied by one family, excluding hotels, motels, and inns. In no case shall a travel trailer, motor home, automobile, tent, or other portable building defined as a recreational vehicle be considered a dwelling. In the case of mixed occupancy where a building is occupied in part as a dwelling unit, the part so occupied shall be deemed a dwelling unit for the purposes of this chapter.

Dwelling, accessory means living or sleeping quarters, temporary or permanent, in an accessory building. Accessory dwelling units are prohibited in travel trailers, motor homes, or other recreational vehicle, auto chassis, boat, or portable building.

Dwelling, manufactured (also known as a "mobile home") means a vehicular, portable structure built on a chassis and designed to be used without a permanent foundation as a dwelling when connected to required utilities and which is, or is intended to be, attached to the ground, to another structure, or to a utility system on the same premises for more than 30 consecutive days. The unit shall be labeled as prescribed under the provisions of the Mobile Homes Construction Safety Standards as promulgated by the United States Department of Housing and Urban Development being 24 CFR 3280. Recreational vehicles as described and regulated shall not be considered "mobile homes" for the purpose of this chapter. *See also "Dwelling, one-family or single-family."*

Dwelling, premanufactured means an assembly of materials or products intended to comprise all or part of a building or structure, and that is assembled, at other than the final location of the unit of the building or structure, by a repetitive process under circumstances intended to ensure uniformity of quality and material content. The unit shall be labeled as prescribed in R408.31137 of the Michigan Department of Labor, Construction Code Commission

Administrative Rules Part 11. *See also "Dwelling, one-family or single-family."*

560

Dwelling, multiple means a building designed for and occupied by three or more families living independently with separate housekeeping, cooking, and bathroom facilities for each. Multiple dwelling units include the following:

- (1) **Apartment.** An apartment is an attached dwelling unit with party walls, contained in a building with other apartment units which are reached from a common stair landing or walkway, or are accessed directly from the outside.
- (2) **Efficiency unit or studio apartment.** An efficiency unit or studio apartment is a type of multiple-family or apartment unit consisting of one principal room with sleeping facilities, plus bathroom and kitchen facilities, hallways, closets, and/or a dining alcove located directly off the principal room. Sleeping facilities may also be separated from the principal living space by dividers or lofts.

570

Dwelling, one-family or single-family means a detached building containing not more than one dwelling unit designed for residential use.

Dwelling, two-family or duplex means a detached building, designed exclusively to be occupied by two families living independently of each other, with separate housekeeping, cooking, and bathroom facilities for each.

Dwelling unit, single-family attached or townhouse means an attached single-family dwelling unit with party walls, designed as part of a series of three or more dwellings, with its own front door which opens to the outdoors at front level, and typically with its own basement utility connections, and front and rear yards. A townhouse may be located on its own lot, or may be located on land commonly owned by a condominium association or similar association. Townhouses are also commonly known as rowhouses.

580

E

Easement means a grant of one or more of the property rights by the property owner to and/or for the use by the public, a corporation, or another person or entity. The term "easement" often applies to public or private rights-of-way and to "utility easements" which give utility companies the right to use land for the construction and maintenance of utilities.

Encroachment means any construction, structure, filling grading, or deposition of materials in, upon, across or projecting into a floodplain, channel, or floodway.

590

Erected means built, constructed, reconstructed, moved upon, or any physical operations on land required for the building. Excavations, fill, drainage, and installation of utilities shall be considered part of erected.

Essential services means the erection, construction, alteration, or maintenance by public utilities or municipal departments or City licensed cable television companies or underground, surface, or overhead gas, steam, electrical, fuel or water systems for the purposes of transmission, distribution, collection, communication, supply or disposal; including towers, poles, boxes, wires, mains, drains, sewers, pipes, conduits, cables, fire alarm and police call boxes, traffic signals, hydrants, and similar equipment, which are necessary for the furnishing of adequate service by such utilities or municipal departments for the general health, safety, and welfare of the public. The location, size, and intensity of essential services shall be regulated by the standards of this chapter. Essential services shall also not include communication providers when there is more than one entity servicing a geographic area and which are not regulated by the state public service commission.

600

Excavation means the removal or movement of soil, sand, stone, gravel, or fill dirt, except for common household gardening, farming, and general ground care.

F

Family means:

- (1) One individual;
- (2) A group of two or more persons related by blood, marriage or adoption, together with foster children; together with:
 - (i) No more than two domestic workers employed by the household; OR
 - (ii) No more than two additional unrelated persons occupying the unit as boarders, roomers, or guests; All of whom are domiciled together as a common, domestic, household in a single dwelling unit;
- (3) A group of persons, none of whom are related to each other by blood, marriage, or adoption, who reside

610

together in a single dwelling unit, provided that the total number of occupants in such group shall not exceed three, except in the MD district and in any permitted residential uses in any corridor district the total number of occupants in this group shall not exceed four, unless otherwise provided for in this chapter; or

- (4) A collective number of individuals living together in one dwelling unit, whose relationship is of a continuing, nontransient, domestic character, and who are cooking and living as a single, nonprofit housekeeping unit. This definition shall not include any society, club, fraternity, sorority, association, lodge, coterie, organization, or group of students or other individuals whose domestic relationship is of a transitory or seasonal nature or for an anticipated limited duration of a school term or terms or other similar determinable period.

Family day care home. See “Child Care.”

Farmers’ market means an indoor or outdoor market open to the public offering for sale at retail vegetables, produce, other farm products, and value-added food products, occurring in a pre-designated area, where the vendors are individuals who have grown or produced the food products or have taken the same on consignment for retail sale.

FBFM means the flood boundary and floodway map, used as a floodplain management map that depicts, based on detailed analyses, the boundaries of the 100-year and SOO-year floods and the 100-year floodway. For the purposes of this chapter, the FBFM is the map titled Flood Insurance Rate Map(s) (FIRMS) Washtenaw County (All Jurisdictions) panel number(s) of 26161C; 00269E, 0288E, 0407E, and 0426E dated 4/3/12.

Fence means a permanent or temporary unroofed barrier enclosing or bordering a plot of land or portion thereof composed of wood, shrubs or suitable manmade materials for the purpose of preventing or controlling entrance, confining within, screening, or marking a boundary.

Fill means the deposit or dumping of any matter onto or into the ground, except for common household gardening, farming, and general ground care.

FIRM means the flood insurance rate map titled Flood Insurance Rate Map(s) (FIRMS) Washtenaw County (All Jurisdictions) panel number(s) of 26161C; 00269E, 0288E, 0407E, and 0426E dated 4/3/12.

Flood means a temporary increase in the stage of a river or stream resulting in the inundation of lands not normally covered by water.


Flood insurance study means the engineering study performed by FEMA to identify flood-prone areas, insurance risk zones, and other flood data and contained in a document titled, Flood Insurance Study, Washtenaw County (All Jurisdictions) Community Number 260216, dated April 3, 2012.

Floodplain means that area of land adjoining a river or stream which will be inundated by a 100-year flood.

Floodway means the channel of a river, stream, creek, or other watercourse and the adjacent land areas that must be reserved in order to discharge the base flood without cumulatively increasing the water surface elevation more than one foot. In the City, the floodway includes the Huron River and Paint Creek along with the adjoining land, as shown on the Federal Emergency Management Agency insurance maps.

Floor area, gross means the total area of a building measured by taking the outside dimensions of the building at each floor level intended for occupancy or storage, not including any uncovered or unenclosed porches, patios, or decks.

Floor area, usable nonresidential means the sum of the horizontal areas of each floor, measured from the interior faces of the exterior walls, including all areas used for, intended to be used for, and accessible for the sale of merchandise, provision of services, or service to patrons, clients or customers. Floor area which is used for or intended to be used for the storage or processing of merchandise, or for utilities shall be excluded from the computations of usable nonresidential floor area. If precise floor plans are not available for calculations, usable nonresidential floor area shall be 80 percent of gross nonresidential floor area.



Floor area, usable residential means the gross floor area minus area in basements, unfinished attics, attic floor area with less than five feet vertical distance from floor to finished ceiling, attached garages, uncovered or enclosed porches, patios, terraces, carports, breezeways, decks, or verandas.

700 **Foster family home.** A private residence, licensed by the state, that houses four or fewer foster children, up to age 19, under constant child care and supervision. Under Act No. 116 of the Public Acts of Michigan of 1973 (MCL 722.111 et seq., MSA 25.358(11) et seq.), a foster family home does not require local zoning approval before being licensed by the state department of social services.

Foster family group home. A private residence, licensed by the state, that houses five or six foster children, up to age 19, under constant care and supervision. Under Act No. 116 of the Public Acts of Michigan of 1973 (MCL 722.111 et seq., MSA 25.358(11) et seq.), a foster family group home shall be considered a residential use of property for the purposes of zoning and permitted use in all residential zones and is not subject to a special use permit or procedure different from those required for other dwellings of similar density in the same zone.

710 **Fraternity or sorority house** means a building, rented, occupied or owned by a national or local chapter of some regularly organized college fraternity or sorority which is officially recognized by a college or university, or by or on its behalf by a building corporation or association composed of members of such fraternity or sorority, as a place of residence.

Frontage, Private refers to the side of the building that faces the primary street, and includes the area between the building façade and the lot line.

720 **Frontage, Public** means between the face of the curb and the back of the sidewalk. It includes the sidewalk, street trees, street lighting, and any landscaped planting strips that there may be. The public frontage is the crucial area where pedestrians circulate and access property and buildings. It serves as the walkable urban districts' primary source of public open spaces, where people often mingle, converse, play, and eat. The public frontage is both an important part of the transportation system and of the social and economic fabric.

G

Garage means an accessory building or portion of a principal building used or designed to be used primarily for the storage of motor vehicles, boats, or trailers owned and used by the occupants of the building to which it is accessory.

Garden/Community Garden means land used to grow and harvest food or non-food crops for personal or group use. The products of gardens/community gardens may or may not be for commercial purposes.

730 **Gas station.** See "*Automobile filling station.*"

Geothermal Energy means power extracted from heat stored in the earth. Geothermal resources include: all products of geothermal processes embracing indigenous steam, hot water and hot brines; steam and other gases, hot water and brines resulting from water, other fluids or gas artificially introduced into geothermal formations; heat or other associated energy found in geothermal formations, including any artificial stimulation or induction thereof; and, any mineral or minerals, exclusive of fossil fuels and helium gas, which may be present in solution or in association with geothermal steam, water or brines.

740 **Grade** means the average level of the finished surface of the ground adjacent to the exterior walls of the building or structure.

Greenbelt means a strip of land of definite width and location reserved for the planting of a combination of shrubs, trees, and ground cover to serve as an obscuring screen or buffer for noise or visual enhancement, in accordance with the requirements of this chapter.

Greenhouse, commercial means a space, building, structure, or combination thereof, where live trees, shrubs, and other plants used in gardening and landscaping are propagated, stored, and/or offered for sale on the premises. *If business is conducted primarily outdoors, see "Open air business."*

750 **Group residence** means a building used as a residence by a group of persons who are not a family on a weekly or longer basis. Typical uses include cooperatives, sororities and fraternities. This definition does not include

boarding houses, roominghouses or other group living more specifically defined in this Chapter, specifically any group living or care facility licensed by the State of Michigan.

Ground cover means low-growing plants that form a dense, extensive growth after one complete growing season, and tend to prevent weeds and soil erosion.

H

760 **Home occupation** means an occupation or profession carried on by a member or members of the immediate family residing on the premises which use is clearly incidental and secondary to the use of the dwelling for dwelling purposes; does not change the character thereof; and which does not endanger the health, safety, and welfare of any other persons residing in that area by reason of noise, noxious odors, unsanitary or unsightly conditions, fire hazards and the like.

Homeless Shelter means a facility which provides congregate style temporary lodging with or without meals and supportive services on the premises to primarily the homeless for more than four (4) weeks in any calendar year. A shelter does not provide such lodging to any individual (1) who is required because of age, mental disability or other reason to reside either in a public or private institution or (2) who is imprisoned or otherwise detained pursuant to
770 either federal or state law. A shelter for the homeless is considered a different land use than adult foster care facilities, supportive housing, nursing homes, temporary emergency shelters, or warming centers.

Hospital means an institution which is licensed by the state department of health to provide in-patient and out-patient medical and major surgical services for the sick and injured, and which may include such related facilities as laboratories, medical testing services, central service facilities, and staff offices.

Hotel or motel means a building in which lodging is provided and offered to the public for compensation, which is open to transient guests generally on a per-day basis and not for long-term lodging, in distinction from a roominghouse, bed and breakfast lodging, or inn. Hotels or motels customarily provide services such as desk
780 service, maid service, laundering of linens, the use of furniture, etc. No kitchen or cooking facilities are to be provided, with the exception of units for use of the manager or caretaker; unless approved by the Planning Commission as a special use.

I

Ingress and egress means, and is generally used in reference to a driveway which allows vehicles to enter or leave a parcel of property, or to a sidewalk or entranceway which allows pedestrians to enter or leave a parcel of property, a building, or another location.

Indoor recreation means recreation uses occurring entirely inside a building including bowling alleys, gymnasiums or court sports facilities, tennis clubs, roller or ice skating rinks, recreation centers, personal fitness centers, and
790 similar recreation use.

Inn. See “Bed and Breakfast.”

J

Junk means any motor vehicles, machinery, appliances, products or merchandise with parts missing, or other scrap materials that are damaged, deteriorated, or are in a condition which prevents their use for the purpose for which the product was manufactured.

Junkyard means an area where waste and used or secondhand materials are bought and sold, exchanged, stored, baled, packed, disassembled, or handled including, but not limited to: junk, scrap iron, metals, paper, rags, tires,
800 bottles, and automobiles.

K

Kennel means any lot or premises on which four or more dogs, cats, or other domestic animals six months or older are kept, either permanently or temporarily, either for sale, breeding, boarding, training, hobby, protection, grooming or as pet; and may offer provision for minor medical treatment, including animal shelters.

L

Laboratory means a place devoted to experimental, routine, or basic study such as testing and analytical operations and in which the manufacturing of products, except prototypes, is not performed.

810 **Landscaping** means the treatment of the ground surface with live plant materials such as, but not limited to, grass, ground cover, trees, shrubs, vines, edible plants, and flowers. A landscape design may include other decorative manmade materials such as wood chips, crushed stone, boulder, raised garden beds, or mulch. Structural features such as fountains, pools, statues, and benches may also be considered a part of landscaping, but only if provided in combination with live plant material. Artificial plant materials shall not be counted towards meeting the requirements for landscaping.

Loading space, off-street means an off-street space of definite size and dimensions in accordance with the requirements of this chapter, which is safely and conveniently located on the same lot as the building or buildings being served, for the temporary parking of delivery vehicles while loading and unloading merchandise and materials.

820 **Lot (or zoning lot or parcel)** means a piece of land under one ownership and control that is at least sufficient in size to meet the minimum requirements for use, coverage, area, setbacks, parking, and open space as required by this chapter. A lot shall have frontage on a street. A lot may consist of the following:

- (1) A single lot of record (See "Lot of record").
- (2) A portion of a lot of record.
- (3) A combination of complete lots of record, or portion thereof.
- (4) A piece of land described by metes and bounds.

830 **Lot, abutting** means lots which share a common interior lot line and which are not separated by a public or private right-of-way or easement.

Lot, adjacent means lots which adjoin each other or which are separated only by a public or private right-of-way or easement.

Lot, contiguous means lots adjoining each other.

Lot, corner means a lot of which at least two adjacent sides abut their full length upon a street, provided that such two sides intersect at an angle of not more than 135 degrees. Where a lot is on a curve, if the tangents through the extreme point of the street lines of such lot make an interior angle of not more than 135 degrees, it shall be considered a corner lot. In the case of a corner lot with a curved street line, the corner is that point on the street lot line nearest to the point of intersection of the tangents described above. Tangents are straight lines extended from the outer edges of a curve which intersect to form a corner.

Lot, double frontage means a lot other than a corner lot having frontage on two more or less parallel streets. Also called a through lot. In the case of a row of double frontage lots, one street shall be designated as the front street for all lots in the plat. If there are existing buildings in the same block fronting on one or both of the streets, the required minimum front yard setback shall be observed on the street where buildings presently front.

Lot, interior means a lot other than a corner lot.


Lot area means the total horizontal area within the lot lines of a lot, exclusive of any abutting public street right-of-way or private road easements, or the area of any lake, except that any lot which abuts an alley, may include the area of half the width of such alley where it abuts the lot in determining the total area of that lot.

Lot coverage means the part or percent of the lot that is occupied by buildings or structures.

Lot depth means the horizontal distance between the front and rear lot lines, measured along the midpoint between the side lot lines.

Lot line means any line separating a parcel of land from another. Lot lines are further defined as follows:

- (1) **Front lot line** means, in the case of an interior lot abutting on one public or private street, the line separating the lot from such street right-of-way. In the case of a corner or double frontage lot, the front lot line shall be that line separating such lot from the street which is designated as the front street in the plat and/or in the request for a building permit.
- (2) **Rear lot line** means the lot line which is opposite and most distant from the front lot line. In the case of irregular, triangular, wedge shaped, or lots that are pointed in the rear, the rear lot line shall be an imaginary line parallel to the front lot line, not less than ten feet in length, lying farthest from the front lot line and wholly within the lot.



(3) **Side lot line** means any lot line other than the front or rear lot lines. A side lot line separating a lot from a street is a street side lot line. A side lot line separating a lot from another lot or lots is an interior side lot line.


(4) **Interior lot line** means any lot line which does not separate a lot from a street right-of-way. A lot line which separates a lot from an alley right-of-way shall be considered an interior lot line.

Lot of record means a lot or parcel of land, the deed of which has been recorded in the office of the registrar of deeds of the county.

Lot split or consolidation means the dividing or uniting of lots by virtue of changes in the deeds in the office of the county registrar of deeds and/or the City treasurer.

Lot, through see “Lot, double-frontage.”

Lot width means the straight line distance between the side lot lines, measured at the two points where the minimum front yard setback line intersects the side lot lines.



M

Major thoroughfare. See “Street.”

Massage parlor or **massage establishment**; see “Adult Regulated Uses.”

Massage therapist means an office where massage is performed for financial compensation only by individuals who satisfy the requirements of the Massage Therapy Licensing Act (PA 471 of 2008) as amended.

Master deed means the legal document prepared and recorded pursuant to Act No. 59 of the Public Acts of Michigan of 1978 (MCL 559.101 et seq., MSA 26.50(101) et seq.), as amended, to which is attached as exhibits and incorporated by reference the approved bylaws for the project and the approved condominium subdivision plan for the project.

Master plan means a document which is prepared under the guidance of the City Planning Commission and consists of graphic and written materials which indicate the general location for streets, parks, schools, public buildings, and all physical development of the City. The master plan is intended as a guide for all development within the City, and is used to guide the Zoning Board of Appeals and the Planning Commission in all decisions before those bodies. The master plan is updated periodically.

Medical or dental clinic or office means an office of physicians, dentists, massage therapists, or similar professionals or which is staffed on a rotational basis with personnel from an area hospital, where persons are examined or treated on an outpatient basis only, including outpatient surgery.

Medical marijuana dispensary means a facility, including a membership club, where primary caregivers who are legally registered by the Michigan Department of Community Health (MDCH) may lawfully assist qualifying patients to whom the primary caregiver is connected through the state registration process and who are also legally registered by the MDCH with the medical use of marijuana in accordance with the Michigan Medical Marijuana Act, as amended. A use which purports to have engaged in the medical use of marijuana either prior to enactment of said Act, or after enactment of said Act but without being legally registered by the MDCH, shall be deemed to not be a legally established use, and therefore not entitled to legal nonconforming status under the provisions of this Ordinance and/or State Law.

Medical Marijuana Growing/Manufacturing Facility. A facility for the cultivation and processing of medical marijuana into a usable form by primary caregivers who are legally registered by the Michigan Department of Community Health (MDCH) in accordance with the Michigan Medical Marijuana Act, as amended. A use which purports to have engaged in the cultivation and processing of medical marijuana into a usable form either prior to enactment of said Act, or after enactment of said Act but without being legally registered by the MDCH, shall be deemed to not be a legally established use, and therefore not entitled to legal nonconforming status under the provisions of this Ordinance and/or State Law. A maximum of five (5) primary caregivers may operate at a medical marijuana growing/manufacturing facility, provided all applicable zoning ordinance standards can be met.

Medical Marijuana Home Occupation means the cultivation of medical marijuana by a registered primary caregiver as defined in Sec. 3 of the Act, MCL §333.26423(g), in compliance with the General Rules of the Michigan Department of Community Health, the Michigan Medical Marijuana Act, Initiated Law 1 of 2008, MCL §333.26423(e), within a single family dwelling that is the registered primary caregiver's primary residence and which cultivation is in conformity with the restrictions and regulations contained in the Act and in the State Regulations developed by the Michigan Department of Community Health (MCDH). Medical Marijuana Home Use does not include any multi-family dwelling.
(State Law reference(s)--Michigan Medical Marihuana Act, Initiated Law 1 of 2008, MCL §333.264 et seq)

Mezzanine. See *Story, mezzanine*.

Microbrewer/small distiller/small wine maker means a facility in which a limited amount beer, wine or other alcoholic beverages, defined by the State of Michigan Liquor Control Commission, are brewed, fermented, or distilled and then packaged and stored for distribution.

Motel. See "Hotel or motel."

Municipality means the City.

Mural means a hand-produced work of visual art that is tiled or painted directly upon, or affixed directly to, an exterior wall of a building; considered ornamentation.

N

Nonconforming lot means a lot which was lawfully in existence at the effective date of the ordinance from which this chapter is derived, or amendments thereto, and which does not now conform to the lot size, lot width, or other provisions of this chapter for the zoning district in which it is located.

Nonconforming structure means a building or structure which was lawful on the effective date of adoption or amendment of this chapter, but which does not conform to the new chapter regulations for lot area, lot area per dwelling unit, lot width, lot coverage, floor area, height, greenbelts or screening, off-street parking, loading space, yard, or other requirements of the zoning district in which it is located.

Nonconforming use means a use which was lawfully in existence at the effective date of the ordinance from which this chapter is derived, or amendment thereto, and which does not now conform to the use regulations of this chapter for the zoning district in which it is now located. A nonconforming use may include a use that requires a Special Use Permit under current regulations contained in this chapter, where under previous regulations a Special Use Permit was not required or granted.

Nuisance means any offensive, annoying, or disturbing practice or object, which prevents the free use of one's property, or which renders its ordinary use or physical occupation uncomfortable. A nuisance commonly involves continuous or recurrent acts which give offense to the senses, violate the laws of decency, obstruct reasonable and comfortable use of property, or endanger life and health.

Nursery, day nursery, or nursery school. See "Child care center."

Nursing home, convalescent home, or rest home means a home for the care of the aged, infirm, or those suffering from physical or mental disorders, wherein two or more persons are housed or lodged and furnished with nursing care. Such facilities are licensed in accordance with Act No. 368 of the Public Acts of Michigan of 1978 (MCL

1010

O

Occupancy, change of means an abandonment of an existing use and the substitution of a use of a different kind or class, or the expansion of a use.

Occupied means used in any way at the time in question.

Open air business means any business that is conducted primarily out-of-doors. Unless otherwise specified, open air businesses shall include, but are not limited to:

- 1020
- (1) Retail sales of garden supplies and equipment, including but not limited to: trees, shrubbery, plants, flowers, seed, topsoil, trellises, and lawn furniture.
 - (2) Roadside stands for the sale of agricultural products, including fruits, vegetables, and Christmas trees.
 - (3) Outdoor display and sale of model garages, swimming pools, playground equipment, and similar uses.

Open space means that part of a lot, including courts and/or yards, which is open and unobstructed from its lowest level to the sky, and is accessible to all occupants upon the zoning lot.

Ownership, change in means whenever the title to the property is transferred to another person, including purchase by land contract.

P

Parcel. See "Lot."

1030

Park means either a publicly owned and designated park, or an amenity provided and maintained by a property owner for public use.

Parking garage means a building for the storage only of noncommercial vehicles of occupants in the same block or abutting blocks and providing no service to vehicles stored therein.

Parking lot, community means a parking lot on public or privately-owned property which provides parking with or without compensation for uses located in the general area in which it is situated.

1040

Parking, off-street means an area not located within a public right-of-way which provides vehicular parking spaces along with adequate drives and aisles for maneuvering so as to provide for safe and convenient ingress and egress to the parking area.

Parking space means an area, enclosed or unenclosed, of definite length and width as designated in this chapter, to store one automobile or other vehicle which is fully accessible by a driveway connecting the parking space with a street, road or alley and permitting ingress and egress of an automobile. The term "parking space" is exclusive of the access drives and aisles thereto.

1050

Party wall means a wall starting from the foundation and extending continuously through all stories to or above the roof that separates one building from another and that is in joint use by each building.

Passive solar building means a building with walls and roof that are predominantly transparent or translucent and does not have a foundation or permanent electrical utilities. Primarily used to grow plants. It may also be called a hoop house or greenhouse.

Performance standard means a criteria or limit relating to nuisance elements which a particular use or operation may not exceed. Performance standards are typically established to control noise, odor, smoke, toxic or noxious matter, vibration, fire and explosive hazards, glare, heat, or other effects.

1060

Person means an individual, trustee, executor, fiduciary, corporation, firm, partnership, association, organization, sole proprietor, or other legal entity acting as a unit.

Personal service establishment means a retail, office, or service business that is characterized by a one-on-one interaction between a customer and a proprietor or employee of the business. Includes but is not limited to the

following types of establishments: tailor, beauty salon &/or barber, cobbler, locksmith, small appliance repair, graphic design or printmaking services, or postal center.

Planned unit development (PUD) means an area planned and developed as a single entity containing one or more residential clusters or planned unit residential developments or one or more public, quasi-public, commercial or industrial areas.

Planning Commission means the City Planning Commission, created pursuant to the provision of Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.).

Porous paving means systems that allow water to pass freely through interstitial space ingrained throughout the paving matrix, thereby transforming traditionally impervious surfaces such as pervious concrete and asphalt, interlocking pavers, reinforced gravel and grass paving.

Principal use. See "Use, principal."

Private street or road. See "Street."

Public utility means any persons, firm, corporation, municipal department, or board, duly authorized through government rate regulation (such as by the state public utilities commission or the City) to furnish to the public under government regulations any of the following: electricity, gas, steam, communications services, cable television services, transportation services, water, sewer service, or sewage treatment.

Premises means a lot or property together with all buildings or structures thereon.

R

Rain gardens mean landscaped depressions that can be built to any size or shape. Also known as 'bio-retention cells', they are designed to allow water to settle and infiltrate into the soil.

Recycling center means an enclosed area or storage facility where area residents can drop off recyclable household wastes such as newspapers, cans, bottles, plastics, and cardboard which may be sorted and stored for short periods of time on the site until hauled away to another location for processing, reuse, or safe disposal.

Religious Institution means any structure wherein persons regularly assemble for religious activity or worship, including such uses normally accessory thereto, such as a fellowship hall, religious classrooms, parsonages or rectories, and offices. Where a group of persons, who are affiliated with a religious organization, reside together within a dwelling which is the principal building on a site, such dwelling shall not be considered a religious institution.

Refuse means the miscellaneous waste materials resulting from housekeeping, mercantile enterprises, trades, manufacturing and office, including other waste matter such as slag, stone, broken concrete, fly ash, sashes, tin cans, glass, scrap metal, rubber, paper, rags, chemicals, or any similar or related combinations thereof.

Research use means facilities for scientific research, and the design, development and testing of electrical, electronic, magnetic, optical and computer and telecommunications components in advance of product manufacturing, and the assembly of related products from parts produced offsite, where the manufacturing activity is secondary to the research and development activities, and includes pharmaceutical, chemical, and biotechnology research and development.

Restaurant means any establishment whose principal business is the sale of food and beverages to the customer in a ready-to-consume state, and whose method of operation is characteristic of a carry-out, drive-in, drive-through, fast food, or sit-down restaurant, as defined below. Any restaurant which combines elements of two or more of the following types of restaurants shall be subject to the regulations of the most restrictive restaurant type employed:

- (1) **Restaurant, carry-out.** A restaurant whose method of operation involves the sale of food, beverages, and/or frozen desserts in disposable or edible containers or wrappers in a ready-to-consume state for consumption off the premises, typically from a counter or window inside the building. Indoor seating for consumption on the premises is typically not present.

- (2) **Restaurant, drive-in.** A restaurant whose method of operation involves delivery of prepared food so as to allow its consumption in a motor vehicle or elsewhere on the premises, but outside of an enclosed building.
- (3) **Restaurant, drive-through.** A restaurant whose method of operation involves the delivery of the prepared food to the customer in a motor vehicle, typically through a drive-through window, for consumption off the premises. Indoor seating for consumption on the premises is typically not present.
- (4) **Restaurant, fast food.** A restaurant whose method of operation involves minimum waiting for delivery of ready-to-consume food to the customer at a counter for consumption at tables, booths, or stands inside the structure or out, or for consumption off the premises, but not in a motor vehicle at the site.
- 1130 (5) **Restaurant, sit-down.** A restaurant whose method of operation involves either:
- (i) The delivery of prepared food by servers (waitpersons) to customers seated at tables within a completely enclosed building; or
 - (ii) The prepared food is acquired by customers at a cafeteria line or ordering counter and is subsequently consumed by the customers at tables within a completely enclosed building.

Right-of-way means a right-of-way dedicated to or owned by a public body and available for use by the general public. In the case of public streets, the right-of-way often includes curbs, lawn strips (also referred to as the margin or parkway), sidewalks, and lighting and drainage facilities.

- 1140 **Room,** for the purpose of determining lot area requirements and density in a multi-family district, means a living room, dining room, or bedroom, and any other room equal to at least eighty (80) square feet in area. A room shall not include the area in kitchen, sanitary facilities, utility provisions, corridors, hallways and storage.

Roominghouse means a building, other than a hotel or motel, bed and breakfast lodging, or inn, where for compensation or by prearrangement for definite periods of time, lodging or lodging and meals are provided for three or more unrelated persons, not living as group or household. The term "unit" as it refers to a roominghouse shall mean sleeping room, or a room which may be used as a sleeping room. (See "Sleeping room.") A boardinghouse or lodginghouse shall be deemed a roominghouse for the purposes of this chapter.

S

- 1150 **Satellite antenna** means an accessory structure which at its widest dimension is in excess of 36 inches, capable of receiving signals from orbiting satellites and other extraterrestrial sources, together with other equipment related to such purposes.

Screen or screening means a wall, non-wire fence, or combination of plantings of sufficient height, length, and opacity to form a visual barrier

Self-storage facility means a building or group of buildings in a controlled access compound that contains individual compartmentalized and controlled access stalls or lockers of no more than 500 square feet each for the dead storage of customers' goods or wares in enclosed buildings.

- 1160 **Setback** means the distance between a front, side, or rear lot line and the nearest supporting member of a structure on the lot. The "minimum required setback" is the minimum distance between a front, side, or rear lot line and the nearest supporting member of a structure (including, but not limited to, the foundation, bay windows or similar architectural features at the ground floor level supported by the building or the ground, and enclosed or covered porches) in order to conform to the required yard setback provisions of this chapter. For a site condominium, setbacks are measured from the respective front, side, and rear yard area lines associated with the condominium lot to the respective front, side, and rear of the condominium structure/building envelope.

SIGNS

- 1170 **Sign** means any visual or graphic device designed to inform or attract attention and which is designed to be visible from outside any building or structure in which, upon which, or attached to which it may be located.

Sign, abandoned means a sign that contains or exhibits broken panels, visible rust, visible rot, damaged support structures, or which is otherwise dilapidated, unsightly, or unkempt; and for which the business or property owner has not accepted maintenance responsibility or intentionally altered for a period of no less than 365 days, where such acts evidence an intent to abandon.

1180 **Sign, animated** means a sign that uses light emitting elements including but not limited to light bulbs, fixtures, LEDs, fiber optic lighting to create a continuously scrolling, flashing, or animated effect.

Sign, awning means a sign that is painted on, attached to, or an integral part of an awning or canopy; considered a building-mounted sign.

Sign, banner means a sign consisting of a large piece of cloth or similar flexible material; considered a temporary sign.

1190 **Sign, billboard** means any freestanding permanent sign that is more than ten feet tall and has an area of more than 300 sf, and as defined in the Highway Advertising Act of 1972, PA 106 of 1972, as amended.

Sign, building-mounted means a sign that is attached to a building. Such signs may include, but are not limited to awning, projecting, wall, and window signs.

Sign, electronic message means a sign with a message displayed on a surface with an electronically illuminated changeable copy area, often composed of LEDs.

Sign, freestanding means any sign not attached to a building, including monument or pole signs.

1200 **Sign, historic marker** means a sign that is erected by a duly organized local historic preservation organization.

Sign, illuminated means a sign that provides artificial light directly or through transparent or translucent material from a source connected to or within such a sign, on which is illuminated by a light so shielded as to prevent direct rays from being visible from the public right-of-way.

1210

Sign, inflatable means a sign that is intended to be expanded by air or other gas for its proper display or support; considered a temporary sign.

Sign, mechanical means a sign that has any visible moving parts, mechanical movement or other apparent visible movement, achieved by electrical or mechanical means or action of normal wind currents.


Sign, overhead banner means a sign consisting of a large piece of cloth or similar flexible material suspended across a street or other public space and attached at each end; considered a temporary sign.

1220 **Sign, permanent** means a sign that is securely anchored and affixed to the ground or a building in a manner such that it can remain in place without maintenance for an indefinite period of time, often one year or more.

Sign, projecting means a sign which is attached directly to the building wall or suspended under an awning, canopy, or marquee, and which extends more than 18 inches from the face of the wall; considered a building-mounted sign.

Sign, public means a sign erected or installed by a government entity.

1230 **Sign, roof** means a sign which is constructed and maintained upon or above the roof of a building, marquee, or parapet wall and which is wholly or partially supported by such building; considered a type of building-mounted sign.



Sign, sidewalk means a temporary sign placed within the pedestrian right-of-way. These types of signs include “A” Frame and “T” Frame styles.


Sign, temporary means signs not permanently affixed to the ground or to a building, often constructed of cloth, canvas, fabric, plastic or other light temporary material, with or without a structural frame.

Sign, wall means a sign which is painted on or attached directly to a building wall that extends 18 inches or less from the face of the wall and which does not extend above the parapet, eaves, or building façade; considered a type of building-mounted sign.


Sign, window means any sign within a building placed within 12 inches of a window or upon a window pane and that is visible from the exterior of the building, not including merchandise located in a window.



Sign area means the gross surface area within a single continuous perimeter enclosing the extreme limits of all sign copy, or the surface of any internally-illuminated sign. Such perimeter does not include any structural or framing elements lying outside the limits of such sign and not forming an integral part of the display. Where a sign has two or more faces, the sign area shall equal the total area of all sign faces, except where two faces are placed back to back and are at no point more than three feet apart, in which case the sign area is considered to be the area of the larger face.



Sign height means the vertical distance measured from the average grade at the sign location to the highest point of the sign.



Sign structure means anything constructed or erected for the exclusive purpose of supporting a sign.

Site plan means a detailed plan showing all features of a proposed development so that the proposal may be evaluated to determine whether it meets the provisions of this chapter.

Sleeping room means a single room within a roominghouse which is usually individually rented and the entry door to the room is individually locked requiring the use of a key to gain access, and which is primarily used for sleeping purposes. The occupants may have direct access within the building to sanitary facilities, kitchen facilities and dining facilities or may share these facilities in common with other residents. See "Roominghouse."

Solar Collector means a device, substance, or element that relies upon sunshine to absorb and transform direct solar radiation through a medium to generate energy that can be used to heat or cool a building, heat or pump water, or generate electricity or other application that would otherwise require the use of a non-renewable energy source.

Solar Farm means large areas of land with several photovoltaic modules and inverters, or parabolic troughs placed on them for large scale energy generation.

Sorority house. See "Fraternity or sorority house."

Special use means a use that would be detrimental to other uses permitted in the same zoning district unless carefully controlled as to the number, area, size, exterior design, location, or relation to the adjacent properties and to the neighborhood or City as a whole, and may be permitted if the proper safeguards are taken. Formerly called conditional use.

Story means that portion of a building included between the upper surface of any floor and the upper surface of the next floor above it, or any portion of a building between the topmost floor and the roof having a usable floor area which exceeds two-thirds of the usable floor area of the floor immediately below it. Mezzanines and basements shall be deemed full stories as specified within their definitions.

(1) A *mezzanine* shall be deemed a full story when it covers more than one-third of the area of the story underneath such mezzanine, or if the vertical distance from the floor next below the mezzanine to the floor next above it is 24 feet or more.

(2) A *basement* shall be considered a story above grade where the finished surface of the floor above the basement is:


- (i) More than six feet above grade plane;
- (ii) More than six feet above the finished ground level for more than 50 percent of the total building perimeter; or
- (iii) More than 12 feet above the finished ground level at any point.

(3) *Story, first* means the lowest story of the ground story of any building that is not a basement, except that any basement or cellar used for residential purposes shall be deemed the first story.

(4) *Story, half* means a partial story under a gable, hip or gambrel roof, the usable floor area which does not exceed two-thirds of the floor area of the uppermost full story.

Street means a public or private street, road, or thoroughfare intended primarily to provide vehicular circulation and access to abutting property. Various types of streets are defined as follows:

(1) *Collector street* means a street whose principal function is to carry traffic between local or minor streets and major streets but may also provide direct access to abutting properties.



- (2) *Cul-de-sac* means a street that terminates in a vehicular turnaround.
- (3) *Local or minor street* means a street whose function is to provide access to abutting properties.
- (4) *Major thoroughfare* means a street that carries high volumes of traffic and serves as a main avenue through or around the City. Major thoroughfares may also be referred to as major streets or arterial streets. For the purposes of this chapter, major thoroughfares shall include those streets designated as "state trunkline," "county primary," or "major street" on the most recently approved City of Ypsilanti Act 51 map (P.A. 1951).

Street line means a dividing line between a street and a lot, also known as the right-of-way line.

1360

Street, primary means the street to which a property is addressed; if a property has more than one address, then the primary street is the one that has the higher National Functional Classification (NFC); if the property has more than one address and the NFC levels are equal, then the primary street is the one that has more frontage.

Street, private means a street or road under private ownership which has been constructed for the purposes of providing access to adjoining property and which is normally open to the public so that persons other than the occupants of adjoining property may travel thereon, but which has not been accepted for maintenance by the City, county, state, or federal government.

1370

Street, public means a street or road, the right-of-way and improvements of which have been accepted for maintenance by the City, county, state or federal government.

Structure means anything constructed or erected in, on, over or below the ground. All buildings are structures, however, not all structures are buildings. Structures include, but are not limited to, principal and accessory buildings, tower, decks, fences, privacy screens, wall, antennae, swimming pools, and sign structures.

Structure, accessory. See "Accessory use, building, or structure."

1380

Subdivision plat means the division of a tract of land into two or more lots, building sites, or other divisions for the purpose of sale or building development, in accordance with the land division act, Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101 et seq., MSA 26.430(101) et seq.), as amended.

Substance abuse treatment facility means:

- (1) *Boarding.* Any facility providing substance abuse treatment or preventive or addictive counseling, including the dispensing of or distribution of drugs as part of the treatment, where individuals receiving the treatment live on the premises for a period of time, including overnight stays.
- (2) *Walk-in.* Any facility providing substance abuse treatment or preventive or addictive counseling, including the dispensing or distribution of drugs as part of the treatment plan, where no one resides on the premises overnight.

1390

Supportive Housing means a facility that provides housing for twenty-four (24) hours per day and supportive services designed to assist residents with improving daily living skills, securing employment, rehabilitation, or obtaining permanent, independent housing. Supportive housing is not intended for short-term, emergency housing and care, but rather longer periods ranging from a few months to a few years. Supportive housing is distinguished from a hospital or other health care environment, and facilities regulated by the State of Michigan as State licensed residential facilities. This definition shall not include fraternities, sororities, dormitories, adult foster care facilities, group homes, nursing homes, substance abuse treatment facilities, emergency shelters, individuals utilizing tenant-based or homeownership-based voucher funding through the U.S. Department of Housing and Urban Development, community correctional facilities, and housing for the rehabilitation of former occupants of correctional facilities.

1400

Supportive Services are services provided to residents of supportive housing for the purpose of facilitating the independence of residents, and may be provided on the premises, or off-site. Some examples are case management, medical or psychological counseling and supervision, child care, transportation, and job training.

Swale, biofiltration means shallow drainage ways with low-pitched side slopes that detain, evaporate, and/or infiltrate the runoff associated with a storm event. They are designed to remove silt and sediment-associated pollutants before discharging to storm sewers and to reduce volume if soils allow for infiltration. Swales may be rock-lined or vegetated.

1410

Swimming pool means any structure or container located either above or below grade designed to hold water to a depth of greater than two feet when filled, and intended for swimming, bathing, or aquatic recreation. A swimming

pool does not include plastic, canvas, or rubber portable pools temporarily erected upon the ground holding less than 300 gallons of water nor decorative pools with less than two feet of water depth.

T

Temporary use or building. See "Building, temporary" or "Use, temporary."

Theater means an enclosed building used for presenting performances or motion pictures which are observed by paying patrons from seats situated within the building.

Townhouse. See "Dwelling unit, single-family attached or townhouse."

1420

Toxic or hazardous waste means waste or a combination of waste and other discarded material including solid, liquid, semi-solid or contained gaseous material which because of its quantity, concentration, or physical, chemical, or infectious characteristics may cause or significantly contribute to the following if improperly treated, stored, transported, disposed of, or otherwise managed:

- (1) An increase in mortality;
- (2) An increase in serious irreversible illness;
- (3) Serious incapacitating, but reversible illness; or
- (4) Substantial present or potential hazard to human health or the environment.

1430

Tree means a self-supporting woody, deciduous or evergreen plant with a well-defined central stem which normally grows to a mature height of 15 feet or more in the county.

U

Use means the purpose for which land, lots, or building thereon is designed, arranged, or intended, or for which it is occupied, maintained, or leased.

Use, accessory. See "Accessory use, building, or structure."

Use, nonconforming. See "Nonconforming use."

1440

Use, permitted means a use which may be lawfully established in a particular district or districts provided it conforms with all requirements, regulations, and standards of such district.

Use, principal means the main use of land and/or buildings and the main purpose for which land and buildings exist.

Use, special. See "Special use."

Use, temporary means a use permitted to exist during a specified period of time under conditions and procedures as provided in this chapter.

1450

Use, unclassified means a use that is not specifically or implicitly addressed in this Chapter, often due to emerging technologies or omissions within this chapter. Such uses are so differentiated from uses or categories specified in this chapter that the standards of this chapter cannot be reasonably applied to them.

Use, Residential means a use classified as residential under the Building Code, generally including single-family residences, one- and two-family homes and group living. For the purposes of the Zoning Ordinance, this shall not include hotels or bed and breakfasts.

1460

Use, Non-residential means any use not classified as residential under the Building Code. For the purposes of the Zoning Ordinance, this includes hotels and bed and breakfasts.

V

Variance means a modification of the literal provisions of this chapter in accordance with the provisions of this chapter in cases where strict enforcement would cause undue hardship as a result of special circumstances affecting

an individual property that do not generally affect other properties in the same zoning district.

Vehicle storage facility means a building or portion thereof or an outdoor controlled-access compound, designed or used exclusively for long-term or seasonal storage of four or more automobiles, trucks, tractors, boats, mobile homes, recreational vehicles and trailers, and other types of vehicles. A vehicle storage facility may be combined with a self-storage facility.

Vehicle, Commercial means a truck or motor vehicle with cab and chassis and with a stake, rack, body, dump body, wrecker body, tanker body or any other body, the mounted height of which exceeds the height of the cab roof more than eight inches. Any truck or motor vehicle which has a commercial license plate and is designed to accommodate a body length in excess of nine feet. Commercial vehicles shall not include motor homes or recreational vehicles, but shall include construction equipment such as backhoes, power shovels, bulldozers, earth moving equipment, semi trucks, tractors and trailers.

Vehicle, Inoperable means any motor vehicle which, by reason of dismantling, disrepair, or other causes, is incapable of being propelled under its own power or any motor vehicle which meets any of the three (3) of the following requirements: Has any missing or broken windows; Has a missing hood.; Has a missing door.; Has missing or flat tires; Has missing trunk lid; Has a missing engine, or any substantial part thereof; Is inoperable because of missing or defective steering mechanism; Does not have any or all of the following: operable head lights, parking lights, clearance lights, tail lights, stop lights.

Vehicle, Motor means any wheeled vehicle which is self-propelled or intended to be self-propelled.

Vehicle, Recreational means a boat, snowmobile, off-road vehicle, camper travel trailer, motor home, pick-up camper, trailer which is designed for private recreational or recreational travel use. Any trailer which is principally used for transporting any of the above shall also be considered a recreational vehicle.

Vehicle, Unlicensed means any motor vehicle that does not have lawfully affixed to it a valid, unexpired license plate.

Vehicle, Untitled means any motor vehicle which has not been titled in accordance with the law.

Vegetated roof means the roof of a building that is partially or completely covered with vegetation, including for food production, and a growing medium, planted over a waterproofing membrane.

Veterinary clinic or hospital means a place for the care, diagnosis, and treatment of sick or injured animals, or those in need of medical or minor surgical attention. A veterinary clinic or hospital may include customary pens, animal runs, or cages enclosed within the walls of the clinic building.


W

Warehouse means an enclosed building used for the storage of commercial goods or wares which are intended for sale, transfer or processing.

Y

Yard means an open space between a building and the adjoining lot lines, unoccupied and unobstructed by any portion of a structure from the ground upward, except as otherwise provided in this chapter. The minimum required setback is the minimum depth of a front, rear, or side yard necessary to conform to the required yard setback provision of this chapter.

- (1) **Yard, front** means a yard extending across the front of a lot and being the minimum horizontal distance between the street line and the principal building or any projections thereof other than projection of uncovered steps, unenclosed balconies or unenclosed porches.
- (2) **Yard, rear** means a yard extending across the full width of the lot between the rear lot line and the nearest point of the principal building. On all lots, the rear yard shall be opposite the front yard.
- (3) **Yard, side** means a yard between a principal building and the side lot line, extending from the front yard to the rear yard, the width of which shall be the horizontal distance from the nearest point of the side lot line to the nearest point on the principal building.
- (4) **Yard, street side** means a yard between the principal building and the street side lot line on a corner lot, extending from the front yard rearward to the rear lot line, the width of which shall be the horizontal distance of the side lot line to the nearest point on the principal building.



Z

Zoning Map means the Zoning Map of the City together with all amendments subsequently adopted.

Secs. 122-204 – 299. Reserved.

Article III: Development Procedures and Administration

Division 1: Generally.

Sec. 122-300. Eligibility for zoning authorization.

- (a) If a person, firm, or corporation is delinquent in paying a civil fine, costs, or a justice system assessment imposed by the City of Ypsilanti's Administrative Hearings Bureau, that person is not eligible to apply for any zoning authorization under the City of Ypsilanti's Zoning Ordinance, including but not limited to, the following zoning authorizations:
- (1) A zoning amendment under Article III "Development Procedures and Administration," Division 4 "Amendments."
 - (2) A variance under Article III "Development Procedures and Administration," Division 5 "Variances and Appeals."
 - (3) Site plan review or amendment to an approved site plan under Article III "Development Procedures and Administration," Division 2 "Permits," Subdivision I, "Zoning Compliance."
 - (4) A special use permit or to amend a special land use under Article III "Development Procedures and Administration," Division 2 "Permits," Subdivision II, "Special Land Uses."
 - (5) A planned unit development under Article VII, Division 1 "Planned Unit Development."
 - (6) A site condominium subdivision project under Article VII, Division 2 "Site Condominium Subdivisions."
 - (7) An application for occupation, construction or substantial improvement in a floodplain under Article VII, Division 3 "Flood Damage Prevention."
- (b) Subsection (a) above does not apply if:
- (1) If the applicant for zoning authorization became the owner of the property by foreclosure or by taking a deed in lieu of foreclosure and is one (1) of the following:
 - (i) A government-sponsored enterprise. As used in this subsection, "government-sponsored enterprise" means the term as defined in 2 USC 622(8), or the Michigan state housing development authority created under the state housing development authority act of 1966, 1966 PA 346, MCL 125.1401 to 125.1499c.
 - (ii) A financial institution. As used in this subsection, "financial institution" means that term as defined in section 4(c) of the Michigan strategic fund act, 1984 PA 270, MCL 125.2004.
 - (iii) A mortgage servicer. As used in this subsection, "mortgage servicer" means that term as defined in section 1a of the mortgage brokers, lenders, and servicers licensing act, 1987 PA 173, MCL 445.1651a, that is subject to the mortgage brokers, lenders, and servicers licensing act, 1987 PA 173, MCL 445.1651 to 445.1684.
 - (iv) A credit union service organization that is organized under the laws of this state or the United States.
 - (2) If the application for zoning authorization will correct, in whole or in part, the blight violation that was the subject of the delinquent payment referred to in subsection (a).

Sec. 122-301. Administrative liability.

No officer, agent, employee, or member of the City Council, Planning Commission, or Zoning Board of Appeals shall render themselves personally liable for any damage that may accrue to any person as the result of any act, decision, or other consequence or occurrence arising out of the discharge of their duties and responsibilities pursuant to this chapter.

Sec. 122-302. Vested right.

It is hereby expressly declared that nothing in this chapter shall be interpreted or construed to give or grant to any person, firm or corporation any vested right, license, or privilege in the continuation of any particular use, zoning classification or any permissible activities therein. Such provisions are hereby declared to be subject to subsequent amendment, change or modification as may be necessary for the preservation or protection of public health, safety and welfare.

Sec. 122-303. Fees.

Fees for the review of applications and inspections, where required by this Chapter, shall be established and may be amended by resolution of City Council. Such fees are nonrefundable unless noted otherwise.

Sec. 122-304. Reserved.

Division 2: Permits.

Subdivision I: Zoning Compliance.

Sec. 122-305. Purpose.

- (a) The purposes of development review are as follows:
- (1) To determine compliance with the provisions of this chapter;
 - (2) To promote the orderly development of the City, to prevent the depreciation of land values through uses or structures which do not give proper attention to site or area protection; and
 - (3) To provide consultation and cooperation between the applicant and the City in order to accomplish the developer's objectives in harmony with the spirit and intent of this chapter.
- (b) The development review procedures and standards in this article are intended to provide a consistent and uniform method of review of proposed development plans. The application of these regulations, consistent with the Master Plan, will ensure orderly and favorable development and redevelopment within the City.

Sec. 122-306. Application procedure; contents.

- (a) An application for development review shall be made to the City Planner along with a fee as required by the City Council. The application shall, at a minimum, contain the following information:
- (1) The applicant's name, address and phone number.
 - (2) Proof that the applicant is the owner of the property or has a legal or financial interest in the property, such as a purchase agreement, or a signed, notarized statement from the property owner authorizing such application.
 - (3) The name, address and phone number of the owner of record if different from the applicant.
 - (4) The address and/or parcel number of the property.
 - (5) Brief project description, including number of structures and dwelling units, square footage of each building, number of parking spaces, estimated number of employees, and any unique features of the site or proposed development.
 - (6) Area of the parcel in acres, excluding street rights-of-way.
- (b) The City Planner shall review all application materials. If such materials are incomplete, they shall be returned to the applicant.

Sec. 122-307. Levels of Review.

- (a) Review is required for the activities or uses as listed in the table below. Applications submitted for review may be required to submit a sketch or site plan, as well as additional documentation. The City Planner may defer approval of any application to the Planning Commission. The Planning Commission or City Council shall have the authority to review and to approve, approve with conditions, or deny applications as provided in this Ordinance, when an "X" is in the table below. Any decision made by the City Council shall be based upon recommendation by the Planning Commission.
- (b) Planning Commission review. The Planning Commission in its entirety may review and approve site plans, or the Planning Commission may designate a subcommittee of no less than three of its members to review and/or approve site plans.

(c) Levels of Review Table				
Activities or uses	Type of plan required	City Planner	Planning Commission	City Council
(1) New Construction				
Single or two-family dwelling on individual lot	Sketch	X		
Accessory dwelling unit or accessory building to single or two-family use	Sketch	X		
Essential services, electrical substations, private utilities and similar uses	Site	X		
Non-residential	Site	Review & recommend to PC	X	
Special Land Use or Limited Building Type	Site or Limited Site, at Planner discretion	Review & recommend to PC	X	
Subdivisions (both site condominiums & plats)	Site	Review & recommend to PC	Review & Recommend to City Council	X
Rezoning, including conditional rezonings	Site	Review & recommend to PC	Review & Recommend to City Council	X
Planned Unit Development (PUDs)	Site	Review & recommend to PC	Review & Recommend to City Council	X
(2) Expansion / Modification to Existing Buildings				
Single or two family dwelling on individual lot	Sketch	X		
Accessory dwelling unit	Sketch	X		

(c) Levels of Review Table				
Activities or uses	Type of plan required	City Planner	Planning Commission	City Council
Where no requests for exceptions as allowed by this Chapter are made, and the proposed expansion/modification does not exceed 25% of the existing total gross floor area of the building (up to a maximum of 5,000 square feet), or 500 square feet, whichever is greater.	Site	X		
Where a building encroaches into the required setback from a planned easement; or area of expansion exceeds the threshold permitted for administrative review; or when waivers are requested.	Site	Review & recommend to PC	X	
Expansion or intensification of a Special Land Use	Site	Review & recommend to PC	X	
(3) Change in Use				
Temporary uses, buildings & structures	Sketch	X		
Change in use to a new Special Land Use with <i>no</i> requests for waivers as provided in this chapter and no proposed changes to the site or building footprint	Limited Site	Review & recommend to PC	X	
Change to an equally or less intense use, as determined by the City Planner, that does not involve substantial change in parking, traffic flow, hours of operation, public services, effluent discharge, or substantial alteration of the physical character of the site	Sketch	X		
Change to a more intense use, as determined by the City Planner, that may involve substantial change in parking, traffic flow, hours of operation, public services, effluent discharge, or substantial alteration of the physical character of the site	Site	Review & recommend to PC	X	
(4) Accessory Structures & Site Improvements				

(c) Levels of Review Table				
Activities or uses	Type of plan required	City Planner	Planning Commission	City Council
Accessory buildings, structures, and off-street parking for single and two-family dwelling units on individual lots	Sketch	X		
Accessory buildings less than 250 square feet	Sketch	X		
Accessory buildings, except when accessory to single and two-family dwellings, 250 square feet or more	Site	X		
New parking lot and/or garage, except when accessory to single and two-family dwellings, with no requests for waivers allowed in this Chapter	Site	X		
Expand or modify an existing parking lot that results in drainage alterations, changes in circulation patterns or access, or addition or replacement of base or subgrade, with no requests for waivers allowed in this Chapter	Site	X		
New parking lot and/or garage, or expand/modify existing parking lot, with requests for waivers allowed in this Chapter	Site	Review & recommend to PC	X	
(5) Other uses or site improvements				
Community garden as principal use	Sketch	X		
Infrastructure and paving improvements including sidewalks, bicycle facilities, and pathways on private property in excess of 500 sq ft, excluding parking areas and driveways; with no requests for waivers allowed in this chapter	Sketch	X		
Construction, relocation or erection of structures including signs, screening walls, trash receptacles, fences, walls, lights, poles, cooling/heating or other mechanical equipment	Sketch	X		
Swimming pools	Sketch	X		

Sec. 122-308. Sketch Plans.

A sketch plan may be submitted for administrative reviews or as noted elsewhere in this Ordinance. A sketch plan is a scaled drawing based on a legal survey containing less information than a site plan, drawn in compliance with this Ordinance but not required to be prepared by a licensed professional. Sketch plans shall contain the following information:

- (a) Address of project, scale, north arrow, date of original drawing, and date of any revisions.
- (b) Name, address and phone number of the site owner, developer, and/or plan designer.
- 1630 (c) The area of the site in square feet or acres, excluding all existing and proposed rights-of-way.
- (d) Location and setbacks of existing and proposed buildings; their intended use; the length, width and height of each building; and the square footage of each building. The location and dimensions of any open air uses shall also be provided, such as recreational fields, outdoor cafes, or open air sales areas.
- (e) Parking areas and access drives, showing the number and size of spaces, aisles, loading areas, and barrier-free access ramps, and type of surfacing.
- (f) Landscape plan showing type, size, and location of all plant material. Existing vegetation which is to be retained on the site shall be illustrated.
- (g) Location of all proposed and existing accessory structures, including fences or walls, outdoor lighting fixtures, outdoor communication devices, flagpoles, storage sheds, transformers, dumpsters or trash removal areas, and signs. Also show the location of all sidewalks or pathways, fire hydrants, and utility poles.
- 1640 (h) Location of all outdoor storage areas for materials and the manner in which materials shall be screened and/or covered.
- (i) Notation of any variances or special use permits which are required, any legal nonconforming uses or structures, and any state or federal permits which have been secured or may be necessary to secure.

Sec. 122-309. Site Plans.

Each site plan submitted for review under this chapter shall be drawn at a minimum scale of one inch equals 200 feet and shall contain the following information:

- (a) Name of development, scale, north arrow, date of original drawing and any revisions, and general location map showing major thoroughfares and site location.
- 1650 (b) Name, address and phone number of the site owner, developer and plan designer, and the professional seal of the designer.
- (c) The area of the site in square feet and acres, excluding all existing and proposed rights-of-way. Property lines, dimensions, and building setback distances and dimensions of all structures and lot lines within 50 feet of the site shall also be indicated. If the parcel is a part of a larger parcel, boundaries of the total land holding shall be shown.
- (d) Existing zoning of the site and all adjacent properties.
- (e) Direction of stormwater drainage, ground elevations of all existing buildings, drives and parking lots, and any unusual surface conditions shall be provided. Indicate any areas located within floodplains.
- 1660 (f) Location of existing and proposed buildings; their intended use; the length, width and height of each building; and the square footage of each building. The location and dimensions of any open air uses shall also be provided, such as recreational fields, outdoor cafes, or open air sales areas.
- (g) Location of abutting streets, existing and proposed rights-of-way, service drives, curb cuts, and access easements serving the site, as well as driveways opposite the site and all driveways within 100 feet of the site. The centerline of road rights-of-way shall be shown.
- (h) Proposed parking areas and access drives, showing the number and size of spaces, aisles, loading areas, and handicapped access ramps. Also, the proposed method of surfacing such areas shall be noted.
- (i) Building floor plans and architectural wall elevations. The height of all buildings or structures shall be indicated.
- 1670 (j) Landscape plan in accordance with **Article VI, Division 3 "Landscaping and Screening,"** which indicates type and size of all plant material, including all areas to be sod or seeded for grass. Existing vegetation which is to be retained on the site shall be illustrated.
- (k) Location of all proposed accessory structures, including fences or walls; outdoor lighting fixtures, including photometric study to demonstrate compliance with **§122-609**, outdoor communication devices, flagpoles, storage sheds, transformers, dumpsters or trash removal enclosures, and signs. Also show the location of all sidewalks or pathways, fire hydrants, existing and proposed utility poles, utility easements, and drainways.
- (l) Location of all outdoor storage areas for materials and the manner in which materials shall be screened and/or covered.
- 1680 (m) Location and specifications for any existing or proposed above or below ground storage facilities for any chemicals, salts, flammable materials, or hazardous materials as well as any containment structures or clear zones required by this chapter or other state or federal agencies.
- (n) If phased construction is to be used, each phase must be noted and each phase must stand on its own.
- (o) Notation of any variances or special use permits which are required, any legal nonconforming uses or structures, and any state or federal permits which have been secured or may be necessary to secure.
- (p) Locations of all planned easements for non-motorized pathways in the City of Ypsilanti's Non-Motorized Plan, a 50 to 100 foot conservation and /or access easement along any Huron River frontage, and any planned road

easement expansions approved by City Council.

- (q) For proposals in the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, the following information shall be provided:
- (1) The building type;
 - (2) For proposed development of one acre or more, a circulation plan shall be submitted that identifies potential cross-and joint-access to adjacent parcels and the existing block layout. All contiguous lots shall be considered to be part of a block for this purpose. Pedestrian accommodations and alternative transportation modes shall be reflected in the submitted circulation plan, as required by §122-672.
- (r) Other data which the Planning Commission, City Planner, or consulting engineer may deem reasonably necessary for adequate review.
- (s) The approving body, Planning Commission or City Planner, may grant waivers of data requirements when specific data is deemed unnecessary in determining compliance of a site plan with the regulations or standards of this chapter.
- (t) In cases when a Special Use permit is being applied for, the City Planner may grant waivers of the standard site plan data requirements when specific data is deemed unnecessary in determining compliance of a site plan with the regulations or standards of this chapter. In no case shall less information be required for this Limited Site Plan than for a Sketch Plan. The submitted drawings shall be referred to as a Limited Site Plan.

Sec. 122-310. Review procedure and authorization.

All applications required under this article shall be subject to review as follows:

- (a) **Pre-application conference required for new construction.** For any new construction, the applicant/property owner must attend a pre-application conference to be coordinated by the City Planner. This meeting may include the Building Official, City Attorney, City Engineer, Fire Inspector, Police Chief, City Manager, Economic Development Official, Planning Commission member(s) and City Council member(s) and any other government official deemed applicable. The City Planner may consult with any of the above offices and share input at the conference. The applicant shall not be bound by the plan reviewed in a pre-application conference, nor shall the any approving authority be bound by any such conference.
- (b) **Distribution of plans.** Upon submission of all required application materials, the site plan proposal shall, when applicable, be placed on the Planning Commission agenda for review. Before the Planning Commission meeting, the site plan and application shall be reviewed for comment by the City Department of Community and Economic Development and any other City officials deemed necessary. The plan may also be submitted to the City Engineer or City Attorney for review.
- (c) **Authorization.** The City Planner or the Planning Commission, as applicable, shall have the power to approve, approve subject to conditions, or deny any site plan submitted to it under this chapter. The Planning Commission may also table consideration of a site plan until a later meeting. The applicant shall be advised of any action in writing. A building permit shall not be issued until a site plan has been approved as required in this chapter.
- (d) **Review period.** The City Planner or Planning Commission shall render a decision on a site plan within 65 days of its initial review of the site plan, unless an extension of time is agreed to by the City Planner or Planning Commission and the applicant.
- (e) **Review standards.** The City Planner or Planning Commission shall review each development proposal according to the standards for site plan review as contained in §122-311 and any other applicable regulations of this chapter. In addition, the City Planner or Planning Commission shall consider the findings and recommendations of the Department of Community and Economic Development, and is empowered to seek the review and recommendation of appropriate county, state or federal agencies, or other professionals, consultants, or agencies deemed necessary to assist in the review.
- (f) **Signature of approval.** Upon approval of a development proposal, three paper copies of the plan shall be signed and dated by the City Planner or the chair of the Planning Commission. If approval is subject to conditions, such conditions shall also be written on each of the site plans. One paper copy of the plan shall be retained by the applicant, one paper copy of the plan shall be retained by the City Planner's office, and one paper and one electronic copy of the plan shall be submitted to the Building Department as part of the building permit review process.
- (g) **Effect of approval.** Approval of a development proposal authorizes issuance of a certificate of zoning compliance and issuance of a building permit, provided all other requirements for a building permit have been met. In the case of uses without buildings or structures, approval of a final site plan authorizes issuance of a certificate of zoning compliance and issuance of a certificate of occupancy, provided all other requirements for such certificates have been met.
- (h) **Expiration of approval.** Approval of a development proposal shall expire and be of no effect unless a building permit has been issued within one (1) year of the date of the approval. Approval of a development proposal

shall expire and be of no effect two years following the date of approval unless construction has begun on the property and is diligently pursued to completion in conformance with the approved site plan.

Sec. 122-311. Standards for site plan and sketch plan review.

Plans shall be reviewed for compliance with the following general standards:

- (a) The applicant is eligible to legally apply, and all required information has been provided.
- (b) The development proposal conforms with all the provisions and requirements, as well as the spirit and intent of this chapter and the Master Plan. The proposed development will meet all the regulations of the zoning district in which it is located.
- (c) All elements of the site or sketch plan is harmoniously and efficiently organized in relation to the character of the proposed use, the size and type of lot, the size and type of buildings, and the character of the adjoining property. The site shall be so developed as not to impede the normal and orderly development or improvement of surrounding property for uses permitted in this chapter.
- (d) With respect to vehicular and pedestrian circulation on the site, including walkways, interior drives, and parking; circulation shall to the extent possible create potential cross-and joint-access to adjacent parcels and the existing block layout. Special attention shall be given to the location, number and spacing of ingress and egress points; general interior circulation including turnaround areas; adequate provisions for delivery of services (trash removal, school buses, mail and parcel delivery); separation of pedestrian and vehicular traffic; avoidance of building corners next to access drives; identification of addresses; storage of plowed snow; and arrangement of parking areas that are safe and convenient, and insofar as practicable, do not detract from the design of the proposed buildings and structures, neighboring properties, pedestrian and bicyclist safety, access to transit and flow of traffic on adjacent streets. All buildings or groups of buildings shall be so arranged as to permit adequate access by emergency vehicles as required by the City building code.
- (e) Streets are designed in context with the urban form and continue the established pattern of the surrounding area.
- (f) Adequate services and utilities including sanitary sewers shall be available or provided, with sufficient capacity to properly serve the development. Appropriate measures will be taken to ensure that site drainage will not adversely affect adjoining properties or the capacity of the public storm drainage system, or nearby bodies of water. Provisions shall be made to accommodate stormwater and prevent soil erosion. All stormwater management facilities, including but not limited to storm sewers and detention/retention facilities, shall be designed in accordance with the "Rules of the Washtenaw County Water Resources Commissioner," together with any special provisions established by the City.
- (g) Natural resources will be protected to the maximum feasible extent. The proposed development will not cause soil erosion or sedimentation problems, and will respect floodways or floodplains on or in the vicinity of the subject property.
- (h) The plan shall provide reasonable visual and sound privacy for all dwelling units on or adjacent to the property. Fences, walks, barriers, and landscaping shall be used, as appropriate, for protection and enhancement of the property. All outdoor storage of materials, loading and unloading areas, and refuse containers shall be screened or located so as not to be a nuisance. Outdoor lighting shall be shielded so as to not adversely affect neighboring properties or traffic on adjacent streets.
- (i) Separate phases of development shall be in logical sequence, and each phase shall stand alone so that no one phase will depend upon a subsequent phase for adequate access, public utility services, drainage, or other improvements.
- (j) Plans shall conform to all applicable requirements of state and federal statutes, including health and pollution laws, fire or explosion hazards, toxic and hazardous materials, fair housing, and barrier-free requirements. Site plan approval may be conditioned on the applicant receiving necessary county, state, or federal permits before a local building permit or occupancy permit is granted.
- (k) An objective of plan review shall be to protect and promote public health, safety, sustainability and general welfare. It is also the intent of plan review to improve the quality of existing developments as they are expanded, contracted, or redeveloped in keeping with sound site development standards of this chapter and the City master plan.

Sec. 122-312. Issuance of building permit.

The Building Department shall, upon receipt of notice of approval from the Planning Commission or City Planner and upon application by the applicant, issue a building permit provided all other applicable City regulations have been met.

Sec. 122-313. Amendment of approved site plan.

- (a) A site plan may be amended upon application and in accordance with the procedures and requirements provided in [§122-306](#).

- 1800 (b) Minor changes to a site plan may be made without following the procedures of §122-306 at the discretion of the City Planner. The original approving body shall have the authority to determine if a proposed change is minor or major and if such change requires an amendment to an approved site plan. A sketch plan, meeting the requirements of §122-308 may be allowed by the original approving body for submission for review for a minor or major revision.
- (c) Major revisions would include, but not be limited to, increases in scope or density of use, land area, or building size; the addition of uses not authorized by the original site plan approval; the rearrangement or relocation of buildings or structures; changes in the character or function of drives, parking areas, and landscaping; or changes in the concept of the development.
- 1810 (d) A record of such determinations and reasons for allowing any minor amendment shall be recorded in writing. In the case of minor changes to an approved site plan, two paper copies and one electronic copy of the revised site plan or sketch plan drawing shall be submitted by the applicant showing such minor changes for purposes of City record.

Sec. 122-314. Modification of plan during construction.

All site improvements shall conform to the approved site plan. If the applicant makes any changes during construction in the development in relation to the approved site plan, such changes shall be made at the applicant's risk, without any assurance that the Planning Commission or City Planner will approve the changes. It shall be the responsibility of the applicant to notify the City Building Department and the City Planner of any changes. The Building Department, the City Planner, or the Planning Commission, whichever is applicable, may require the applicant to correct the changes so as to conform to the approved site plan.

1820 Sec. 122-315. As-built drawings.

Upon completion of the installation of required improvements as shown on an approved site plan, the property owner shall submit to the Building Department an electronic and paper "as-built" site plan, certified by an engineer or architect, at least one week prior to the anticipated occupancy of any building. A Certificate of Occupancy shall be withheld by the Building Department in any case where the site plan and major conditions as approved by the Planning Commission or City Planner have not been complied with and a performance guarantee has not been issued for incomplete improvements in accordance with §122-317.

Sec. 122-316. Phasing of development.

- 1830 (a) The applicant may divide the proposed development into two or more phases. In such case, the site plan shall show the entire property involved and shall clearly indicate the location, size, and character of each phase. However, complete site plans for all phases of a project need not be provided at once. Subsequent site plans may be submitted for review and approval for each phase as the project proceeds.
- (b) Each phase of a project shall stand on its own. No phase shall rely on the completion of any subsequent phases of the project for parking, utilities, landscaping, or any other element required by this chapter.

Sec. 122-317. Performance guarantee.

- 1840 (a) **Purpose.** To ensure faithful compliance with the provisions of this chapter and any conditions imposed thereunder, a performance guarantee may be required by City staff, the Planning Commission, or when appropriate the City Council to be deposited with the City. Improvements for which a performance guarantee may be required include, but are not limited to, landscaping, berms, screening, lighting, surfacing of drives, parking, traffic control devices, water or sewer line expansions, sidewalks, drainage, and other improvements.
- (b) **General requirements.** A performance guarantee may be in the form of a bond, irrevocable bank letter of credit, cash deposit, or other form of security. Such guarantee shall be provided to the City clerk, and shall be provided any time after a site plan has been approved.
- (c) **Amount.** The amount of the performance guarantee shall be 100% of the cost of the improvements associated with the performance guarantee. Accordingly, the applicant shall provide an itemized cost estimate of the improvements, and such estimate shall be verified by the Building Department. The form of the guarantee shall be approved by the City attorney.
- 1850 (d) **Failure to complete improvements.** If the applicant should fail to provide any of the site improvements according to the approved site plans within the time period specified in the guarantee, the performance guarantee shall be forfeited. The City shall rebate a proportional share of cash deposits only when requested by the depositor, based on the percent of improvements completed, as attested to by the depositor and verified by the Building Department. In cases where the provisions of this article have not been met, the amount of the aforementioned performance guarantee shall be used by the City to complete the required improvements and the balance, if any, shall be returned to the applicant.

Sec. 122-318. Record of approval.

An approved site plan shall become part of the record of approval, and subsequent action relating to a site in question shall be consistent with the approved site plan, unless the City Planner, or Planning Commission, as applicable, agrees to such changes as provided in this article. Any violation of the provisions of this article, including any improvement not in conformance with the approved final site plan, shall be deemed a violation of this chapter and shall be subject to all penalties therein.

1860

Sec. 122-319. Reserved.

DRAFT 03-16-2017

Subdivision II: Special Land Uses.

Sec. 122-320. Statement of intent.

- 1870 (a) The formulation and execution of this chapter is based upon the division of the City into districts, within each of which certain specified, mutually compatible uses are permitted by right, and the bulk and location of buildings and structures are substantially uniform. It is recognized, however, that there are certain uses which, because of their unique characteristics, cannot be properly classified in any particular district without special consideration. Such uses are essential or desirable for the welfare of the community and are essentially appropriate and not incompatible with the uses permitted by right in a zoning district; but not at every location therein, or without restrictions or conditions being imposed by reason of special problems presented by the use or its particular location in relation to neighboring properties.
- (b) This article requires special approval of such uses. The procedures and standards in this article are intended to provide a consistent and uniform method for review of proposed plans for special land uses.

Sec. 122-321. Authority to grant permits.

The City Planning Commission shall have the authority to approve special uses and to attach conditions to any approved special use. Only those uses specifically listed as special uses in this chapter shall be considered for special use review and approval, except as provided for unclassified uses in §122-431(c).

Sec. 122-322. Application; contents.

- 1880 (a) An application for a special use permit shall be made by filing an application form, containing the required information, and fee with the City Planner's office. The fee shall be set by resolution of the City Council. No part of the fee shall be returnable to the applicant. An application for a special use permit shall contain the following information:
- (1) The applicant's name, address, and telephone number; and the names and addresses of all record owners and proof of ownership.
 - (2) The applicant's interest in the property and, if not the fee simple owner, a signed authorization from the owner for the application.
 - (3) Legal description and address of the property.
 - (4) Reference to the section of this chapter under which the special land use permit is sought.
 - (5) A description of the proposed use of the property.
 - 1890 (6) A site plan, which shall include all of the information required by this chapter in §122-309. For special land uses to occupy an existing building with no building additions, the City Planner may allow a limited site plan drawn in accordance with §122-309(t).
- (b) A public hearing by the Planning Commission shall be scheduled for within 65 days of the filing date of an application for a special use permit. The applicant or designated representative shall be present at the public hearing and any other scheduled review meetings on the proposal. Otherwise, consideration of the proposal may be tabled due to lack of representation.

Sec. 122-323. Public hearing.

- 1900 (a) Notification requirements. A notice of a public hearing shall be published in a newspaper of general circulation in the City and shall be sent by mail or personal delivery to the owners of property for which approval is being considered, to all persons to whom real property is assessed within 300 feet of the boundary of the property in question, and to the occupants of all structures within 300 feet. The notice shall be given not less than 15 days before the date of the public hearing. If the name of an occupant is not known, the term "occupant" may be used in making notification. Notification need not be given to more than one occupant of a structure, except if a structure contains more than one dwelling unit or spatial area owned or leased by different individuals, partnerships, businesses, or organizations, one occupant of each unit or spatial area shall receive notice. In case of a single structure containing more than four dwelling units or other distinct spatial areas owned or leased by different individuals, partnerships, businesses, or organization, notice may be given to the manager or owner of the structure who shall be requested to post the notice at the primary entrance to the structure.
- 1910 (b) Contents of notification. The notice shall include the following:
- (1) Description of the nature of the special use request.
 - (2) A legal description or address of the property which is the subject of the special use request.
 - (3) Statement of when and where the public hearing will be held.
 - (4) Statement of when and where comments will be received concerning the request.

Sec. 122-324. Standards for reviewing special use requests.

- (a) Following the public hearing, the Planning Commission shall review the application for the special land use proposal, together with the public hearing findings and any reports or recommendations of the City Planner, Department of Community and Economic Development, City attorney, City building inspector, or other reviewing agencies.
- (b) Approval of a special land use permit shall be based on the determination that the following standards are met:
- (1) The proposed use conforms with all the provisions and requirements of this chapter, including site plan or sketch plan review standards, as applicable, and the applicable site development standards for the specific use, as well as the spirit and intent of this chapter and the Master Plan. The location, scale, and intensity of the proposed use shall be compatible with adjacent uses and the zoning of the land. Height, location and size of buildings shall be compatible with uses and buildings on adjacent properties. The intensity of the proposed use, such as volume, frequency and times of operation, and its compatibility shall be considered. If nonconformities are present, all reasonable effort has been made to eliminate them.
 - (2) The proposed use shall promote the use of land in a socially and economically sustainable manner and shall not be detrimental, hazardous, or disturbing to existing or future neighboring uses, persons, property or public welfare. Noise, odor, smoke and potential contamination of air, soil and water and its potential effect on neighboring uses, persons and property, as well as public welfare, shall be considered.
 - (3) The proposed special land use shall be designed, constructed, operated and maintained to assure long-term compatibility with surrounding land uses. Consideration shall be given to the placement, bulk, and height of structures; materials used in construction; location and screening of parking areas, driveways, outdoor storage areas, outdoor activity areas, and mechanical equipment; nature of landscaping and fencing; and hours of operation.
 - (4) The proposed special land use shall not present unreasonable adverse impacts on the transportation system. Consideration shall be given to the estimated pedestrian, bicycle and vehicular traffic generated by such use, access to transit, proximity to major thoroughfares, proximity to intersections, required vehicular turning movements, and provisions for pedestrian and bicycle traffic.
 - (5) The proposed use shall not create additional requirements at public cost for public facilities and services that will be detrimental to the economic sustainability of the community.
 - (6) Within the MD district, the proposed special land use will help to allow residents to access everyday needs by foot, if a similar service is not currently provided within a quarter mile walking distance.

Sec. 122-325. Planning Commission action.

The Planning Commission must approve, approve with conditions, or deny a special use permit application. The Planning Commission's decision, the basis for the decision, and all conditions imposed, must be described in a written statement which must be made a part of the record of the meeting.

Sec. 122-326. Conditions of approval.

- (a) Reasonable conditions may be required in conjunction with an approval. The conditions may include conditions necessary to ensure that public services and facilities affected by a proposed land use or activity will be capable of accommodating increased service and facility loads caused by the land use or activity, to conserve natural resources and energy, to ensure compatibility with adjacent uses of land, and to promote the use of land in a socially and economically desirable manner. Conditions imposed must do all of the following:
- (1) Be designed to protect natural resources, the health, safety, and welfare, as well as the social and economic well-being.
 - (2) Be related to the valid exercise of police power and purposes which are affected by the proposed use or activity.
 - (3) Be necessary to meet the intent and purposes of this chapter, be related to standards established in this chapter, and be necessary to ensure compliance with those standards.
- (b) Failure by an applicant to comply with any such conditions is considered a violation of this chapter and grounds for Special Use Permit revocation. Conditions of approval must remain unchanged except upon mutual consent of the City Planning Commission and the landowner. Any such changes must be recorded in the minutes of the City Planning Commission meeting at which the action occurred.

Sec. 122-327. Duration of special use approval.

Once a special use is established, Special Use Permits run with the land, and cannot be issued for specified periods. Special Use Permits may be revoked by the Planning Commission in accordance with [§122-329](#).

Sec. 122-328. Amendments to special land uses.

1970 When an application is received to expand the use, change the traffic pattern, or otherwise alter elements of a special land use, the application is subject to the same procedures followed for an original approval of special land use.

Sec. 122-329. Revocation of special land use approval.

Approval of a special land use permit may be revoked by the Planning Commission if construction is not in conformance with the approved plans, or if compliance with Special Use Permit conditions has not been consistently demonstrated. In such case, the issue must be placed on the agenda of the Planning Commission for consideration. Written notice must be given to the applicant not less than ten days prior to the meeting. The applicant must be given the opportunity to present information to the Planning Commission and answer questions. The Planning Commission may revoke the special use permit if it finds that a site plan or special use permit violation exists and has not been remedied prior to the meeting.

Sec. 122-330. Appeals.

1980 Any decision of the Planning Commission regarding a special use permit must not be appealed to the City Zoning Board of Appeals. Such appeals must be taken to the circuit court.

Sec. 122-331. Reapplication.

No application for a Special Use Permit which has been denied wholly or in part by the Planning Commission shall be resubmitted for a period of 365 days from the date of such denial, except on grounds of new evidence or proof of changed conditions found by the Planning Commission to be valid.

Secs. 122-332--122-334. Reserved.

Subdivision III: Temporary Use Permits.

Sec. 122-335. Requirements.

The Building Department, unless otherwise indicated, may issue temporary use permits for the uses listed below in any district, unless otherwise indicated, after determining that such uses will meet the standards under subsection (h) of this section and review standards for that specific use included in this section. A second temporary use permit may be issued by the Building Department at the end of such time limit for good cause shown. A third temporary use permit may only be authorized by the Planning Commission, following the noticing procedures outlined in §122-323. The Building Department, at its discretion, may refer any request for a temporary use permit to the Planning Commission.

(a) **Temporary dwellings.** An individual mobile home, private garage, basement, or other temporary structure may be used as temporary living quarters for up to 60 days while a dwelling or structure is being constructed on the same premises. A temporary use permit must be issued prior to any such use.

(b) **Construction buildings.** Temporary buildings for uses incidental to construction work may be authorized for a period of up to 12 months. Such buildings shall be removed within 15 days after completion or abandonment of construction work.

(c) **Signs and supplies.** The storage of building supplies and machinery; temporary storage buildings; the assembly of materials and customary trade; and contractor, architect, and identification signs in connection with a construction project may be authorized by the Building Department for a period of up to 12 months. All signs shall meet the provisions under Article VI, Division 5, as well as district-specific regulations.

(d) **Seasonal uses.** Seasonal temporary uses or unusual, nonrecurrent temporary uses, and associated signs may be authorized for up to 30 days. All signs shall meet the provisions under Article VI, Division 5, as well as district-specific regulations.

(e) **Temporary mobile food establishments.** The City Planner may authorize a temporary special permit to temporary mobile food establishments for no more than 200 consecutive days in one calendar year, with the following standards:

(1) Permits expire on December 31st of each year.

(2) Temporary mobile food establishments are only permitted in Center, Parks, General Corridor, Neighborhood Corridor, and Health and Human Services zoning districts.

(3) The area occupied by temporary mobile food establishments and their accessory materials may not occupy more than 20% of the required parking spaces for the principal/permanent use(s) of the site. This requirement does not apply in Center or in Historic Corridor zoning districts.

(4) Evidence of approval or exemption from the Washtenaw County Health Department and/or the Michigan Department of Agriculture and Rural Development, as applicable, shall be provided.

(5) Sanitary facilities shall be provided if seating is provided. This requirement may be met via a temporary sanitary facility such as a port-a-john or via an agreement with a neighboring establishment with the same operating hours as the temporary food establishment.

(6) Operating hours shall be no later than 10pm Sunday through Thursday, and 11pm Friday and Saturday; nor any earlier than 7am on any day of the week.

(7) No outdoor amplified music, sound, or noise shall be permitted. Outdoor generators shall be identified on the sketch plan; no outdoor generators shall be permitted within 200 feet of a property that is not zoned Center, Parks, General Corridor, Neighborhood Corridor, or Health and Human Services zoning district.

(8) All outdoor lighting shall be down-directed and fully shielded.

(9) The temporary mobile food establishment and all accessory materials shall be located on a paved surface, or evidence submitted that placement on an unpaved surface will not increase stormwater runoff or pose an accessibility challenge for patrons who may use a mobility assistance device, such as a wheelchair or walker.

(10) A sketch plan of the proposed location shall be provided; location of any seating, waste containers, fuel storage, sanitary facilities, lighting, generators, or other accessory materials shall be shown.

(11) The standards in subsection (h) of this section also apply to temporary mobile food establishments.

(f) **Parking areas.** Temporary special permits may be issued for the use of unimproved areas for parking for a period of up to 30 days.

(g) **Sales office for subdivision.** Temporary special permits may be issued for a period of up to six months for a temporary office which is both incidental and necessary for the sale or rental of property in a new subdivision or housing project.

(h) **Standards.** No temporary structure or use permit shall be authorized until the following additional standards are met:

- 2050
- (1) The location and erection of any temporary structure shall conform to all of the regulations of the zoning district in which it is situated and all other applicable regulations of this chapter.
 - (2) If an open-air use, it must be located on a fully paved surface, unless otherwise indicated.
 - (3) The location of such use shall not be injurious to adjacent properties or the surrounding neighborhood.
 - (4) The water supply and sanitary facilities of any temporary dwelling shall conform to all applicable requirements of the state health department, the county health department, and City codes and other regulations.
 - (5) The following shall be taken into consideration:
 - (i) The reasons and necessity for the temporary use or structure.
 - (ii) The nature of the use or structure.
 - (iii) The proposed location of the use or structure.
 - (6) If not required above, the approving body may request a sketch plan, drawn to scale no smaller than one inch equals 50 feet, showing the location of the temporary use in relation to the lot lines and other structures.
 - (7) Reasonable conditions may be required with the approval of a temporary special permit by the approving body. The conditions may include, but are not limited to, conditions necessary to ensure that public services and facilities are not adversely affected, to protect the natural environment and conserve natural resources and energy, to ensure compatibility with adjacent uses of land, and to promote the use of land in a socially and economically desirable manner.
- 2060

Secs. 122-336--122-339. Reserved.

Subdivision IV: Building Permits.

Sec. 122-340 Requirements; Duration.

- (a) **Permit requirement.** No building or structure within the City shall hereafter be erected, moved, repaired, altered or razed, nor shall any work be started to erect, move, repair, alter, or raze until a building permit has been issued in accordance with the building regulations of this Code. No building permit shall be issued unless it is in conformity with the provisions of this chapter and all amendments hereto.
- 2070 (b) **Application requirements.** All applications for building permits shall be submitted to the Building Department. The application shall be accompanied by a site plan approved by the Planning Commission or City Planner, where applicable, when required under **Article III, Division 2 “Permits,” Subdivision 1 “Zoning Compliance.”**
- (c) **Cancellation of permits.** The Building Department shall have the power to revoke and cancel any permit in the event of failure or neglect to comply with all of the terms and provisions of this chapter.
- (d) **Expiration of permit.** All building permits shall expire six months from their date of issuance if construction has not been begun and diligently pursued. The Building Department may, upon a showing of due cause, extend the permit for one additional time as the building department determines to be reasonably necessary for completion. Thereafter, the applicant shall file a new building permit application, accompanied by the required fee.

Sec. 122-341. Certificate of occupancy.

- 2080 (a) **Certificate required.** No dwelling, building, structure or land shall be occupied or used until a certificate of occupancy has been issued for such occupancy or use, which occupancy or use shall be in compliance with this chapter, including approved site plans as applicable. No structure or land shall be occupied by a changed use or occupancy until a certificate of occupancy for the changed use has been issued.
- (b) **Temporary certificate of occupancy.** If the applicant can show prior substantial compliance with this chapter and can demonstrate need, the building department may issue a temporary certificate of occupancy for a period of not more than six months.

Secs. 122-342--122-344. Reserved.

Division 3: Nonconformities.

2090 **Sec. 122-345. Purpose.**

- (a) It is recognized that there exists within the districts established by this chapter uses of land which were lawful before this chapter was passed or amended, but which would be prohibited or restricted under the terms of this chapter.
- (b) It is the intent of this chapter to permit these nonconformities to continue until they are removed, abandoned, or brought into compliance with this chapter but not to encourage their survival. Such uses are declared by this chapter to be incompatible with permitted uses in the districts. It is further the intent of this chapter that nonconforming buildings, structures, or lots shall not be enlarged upon, expanded or extended, nor be used as grounds for adding other structures or uses prohibited in the district.
- 2100 (c) It is further recognized that certain nonconforming uses are not necessarily contrary to the public health, safety and welfare and that such uses were lawful at the time of their inception, and that no useful purpose would be served by the strict application of the elimination of lawful nonconforming use status. Therefore, two classes of nonconforming uses are designated, being class A and class B. All nonconforming uses are classified as class B nonconforming uses unless designated class A nonconforming uses.

Sec. 122-346. Authority to continue class B nonconforming.

Any class B nonconforming use which existed lawfully at the time of the adoption of the ordinance from which this chapter derives and which remains nonconforming and any such use which becomes nonconforming upon the adoption of this article, or of any subsequent amendments thereto, may be continued, subject to the regulations in this article.

Sec. 122-347. Nonconforming lots.

- 2110 A nonconforming lot is a lot of record or a lot described in a deed or land contract existing at the effective date of the ordinance from which this chapter derives that does not meet the minimum area or lot dimensional requirements of the district in which the lot is located. The following regulations must apply to any nonconforming lot:
- (a) Use of nonconforming lot. Any nonconforming lot must be used only for a use permitted in the district in which it is located.
 - (b) Single lot of record. A principal structure and customary accessory structures may be erected on any single lot of record at the effective date of adoption or amendment of this chapter, notwithstanding limitations imposed by other provisions of this chapter. Such lot must be in separate ownership and not of continuous frontage with other lots in the same ownership. This provision must apply even though such lot fails to meet the requirements for area or width or both, that are generally applicable in the district, provided that yard setback dimensions and requirements other than those applying to area or width of the lot must conform to the regulations for the district in which such lot is located. However, no more than one dwelling unit must occupy any lot except in conformance with the provisions of this chapter for required lot area for each dwelling unit.
 - 2120 (c) Variance from yard or other requirements. If the use of a legal nonconforming lot requires a variation from any yard or other requirements, other than lot area or width, then such variance must be obtained from the Zoning Board of Appeals.
 - (d) Contiguous lots in same ownership. When two or more contiguous nonconforming lots or parts of nonconforming lots are in a single ownership at the time of, or subsequent to the adoption or amendment of this chapter, such lots must be considered to be a single lot for the purposes of this chapter, and no portion of such lot must be used, occupied, divided, or sold in any manner which would diminish compliance with minimum lot width and area requirements of this chapter.
- 2130

Sec. 122-348. Nonconforming use of land.

A nonconforming use of land occurs when property is used for a purpose or in a manner which was lawfully in existence before this chapter was adopted, but has become nonconforming under the terms of this chapter or its amendments.

- (a) The nonconforming use of land not involving a building or structure, or in connection with which any building or structure thereon is incidental or accessory to the principal use of the land, may be continued subject to the regulations which follow:
 - (1) **Change.** The nonconforming use of land must not be changed to any other use except to a use permitted in the district in which the land is located.
 - 2140 (2) **Expansion.** A nonconforming use of land must not be expanded or extended beyond the area it occupies.
 - (3) **Moving.** No such nonconforming use must be moved in whole or in part to any other portion of the lot or

parcel occupied by such use at the effective date of adoption or amendment of this chapter.

(4) **Change in occupancy or ownership.** A change in occupancy or ownership shall not constitute a change in use.

(5) **Abandonment.** If the nonconforming use of land is discontinued for a period of 365 consecutive days, where there is an intent demonstrated by the property owner to abandon the nonconforming use, such use shall not be renewed, and any subsequent use of the land must conform to the regulations of the district in which the land is located. A nonconforming use may be determined to be abandoned if the use has ceased and one (1) or more of the following conditions exist, that said condition(s) demonstrating intent on the part of the property owner to abandon the nonconforming use:

- (i) One (1) or more utility meters, such as water, gas and electricity to the property, have been removed;
- (ii) The property, buildings and/or grounds are unsafe or unsanitary, as described in Chapter 18, Article V;
- (iii) Cessation of business operations;
- (iv) Receipt of a written declaration by the property owner.
- (v) Signs or other indications of the existence of the nonconforming use have been removed;
- (vi) Removal of equipment or fixtures that are necessary for the operation of the nonconforming use;
- (vii) Failure to maintain current licenses, certificates, permits, registrations or other appropriate documentation for the nonconforming use;
- (viii) Bank or tax foreclosure;
- (ix) Operation or maintenance of a permitted or different use at the property; or
- (x) Other actions or omissions, which in the opinion of the Planning or Building Department(s), evidence an intention of the part of the property owner to abandon the nonconforming use.

(b) A nonconforming use of land is not eligible for class A nonconforming designation.

Sec. 122-349. Class B nonconforming uses of buildings.

All nonconforming uses of buildings not designated class A shall be class B nonconforming uses of buildings. Class B nonconforming uses of buildings shall comply with all the provisions of this article relative to nonconforming uses of buildings. The class B nonconforming use of a building, or building and lot in combination, may be continued subject to the following provisions:

(a) **Change in use.** The nonconforming use of a building may not be changed to a different use unless the new use is permitted in that same district. Any building, or building and lot in combination, in or on which a nonconforming use is replaced by a permitted use, must thereafter conform to the regulations of the district in which it is located and the nonconforming use may thereafter not be resumed.

(1) A building or structure used for residential purposes which is nonconforming due to the number of dwelling units contained therein may only be changed so that the number of dwelling units is decreased, or so that the use is brought into conformity with this chapter.

(2) Notwithstanding the above, a nonconforming use of a building or structure may be changed to another nonconforming use so that the degree of nonconformity is lessened when authorized by the planning commission after a public notice and hearing in accordance with [§122-323](#). In considering such authorization, the planning commission must consider the following:

- (i) Whether the proposed use is equally or more appropriate than the present nonconforming zoning district in which the building, structure or land is located. No change to a less appropriate use may be authorized by the Planning Commission.
- (ii) Whether the proposed use will interfere to a lesser extent with the use of adjoining lands or other properties in the surrounding neighborhood for the uses for which they have been zoned pursuant to the provisions of this chapter.
- (iii) The effect of the proposed use on adjoining lands and the surrounding neighborhood.
- (iv) In permitting such change, the Planning Commission may require appropriate conditions and safeguards in accord with the purpose and intent of this chapter.
- (v) Where a nonconforming use of a structure, or structure and land, is hereafter changed to a more conforming use, it must not thereafter be changed to a less conforming use.

(b) **Expansion of class B nonconforming use.**

(1) The nonconforming use of any part of a building or structure must not be expanded or extended into any other portion of such building or structure.

(2) No visible structural alteration must be made to the building or structure devoted to a nonconforming use, except repairs and maintenance work which are required to keep such building in sound condition or as required by law.

(3) An existing structure containing a nonconforming use shall not be enlarged, constructed, reconstructed, moved or structurally altered or extended, unless the use is changed to a use which is permitted in the district in which the structure is located.

- 2200 (c) **Change in occupancy or ownership.** A change of occupancy or ownership shall not constitute a change in use.
- (d) **Removal or destruction.** If a building or structure in which a nonconforming use is being conducted is removed, destroyed, or severely damaged to the extent that the cost of restoration of the structure exceeds 100 percent of the state equalized value (SEV) or 50 percent of a higher value established by the most recent appraisal of the structure exclusive of the foundation and land, the nonconforming use shall not be renewed, and any subsequent use of the premises must conform to the use regulations of the district in which the premises are located. Single-family homes on individual lots that are considered a non-conforming use in the NC, Neighborhood Corridor Zoning District, shall be allowed to be rebuilt regardless of the amount of damage done to the structure so long as the rebuilt building is not enlarged or expanded. Single-family and two-family homes on individual lots that are considered a non-conforming use in the PMD, Production, Manufacturing, and
- 2210 Distribution Zoning District, shall be allowed to be rebuilt regardless of the amount of damage done to the structure so long as the rebuilt building is not enlarged or expanded.
- For the purpose of calculating a fair and equitable cost of restoration regulated by this section, the average of two bid estimates from licensed contractors must be used. All work requiring permits under state and local regulations, and materials necessary to bring the structure up to current code must be included. Clean up costs, demolition, furnishings, appliances, and site work, i.e. landscaping, fencing, paving, shall not be included. The actual repair and reconstruction may be done by the owner or contractor of their choice.
- (e) **Abandonment.** If the nonconforming use of land is discontinued for a period of 365 consecutive days, where there is an intent demonstrated by the property owner to abandon the nonconforming use, it must not thereafter be renewed, and any subsequent use of the land must conform to the regulations of the district in which the land is located. A nonconforming use must be determined to be abandoned if the use has ceased and one (1) or more of the following conditions exist, that said condition(s) being deemed to demonstrate intent on the part of the property owner to abandon the nonconforming use:
- 2220 (1) One (1) or more utility meters, such as water, gas and electricity to the property, have been removed;
- (2) The property, buildings and/or grounds are unsafe or unsanitary, as described in Chapter 18, Article V;
- (3) Cessation of business operations;
- (4) Receipt of a written declaration by the property owner.
- (5) Signs or other indications of the existence of the nonconforming use have been removed;
- (6) Removal of equipment or fixtures that are necessary for the operation of the nonconforming use;
- 2230 (7) Failure to maintain current licenses, certificates, permits, registrations or other appropriate documentation for the nonconforming use;
- (8) Bank or tax foreclosure;
- (9) Operation or maintenance of a permitted use or different use at the property; or
- (10) Other actions or omissions, which in the opinion of the Planning or Building Department(s), evidence an intention of the part of the property owner to abandon the nonconforming use.

Sec. 122-350. Class A nonconforming uses of buildings.

Nonconforming uses of buildings shall be designated Class A provided that the Planning Commission finds all of the following exists with respect to the use or structure:

- (a) The use of structure was lawful at its inception.
- 2240 (b) The decision to continue the nonconforming use, if granted, will not alter the essential character of the area or neighborhood.
- (c) Continuance of the use or structure would not be contrary to the public health, safety, or welfare or the spirit of the chapter.
- (d) No useful purpose would be served by strict application of the provisions of this chapter with which the use or structure does not conform.
- (e) Nonconforming uses of buildings are subject to the following restrictions:
- (1) Change in use. The nonconforming use of a building may not be changed to a different use unless the new use is permitted in that same district. Any building, or building and lot in combination, in or on which a nonconforming use is replaced by a permitted use, must thereafter conform to the regulations of the district in which it is located and the nonconforming use may thereafter not be resumed.
- 2250 (2) A building or structure used for residential purposes which is nonconforming due to the number of dwelling units contained therein may only be changed so that the number of dwelling units is decreased, or so that the use is brought into conformity with this chapter.
- (3) Notwithstanding the above, a nonconforming use of a building or structure may be changed to another nonconforming use so that the degree of nonconformity is lessened when authorized by the Planning Commission after a public notice and hearing in accordance with [§122-323](#). In considering such authorization, the Planning Commission must consider the following:
- (i) Whether the proposed use is equally or more appropriate than the present nonconforming zoning

district in which the building, structure or land is located. No change to a less appropriate use may be authorized by the Planning Commission.

(ii) Whether the proposed use will interfere to a lesser extent with the use of adjoining lands or other properties in the surrounding neighborhood for the uses for which they have been zoned pursuant to the provisions of this chapter.

(iii) The effect of the proposed use on adjoining lands and the surrounding neighborhood.

(iv) In permitting such change, the Planning Commission may require appropriate conditions and safeguards in accord with the purpose and intent of this chapter.

(v) Where a nonconforming use of a structure, or structure and land, is hereafter changed to a more conforming use, it must not thereafter be changed to a less conforming use.

(f) Removal or destruction. If a class A nonconforming structure is destroyed, or severely damaged, it may be restored in conformance with the plans submitted when the status was conferred.

(g) This designation shall run with the land.

Sec. 122-351. Class A Conditions.

The decision to grant a class A designation shall be made by the Planning Commission in writing, setting forth its findings of fact and basis for the designation. Only multiple family dwellings and/or group residence uses in R1 and CN-Mid shall be eligible for this designation. For changes or improvements to a class A use, site plans shall be required.

(a) Application. An application for class A nonconforming status shall be filed with the City Planner's office by the record owner of the property in question or by a person authorized to act on the record owner's behalf. The application shall consist of a completed application form, fee, and the following information:

(1) Name, address, and telephone number of the applicant and property owner; and the interest of the applicant in the property.

(2) Legal description, address, and tax parcel number of the subject property.

(3) An accurate, scaled drawing of the property, showing all property lines and dimensions correlated with the legal description; the location and dimensions of all existing and proposed structures and uses on the property; any roads, alleys, easements, drains, or waterways which traverse or abut the property; and the lot area and setback dimensions necessary to show compliance with the regulations of this chapter. In most cases, a site plan or survey will meet this requirement.

(4) The applicant shall show compliance with all applicable conditions of the City of Ypsilanti Code of Ordinances, and all applicable conditions of the International Property Maintenance Code, as adopted under Chapter 18 of the City of Ypsilanti Code of Ordinances.

(5) Other reasonable information deemed necessary by the Planning Commission in order to make a proper decision.

(6) No application for Class A designation shall be accepted after such time as the building has been destroyed as described in §122-349(d) or the use abandoned as described in §122-349(e).

(b) Conditions. The Planning Commission may condition its approval on the following:

(1) Screening and landscaping in keeping with community standards to ensure compatibility with adjacent uses.

(2) Restrictions on lighting, noise, odor, or visual impact.

(3) Signage must comply with current zoning district requirements. Existing nonconforming signs may be required to be eliminated or reduced in size and number.

(4) Replacement of a building must not create a more nonconforming yard setback condition which would impact on conforming properties in the immediate vicinity.

(5) Other reasonable safeguards and improvements may be imposed by the Planning Commission to protect conforming uses in the surrounding area.

(c) Procedure. By the following procedure, the Planning Commission shall assure the public health, safety and welfare, and the spirit and purpose of this chapter:

(1) A class A designation shall be deemed temporary until the Planning Commission has received written verification from the building official that the party requesting the class A designation has complied with all of the conditions set forth by the Planning Commission.

(2) Once the Planning Commission has received written verification from the building director that the party requesting the class A designation has complied with said conditions, the class A designation shall become final, subject to other provisions of this chapter as hereafter prescribed.

(3) No class A nonconforming use shall be resumed if it has been abandoned as defined in §122-349(e). No class A nonconforming use shall be used, altered, or enlarged in violation of any conditions imposed in its designation.

(4) A temporary class A nonconforming use designation shall be void after six months if any conditions imposed by the designation remain outstanding, unless the Planning Commission grants a written request

for an extension of six months. No more than two extensions may be granted.

- (d) **Revocation.** Approval of a Class A designation may be revoked by the Planning Commission if the use and building is not in conformance with the approved plans, or if compliance with conditions has not been consistently demonstrated. In such case, the issue shall be placed on the agenda of the Planning Commission for consideration. Written notice must be given to the applicant not less than ten days prior to the meeting. The applicant must be given the opportunity to present information to the Planning Commission and answer questions. The Planning Commission may revoke the Class A designation if it finds that a violation of the conditions set forth by the Planning Commission in their initial decision exists and has not been remedied prior to the meeting.

Sec. 122-352. Nonconforming structures.

- (a) A nonconforming building or structure is a structure, including a sign, which was lawful on the effective date of adoption or amendment of this chapter, but which does not conform to the new chapter regulations for building type, lot area, lot area per dwelling unit, lot width, lot coverage, floor area, height, screening, off-street parking, loading space, yard, or other requirements of the zoning district in which it is located.
- (b) Nonconforming buildings and structures may be re-used and occupied by new owners or tenants if all requirements of this Chapter are met and the restrictions below are met.
- (c) Nonconforming buildings and structures are subject to the following restrictions:
- (1) Expansion. Nonconforming structures may be expanded only in compliance with the following regulations:
 - (i) All nonconforming structures, in any zoning district, may only be expanded in such a way that does not increase a non-conforming characteristic.
 - (ii) All expansions must meet all requirements of the zoning district in which it is located, including lot coverage, heights, yard requirements, and off-street parking.
 - (iii) A non-conforming building type may not be expanded.
 - (2) Alterations. A nonconforming structure may be altered to decrease its nonconformity.
 - (3) Moving. A nonconforming structure which is moved within a site or to another site must conform to the regulations of the district in which it is located.
 - (4) Damage and removal. A nonconforming structure which is damaged by any means may be restored to its original conditions and location prior to such damage, provided such construction is completed within 18 months of the date of damage and is diligently pursued to completion. Failure to complete reconstruction results in the loss of legal nonconforming status.
 - (5) Restoration or repair.
 - (i) All repairs and maintenance work required to keep a nonconforming building in sound condition may be made, but such structure may not be structurally altered in a way inconsistent with the description and purpose of this article.
 - (ii) If a nonconforming structure or a structure housing a nonconforming use becomes physically unsafe or unlawful or poses a threat to the public health, safety, and welfare due to a lack of repairs or maintenance, the structure may be declared by the Building Department to be unsafe or unlawful by reason of physical condition. Such structure may not thereafter be restored, repaired, or rebuilt except in conformity with the provisions of this Chapter.
- (d) Restoration of Historic Structures. Restoration may be permitted of a legal nonconforming structure, designated as historic by the Ypsilanti Historic District Commission, which has been destroyed or abandoned, **as defined in §122-349**, provided the Planning Commission finds all of the following provisions are met:
- (1) The approved design of the restored building maintains the same design and historical character it had prior to the destruction or abandonment; or, in the case of a building that had been altered prior to destruction or abandonment, that the restored building more closely parallels the design of the original historic structure.
 - (2) All reasonable attempts at eliminating or reducing the nonconforming nature of the structure have been considered and are implemented in the restoration project.
- (e) Signs of Local Historic Significance. The City Council may approve and/or amend a list of existing nonconforming signs deemed to be of local historical significance by the Historic District Commission. Signs deemed historically significant may be repaired, reconstructed, or relocated, subject to review and approval by the Building Official.

Sec. 122-353. Acquisition of nonconformities.

The City may acquire private property to remove a nonconformity, as provided in Act No. 207 of the Public Acts of Michigan of 1921 (MCL 125.581 et seq., MSA 5.2931 et seq.), as amended.

2370

Sec. 122-354. Building or structure under construction on effective date of the ordinance from which this chapter is derived.

Any building or structure must be considered existing and lawful for the purposes of this article if, on the effective date of the ordinance from which this chapter is derived, a building permit has been obtained therefore, if required; or if no building permit is required, a substantial start has been made toward construction and construction is thereafter pursued diligently to conclusion.

Sec. 122-355. Unlawful nonconformities.

- (a) No nonconformity shall be permitted to continue in existence if it was unlawful at the time it was established.
- (b) The City shall maintain records of nonconforming uses and structures as accurate as is feasible for determining legal nonconforming uses and structures in existence on the effective date of the ordinance from which this chapter is derived. However, failure on the part of a property owner to provide the City with necessary information to determine legal nonconforming status may result in denial of a required or requested permit.

2380

Secs. 122-356—122-359. Reserved.

Division 4: Amendments.

Sec. 122-360. General requirements. (61)

- (a) The City Council shall have authority to amend, supplement, or change zoning district boundaries or the provisions and regulations of this chapter, pursuant to the authority and procedures set forth in Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.), as amended.
- (b) Text amendments to this chapter may be initiated by a motion of the City Council or the Planning Commission, or by the filing of an application by any interested person or organization. Changes in district boundaries may be initiated by a motion of the City Council or the Planning Commission, or by the filing of an application by any person having a freehold interest in the subject property or by such person's designated agent.
- (c) The owner of land who has filed an application for changes in district boundaries may voluntarily offer with conditions relating to the use and/or development of land, either at the time the application is filed or may be made at a later time during the approval process. The City Council may establish a period of time during which the conditions apply to the land. No employee or official of the City of Ypsilanti shall require an owner to offer conditions as a requirement for rezoning. The lack of an offer of conditions shall not affect an owner's rights under this Ordinance.
- (d) All proposed amendments shall be referred to the Planning Commission for a public hearing, review and recommendation, before action may be taken thereon by the City Council.

Sec. 122-361. Amendment procedures. (62)

- (a) **Application.** Applications for amendments to this chapter shall be filed with the City Planner's office on an appropriate form provided by the City and accompanied by the required fee. No fee shall be required if a proposed amendment was initiated by the City Council or Planning Commission. All applications for amendments to this chapter shall, at a minimum, include the following:
 - (1) The applicant's name, address, and interest in the application; and the name, address, and interest of every person having a legal or equitable interest in any land which is to be rezoned. The application shall be signed by both the landowner and the applicant, if not the same.
 - (2) The nature and effect of the proposed amendment.
 - (3) If the proposed amendment would require a change in the Zoning Map, a boundary change and/or a change in building type allowed on a site designated on the Zoning Map, a fully dimensioned map showing the boundaries of land which would be affected by the proposed amendment, a legal description of the entire land area, a legal description of each subarea owned by a different person or organization, the present zoning of the land, the zoning of all adjacent lands, existing uses and structures on the subject property and adjacent properties, and all public and private rights-of-way and easements bounding or intersecting the land to be rezoned.
 - (4) If the proposed Zoning Map amendment includes voluntary conditions set forth by the owner of the property, a written statement of those voluntary conditions shall be included. The "Statement of Conditions" shall:
 - (i) Be in a form recordable with the Washtenaw County Register of Deeds or, in the alternative, be accompanied by a recordable Affidavit or Memorandum prepared and signed by the owner giving notice of the "Statement of Conditions" in a manner acceptable to the City Attorney.
 - (ii) Contain a legal description of the land to which it pertains.
 - (iii) Contain a statement acknowledging that the "Statement of Conditions" runs with the land and is binding upon successor owners of the land.
 - (iv) Incorporate by attachment or reference any site plan, diagram, or other documents submitted or approved by the owner that are necessary to illustrate the implementation of the "Statement of Conditions". If any such documents are incorporated by reference, the reference shall specify where the document may be examined.
 - (v) Contain a statement acknowledging that the "Statement of Conditions" or an Affidavit or Memorandum giving notice thereof may be recorded by the Township with the Washtenaw County Register of Deeds.
 - (vi) Contain the notarized signatures of all of the owners of the subject land preceded by a statement attesting to the fact that they voluntarily offer and consent to the provisions contained within the "Statement of Conditions".
 - (5) If the application is for an amendment to this chapter text, a description of the proposed change, with a detailed explanation as to why the proposed amendment is needed.
 - (6) All other circumstances, factors, and reasons which the petitioner offers in support of the proposed

amendment.

(b) **Public hearing.**

- (1) At least one public hearing on a proposed amendment shall be held by the Planning Commission. Notice of such public hearing shall be published at least once in a newspaper of general circulation in the City, not less than 15 days prior to the date set for the public hearing. The contents of the notice shall include the following.
- (2) Time and place of the public hearing.
- (3) A description of the proposed amendment.
- (4) The street address and legal description of any property for which a zoning change is requested, the present zoning of that property, and the proposed new zoning designation. If 11 or more adjacent properties are proposed for rezoning, individual addresses and legal descriptions are not required.
- (5) Not less than 15 days' notice of the public hearing shall be given by mail to each public utility company and railroad company owning or operating any public utility or railroad within the zoning district affected by the proposed amendment that registers its name and address with the City for the purpose of receiving such notice.
- (6) If an individual property or up to 10 adjacent properties are proposed for rezoning, written notice of the public hearing shall be given the owner of the property in question, and to all owners of real property and occupants of structures within 300 feet of the property in question. The notice shall be mailed or delivered not less than 15 days before the public hearing.
- (7) Any notices served by mail require an affidavit of mailing to be filed with the Planning Commission prior to the public hearing.

(c) **Planning Commission recommendation.** Following the public hearing, the Planning Commission shall prepare a report of its recommendations regarding the proposed amendment, and transmit such report to the City Council. The Planning Commission may recommend changes in the amendment in order to reflect objections raised at the hearing or to correct typographical or grammatical errors. The Planning Commission may reduce the area of land to be rezoned as described in the public hearing notice, but may not enlarge the area of land to be rezoned.

(d) **City Council action.** After the Planning Commission has held a public hearing and has made a written report to the City Council indicating their recommendation on the proposed amendment, the City Council may adopt the proposed amendment, decline to adopt the proposed amendment, or may adopt it in whole or part with or without additional changes. The City Council may also hold a public hearing on the proposed amendment or refer the proposed amendment back to the Planning Commission for further study and review or for additional public hearings. Upon the presentation of a protest petition meeting the requirements of section-4 403 of Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.) an amendment to this chapter or Zoning Map which is the object of such petition shall be passed by an affirmative vote of not less than two-thirds members of the City Council.

(e) **Publication.** Following adoption of an amendment to this chapter by the City Council, a notice of adoption shall be published in a newspaper of general circulation in the City within 15 days after adoption. The notice shall include the following information:

- (1) Either a summary of the regulatory effect of the amendment including the geographic area affected, or the text of the amendment.
- (2) The effective date of the amendment.
- (3) The place and time where a copy of the amendment may be purchased or inspected.

Sec. 122-362. Standards for Amendments. (63)

(a) **Text Amendment.** For a change to the text of the Zoning Ordinance, the Planning Commission shall consider and the City Council may consider, whether the proposed amendment meets the following standards:

- (1) The proposed amendment is consistent with the guiding values of the Master Plan; and
- (2) The rezoning is consistent with description and purpose of the proposed district, and.
- (3) The proposed amendment is consistent with the intent of this Zoning Ordinance; and
- (4) The proposed amendment will enhance the functionality, transportation network or character of the future development in the City; and
- (5) The proposed amendment will preserve the historic nature of the surrounding area and of the City; and
- (6) The proposed amendment will enhance the natural features and environmental sustainability of the City; and
- (7) The proposed amendment will protect the health, safety, and general welfare of the public; or
- (8) The proposed amendment is needed to correct an error or omission in the original text; or
- (9) The proposed amendment will address a community need in physical or economic conditions or development practices; and

(10) The proposed amendment will not result in the creation of significant nonconformities in the City.

- (b) **Zoning Map Amendment.** For a change in the Zoning Map, the Planning Commission shall consider and the City Council may consider, whether the proposed rezoning meets the following standards:

- (1) The rezoning is consistent with the policies, guiding values and City Framework (Future Land Use Map) of the Master Plan, including any subarea or corridor studies. If conditions have changed since the current Master Plan was adopted, the consistency with recent development trends in the area.
- (2) The rezoning sustains the site's physical, geological, hydrological and other environmental features with the potential uses allowed in the proposed zoning district.
- (3) The property proposed to be re-zoned can accommodate the requirements of the proposed zoning district.
- (4) All the potential uses and building types allowed in the proposed zoning district are compatible with surrounding uses, buildings, and zoning in terms of land suitability, impacts on the environment, impacts on the transportation network, density, nature of use, aesthetics, infrastructure and potential influence on property values.
- (5) The capacity of City infrastructure and services sufficient to accommodate the uses permitted in the requested district without compromising the health, safety, sustainability and welfare of the City.
- (6) The rezoning will not be detrimental to the financial stability and economic welfare of the City.
- (7) The rezoning not would negatively impact the condition of any nearby parcels considering existing vacancy rates, current per-square-foot lease or sale rates, and other impacts.
- (8) The rezoning is consistent with the trend of development in the neighborhood or surrounding area.
- (9) The property in question was improperly zoned or classified when this Chapter was adopted or amended.
- (10) Where a rezoning is reasonable given the above criteria, a determination shall be made that the requested zoning district is more appropriate than another district or than amending the list of permitted or special land uses within a district.

- (c) **Conditional Zoning Map Amendment.** For a change in the Zoning Map with voluntary conditions, the Planning Commission shall consider and the City Council may consider, whether the proposed rezoning and voluntary conditions meet the following conditions:

- (1) The voluntary conditions are first offered and heard at a public meeting.
- (2) The rezoning and voluntary conditions are consistent with the policies, guiding values and City Framework (Future Land Use Map) of the Master Plan, including any subarea or corridor studies. If conditions have changed since the current Master Plan was adopted, the consistency with recent development trends in the area.
- (3) The rezoning and voluntary conditions are consistent with the description and purpose of the district of the property.
- (4) The rezoning and voluntary conditions sustains the site's physical, geological, hydrological and other environmental features with the potential uses allowed in the proposed zoning district.
- (5) The property proposed to be re-zoned can accommodate the requirements of the proposed zoning district and voluntary conditions.
- (6) All the potential uses and building types allowed in the proposed zoning district under the voluntary conditions are compatible with surrounding uses, buildings, and zoning in terms of land suitability, impacts on the environment, impacts on the transportation network, density, nature of use, aesthetics, infrastructure and potential influence on property values.
- (7) The capacity of City infrastructure and services are sufficient to accommodate the uses permitted in the requested district under the voluntary conditions without compromising the health, safety, sustainability and welfare of the City.

- (8) The rezoning and voluntary conditions will not be detrimental to the financial stability and economic welfare of the City.
- (8) The rezoning and voluntary conditions will not negatively impact the condition of any nearby parcels considering existing vacancy rates, current per-square-foot lease or sale rates, and other impacts.
- (9) The rezoning and voluntary conditions are consistent with the trend of development in the neighborhood or surrounding area.
- (10) The voluntary conditions bear a reasonable and rational relationship to the property for which rezoning is requested.
- (11) The voluntary conditions shall run with the land, and may only be removed or changed through another act of rezoning.

- (d) **Building Type Designation on Zoning Map.** For a change in building type designation on the Zoning Map, the Planning Commission shall consider and the City Council may consider, whether the proposed amendment meets the following conditions:

- (1) The building type change is consistent with the policies, guiding values and City Framework (Future Land Use Map) of the Master Plan, including any subarea or corridor studies. If conditions have changed since

the current Master Plan was adopted, the building type change is consistent with recent development trends in the area.

- (2) The building type sustains the site's physical, geological, hydrological and other environmental features with the potential uses allowed on the proposed property and surrounding property.
- (3) The building type change is consistent with the size, scale and character desired within the zoning district.
- (4) The property can accommodate the requirements of the proposed building type change.
- (5) The building type change is compatible with surrounding uses, buildings, and zoning in terms of land suitability, impacts on the environment, impacts on the transportation network, density, nature of use, aesthetics, infrastructure and potential influence on property values.
- (6) The capacity of City infrastructure and services sufficient to accommodate the building type change on the property in question without compromising the health, safety, sustainability and welfare of the City.
- (7) The building type change will not be detrimental to the financial stability and economic welfare of the City.
- (8) The building type change will not would negatively impact the condition of any nearby parcels considering existing vacancy rates, current per-square-foot lease or sale rates, and other impacts.
- (9) The building type change is consistent with the trend of development in the neighborhood or surrounding area.
- (10) The building type change on the property in question is consistent with the description and purpose of the district of the property.
- (11) In cases where requested building type is designed to accommodate commercial uses on the first floor in the Core Neighborhood, Core Neighborhood-Mid, or Core Neighborhood Single Family districts, the parcel must be located on a corner of two or more streets.

Sec. 122-363. Protests. (64)

- (a) In case a protest against a proposed rezoning is presented, duly signed by the owners, or part owners, of 20 percent of the area of land proposed to be altered, or by the owners of at least 20 percent of the area of land included with the area extending outward 100 feet from any point on the boundary of the land included in the proposed change, such amendment shall not be passed except by a two-thirds vote of the City Council. The protest petition shall be presented to the City Council before final City Council action on the amendment.
- (b) For purposes of the protest, publicly-owned land shall be excluded in calculating the 20 percent land area requirement.

Sec. 122-364. Conditional Zoning Map Amendment Administration. (65)

- (a) **Zoning Map.** Upon a conditional Zoning Map amendment taking effect, the Zoning Map shall be amended to reflect the new zoning classification along with a designation that the land was rezoned with a "Statement of Conditions". The Planning Department shall maintain a listing of all lands rezoned with a "Statement of Conditions".
- (b) **Statement of Conditions.** The approved "Statement of Conditions" shall be approved by the City Attorney and then filed by the City of Ypsilanti with the Washtenaw County Register of Deeds. If a time period for compliance with conditions has been required by City Council, the time period must be included in the document approved and filed with the Washtenaw County Registrar of Deeds. The City Council shall have authority to waive this requirement if it determines that, given the nature of the conditions and/or the time frame within which the conditions are to be satisfied, the recording of such a document would be of no material benefit to the City or to any subsequent owner of the land.
- (c) **Compliance with Conditions.** Upon a conditional Zoning Map amendment taking effect, the use of the land shall conform thereafter to all of the requirements regulating use and development within the new zoning district as modified by any more restrictive provisions contained in the "Statement of Conditions". Any person who establishes a development or commences a use upon land that has been rezoned with conditions shall continuously operate and maintain the development or use in compliance with all of the conditions set forth in the "Statement of Conditions". Any failure to comply with a condition contained within the "Statement of Conditions" shall constitute a violation of this Ordinance. Additionally, any such violation shall be deemed a nuisance per se and subject to judicial abatement as provided by law. No permit or approval shall be granted under this Ordinance for any use or development that is contrary to an applicable "Statement of Conditions".
- (d) **Time period for conditions.** If approved with a time period for conditions, the City of Ypsilanti shall not add or alter the conditions during that time period. The landowner may request an extension of the time period from the City Council. Except if an extension is granted, the land shall revert to its former zoning classification if conditions are not satisfied within the approved time period.

Sec. 122-365. Resubmitted amendments. (66)

No petition for an amendment which has been disapproved by the City Council shall be resubmitted for a period of

one year from the date of disapproval, except as may be permitted by the Planning Commission after new and significant facts or conditions have been offered which might result in favorable action upon resubmission.

Secs. 122-366 – 369. Reserved.

DRAFT 03-16-2017

Division 5: Variances and Appeals.

Sec. 122-370. Variances. (94)

(a) **Application.** An application for a variance to the provisions of this chapter shall be filed with the City Planner's office by the record owner of the property in question or by a person authorized to act on the record owner's behalf. The application shall consist of a completed application form, fee, and the following information:

- (1) Name, address, and telephone number of the applicant and property owner; and the interest of the applicant in the property.
- (2) Legal description, address, and tax parcel number of the subject property.
- (3) An accurate, scaled drawing of the property, showing all property lines and dimensions correlated with the legal description; the location and dimensions of all existing and proposed structures and uses on the property; any roads, alleys, easements, drains, or waterways which traverse or abut the property; and the lot area and setback dimensions necessary to show compliance with the regulations of this chapter. In most cases, a site plan or sketch plan will meet this requirement.
- (4) Other reasonable information deemed necessary by the Zoning Board of Appeals in order to make a proper decision.

(b) **Standards for variances.** A variance from the literal enforcement of this chapter may be granted by the Zoning Board of Appeals only if all of the following standards are met:

- (1) Literal enforcement of this chapter will pose practical difficulties to the applicant because of special conditions or circumstances which are unique to the specific property such as: exceptional shallowness or shape of the property, exceptional topographic conditions, extraordinary situation of a building or structure, use or development of an adjacent property, or difficulties relating to construction or structural changes on the site. Mere inconvenience or a desire to attain higher financial return shall not itself be deemed sufficient to warrant a variance.
- (2) Such variance is necessary for the preservation and enjoyment of a substantial property right enjoyed by other property owners in the same district under the terms of this chapter. Granting of the variance shall not confer upon the applicant any special privilege that is denied by this chapter to other lands, structures, or buildings in the same district.
- (3) The alleged practical difficulties on which the variance request is based have not been created by any person presently having an interest in the property.
- (4) The granting of the variance will not be detrimental to the public welfare or injurious to other property or improvements in the neighborhood in which the property is located.
- (5) The allowance of the variance will result in substantial justice being done, considering the public benefits intended to be secured by this chapter, the individual hardships that will be suffered by a failure of the Zoning Board of Appeals to grant the variance, and the rights of others whose property would be affected by the allowance of the variance.
- (6) A variance granted shall be the minimum variance that will make possible a reasonable use of the land, buildings, or structure.

(c) **Variances; reapplication.** An application for a variance which has been denied wholly or in part by the Zoning Board of Appeals shall not be resubmitted for a period of one year from the date of denial, except on grounds of new evidence of changed conditions found by the Zoning Board of Appeals to be valid. The Zoning Board of Appeals shall review any subsequent application for a variance on the conditions and circumstances which exist at the time of the subsequent application.

(d) **Variance to run with land.** A variance shall run with the land and shall not become void if property is sold to a new owner. However, a variance shall become null and void if no building permit or no construction is started within one year of the approval date of the variance.

Sec. 122-371. Appeals. (95)

(a) **Questions first go to administrative official.** All questions concerning administrative decisions under this chapter shall first be presented to the applicable City official or agency. Such questions shall be presented to the Zoning Board of Appeals only on appeal from the decisions of the applicable City official or agency.

(b) **Filing appeal.** Appeals may be commenced by a person aggrieved by the decision of any officer, department, board, agency, or bureau of the City, county, state, or federal governments by filing a notice of appeal with the City Planner's office. The notice of appeal shall be signed, shall specify the requirement or decision from which the appeal is made, and shall state the specific grounds on which the appeal is based. The applicable fee shall be submitted with the notice of appeal; such fee shall be nonrefundable. Appeals shall be filed within 60 days of the decision in question.

- 2670 (c) **Stay of action.** An appeal stays all proceedings in the furtherance of the action appealed from unless the Building Department certifies to the Zoning Board of Appeals after the notice is filed that, by reason of facts stated in the certificate, a stay would cause imminent peril to life or property. In such case, proceedings shall not be stayed other than by a restraining order which may be granted by the Zoning Board of Appeals or by circuit court, following written request, notice to the officer or body from whom the appeal is taken, and due cause shown.
- (d) **Power to subpoena.** The Zoning Board of Appeals shall have the power to subpoena witnesses; administer oaths; compel testimony; and require the production of reports, papers, files, and other evidence pertinent to the matters before it.
- 2680 (e) **Decisions regarding appeals.** The Zoning Board of Appeals may, so long as such action is in conformity with the terms of this chapter, reverse or affirm, wholly or partly, or may modify the order, requirement, decision, or determination from which an appeal is sought. To that end, the Zoning Board of Appeals shall have the powers of the public official or body from whom the appeal is taken.

Secs. 122-372 – 374. Reserved.

Division 6: Violations and Penalties.

Sec. 122-375. Violations and Penalties. (8)

- (a) **Public nuisance.** Any building or structure which is erected, altered, converted, or used, or any use of premises or land which is begun or changed subsequent to the passage of this chapter and in violation of any of the provisions of this chapter is hereby declared to be a public nuisance per se, and may be abated by order of the City Council, subject to appeal to any court of competent jurisdiction.
- 2690 (b) **Blight Violation.** A person who violates any provision of this chapter is responsible for a blight violation, subject to payment of a civil fine and costs as set forth in section 71-73. Repeat offenses under this chapter shall be subject to increased fines and costs as set forth in section 71-73. A person who violates this chapter is also subject to enforcement by the procedures, costs, and penalties set forth in Section 1-15 of the Ypsilanti City Code for blight violations.
- (c) **Owner responsibility.** The owner of any building, structure or premises or part thereof, where any condition in violation of this chapter shall exist or shall be created, and who has assisted knowingly in the commission of such violation, shall be guilty of a separate offense and upon conviction thereof shall be liable for the fines provided in this chapter.
- (d) **Each day separate offense.** Each and every day during which a violation of this chapter shall exist shall constitute a separate offense.
- 2700 (e) **Rights and remedies are cumulative.** The rights and remedies provided in this chapter are cumulative and are in addition to any other remedies provided by law.
- (f) **Rights and remedies preserved, no waiver.** Any failure or omission to enforce the provisions of this chapter, and any failure or omission to prosecute any violations of this chapter, shall not constitute a waiver of any rights and remedies provided by this chapter or by law, and shall not constitute a waiver of nor prevent any further prosecution of violations of this chapter.
- (g) **Money received from penalties.** All money received from penalties assessed shall be placed in the City's general fund.

Secs. 122-376 – 122-379. Reserved.

Division 7: Authorities.

2710 Sec. 122-380. Establishment of administrative officers. (31)

The provisions of this chapter shall be administered and enforced by the City Manager or by such person or persons, such as the City Planner or Building Inspector, that the City Manager may delegate to enforce the provisions of this chapter. All departments, officials and public employees of the City vested with the duty or authority to issue permits or licenses shall conform to the provisions of this chapter.

Sec. 122-381. Duties and enforcement powers. (32)

Typical duties and powers of the City Manager, or such person or persons the City Manager may delegate to act as Building Inspector, City Planner or other agents to enforce this chapter, shall include, but not be limited, to the following:

- 2720 (a)** The Building Inspector, or such person or persons as the City Manager may delegate, shall have the power to:
 - (1) Make inspections of buildings and premises necessary to carry out the duties of enforcement of this chapter.
 - (2) Issue building permits.
 - (3) Issue certificates of occupancy.
 - (4c) Conduct surveillance and issue notices of violation pursuant to this chapter.
- (b)** Adequate records of permits and applications issued, inspections, violations, nonconformities, variances, construction plans, fees collected, etc., shall be maintained. Public notices shall be published as necessary.
- (c)** Persons who have zoning questions shall be assisted, and when applicable, such questions shall be brought before the Planning Commission or Zoning Board of Appeals.
- 2730 (d)** Advice may be provided to the City Council, Planning Commission or Zoning Board of Appeals on petitions and applications that come before these bodies.
- (e)** It shall be unlawful for the City Manager or their delegate to approve any permits or Certificates of Occupancy for any excavation or development proposal until such plans have been inspected in detail and found to conform with this chapter, or when applicable, site plan approval has been obtained.
- (f)** Under no circumstances shall the City Manager or their delegate be permitted to make changes to this chapter nor vary the terms of this chapter in carrying out duties in administering and enforcing this chapter.
- (g)** The City Manager or their delegate shall not refuse to issue a permit when the conditions imposed by this chapter are complied with by the applicant, despite violations of any contract such as covenants or private agreements which may occur upon granting of such permit.

Secs. 122-382 – 122-384. Reserved.

2740 **Subdivision I: Planning Commission.**

Sec. 122-385. Authority. (46)

This ordinance is adopted pursuant to the authority granted the City Council under the Michigan Planning Enabling Act, Public Act 33 of 2008, MCL 125.3801 et seq., and the Michigan Zoning Enabling Act, Public Act 110 of 2006, MCL 125.3101 et seq., as amended, to establish a Planning Commission with the powers, duties and limitations provided by those Acts.

Sec. 122-386. Purpose. (47)

2750 The purpose of this ordinance is for the City Council to confirm the establishment, under the Michigan Planning Enabling Act, Public Act 33 of 2008, MCL 125.3801 et seq., of the City Planning Commission, formerly established under the Municipal Planning Act, MCL 125.31 et seq., to establish the appointments, terms, and membership of the Planning Commission; to identify the officers and the minimum number of meetings per year of the Planning Commission; and to prescribe the authority, powers and duties of the Planning Commission as provided in and subject to the terms and conditions of this ordinance.

Sec. 122-387. Establishment. (48)

There shall be a City Planning Commission in accordance with the Michigan Planning Enabling Act, Public Act 33 of 2008, as amended, with the powers and duties as therein set forth and as hereinafter provided.

Sec. 122-388. Zoning Board of Appeals member of the Planning Commission. (50)

As provided in the Michigan Zoning Enabling Act, MCL 125.3601, one member of the Planning Commission may be appointed by the City Council to serve on the Zoning Board of Appeals, with the term of that appointment to correspondence to that member's term as a Planning Commission member.

2760 **Sec. 122-389. Procedures of the Planning Commission. (51)**

- (a) The Planning Commission shall adopt bylaws for the transaction of business and shall keep a public record of its resolutions, transactions, findings, and determinations.
- (b) The Planning Commission's procedures shall be in conformity with applicable ordinances, resolutions and policies adopted by the City Council.

Sec. 122-390. Meetings of the Planning Commission. (52)

- (a) The Planning Commission shall hold not less than four (4) regular meetings each year. At its first meeting of the calendar year, the Planning Commission shall adopt and provide notice of its regular meetings for the ensuing year in accordance with the Open Meeting Act, Public Act 267 of 1976, as amended; provided, however, that a meeting need not be held if pending matters do not warrant a meeting.
- 2770 (b) Special meetings may be called by the chairperson or upon written request to the secretary by at least two members of the Planning Commission. Unless the Planning Commission bylaws provide otherwise, the secretary shall send written notice of a special meeting to Planning Commission members not less than 48 hours before the meeting. All costs of special meetings held to consider requests of applicants for approvals under the zoning ordinance (or for such other purposes as may be necessary) shall be paid by the applicant for such requests.
- (c) The business that the Planning Commission may perform shall be conducted at a public meeting held in compliance with the Open Meetings Act, Public Act 267 of 1976, as amended.

Sec. 122-391. Duties and responsibilities of the Planning Commission. (53)

2780 The members of the Planning Commission shall have the following principal duties and responsibilities, among others:

- (a) Prepare, consider, and approve a master plan as a guide for development within the City's planning jurisdiction. An update shall be considered no less frequently than every five (5) years; upon which consideration a determination shall be made as to the necessity of such a revision.
- (b) Review and advise upon plans for capital improvements, such as construction, expansion, removal, or vacating of public lands, buildings, or right-of-ways. This review should focus on consistency with adopted plans of the City and other governmental units. This may be done by an annual review of the City's Capital Improvement Plan prior to adoption by City Council, rather than of each project individually.
- (c) Take such action on petitions, staff proposals, and City Council requests for amendments to the zoning

ordinance as required.

- 2790 (d) Review subdivision and condominium proposals and recommend appropriate actions to the City Council, in accordance with the Land Division Act, Public Act 288 of 1967.
- (e) Prepare special studies and plans, as deemed necessary by the Planning Commission or City Council, for which appropriations of funds have been approved by the City Council, as needed.
- (f) Prepare an annual written report to the City Council concerning its operations and the status of planning activities, including recommendations regarding actions by the City Council related to planning and development, with the report to be presented within 90 days of the beginning of each calendar year.
- (g) Promote understanding of and interest in the master plan and the City zoning ordinance.
- 2800 (h) Carry out duties and responsibilities as required by and in accordance with the Michigan Zoning Enabling Act, Public Act 110 of 2006, as amended, and the Michigan Planning Enabling Act, Public Act 33 of 2008, as amended.

Sec. 122-392. Approval, ratification and reconfirmation. (54)

All official actions taken by the City Planning Commission preceding the Planning Commission established by this ordinance are hereby approved, ratified, and reconfirmed. Any project, review, or process taking place at the effective date of this ordinance shall continue with the Planning Commission created by this ordinance, subject to other requirements of this ordinance, and shall be deemed a continuation of any previous City Planning Commission. This ordinance shall be in full force and effect from and after its adoption and publication.

Secs. 122-393 – 122-394. Reserved.

Subdivision II: Zoning Board of Appeals.

Sec. 122-395. Establishment and membership. (91)

- 2810 (a) **Established.** There is hereby established a Zoning Board of Appeals, which shall perform its duties and powers in accordance with Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.), as amended, and in such a way that the objectives of this chapter shall be observed, public safety secured, and substantial justice done.
- (b) **Membership.** The Zoning Board of Appeals shall consist of five members appointed by the Mayor with the City Council's consent. The members of the Zoning Board of Appeals shall be residents of the City. No employee or contractor of the City Council may sit on the Zoning Board of Appeals. One member of the Zoning Board of Appeals shall also sit on the City Planning Commission. Each member of the Zoning Board of Appeals shall hold office for a term of three years. Terms shall be staggered to provide for as nearly as possible the appointment of an equal number of members each year. Those persons now serving as members of the
- 2820 Zoning Board of Appeals shall serve the balance of the terms for which they were appointed. All vacancies for unexpired terms shall be filled for the remainder of the term.
- (c) **Officers.** The Zoning Board of Appeals shall annually elect its own chairperson and vice-chairperson. The terms of the chairperson and vice-chairperson shall be for a period of one year.
- (d) **Alternate members.** The mayor, with the City Council's consent, shall appoint two alternate members for the Zoning Board of Appeals to sit as regular members of the Zoning Board of Appeals in the absence of a regular member. If a regular member is absent from or unable to attend one or more consecutive meetings of the Zoning Board of Appeals or for a period of more than 30 consecutive days, then alternate members may be called on a rotating basis to serve in the place of a regular member. For the purpose of reaching a decision on a case in which the regular member has abstained for reasons of conflict of interest, an alternate member may also be
- 2830 called. The alternate member having been appointed shall serve in the case until a final decision has been made. The alternate member shall have the same voting rights as a regular member of the Zoning Board of Appeals.
- (e) **Meetings.** All meetings of the Zoning Board of Appeals shall be held at the call of the chairperson and at such times as the Zoning Board of Appeals may determine. All hearings conducted by the Zoning Board of Appeals shall be open to the public. Minutes shall be kept of each meeting and the Zoning Board of Appeals shall record into the minutes all findings, conditions of approval, facts, and other relevant factors, and all its official actions. The vote of each member upon a question, or absence or abstention, shall be recorded into the minutes of the meeting.
- (f) **Rules and procedures.** The Zoning Board of Appeals shall adopt general rules and regulations governing its procedure and may make rules for the filing of appeals and other matters requiring its attention which shall not
- 2840 cause reasonable delays in the transaction of its business.
- (g) **Abstention.** A member of the Zoning Board of Appeals shall abstain from voting on any question on which they have a conflict of interest. Failure of a member to abstain in such cases shall constitute misconduct of office.
- (h) **Resignations.** When Zoning Board of Appeals members propose to resign, if reasonably feasible, they shall give notice of their intent in writing to the chairperson, and make the date of resignation effective in such a manner as to allow time for appointment of replacements. Failure to attend three consecutive regular meetings, or three of seven consecutive meetings, without recorded consent of the chairperson shall be construed as resignation from the Zoning Board of Appeals by absence. When a member dies or resigns (including resignation by absence), the chairperson shall promptly notify the mayor that a vacancy exists.

2850 Sec. 122-396. Powers and duties. (92)

- (a) The board of appeals shall hear and decide all questions and decisions regarding the following:
- (1) Interpretation of the official Zoning Map, including the interpretation of the location of zoning district boundaries when in doubt.
 - (2) The interpretation of the language of this chapter when its meaning is unclear, or when there is uncertainty as to whether the language applies to a particular situation.
 - (3) The hearing of requests for nonuse variances from the strict application of the provisions of this chapter in accordance with §122-370.
 - (4) The hearing of requests for appeals from any order, requirement, decisions, or determination made by an administrative body or official charged with the enforcement of this chapter in accordance with §122-371.
- 2860 (5) Hear and decide on any other matters referred to the Zoning Board of Appeals or upon which the Zoning Board of Appeals is required to pass under the terms of this chapter.
- (b) The Zoning Board of Appeals shall not change the zoning district classification of any property or make any

change in the terms of this chapter, and shall not take any action which would, as a result, make legislative changes in or negate any provisions of this chapter.

- (c) The Zoning Board of Appeals shall not have authority to hear appeals on decisions made by the Planning Commission or City Council regarding planned unit developments.
- (d) The Zoning Board of Appeals shall not have the authority to grant a use variance.

Sec. 122-397. General procedures. (93)

- (a) **Hearings.** The Zoning Board of Appeals shall hold a public hearing on each question submitted to it for decision. Such hearing shall be set within a reasonable time, not to exceed 45 days from the filing date of an appeal or variance request. Written notice of such hearing including the date, time, and place of the public hearing; the nature of the appeal; and a description of any property in question; shall be given to the appellant, if different than owner(s) of the property, to persons to whom real property is assessed within 300 feet of the boundary of the property subject to the request, regardless of whether the property or occupant is located within the boundaries of the City of Ypsilanti, and to the occupants of all structures within 300 feet of the premises. The notice shall be delivered personally or by mail, addressed to the respective owners and tenants at the address given in the last assessment roll. If a tenant's name is not known, the term "occupant" may be used. Notification need not be given to more than one (1) occupant of a structure, except that if a structure contains more than one (1) dwelling unit or spatial area owned or leased by different individuals, partnerships, businesses, or organizations, one (1) occupant of each unit or spatial area shall receive notice. In the case of a single structure containing more than four (4) dwelling units or other distinct spatial areas owned or leased by different individuals, partnerships, businesses or organizations, notice may be given to the manager or owner of the structure who shall be requested to post the notice at the primary entrance to the structure. The notice shall also be published in a newspaper of general circulation in the City. All notices shall be given at least 15 days prior to the public hearing. An affidavit of mailing shall be filed with the Zoning Board of Appeals prior to the public hearing. The Zoning Board of Appeals may recess a hearing to gather additional information, to make site inspections, or to engage in other activities as may be necessary to make a proper decision. The Zoning Board of Appeals shall reconvene the hearing within 35 days of the original hearing date. The reconvened hearing date shall be announced at the original hearing and this announcement shall constitute proper public notification.
- (b) **Decisions by the Board of Appeals.** The concurring vote of a majority of the entire membership of the Zoning Board of Appeals (three votes) shall be necessary to reverse any order, requirement, or decision of any administrative official; to effect any variance in the non-use terms of this chapter; or to decide any matter upon which the Zoning Board of Appeals is required to pass by this chapter.
- (c) **Time limit.** The Zoning Board of Appeals shall decide upon all matters within 90 days from the filing date. The time limit may be extended by written agreement between the applicant or appellant and the Zoning Board of Appeals.
- (d) **Representation.** Any person may appear on their own behalf at a hearing or may be represented by an agent or attorney.
- (e) **Conditions of approval.** The Zoning Board of Appeals may attach conditions to any affirmative action as it deems reasonable to minimize any detrimental effects of its decisions and to promote the purposes of this chapter. Such conditions shall be in accordance with [§122-326](#) and Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.), as amended. A performance guarantee may be required as a condition of an affirmative action when in accordance with [§122-317](#).
- (f) **Official record.** The decisions and orders of the Zoning Board of Appeals in disposing of an appeal or a request for a variance, along with any conditions attached, shall be entered into the official record for each case. Such record shall include the reasons for a determination, a summary of the evidence introduced, and the reasons for any conditions imposed.

Sec. 122-398. Decisions final. (96)

All decisions of the Zoning Board of Appeals are final. However, a person having an interest aggrieved by a decision may appeal to the circuit courts, as provided in Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.), as amended. Such an appeal must be filed within 30 days after the Zoning Board of Appeals certifies its decision in writing or approves the minutes of its decision.

Sec. 122-399. Time limitations. (97)

If a variance or other requested action is granted or authorized, the necessary permits shall be obtained and any authorized actions shall be begun within one year following the date of such variance or authorization and shall be completed as authorized by the permit or elsewhere in this chapter. Should the applicant/appellant fail to obtain such permits or fail to commence work within such subsequent period, it shall be presumed that the applicant/appellant

2920 has waived, withdrawn, or abandoned their appeal; and all permissions, authorizations, variances, and permits shall be deemed to be rescinded.

DRAFT 03-16-2017

Article IV: Districts

Division 1: Generally

Sec. 122-400. Establishment of Districts. (231)

Ypsilanti's Master Plan classifies the City into neighborhoods, corridors, centers, and special districts. These classifications are the basis for the regulation of these areas.

For the purposes of this chapter, the City is hereby divided into the following zoning districts having the names and symbols here shown:

Use-Based Districts

- P, Parks
- R1, Single-family residential district
- MD, Multiple dwelling residential district
- PMD, Production, Manufacturing and Distribution

Walkable Urban Districts

- CN-SF, Core Neighborhood Single Family
- CN-Mid, Core Neighborhood Mid
- CN, Core Neighborhood
- C, Center
- HC, Historic Corridor
- NC, Neighborhood Corridor
- GC, General Corridor
- HHS, Health and Human Services

Sec. 122-401. Zoning Map. (232)

- (a) The locations and boundaries of the zoning districts are hereby established as shown on a map adopted by the City Council. The map is entitled the "Zoning Map, City of Ypsilanti, Washtenaw County, Michigan," and must bear the date adopted or amended. It is the duty of the City mayor and clerk to authenticate such records by placing their official signatures thereon. Such map with all accompanying explanatory matter is hereby made a part of this chapter as if the matters and information set forth thereon were all fully described in this chapter.
- (b) In the Walkable Urban Districts the Zoning Map contains notations on property where building types noted in §122-465 are allowed in certain areas and required street construction or connections.
- (c) A copy of the Zoning Map shall be available for sale or distribution to the public. The Zoning Map shall be updated regularly.

Sec. 122-402. Application of chapter. (233)

- (a) Land uses are permitted specifically in the various zoning districts of this chapter. Where not specifically permitted, uses are thereby specifically prohibited unless construed to be similar to a use expressly permitted.
- (b) Except as otherwise provided in this chapter, erection of buildings and uses of land must conform to the specific provisions for the zoning districts involved. No land shall be redeveloped or a use commenced, expanded or continued within the City except as specifically, or by necessary implication, authorized by this chapter.
- (c) Lawful nonconforming structures and uses existing at the time of passage of this chapter are specifically governed by Article III, Division 3 "Nonconformities," and generally governed by this chapter.

Sec. 122-403. Interpretation of district boundaries. (234)

Where uncertainty exists with respect to the boundaries of the various districts as shown on the Zoning Map, the following rules apply:

- (a) Boundaries indicated as approximately following lot lines, the centerlines of streets or alleys, and City limits must be construed as following such lines.
- (b) Boundaries indicated as parallel to or extension of features indicated in subsection (a) of this section shall be so construed. Distances not specifically indicated on the official Zoning Map are determined by the scale of the map.

- (c) Where physical or natural features existing on the ground are at variance with those shown on the Zoning Map, or in other circumstances not covered above, the Zoning Board of Appeals must interpret the district boundaries.
- (d) Where one parcel is divided into two or more portions by reason of different zoning district classifications, each of these portions must be used independently of the others in respective zoning classifications; and for the purposes of applying the regulations of this chapter, each such portion must be considered as if in separate and different ownership. However, if the Zoning Board of Appeals finds that any portion of a lot so divided is inadequate in area for a viable use, such portion may be combined with an adjacent lot and/or rezoned as appropriate.

Sec. 122-404. Uses permitted as a right. (235)

Permitted uses, as identified in the divisions covering each district, are recognized as uses of land and buildings in certain districts which are harmonious with other such uses which may lawfully exist within the same district. A permitted use is subject to the general provisions, parking regulations, district intent, permit, certificate and site plan requirements found elsewhere in this chapter, but otherwise is considered to be a lawful use not requiring special or extraordinary controls or conditions, unless otherwise indicated in this chapter.

Sec. 122-405. Uses permitted under special approval. (236)

The uses identified as special uses in divisions covering each district are recognized as possessing characteristics of such unique and special nature (relative to location, off-site impacts, design, size, public service and utility needs, and other similar characteristics) as necessitating individual standards and conditions in order to safeguard the general health, safety and welfare of the community. Article III, Division 2 "Permits," Subdivision II "Special Land Uses," regarding procedure and requirements for special uses, applies to these uses.

Sec. 122-406. Zoning of vacated land. (237)

Vacated streets or alleys, or the divided portions thereof, are automatically given the same zoning classification as the private property to which they are attached upon vacation.

Sec. 122-407. Zoning of annexed land. (238)

Property duly annexed to the City will be zoned R1, single-family residential, upon annexation. However, the City Council may, in the annexation ordinance, designate an appropriate zoning designation upon annexation, based upon existing use of the property, the City's adopted master plan, or the use of surrounding properties.

Secs. 122-408 – 409. Reserved.

Division 2: Use Based Districts

Sec. 122-410. Purpose. (split from 231)

Outlying neighborhoods (outlying residential and multiple-family) and special districts (parks and production, manufacturing, and distribution) are areas where regulation by use and intensity is appropriate. These districts were primarily constructed after the Second World War, were developed with the automobile in mind as much as the individual, and generally were developed well after the advent of zoning regulations. These neighborhoods tend to be less dense and have stronger separation between commercial, residential, and industrial uses than do areas developed prior to the 1940s. The regulations set forth herein continue the separation of uses where prudent, enable the continuing integration of the automobile into daily life while maintaining transportation choices, reinforce connections between these and other neighborhoods, and respect the history of the neighborhoods.

3010

Secs. 122-411 – 414. Reserved.

Subdivision I: Park District (P)

Sec. 122-415. Purpose. (301)

The Park (P) district is designed to preserve green space for recreation and for preservation of natural resources. Temporary uses may be allowed to encourage use and vitality of these areas.

Sec. 122-416. Permissible Uses. (302)

In the Parks district, no uses shall be permitted except the following.

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES		NOTES	SPECIFIC REGULATIONS
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES			
Park	P		
Outdoor and indoor education areas	P		
Outdoor recreation areas such as swimming pools, tennis courts, and performance venues	P		
Conservation areas, wildlife preserves, forests preserves, arboreta, botanical or zoological gardens, public tree or plant nurseries	P		
Privately owned or operated uses accessory to City parks	S	Includes but not limited to concession stands, canoe liveries, or bicycle liveries.	
INFRASTRUCTURE			
Essential Services	P		Section 122-523
Solar Farms	S		Section 122-513
Alternative Energy	A		Section 122-513
SERVICES			
Cemetery	P		
Crematory	S		All principal buildings must be set back at least 75 feet from all property lines.
TEMPORARY USES			
Mobile food establishments	P		Section 122-335
URBAN AGRICULTURE			
Community Gardens	P		Section 122-525
Passive solar building	P		

Sec. 122-417. Non-Use and Dimensional Regulations. (303)**(a) Minimum Lot Width**

Determined by the use and the required off-street parking, loading, screening, and yard setbacks.

(b) Minimum Lot Size

Determined by the use and the required off-street parking, loading, screening, and yard setbacks.

(c) Minimum Setbacks for Principal Structures and Attached Accessory Structures

Front yard	25 feet	Minimum setbacks increase by one foot for each foot a building or structure exceeds 30 feet in height.
Side yard	15 feet	
Street Side yard	25 feet	
Rear yard	20 feet	

(d) Height

Maximum height	Equal to that of adjacent zoning district or building type along the property line. If different heights abut, the largest setback is required.	Subject to §122-613 .
----------------	---	---------------------------------------

(e) Parking Setbacks

Front & street side yard	10 feet
Side & rear yards	10 feet

(f) Fences

Front Yard	No more than 4' in height and 50% opacity	• Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. • Subject to §122-635 • Subject to §122-675
Side, Street Side, and Rear Yards	No more than 6' in height, no opacity restriction	

(g) Signs

Freestanding Signs (temporary)	Maximum area	10 sf	Permit not required.
	Maximum height	3 feet	
	All setbacks:	0 feet Subject to §122-675	
Freestanding Signs (permanent)	Maximum area	100 sf	Permit required.
	Maximum height	35 feet	
	Front setback	3 feet Subject to §122-675	
	Side, street side, and rear setback	10 feet Subject to §122-675	
	Maximum # signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	

Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Billboards	Location	adjacent to and visible from I-94, as defined by the Highway Advertising Act of 1972.	Permit required.
	Maximum Area	672 sf	
	Maximum Height	65'	
	Other restrictions	Subject to §122-675	

(h) Other Accessory Structures

Subject to Article VI, Division 4, "Accessory Structures, Porches, and Decks"

Secs. 122-418 – 419. Reserved.

Subdivision II. Single-Family Residential District (R1)

ORIGINAL: 251-253

Sec. 122-420. Purpose. (251)

The Single-Family Residential (R1) district is designed to provide an environment of predominantly low-density, single-family detached dwellings, along with related facilities such as schools and religious institutions.

Sec. 122-421. Permissible Uses. (252)

In the Single-Family Residential (R1) district, no uses shall be permitted except the following.

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	R1	NOTES	SPECIFIC REGULATIONS
RESIDENTIAL			
Single-Family Detached Dwelling	P	Manufactured and premanufactured dwellings may be located and installed according to same standards that would apply to a site-built single-family dwelling on the same lot.	
Home Occupation	A		Section 122-527
Family Child Care Home	A	1-6 children	Must be licensed by the state and must comply with the minimum state standards for such facilities.
Group Child Care Home	S	6-12 children	Section 122-521
Adult foster care family homes	A	1-6 adults, excludes facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities.	Must be licensed by the state and must comply with the minimum state standards for such facilities.
RECREATION, EDUCATION & PUBLIC ASSEMBLY			
Park	P		
Primary & Secondary Schools (public & private), less than 15,000 square foot footprint	S	Public schools are only subject to State regulations regarding location and construction.	Section 122-545
Post-secondary educational institutions (public & private), less than 15,000 square foot footprint	S	Public schools are only subject to State regulations regarding location and construction.	Section 122-545
Religious institution, less than 15,000 square foot footprint	S		Section 122-543
Municipal, county, regional & state service uses	S		Section 122-535
SERVICES			
Bed & Breakfast or Inn	S		Section 122-520
Farmers' Market	A		When accessory to a nonresidential use. Temporary use only.
Garage Sales	A		Section 122-524
INFRASTRUCTURE			
Essential Services	P		Section 122-523
Communication Devices	A		Article V, Division 3

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	R1	NOTES	SPECIFIC REGULATIONS
Alternative Energy	A		Section 122-513
GARDENS/COMMUNITY GARDENS			
Community Gardens	P		Exempt from area regulations in §122-422. Subject to §122-525
Toolhouses, sheds, garages, and other similar buildings for the storage of domestic supplies	A		Must meet accessory structure regulations for lot coverage and maximum floor area. Rear or side yard only.
Passive solar building	A		Must meet accessory structure regulations for lot coverage. Rear or side yard only. Must meet regulations in §122-422, with an exception for an up to 200 sq ft passive solar building if floor area of existing detached accessory structures are less than 200 sq ft or equal to the gross floor area of the ground floor of the principal structure. Maximum square footage is 800 sq ft.

3030

Sec. 122-422. Non-Use and Dimensional Regulations. (253)**(a) OVERALL SITE REGULATIONS****(1) Maximum Lot Coverage**

Residential Uses	35%
Non-residential Uses	50%

(2) Parking Setbacks *(non-residential uses only; residential uses covered by §122-682)*

Front & side street yard	Not allowed
Side and rear yards	10 feet

(3) Minimum Lot Width

Lot width	45 ft.
-----------	--------

(4) Outdoor Lighting

See §122-609

(b) PRINCIPAL AND ATTACHED ACCESSORY STRUCTURES*Also subject to Article VI, Division 4***(1) Height**

Maximum height	30 feet or 2.5 stories	See exceptions in §122-613.
----------------	------------------------	-----------------------------

(2) Residential Uses

Lot size, minimum	5,000 square feet	
Front yard setback, minimum	25 feet	Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.
Side yard setback, minimum	4 feet	
Side yards (combined) setback, minimum	12 feet	
Street Side yard setback, minimum	8 feet	
Rear yard setback, minimum	25 feet	
Corner Lots	Platted or of record after August 8, 1984	Front yard regulations apply to each street side of the corner lot. The rear yard requirements for a corner lot apply to the open space which is opposite and most distant from the front lot line as designated in the plat and/or in the request for a building permit.
	Platted or of record prior to August 8, 1984	Front yard regulations apply only along the front lot line as designated in the plat and/or in the request for a building permit. The yard along the second street must meet the requirements for side yards on corner lots as specified in the district regulations.
Usable floor area, minimum	500 sf	

(3) Non-residential uses

Front yard minimum	25 feet	Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.
Side yard minimum	8 feet	

(b) PRINCIPAL AND ATTACHED ACCESSORY STRUCTURES*Also subject to Article VI, Division 4*

Side yards (combined) minimum	Equal to the height of the structure or the setbacks required for residential uses, whichever is greater.	
Street side yard minimum	8 feet	
Rear yard minimum	25 feet	
Corner Lots	Platted or of record after August 8, 1984	Front yard regulations apply to each street side of the corner lot. The rear yard requirements for a corner lot apply to the open space which is opposite and most distant from the front lot line as designated in the plat and/or in the request for a building permit
	Platted or of record prior to August 8, 1984	Front yard regulations apply only along the front lot line as designated in the plat and/or in the request for a building permit. The yard along the second street must meet the requirements for side yards on corner lots as specified in the district regulations.

(c) DETACHED ACCESSORY STRUCTURES

Also subject to Article VI, Division 4

(1) Height

Maximum height	15 feet
----------------	---------

(2) Size of Accessory Buildings

Maximum Floor Area	The gross ground floor area of all accessory buildings must not exceed gross floor area of the ground floor of the principal structure, nor cause lot coverage regulations for all buildings and paved surfaces on-site to be exceeded.
--------------------	---

(3) Fences

Front Yard	No more than 4' height and 50% opacity	• Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. • Subject to §122-635 • Subject to §122-675
Side, Street Side, and Rear Yards	6' height max, no opacity restriction	

(4) Buildings Accessory to Residential Uses

Front yard	Not allowed	
Side yard minimum	3 feet	1 foot if lot line abuts an alley
Street Side yard	Not allowed	
Rear yard minimum	3 feet	1 foot if lot line abuts an alley, 12 feet for a through lot
Distance from principal structure, minimum	7 feet	Minimum distance to comply with fire regulations and/or building code, if greater than minimum listed. An attached enclosure or roof over a pathway between buildings on a lot, such as a breezeway, is exempt from this setback provided it is 8 feet or less in width and 15 feet or less in height.

(5) Buildings Accessory to Non-residential uses

Front yard	Not allowed	
Side yard minimum	3 feet	1 foot if lot line abuts an alley
Street Side yard minimum	8 feet	
Rear yard minimum	3 feet	1 foot if lot line abuts an alley, 12 feet for a through lot
Distance from principal structure minimum	5 feet or minimum to comply with fire regulations and building code, whichever greater.	

(d) SIGNS*Also subject to Article VI, Div 5***(1) Signs – Residential Uses**

(i) Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit not required.
	Maximum height	3 feet	
	All setbacks	0 feet Subject to §122-675	
(ii) Freestanding signs (permanent)	Not permitted		
(iii) Building-mounted signs (temporary)	Maximum area	0.5 square feet for each linear foot of building frontage or 12 square feet, whichever less	Permit not required.
(iv) Building-mounted signs (permanent)	Maximum area	1 sq ft	Permit not required.
(v) Billboards	Not permitted		

(2) Signs – Non-residential Uses

(i) Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit not required.
	Maximum height	3 feet	
	All setbacks	0 feet Subject to §122-675	
(ii) Freestanding signs (permanent)	Maximum Area	16 sf	Permit required.
	Maximum Height	6 feet	
	Front Setback	3 feet Subject to §122-675	
	Side, street side, and rear setback	10 feet Subject to §122-675	
	Maximum number of signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	
(iii) Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever less	Permit required.
(iv) Building-mounted signs (permanent)	Maximum Area	0.5 square feet for each linear foot of building frontage, or 12 square feet, whichever less	Permit required.
(v) Billboards	Not permitted		

Secs. 122-423 – 424. Reserved.

Subdivision III: Multiple Dwelling Residential District (MD)

3040

Sec. 122-425. Purpose. (261)

The multiple-family residential district is located adjacent to high traffic generators and major thoroughfares and corridors, and can serve as zones of transition between nonresidential districts and neighborhoods. It is designed to allow a multiple-family residential development, rental or owner-occupied, designed specifically for apartments, townhouses, and/or other housing types. It is further designed to insure sound development policies for areas having a concentration of multifamily units, while assuring an adequate supply of multiple-family living units in the housing mix of the City overall. Recreation, service, and retail uses are permissible as special land uses to allow residents to access everyday needs by foot, if they are not already within a quarter-mile walking distance.

Sec. 122-426. Permissible Uses. (262)

In the Multiple Dwelling (MD) district, no uses shall be permitted except the following.

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	MD	NOTES	SPECIFIC REGULATIONS
RESIDENTIAL			
Group Residences	S		Single-family building type only.
Townhomes/rowhomes	P		
Two-Family Dwelling	P		
Multiple Family Dwellings, maximum of 6 units per building	P		Responsible party for management must be on file with the City.
Multiple Family Dwellings, more than 6 units per building	S		Responsible party for management must be on file with the City.
Home Occupation	A		Section 122-527
Family Child Care Home	A	1-6 children	Must be licensed by the state and must comply with the minimum state standards for such facilities.
Group Child Care Home	S	6-12 children	Section 122-521
Group living with support staff, not licensed by State of Michigan	S	Includes supportive housing, rehabilitation housing, or dormitories.	
Adult foster care family homes	A	1-6 adults, day care and 24 hour care, excludes facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities.	Must be licensed by the state and must comply with the minimum state standards for such facilities.
Adult foster care small & group homes, adult congregate facilities	S	7 or more adults, licensed by State of Michigan	Section 122-511
Adult foster care facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities.	S		
RECREATION, EDUCATION & PUBLIC ASSEMBLY			
Park	P		
Indoor recreation	A		Section 122-529

USES	MD	NOTES	SPECIFIC REGULATIONS
Social facility for multiple dwelling residents and their guests	A		
Primary & Secondary Schools (public & private)	S	Public schools are subject to State regulations regarding location and construction.	Section 122-545
Post-secondary educational institutions (public & private)	S	Public schools are subject to State regulations regarding location and construction.	Section 122-545
Religious institution	S		Section 122-543
Municipal, county, regional & state service uses	S		Section 122-535
SERVICES			
Bed & Breakfast or Inn	S		Section 122-520
Child care centers and day care centers	S		Section 122-521
Nursing homes	S		Section 122-536
Medical or Dental Clinics, less than 5,000 square feet	S		
Financial services, including banks	S		Drive through facilities are not allowed in MD
Personal service establishments	A		
COMMERCIAL			
Food stores, excluding sale of alcohol, less than 15,000 square feet	S		
Farmers' Market	A		
Garage Sales	A		Section 122-524
RESTAURANTS			
Carry-out and/or delivery restaurant	S		Drive through facilities are not allowed in MD
Café or coffee shop	S		Drive through facilities are not allowed in MD
INFRASTRUCTURE			
Essential Services	P		Section 122-523
Communication Devices	A		Article V, Division 3
Alternative Energy	A		Section 122-513
Automobile Share Parking	A		
GARDENS / COMMUNITY GARDENS			
Community Gardens	P		Exempt from area regulations in §122-427 , subject to §122-525
Toolhouses, sheds and other similar buildings for the storage of domestic supplies	A		- Must meet accessory structure regulations for lot coverage and maximum floor area. - Rear or side yard only.

USES	MD	NOTES	SPECIFIC REGULATIONS
Passive solar building	A		• Must meet accessory structure regulations for lot coverage and maximum floor area. • Rear or side yard only. • Maximum square footage is 800 square feet.

3050

Sec. 122-427. Non-Use and Dimensional Regulations. (263)**(a) OVERALL SITE REGULATIONS***Also subject to Article VI***(1) Maximum Impervious Surface Lot Coverage**

Residential Uses	45%
Non-residential Uses	50%

(2) Parking Location and Setbacks

Front & side street yard	Not permitted.
Side and rear yards	10 feet

(3) Minimum Lot Width

Lot width for all buildings	45 ft.
-----------------------------	--------

(4) Outdoor LightingSee [Section 122-609](#)**(b) PRINCIPAL AND ATTACHED ACCESSORY STRUCTURES***Also subject to Article VI, Division 4***(1) Height**

Maximum height	65 feet or 6 stories	See exceptions in §122-613 .
----------------	----------------------	--

(2) Residential and Multifamily Uses

Minimum Lot Area	Two-family dwelling	6,000 sq. ft.
	Group living	6,000 sq. ft.
	Multiple-family	8,000 sq. ft.
	Ratio of Lot Size to Number of Rooms	The total number of rooms in a multiple dwelling structure may not be more than the area of the parcel in square feet divided by 1,400 square feet, exclusive of right-of-way.
Outdoor Space	A total of one hundred thirty (130) square feet of outdoor living space must be provided for each bedroom or studio/efficiency unit. Porches, balconies and improved roof areas may count toward the required outdoor living space, provided no such area is less than five (5) feet in width. Such outdoor areas must be buffered from streets and parking lots. Off-street parking areas, driveways, and accessory uses may not be counted as required open space.	
Front yard setback	25 feet	
Side yard setback	4 feet	For buildings with more than 6 units, 6 feet.
Side yard setback when abutting an R1 district	25 feet	
Side yard setback (combined)	12 feet	For buildings with more than 6 units, 14 feet
Street Side yard setback	8 feet	For buildings with more than 6 units, 15 feet
Rear yard setback	25 feet	
Distance between buildings	20 feet	
Corner Lots	Platted or of record after August 8, 1984	Front yard regulations apply to each street side of the corner lot. The rear yard requirements for a corner lot apply to the open space which is opposite and most distant from the front lot line as designated in the plat and/or in the request for a building permit.

(b) PRINCIPAL AND ATTACHED ACCESSORY STRUCTURES*Also subject to Article VI, Division 4*

	Platted or of record prior to August 8, 1984	Front yard regulations apply only along the front lot line as designated in the plat and/or in the request for a building permit. The yard along the second street must meet the requirements for side yards on corner lots as specified in the district regulations.
Usable floor area, minimum	1 Bedroom	600 sf
	2 Bedroom	800 sf
	3+ Bedroom	1,000 sf

(3) All Other Uses

Front yard setback	25 feet	
Side yard setback	6 feet	
Side yard setback (combined)	14 feet	
Street side yard setback	15 feet	
Rear yard setback	25 feet	
Corner Lots	Platted or of record after August 8, 1984	front yard regulations apply to each street side of the corner lot. The rear yard requirements for a corner lot apply to the open space which is opposite and most distant from the front lot line as designated in the plat and/or in the request for a building permit
	Platted or of record prior to August 8, 1984	front yard regulations apply only along the front lot line as designated in the plat and/or in the request for a building permit. The yard along the second street must meet the requirements for side yards on corner lots as specified in the district regulations.

(c) DETACHED ACCESSORY STRUCTURES

Also subject to Article VI, Division 4

(1) Height

Maximum height	15 feet
----------------	---------

(2) Size of Accessory Buildings

Maximum Floor Area	No limitations other than maximum impervious surface lot coverage.
--------------------	--

(3) Fences

Front Yard	No more than 4' height and 50% opacity	- Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. - Subject to §122-635 - Subject to §122-675
Side, Street Side, and Rear Yards	6' height max, no opacity restriction	

(4) Buildings Accessory to Residential Uses

Front yard	Not allowed	
Side yard	3 feet minimum	1 foot if lot line abuts an alley
Street Side yard	8 feet minimum	
Rear yard	3 feet minimum	1 foot if lot line abuts an alley, 12 feet for a through lot
Distance from principal structure	7 feet minimum	Minimum distance to comply with fire regulations and/or building code, if greater than 7 feet. An attached enclosure or roof over a pathway between structures on a lot, such as a breezeway, is exempt from this setback provided it is 8 feet or less in width and 15 feet or less in height.

(5) Buildings Accessory to Non-Residential Uses

Front yard	Not allowed	
Side yard	3 feet minimum	1 foot if lot line abuts an alley
Street Side yard	8 feet minimum	
Rear yard	3 feet minimum	1 foot if lot line abuts an alley, 12 feet for a through lot
Distance from principal structure	5 feet, or minimum to comply with fire regulations and building code, whichever greater.	

(d) SIGNS*Also subject to Article VI, Division 5***Signs**

Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit not required.
	Maximum Height	3 feet	
	All setbacks	0 feet minimum Subject to §122-675	
Freestanding Signs (permanent)	Maximum Area	16 sf	Permit required.
	Maximum Height	6 feet	
	Front Setback	3 feet minimum Subject to §122-675	
	Side, street side, and rear setback	10 feet minimum Subject to §122-675	
	Maximum number of signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever less	Permit required.
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or up to 32 sf each face of the building façade that faces a street, parking area, or on a façade where a public entrance is located	Permit required.
Billboards	Not permitted		

Secs. 122-428 – 429. Reserved.

Subdivision IV: Production, Manufacturing And Distribution District (PMD)

Sec. 122-430. Purpose. (291)

The Production, Manufacturing and Distribution (PMD) district is designed to create and sustain producing, manufacturing, storing, and distributing goods. These districts are generally located where buildings can be on large plots of contiguous land, serviced by railroad lines or major thoroughfares, and adequately served by required utilities and services. Uses are expected to generate waste, noise, odor, and truck traffic; however, uses should produce minimal external impacts that are detrimental in any way to other uses in the district or to properties in adjoining districts. Special uses are expected to produce undesirable external impacts and should, therefore, be located only where such impacts will not be detrimental to other uses in the PMD district or to properties in adjoining districts.

Sec. 122-431. Permissible Uses and Use-based Regulations. (292)

- (a) **Deleterious operations.** No activity, operation, or use is permitted on any property which by reason of the emission of odor, fumes, smoke, vibration, radiation, heat, glare, dust, soot, noise, or disposal of waste is deleterious to other permitted activities in the zoning district or is obnoxious or offensive to uses permitted in neighboring districts, or is harmful to the general health, safety, or welfare, of the community.
- (b) **Enclosed buildings.** All manufacturing, compounding, assembling, processing, packaging, or other industrial or business activity in must be conducted within a completely enclosed building, except as otherwise specified.
- (c) **Unclassified Uses.** Any unclassified use may be permitted as a Special Use by determination of the City Council after having been recommended by the Planning Commission. The City Council may impose any required setback and/or performance standards above and beyond the requirements of this chapter so as to insure public health, safety and general welfare.

<i>P=Principal; A=Accessory; S/Res= Special Land Use when adjacent to R-1, CN, CN-Mid, CN-SF, or MD zoning, otherwise permitted; S=Special Land Use</i>			
USES	PMD	NOTES	SPECIFIC REGULATIONS
INFRASTRUCTURE			
Essential Services	P		Section 122-523
Communication Devices	A		Article V, Division 3
Radio & Television Studios or Stations	P		
Radio and television towers, public utility microwaves, and public utility television transmitting towers, mobile communications towers, cellular phone towers and their accessory facilities	P		Section 122-566
Utility buildings including electric and gas service buildings and yards, telephone exchange buildings, electrical transformer stations and substations, gas regulator stations, and water and propane tank holders.	P		
Railroad yards not including manufacture and repair	S/Res		
Energy, electricity and heat generation plants	S	Includes solar farms and geothermal plants	Section 122-513
Landfill	S	May include anaerobic digester.	
Water or sewage treatment plant	S		
Biofiltration Facility	P		
Alternative Energy	A		Section 122-513
SERVICES			

*P=Principal; A=Accessory;
S/Res= Special Land Use when adjacent to R-1, CN, CN-Mid, CN-SF, or MD zoning,
otherwise permitted;
S=Special Land Use*

USES	PMD	NOTES	SPECIFIC REGULATIONS
Business and professional offices and services, 15,000 square feet or more	P		
Business and professional offices and showrooms	A		
Kennels, commercial	S/Res		Section 122-531
Offices for skilled trade services including but not limited to plumbing, electric, heating, and painting establishments	P		
Repair of appliances, machines or vehicles	P		
Self-storage facilities	P		
Printing services, including but not limited to: publishing, engraving, photo development, lithographing, silk screening and three-dimensional printing	P		Section 122-542
Construction and Landscape Contractors, contractor's yards, equipment and materials storage	P		
Recycling centers	S		
Adult Regulated Uses	S		Section 122-512
AUTO-ORIENTED			
Automobile Wash & Detailing	P		
Automobile Share Parking	A		
Truck Wash	S		
Automobile Repair	P		Section 122-515
Automobile rental (parking, storage, wash & repair)	P		
Vehicle &/or Recreational Vehicle Storage and Towing	S/Res		No storage of vehicles is permitted in setback from R-1, CN-SF, CN-Mid, CN, MD district.
Junkyards; Vehicle Wrecking, Salvage, Storage of Inoperable Vehicles	S		Section 122-530
RESEARCH			
Laboratories	S/Res		
Development & Research	S/Res		
PRODUCTION, MANUFACTURING & DISTRIBUTION			
Manufacture or processing of food products including brewing & distilling	P		
Craft manufacturing	P		
Medical Marijuana Growing/Manufacturing Facility	S		Section 122-533
Storage, warehousing, and wholesale distribution	S/Res	Outdoor storage is a special land use subject to section 122-539	

<i>P=Principal; A=Accessory; S/Res= Special Land Use when adjacent to R-1, CN, CN-Mid, CN-SF, or MD zoning, otherwise permitted; S=Special Land Use</i>			
USES	PMD	NOTES	SPECIFIC REGULATIONS
Central dry cleaning plants	S		
Clothing production	P		
Software, film, music, television and radio, and video game development & physical production	S/Res	Adult regulated uses are special land uses.	
Assembly and production, from prefabricated parts, of household appliances, electronic products, hardware products, and similar products	S/Res		
Processing or assembling of parts for production of finished equipment	S/Res		
Dry cleaning plants or laundries	S		
Manufacturing, Compounding, Processing, packing or treatment of such products as candy, cosmetics, drugs, perfumes, pharmaceuticals, and toiletries, except the rendering or refining of fats and oils	S/Res		
Manufacturing of alcohol; ammonia; bleaching powder or chlorine; asphalt, including refining; brick, tile or terra cotta; chemicals; concrete or cement products; lampblack; oil cloth or linoleum; paint, oil, shellac, turpentine, lacquer or varnish; petroleum products; plastics; soap; sodium compounds; tar distillation or tar products	S		
Manufacturing of machine tools, machinery, vehicles of all types, machine or vehicle components or that requires metal plating or galvanizing, plastic extrusion or molding or similar process	S		
Metal Foundry or fabricating plant and heavyweight casting	S		
Manufacture of construction materials	S		
Manufacturing of textiles, rubber or synthetic treated products	S		
Manufacture and repair of train cars, locomotives and track	S		
Animal slaughter and processing	S	Does not include aquaculture and aquaponics.	All activities must take place inside a fully enclosed building.
Ethanol, petroleum and fuel production, refining and storage	S		
Passive solar building	P		
Hydroponics, aquaculture, aquaponics, and similar raising of food	P		All activities must take place inside a fully enclosed building.
STORAGE			
Outdoor storage	S/Res		Section 122-539

3080

<i>P=Principal; A=Accessory; S/Res= Special Land Use when adjacent to R-1, CN, CN-Mid, CN-SF, or MD zoning, otherwise permitted; S=Special Land Use</i>			
USES	PMD	NOTES	SPECIFIC REGULATIONS
Storage of liquid and solid fuels	S		Section 122-652

Sec. 122-432. Non-use and Dimensional Regulations. (293)

(a) OVERALL SITE REGULATIONS			Also subject to Article VI
(1) Maximum Lot Coverage			
All impervious surfaces		90%	
(2) Parking Location and Setbacks			
Front & street side yard		10 feet	
Side and rear yards		10 feet	
From adjacent R-1, CN-SF, CN-Mid, CN, MD districts		15 feet	
(3) Minimum Lot Width			
Determined by the use and the required off-street parking, loading, screening and yard setbacks			
(4) Minimum Lot Area			
Determined by the use and the required off-street parking, loading, screening and yard setbacks			
(5) Outdoor Lighting			
See Section 122-609			
(6) Landscaping			
See section Article VI, Division 3 for additional guidelines regarding landscaping.			
Conflicting Land Use Screening	From adjacent R-1, CN-SF, CN-Mid, CN, MD, HHS districts	Section 122-634. Screening must be a solid wall or fence constructed of face brick, poured-in-place simulated face brick, precast brick face panels having simulated face brick, stone, or wood.	
Greenbelt	• Must be provided along the front yard and any street side yard. • Must be landscaped with a minimum of one (1) tree for every thirty (30) feet of frontage. No evergreens. • No less than 10' deep • Remainder must be landscaped in grass, ground cover, shrubs and other natural landscape materials. • Access drives from public rights-of-way through required greenbelts are permitted, but such drives may not be subtracted from the dimension used to determine the minimum number of trees required.		

(b) PRINCIPAL STRUCTURES AND ATTACHED ACCESSORY STRUCTURES*Also subject to Article VI***Height**

Maximum height	60 feet	See exceptions in §122-613 .
----------------	---------	--

Minimum Setbacks

Front yard	25 feet	Minimum setbacks increase by one foot for each foot a building or structure exceeds 30 feet in height.
Side yard	15 feet	
Street Side yard	15 feet	
Rear yard	20 feet	
From adjacent R-1, CN-SF, CN-Mid, CN, MD, HHS	25 feet	

(c) DETACHED ACCESSORY STRUCTURES

Also subject to Article VI, Division 4

(1) Height		
Maximum height	60 feet	Subject to §122-613
(2) Size of Accessory Buildings		
Maximum Floor Area	No limitations other than maximum lot coverage.	
(3) Fences		
Front Yard	No more than 6' height and 50% opacity	• Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. • Subject to §122-635 • Subject to §122-675
Side, Street Side, and Rear Yards	10' height max, no opacity restriction	
(4) Minimum Setbacks		
Front yard	25 feet	Minimum setbacks increase by one foot for each foot a building or structure exceeds 30 feet in height.
Side yard	15 feet	
Street Side yard	15 feet	
Rear yard	20 feet	
From adjacent R-1, CN-SF, CN-Mid, CN, MD, HHS	25 feet	

3090

(d) SIGNS			
Also subject to Article VI, Division 5			
(1) Signs – Residential Uses			
Freestanding Signs (temporary)	Maximum Area	10 sf	Permit not required.
	Maximum height	3 feet	
	All Setbacks:	0 feet; Subject to §122-675	
Freestanding signs (permanent)	not permitted		n/a
Building-mounted signs (temporary)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit not required.
Building-mounted signs (permanent)	Maximum Area	1 sf	Permit not required.
Billboards	Location	adjacent to and visible from I-94, as defined by the Highway Advertising Act of 1972.	Permit required.
	Maximum Area	672 sf	
	Maximum Height	65'	
	Other restrictions	Subject to §122-675	
(2) Signs – Non-residential Uses & Group Living			
Freestanding Signs (temporary)	Maximum Area	10 sf per sign	Permit required.
	Maximum height	8 feet	
	All setbacks:	0 feet; Subject to §122-675	
	max # signs	no more than 1 per 20' frontage on primary face and 1 per 50' on secondary face	
Freestanding Signs (permanent)	Maximum Area	16 sf	Permit required.
	Maximum Height	6 feet	
	Front Setback	3 feet; Subject to §122-675	
	Side, street side, and rear setback	10 feet; Subject to §122-675	
	Maximum # signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Billboards	Location	Must be adjacent to and visible from I-94, as	Permit required.

		defined by the Highway Advertising Act of 1972.	
	Maximum Area	672 sf	
	Maximum Height	65'	
	Other restrictions	Subject to §122-675	

Secs. 122-433 – 434. Reserved.

Division 3: Walkable Urban Districts

Sec. 122-435. Purpose. (271)

Core neighborhoods, corridors, and centers are classified as walkable urban places, where the regulations go beyond use or intensity to reinforce the context of the built environment through form and scale. The office district as laid out in the Master Plan, included here as Health and Human Services, has been classified as a walkable urban area because it is surrounded by Neighborhoods, Centers, and Corridors, and has an underlying street network and mixture of uses. These districts were primarily developed prior to the 1940s, and around the concept that individuals would not be driving in the course of daily business. These districts are still places where a person can walk, bike, or ride transit to work and to fulfill most shopping and recreation needs; they allow for the use of automobiles and freight vehicles, but do not require them. They are largely supported through a network of interconnected, tree-lined streets, diverse housing choices, a mix of commercial and residential uses, and public transit. The regulations set forth herein are meant to encourage a sensible mix of compatible uses, to enable residents to live without a personal vehicle, and to respect the history of the neighborhoods.

Secs. 122-436 – 439. Reserved.

Subdivision I: Core Neighborhoods (CN-Sf, CN-Mid, CN)

Sec. 122-440. Purpose. (from 271)

Core neighborhoods are built on a grid street network connected to the adjacent business districts. They border center districts or other core neighborhoods. These neighborhoods have a range of residential building types, with religious institutions, schools, stores and automobile filling stations intermixed. There are three types of core neighborhoods:

- (a) Core Neighborhood Single Family (CN-SF). These neighborhoods are east of Depot Town and north of Michigan Avenue, known as the historic eastside. Housing types include mansions, estates, houses, and cottages. Residential uses are restricted to single-family; neighborhood businesses are limited.
- (b) Core Neighborhood Mid (CN-Mid). These neighborhoods generally abut the Core Neighborhoods, and offer a less dense and less intense residential area with opportunities for accessibly-placed low-intensity walkable, neighborhood businesses. Housing types range from mansions to cottages, with multiple-family and single-family uses. This zoning may also be used as a transition zone between single-family districts and mixed use districts.
- (c) Core Neighborhoods (CN). These neighborhoods directly border center districts and have a variety of housing types, ranging from cottages to apartment buildings. This district affords opportunities for accessibly-placed walkable, neighborhood businesses.

Sec. 122-441. Permissible Uses. (272)

In the Core Neighborhood districts, no uses shall be permitted except the following.

<i>P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted</i>					
USES	CN-SF	CN-MID	CN	NOTES	SPECIFIC REGULATIONS
RESIDENTIAL					
Single-Family Detached Dwelling	P	P	P		
Single-Family Attached Dwellings		P	P		In "townhome" building type only
Accessory Dwelling Unit	--	A	A		
Two-family dwelling units	--	P	P		
Multiple Family Dwellings, maximum of 4 units per building	--	S	P		
Multiple Family Dwellings, more than 4 units per building	--	--	S		
Apartments located above ground floor of permitted nonresidential uses	--	--	P		
Home Occupation	A	A	A		Section 122-527
Family Child Care Home	A	A	A	1-6 children	Must be licensed by the state and must comply with the minimum state standards for such facilities.
Group Child Care Home	S	S	S	6-12 children	Section 122-521
Adult foster care family homes	A	A	A	1-6 adults, day care and 24 hour care	Must be licensed by the state and must comply with the minimum state standards for such facilities.
Group residence	--	--	S		Section 122-526
Roominghouse	--	--	S		

Group living with support staff, not licensed by State of Michigan	--	--	S	Includes supportive housing, rehabilitation housing or dormitories.	Section 122-548
Adult foster care small & group homes, adult congregate facilities	--	S	S	7 or more adults. Licensed by State of Michigan.	Section 122-511
Adult foster care facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities.	--	--	S		
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES					
Park	P	P	P		
Indoor recreation	--	--	A		Section 122-529
Primary & Secondary Schools (public & private)	S	S	S	Public schools are only subject to State regulations regarding location and construction.	Section 122-545
Post-secondary educational institutions (public & private)	S	S	S	Public schools are only subject to State regulations regarding location and construction.	Section 122-545
Religious institution	S	S	S		Section 122-543
Private assembly, including banquet hall	--	--	S		
Municipal, county, regional, & state service uses	S	S	S		Section 122-535
Public Art	A	A	A		
SERVICES					
Bed & Breakfast or Inn	S	S	S		Section 122-520
Funeral Homes	--	S	S		
Nursing Homes	--	S	S		Section 122-536
Medical or Dental Offices, less than 5,000 square feet	--	S	S		
COMMERCIAL					
Arts & crafts studios	--	--	S		
Food stores, excluding sale of alcohol, less than 15,000 square feet	S	S	S		
Farmers' Market	A	A	A		When accessory to a non-residential use.
Garage Sales	A	A	A		Section 122-524
RESTAURANTS					
Carry-out and/or delivery restaurant	--	--	S		

Café or coffee shop	--	--	S		
AUTO-ORIENTED					
Automobile Filling Station - no repair	S	S	S		Section 122-516
Automobile Share Parking	--	--	A		
INFRASTRUCTURE					
Essential Services	P	P	P		Section 122-523
Communication Devices	A	A	A		Article V, Division 3
Alternative Energy	A	A	A		Section 122-513
GARDENS/COMMUNITY GARDENS					
Community gardens	P	P	P		Section 122-525
Passive solar building	A	A	A		• Must meet accessory building regulations for building type. • Maximum square footage is 800 square feet.
Toolhouses, sheds, and other similar buildings for the storage of domestic supplies	A	A	A		Must meet accessory building regulations for building type.

<i>For most non-use and dimensional requirements, see Subdivision V of this Division.</i>			
<i>Also subject to Article VI</i>			
	Maximum # signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 8sf.	
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Building-mounted signs (permanent)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit required.
Billboards	not permitted		n/a

3130 **Secs. 122-443 – 444. Reserved.**

Subdivision II: Center (C)

Sec. 122-445. Purpose. (271)

These are mixed-use areas with historic buildings. These are the places where people shop, go to school, live, come to work, visit, drop by City Hall, eat, gather and have fun. They host events that bring thousands of visitors each year and bring the City together as a community. The intent of the zoning district is preserve the urban form, walkable nature and vibrant mix of uses in these areas.

Sec. 122-446. Permissible Uses. (272)

In the Center district, no uses shall be permitted except the following.

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	C	NOTES	SPECIFIC REGULATIONS
RESIDENTIAL			
Single-family attached dwellings	P		In "Townhome" building type only
Multiple Family Dwellings	P		In "Apartment Building" building type only
Apartments located above ground floor of permitted nonresidential uses	P		
Home Occupation	A		Section 122-527
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES			
Museums & libraries	P		
Parks	P		
Public Art	A		
Indoor recreation	P		
Performance venues/theaters	P		
Municipal, county, regional & state service uses	P	Only subject to State regulations regarding location and construction.	Section 122-535
Post-secondary educational institutions (public & private)	P	Public schools are only subject to State regulations regarding location and construction.	Section 122-545
INFRASTRUCTURE			
Essential Services	P		Section 122-523
Communication Devices	A		Article V, Division 3
Alternative Energy	A		Section 122-513
Public & Private Transportation Passenger Terminals	S		Section 122-541
SERVICES			
Business and professional offices and services	P		
Financial services, including banks	P		No drive through or drive-in facilities are permitted in C.
Personal service establishments	P		
Body Art Facilities	P		

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	C	NOTES	SPECIFIC REGULATIONS
Printing services, including but not limited to: publishing, engraving, photo development, lithographing, silk screening and three-dimensional printing	S		
Hotels & motels	P		
Child Care Centers	P		Section 122-521
Laundromats and dry cleaners	P		No dry cleaning on premises.
Medical or dental clinics	P		
Medical Marijuana Dispensary	P		Section 122-532
Catering services	A		
Self-storage	S		Section 122-546
COMMERCIAL			
Retail stores	P		
Resale stores	P		
Arts & crafts studios	P		
Food stores, excluding sale of alcohol	P		
Food stores less than 15,000 square feet, with sale of alcohol	S		
Food stores greater than 15,000 square feet, with sale of alcohol	P		
Farmers' market and other open-air markets	P		
Auction houses	P		Section 122-514
RESTAURANTS			
Carry-out and/or delivery restaurant	P		
Café or coffee shop	P		
Sit-down	P		
Bar/Lounge	P		
Tasting room and/or restaurant	A		Carry-out sales allowed with proper licenses.
Outdoor cafes	A		Section 122-540
Fast Food	P		No drive through or drive-in facilities are permitted in C.
AUTO-ORIENTED			
Parking lot	S	Permitted as an accessory use without special use permit.	Section 122-519
Parking Garage	S		Section 122-518
Automobile Share Parking	A		
PRODUCTION, MANUFACTURING & DISTRIBUTION			

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	C	NOTES	SPECIFIC REGULATIONS
Microbrewer/ small distiller /small wine maker	P		Carry-out sales allowed with proper licenses.
TEMPORARY USES			
Mobile Food Establishments	P		Section 122-335
PERFORMANCE OR STRUCTURES REQUIRING SPECIAL LAND USE			
Operation between 2 a.m. and 6 a.m. during any 24-hour period	P		
Sale of alcoholic beverages for consumption off the premises, not otherwise specified above.	S		

3140

Sec. 122-447. Non-use and dimensional requirements for site improvements not regulated by building type.

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

(a) Outdoor Lighting			
See Section 122-609			
(b) Fences			
Front Yard & Street Side Yard	Not permitted, except for off-street parking screening or otherwise permitted by Planning Commission	- Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. - Subject to §122-635 - Subject to §122-675	
Side & Rear Yards	6' height max, no opacity restriction		
(c) Detached Accessory Buildings			
No more than two detached accessory buildings are permitted per parcel.			
(d) SIGNS			
(1) Residential Uses			
Freestanding Signs (temporary)	Maximum Area	10 sf	Permit not required
	Maximum height	3 feet	
	All setbacks	0 feet Subject to §122-675	
Freestanding signs (permanent)	not permitted		N/A
Building-mounted signs (temporary)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit not required
Building-mounted signs (permanent)	Maximum Area	1 sf	Permit not required
Billboards	not permitted		n/a
(2) Non-residential Uses & Group Living			
Freestanding Signs (temporary)	Maximum Area	10 sf total	Permit required
	Maximum height	3 feet	
	All setbacks	0 feet Subject to §122-675	
Sidewalk Signs (freestanding temporary signs in the	Max size of 6sf per face, maximum 2 faces, max height of 4 feet.		Permit required
	Must allow for a 5' clear path of travel on at least one side.		
	May only be displayed during business hours.		
	Sidewalk signs must be constructed of durable wood, metal,		

For most non-use and dimensional requirements, see Subdivision V of this Division.			
Also subject to Article VI			
public ROW)	or plastic. Any fabric shall be affixed in place on all sides.		
	Subject to §122-675		
	Maximum number of signs	one per business	
Freestanding Signs (permanent)	Not Permitted		
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required
Overhead banners (building-mounted signs that span a public right-of-way)	The design, method of installation, and location of overhead banners must not endanger persons using any part of the public right-of-way or unduly interfere with the movement of people.		Permit required
	Minimum height to bottom of banner is 18 feet.		
	Must not be located closer than 10 feet to an intersection.		
	Shall not be more than 4 feet in height.		
	No more than one overhead banner shall be placed per block at any given time.		
	Overhead banners may remain in place for no longer than thirty days.		
	When located spanning a State trunkline, must conform to PA 200 of 1969 and obtain a permit from MDOT.		
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required
Billboards	not permitted		

Secs. 122-448 – 449. Reserved.

Subdivision III: Corridors (HC, NC, GC)

Sec. 122-450. Purpose. (271)

Corridors are mixed-use and commercial areas located along the arteries of the City, such as Washtenaw, Huron, Hamilton, Michigan, Harriet, and River.

- (a) Historic Corridor (HC). Historic corridors are located primarily in the Historic District, and are on Cross Street, Huron Street, Hamilton Street, and River Street. These corridors are lined with historic buildings and are integrated into the adjacent neighborhoods and centers. The intent of this district is to preserve the walkability, character and historic nature of these streets, while allowing for adaptive re-use of historic buildings.
- (b) Neighborhood Corridor (NC). Neighborhood corridors have a linear land pattern and are adjacent to residential neighborhoods. The size, form and scale of buildings and the type and intensity of uses should be complementary to abutting single-family or core neighborhoods, including less intense multiple-family residential building types and uses.
- (c) General Corridor (GC). General corridors are located along roads with heavy traffic and have commercial establishments, restaurants, offices, and other businesses that are geared toward automobile traffic. Multiple-family residential building types and uses are appropriate in this district.

Sec. 122-451. Permissible Uses. (272)

In the Corridor districts, no uses shall be permitted except the following.

<i>P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted</i>					
USES	HC	NC	GC	NOTES	SPECIFIC REGULATIONS
RESIDENTIAL					
Single-Family Detached Dwelling	P	--	--		
Single-Family Attached Dwelling	--	P	P		In "Townhome" building type only
Accessory Dwelling Unit	A	--	--		
Two-family dwelling units	P	P	P		
Multiple Family Dwellings, maximum of 4 units per building	P	P	P		
Multiple Family Dwellings, more than 4 units per building	S	S	P		Section 122-534
Apartments located above ground floor of permitted nonresidential uses	P	P	P		
Home Occupation	A	A	A		Section 122-527
Family Child Care Home	A	A	A	1-6 children	Must be licensed by the state and must comply with the minimum state standards for such facilities.
Group Child Care Home	A	A	A	6-12 children	Section 122-521
Adult foster care family homes	A	A	A	1-6 adults	Must be licensed by the state and must comply with the minimum state standards for such facilities.
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES					
Parks	P	P	P		

<i>P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted</i>					
USES	HC	NC	GC	NOTES	SPECIFIC REGULATIONS
Outdoor recreation	--	S	P		Section 122-529
Museums & libraries, less than 15,000 square feet	P	P	--		
Museums & libraries 15,000 square feet or more	S	S	--		
Primary & Secondary Schools (public & private)	S	S	--	Public schools are only subject to State regulations regarding location and construction.	Section 122-545
Post-secondary educational institutions (public & private)	S	S	--	Public schools are only subject to State regulations regarding location and construction.	Section 122-545
Religious institution	S	S	--		Section 122-543
Private assembly, including banquet halls	S	S	--		
Indoor recreation less than 15,000 square feet	--	P	P		
Indoor recreation 15,000 square feet or more	--	--	P		
Municipal, county, regional & state service uses	S	P	P		Section 122-535
Public Art	A	A	A		
SERVICES					
Business and professional offices, less than 15,000 square feet	P	P	P		
Business and professional offices, 15,000 square feet or more	--	S	P		
Financial services, including banks, less than 15,000 square feet	P	P	P		Drive through or drive-in facilities require special land use
Financial services, including banks, 15,000 square feet or more	--	S	P		Drive through or drive-in facilities require special land use.
Homeless Shelter	--	--	P		Section 122-528
Personal service establishments, less than 15,000 square feet	P	P	P		
Personal service establishments, 15,000 square feet or more	--	--	P		
Body art facilities	--	--	P		
Offices for skilled trade services including but not limited to plumbing, electric, heating, and painting establishments	--	S	P		Section 122-537

<i>P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted</i>					
USES	HC	NC	GC	NOTES	SPECIFIC REGULATIONS
Printing services, including but not limited to: publishing, engraving, photo development, lithographing, silk screening and three-dimensional printing	--	S	S		Section 122-542
Bed & Breakfast or Inn	P	S	--		Section 122-520
Hotels & motels	--	--	P		
Child Care Centers	S	P	P		Section 122-521
Funeral homes	S	S	S		
Laundromats and dry cleaners, less than 15,000 square feet	--	P	P		No dry cleaning on premises.
Laundromats and dry cleaners, 15,000 square feet or more	--	--	P		No dry cleaning on premises.
Nursing Homes	S	--	S		Section 122-536
Medical or dental clinics, less than 10,000 square feet	P	P	P		
Medical or dental clinics, 10,000 square feet or more	S	S	P		
Veterinary hospitals and clinics	--	S	S		Section 122-549
Kennels, commercial	--	--	S		Section 122-531
Substance abuse treatment facilities	--	--	S		Section 122-547
Catering services, less than 15,000 square feet	P	P	P		
Catering services, 15,000 square feet or more	--	--	P		
Self-storage	--	--	P		Section 122-546
COMMERCIAL					
Retail stores, less than 15,000 square feet	S	P	P		
Retail stores, greater than 15,000 square feet	--	--	P		
Resale stores	--	P	P		
Arts & crafts studios	P	P	P		
Food stores, excluding sale of alcohol, less than 15,000 square feet	S	P	P		
Food stores, with sale of alcohol, less than 15,000 square feet	--	S	P		
Food stores greater than 15,000 square feet with or without sale of alcohol	--	--	P		
Commercial Greenhouse			P		
Farmers' market and other open-air markets	--	P	P		

<i>P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted</i>					
USES	HC	NC	GC	NOTES	SPECIFIC REGULATIONS
Outdoor retail sales	--	S	S		Section 122-538
RESTAURANTS					
Carry-out and/or delivery restaurant	--	P	P		
Café or coffee shop	P	P	P		
Sit-down, with seating limit of 50 seats	P	P	P		
Sit-down, no seating limit	--	--	P		
Bar/Lounge	--	S	P		
Tasting room and accessory to microbrewer/ small distiller/ small wine maker	--	S	P		Carry-out sales allowed with proper licenses.
Fast Food	--	S	P		Must be located on major thoroughfare. Drive through or drive-in facilities require special land use.
Drive through restaurant of any type	--	--	S		Section 122-522
Outdoor cafes	A	A	A		Section 122-540
AUTO-ORIENTED					
Parking lot	--	--	S	Permitted as an accessory use without special use permit.	Section 122-519
Parking Garage	--	--	S		Section 122-518
Automobile Sales	--	--	S		
Automobile Filling Station - no repair	--	S	S		Section 122-516
Automobile Filling Station with repair	--	--	S		Sections 122-516 and 122-515
Automobile Wash & Detailing	--	--	S		
Automobile Repair	--	--	S		Section 122-515
Automobile Share Parking	A	A	A		
Automobile rental or share organization (parking, storage, wash & repair)	--	--	S		
Vehicle, Recreational Vehicle, Storage and Towing	--	--	S		
RESEARCH					
Laboratories	--	--	S		
Research & Development	--	--	S		
PRODUCTION, MANUFACTURING & DISTRIBUTION					
Craft production, clothing production or food production, less than 16,000 square feet	--	P	P		

<i>P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted</i>					
USES	HC	NC	GC	NOTES	SPECIFIC REGULATIONS
Craft production, clothing production or food production, 16,000 square feet or greater	--	--	S		
Microbrewer/ small distiller /small wine maker, less than 16,000 square feet	--	P	P		
Microbrewer/ small distiller /small wine maker, 16,000 square feet or greater	--	--	S		Carry-out sales allowed with proper licenses.
Wholesale or distribution facility with total gross floor area of less than 16,000 square feet	S	S	P		
Wholesale or distribution facility with total gross floor area 16,000 square feet or greater	--	--	S		
Medical Marijuana Growing/Manufacturing Facility	--	--	S		Section 122-533
TEMPORARY USES					
Mobile Food Establishments	--	P	P		Section 122-335
INFRASTRUCTURE					
Essential Services	P	P	P		Section 122-523
Communication Devices	A	A	A		Article V, Division 3
Alternative Energy	A	A	A		Section 122-513
GARDENS/COMMUNITY GARDENS					
Passive solar building	A	A	A		Must meet accessory structure regulations for building type. Maximum square footage is 800 square feet in the HC zoning district.
Community gardens	--	A	A		Section 122-525
PERFORMANCE OR STRUCTURES REQUIRING SPECIAL LAND USE					
Operation between 2 a.m. and 6 a.m. during any 24-hour period	--	S	S		
Drive through facilities	--	S	S		Section 122-522
Ongoing outdoor retail sales or display	--	S	S		Section 122-538
Outdoor storage	--	S	S		Section 122-539

Sec. 122-452. Non-use and dimensional requirements for site improvements not regulated by building type.

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

(a) Outdoor Lighting

See Section 122-609

(b) Fences

Front Yard and Street Side Yard	No more than 6' height	- Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. - Subject to §122-635 - Subject to §122-675
Side and Rear Yards	10' height max	

(c) Detached Accessory Buildings

No more than two detached accessory buildings are permitted per parcel.

(d) SIGNS

(1) Residential Uses

Freestanding Signs (temporary)	Maximum Area	10 sf	Permit not required.
	Maximum height	3 feet	
	All setbacks	10 feet Subject to §122-675	
Freestanding signs (permanent)	not permitted		
Building-mounted signs (temporary)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit not required.
Building-mounted signs (permanent)	Maximum area	1 sf	Permit not required.
Billboards	not permitted		

(2) Non-residential Uses & Group Living

Freestanding Signs (temporary)	Maximum Area	10 sf per sign	Permit required.
	Maximum height	8 feet	
	All setbacks	10 feet Subject to §122-675	
	Maximum # of signs	No more than 1 per 20' of lot frontage on primary lot frontage and 1 per 50' on secondary lot frontage	
Sidewalk Signs (freestanding temporary signs in the	Not permitted in NC or GC.		Permit required.
	Max size of 6sf per face, maximum 2 faces, max height of 4 feet.		
	Must allow for a 5' clear path of travel on at least one side.		

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

public ROW)	May only be displayed during business hours.		
	Sidewalk signs must be constructed of durable wood, metal, or plastic. Any fabric shall be affixed in place on all sides.		
	Subject to §122-675		
	max # signs	1 per business	
Freestanding Signs (permanent)	Maximum Area	HC & NC: 20 sf; GC: 100 sf	Permit required.
	Maximum Height	10 feet	
	Front Setback	3 feet from lot line or 10 ft from back of curb, whichever greater distance from roadway. Subject to §122-675	
	Side, street side, and rear setback	10 feet Subject to §122-675	
	Maximum # signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 50% of the area of the sign on the primary face.	
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Overhead banners (building-mounted signs that span a public right-of-way)	Not permitted in NC or GC.		Permit required.
	The design, method of installation, and location of overhead banners must not endanger persons using any part of the public right-of-way or unduly interfere with the movement of people.		
	Minimum height to bottom of banner is 18 feet.		
	Must not be located closer than 10 feet to an intersection .		
	Shall not be more than 4 feet in height.		
	No more than one overhead banner shall be placed per block at any given time.		
	Overhead banners may remain in place for no longer than thirty days.		
	When located spanning a State trunkline, must conform to PA 200 of 1969 and obtain a permit from MDOT.		
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Billboards	not permitted		

Secs. 122-453 – 459. Reserved.

Subdivision IV: Health And Human Services (HHS)**Sec. 122-460. Purpose. (271)**

The Health and Human Services district is located on either side of Towner between Prospect and Arnet Streets. A cluster of office, health and human service uses are in this district. The intent of the district is to require a more urban form through redevelopment of parking lots and reconnecting the street grid and circulation system.

Sec. 122-461. Permissible Uses. (272)

In the Health and Human Services district, no uses shall be permitted except the following.

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	HHS	NOTES	SPECIFIC REGULATIONS
RESIDENTIAL			
Single-Family Attached Dwelling	P		In "Townhome" building type only
Two-family dwelling	P		
Multiple Family Dwellings, maximum of 6 units per building	P		
Multiple Family Dwellings, more than 6 units per building	S		Section 122-534
Apartments located above ground floor of permitted nonresidential uses	P		
Home Occupation	A		Section 122-527
Group living with support staff, not licensed by State of Michigan	P	Includes supportive housing, rehabilitation housing or dormitories.	Section 122-548
Family Child Care Home	A	1-6 children	Must be licensed by the state and must comply with the minimum state standards for such facilities.
Group Child Care Home	A	6-12 children	Section 122-521
Adult foster care family homes	A	1-6 adults, day care and 24 hour care Excludes facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities.	Must be licensed by the state and must comply with the minimum state standards for such facilities.
GROUP LIVING			
Group residence, maximum of 6 residents	P		Section 122-526
Group residence with 7 or more residents	S		Section 122-526
Adult foster care small & group homes, adult congregate facilities	P	7 or more adults, licensed by State of Michigan	Section 122-511
Adult foster care facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities.	S		
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES			
Parks	P		

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	HHS	NOTES	SPECIFIC REGULATIONS
Public Art	A		
Indoor recreation	P		
Municipal, county, regional & state service uses	P		Section 122-535
Post-secondary educational institutions (public & private)	S		Section 122-545
Outdoor recreation	A		Section 122-529
INFRASTRUCTURE			
Essential Services	P		Section 122-523
Communication Devices	A		Article V, Division 3
Alternative Energy	A		Section 122-513
SERVICES			
Business and professional offices and services	P		
Financial services, including banks	P		Drive through or drive-in facilities require special land use
Adult drop-in center	P		Section 122-510
Homeless Shelter	P		Section 122-528
Personal service establishments	P		
Child Care Centers	P		Section 122-521
Funeral homes	S		
Nursing Homes	P		Section 122-536
Medical or dental clinics	P		
Hospitals	P		
Substance abuse treatment facilities	S		Section 122-547
Catering services	P		
COMMERCIAL			
Retail stores less than 15,000 square feet	P		
Food stores, excluding sale of alcohol	P		
Farmers' market and other organized markets	P		
RESTAURANTS			
Carry-out and/or delivery restaurant	P		
Café or coffee shop	P		
Cafeteria	A		
AUTO-ORIENTED			
Parking Garage	S		Section 122-518
Automobile Share Parking	A		
RESEARCH			
Laboratories	P		
TEMPORARY USES			

<i>P=Principal, A=Accessory, S=Special Land Use</i>			
USES	HHS	NOTES	SPECIFIC REGULATIONS
Food concession sales	P		Section 122-335
URBAN AGRICULTURE			
Community gardens	A		Exempt from area regulations in §122-462, subject to §122-525
Toolhouses, sheds and other similar buildings for the storage of domestic supplies	A		Must meet accessory structure regulations for building type.
Passive solar building	A		Must meet accessory structure regulations for building type.
PERFORMANCE OR STRUCTURES REQUIRING SPECIAL LAND USE			
Operation between 2 a.m. and 6 a.m. during any 24-hour period	S		

Sec. 122-462. Non-use and dimensional requirements for site improvements not regulated by building type.

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

(a) Fences			
Front yard, street side yard	No more than 6' height and 50% opacity	Opacity is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence. • Subject to §122-635 • Subject to §122-675	
Side, and rear yards	10' height max, no opacity restriction		
(b) Outdoor Lighting			
See Section §122-609			
(c) Detached Accessory Buildings			
No more than two detached accessory buildings are permitted per parcel.			
(d) SIGNS			
(1) Residential Uses			
Freestanding Signs (temporary)	Maximum Area	10 sf	Permit not required.
	Maximum height	3 feet	
	All setbacks	10 feet Subject to §122-675	
Freestanding signs (permanent)	not permitted		
Building-mounted signs (temporary)	Maximum Area	1/2 sf per foot of building frontage or 12 sf, whichever is less	Permit not required.
Building-mounted signs (permanent)	Maximum area	1 sf	Permit not required.
Billboards	not permitted		
(2) Non-Residential Uses & Group Living			
Freestanding Signs (temporary)	Maximum Area	10 sf per sign	Permit required.
	Maximum height	8 feet	
	All setbacks	10 feet Subject to §122-675	
	Maximum # of signs	No more than 1 per 20' of lot frontage on primary frontage and 1 per 50' on secondary frontage	

For most non-use and dimensional requirements, see Subdivision V of this Division.

Also subject to Article VI

Sidewalk Signs (freestanding temporary signs in the public ROW)	not permitted		
Freestanding Signs (permanent)	Maximum Area	20 sf	Permit required.
	Maximum Height	10 feet	
	Front Setback	3 feet from lot line or 10 ft from back of curb, whichever greater distance from roadway; Subject to §122-675	
	Side, street side, and rear setback	10 feet; Subject to §122-675	
	max # signs	1, unless a lot has more than 100' on two frontages; then allowed a second sign on the secondary frontage at 50% of the area of the sign on the primary face.	
Building-mounted signs (temporary)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Overhead banners (building-mounted signs that span a public right-of-way)	Not permitted		
Building-mounted signs (permanent)	Maximum Area	1 sf per foot of building frontage or 100 sf, whichever is less	Permit required.
Billboards	not permitted		

Secs. 122-463 – 464. Reserved.

Subdivision V: Building Types

Sec. 122-465. Building Types. (274)


Building types are specific sets of height, bulk, and setback regulations, dictated by district and lot size and dimension. Building Types only apply in Walkable Urban Districts, and apply to any new construction or expansion in those districts. The building types are consistent with the size, scale and character desired within each zoning district.

- 3190 (a) **Building Types by Neighborhoods, Centers, Corridors and Health and Human Services District.** The following building types are allowed in Neighborhoods, Centers, Corridors and Health and Human Services districts as shown in the table below. “P” stands for permitted building types, “L” stands for building types allowed in special locations shown on the Zoning Map.

BUILDING TYPE		CN-SF	CN-MID	CN	C	HC	NC	GC	HHS
MA	Mansion	L	L	L	--	L	--	--	--
ES	Estate	P	P	P	--	P	P	--	--
HS	House	P	P	P	--	P	P	--	P
CO	Cottage	P	P	P	--	--	--	--	--
TH	Townhouse	--	P	P	L	--	P	--	P
AH	Apartment House	--	P	P	P	P	P	--	P
CA	Courtyard Apartment	--	--	P	L	P	P	P	--
AB	Apartment Building	--	--	P	L	L	P	P	--
CS	Commercial/Mixed-Use Small	--	--	L	P	P	P	P	--
CM	Commercial/Mixed Use Medium	--	--	--	P	P	P	P	--
CL	Commercial/Mixed Use Large	--	--	--	P	--	--	P	P
SC	Single Story Commercial Building	L	L	L	--	L	P	P	--
LS	Large Single Story Commercial Building	--	--	--	--	--	--	P	P
MB	Multiple Story	--	--	--	P	--	--	P	P
IT	Institutional	L	L	L	L	L	L	L	L

- (b) **How to Read Building Type Diagrams.** The following categories are included in each building type diagram. Each standard is labeled by a letter; that letter corresponds to a location on an illustration of the standard. Each standard is described as follows:
- (1) **Building Type Parameters.** The diagrams and text that follow provide the building parameters by building type. Building types must be consistently applied by District and not permitted a variance or waiver to increase in lot size.
 - (2) **Lot Size determines Building Type.** The size of the lot determines what type of building may be placed on a lot. For instance, a cottage or a house building type may be constructed on 5,000 square foot lot, since all of the those building types fit within the allowed lot size for those building types, but an estate building type is not allowed. Maximum lot depth and width do not determine building types, but all building types must meet the minimum lot width, depth and size.
 - (3) **Lot requirements.** Lists the minimum and maximum lot width, lot depth, and lot size; also the maximum lot coverage.
 - (4) **Building envelope.** Lists the minimum and maximum setbacks for street, side, and rear setbacks, as well as the required frontage buildout.
 - (5) **Accessory Structure Envelope.** Lists the setbacks and maximum building footprint permitted for accessory structures.
 - (6) **Building height.** Lists permitted heights in stories.

- (i) First or Ground Story. The minimum height for all first stories is twelve (12) feet. For the MA, ES, HS, CO, TH, CA, and AB building types the maximum height for the first story shall be fourteen (14) feet; for all others, the maximum height for the first floor shall be twenty (20) feet. Institutional building types, however, have no maximum height for the first floor. This shall not be construed as limiting multi-story or open foyers or lobbies.
- (ii) Subsequent stories. The minimum height for second story and above is ten (10) feet; the maximum height for second story and higher must not exceed twelve (12) feet. However, the top story of any building has a minimum height of ten (10) feet, but no maximum height.
- (iii) Basements. There are no required maximum or minimum heights for basements outside of that required under Building Code.
- (iv) Exceptions to Height Requirements. See exceptions in §122-613.
- (7) **Parking zones.** The amount of parking is determined by Article VI, Division 8 “Parking Types and Quantities,” but the area in which parking may be provided is determined by building type. Driveways are permitted in any zone, provided all other requirements of this chapter have been met. The diagrams illustrate a corner lot on a primary and non-primary street. Zones are the lot area between the principal building and:
 - Zone 1: the right-of-way of any primary street;
 - Zone 2: any common interior lot line;
 - Zone 3: any rear lot line;
 - Zone 4: the right-of-way of any non-primary street.



- (8) **Private frontages.** The private frontage style may be noted as “required” or as “preferred.” If there are multiple frontages provided in the table, the applicant may choose which to provide per building.
- (9) **Exceptions to Setbacks.** The following exceptions apply to setbacks for all building types:
 - (i) **Historic Structure.** A structure may encroach up to within five feet of a required front or rear yard setback, or within three feet of a side yard setback, upon a recommendation from the Historic District Commission that contains a finding that such setbacks allow for the restoration of a historic feature and with Planning Commission approval.
 - (ii) **Accessory Structure Adjacent to Alley or Railroad.** Any setback for an accessory structure adjacent to an alley or railroad right-of-way is one foot.
- (10) **Double Frontage Lots.** In the case of a row of double frontage lots, one street must be designated as the front street for all lots in the row, with rear setbacks applying to the yards fronting the other street. If there are existing buildings in the same block fronting on one or both of the streets, the required minimum front yard setback must be observed on the street where buildings presently front.
- (c) **Infill and Redevelopment.** Additions, renovations, and new buildings on existing built parcels may require the assembly of building types. The building types are outlined by lot size, and can often fit within existing lots. For instance, an addition to an existing building that meets the setbacks for their building type, but is on a lot deeper than the maximum, does not need to adjust lot lines.
- (1) **Lot Requirements For New Construction.** Several buildings of either one type or multiple types are permitted on one lot, provided that each building type is provided at least the minimum area required by building type, and other requirements of this chapter are met. There is no requirement to plat or divide land to create lots on the existing parcel site. For example, a multiple-story building and a commercial mixed use building can be built on the same parcel, without any changes to the lot line locations or a lot split, as long as the other lot requirements for the district can be met. In a single-building type example, two rows of townhouses can be built on a single parcel, without changes or splits of the lot, as long as the width of each unit meets the lot requirements and the distance between the two buildings meets the side or rear yard setback for both buildings, whichever is applicable.

3260

(2) Lot and Block Requirements for Existing Buildings. In the event when an addition is proposed for an existing building, and the existing building exceeds the height requirements or encroaches on the setbacks for the building type, the City Planner must determine if an administrative waiver can be granted, or if it should require a review by the Planning Commission. An administrative waiver can be issued with a finding that the existing building with proposed additions will not cause the block perimeter to exceed a total length of 1,600 feet in the C, CN, CN-Mid, and CN-SF districts or 2,000 feet in the HC, NC, GC, and HHS districts; or a block side length of 400 feet in the C, CN, CN-Mid, and CN-SF districts or 500 feet in the HC, NC, GC, and HHS districts.

3270

If the proposed additions to an existing building exceed the block requirements, the applicant is subject to review by the Planning Commission.

MA MANSION

Mansions are generally very large buildings originally built as residences, located on very large lots that distinguish the building from others nearby with expansive yards. They generally have a single primary entrance.

This building type is only permitted as a Limited building type.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	14,440	--
B	Lot width (ft)	120	--
C	Lot depth (ft)	120	--
D	Lot coverage (%)	--	30
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	30 ⁽¹⁾	--
F	Side setback (interior lot line) (ft)	25	--
G	Rear setback (ft)	40	--
H	Frontage buildout (%)	--	--
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	5	--
K	Rear setback (ft)	5	--
L	Building footprint (sf)	--	1,200
Note: there is a maximum of two accessory buildings.			
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	3
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the front, side, street-side, and rear yards.	

(1) Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



ES ESTATE

Large buildings, built as residences, located on large lots that accommodate large yards. They generally have distinguishing architectural features and one primary entrance.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	9,600	21,780
B	Lot width (ft)	80	120
C	Lot depth (ft)	120	--
D	Lot coverage (%)	--	30
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	20 ⁽¹⁾	--
F	Side setback (interior lot line) (ft)	10	--
G	Rear setback (ft)	25	--
H	Frontage buildout (%)	--	80
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	5	--
K	Rear setback (ft)	5	--
L	Building footprint (sf)	--	950
Note: there is a maximum of two accessory buildings.			
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	3
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side, street-side, and rear yards.	
PRIVATE FRONTAGES		Porch or Stoop required.	

(1) Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



HS HOUSE

Houses are detached, generally single-family dwelling units. They are located on lots that accommodate a primary building with small side yards and relatively large rear or front yards. They generally have one primary entrance.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	4,000	12,000
B	Lot width (ft)	35	80
C	Lot depth (ft)	100	--
D	Lot coverage (%)	--	60
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	15 ⁽¹⁾	25
F	Side setback (interior lot line) (ft)	5	--
G	Rear setback (ft)	20	--
H	Frontage buildout (%)	60	80
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	5	--
K	Rear setback (ft)	5	--
L	Building footprint (sf)	--	800
Note: there is a maximum of two accessory buildings.			
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	3
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side, street-side, and rear yards.	
PRIVATE FRONTAGES		Porch or Stoop required.	

(1) Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



CO COTTAGE

Cottages are generally small residential buildings, sized for a single dwelling, located on lots that accommodate a detached primary building with small yards. They are generally a single-story building or bungalow with a single primary entrance.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	2,500	6,300
B	Lot width (ft)	25	35
C	Lot depth (ft)	50	150
D	Lot coverage (%)	--	70
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	10 ⁽¹⁾	20
F	Side setback (interior lot line) (ft)	3	--
G	Rear setback (ft)	10	--
H	Frontage buildout (%)	70	90
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	5	--
K	Rear setback (ft)	5	--
L	Building footprint (sf)	--	500
Note: there is a maximum of two accessory buildings.			
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	2
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side, street side, and rear yards.	
PRIVATE FRONTAGES		Porch or Stoop required.	

(1) Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



TH TOWNHOUSE

Townhouses consist of rows of attached residential buildings. They are located on lots which accommodate a building with more than one dwelling unit, party walls, and a private back yard. Each dwelling has its own entrance to the street.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	1,200	3,000
B	Lot width (ft)	15	25 ⁽²⁾
C	Lot depth (ft)	80	120
D	Lot coverage (%)	--	60
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	10 ⁽¹⁾	20 ⁽²⁾
F	Side setback (interior lot line) (ft)	0 ⁽²⁾	--
G	Rear setback (ft)	15	--
H	Frontage buildout (%)	90	100
Note: A maximum of six units may be provided in a row.			
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	5	--
K	Rear setback (ft)	5	--
L	Building footprint (sf)	--	800
Note: there is a maximum of two accessory buildings.			
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	3
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the rear yard.	
PRIVATE FRONTAGES		Porch or Stoop required.	

- (1) Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.
- (2) End unit lot may be up to ten feet larger.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



AH APARTMENT HOUSE

Apartment Houses may be buildings converted from single-family detached buildings or built to resemble them that contain two or more dwelling units, with lots that accommodate the parking and outdoor living areas for several dwellings.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	4,000	18,000
B	Lot width (ft)	40	120
C	Lot depth (ft)	100	150
D	Lot coverage (%)	--	50
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	15 ⁽¹⁾⁽²⁾	25
F	Side setback (interior lot line) (ft)	5	--
G	Rear setback (ft)	20	--
H	Frontage buildout (%)	60	80
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30 ⁽¹⁾	--
J	Side setback (ft)	5	--
K	Rear setback (ft)	5	--
L	Building footprint (sf)	--	800
Note: there is a maximum of two accessory buildings.			
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	3
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side, street side, and rear yards.	
PRIVATE FRONTAGES		Porch or Stoop required.	

- (1) Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must be within the range so established.
- (2) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



CA**COURTYARD
APARTMENT**





A Courtyard Apartment is generally a grouping of apartment buildings arranged around and fronting on a central courtyard that may be partially or wholly open to the street, on a lot that accommodates the associated parking and outdoor living areas. Each dwelling may have its own entrance.

LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	6,400	20,000
B	Lot width (ft)	80	200
C	Lot depth (ft)	80	180
D	Lot coverage (%)	--	80
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	10(1)	20
F	Side setback (interior lot line) (ft)	0	10
G	Rear setback (ft)	10	--
H	Frontage buildout (%)	50	75
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	5	--
K	Rear setback (ft)	5	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	2	4
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side and rear yards.	
PRIVATE FRONTAGES		Forecourt required.	

(1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.



EXAMPLE

LOT REQUIREMENTS AND BUILDING ENVELOPE**ACCESSORY BUILDING ENVELOPE****BUILDING HEIGHT****PARKING LOCATION**

AB**APARTMENT BUILDING**





Apartment Buildings are generally multiple-story multifamily residential buildings, located on lots that may be as large as a city block and can accommodate two or more buildings and accessory parking, waste disposal, and outdoor living areas.

LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	4,000	90,000
B	Lot width (ft)	30	300
C	Lot depth (ft)	100	300
D	Lot coverage (%)	--	80
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	10 ⁽¹⁾	25 ⁽¹⁾
F	Side setback (interior lot line) (ft)	5	--
G	Rear setback (ft)	15 ⁽²⁾	--
H	Frontage buildout (%)	60	80
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	10	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	2	6
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side and rear yards.	
PRIVATE FRONTAGES		Porch, Stoop, or Forecourt required.	

- (1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.
 (2) When adjacent to existing detached single-family homes, the rear setback shall be a minimum of 25 feet.



EXAMPLE

LOT REQUIREMENTS AND BUILDING ENVELOPE**ACCESSORY BUILDING ENVELOPE****BUILDING HEIGHT****PARKING LOCATION**

CS**COMMERCIAL/
MIXED-USE - SMALL**





These are generally small multiple-story buildings designed for commercial uses on the ground floor and dwellings or offices above, located on lots that can accommodate a building that is less than 20% of that block's width.

LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	1,800	7,200
B	Lot width (ft)	15	60
C	Lot depth (ft)	80	120
D	Lot coverage (%)	--	90
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	0 ⁽¹⁾	15 ⁽¹⁾
F	Side setback (interior lot line) (ft)	0	--
G	Rear setback (ft)	5	--
H	Frontage buildout (%)	80	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	3	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	2	5
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side and rear yards.	
PRIVATE FRONTAGES		Commercial required.	

(1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.



EXAMPLE

LOT REQUIREMENTS AND BUILDING ENVELOPE**ACCESSORY BUILDING ENVELOPE****BUILDING HEIGHT****PARKING LOCATION**

CM COMMERCIAL/ MIXED-USE - MEDIUM

These are generally moderately-sized multiple-story buildings designed for commercial uses on the ground floor and dwellings or offices above, located on lots that can accommodate a building that spans 20-40% of that block's width.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	--	60,000
B	Lot width (ft)	60	120
C	Lot depth (ft)	--	500
D	Lot coverage (%)	--	90
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	0 ⁽¹⁾	15 ⁽¹⁾
F	Side setback (interior lot line) (ft)	0	--
G	Rear setback (ft)	10 ⁽²⁾	--
H	Frontage buildout (%)	90	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	10	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	2	5
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side and rear yards.	
PRIVATE FRONTAGES		Commercial required.	

- (1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.
 (2) When adjacent to existing detached single-family homes, the rear setback shall be a minimum of 25 feet.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



CL**COMMERCIAL/
MIXED-USE - LARGE**





These are generally large multiple-story buildings designed for commercial uses on the ground floor and dwellings or offices above, located on lots that can accommodate a building that spans up to an entire block's width.

LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	--	150,000
B	Lot width (ft)	120	300
C	Lot depth (ft)	--	500
D	Lot coverage (%)	--	90
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	0 ⁽¹⁾	15 ⁽¹⁾
F	Side setback (interior lot line) (ft)	0	--
G	Rear setback (ft)	10 ⁽²⁾	--
H	Frontage buildout (%)	90	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	10	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	2	8
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side and rear yards.	
PRIVATE FRONTAGES		Commercial required.	

- (1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.
 (2) When adjacent to existing detached single-family homes, the rear setback shall be a minimum of 25 feet.



EXAMPLE

LOT REQUIREMENTS AND BUILDING ENVELOPE**ACCESSORY BUILDING ENVELOPE****BUILDING HEIGHT****PARKING LOCATION**

SC**SINGLE STORY
COMMERCIAL
BUILDING**





These are generally designed for a single commercial use, located in lots that accommodate accessory parking, loading, and waste disposal areas.

LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	7,500	90,000
B	Lot width (ft)	50	300
C	Lot depth (ft)	100	300
D	Lot coverage (%)	--	60
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	5 ⁽¹⁾	15 ⁽¹⁾
F	Side setback (interior lot line) (ft)	0	--
G	Rear setback (ft)	15 ⁽²⁾	--
H	Frontage buildout (%)	50	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	10	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	1
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side, street side, and rear yards.	
PRIVATE FRONTAGES		Commercial required.	

- (1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.
 (2) When adjacent to existing detached single-family homes, the rear setback shall be a minimum of 25 feet.



EXAMPLE

LOT REQUIREMENTS AND BUILDING ENVELOPE**ACCESSORY BUILDING ENVELOPE****BUILDING HEIGHT****PARKING LOCATION**

LS

LARGE SINGLE STORY COMMERCIAL BUILDING

These are generally designed for more than one commercial use, each generally with its own entrance, located in lots that accommodate accessory parking, loading, and waste disposal areas.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	90,000	--
B	Lot width (ft)	300	block
C	Lot depth (ft)	300	block
D	Lot coverage (%)	45	80
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	5 ⁽¹⁾	15 ⁽¹⁾
F	Side setback (interior lot line) (ft)	0	--
G	Rear setback (ft)	10 ⁽²⁾	--
H	Frontage buildout (%)	50	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	10	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	1
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side, street side, and rear yards.	
PRIVATE FRONTAGES		Commercial required.	

- (1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.
 (2) When adjacent to existing detached single-family homes, the rear setback shall be a minimum of 25 feet.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



MB MULTIPLE STORY BUILDING

These are generally designed for more than one commercial use or user, with a common entrance on the ground floor. They are located on lots that accommodate accessory parking, loading, and waste disposal areas, spanning up to an entire block width.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	--	150,000
B	Lot width (ft)	120	block
C	Lot depth (ft)	--	500
D	Lot coverage (%)	--	90
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	5 ⁽¹⁾	25 ⁽¹⁾
F	Side setback (interior lot line) (ft)	0	--
G	Rear setback (ft)	10 ⁽²⁾	--
H	Frontage buildout (%)	50	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	10	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	2	6
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side, street side, and rear yards.	
PRIVATE FRONTAGES		Commercial required.	

- (1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.
 (2) When adjacent to existing detached single-family homes, the rear setback shall be a minimum of 25 feet.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



IT INSTITUTIONAL

These buildings are generally designed to house government, assembly, or institutional uses, on lots that can accommodate the primary building, associated parking, loading, waste disposal areas, and outdoor space.


LOT REQUIREMENTS		MIN	MAX
A	Lot size (sf)	5,000	--
B	Lot width (ft)	50	block
C	Lot depth (ft)	100	block
D	Lot coverage (%)	--	60
BUILDING ENVELOPE		MIN	MAX
E	Street setback (front or side) (ft)	15 ⁽¹⁾	--
F	Side setback (interior lot line) (ft)	0	--
G	Rear setback (ft)	15	--
H	Frontage buildout (%)	50	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I	Street setback (ft)	30	--
J	Side setback (ft)	10	--
K	Rear setback (ft)	10	--
L	Building footprint (sf)	--	800
BUILDING HEIGHT		MIN	MAX
M	Principal building (stories)	1	4 ⁽²⁾
N	Accessory structure(s) (ft)	--	15
PARKING LOCATION		Permitted in the side, street side, and rear yards.	
PRIVATE FRONTAGES		None required.	

- (1) If located on Washtenaw Avenue, must build no more than ten feet from future right-of-way line as defined in the ReImagine Washtenaw plan.
- (2) Additional height may be permitted by Planning Commission with a finding that the additional height is consistent with other buildings in that block.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY BUILDING ENVELOPE



BUILDING HEIGHT



PARKING LOCATION




Sec. 122-481. Porch

P PORCH

The façade is set back from the front lot line per applicable street setback requirements. The façade includes an attached front porch structure. A wide variety of porch designs are possible. Unenclosed porches can project up to ten feet into the required front yard.

PORCH DIMENSIONS		MIN	MAX
A	Clear span width (ft)	10	--
B	Depth (ft)	5	--
C	Height (ft)	7	--
YARD REQUIREMENTS			
D	Must be landscaped/pervious, with a path at least 3 feet wide connecting the porch to the sidewalk.		




Sec. 122-482. Stoop

S **STOOP**

The building façade is set back from the front lot line per applicable street setback requirements. The façade includes an attached entry stoop (an elevated landing with stairs) that is placed at or near the front lot line. The ground floor is elevated to provide privacy. The stoop may include a roof.

STOOP DIMENSIONS		MIN	MAX
A	Clear span width (ft)	5	8
B	Depth (ft)	3	8
C	Height (ft)	7	--
YARD REQUIREMENTS			
D	Must be landscaped/pervious, with a path at least 3 feet wide connecting the porch to the sidewalk.		




Sec. 122-483. Forecourt

F FORECOURT

The façade is set back from the front lot line per applicable street setback requirements. A portion of the façade is recessed to form an uncovered court. The court is suitable for outdoor dining, gardens, formal entries etc.. A fence, wall, or landscaping may be used to define the private space of the court. The court may be elevated behind a retaining wall at or near the front lot line with entry steps to the court.

FORECOURT DIMENSIONS		MIN	MAX
A	Clear span width (ft)	12	--
B	Depth (ft)	12	50
YARD REQUIREMENTS			
C	Must be landscaped/pervious, with a path at least 6 feet wide connecting the building entrance to the sidewalk.		




C

COMMERCIAL

The façade is set back from the front lot line per applicable street setback requirements, typically at or near the front lot line with the entrance at sidewalk grade. The façade may include an awning, shed roof, or gallery (a lightweight colonnade with no habitable building space above it) that covers the sidewalk and may extend into the right-of-way. The facade has a substantial amount of glazing at the sidewalk level. Recessed entrances are acceptable.

FAÇADE DIMENSIONS		MIN	MAX
A	Distance between openings (ft)	--	2
B	Door recess (ft)	--	5
C	Ground floor transparency (%)	60	--
D	Height to bottom of window (ft)	--	2.5
YARD REQUIREMENTS			
E	Must be landscaped/pervious, with a path at least 6 feet wide connecting the building entrance to the sidewalk.		
OPTIONAL AWNING OR GALLERY			
F	Setback from curb (ft)	2	--
G	Clear depth - awning (ft)	4	10
	Clear depth - gallery (ft)	8	10
H	Clear height (ft)	8	--



Secs. 122-485 – 499. Reserved.

Article V: Use Regulations

122-500. Purpose. (771)

It is recognized that there are certain uses that, due to size, location, use, or intensity, may adversely impact surrounding properties if not regulated. Such uses are generally listed within this chapter as special uses within specified zoning districts. This article states specific standards for approval of such uses in order to eliminate or mitigate any potential adverse impacts these uses may have on surrounding properties.

122-501. Compliance with article. (772)

The uses in this article, whether specifically allowed as permitted uses, permitted accessory uses, or special uses in any zoning district, may only be approved, established, operated, used, expanded or enlarged in accordance with the specific provisions listed in this article.

Secs. 122-502 – 509. Reserved.

Division 1: Specific Standards For Certain Uses

A

Sec. 122-510. Adult drop-in centers or neighborhood counseling centers. (793)

Adult drop-in centers or neighborhood counseling centers are subject to the conditions hereinafter imposed:

- 3330 (a) Access to and from the site must be directly to a major street as defined in §122-673, or to a major street through an HHS or a nonresidential district. In no event may access be through an R1, MD, CN, CN-Mid, or CN-SF district.
- (b) Social services, such as food and/or clothing distribution or other similar services, are permitted only if the Planning Commission should find that adequate ingress and egress, parking, and indoor waiting and storage areas are provided.

Sec. 122-511. Adult foster care small homes with more than six persons for whom care is being provided, adult foster care large group homes, and adult foster care congregate facilities. (773)

Adult foster care small homes with more than six persons for whom care is being provided, adult foster care large group homes, and adult foster care congregate facilities are subject to the conditions hereinafter imposed:

- 3340 (a) All such facilities must be registered with or licensed by the state and must comply with the minimum state standards for such facilities and the Building Code.
- (b) For each adult cared for, the square footage of outdoor recreation or relaxation area required by the Building Code and licensing agency must be provided in the rear, side, or street side yard. Such outdoor space must be fenced and screened from any adjacent lot.
- (c) If the owner of the property does not reside on the premises, the owner must appoint a resident manager, who must reside on the premises. The property owner must provide the name and contact information of this person to the Building Department, and keep such information up-to-date.
- (d) Uses must not be located within 200 feet of property zoned R1 or CN-SF.
- 3350 (e) All new construction or additions to existing buildings shall be compatible with the scale and character of the surroundings, and exterior building materials shall be harmonious with other buildings in the neighborhood.
- (f) Screening in accordance with §122-634 shall be provided along all rear and side yard boundaries between the proposed use and property either zoned or used for single-family and two-family purposes.

Sec. 122-512. Adult regulated uses. (774)

- 3360 (a) In the development and execution of this section, it is recognized that there are certain uses, which by their very nature are recognized as having serious objectionable operational characteristics, particularly when several of them are concentrated in a small area, thereby having a deleterious effect on surrounding neighborhoods. Regulation of the location of these uses is necessary to ensure that the adverse effects of such businesses will not cause or contribute to the blighting or downgrading of the City's residential neighborhoods or commercial centers. It is the intent of this section to provide reasonable regulations for the establishment of adult regulated uses in a viable, accessible location where the adverse impact of their operations may be minimized. Uses subject to these regulations and the requirements of Article V of Chapter 10 are as follows:
- (1) Adult: Adult book or supply store, adult hotels or motels, adult motion picture theater/adult live stage performing theater, and adult mini-motion picture theater.
- (2) Cabarets.
- (3) Massage parlors and massage establishments.
- (4) Pawnshops.
- 3370 (b) No adult regulated use may be permitted within 1,000 feet of any other adult regulated use. Measurement of the 1,000-foot radius must be made from the outermost boundaries of the lot or parcel on which the adult regulated use is proposed. The Planning Commission may waive this requirement for pawnshops if the following findings are made that:
- (1) The proposed use will not be contrary to the public interest or injurious to nearby properties, and that the spirit and intent of this article is observed.
- (2) The proposed regulated use will not enlarge or encourage the development of a "skid-row" or blighted area.
- (3) The establishment of an additional adult regulated use in the area will not be contrary to any program of neighborhood conservation nor will it interfere with any program of urban revitalization.
- (4) All applicable regulations of this chapter will be observed.
- The Planning Commission may not waive this locational requirement for adult uses, cabarets, massage parlors,

or massage establishments.

- 3380 (c) No adult regulated use may be permitted within 500 feet of any R1, HHS, P, MD, CN, CN-Mid and CN-SF district; nor may any adult regulated use be permitted within 500 feet of any school, park, library, playground, movie theater, licensed child care facility, or any other area or use where minor children are likely to congregate; nor may any adult regulated use be permitted within 500 feet of any religious institution. Measurement must be from the outermost boundaries of the lot or parcel on which the adult regulated use is proposed to be located. This prohibition may be waived if the Planning Commission is presented with a validated petition requesting such waiver, signed by two-thirds of all persons owning, residing in, or doing business in the area within 500 feet of the proposed adult regulated use. The circulator of the petition must sign an affidavit attesting that the circulator personally witnessed the signatures and the signatures were affixed to the petition by the person whose name appears thereon. The signatures must be validated by the community economic development department. The Planning Commission cannot consider the waiver of the locational requirements until the required petition has been duly filed and verified. Pawnshops are not be subject to these locational requirements.
- 3390 (d) The building and premises must be designed and constructed so that material depicting, describing, or relating to specified sexual activities or specified anatomical areas, cannot be observed by pedestrians or from vehicles on any public right-of-way. This provision must apply to any display, decoration, sign, show window, or other opening.
- (e) No person may reside in or permit any person to reside in the premises of an adult regulated use.
- (f) Such uses must comply with all applicable federal, state, and local licensing regulations. Initial and annual proof of such compliance must be a condition of special use approval and the continuance thereof.
- 3400 (g) Upon finding that any condition, safeguard, or requirement has been breached, the Building Department can revoke any occupancy permit. All operations must cease 14 days following such notification of revocation by the Building Department, unless such violations are corrected. Also, if violations are not corrected within 14 days, reinstatement of a revoked permit must require a new special use application and approval thereof.

Sec. 122-513. Alternative Energy. (788)

Alternative energy production is subject to the conditions hereinafter imposed:

(a) Photovoltaic Production

- 3410 (1) Attached accessory photovoltaic structures are permitted in all zoning districts when meeting the following requirements:
- (i) Positioning. All attached photovoltaic structures positioning and attachment must meet Building Department requirements for snow loads and wind loads.
- (ii) Height. All attached photovoltaic structures must meet the following height regulations by type:
- (a) Maximum. The maximum height of photovoltaic roof paneling installed on a sloped roof or flat roof of a building is ten feet above the maximum building height allowed for that zoning district or building type. Photovoltaic panels attached to the side of a structure must not project vertically above the building height allowed for that zoning district or building type.
- (2) Detached accessory photovoltaic structures, when mounted top-of-pole for outdoor lights, are permitted in all zoning districts. In no instance may such panels exceed 20 feet in height.
- (3) Solar farms. On sites where the primary use is photovoltaic energy production, all structures must meet the height requirement of the zoning district.
- 3420 (i) Abandonment. Any freestanding photovoltaic system which is not used for six (6) months will be deemed to be abandoned. The applicant/permit holder will be so notified in writing by the municipality and requested to dismantle the site and return it to its original state. If there are mitigating circumstances as to why the site has not been used, the applicant/permit holder may contact the municipality and request a three-month extension. If a site has been deemed abandoned and no request for an extension is received, the applicant/permit holder will again be notified to dismantle the site and return it to its original state. If the applicant/permit holder does not do this, the municipality will have the removal and restoration done at the owner/applicant's expense. Removal will include removing posts, equipment, panels, foundations and other items so that the ground is restored to its preconstruction state and is ready for development as another land use.
- 3430 (b) Solar water heating. Attached accessory solar water heating systems are permitted in all zoning districts. Solar collectors installed on a sloped roof of a building must not project vertically above the peak of the roof. Solar collectors attached to a flat roof must not project vertically more than 10 feet above the roof. Solar panels attached to the side of a structure must not project vertically above the building height allowed for that zoning district or building type.
- (c) Wind energy production. Attached accessory wind energy production structures are permitted in all zoning districts, subject to height limitations.

- (d) Geothermal energy production. Attached accessory geothermal energy production systems are permitted in all zoning districts.
- (e) Other methods. Other methods of alternative energy production may be submitted to the City Planner and, at their discretion, may be approved, approved subject to another City department(s) review, approved subject to Planning Commission review, or denied

3440

Sec. 122-514. Auction House. (812)

Auction Houses are subject to the conditions hereinafter imposed:

- (a) The applicant shall provide a use statement with the following information:

- The maximum capacity of the facility;
- Number and frequency of the auctions;
- Method for providing parking during auctions;
- An acknowledgement that any outdoor activities are subject to the requirements for open-front or open-air businesses, and that such are only permitted in certain zoning districts and may have additional requirements.

3450 **Sec. 122-515. Automobile service or repair. (775)**

Automobile service and repair are subject to the conditions hereinafter imposed:

- (a) All lubrication equipment, hoists, and pits must be enclosed entirely within a building. All repair operations must take place within a completely enclosed building, and such building must not be located within 100 feet of any interior lot line abutting a residentially zoned district.
- (b) The entire lot, excluding areas occupied by landscaping and building, must be hard-surfaced with concrete or plant-mixed bituminous material. Curbs of at least six inches in height must be installed around the perimeter of all surfaced areas. Drainage must be provided in accordance with §122-683.
- (c) The storage, sale or rental of new or used automobiles, trucks, trailers, and any other vehicles on the premises is prohibited. Vehicles awaiting repair, or inoperable, wrecked, or partially dismantled vehicles, must not be stored or parked outside for a period exceeding seven days.

3460

REMOVED (D): duplicates existing requirements in parking quantity sections.

Sec. 122-516. Automobile filling stations. (776)

Automobile filling stations are subject to the conditions hereinafter imposed:

- (a) The curb cuts are not permitted at such locations that will tend to create traffic hazards in the streets immediately adjacent thereto. Entrances must be no less than 25 feet from a street intersection (measured along the road right-of-way). Drives must be no less than 20 feet wide, nor wider than 30 feet at the right-of-way line. No more than one such drive or curb opening may be permitted for every 75 feet of frontage along any street or in accordance with county or state requirements, whichever is greater.
- (b) The entire lot, excluding areas occupied by landscaping and building, must be hard-surfaced with concrete or plant-mixed bituminous material. Curbs of at least six inches in height must be installed around the perimeter of all surfaced areas. Drainage must be provided in accordance with §122-683.
- (c) All fuel pumps must be located not less than 15 feet from any lot line; provided however, that fuel pumps may not be located less than 40 feet from any interior lot line which abuts residentially zoned property, nor closer than 100 feet from any religious institution, theater, hall, or other place of public assembly.
- (d) A rigid canopy which covers the fuel dispensing area is permitted provided that the lowest edge of such canopy must be a minimum of 14 feet above grade. All support structures for canopies must be located so as not to obscure the vision of motorists using any nearby streets, driveways, or maneuvering aisles.
- (1) For service stations located within a NC zoning district, the nearest edge of any canopy must be set back a minimum of 10 feet from any lot line.
- (2) For service stations located within a GC zoning district, the nearest edge of any canopy must be set back a minimum of 15 feet from any lot line.
- (e) The storage, sale, or rental of new or used automobiles, trucks, trailers, or any other vehicles on the premises is prohibited. Inoperable, wrecked or partially dismantled vehicles must not be stored or parked outside for a period exceeding two days.

3470

3480

Sec. 122-517. Automobile wash establishments. (777)

Automobile wash establishments are subject to the conditions hereinafter imposed:

- (a) All washing activities must be carried out within a building. Vacuuming activities may be permitted outdoors, provided such activities are located at least 50 feet from adjacent R1, P, MD, CN, CN-Mid and CN-SF districts or property with first-floor residential uses.

- 3490 (b) The entire lot, excluding areas occupied by landscaping and building, must be hard surfaced with concrete or plant-mixed bituminous material. Curbs of at least six inches in height must be installed around the perimeter of all surfaced areas. Drainage must be provided in accordance with §122-683.
- (c) Sufficient space must be provided on the lot so that vehicles do not enter or exit the wash building directly from an adjacent street or alley. All maneuvering areas, stacking lanes, and exit aprons must be located on the car wash parcel itself. Streets and alleys may not be used for maneuvering or parking by vehicles to be serviced by the automobile wash.

Sec. 122-518. Automobile parking garages. (781)

Automobile parking garages are permitted subject to the conditions hereinafter imposed:

- 3500 (a) Such use must not be located within 100 feet of an R1, CN-Mid or CN-SF district.
- (b) All parking garages in the Walkable Urban Districts shall be constructed under the IT building type.
- (c) The architectural style and facade of the structure must be in keeping with the character of surrounding residential and business uses.
- (d) All areas not used for parking or vehicular maneuvering must be landscaped and maintained in good condition.
- (e) No access from a major thoroughfare is permitted. The vehicle entrances to structured parking should be from side streets and/or access roads.
- (f) Direct pedestrian access from parking garages to any adjacent street must be provided.
- (g) The exterior facades of all parking garages fronting on any street must be designed to achieve an architectural unity with the block.
- 3510 (h) The parking garage must have sheltered bicycle and motorcycle parking areas within 25 feet of the vehicular entrance.

Sec. 122-519. Automobile parking lot as principal use. (782)

A parking lot as a principal use is permitted subject to the conditions hereinafter imposed:

- (a) Parking lots must meet all dimensional requirements for off-street parking in accordance with Article VI, Division 7 of this chapter.
- (b) Parking lots must contain an amount of bicycle spaces equal to 5% of the number of vehicle spaces year-round; another 5% must be provided April-October, with that area being used for snow storage or additional vehicle parking during the winter months.
- (c) Parking lots must contain twice the number of barrier-free parking spaces as would be required under Michigan Barrier-Free code, with no fewer than two barrier-free spaces being provided.

3520 **B**

Sec. 122-520. Bed and breakfasts and inns. (778)

Bed and breakfast lodgings and inns are subject to the conditions hereinafter imposed:

- (a) When located within the CN, CN-Mid, CN-SF, or R1 zoning districts the structure to be used as a bed and breakfast lodging must be the principal residence of the owner/operator; in all other zoning districts, it must be the principal residence of the owner/operator or a resident manager. In either case, such party must live on the premises when the bed and breakfast lodging is in operation. A minimum of 450 square feet of living space must be reserved for the owner/operator's or resident manager's quarters.
- (b) If the owner of the property does not reside on the premises, the property owner must provide the name and contact information of resident manager to the Building Department, and keep such information up-to-date.
- 3530 (c) Rooms used for sleeping must have a minimum of 100 square feet for two occupants, plus an additional 50 square feet for each additional occupant.
- (d) When located within the CN, CN-Mid, CN-SF, or R1 zoning districts, food may only be served to guests staying at the bed and breakfast lodging. There may not be separate cooking facilities for the bed and breakfast lodging other than those which serve the principal residence. In other districts, the establishment may operate a restaurant on the premises, provided that all requirements of this chapter related to restaurants, as well as any other applicable regulations, are met; and provided that no expansion of the residential building in order to accommodate a restaurant is made.

C

Sec. 122-521. Child care centers and group day care homes. (779)

Child care centers and group day care homes are subject to the conditions hereinafter imposed:

3540

- (a) All child care centers and, group day care homes must be registered with or licensed by the state department of social services and must comply with the minimum state standards for such facilities.
- (b) The square footage of outdoor recreation area required by the Building Code and licensing agency must be provided in the rear, side, or street side yard. Such outdoor space must be fenced and screened from any adjacent lot.

D

Sec. 122-522. Drive-through or drive-in facilities. (784&783)

Drive-through or drive-in facilities in combination with any kind of other use are subject to the conditions hereinafter imposed:

- 3550 (a) Uses must not be located within 100 feet of property zoned CN, CN-Mid, CN-SF, or R1 district, measured from the lot line.
- (b) Off-street loading and stacking spaces must be provided in accordance with §122-694.
- (c) Canopies and support structures associated with drive-through facilities must meet all minimum yard setback requirements for principal buildings.. The lowest edge of a canopy must be at least 12 feet above grade.
- (d) The sound from amplification equipment must not be audible beyond the boundaries of the site.
- (e) Uses must have direct access to a major thoroughfare in accordance with §122-673. Ingress and egress curb cuts to the site must be located at least 60 feet from the intersection of any two streets, measured along the nearest right-of-way line.
- (f) Any drive-through or drive-in facilities in C, HC, NC, GC must also provide for walk-up and bicycle users.

3560

E

Sec. 122-523. Essential services. (637)

- (a) *General provisions.* Essential services which are located underground or involve the customary placing of utility poles in public rights-of-way or public easements or the placing of utility boxes in the rear of private properties, and which are reasonably necessary for the furnishing of adequate services for the public health, safety, or welfare must be permitted as authorized and regulated by law and other ordinances of the City in any zoning district.
- (b) *Public utility buildings.* The Planning Commission may authorize the erection, maintenance, and use of a building, or an alteration or addition to an existing building by a public utility as a special use and after site plan review in any zoning district, including a building with a height greater than otherwise permitted in the zoning district; provided that the Planning Commission finds that such building is necessary at a selected location, will not be injurious to the surrounding neighborhood, and is not contrary to the spirit or purpose of this chapter. Where possible, such buildings must be located in predominantly non-residential areas, rather than predominantly residential or multifamily areas.

3570

F

G

Sec. 122-524. Garage sales, rummage sales, yard sales, and owner-made craft sales. (670)

- (a) Duration. Each occasion may not take place for a period of time longer than 12 hours per day for a maximum of three consecutive days.
- (b) Number. There must be no more than three occasions per year on any premises.
- 3580 (c) Hours. All articles or property that are offered for sale must be totally enclosed within a lawful structure or building between the hours of dusk to dawn.

Sec. 122-525. Gardens/Community Gardens (815)

The goal of this standard is to clarify within existing districts that gardening is allowed as an accessory use and to allow for interim or long term low-intensity gardens and/or community gardens on vacant lots in R1, CN, CN-Mid, and CN-SF districts-as long as the use provides minimal impacts to residential character, and minimal increase in traffic in and around related parcels.

Furthermore, the City of Ypsilanti is an urban environment, and while these provisions are intended to support the local food system, it is not the intent of these standards to create agricultural districts within the City. Additionally, if any gardening or related use invokes the State Right-to-Farm Act, then this section and related sections in this Chapter are to become null and void.

- (a) All principal use gardens/community gardens in R1, CN, CN-Mid, and CN-SF districts must maintain a 3 foot setback on street frontages as well as meet traffic visibility regulations detailed in §122-675. Further, they shall not encroach onto adjacent parcels or sights-of-way.
- (b) Sale of goods grown in a garden/community garden is prohibited on garden sites in residential districts. Sales of goods from greenhouse in business or other districts are subject to underlying district requirements.
- (c) The property shall be maintained in an orderly and neat condition and shall not be detrimental to the physical environment or to public health and general welfare, and remains subject to compliance with the Property Maintenance Code, noise ordinance, and related ordinances.
- (d) The property shall be maintained so as to prevent the free flow of storm water, irrigation water, chemicals, dirt, or mud across or onto adjacent lots, properties, public streets, or alleys.
- (e) Motorized equipment within a residential zoning district or residential planned unit development district shall be restricted to hours beginning at 8:00 a.m. and ending at 8:00 p.m.
- (f) Compost piles may only be used for waste generated on site, and are subject to accessory structure setbacks.
- (g) Gardens shall use integrated pest management techniques and best practices in accordance with Chapter 110, Article IV of this Ordinance.

Sec. 122-526. Group Residences and Roominghouses. (804)

Group residences and roominghouses are permitted subject to the following conditions:

- (a) The minimum usable floor area of the structure, size of common interior living space, and kitchen facilities must comply with the applicable Building Codes and Fire Codes adopted by the City of Ypsilanti. Kitchen facilities shall be provided on the premises for the residents therein.
- (b) Rooms for sleeping shall have a minimum square footage as required by the Building Code.
- (c) If the owner of the property does not reside on the premises, the owner must appoint a resident manager, who must reside on the premises. The property owner must provide the name and contact information of this person to the Building Department, and keep such information up-to-date.
- (d) A roominghouse or group residence permitted as a special use shall not be located within 200 feet of an R1 or CN-SF district.
- (e) For roominghouses or group residences permitted as a special land use access to and from the site shall be directly to a major street or to a major street through a CN, CN-Mid or nonresidential district. In no event shall access be through an R1 or CN-SF district.

H

Sec. 122-527. Home occupations. (669)

- (a) **Prohibited home occupations.** The following are not permitted as home occupations: animal grooming establishments, barber shops or beauty parlors with more than one stylist or chair, medical clinics or hospitals with more than one practitioner and one non-practicing staff, commercial stables, day care centers, kennels, real estate offices, restaurants, vehicle repair or painting, retail or wholesale sales of any items stocked on the premises, landscape installation and maintenance businesses, construction contractors, snow removal, funeral homes, nursing homes, antique shops, bed and breakfast establishments, private clubs, trailer rentals, adult regulated uses, millinery and other apparel shops, veterinarian's office, clinic or hospital, or any use that endangers the health, safety, and welfare of any other persons residing in that area by reason of noise, noxious odors, unsanitary or unsightly conditions, fire hazards and the like. This section is not intended to prohibit offices related to the administration of construction contracting, landscaping, maintenance, or snow removal businesses.
- (b) **Permitted home occupations.** Any home occupation that is not specifically prohibited by subsection (a) of this section must be permitted if it meets the following standards:
 - (1) All home occupations must obtain a business license from the City Assessor; if the occupant is not the owner of the premises then consent must be obtained from the property owner to ensure the owner's knowledge of the use.
 - (2) The home occupation must not change the outside appearance of the dwelling nor alter the residential character of the structure.
 - (3) The home occupation must not be visible from the street.
 - (4) The home occupation must be owned and operated only by a member or members of the immediate

family residing on the premises.

(5) No more than one other person may be employed or involved with such activity on premises other than a member of the immediate family residing in the dwelling unit.

(6) All wholesale, jobbing or retail business must be conducted entirely by mail, telephone, electronically or by delivery.

(7) Services and transactions must be conducted by appointment only, walk-in trade is prohibited.

(8) The maximum area for home occupations must be calculated as 25 percent of the usable residential floor area of a dwelling unit or 300 feet whichever is less. Areas designated for home occupations may be located in any useable area of the home, the basement, or any accessory building.

(9) No motor power other than electrically operated motors may be utilized. No single electrical motor used in the home occupation may exceed one horsepower. All electrical motors and equipment used in the conduct of the home occupation must be shielded so as not to cause radio or television interference for adjoining properties.

(10) A home occupation must not create noise, dust, vibration, smell, smoke, glare, electrical interference, fire hazards, or any other hazard or nuisance to any greater or more frequent extent than would normally be generated in the zoning district in which it is located.

(11) In no case may a home occupation be open to the public earlier than 7:00 a.m. nor later than 9:00 p.m.

(12) There must be no deliveries to or from the home occupation with a vehicle having more than two axles.

(13) No merchandise or articles for sale may be displayed on the lot used for the home occupation.

(14) The home occupation may increase vehicular traffic flow and parking by no more than two additional vehicles at a time.

(c) Medical Marijuana Home Occupation. In addition to the requirements in §122-527, Medical marijuana home occupations must be subject to the following requirements:

(1) The medical use of marijuana must comply at all times and in all circumstances with the Michigan Medical Marihuana Act and the General Rules of the Michigan Department of Community Health, as they may be amended from time to time.

(2) A registered primary caregiver operating a medical marijuana home occupation must not be located within 1,000 feet of a school, as measured from the outermost boundaries of the lot or parcel on which the home occupation and school is located.

(3) Not more than one (1) primary caregiver per parcel may be permitted to grow or cultivate medical marijuana.

(4) Not more than five (5) qualifying patients may be assisted with the medical use of marijuana within any given calendar week.

(5) All medical marijuana must be contained within an enclosed, locked facility inside a primary or accessory building.

(6) All necessary building, electrical, plumbing and mechanical permits must be obtained for any portion of the building in which electrical wiring, lighting and/or watering devices that support the cultivation, growing or harvesting of marijuana are located.

(7) If a room with windows is utilized as a growing location, any lighting methods that exceed usual residential periods between the hours of 11pm and 7am must employ shielding methods, without alteration to the exterior of the residence, to prevent ambient light spillage that may create a distraction for adjacent residential properties.

(8) That portion of the building where energy usage and heat exceeds typical residential use, such as grow room, and the storage of any chemicals such as herbicides, pesticides, and fertilizers must be subject to inspection and approval by the Ypsilanti Fire Department to insure compliance with the Michigan Fire Protection Code.

(9) The premises must be open for inspection upon request by the Building Official, the Fire Department and law enforcement officials for compliance with all applicable laws and rules, during the stated hours of operation/use and as such other times as anyone is present on the premises.

Sec. 122-528. Homeless Shelter. (785)

Shelters for the homeless are permitted subject to the conditions hereinafter imposed:

(a) The facility must be operated by a recognized human service agency, incorporated by the state, and which is not for profit.

(b) Resident manager and support services must be provided 24 hours a day, 7 days a week.

(c) No such facility may be located within 1,000 feet of a similar facility.

I

Sec. 122-529. Indoor and Outdoor Recreation and Gyms. (802)

Indoor and Outdoor recreation and gyms are subject to the conditions hereinafter imposed:

- (a) If the proposed use would attract persons from, or is intended to serve areas beyond the immediate neighborhood, the site shall have direct access to a major thoroughfare in accordance with §122-673.
- (b) The Planning Commission may reduce the number of off-street parking spaces required as specified in §122-692 in those instances with a finding that the users will originate from the immediately adjacent areas and will therefore be pedestrian.

J

Sec. 122-530. Junkyards. (790)

Junkyards are permitted subject to the conditions hereinafter imposed:

- (a) The minimum lot size must be one acre.
- (b) No junkyard may be located within 300 feet of a R1, HHS, P, MD, CN, CN-Mid and CN-SF district.
- (c) A minimum setback of 50 feet must be maintained between the front property line and the portion of the property on which junk materials are placed or stored. Outdoor storage areas must also conform to all other setback requirements for principal buildings.
- (d) All outdoor storage areas for junkyards must be screened by a six-to eight-foot obscuring wall constructed of masonry, concrete or other similar material.
- (e) All roads, driveways, parking lots, and loading and unloading areas must be paved or treated in a manner approved by the City Building Department so as to confine any wind-borne dust to within the boundaries of the site.
- (f) Proper access to all parts of the storage areas must be provided for fire and emergency services, as required by the Building Code.

K

Sec. 122-531. Kennels, commercial. (791)

Commercial kennels are permitted subject to the conditions hereinafter imposed:

- (a) Any such kennel must be subject to all permit and operational requirements established by City, county, and state regulatory agencies.
- (b) Buildings in which animals are kept, animal runs, and exercise areas must not be located in any required yard setback areas, and must be located at least 300 feet from any dwellings and 100 feet from any buildings used by the public.
- (c) All outdoor animal runs or exercise areas must be fenced and secured at all times so that no animal contained therein may escape such enclosure.

L

M

Sec. 122-532. Medical Marijuana Dispensaries. (813)

- (a) The intent of the Zoning Ordinance is to regulate medical marijuana dispensaries and growing/manufacturing facilities by providing for regulations and fees in a manner that promotes and protects the public health, safety and welfare, mitigates potential impacts on surrounding properties and persons, and that conforms with the policies and requirements of the Michigan Medical Marijuana Act, MCL 333.26421, et seq (hereinafter "Act"). Nothing in this Chapter, or in any companion regulatory provision adopted in any other provision of this Code, is intended to grant, nor shall they be construed as granting, immunity from criminal prosecution for growing, sale, consumption, use, distribution, or possession of marijuana not in strict compliance with the Act or the General Rules. Also, since Federal law is not affected by the Act or the General Rules, nothing in this Chapter, or in any companion regulatory provision adopted in any other provision of this Code, is intended to grant, nor shall they be construed as granting, immunity from criminal prosecution under Federal law. The Act does not protect users, caregivers or the owners of properties on which the medical use of marijuana is occurring from

Federal Prosecution, or from having their property seized by Federal authorities under the Federal Control Substances Act.

(b) The following Standards for Medical Marijuana Dispensaries shall apply:

- 3750 (1) The medical use of marijuana shall comply at all times and in all circumstances with the Michigan Medical Marihuana Act and the General Rules of the Michigan Department of Community Health, as they may be amended from time to time;
- (2) The dispensary shall not be located within one thousand (1,000) feet of a school, as measured from the outermost boundaries of the lot or parcel on which the dispensary and school are located;
- (3) The dispensary shall not be located within a five hundred (500) feet of a lawfully existing medical marijuana dispensary or growing/manufacturing facility as measured from the outermost boundaries of the lot or parcel on which the proposed dispensary and lawfully existing dispensary or growing/manufacturing facility is located;
- (4) Smoking and/or use of medical marijuana shall be prohibited at the dispensary;
- 3760 (5) All activity related to the dispensary shall be done indoors;
- (6) The premises shall be open for inspection upon request by the Building Official the Fire Department and law enforcement officials for compliance with all applicable laws and rules, during the stated hours of operation/use and as such other times as anyone is present on the premises.
- (7) Quarterly inspections may be made by the City Official's designee to confirm the dispensary or growing/manufacturing facility is operating in accordance with applicable laws including, but not limited to, State Law and City Ordinances;
- (8) Any medical marijuana dispensary shall maintain a log book and/or database identifying by date the amount of medical marijuana on the premises for each qualifying patient/caregiver, keeping the qualifying patient and caregiver information confidential. This log shall be available to law enforcement personnel to confirm that the medical marihuana dispensary does not have more medical marijuana than authorized at the location and shall not be used to disclose more information than is reasonably necessary to verify the lawful amount of medical marijuana at the facility. The facility shall maintain the confidentiality of qualifying patients in compliance with the Michigan Medical Marijuana Act, as amended.
- 3770 (9) If the dispensary ceases operation for a length of time of sixty (60) days or greater, the permit shall expire;
- (10) Dispensary drive-through facilities shall be prohibited;
- (11) All medical marijuana shall be contained within the main building in an enclosed, locked facility in accordance with the Michigan Medical Marijuana Act, as amended;
- (12) Application for a Medical Marijuana Dispensary License shall be made to the City Clerk upon application forms provided by the Clerk for Medical Marijuana Dispensary and signed by the applicant verifying the truth and accuracy of all information and representations in the application. Applications including information and documentation provided pursuant to an application shall be subject to the confidentiality rules under the Act. In addition to information and submittals, the application shall include payment of application fee in an amount set by the City Council;
- 3780 (13) The police department shall review the proposed application to operate a dispensary regarding public health, safety, and welfare concerns of the proposal;
- (14) Growing or cultivation of medical marijuana in a dispensary is prohibited.

Sec. 122-533. Medical Marijuana Growing/Manufacturing Facility. (814)

- 3790 (a) The intent of the Zoning Ordinance is to regulate medical marijuana dispensaries and growing/manufacturing facilities by providing for regulations and fees in a manner that promotes and protects the public health, safety and welfare, mitigates potential impacts on surrounding properties and persons, and that conforms with the policies and requirements of the Michigan Medical Marijuana Act, MCL 333.26421, et seq (hereinafter "Act"). Nothing in this Chapter, or in any companion regulatory provision adopted in any other provision of this Code, is intended to grant, nor shall they be construed as granting, immunity from criminal prosecution for growing, sale, consumption, use, distribution, or possession of marijuana not in strict compliance with the Act or the General Rules,. Also, since Federal law is not affected by the Act or the General Rules, nothing in this Chapter, or in any companion regulatory provision adopted in any other provision of this Code, is intended to grant, nor shall they be construed as granting, immunity from criminal prosecution under Federal law. The Act does not protect users, caregivers or the owners of properties on which the medical use of marijuana is occurring from Federal Prosecution, or from having their property seized by Federal authorities under the Federal Control Substances Act.
- 3800 (b) The following standards for Medical Marijuana Growing/Manufacturing Facilities shall apply:
- (1) The medical use of marijuana shall comply at all times and in all circumstances with the Michigan Medical Marihuana Act and the General Rules of the Michigan Department of Community Health, as they may be amended from time to time;

- (2) The growing/manufacturing facility site shall not be located within one thousand (1,000) feet of a school, as measured from the outermost boundaries of the lot or parcel on which the growing/manufacturing facility and school are located;
- (3) The growing/manufacturing facility site shall not be located within a five hundred (500) feet of a lawfully existing medical marijuana dispensary and/or lawfully existing growing/manufacturing facility as measured from the outermost boundaries of the lot or parcel on which the proposed growing/manufacturing facility and lawfully existing dispensary or growing/manufacturing facility is located;
- (4) Smoking and/or use of medical marijuana shall be prohibited at the growing/manufacturing facility;
- (5) All activity related to the growing/manufacturing facility shall be done indoors;
- (6) The premises shall be open for inspection upon request by the Building Official the Fire Department and law enforcement officials for compliance with all applicable laws and rules, during the stated hours of operation/use and as such other times as anyone is present on the premises.
- (7) Quarterly inspections may be made by the City Official's designee to confirm the growing/manufacturing facility is operating in accordance with applicable laws including, but not limited to, State Law and City Ordinances;
- (8) Any medical marijuana growing/manufacturing facility shall maintain a log book and/or database identifying by date the amount of medical marijuana on the premises for each qualifying patient/caregiver, keeping the qualifying patient and caregiver information confidential. This log shall be available to law enforcement personnel to confirm that the medical marijuana dispensary or growing/manufacturing facility does not have more medical marijuana than authorized at the location and shall not be used to disclose more information than is reasonably necessary to verify the lawful amount of medical marijuana at the facility. The facility shall maintain the confidentiality of qualifying patients in compliance with the Michigan Medical Marijuana Act, as amended.
- (9) If the growing/manufacturing facility ceases operation for a length of time of sixty (60) days or greater, the permit shall expire;
- (10) Growing/manufacturing facility drive-through facilities shall be prohibited;
- (11) All medical marijuana shall be contained within the main building in an enclosed, locked facility in accordance with the Michigan Medical Marijuana Act, as amended;
- (12) All necessary building, electrical, plumbing and mechanical permits shall be obtained for any portion of the structure in which electrical wiring, lighting and/or watering devices that support the cultivation, growing or harvesting of marijuana are located;
- (13) That portion of the structure where the storage of any chemicals such as herbicides, pesticides, and fertilizers shall be subject to inspection and approval by the Ypsilanti Fire Department to insure compliance with the Michigan Fire Protection Code;
- (14) Application for a Medical Marijuana Growing/Manufacturing Facility License shall be made to the City Clerk upon application forms provided by the Clerk for Medical Marijuana Growing/Manufacturing Facility License and signed by the applicant verifying the truth and accuracy of all information and representations in the application. Applications including information and documentation provided pursuant to an application shall be subject to the confidentiality rules under the Act. In addition to information and submittals, the application shall include payment of application fee in an amount set by the City Council;
- (15) The police department shall review the proposed application to operate a dispensary or growing/manufacturing facility regarding public health, safety, and welfare concerns of the proposal;
- (16) The dispensing of medical marijuana at the medical marijuana growing/manufacturing facility shall be prohibited.
- (17) There shall be no other accessory uses permitted within the same building.

Sec. 122-534. Multiple-family dwellings containing more than six units. (794)

Multiple family dwellings containing more than six units are subject to the conditions hereinafter imposed:

- (a) Access to the site from a major thoroughfare must not traverse through or abut an R1, CN-SF or CN-Mid district, unless access is directly from a major thoroughfare.
- (b) Access drives, parking areas, and maneuvering lanes must be located to encourage pedestrian and vehicular safety and convenience and to minimize their conflict with buildings and outdoor living areas. Sidewalks for convenient pedestrian flow between buildings, parking areas, outdoor living areas, and public rights-of-way must be provided.
- (c) The required parking spaces must be as conveniently located in close proximity to the dwellings they are intended to serve as is practicable. In no case may any parking space be located further than three hundred (300) feet from the nearest entrance to the building.

Sec. 122-535. Municipal, county, regional, and state service buildings and uses. (795)

Municipal, county, regional, and state service buildings and uses are permitted subject to the conditions hereinafter imposed:

- (a) For such uses proposed to be located within an R1, MD, CN, CN-SF, CN-Mid district, operating requirements must necessitate that the facility be located within that district in order to serve the immediate vicinity. Where possible such facilities must be located in another zoning district. Storage yards, sales or business offices, commercial buildings or activities, sanitary landfills, or water or sewage treatment plants are prohibited in the R1, MD, CN, CN-SF, and CN-Mid districts.
- 3870 (b) Public buildings and utility uses must not include any outdoor storage of materials or vehicles, unless as permitted within the PMD district.

N

Sec. 122-536. Nursing homes, convalescent homes and rest homes. (796)

Nursing homes, convalescent homes, and rest homes are subject to the conditions hereinafter imposed:

- (a) Such facilities must be constructed, maintained, and operated in conformance with applicable state and federal laws.
- 3880 (b) Such facility must provide the square footage of outdoor open space required by the Building Code and licensing agency. The open space must be landscaped, buffered from streets and parking lots, and include places for walking and sitting. Off-street parking areas, driveways, and accessory uses or areas may not be counted as required open space.

O

Sec. 122-537. Offices and showrooms for skilled trade services. (797)

Offices and showrooms of a skilled trade service are subject to the conditions hereinafter imposed:

- (a) Any fabrication, repair, cleaning or other processing of goods must conform to fire and building code.
- (b) Those areas of the ground floor which face upon or are visible from any adjacent streets must be used only for entrances, offices, sales, or display.
- (c) There must be no outside storage of materials or goods of any kind.
- (d) Storage of commercial and other vehicles inside the building is permitted, pursuant to building and fire code.

Sec. 122-538. Open-front or open-air businesses; outdoor recreation/amusement facilities; outdoor sales of new or used automobiles, trucks and tractors, boats, etc. (798, 800)

3890 Open-front or open-air businesses; outdoor recreation/amusement facilities; and outdoor sales or rentals of new or used automobiles, trucks and tractors, boats, mobile homes, recreational vehicles and trailers are subject to the conditions hereinafter imposed:

- (a) All loading and parking areas for open air businesses shall be confined within the boundaries of the site, and shall not be permitted to spill over onto adjacent public rights-of-way. Curbs or wheel stops shall separate parking areas from all sidewalks.
- (b) All areas of a front yard or street side yard which are not landscaped, shall be paved in accordance with adopted engineering standards. .
- 3900 (c) The location, layout, design, or operation of the outdoor business shall not impair the continued enjoyment, use, and future development of nearby properties. The use shall not generate excessive noise, odors, dust, or other impacts. The Planning Commission may specify hours of operation and stricter screening mechanisms to assure compatibility with adjacent uses.
- (d) In the case of automotive, commercial vehicle, or recreational vehicle sales lots, no major repair or major refinishing is permitted outside a fully enclosed building.
- (e) Outdoor sales, storage, and display areas shall comply with all minimum setback requirements for the zoning district or building type.
- (f) In the case of uses other than automotive, commercial vehicle, or recreational vehicle sales lots, all items offered for sale must be totally enclosed within a lawful structure or building, or otherwise safely and securely stored, between the hours of dusk to dawn.

3910 **Sec. 122-539. Outdoor storage of raw materials, supplies and products. (801)**

Outdoor storage of raw materials and supplies or finished or semi-finished products shall be subject to the conditions hereinafter imposed:

- (a) All such storage shall be located within a rear yard and screened with fencing in accordance with §122-634. No material shall be stored above the height of the screening.
- (b) All storage areas shall conform to all district setback requirements for principal uses, but in no case shall outside storage be located closer than 50 feet to residentially zoned property.
- (c) Property access to all parts of the storage areas shall be provided for fire and emergency services.
- (d) All loosely packed materials such as sand, topsoil, dirt, fertilizer, etc., shall be covered and contained to prevent them from being blown or washed off of the site.
- (e) No materials which give off noxious odors shall be stored outdoors.
- (f) Outdoor storage and display areas shall comply with all minimum setback requirements for the zoning district or building type.

Sec. 122-540. Outdoor cafes, restaurants, seating areas, and beer gardens. (799)

Outdoor cafes, restaurants, seating areas, and beer gardens shall be permitted subject to the conditions hereinafter imposed:

- (a) All outdoor seating areas at grade level must be accessory to business which provides indoor seating or food concession. All storage, preparation and cooking of food and all vending machines shall be within an enclosed building or food concession.
- (b) The outdoor seating area shall be separated from all parking areas by means of a minimum three-foot high planting, wall, or other architectural feature delineating the space.
- (c) The outdoor seating area shall not be located within 50 feet of any properties zoned R1, MD, CN, CN-Mid, or CN-SF.
- (d) All outdoor areas shall be kept clean and void of litter at all times.

P

Sec. 122-541. Passenger terminals and stations. (786)

Passenger terminals and stations are permitted subject to the conditions hereinafter imposed:

- (a) All ticket booths, waiting areas, and other passenger facilities must be wholly contained within an enclosed building.
- (b) Stopping and stacking spaces for buses or taxis must not encumber traffic nor present a safety hazard for vehicles or pedestrians on public rights-of-way.
- (c) Curb cuts must not be permitted at such locations that will tend to create traffic hazards in the streets immediately thereto. No drives may be wider than 30 feet at the right-of-way line, and no more than one such drive or curb cut may be permitted for every 50 feet of frontage along any street.

Sec. 122-542. Printing services. (810)

Printing services shall be permitted subject to the conditions hereinafter imposed:

- (a) All principal use activities, including storage of equipment and chemicals, shall be conducted within a totally enclosed building.
- (b) No exterior windows shall be oriented towards single-family residential uses.
- (c) Such uses shall not create a nuisance to adjacent residences through excessive noises or the smell of chemicals.

Q

R

Sec. 122-543. Religious Institutions and Private Assembly spaces, including social facilities. (780)

Religious institutions, private assembly spaces, and social clubs, including accessory offices, meeting rooms, and athletic facilities are subject to the conditions hereinafter imposed:

- (a) When located within the R-1 and MD districts, parking areas are prohibited in the required front yard. Parking areas must be screened in accordance with §122-684.
- (b) Buildings of greater than the maximum height allowed in the zoning district may be permitted by the Planning Commission with the condition that the front, side, and rear yards are increased beyond the minimum required yards by one foot for each foot of building height that exceeds the maximum height allowed. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, the Planning Commission may grant exceptions based on maximum compliance possible with the IT institutional building type.

- (c) Related uses such as social centers, social service centers, child care centers, and rental banquet facilities are prohibited except in accordance with the underlying zoning district.

Sec. 122-544. Recycling centers. (803)

Recycling centers for discarded items shall be permitted subject to the conditions hereinafter imposed:

- (a) Such use shall be located no closer than 300 feet to property zoned R1, CN-SF, CN-Mid, CN, or MD.
- (b) All separation and storage areas shall conform to the setback requirements for buildings in the PMD district and screened with fencing in accordance with §122-634.
- 3970 (c) Access to such site shall not be through or abut property zoned R1, CN-SF, CN-Mid, CN, or MD.
- (d) Proper access to all parts of the storage areas shall be provided for fire and emergency access as provided by the City building code.
- (e) Recycling drop-off centers shall not occupy more than 6,000 square feet of area; shall not handle vegetative yard wastes (grass clippings, leaves, brush, etc.) or industrial, toxic, or liquid wastes; and shall not be involved in the compounding, washing or cleaning, treating, or composting of any materials.

S

Sec. 122-545. Primary, Secondary and Post-Secondary Schools (public & private). (805)

Elementary, junior, senior high, and post-secondary schools, public and private schools (but not regulating home schooling as defined by the state department of education) shall be subject to the conditions hereinafter imposed:

- 3980 (a) Staff and curriculum must meet the educational qualifications established by the state.
- (b) All buildings must meet the building and fire safety qualifications as established by the state.
- (c) Except in the CN, CN-SF, CN-Mid, C, HC, NC, GC, and HHS districts, the minimum lot area shall be 13,000 square feet. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, and HHS districts, the minimum lot area is determined by the IT institutional building type.
- (d) The site shall have direct access to a major thoroughfare, as provided in §122-673.
- (e) Except in the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, buildings of greater than the maximum height allowed within a given zoning district may be allowed provided that the front, side, and rear yards are increased above the minimum required yards by one foot for each foot of building height that exceeds the maximum height allowed. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, the maximum height is determined by the IT institutional building type.
- 3990 (f) Except in the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, off-street parking shall be prohibited in the required front yard setback area. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, parking location is determined by the IT institutional building type. In the case any off-street parking area abuts a lot in any residential district, screening must be provided as provided in §122-634.
- (g) If bus transportation is to be provided, documentation that adequate ingress and egress for bus traffic to the site shall be provided. If public bus transportation is utilized, a bus drop-off point within 250 feet of the school shall be available.
- (h) All site improvements shall be shown on the site plan.

Sec. 122-546. Self-storage facilities and vehicle storage facilities. (806)

4000 Self-storage facilities and vehicle storage facilities shall be subject to the conditions hereinafter imposed:

- (a) In the C, NC and GC districts, self-storage and vehicle storage facilities must comply with the regulations for building types. In all other districts, the facility shall be surrounded by a six-foot high solid obscuring fence, except for entrance gates. Required fencing near ingress and egress driveways may be lowered to permit adequate sight distances for vehicles entering and exiting the facility.
- (b) No single storage space shall exceed 500 square feet, except for vehicle storage facilities.
- (c) Only vehicles may be stored in vehicle storage facilities.
- (d) Adequate security shall be provided and maintained.
- (e) A single residential unit, to be occupied only by a residential manager and their family, with a floor area not exceeding 1,500 square feet, is permitted.

4010 **Sec. 122-547. Substance abuse treatment facilities. (808)**

Substance abuse treatment facilities shall be subject to the conditions hereinafter imposed:

- (a) Such facilities shall have direct access to a major thoroughfare, in accordance with §122-673.
- (b) Such uses shall not be located within 1,000 feet of an R1, CN-Mid, or CN-SF district or of another such facility.

Sec. 122-548. Supportive Housing. (811)

Supportive housing shall be subject to the conditions hereinafter imposed:

- (a) The maximum number of persons served per the facility shall not exceed 8.
- (b) On-site services shall be for residents of the facility only.
- (c) If the owner of the property does not reside on the premises, the owner must appoint a resident manager, who resides on the premises. The property owner must provide the name and contact information of this person upon request by the City.
- (d) For each adult cared for, the square footage of outdoor recreation or relaxation area required by the Building Code must be provided in the rear, side, or street side yard. Such outdoor space must be fenced and screened from any adjacent lot.
- (e) All new construction or additions to existing buildings shall be compatible with the scale and character of the surroundings, and exterior building materials shall be harmonious with other buildings in the neighborhood.
- (f) Screening in accordance with §122-634 shall be provided along all rear and side yard boundaries between the proposed use and property either zoned or used for single-family and two-family purposes.

T

U

V

Sec. 122-549. Veterinary hospitals and clinics. (809)

Veterinary hospitals and clinics shall be permitted subject to the conditions hereinafter imposed:

- (a) All principal use activities, including animal boarding, shall be conducted within a totally enclosed building.
- (b) Buildings used for such purposes within 500 feet of a residential zoning district shall construct those indoor areas used for animal boarding an exercise in accordance with the soundproofing guidelines for dwelling units set forth in Section 1207.2 of the Michigan Building Code (2006).
- (c) A veterinary hospital or clinic shall be subject to the requirements, limitations, and regulations listed in Chapter 14, Division 4, of this Code.

W

X

Y

Z

Secs. 122-550 – 559. Reserved.

Division 2: Storage of Vehicles

Sec. 122-560. General prohibition. (731)

Except as otherwise provided in this chapter, no vehicles may be parked or stored on any residentially-zoned lot except for operable passenger automobiles, pickup trucks, vans, or motorcycles which are personally owned by the persons residing on the premises, or their guests.

Sec. 122-561. Commercial vehicles in residential areas. (732)

The parking or storage of a commercial vehicle over a two ton capacity is prohibited on any residential lot. However, this section does not apply to commercial vehicles temporarily parked less than eight hours in a residential area in conjunction with maintenance or service to a residential property.

Sec. 122-562. Recreational vehicles. (733)

- (a) The parking or storage of recreational vehicles, whether or not the recreational vehicle is mounted upon or hitched to another vehicle, including vacant mobile homes, antique or racing automobiles, or any other vehicles of a similar nature and related equipment, is prohibited on any lot in an R1, CN-SF, CN-Mid, CN, MD or HHS zoning district unless parked within a completely enclosed building or within a rear or side yard other than within a required yard setback area. Such vehicles stored in a side yard must be screened from view from the street and the adjacent property by an acceptable fence or landscaped screen, in accordance with [§122-634](#) of this chapter. Notwithstanding the above, no recreational vehicle may be parked or stored on any indoor or outdoor parking space which is required to meet the minimum parking space requirement in an CN, MD or HHS district.
- (b) No more than two recreational vehicles per dwelling unit may be stored outdoors at one time. The size of recreational vehicles kept or stored outdoors may not exceed eight feet in width, ten feet in height, or 32 feet in length.
- (c) Trailer coaches, motor homes, and other vehicles or equipment designed or adaptable for sleeping purposes must remain unoccupied and must not be connected to sanitary sewer facilities, or to electricity, water, or gas.

Sec. 122-563. Unlicensed, untitled, and inoperable motor vehicles, and disassembled parts of motor vehicles. (734)

No unlicensed, untitled, or inoperable motor vehicles, or disassembled parts of motor vehicles may be kept on any property within the City except as follows:

- (a) Contained entirely within a completely enclosed building so long as any indoor parking spaces, necessary for meeting minimum space requirements, must not be used for the storage of unlicensed or inoperable vehicles and so long as the storage is not otherwise prohibited.
- (b) The storage of vehicles as is specifically authorized in PMD and GC districts.
- (c) Minor repairs, such as changing flat tires, of vehicles where the repairs will be completed within 24 hours.

Sec. 122-564. Responsibility for violations. (736)

In any proceeding for violation of any provision of this division, both the person to whom a vehicle is registered as determined from the registration plate displayed on such motor vehicle, and the owner of the property on which the vehicle is stored, will be presumed to be persons who committed the violation charged. In the case of unlicensed vehicles, the owner of the property on which the vehicle is located will be considered to be the person responsible for the violation charged.

Secs. 122-565 – 569. Reserved.

Division 3: Communication Devices

Sec. 122-570. Intent. (681)

It is the intent of this division to provide reasonable regulations for the mounting of private communication antennas. The objectives of this division are to promote safety and prevent injury to persons and property, to maintain and promote the aesthetic and architectural quality of properties, to preserve property values, to balance the City's authority and duty to regulate the placement of communication devices in relation to the right to construct and use communication devices without reasonable restrictions, and to conditionally exclude from regulation by this division certain VHF and UHF television antennas meeting the criteria of §122-572(a).

Sec. 122-561. General standards. (682)

- (a) Permits. All applicants proposing to erect any communication device in any zoning district, except as excluded under §122-572(a), must be required to obtain a building permit and make payment of required fees.
- (b) Plot plan and mounting detail. Prior to issuance of a building permit for the erection of a communication device in any zoning district, the applicant must submit a plot plan showing to scale the precise proposed location of the communication device; its relative location to buildings on the site, adjoining properties, roads, landscaping, and natural features; the height and design of the structure; and foundation and/or mounting detail as appropriate for the Building Department to determine safety and building code compliance.
- (c) Standards. All communication devices must be installed, maintained, and grounded according to the standards as stated in the building code and must also meet wind and ice loads as specified in the building code.
- (d) Restrictions. All communication devices are subject to the following restrictions:
 - (1) Protrusion. Communication devices must not protrude or overhang in any way over any public right-of-way or adjoining property.
 - (2) Location. Communication devices must not be located in front yards or in the street side yard of corner lots.
 - (3) Advertising, symbols, lighting. No portion of any communication device may display any advertising message or other graphic representation other than a manufacturer's logo or nameplate or warning signs; provided such logo or letters are of a size and character that is not legible from adjacent properties. Except as required by the Federal Communications Commission, no communication device may be illuminated by direct or indirect lighting.
 - (4) Color and texture. All communication devices must be of a color and texture so as not to be conspicuous and to promote its visual blending into the adjacent background.
 - (5) Wood construction prohibited. Communications devices must not be constructed of wood.
 - (6) Ground mounted devices. All communication devices not mounted on a principal or accessory building must be permanently anchored to a foundation located on the ground. No ground mounted device may be located closer to a property line than its height as measured from the ground elevation at the base of the antenna structure.
 - (7) Roof mounted devices. All communication devices mounted on the roof of a building must be located on that portion of the building located adjacent to the rear of the property, unless it can be demonstrated that an alternative location is as safe or safer, and the visibility of the antenna from the adjacent properties and by pedestrian or vehicular passers-by is reduced or equal in comparison to a rear yard orientation/location.

Sec. 122-572. Antenna systems. (683)

In addition to the foregoing general standards of this division, the following standards must apply to antenna systems:

- (a) Conventional VHF and/or UHF television antennas which have width and height dimensions of not more than 135 inches and ten feet respectively, which are situated on the portion of the roof adjacent to the rear yard on the property, and which do not extend higher than ten feet above the ridge and/or peak of the roof, must be exempt from the requirements of applying for and receiving approval under this division. Exemption of such VHF and UHF television antennas from this division is based upon the following findings: there is relatively small concern for wind and snow load issues, there has been a long demonstrated safety record, there has been an historical acceptance of such facilities from an architectural and aesthetic standpoint, and the cost of compliance with the procedure for application and review would be great in relation to the cost of purchasing and installing such antennas.
- (b) Antenna systems which do not meet the criteria and condition of subsection (1) of this section must be regulated as follows:
 - (1) The antenna system must be located in a fenced or walled enclosure, so as to deter any person from climbing the tower, except for service or repair.

- (2) The antenna system must be of a self-supporting design.
- (3) Proof of liability insurance in the amount of \$100,000.00 must be submitted indicating protection of all adjacent property owners within a radius equal to 1½ times the height of the tower. This must include any City-owned property or right-of-way.
- (4) The antenna system must be used only for legal, amateur or commercial receiving and transmitting, as licensed by the Federal Communications Commission.

Sec. 122-573. Satellite dish stations. (684)

In addition to the general standards of §122-571, the following must apply to all satellite dish antennas:

- (a) Permit applications must contain the following additional information:
 - (1) In the case of a satellite dish proposed to be mounted on a roof in a commercial or manufacturing district, a detailed plan showing the exact location of the antenna on the roof.
 - (2) A picture, sketch, or catalog cut of the proposed installation, including the proposed coloration of the satellite dish.
 - (3) Proof of liability insurance in a minimum amount of \$100,000.00.
 - (4) Such other pertinent information as may be required by the Building Department.
- (b) No more than one satellite dish installation may be permitted on any single lot of record.
- (c) The satellite dish and all structural supports must be of noncombustible and corrosive resistant material.
- (d) Each satellite dish installation must be designed to withstand a wind force of 75 miles per hour without the use of any supporting guide wires.
- (e) Any driving motor must be limited to 100-volt maximum power design and be encased in protective guards. Any motor with operating voltage of more than 50-volt A.C. nominal must comply with Article 430 of the National Electrical Code.
- (f) A satellite dish antenna must be permanently mounted. A satellite dish antenna may only be on wheels or temporarily installed when used to demonstrate and/or test the feasibility of use.

Sec. 122-574. Communication devices in residential districts. (685)

In addition to the foregoing provisions, the following requirements apply to all communication devices in the R1, MD, CN, CN-Mid, CN-SF and HHS zoning districts:

- (a) Antenna systems.
 - (1) Ground mounted restrictions. Ground mounted antenna systems must not exceed a height of 75 feet, or a height equal to the distance from the base of the antenna system to the nearest property line whichever is less. There must be no more than one ground mounted antenna system on a single zoning lot.
 - (2) Roof mounted height restrictions. Roof mounted antenna systems must not exceed in height the lesser of the height of the roof plus ten feet, or the distance from the base of the antenna tower system (at its connection point with the roof) to the nearest property line.
- (b) Satellite dish stations.
 - (1) Height. No part of any satellite dish station may exceed 12 feet in height.
 - (2) Size. The diameter or any exterior dimension of any satellite dish station must not exceed ten feet.
 - (3) Location. All satellite dish stations in residential districts must be located in a rear yard and comply with the minimum distance requirements for detached accessory structures, as stated in §122-651, however, a satellite dish station may be located on the roof of a building under the following conditions:
 - (i) In the R1, CN-SF and CN-Mid zoning district, a satellite dish station may be located on the roof of a building associated with nonresidential use (i.e. school, religious institution or public service building), provided that the satellite dish station is located toward the rear of the building and is entirely screened from view from any public streets, pedestrian rights-of-way, or adjoining properties.
 - (ii) In the MD, or CN zoning districts, a satellite dish station may be located on any roof; provided the satellite dish station is located toward the rear of the building, no portion of the dish station extends higher than four feet above the ridge or peak of the building's roof, and the dish station is entirely screened from view from any public street or pedestrian right-of-way.
 - (iii) Screening. Conflicting land use screening must be installed around a ground mounted satellite dish antenna so as to reasonably conceal the view of the satellite dish antenna from adjacent public rights-of-way.

Sec. 122-575. Communication devices in C, HC, NC and GC districts. (686)

The following requirements must apply to all communication devices in the C, HC, NC, and GC zoning district.

- (a) Antenna systems.
 - (1) Ground mounted height restrictions. Ground mounted antenna systems must not exceed in height the lesser of 75 feet, or the distance from the base of the antenna system to the nearest property line.

- (2) Roof mounted height restrictions. Roof mounted antenna systems must not exceed in height the lesser of the height of the roof plus 40 feet, or the distance from the base of the antenna tower system (at its connection point with the roof) to the nearest property line.
- (b) Satellite dish stations.
 - (1) Ground mounted height restrictions. No part of any ground mounted satellite dish station may exceed 15 feet above ground level.
 - (2) Roof mounted height restrictions. Roof installations are permitted only on a building where the height of the roof surface where the satellite dish is to be mounted is at least 15 feet in height. No part of any satellite dish station may exceed higher than four feet above the ridge or peak of the building's roof, unless enclosed by an opaque screen not less in height than the satellite dish station. The design of the screening device must be compatible with the architectural design of the building upon which it is located.
 - (3) Size. The diameter or any exterior dimension of any satellite dish station must not exceed 15 feet.
 - (4) Location. All ground mounted satellite dish stations must be located in rear yards and comply with minimum distance requirements for accessory structures, as stated in [§122-651](#).
 - (5) Screening. Conflicting land use screening must be installed around a ground mounted satellite dish antenna so as to reasonably conceal the view of the satellite dish antenna from public rights-of-way.

Sec. 122-576. Communication devices in the PMD zoning district. (687)

- (a) Intent. The intent of this Section is to permit the location of mobile communication facilities within the PMD zoning district and while protecting the safety and character of nearby residential areas and the City. It is further the intent of this Section to require co-location of transmission and receiving apparatus on existing structures or facilities, unless it can be demonstrated by the applicant that co-location is not technically feasible.
- (b) Definitions.
 - (1) **Mobile Communication Facilities** mean and include all structures and accessory facilities relating to the use of the radio frequency spectrum for the purpose of transmitting or receiving radio signals. This may include, but not be limited to, cellular telephone towers, radio towers, television towers, telephone devices and exchanges, micro-wave relay towers, telephone transmission equipment building and commercial mobile radio service facilities. Not included within this definition are: citizen band radio facilities; short wave facilities; ham, amateur radio facilities; satellite dishes; and, governmental facilities which are subject to state or federal law or regulations which preempt municipal regulatory authority.
 - (2) **Attached Mobile Communications Facilities** means mobile communication Facilities that are affixed to existing structures, such as existing buildings, towers, water tanks, utility poles, and the like. A wireless communication support structure proposed to be newly established shall not be included within this definition.
 - (3) **Mobile Communication Support Structures** means structures erected or modified to support wireless communication antennas. Support structures within this definition include, but not be limited to, monopoles, lattice towers, light poles, wood poles and guyed towers, or other structures which appear to be something other than a mere support structure.
 - (4) **Co-location** means the location by two or more wireless communication providers of mobile communication towers on a common structure, tower, or building, with the view toward reducing the overall number of structures required to support wireless communication antennas within the community.
- (c) Locational Factors.
 - (1) The applicant must demonstrate the need for the proposed facility to be located as proposed based upon the presence of one or more of the following factors:
 - (i) Proximity to a major thoroughfare.
 - (ii) Areas of population concentration.
 - (iii) Concentration of commercial, industrial, and/or other business centers.
 - (iv) Areas where signal interference has occurred due to tall buildings, masses of trees, or other obstructions.
 - (v) Topography of the proposed facility location in relation to other facilities with which the proposed facility is to operate.
 - (2) It is the policy of the City to minimize the overall number of newly established locations for mobile communication Facilities and encourage the use of existing structures.
 - (i) Co-location must be deemed to be "feasible" for purposes of this section where all of the following are met:
 - The wireless communication provider entity under consideration for co-location will undertake to pay market rent or other market compensation for co-location.
 - The site on which co-location is being considered, taking into consideration reasonable modification or replacement of a facility, is able to provide structural support.

- The co-location being considered is technologically reasonable, e.g., the co-location will not result in unreasonable interference, given appropriate physical and other adjustment in relation to the structure, antennas, and the like.
- The height of the structure necessary for co-location will not be increased beyond a point deemed to be permissible by the City, taking into consideration the standards set forth in this section.

(ii) Requirements for Co-location:

- Approval for the construction and use of a new wireless communication facility must not be granted unless and until the applicant demonstrates that a feasible co-location is not available for the coverage area and capacity needs.
- All new and modified mobile communication facilities must be designed and constructed so as to accommodate co-location.
- If a party who owns or otherwise controls a facility fails or refuses to alter a structure so as to accommodate a proposed and otherwise feasible co-location, such facility will thereupon and thereafter be deemed to be a nonconforming structure and use, and must not be altered, expanded or extended in any respect.

(d) Application Requirements.

- (1) A site plan prepared in accordance with **Article III, Division 2 "Permits," Subdivision I "Zoning Compliance."** The site plan must also include a detailed landscaping plan illustrating screening and aesthetic enhancement for the structure base, accessory buildings and enclosure.
- (2) The application must include a signed certification by a State of Michigan licensed professional engineer with regard to the manner in which the proposed structure will fall, which certification will be utilized, along with other criteria such as applicable regulations for the district in question, in determining the appropriate setback to be required for the structure and other facilities.
- (3) The application must include a description of security to be posted at the time of receiving a building permit for the facility to ensure removal of the facility when it has been abandoned or is no longer needed (see **§122-576(f)**). In this regard, the security must, at the election of the applicant, be in the form of: (1) cash; (2) surety bond; (3) letter of credit; or, (4) an agreement in a form approved by the City Attorney and recordable at the office of the Register of Deeds, establishing a promise of the applicant and owner of the property to timely remove the facility as required under this section of the ordinance, with the further provision that the applicant and owner must be responsible for the payment of any costs and attorneys' fees incurred by the City in securing removal.
- (4) The application must include a map showing existing and known proposed mobile communication facilities within the City, and further showing existing and known proposed mobile communication facilities within areas surrounding the borders of the City in the location, and in the area, which are relevant in terms of potential co-location or in demonstrating the need for the proposed facility. If and to the extent the information in question is on file with the community, the applicant is required only to update as needed. Any proprietary information may be submitted with a request for confidentiality in connection with the development of governmental policy, in accordance with MCL 15.243(1)G. This ordinance serves as the promise to maintain confidentiality to the extent permitted by law. The request for confidentiality must be prominently stated in order to bring it to the attention of the City.
- (5) The name, address and phone number of the person to contact for engineering, maintenance and other notice purposes. This information must be continuously updated during all times the facility is on the premises.

(e) General Regulations.

- (1) Towers must not exceed 140 feet in height when measured at grade level. This requirement may be waived in the sole discretion of the City based upon a consideration of the following standards.
 - (i) The tower is to be used by no less than one additional co-locator.
 - (ii) The topography of the site in relationship to the immediate surrounding area necessitates a tower of increased height.
 - (iii) The screening capabilities of the site provide adequate mitigation of the obtrusive visual effects of the tower.
 - (iv) The land use characteristics of the area surrounding the subject site are compatible with a tower of increased height.
 - (v) There is no feasible and prudent alternative to a tower of increased height based upon the opinion of an independent expert.
- (2) The accessory building contemplated to enclose switching equipment must be limited to fifteen (15) feet in height.
- (3) The setback of the support structure from any residential district must be no less than double the height of the structure. The setback of the support structure from an existing or proposed rights-of-way or other

- 4320 publicly traveled roads must be no less than the height of the structure.
- (4) Where the proposed support structure abuts a parcel of land zoned from other than residential purposes, the minimum setback of the structure and accessory structures must be in accordance with the required setbacks from the main or principal buildings as provided in the schedule of regulations for the zoning district in which the support structure is located.
- (5) There must be an unobstructed paved access drive to the support structure for operation, maintenance, repair and inspection purposes, which may be provided through or over an easement. This access drive must be a minimum of fourteen (14) feet in width.
- (6) Where a wireless communication facility is proposed on a roof of a building, the equipment enclosure is not permitted as a roof appliance or penthouse on the building. The equipment enclosure may be located 4330 within the principal building or may be an accessory building, providing that as an accessory building it conforms with all district requirements for principal buildings, including yard setback and building height.
- (7) The support structure must be constructed in accordance with all applicable building codes and must include the submission of a soils report from a soils engineer, licensed in the State of Michigan. This soils report must include soil borings and statements indicating the suitability of soil conditions for the proposed use. The clearance requirements of the Federal Aviation Administration and Federal Communications Commission must be noted.
- (8) No wireless communication tower may be located within three thousand (3,000) feet of another wireless communication tower. This requirement may be waived at the sole discretion of the City if one of the following conditions are met:
- 4340 (i) The communication apparatus is located on an existing tower or other structure capable of accommodating such apparatus.
- (ii) The tower/facility is of an exceptional design so as to create a positive architectural and/or environmental feature which is compatible with the character of the surrounding area and community.
- (iii) The tower is intended to serve solely a governmental agency.
- (9) The tower and appurtenant apparatus building must be secured by fencing a minimum of six (6) feet in height. Conflicting land use screening of the apparatus building must be provided.
- (10) The applicant must submit details of tower lighting approved by the Federal Aviation Administration.
- (11) A maintenance plan must be presented as part of the site plan for the proposed facility.
- 4350 (12) The name, address and phone number of the person to contact for engineering, maintenance and other notice purposes must be posted on the perimeter fencing, and must be continuously updated during all times the facility is on the premises.
- (13) The proposed tower or wireless communication facility must be located within 500 feet of the Interstate 94 right-of-way. This does not apply to collocation of wireless communication antenna on existing towers, buildings, or other existing structure.
- (f) Removal.
- (1) The City reserves the right to request evidence of ongoing operation at any time after the construction of an approved tower.
- (2) A condition of every approval of a wireless communication facility must be adequate provision for removal of all or part of the facility by users and owners when the facility has not been used for 180 days or more.
- 4360 (3) The situations in which removal of the facility is required, the removal of antennas or other equipment from the facility, or the cessation of operations (transmission and/or reception of radio signals) must be considered as the beginning of a period of nonuse.
- (4) Upon the determination that a facility must be removed, the property owner or persons who had used the facility must immediately apply or secure the application for any required demolition or removal permits, and immediately proceed with and complete the demolition/removal, restoring the premises to an acceptable condition as reasonably determined by the Zoning Administrator.
- (5) If the required removal of a facility or a portion thereof has not been lawfully completed within sixty (60) days of the applicable deadline, and after at least thirty (30) days written notice, the City may remove or secure the removal of the facility or required portions thereof, with its actual cost and reasonable 4370 administrative charge to be drawn or collected from the security posted at the time application was made for establishing the facility.

Secs. 122-577 – 599. Reserved.

Article VI: Site Regulations

Division 1: Generally

Sec. 122-600. Scope. (631)

The provisions of this chapter apply to all lots and parcels of land and to every building, structure, or use, and extends vertically. No lot, building, structure, or part thereof, must hereafter be located, erected, altered, occupied, or used except in conformity with the provisions of this chapter. The general provisions of this article apply unless specifically stated otherwise.

Sec. 122-601. Control of heat, glare, fumes, dust, noise, etc. (632)

Every use must be so conducted and operated that it is not obnoxious or dangerous by reason of heat, glare, fumes, dust, noise, radiation, vibration, or odors beyond the lot on which the use is located. Furthermore, it shall be unlawful for any person to create, assist in creating, permit, continue, or permit the continuance of any public nuisance as defined and regulated under Article II of chapter 42.

Sec. 122-602. Damaged or destroyed buildings. (633)

- (a) The owner of any building or structure which has been damaged or destroyed by fire, windstorm, or other casualty must repair such damage within six months after its occurrence. However, nonconforming buildings and structures may only be repaired when in conformance with Article III, Division 3 "Nonconformities."
- (b) In the event the building or structure is damaged beyond repair, or repairs are not permitted by the terms of this chapter, then any part left standing after such damage or destruction must be demolished within six months of its occurrence pursuant to a permit granted by the City Building Department.

Sec. 122-603. Moving of buildings or structures. (643)

The moving of a building or structure to a different location must be considered as the erection of a new building and all provisions, regulations, and requirements relative to the erection of a new building must be applicable thereto. A performance guarantee may be required prior to such moving as provided in §122-317.

Sec. 122-604. Dumping on land prohibited. (634)

The use of land for the dumping or disposal of scrap metal, junk, junk cars, parts of automobiles, trucks, and boats; tires, garbage, rubbish, or other refuse; or of ashes, slag, or other wastes or by-products; is not permitted in any zoning district.

Sec. 122-605. Depositing or burying garbage; excavation or filling. (638)

- (a) The deposit or burying of garbage anywhere in the City is expressly prohibited.
- (b) The removal or filling of topsoil, sand, gravel or other material from or on the land is not permitted in any zoning district unless a site plan for such excavation or filling has first been approved by the Planning Commission and a permit is issued by the Building Department. Before approving such plan, the Planning Commission must determine that such removal will not cause standing water to collect or, at the expiration date of such permit, leave the surface of the land in an unsuitable condition or unfit for other land uses permitted in the district in which the removal or filling occurs; and that such fill or removal will not cause water or other materials to encroach on any public street, sidewalk, or adjacent property not owned by the applicant. When appropriate, the City may require that such fill or excavation areas are protected with fencing, rail guards, and warning signs.
- (c) This section does not apply to the normal removal or filling of soil for the construction of an approved building or structure when such plans have received site plan approval and a permit for such construction has been issued by the Building Department, or for the demolition of such when such demolition has received a permit from the Building Department.
- (d) This section is also not intended to regulate common household gardening, household composting, or general ground care.

Sec. 122-606. Dwelling on rear of lot. (635)

- (a) No building on the same lot and in the rear of a principal building may be used as a dwelling, nor may any building be located in front of a building used as a dwelling on the same lot, except as provided by this chapter, as legal accessory dwelling unit, or within an approved planned unit development.
- (b) The only exceptions to this requirement are dormitories, rectories, convents, or similar living quarters operated

and maintained in connection with a religious institution, school, hospital, or similar institution.


Sec. 122-607. Building Entrances, Rights of Way, and Easements. (636)

- (a) **Building entrance must face street.** No principal building can be placed on a lot unless the building is situated in such a manner that the front entry into the building faces the street to which the property is addressed.
- (b) **Construction of permanent structure over right of way or easement unlawful.** It is unlawful for any person to install, erect, cause or permit the installation of a permanent structure (such as a garage, building, swimming pool, fence, or tree) on or across an easement of record which will prevent or interfere with the free right or opportunity to use or make accessible such easement for its proper use, without prior authorization by City Council and/or the holder of such easement.
- (c) **Planned easements.** All site plans must show planned easements for non-motorized pathways in the City of Ypsilanti's Non-Motorized Plan, a 50 to 100 foot conservation and /or access easement along any Huron River frontage, the ReImagine Washtenaw Corridor Improvement Study and any planned road easement expansions approved by City Council. A proposed expansion of a structure or new building where the building or structure encroaches from the required setback from a planned easement for a street must be approved by the Planning Commission.

Sec. 122-608. Trash receptacles and dumpsters. (650) (637)

Any new or altered commercial use, including residential uses with three or more units, which requires zoning compliance review and has an outdoor trash storage area must comply with the following requirements:

- (a) No outdoor trash storage area may be located in any front yard or any required side yard setback which is adjacent to a street, unless there is no alternative as established by the City Planner or the Planning Commission. In no instance may any trash receptacle or dumpster be located within or block a designated parking space.
- (b) Any outdoor trash storage area must be limited to normal refuse which is collected on a regular basis and must be maintained in a neat, orderly and sanitary condition. This maintenance is the responsibility of the owner of the premises on which the containers are placed.
- (c) Adequate vehicular access must be provided to such containers for truck pickup either via a public alley or vehicular access aisle which does not conflict with the use of off-street parking spaces or entrances to or exits from principal buildings nearby.
- (d) All trash storage areas must be on a paved pad, and must be screened with an enclosure at least one (1) foot taller than the dumpster.
- (f) Where a dumpster is the primary means of collecting refuse, the trash storage area must be on a concrete pad, and screened with an enclosure at least six feet in height. The enclosure must be of a solid brick or masonry wall on three sides with an 80% opacity wooden swing door on the fourth side.



Sec. 122-609. Lighting. (641) (638)

- (a) Parking and loading facilities, building entrances, and building exits used during night-time hours shall be artificially illuminated.
- (b) All outdoor lighting must be so designed and arranged so as not to shine on adjacent properties or occupied dwellings, or adversely impact vehicular or pedestrian traffic on nearby streets, drives, walkways, or general rights-of-way.

- (1) Outdoor lighting originating on a site may not exceed one-half (0.5) footcandle at the lot line.
(2) Light fixtures must be full cutoff.
- 4480 (c) Outdoor lighting fixtures must not exceed 30 feet in height or the height of the principal building on the site, whichever is less. For development sites abutting lots zoned for one and two-family residential uses, lights must not exceed a height of 16 ft. The Planning Commission may modify the height restrictions in commercial and industrial districts, based on consideration of the following: the position and height of buildings, the character of the proposed use; and the character of surrounding land uses.
- (d) Where outdoor lighting is required by this chapter, the light intensity provided at ground level must be a minimum of one-third (0.3) footcandle anywhere in the area to be illuminated. Light intensity must average a minimum of one-half (0.5) footcandle over the entire area, measured five feet above the surface. Motion-activated lights are permitted, provided that the maximum levels are not exceeded and the lighting is kept in good working order.
- 4490 (e) Ornamental lighting.
- (1) Lighting placed inside a building but designed to be seen from the exterior, such as neon tubing outlining windows, is permitted; however, flashing or "chasing" effects are prohibited.
- (2) Uplighting intended to highlight ornamental features of a building or landscape is permitted, subject to the Building Code, provided that light output is not designed to exceed 400 lumens per fixture nor a color temperature of 3000K.

Sec. 122-610. Grades; elevation differentials. (639)

The grading of all building lots must be such as to divert water away from buildings and to prevent standing water and soil saturation detrimental to structures, lot use, and surrounding property.

Sec. 122-611. Steep slopes protection. (640)

- 4500 This section is intended to protect resources in environmentally sensitive areas to ensure that development does not result in erosion and in flooding during site preparation and the development process. Site alterations, re-grading, filling or the clearing of vegetation, or any other activity deemed detrimental to any environmentally sensitive area or resource prior to the submission of plans for subdivision or land development are a violation of this Ordinance.
- (a) General Design Standards. Structures must be designed in a manner that requires a minimum amount of alteration to the steep slope and that otherwise complies with the grading standards in item b of this section, except where a geologic hazard investigation report recommends otherwise, multi-level building design and/or terracing must be used. Otherwise, structures must be sited on existing level areas of the site. Particular caution must be taken to prevent increases in the rate of stormwater runoff and erosion downslope of any steep slope development site.
- 4510 (b) Specific Design Standards. The following specific design standards must be met on sites with steep slopes:
- (1) Any site disturbance of slopes exceeding twelve (12%) percent must be minimized.
- (2) No site disturbance must be allowed on slopes exceeding fifteen (15%) percent, except under the following circumstances.
- (i) Grading for a portion of a driveway accessing a single family dwelling when it can be demonstrated that no other routing which avoids slopes exceeding fifteen (15%) percent is possible.
- (ii) Upon submission of a report by a certified soil or geotechnical engineer indicating that the steep slope may be safely developed and execution of a provision agreeing to hold the City of Ypsilanti harmless from any claims of damages due to approval of such development. If development is allowed to proceed under this subsection, no more than (15%) percent of such areas must be developed and/or re-graded or stripped of vegetation.
- 4520 (iii) Finished slopes of all cuts and fills must not exceed three-to-one (3:1 or 33%), unless the applicant can demonstrate that steeper slopes can be stabilized and maintained adequately.

Sec. 122-612. Retaining walls. (646) (641)

Retaining walls in excess of one foot in height require a building permit. All retaining walls must be designed and built so as to safely resist lateral pressures of soil behind them and be safely supported by soil beneath them. Additionally, retaining walls must be maintained in structurally sound and safe repair and must not impair drainage or create negative impacts on any other lot.

Sec. 122-613. Height exceptions (NEW) (642)

- 4530 (a) The height requirements of all zoning districts may be exceeded by chimneys, flagpoles, church spires, belfries, cupolas, domes, or other similar architectural embellishments, roof mounted communication antennas, water towers, observation towers, power transmission towers, radio towers, masts, smokestacks, ventilators, skylights,

derricks, conveyors, cooling towers, and other similar and necessary mechanical appurtenances pertaining to the permitted uses of the districts in which they are located; provided that they do not exceed the maximum permitted height for buildings in a given district by more than ten feet.

- (b) In the PMD district, chimneys, cooling and fire towers, elevator buildings, parapets, roof storage tanks, communication towers and other necessary appurtenances are permitted to heights greater than ten feet above the maximum permitted building height; provided such appurtenances are located at least the same distance from any adjoining property line as their height.

Secs. 122-614 – 619. Reserved.

4540 **Division 2: Yard, Area, and Lot Requirements**

Sec. 122-620. Altered land parcel. (751) (650)

- (a) No lot or parcel of land may be divided, altered or reduced by sale, gift, or other disposition so that the yards, parking area, or other open spaces, or the land area thereof is less than the minimum requirements of this chapter.
- (b) No lot, parcel of land, parking area, or other open space may be reduced so as to increase its noncompliance with the minimum requirements of this chapter.

Sec. 122-621. Area requirements. (752) (651)

4550 In determining lot, land, yard, parking area or other open space requirements, no area may serve to meet such requirements for more than one principal building or use, and no area necessary for compliance with the space requirements for one principal building or use be included in the calculation of the space requirements for any other building, structure, or use.

Sec. 122-623. Lots adjoining alleys. (753) (652)

In calculating the area of a lot that adjoins an alley for the purpose of applying lot area requirements of this chapter, one-half the width of such alley abutting the lot is considered as part of such lot.

Sec. 122-624. Determinations by Zoning Board of Appeals. (754) (653)

When yard regulations cannot reasonably be complied with, or where their application cannot be determined on lots of peculiar shape, topography or due to architectural or site arrangement, such regulations may be modified or determined by the Zoning Board of Appeals.

Sec. 122-625. Land division. (755) (654)

- 4560
- (a) Lot split or consolidation. The division of lots must take place in accordance with the land division act, Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101 et seq., MSA 26.430(101) et seq.), as amended. Pursuant to the authority granted the City to regulate the division of a lot or parcel of land in a recorded plat, the division of a lot or other parcel of land in a recorded plat is prohibited unless first approved by the City assessor and City Planner in accordance with the land division act, Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101 et seq., MSA 26.430(101) et seq.).
 - (b) Subdivision plats. The subdivision of a tract of land into two or more lots, building sites, or other divisions for the purpose of sale or building development, must take place in accordance with the land division act, Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101 et seq., MSA 26.430(101) et seq.), as amended.

Secs. 122-626 – 629. Reserved.

4570 **Division 3: Landscaping and Screening**

Sec. 122-630. Purpose. (701) (660)

The intent of this section is to:

- protect and preserve the appearance, character, and value of the community;
- minimize noise, air, soil, groundwater, surface water and visual pollution;
- minimize soil erosion and runoff, provide protection from wind and sun, mitigate the heat island effect and promote energy conservation;
- improve the overall aesthetics and appearance, divide the expanse of pavement, and define parking areas and vehicular circulation within off-street parking lots and other off-street parking facilities;
- buffer residential areas and lower-intensity land uses from more intense land uses;
- 4580 • encourage an appropriate mixture of plant material, such as evergreen and deciduous trees and shrubs, to protect against disease infestation and produce a more aesthetic and cohesive design;
- encourage the integration of existing vegetation in landscape plans and preservation of specimen trees.

Sec. 122-631. Landscape plan requirements. (702) (661)

A separate detailed landscape and tree protection plan at a scale of not greater than 1"=50' must be submitted to the City as part of the site plan review or tentative preliminary plat review. The landscape/tree protection plan must demonstrate that all requirements of this Division are met and must include, but not necessarily be limited to, the following items:

- (a) Location, spacing, size (caliper), root type (shallow or deep) and descriptions for each plant type (deciduous, evergreen, annual, or perennial) to be planted.
- 4590 (b) Location, size (caliper), root type (shallow or deep), health and species name of all trees and plants to remain on the site. If trees or plants are proposed to be remain, information showing how these trees and plants will be protected during construction must be shown.
- (c) Typical straight cross section including slope, height, and width of berms.
- (d) Typical construction details to resolve specific site conditions, such as landscape walls and tree wells used to preserve existing trees or maintain natural grade.
- (e) Details in either text or drawing form to ensure proper installation and establishment of proposed plant materials as prescribed by the American Standard for Nursery Stock.
- (f) Identification and description of grass and other ground cover to be planted and method of planting (sod, plugs, sprigs or seeds).
- 4600 (g) Identification of landscape maintenance program in accordance with §122-633.

Sec. 122-632. Landscape elements. (711) (662)

The following minimum standards apply:

- (a) **Quality.** Plant materials must be of generally acceptable varieties and species that are not invasive, free from insects and diseases, hardy to Washtenaw County, conform to the current minimum standard of the American Standard for Nursery Stock, and must have proof of any required governmental regulations and/or inspections.
- (b) **Composition.** A mixture of plant material and species, such as evergreen deciduous trees and shrubs, is recommended as a protective measure against insect and disease infestation. A limited mixture of hardy species is recommended rather than a large quantity of different species to produce a more aesthetic, cohesive design and avoid a disorderly appearing arrangement.
- 4610 (c) **Quantity.** Plant quantities may not count to satisfy more than one requirement, unless otherwise stated within the requirement.
- (d) **Berms.** Berms are only permitted at the discretion of the Planning Commission. If permitted, they must be constructed with slopes not to exceed a 1:3 gradient, and protected with sod, seed, or other form of natural ground cover.
- (e) **Tree Species.** All trees must be a species on a list of approved trees maintained by the City of Ypsilanti, with the exception of fruit-bearing trees. Fruit-bearing trees are allowed in yard areas where they do not overhang sidewalks, walkways, or parking lots. The Planning Commission may allow species not on list of approved trees, with a finding that the species is appropriate to the circumstance.
- (f) **Minimum Size-Requirements.** Where landscaping is required the following schedule sets forth minimum size requirements for representative landscape materials:
- 4620

Plant Material	Minimum Size
Trees	2.5" in caliper

Shrubs	24" in height
--------	---------------

(g) **Credit for Existing Vegetation.** The preservation and incorporation of existing trees and shrubs is encouraged. Existing shrubs and trees may be used to satisfy the requirements of this section, if all of the following requirements apply:

- (1) Paving or other impervious site improvements do not encroach upon the drip line of the existing tree(s) to be preserved.
- (2) If existing plant material is labeled "To Remain" on site plans by the applicant or required by the City, protective techniques must be installed during construction. No vehicle or other construction equipment may be parked or stored within the drip line of any plant material intended to be saved.
- (3) The shrubs and/or trees are in good health. In the event that healthy shrubs or trees which are used to meet the minimum requirements of this Ordinance or those labeled to remain are cut down, destroyed, damaged, or excavated at the drip line, as determined by the City, the applicant must replace them with trees which meet Ordinance requirements.
- (4) The trees or shrubs proposed for credit are not a species that is invasive, brittle, susceptible to disease and insects, has a root structure that will interfere with underground utilities, drops excessive litter or other undesirable characteristics. Species ineligible for credit include but are not limited to: Ash (*Fraxinus*), Black Locust (*Robinia spp.*), Black Walnut (*Juglans nigra*), Siberian Elm (*Ulmus pumila*); Box Elder (*Acer negundo*), Tree-of-Heaven (*Ailanthus spp*), and Gingko Female (*Gingko biloba*).
- (5) The shrubs and/or trees meet the following minimum sizes and may receive credit in lieu of new plantings based on size shown in the table below:

Plant Material	Minimum Size	Size	Credit
Trees	2.5" in caliper	2.5"-8"	1
		8"-12"	2
		12"-20"	3
		Over 20"	5
Shrubs	24" in height	All sizes	1

Sec. 122-633. Installation, maintenance, and completion. (712) (663)

- (a) All required landscaping must be planted before obtaining a Certificate of Occupancy, or a Temporary Certificate of Occupancy may be issued once the appropriate financial guarantee as set forth in §122-317 is placed in escrow in the amount of the cost of landscaping, to be released only after landscaping is completed.
- (b) All landscaping and landscape elements must be planted, and earth moving or grading performed, in a sound and professional manner, according to accepted planting and grading procedures.
- (c) All plant material must be maintained in good condition so as to present a healthy, neat and orderly appearance and must be trimmed or pruned in such a manner so as to not alter their natural growth potential.
- (d) The owner of property required to be landscaped by this Ordinance must maintain such landscaping in a strong and healthy condition, free from physical damage or injury arising from lack of water, chemical damage, insects, diseases, blight or other causes. All materials used to satisfy the requirements of this Ordinance which become unhealthy or dead must be replaced within six (6) months of damage or death or the next appropriate planting period, whichever comes first.
- (e) All landscaped areas must be provided with a readily available and acceptable water supply. Underground sprinkler systems may be installed, utilized and maintained in order to insure the proper watering of all plant materials on the sites.

Sec. 122-634. Screening between conflicting land uses. (703) (664)

(a) Screening between land uses is required when:

- Required elsewhere in this Chapter;
- When a PMD zoning district abuts any other zoning district;
- When a HHS, HC, NC, or GC zoning district abuts a R-1, CN-SF, CN-Mid, CN, or MD zoning district;
- When a non-residential use abuts a property where a residential use occupies the first floor of the principal structure;
- Any building with three dwelling units or more abuts an a building with an equal or lesser number of dwelling units in the R-1, CN-SF, or CN-Mid zoning districts.

(b) The quantities of plant material required by this section may not count for the quantities required elsewhere in

this ordinance.

- (c) Location. Screening must be provided along all lot lines between conflicting land uses when required by this section. The Planning Commission may approve a waiver for the location of the screen upon a finding that the location of utilities interfere with the proposed location; it may also approve a waiver upon a finding that the height of the screening must conform with §122-635.
- (d) Construction. Screens must be a wall, fence, or landscape buffer at least six (6) feet in height.
- (1) A wall or fence must be at least 80% opaque and may be constructed of face brick, poured-in-place simulated face brick, precast brick face panels having simulated face brick, stone, wood, or other durable material, subject to discretionary approval of the approving body. Wire or chainlink fencing with slats is not permitted.
- (2) A landscape buffer must consist of evergreen trees and evergreen shrubbery to maintain a minimum opacity of at least eighty (80) percent. To achieve effective screening, landscape materials must be planted in a staggered manner.

Sec. 122-635. Fences and walls. (713) (665)

Except as otherwise required by this Ordinance, the following regulations apply:

- (a) The use of barbed wire, spikes, nails, or any other sharp point or instrument of any kind on top or on the sides of any fence is prohibited. Planning Commission may waive this restriction with a finding that such materials are in the interest of public safety.
- (b) No fence may be constructed or maintained which is charged or connected with an electrical current.
- (c) Retaining walls must be designed and constructed in accordance with applicable Building Code requirements and the requirements of §122-612.
- (d) Temporary construction fences and fences required for protection around excavations must comply with the Building Code. Such fences must be removed upon the issuance of a Certificate of Occupancy.

Sec. 122-636. Street Trees (704) (666)

The frontage of all public or private streets for any new or altered use which requires site plan review must be landscaped with street trees as follows:

- (a) Location. The street trees must be centered between the sidewalk and the back of street curb. Planning Commission may grant a waiver of this condition with a finding that utilities necessitate a different location, or that the proposed location of the trees will align with already-established street trees along the same block face, provided that said existing trees are to remain.
- (b) Quantity. A minimum of one (1) tree for every thirty (30) lineal feet of frontage, inclusive of proposed or existing access drives. Existing trees in good health to be preserved may count towards the street tree requirements.
- (c) Planting Area Size. Tree pits provided for street trees must be sufficient for the species of tree provided. Where no sufficient planting bed exists or can be provided for street trees within the right-of-way, the applicant may choose to either plant and maintain the required trees within the front yard; or to provide a fee in lieu of planting in the amount of 100% of the materials and installation cost.

Sec. 122-637. Foundation landscaping. (707) (667)

Foundation plantings are required in the MD zoning districts and in the GC and NC zoning districts for the Single Story Commercial Building and Large Footprint Single Story Commercial Building building types, and must meet the following standards:

- (a) Location: Foundation plantings must be provided along the front or sides of any buildings which face a public road and/or is adjacent to a parking lot or other area which provides access to the building(s) by the general public. Foundation planting areas must be between the front or sides of the building and any paved area, adjacent to the building.
- (b) Quantity. Foundation planting areas must contain a minimum of six (6) shrubs per thirty (30) lineal feet of applicable building frontage.
- (c) Planting Area Size. Individual planting areas must be of a size appropriate to the proposed plantings, but no less than four feet in depth, measured perpendicular from the building.

Sec. 122-638. Site landscaping. (708) (668)

Inclusive of any landscaping required by this section, at least ten percent (10%) of the site area, excluding existing public rights-of-way, must be landscaped. Such site area landscaping may include a combination of the preservation of existing tree cover, planting of new trees and plant material, landscape plazas, gardens, vegetated roofs, and foundation landscaping beds.

- 4720 **Sec. 122-639. Accessory Stormwater Control Features (789) (669)**
- (a) **Swales.** Biofiltration swales are permitted in all districts.
 - (b) **Pervious paving.** Pervious paving is permitted in all districts, subject to adopted engineering standards.
 - (c) **Rain gardens.** Rain gardens installed accessory to one- or two-family uses in the R-1 district or the Townhouse, Cottage, or House building types in the CN, CN-Mid, CN-SF districts do not require engineering review.
 - (d) **Rain barrels or cisterns.** Rain barrels or cisterns are permitted in all districts.
 - (1) Underground cisterns or rain barrels are subject to engineering review and constructed in accordance with the State Building Code.
 - 4730 (2) Aboveground rain barrel or cistern systems in excess of 250 gallons accessory to the Mansion, Estate, Apartment House, Courtyard Apartment, Apartment Building, Commercial/Mixed-Use Small, Commercial/Mixed-Use Medium, Commercial/Mixed-Use Large, Single-story Commercial Building, Large Footprint Single Story Commercial Building, Multiple Story, or Institutional building types; or in excess of 250 gallons and located in the R-1 district not accessory to a single-family use; or in excess of 250 gallons and located in the MD or PMD districts, must conform to the accessory building standards in place for those building types and be subject to engineering review and constructed in accordance with the Building Code.
 - (e) **Vegetated roofs.** Vegetated roof systems are permitted in all districts in accordance with the Building Code.
 - (f) **Other methods.** Other methods of onsite stormwater control may be submitted to the City Planner and, at their discretion, may be approved, approved subject to another City department(s) review, approved subject to 4740 Planning Commission review, or denied.
 - (g) The plant material required by this section may be used to meet plant material quantity and placement requirements of this Chapter, provided that Planning Commission or other approving body finds that the intent of this Chapter is met.

Sec. 122-640. Screening of electrical equipment and transformers. (710) (670)

- (a) Transformers that may be visible from any primary visual exposure area must be screened with either plantings or a durable non-combustible enclosure which are unified and harmonious with the overall architectural theme, and meet utility provider standards for location and maintenance.
- (b) Utility equipment must be mounted on the side of a building wherever possible, and must be located where it is substantially screened from public view.

4750 **Sec. 122-641. Modifications or exceptions to requirements. (714) (671)**

- (a) Buildings Abutting Property Lines. Required screening may be omitted along any lot line where a building wall exists immediately abutting the lot line.
- (b) Location Adjustments. Where property line screening is required, the location may be adjusted at the discretion of the Planning Commission so that the screening may be constructed at or within the setback area, provided the areas between the screening and the property lines are landscaped or retain their natural vegetative state.
- (c) Planning Commission Modifications. Any other requirements of this Section may be waived or modified through site plan approval, provided the Planning Commission first makes a finding that:
 - 4760 (1) That the topographic features or special characteristics of the site create conditions so that the strict application of the provisions of this Section will result in less effective screening and landscaping than alternative landscape designs; or
 - (2) That the public benefit intended to be secured by this Section will exist with less than the required landscaping or screening; or
 - (3) The historic district designation on the property precludes the ability to require any or all of the landscape requirements.
- (d) In the case of conflicting land use screening, with the finding that the design and placement of the screen meets the intent of the zoning ordinance in general and the zoning district in particular.

Secs. 122-642 – 649. Reserved.

Division 4: Accessory Structures, Porches, and Decks

Sec. 122-650. Purpose. (666) (680)

4770 The intent of this division is to regulate accessory structures and uses in order to preserve adequate open spaces and separation between uses which may impact adjacent properties. Accessory uses and structures are generally permitted uses in their respective zoning districts, subject to the provisions of the this division.

Sec. 122-651. General standards for accessory structures. (667) (681)

- (a) Attached Accessory Structures. Where an accessory structure is attached to and made a part of the principal building (excluding breezeways or canopies), such accessory structure must comply in all respects with the requirements of this chapter applicable to the principal building.
- (b) Detached Accessory Structures. The following standards, unless otherwise stated in this chapter, govern all detached accessory structures. A "detached accessory structure" is one which is not attached to the principal structure; however, a breezeway or other enclosed or roofed over connecting way may connect the principal structure to an accessory structure provided that such breezeway or connecting way does not exceed eight feet in width and does not exceed the height of the accessory structure. Detached accessory structures include, but are not limited to, garages, sheds, toolhouses, swimming pools, tennis or basketball courts or other recreational equipment.
- 4780 (1) Building permit. No accessory structure may be erected, moved, altered, or razed until a building permit has been obtained from the Building Department.
- (2) Height. The maximum height for a detached accessory structure must be 15 feet; except in the PMD district, in which accessory structures may be constructed equal to the permitted maximum height of structures in such district, subject to Planning Commission review and approval.
- (3) Location. All detached accessory structures must be located in rear yards or side yards. On corner lots, detached accessory structures cannot be located in the required street side yard setback. In no instance may an accessory structure be located within a dedicated easement.
- 4790 (4) Setback and ground coverage requirements. All detached accessory structures must meet the setback and ground coverage regulations for the underlying zoning district and, if applicable, building type.
- (5) Architecture/siding. The architectural character of all accessory buildings must be compatible with that of the principal building. All accessory buildings in all zones except the PMD district, must be sided and roofed with materials which are complementary with the principal building.
- (6) Sleeping quarters. The use of any accessory building for the overnight housing of persons is prohibited, unless expressly permitted by this chapter or this Code.
- (7) Mobile homes. Mobile homes are not permitted as an accessory use to a permitted principal use.
- 4800 (8) Subdivision of lots. No parcel or lot may be subdivided unless and until all detached accessory buildings comply with this chapter with respect to allowable size and setback requirements for the proposed lot on which the buildings are to be located.

Sec. 122-652. Enclosed storage of liquid and solid fuels. (807) (682)

Storage within enclosures of liquid and solid fuels shall be permitted subject to the conditions hereinafter imposed:

- (a) All storage tanks and the handling of all flammable liquids shall be in compliance with the building code as adopted by this Code.
- (b) Below-ground storage tanks shall be located no closer than 50 feet from any property line and, when required, shall be registered with the state fire marshal.

Sec. 122-653. Swimming pools. (668) (683)

4810 Prior to the issuance of a building permit for the construction of an outdoor swimming pool in any zoning district, the following provisions must be satisfied:

- (a) An application for a building permit must be accompanied by a complete and detailed set of plans and specifications for the swimming pool, including type of construction, size, location on lot in relation to lot lines and buildings on the site, fencing, and related equipment, which show that the following minimum standards will be met.
- (b) The swimming pool must be located no closer than ten feet to any side or rear lot line, and no part of any pool may be constructed within a front yard or required side yard setback adjacent to a street.
- (c) Swimming pools must be located a minimum of four feet from any building on the same parcel and a minimum of 25 feet from any dwelling on an adjoining lot which is located within an R1, MD, CN-SF, CN-Mid or CN district.
- 4820

- (d) All pool associated wiring and wiring in, around, over or under the pool must comply with the latest edition of the National Electrical Code as adopted by this Code.
- (e) All swimming pools must be enclosed by a fence of a type not readily climbed by children which must be at least five feet in height from the ground level. However, if the entire yard of the residence is enclosed, then this provision may be waived by the Building Department upon inspection and approval of the yard's enclosure; or if the pool is of a portable or above ground type, with a wall height of at least five feet above the surrounding ground surface, and of such construction as not to be readily climbed by children, then the ends of the fence may be attached to the pool structure and the fence need be erected only around the immediate area of the ladder and other means of access to the pool. Gates must be of self-closing latch type with the latch on the inside of the gate, not readily available for children to open. Gates must be securely locked when the pool is not in use. Pools must be enclosed by such fence before water is placed in pool. All fences are subject to the requirements of §122-635.
- (f) Water retained in any pool regardless of depth must be maintained clean and sanitary as provided in the Building Code, water treatment standards.
- (g) The Building Department has the right at any reasonable hour to inspect any swimming pool for the purpose of determining that all the provisions of this chapter are fulfilled and complied with. Any outdoor swimming pool installed, operated or maintained in violation of the provision of this section constitutes a nuisance, and the City may, in addition to the penalties set forth in §122-375, maintain any proper action for the abatement of such nuisance.

Sec. 122-654. Porches, decks, balconies, fire escapes, and barrier-free access ramps. (644) (684)

(a) Porches, decks, terraces and balconies.

- (1) An open or unenclosed porch or terrace may project into a required front yard setback for not more than ten feet, unless otherwise regulated within this chapter. An open, unenclosed terrace or patio flush with the ground is not subject to this restriction.
- (2) An open or unenclosed porch or terrace over nine inches in height must meet all side and rear yard setback requirements.
- (3) An open or unenclosed balcony may project into a required front yard setback for not more than ten feet, but must meet all side and rear yard requirements.
- (4) All enclosed porches, decks, or balconies are an integral part of a building and must meet all yard setback requirements of that structure.

(b) Fire escapes. No fire escape can be located within any front yard. All fire escapes must meet all side and rear yard setback requirements.

(c) Barrier-free access ramps. Barrier-free access ramps may be located within any front, side or rear yard, provided that no portion of the ramp which exceeds over 36 inches in height is located within any required minimum yard setback area. This provision may be waived by the Building Department for a temporary barrier-free access ramp to a single-or two-family dwelling, provided that the Building Department finds that such proposed barrier-free ramp will not pose a fire or safety hazard, and will not obstruct traffic vision. A temporary barrier-free access ramp must be removed within 14 days after the person needing the ramp ceases to occupy a dwelling.

(d) Architectural features. Window sills, cornices, eaves, bay windows, and other architectural features may project into a required side yard not more than two inches for each one foot of width of such side yard; and may extend into any front or rear yard not more than three feet.

Secs. 122-655 – 659. Reserved.

Division 5: Signs

Sec. 122-660. Purpose. (861) (690)

The purpose of this article shall be to permit such signs as will not, by reason of their size, location, construction or manner of display, endanger life or limb, interfere with traffic safety, or otherwise endanger the public morals, health or safety. It is further the intent of this article to:

- Maintain and enhance the aesthetic value of the City;
- Encourage free expression of ideas and dissemination of messages, regardless of content, using signs that are compatible with their surroundings and legible under the circumstances in which they are seen;
- Enhance pedestrian and vehicular traffic safety;
- Minimize the adverse effects of signs on nearby public and private property;
- Protect and enhance economic vitality by assuring aesthetic appeal for residents and visitors;
- Preserve property values;
- Enhance the effectiveness of permitted signs and directional and warning signs;
- Seek the removal of illegal signs and encourage the replacement or removal of nonconforming signs that are incompatible with the purpose of this article.

Sec. 122-661. Generally. (862) (691)

- (a) **Building Permit Required.** Except as provided in this Chapter, no sign shall be constructed or erected prior to the issuance of a permit by the Building Department, and approval from other applicable reviewing bodies.
- (b) **Public Rights-of-Way.** Signs shall be expressly prohibited from locating in all public rights-of-way and dedicated public easements except as otherwise provided for in this ordinance, and as follows:
- (1) Signs erected by the City or other governmental entities
 - (2) Overhead banners
 - (3) Sidewalk signs
 - (4) Building mounted signs may project over a public right-of-way or easement provided they comply with the applicable design standards for the specific type of sign and that they maintain a minimum clearance of eight feet. A projecting sign shall project not more than four feet from the wall of a building and shall not project above the front wall of the building.
- (c) **Signs exempted.**
- (1) Any sign required by City ordinance or State law, as applicable. This includes, but is not limited to, address signs, Fire Department Connection signs, or signs indicating barrier-free parking locations.
 - (2) Any sign less than three square feet in area and five feet in height on the interior of a site placed so as to be oriented and clearly legible to persons on the site, provided that each sign be no closer than twenty feet to another such sign.
 - (3) Drive-Through Signs. Any use that includes a drive-through is permitted to have signs up to a maximum height of six feet and a maximum area of 32 sq. ft. per drive-through use, located in the rear of the site, when placed so as to be oriented and clearly legible to persons on the site.
- (d) **Traffic and Pedestrian Hazards.** The placement, size, content, coloring or manner of illumination of signs shall not create traffic or pedestrian hazards. No sign shall make use of the words “stop,” “look,” “danger” or other word, phrase or symbol in a manner that is confusing or misleading. No sign or flashing light shall be erected or maintained in any manner which, by reason of its size, location, context, coloring or manner of illumination, shall constitute a traffic hazard or which shall interfere with the visibility of any traffic control device.
- (e) **Obstruction Prohibited.** No sign shall be placed so as to obstruct any fire escape, required exitway, window, or door opening used as a means of passage or as access for firefighting purposes.
- (f) **Obstruction to ventilation.** A sign shall not be attached in any form, shape or manner which will interfere with any opening required for ventilation by the building code; except that such signs may be erected in front of and may cover transom windows when not in violation of the provisions of this chapter.
- (g) **Maintenance.** All signs, sign frames, sign copy area, panels, structural elements, lamps and electrical hardware shall be maintained in good repair and working order, so as to present a neat and orderly appearance. Non-galvanized or corrosion-resistant materials shall be painted when necessary to prevent corrosion.
- (h) **Authorized sign contractors.** Every person before engaging or continuing in the business of constructing, repairing or dismantling signs, poster boards or other display signs in the City, shall first furnish the City a public liability insurance policy, approved by the City attorney, with minimum limits of \$300,000.00 combined single limit bodily injury and/or property damage, and the contractor agrees to indemnify the City from all

4920 damage suits or actions of every nature brought or claimed against the contractor for or on account of injuries to persons or damages to property received or sustained by any person or person through any act of omission or negligence of such erector, agents or employees in the erection, repair or dismantling of any sign, poster board or other display sign. Such policy shall contain a clause whereby such policy cannot be canceled until after a written notice of intention to cancel has been filed with the City clerk at least 30 days prior to the date of cancellation.

- (i) **Sign Area Calculation.** The square footage of a two-, three- or four-faced sign shall mean the square footage of the largest face of the sign.

Sec. 122-662 Construction requirements. (orig part of 862) (692)

- 4930 (a) All signs shall conform to the City building code unless more stringent requirements are specified in this article. Signs and sign structures shall be designed and constructed to resist wind and seismic forces as specified in this section. All bracing systems shall be designed and constructed to transfer lateral forces to the foundation. For signs on building the dead and lateral loads shall be transmitted through the structural frame of the building to the ground in such a manner as not to overstress any of the elements thereof.
- (b) The overturning movement produced from lateral forces shall in no case exceed two-thirds of the deadload resisting movement. Uplift due to overturning shall be adequately resisted by proper anchorage to the ground or the structural frame of the building. The weight of earth imposed over footings may be used in determining the dead-load resisting movement. Such earth shall be carefully placed and thoroughly compacted.
- (c) Wind loads. For the purpose of design, wind pressure shall be taken upon the gross area of the vertical projection of all signs and sign structures at not less than 20 pounds per square foot for those portions less than 60 feet above the ground.
- 4940 (d) Allowable stresses. The design of wood, concrete or steel members shall conform to the requirements of the most recently adopted version of the Michigan Building Code, and loads, vertical and horizontal, exerted on the soil shall not produce stresses exceeding those specified therein. The working stresses of wire rope and its fastenings shall not exceed 25 percent of the ultimate strength of the rope or fasteners. Working stresses for wind or seismic loads combined with deadloads may be increased as specified in the Michigan Building Code.
- (e) Supports. The supports for all signs or sign structures shall be placed in or upon private property and shall be securely built, constructed and erected in conformance with the requirements of this chapter.
- (f) Fastenings. Signs attached to masonry, concrete or steel shall be safely and securely fastened thereto by means of metal anchors, bolts, or approved expansion screws of sufficient size and anchorage to support safely the loads applied. Anchors which attach signs to masonry surfaces shall be inserted into mortar joints.

Sec. 122-663. Sign permit requirements. (864) (693)

- 4950 (a) Application for sign permits shall be made upon forms provided by the Building Department.
- (b) Applications for signs other than overhead banners shall contain or have attached thereto the following information:
- (1) Name, telephone number and address of applicant.
 - (2) Name, address and telephone number of owner or lessee of the premises upon which the sign is to be erected.
 - (3) A written statement signed by the owner or lessee of the premises upon which the sign is to be erected, indicating their consent thereto, or the signed contract between the parties.
 - (4) The address of the premises upon which the sign is to be attached or erected.
 - 4960 (5) One set of plans showing the dimensions, materials, height and method of anchorage of the sign.
 - (6) Position of the sign in relation to nearby buildings, structures and property lines.
 - (7) Insurance policy or proof of financial security as required in §122-661(h).
 - (8) On electrical signs, certification by Underwriters Laboratory or some other recognized testing laboratory. Electrical sign installations shall comply with Article 600 of the National Electrical Code.
 - (9) Such other information as deemed necessary to show compliance with this article.

(c) Application for overhead banners shall contain or have attached thereto, the following information:

 - (1) The name of organization or group sponsoring the banner.
 - (2) Phrase on the banner, and/or sketch of the content
 - (3) Location where banner is to be erected.
 - (4) The dates the banner will be hung.
 - 4970 (5) The name, address and telephone number of the applicant.
 - (6) Insurance policy or proof of financial security as required in §122-661(h).
 - (7) Such other information as deemed necessary to show compliance with this article and with Act No. 200 of the Public Acts of Michigan of 1969 (MCL 247.321 et seq., MSA 9.140(21) et seq.), and R247.271--R247.279 of the Michigan Administrative Code, 1979.

- (d) Application for sidewalk signs shall include a sidewalk occupancy permit application.

Sec. 122-664. Prohibited signs. (865) (694)

The following signs are prohibited in all zoning districts:

- 4980 (a) Unsafe signs. When any sign or sign structure becomes insecure, in danger of falling, or otherwise unsafe, or if any sign or sign structure shall be unlawfully installed, erected, or maintained in violation of any of the provisions of this chapter, or prohibited signs, it shall be considered a nuisance per se. The owner or lessee shall, upon receipt of written notice of the building official, immediately in the case of an unsafe sign-make such sign conform to the provisions of this article or shall remove it. If, after ten days, the notice is not complied with, the building official may remove such sign at the expense of the owner or lessee after having obtained an order from the administrative hearings bureau. The cost, including actual attorney fees, shall be assessed against the property as provided in **Article VIII of the City Charter.**
- (b) Prohibited signs.
- (1) Animated signs.
- (2) Portable signs, not including sidewalk signs.
- 4990 (3) Signs mounted upon a roof.
- (4) Signs containing obscene material. Signs containing symbols that area or purports to be an imitation of or resembles, or which may be mistaken for a traffic control device or that attempts to direct the movement of traffic.
- (5) Mechanical Signs.
- (6) Sign, electronic message, excepting digital billboards.
- (7) Signs not specifically permitted under the sections of this chapter.
- (8) Signs with less than six feet horizontal clearance or 12 feet vertical clearance from overhead electrical conductors which are energized in excess of 250 volts.

Sec. 122-665. Sign Design Standards. (866) (695)

(a) Freestanding Signs

- 5000 (1) **Materials.** Freestanding signs shall be constructed out of decorative materials that complement the design of principal buildings within the development. Natural materials such as stone, decorative masonry, wood, or metal are preferred sign construction materials. The use of exposed neon tubing in conjunction with other types of materials to emphasize the business name or logo is permitted.
- (2) **Billboards.** New billboard permits will be issued only in the following cases:
- (i) For non-digital billboards, when one non-conforming billboard is removed
- (ii) For digital billboards, when two non-conforming billboards are removed.
- (3) **Digital billboards.**
- (i) The message displayed on digital billboards may change a maximum of once every 6 seconds.
- 5010 (ii) All billboards must provide a setback from any adjacent residential zoning district equal to the height of the billboard.
- (iii) Billboard structures which have two or more panels stacked, one above the other, are not permitted.
- (iv) Double-faced billboard structures (two panels mounted on the same structure back-to-back) are permitted.
- (v) Spacing between billboards shall be 1,000 feet as provided in the Highway Advertising Act of 1972, as amended.
- (vi) All billboard structures shall be of steel. No wood or other combustible material shall be permitted to support such signs.
- (vii) Billboard structures shall be restricted to and used only with respect to interstate highways, freeways or primary highways as set forth in the Highway Advertising Act, Act No. 106 of the Public Acts of Michigan of 1972 (MCL 252.301 et seq., MSA 9.391(101) et seq.).
- 5020 (4) **Sidewalk Signs.**
- (i) Sidewalk Signs may have a maximum area of 6 square feet per side.
- (ii) Sidewalk signs may be located on the sidewalk adjacent to the applicant's business.
- (iii) Sidewalk signs shall be located such that they will not impede pedestrian traffic on the sidewalk, and such that they will not present a hazard to vehicular traffic.
- (iv) Sidewalk signs may not be permanently affixed to any object, structure, or the ground.
- (v) Sidewalk signs may only be displayed during business hours and shall be removed when the business to which the sign is accessory is closed.
- 5030 (vi) Each business may have a maximum of one sidewalk sign.
- (vii) Sidewalk signs shall be made of durable materials.

(b) Building Mounted Signs.

- (1) Location. Building mounted signs may be located on any façade that faces a street, parking area, alley, or on a façade where a public entrance is located.
 - (i) Illuminated building mounted signs may not be located on a façade that faces a property line that abuts a residential zoning district unless the sign is set back at least 200 feet from the property line or screening is provided that will completely obscure the view of the sign from the adjacent residential district.
- (2) Minimum Height. Signs that project more than eighteen inches into a right-of-way or over an entrance or other pedestrian or vehicular access point shall maintain a minimum clearance of 8 feet between the grade level below the sign and the lowest part of the sign, inclusive of sign structures and support devices.
- (3) Materials.
 - (i) Building mounted signs shall incorporate exterior materials, finishes and colors that are the same, similar, or complementary to those used on the principal building.
 - (ii) Building mounted signs shall be professionally constructed using high-quality materials such as metal, stone, hard wood, or brass. The use of exposed neon tubing is permitted.
 - (iii) External illumination of signs shall be limited to fully-shielded light fixtures with a maximum of 1000 lumens. Such fixtures shall be mounted above the sign face with all light directed downward and concentrated on the area of the sign to prevent glare upon the street or adjacent property.
- (4) Window Signs. May not occupy more than twenty-five percent (25 %) of the total transparent area of any individual window.
- (5) Banners. Banner requirements shall be as follows:
 - (i) The banner must be made of nonflammable material that will not shred and has adequate air holes. For banners hanging overhead across a street, roadway or highway the banner must contain at least three air holes for every 40 feet.
 - (ii) The Building Department shall be permitted to inspect the banner or a sample of material prior to it being erected.
 - (iii) The banner must be securely attached, sufficient to withstand storms, including strong gusts of wind and continuous pounding by the elements. The manner of attachment shall first be submitted to the Building Department.
 - (iv) If a banner becomes partially unsecured, it shall be immediately reattached or removed by the entity which erected it.
 - (v) If a banner begins to shred, it shall be immediately repaired or removed by the entity which erected it.
 - (vi) If the entity which erected the banner fails to comply with is the standards of **section (iii)** or fails to remove the banner by the time the permit expires, the City shall remove the banner and shall charge the cost thereof to the entity erecting the banner.
 - (vii) Any banner permit may be canceled by the City if the installation becomes dangerous to motorists or pedestrians, unduly interferes with free movement of traffic or otherwise endangers the health, safety or welfare of persons in the City.
 - (ix) A banner shall not have displayed thereon any symbol which is or purports to be an imitation of or resembles, or which may be mistaken for a traffic control device or which attempts to direct the movement of traffic.

Secs. 122-666 – 669. Reserved.

Division 6: Traffic

Sec. 122-670. Circulation Standards. (273) (700)

Circulation Standards are intended to preserve and improve walkability and pedestrian/bicyclist safety within the walkable urban districts, while maintaining adequate vehicular access.

(a) *General*

- (1) Streets are intended for use by vehicular and pedestrian traffic and to provide access to parcels.
- (2) Streets generally consist of vehicular travel and/or parking lanes and public frontages.
- (3) Streets must be designed in context with the urban form and desired design speed of the districts through which they pass. The public frontages of streets that pass from one district to another must be adjusted accordingly or, alternatively, the district may follow the alignment of the street to the depth of one lot, retaining a single public frontage throughout its trajectory.
- (4) Pedestrian comfort and safety is the primary consideration of the public frontage. Design conflict between vehicular and pedestrian movement generally must be decided in favor of the pedestrian.
- (5) Each lot must front a street, pedestrian passage, and/or civic space, such as a park. An entrance to the building with required frontage must face the street or, if a street is not present, the Planning Commission may approve an entrance on the pedestrian passage or civic space.
- (6) All circulation plans must include the easements for non-motorized pathways in the City of Ypsilanti's Non-Motorized Plan, the ReImagine Washtenaw Corridor Improvement Study, and any planned road easement expansions approved by City Council.

(b) *Vehicular access for infill and new development.* A system of joint use driveways and cross access easements must be established wherever feasible and the building site must incorporate the following:

- (1) An alley or system of alleys extending the entire length of each parcel served to provide for driveway separation consistent with access management classification system and standards.
- (2) Stub-outs and other design features to make it visually obvious that the abutting properties may be tied in to provide cross access via a service drive;
- (3) A unified access and circulation system plan that includes coordinated or shared parking areas is encouraged wherever feasible.

(c) *Access for sites comprised of more than one building type, under the same ownership*

- (1) In the interest of promoting unified access and circulation systems, development sites under the same ownership or consolidated for the purposes of development and comprised of more than one building site are not considered separate properties in relation to the access standards of this code.
- (2) The number of connections permitted must be the minimum number necessary to provide reasonable access to these properties, not the maximum permitted for that frontage. All necessary easements, agreements, and stipulations required under joint use driveways and cross access easements must be met. This also applies to phased development plans.
- (3) The street network shall be designed to define blocks as established by district. The block perimeter is measured as the sum of lot frontage lines. Block perimeter at the edge of the development parcel is subject to approval by the Planning Commission.
 - (i) Centers and Core Neighborhoods (C, CN, CN-SF, CN-Mid): Block perimeter must not exceed a total length of 1600 feet and the maximum block length shall generally be 400 feet.
 - (ii) Corridors and Health and Human Services (HC, NC, GC, HHS): Block perimeter must not exceed a total length of 2,000 feet and the maximum block length shall generally be 500 feet.
- (4) In Center Districts, a continuous network of rear and side alleys or lanes must serve as the primary means of vehicular ingress to individual lots whenever possible. Alley or lane entrances should generally align so as to provide ease of access for service vehicles.
- (5) All streets must terminate at other streets, forming a network. Internal streets must connect wherever possible to those on adjacent sites. Cul-de-sacs are subject to approval by the Planning Commission to accommodate specific site conditions only.

Sec. 122-671. Public service access. (645) (701)

All buildings and structures must be provided with adequate access for fire, police, sanitation, and public works vehicles. The Planning Commission may require paved turnaround areas to allow adequate maneuverability for public service vehicles on a site.

Sec. 122-672. Sidewalks. (647) (702)

- (a) For all development projects, either a new public sidewalk or if necessary the reconstruction of existing

sidewalks, must be provided along the perimeter of the lot which abuts any street. New or reconstructed sidewalks must be aligned with existing or proposed sidewalks and must be constructed to City standards and subject to Chapter 94 of the City Code of Ordinances.

(b) This requirement may be modified by the Planning Commission as follows:

- (1) A shared-use path may be provided in lieu of a sidewalk, upon a finding that any portion of the perimeter of a lot is planned to be part of an area-wide non-motorized network that requires such a facility.
- (2) A fee in lieu of construction may be provided by the development in the amount of 100% of the construction cost, upon a finding that any portion of the perimeter of a lot is included in a transportation project programmed in the City's 5-year Capital Improvement Plan, or with a finding that sidewalk construction at this location is impractical due to lack of connectivity. Any fee paid for this purpose is reserved for non-motorized improvements as a part of the identified transportation project or for path and sidewalk construction throughout the City, respectively.
- (3) Any easement required for the construction, maintenance, or operation of a modified facility must be included on the site plan at the time the modification is requested.

Sec. 122-673. Direct access to major thoroughfare. (642) (703)

Whenever this chapter requires that direct access to a major thoroughfare be provided, one of the following provisions must be met:

- (a) Direct driveway ingress and egress is provided from the site directly to a major thoroughfare.
- (b) Access to the site from a major thoroughfare does not traverse through or abut any land zoned R1, MD, CN-SF, CN-Mid, and CN.

Sec. 122-674. Street frontage requirements. (643) (704)


No lot can contain any building used in whole or in part for any purpose unless such lot abuts the minimum lot width of the building type or zoning district on at least one street; or unless it has an exclusive, unobstructed private easement of access or right-of-way of at least 50 feet wide to a street. No more than one single-family dwelling or one nonresidential land use for such frontage or easement will be permitted.

Sec. 122-675. Traffic visibility. (649) (705)

- (a) No structure, wall, fence, vehicle, shrubbery, or trees can be erected, parked, planted or maintained on any lot which will obstruct the view of the driver of a vehicle approaching an intersection or maneuvering from a driveway. Provided, shrubbery and low fences or walls not exceeding 30 inches in height above the curb level and branches of trees not less than eight (8) feet above the street level will be permitted.

- (b) This means, in the case of an intersection, that there must be provided an unobstructed triangular area formed by the street property lines and a line connecting them at points 25 feet from the intersection of the pavement edge lines, or in the case of a rounded corner, from the

intersection of the street property lines extended. In the case of a driveway, there must be provided an unobstructed triangular area formed by the street right-of-way line, the edge of the driveway, and a line connecting them at points ten (10) feet from the intersection of the street right-of-way line and driveway edge.



Secs. 122-676 – 679. Reserved.

Division 7: Off-Street Parking and Loading Requirements

Sec. 122-680. Purpose. (831) (710)

The purpose of this Division is to recognize that motor vehicles, while part of the social and economic well-being of the community, can cause conditions and problems of parking and storage which can have a negative impact on the safety, appearance, health and welfare of the community. It is the intent of this article to provide standards for the parking and storage of motor vehicles in order to ensure that off-street parking facilities are in harmony with the use of surrounding properties and all modes of transportation; maintain barrier-free pedestrian access, ensure adequate accessibility to the off-street parking facilities from City street; and to set standards for design and construction of parking facilities compatible with the health, safety and general welfare of the community.

Sec. 122-681. Scope. (832) (711)

In all zoning districts, off-street parking facilities shall be provided for the storage and parking of motor vehicles and bicycles for the use of occupants, employees, and patrons of all buildings, structures, residences, businesses, or establishments erected, altered, constructed, changed in use, or commenced after the effective date of the ordinance from which this chapter derives. Such space (or spaces) shall be maintained and not be encroached upon, unless an equivalent number of such spaces are provided elsewhere, in conformance with this chapter.

- (a) New or altered buildings. No building or structure shall hereafter be erected, and no existing structure may be so altered that it is increased in size or intensity of use, unless adequate parking space, as required by the provisions of this article division, is provided for the entire building or structure as erected or altered.
- (b) Change in use. The use of any building or structure shall not be changed if additional parking space would be required as a result of the change in use, unless the minimum parking space as required by the provisions of this article division is provided for the entire building.
- (c) Areas excepted. The provisions of this article section regarding quantity of spaces provided shall not apply to uses in the Center District or existing commercial uses in the Historic Corridor zoning districts, except those spaces required for upper-story dwellings. A fee in lieu of providing off-street parking for upper-story units in the Center or Historic Corridor is permitted in accordance with [§122-697](#).

Sec. 122-682. Off-street parking layout and construction for one- and two-family dwellings. (833(1)) (712)

Off-street parking facilities required for one- and two-family dwellings shall consist of a parking strip, apron, driveway, garage, carport, or combination thereof and shall be located on the premises they are intended to serve subject to the provisions of [§122-651](#). Further, parking areas serving one- and two-family dwellings shall be subject to the following:

- (a) **Ingress and egress.** No individual curb cut to a street or alley for a single driveway shall exceed 20 feet in width. The total width of all curb cuts shall not exceed 35 feet on all property lines. On lots with a lot width of 60 feet or less, no more than one curb cut to a single street is permitted. All curb cuts accessing Washtenaw Avenue (M-17) must comply with the Michigan Department of Transportation M-17 Access Management Plan.
- (b) **Driveways.** On lots used for one-family or two-family residential purposes, maneuvering or backing of vehicles into a street or alley is permitted. Driveways may cross the required front yard, or the required street side yard on a corner lot, provided that the total area of the driveway do not exceed 30 percent of the area of such required yard. Driveways may have no less than 9 feet of clear width.
- (c) **Surfacing.** Parking areas and driveways shall be surfaced with crushed limestone or similar gravel material, or shall be hard surfaced with asphalt, concrete, or similar bonded material. Porous paving is also allowed. However, parking areas which are designed for five or more spaces must meet the requirements of [§122-683](#). That portion of the driveway between the lot line and the public way shall be paved with concrete a minimum of six inches thick for residential occupancies. Curb cuts along state trunk lines shall comply with the requirements of the state department of transportation. All other curb cuts shall comply with adopted standards of the Department of Public Works.
- (d) **Parking in yards.** No parking shall be permitted in the front yard, or in the street side yard on a corner lot, except on a driveway which leads to a parking area that is beyond the front line of the structure and the space is in compliance with [§122-685](#).

Sec. 122-683. Off-street Parking layout and construction for all other uses. (833(2) & 835(1-9, 12, 13)) (713)

Off-street parking facilities required for multiple-family and nonresidential uses shall be located on the same lot or parcel as the building or use they are intended to serve, or within 300 feet of such building or use, measured from the nearest point of the building to the nearest point of the off-street parking lot. A shared parking agreement or use easement for the land intended for shared parking must be on file with the county register of deeds, in order for the shared parking spaces to satisfy the quantity requirement. Parking spaces may be located within buildings or structures consistent with the Building Code.

- (a) **Review and approval requirements.** Except for off-street parking accessory to single-or two-family dwelling units, review and approval is required for off-street parking areas in accordance with [Article III](#) of this chapter.
- (b) **Ingress and egress.** Adequate ingress and egress to such parking lot shall be provided by means of clearly defined and limited drives having a minimum width of 20 feet for two-way traffic and 10 feet for one-way traffic, with a maximum of 30 feet. All such drives shall be located so as to minimize traffic congestion.
 - (1) On lots with a lot width of 100 feet or less, no more than one curb cut to a single street is permitted.
 - (2) All curb cuts accessing Washtenaw Avenue (M-17) must comply with the Michigan Department of Transportation M-17 Access Management Plan and the ReImagine Washtenaw Corridor Improvement Study.
 - (3) All curb cuts and approaches to such parking lots shall comply with adopted City standards for curb cuts.
 - (4) Ingress and egress for the parking area in an area zoned CN-Mid, CN, HC, NC, GC, C, HHS, PMD shall not cross land zoned for P, R1 or CN-SF.
 - (5) Parking lot driveways shall be situated so as to minimize vehicle headlights from shining on residential dwellings.
 - (6) Where possible, curb cuts shall be located across from any existing curb cuts on the opposite side of the street, or shall be offset from any opposite-side curb cuts by at least 25 feet.
 - (7) No curb cut for a parking lot may be closer than 50 feet to the intersection of any two streets as measured along the street right-of-way line. However, the Planning Commission may allow a curb cut for a parking lot situated on a small land parcel located no closer than 20 feet to the intersection of any two streets, upon finding that no other access points in compliance with City Ordinances is possible due to the size of the parcel.
- (c) **Access.** All parking spaces shall be provided adequate access by pedestrians and vehicles:
 - (1) **Walkways in Parking Lots.** Paved walkways a minimum of 5 feet in width shall be provided for access to adjacent parks, commercial areas, transit stops, anticipated walkways and institutions. Pedestrian movement shall be accommodated within parking lots through raised walkways, marked crosswalks or similar methods.
 - (2) **Vehicular Access.** All parking spaces must be accessible to vehicles by means of maneuvering aisles. Except for one-and two-family uses, maneuvering or backing from a parking space directly onto a street or walkway shall be prohibited, and all parking spaces shall be designed so that any motor vehicle may be parked or unparked without moving another vehicle.
- (d) **Maneuvering drives.** Each driveway providing access to an off-street parking lot containing five or more parking spaces shall be a minimum of ten feet in width. Where a turning radius is necessary, it shall be an arc that allows unobstructed vehicle flow.
- (e) **Surfacing.** All parking and loading facilities and access drives shall be paved with a durable bonded material in accordance with accepted engineering standards, or alternative surfacing materials to minimize impervious surface and stormwater runoff, employ environmental and other best practices, and achieve low impact design, at the discretion of the City Engineer. Use of pervious alternative surfaces is encouraged in proximity to the Huron River and Paint Creek. Paving materials proposed to improve aesthetics may also be considered by the City Planner and the Planning Commission. Alternative surfaces proposed shall be reviewed by the City's consulting engineer.
- (f) **Drainage.** All off-street parking and loading areas shall be graded and drained to public storm sewers. As an alternative, if in the opinion of the City's consulting engineer, the soils are of a type which will allow for efficient drainage, the use of drywells, infiltration trenches, swales, bio-retention or other best management practices for controlling urban runoff quality are permitted. No surface water shall be permitted to drain onto adjoining properties, unless there is a common engineered drainage system shared with the adjoining property or an appropriate watershed easement has been obtained. No surface water drainage from an off-street parking lot shall be permitted to drain across a public sidewalk.
- (c) **Setback from street.** Parking lot setbacks are designated by the zoning district in which they are located. An allowed exception are circular drives, which may be located in a required minimum front yard or street side yard, provided that such drives shall be designed so that no parking space is located closer than 25 feet to any street right-of-way line.

- (d) **Setback from adjacent lot.** Parking areas are required to be 10' from any adjacent lot. Planning Commission may waive this requirement in whole or in part with a finding that the lot shares a common access and common parking with the adjoining lot, or that stormwater, landscaping, and other similar concerns have been adequately addressed with other methods.
- (g) **Striping.** For parking lots containing five or more spaces, all spaces shall be outlined with three-inch wide strips of white or yellow paint, except that barrier-free spaces shall be blue, with a symbol of compliance in blue, and signed in accordance with the State Barrier-Free Code.
- (h) **Wheel stops.** For parking lots containing five or more spaces or accessory to commercial uses, wheel stops or curbing shall be provided for all parking spaces to prevent any vehicle from projecting beyond the parking lot area, bumping any wall or fence, or encroaching upon any landscaping. In all cases where parking lots abut public or private sidewalks, continuous concrete curbing or bumper stops, at least six inches high, shall be placed so that a motor vehicle cannot be driven or parked on, or hang over, any part of any sidewalk.
- (i) **Lighting.** With the exception of multiple-family dwellings on individual lots containing no more than four units, parking and loading facilities utilized during night-time hours shall be artificially illuminated. All such outdoor lighting shall meet the requirements of [§122-609](#).
- (j) **Maintenance.** All off-street parking areas, including striping, shall be maintained in good usable condition, and when necessary shall be treated to prevent dust or other nuisances. Such parking areas and drives shall also be kept free of litter, debris, and refuse.
- (k) **Additional requirements.** In addition to the above requirements, parking areas shall comply with additional requirements or conditions which may be deemed as reasonably necessary by the Planning Commission for the protection of abutting lots.


Sec. 122-684. Parking screening and landscaping. (835) (714)

- (a) Intent. Separate landscape areas shall be provided within parking lots so as to break up the broad expanse of pavement, mitigate heat island effect, support storm water management, and guide the circulation of vehicular and pedestrian traffic.
- (b) Required landscaping within off-street parking areas. Separate landscape areas shall be provided within off-street parking areas in accordance with the following requirements:

- (1) There shall be a minimum of one (1) tree for every eight (8) parking spaces, provided that a landscape island shall be provided for no more than sixteen (16) continuous spaces.
- (2) Landscape islands must meet the following size requirements:
 - (i) Landscape islands containing a tree shall be a minimum of 160 square feet and a minimum of nine (9) feet wide.
 - (ii) Landscape islands containing a pedestrian pathway shall be a minimum of eleven (11) feet wide, with a pathway of a minimum width of five (5) feet and minimum three (3) feet wide landscape area on both sides.


(iii) If landscaped islands are not used for storm water infiltration, the islands must be raised and curbed.

- (3) The ends of all parking aisles and corners shall be protected with a curbed island.
 - (4) A minimum distance of three (3) feet from the backside of the curb and the proposed landscape plantings shall be provided. Where vehicles overhang a landscape island or strip, a minimum distance of five (5) feet from the backside of the curb and the proposed landscape plantings shall be provided.
 - (5) Shrubs and/or ground covers which will not impede vehicular visibility in accordance with this Ordinance may also be included.
- (c) Required Landscaping at the Perimeter of Off-Street Parking Areas, Loading Zones, and Access Drives. Separate landscape areas shall be provided at the perimeter of off-street parking areas in accordance with the following requirements. This landscaping cannot be counted toward any other landscaping requirement except for the “site landscaping” minimum percentage.
- (1) Off-street parking areas in the side and rear yard which abut a R-1, MD, CN, CN-Mid, CN-SF zoning district must be screened in accordance with [§122-634](#).
 - (2) All off-street parking areas that are visible from a public road shall be screened from view with a solid wall or landscape planting achieving at least 80% opacity year-round at least three (3) feet in height but no more than four (4) feet in height, in conformance with [§122-675](#).
 - (3) All land between a parking lot and any street right-of-way shall be kept free from refuse and debris and must be landscaped. The ground area shall be planted in lawn or other live ground covering. All such landscaping and plantings shall be maintained in a healthy, growing condition, neat and orderly in appearance.
- (d) Landscaped areas, walls, structures, and walks shall be properly protected from vehicular encroachment or overhang through appropriate wheel stops or curbs, as well as a distance of at least 3 feet.



Sec. 122-685. Parking dimensions. (834) (715)

- (a) All off-street parking facilities required by this chapter shall be of adequate size and design to provide safe and reasonably direct ingress and egress from an alley or street. All parking spaces shall be adequate for parking a motor vehicle with room for opening doors on both sides.
- (b) Parking spaces required by this article shall be at least 9 feet wide and 18 feet long (16 feet long if 2 feet of overhang is provided when parking against a curb). Spaces directly adjacent to a fence, wall or enclosure shall be increased by 1 foot in width. Barrier free parking spaces must be designed as required by and in conformity with state law.
- (c) Up to 20% of the parking spaces may be designated as small car spaces, which shall be at least 8 feet wide and 16 feet long and clearly signed for "compact cars."
- (d) Up to 10% of the parking spaces may be designated as motorcycle spaces, which shall be at least 5 feet wide and clearly signed for "motorcycles."
- (e) Minimum Standards. The minimum standards for parking spaces and aisles are indicated in the table below.



Standard Vehicle Parking Dimensions					
Parking Patterns (Degrees)	Space Width (Feet)	Space Length (Feet)	Maneuvering Lane Width (Feet)	Total Width of One Tier of Spaces Plus Maneuvering Lane (Feet)	Total Width of Two Tiers of Spaces Plus Maneuvering Lane (Feet)
0 (parallel)	9	22	12 if one-way 10 if two-way	21 one-way 19 two-way	30 one-way 28 two-way
30 to 53	9	18	13	36	53
54 to 74	9	18	16	38	59
75 to 90	9	18	22	40	62
Compact Vehicle Parking Dimensions					
Parking Patterns (Degrees)	Space Width (Feet)	Space Length (Feet)	Maneuvering Lane Width (Feet)	Total Width of One Tier of Spaces Plus Maneuvering Lane (Feet)	Total Width of Two Tiers of Spaces Plus Maneuvering Lane (Feet)
0 (parallel)	8	18	12	20 one-way 32 two-way	28 one-way 40 two-way
30 to 53	8	17	13	36	53
54 to 74	8	17' 5"	16	38	59
75 to 90	8	16	22	42	62
Motorcycle Vehicle Parking Dimensions					
All motorcycle parking spaces shall be a minimum of five feet by eight feet.					

Sec. 122-686. Barrier-free parking spaces. (839) (716)

Off-street parking facilities as required under this chapter shall include parking spaces which are reserved for physically handicapped persons in accordance with the state barrier free design requirement of the state building code.

Secs. 122-687 – 689. Reserved.

Division 8: Parking Types and Quantities

Sec. 122-690. Generally. (833 - portion) (720)

Any person, organization, or establishment who has any ownership interest in or the control of any real estate within the City is required to provide and maintain in a usable condition off-street parking spaces as follows:

- (a) **Repair prohibited.** No repairs or service to vehicles shall be permitted on areas designated as required off-street parking.
- (b) **Display of vehicles for sale.** The parking of motor vehicles, recreational vehicles, and trailers which are possessed expressly and solely for sale by persons or businesses licensed by the state for such sales are permitted only when in accordance with the requirements of each respective zoning district and the specific provisions of §122-538 regarding the outdoor sales of vehicles. Otherwise, the display of vehicles for sale in designated off-street parking areas is prohibited.
- (c) **Use of loading space.** Loading spaces, as required under §122-695, shall not be counted or used for required parking.
- (d) **Usable floor area and gross floor area.** For the purpose of computing the number of parking spaces required, the definitions for "usable floor area" and "gross floor area" in §122-203 shall apply.
- (e) **Fractional requirements.** When units or measurements determining number of required parking spaces result in requirement of a fractional space, any fraction up to one-half shall be disregarded and fractions including and over one-half shall require one parking space.
- (f) **Uses not specified.** For those uses not specifically mentioned under §122-691, the requirements for off-street parking facilities shall be in accord with a use which the City Planner considers similar in type.
- (g) **Nonoverlapping operating hours.** In the instance of land uses requiring off-street parking spaces where operating hours of the uses do not overlap, the City Planner may grant exception to the individual parking requirements of §122-691.
- (h) **Use of parking lots for storage.**
 - (1) Except as provided under subsection (h)2 of this section, a parking lot may not be used for the storage or parking of trailers, mobile homes, travel trailers, boats, boat trailers, or junked or wrecked vehicles of any type; for the storage of merchandise or industrial equipment or materials; or as a dump for refuse of any description.
 - (2) The parking out-of-doors of motor vehicles which are used as part of a permitted commercial or industrial use, including automobiles, trucks, or trailers, are permitted on off-street parking lots outside normal business hours of such commercial or industrial use; provided no more than a total of five automobiles and three commercial trucks or trailers each weighing less than 10,000 pounds shall be permitted. The outdoor storage of more than five automobiles and three trucks or trailers shall be permitted only after Special Use approval by the Planning Commission in accordance with the provisions of Article III, Division 2, Subdivision III of this chapter.

Sec. 122-691. Minimum and maximum number of parking spaces. (836) (721)

The minimum number of off-street parking spaces by type of use in all zoning district shall be determined in accordance with the following schedule. The maximum number of off-street parking spaces must not exceed 120% of the required parking spaces, except for those uses in the "Residential" category, which are not subject to a maximum. The Planning Commission may grant waivers as noted in [§122-692](#).

USE	AUTOMOBILE SPACES PER UNIT OF MEASURE
RESIDENTIAL	
Single-family detached dwellings and two-family dwellings	1 space per unit
Multiple-family dwellings, including townhouses	1.5 for each dwelling unit, plus 1 for each 10 dwelling units for guest parking.
Upper-story residential units in C, HC, NC, GC, and HHS districts	1 for each dwelling unit.
Group living with support staff, not licensed by State of Michigan	1 for each 3 beds, plus 1 per employee on an average employment shift.
Group residence & roominghouse	1 for each bedroom or sleeping room, plus 1 for each employee or the largest employment shift.
Adult Foster Care	1 for each 3 beds, plus 1 for each employee an average employment shift.
Accessory Dwelling Unit	1 for each dwelling unit
Family Child Care Home	Minimum of 1 and a maximum of 3 child-care drop off spaces.
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES	
Religious institutions; private assembly (such as catering or clubs); performance venues & theaters; libraries, museums, and cultural or community centers; or similar facilities	1 for each 500 square feet of usable floor area, excluding area devoted to storage.
Indoor recreation, including swimming pools	1 for each 3 persons who may be legally admitted at one time based on the occupancy load established by local, county, or state fire, building, or health codes, plus 1 for each employee on an average employment shift.
Primary and secondary schools, public and private	1 for each teacher, employee or administrator, plus 1 for each 10 students
Post-secondary educational institutions (public & private)	1 for each teacher, employee or administrator and 1 for each 5 students.
Municipal, county, regional & state service uses	1 for each 1,000 square feet of usable floor area.
Child care centers	1 off-street parking space per caregiver required to staff facility at the state-licensed capacity, plus 1 space for every 20 children the facility is licensed to care for.
Outdoor recreation and fields	1 for each 1,000 square feet of recreation space.
Stadiums, sports arenas, or similar places of outdoor assembly	1 for each 4 seats or 8 feet of linear bench space.
INFRASTRUCTURE	
Radio & Television Studios or Stations	1 per each 500 square feet of gross floor area.
Utility buildings	1 for each employee on an average employment shift.
Energy, electricity, heat generation, or sewage plants	1 for each employee on an average employment shift.
SERVICES	
Bed & Breakfasts or Inns	1 per occupancy unit plus 1 per employee on an average employment shift.
Motels, hotels or other commercial lodging establishments	1 per occupancy unit plus 1 per employee on an average employment shift; plus extra spaces for dining rooms, ballrooms, or meeting rooms as required.
Business and professional offices and services	1 per 300 square feet of usable floor area.

USE	AUTOMOBILE SPACES PER UNIT OF MEASURE
Funeral homes	1 per 50 square feet of assembly room, parlor and slumber room.
Laundromats	1 per 3 washing machines.
Financial service, including banks	1 per 300 square feet of usable floor area, plus stacking spaces for each drive-through transaction station as required under §122-694 .
Nursing Homes	1 per 3 beds.
Hospitals	1 for each 4 patient beds, plus 1 for every 200 square feet of out-patient service area
Medical or dental offices or clinics, substance abuse treatment facilities	1 for each 300 square feet of usable floor area in waiting rooms, plus 1 for each examining room, dental chair, or similar use area.
Personal service establishments	2 spaces for each of the first 2 beauty or barber chairs, and 1½ spaces for each additional chair, or 1 for each 300 square feet of useable floor area whichever is greater.
Self-storage facilities	1 per 200 storage units, plus 1 per 300 square feet of usable floor area of office space, plus 1 for residence, if provided.
Catering service	1 per 600 square feet of usable floor area.
All other service uses not elsewhere specified	1 for each 300 square feet of gross floor area.
COMMERCIAL	
Furniture and appliances, household equipment; repair shops; showrooms of a plumber, decorator, electrician or similar trade; and other similar uses	1 for each 600 square feet of usable floor area.
Open air businesses	1 for each 600 square feet of lot area used for open air business, plus extra spaces for indoor sales or office space as required.
Shopping centers or clustered commercial centers over 100,000 square feet in gross floor area	1 for each 300 square feet of gross floor area.
Arts & crafts studios	1 per 1,000 square feet plus 1 per classroom.
All other retail uses not elsewhere specified	1 for each 250 square feet of gross floor area.
RESTAURANTS	
Café, coffee shop, restaurants, tasting rooms or bar/lounge, and other establishments where food, beverages, or refreshments are sold primarily for consumption on the premises	1 for each 100 square feet of usable floor area, or 1 for each 3 persons allowed within the maximum occupancy load as established by local, county, or state fire, building or health codes; whichever is greater.
Restaurant, fast food, drive-in or drive-through	1 for each 50 square feet of customer waiting and eating areas, plus 1 for each employee in the largest employment shift, plus 8 stacking spaces for each drive-in or drive-through transaction station.
AUTO-ORIENTED	
Automobile filling stations	1 for each employee, plus spaces required for other uses within the station, such as the retail floor area, carryout restaurants, subtracted by one half space for each automobile fueling position.
Automobile repair	1 for each employee in the largest employment shift, plus 1 space for each auto service stall. In addition, stacking spaces for automobiles awaiting entrance to a service stall shall be provided as required under §122-694 .

USE	AUTOMOBILE SPACES PER UNIT OF MEASURE
Automobile wash (automatic and self-serve) and detailing	1 for each employee in the largest employment shift. In addition, stacking spaces for automobiles awaiting entrance to the wash facility must be provided as required under §122-694 .
Motor vehicle sales and service establishments, trailer sales and rental, and boat showrooms	1 for each 500 square feet of usable floor space of sales room, plus 1 for every 500 square feet of outdoor sales area, plus 1 for each 1 auto service stall in service areas, plus 1 space per employee on the largest employment shift.
Automobile rental (parking, storage, wash & repair)	
Vehicle, Recreational Vehicle, Storage and Towing	1 for 300 square feet of office space, plus 1 space per employee on the largest employment shift.
RESEARCH	
Laboratories or research establishments	5 plus 1 for every 1.5 employees in the largest working shift; or 1 space per each 1,000 square feet of gross floor area for storage areas, and 1 space per 300 square feet of office area; whichever is greater.
PRODUCTION, MANUFACTURING & DISTRIBUTION	
Craft production	1 per 1,000 square feet
Wholesale or distribution facility	5 plus 1 for every employee in the largest working shift; or 1 for every 1,700 square feet of gross floor area, plus 1 for each 300 square feet of office area. Spaces shall also be provided for any retail or service area in addition to the above.
Assembly, processing or manufacturing	5 plus 1 for every 1½ employees in the largest working shift; or 1 space per each 1,000 square feet of gross floor area for assembly, processing and manufacturing and storage areas, and 1 space per 300 square feet of office area.
URBAN AGRICULTURE	
Community garden	None
Hydroponics, aquaculture and aquaponics and similar raising of food	5 plus 1 for every employee in the largest working shift; or 1 for every 1,700 square feet of gross floor area, plus 1 for each 300 square feet of office area. Spaces shall also be provided for any retail or service area shall be in addition to the above.

Sec. 122-692. Parking Requirement Reductions. (837) (722)

Off-street parking requirements may be reduced subject to the following regulations.

- (a) **Transit.** Parking requirements may be reduced by up to 20 percent for buildings, structures, or uses within three hundred (300) feet of a commuter rail station or bus transit center or within one hundred (100) feet of a transit stop. In situations where this would result in a discount of more than 10 spaces, a traffic study may be required to demonstrate that a sufficient number of vehicle drivers would immediately opt for transit, and therefore would not result in adverse parking impacts on surrounding properties. The Ride shall verify that the transit station or transit stop is in a is not scheduled to move in the 5-year plan for the Ride.
- (b) **Car-sharing and carpooling spaces.** Parking spaces reserved, signed, and enforced for hourly car rental/car-sharing services may count as four (4) regular parking spaces. Parking spaces reserved, signed, and enforced for carpooling or vanpooling services may count as two (2) regular parking spaces.
- (c) **Electric car parking/charging spaces.** Electric car spaces shall include a power outlet for use by the parked car. Such spaces should be closest to the main entrance (exclusive of barrier-free spaces). Parking spaces reserved, signed, and enforced for electric car charging stations may count as two (2) regular parking spaces.
- (d) **Bicycle spaces.** Parking requirements may be reduced by one (1) space for every four (4) covered, secure bicycle parking spaces provided on site. Parking requirements may be further reduced by four (4) spaces where free showers are available for employee use within the building.
- (e) **Seasonal bicycle parking.** Up to 5% of vehicle parking spaces may be occupied by bike racks April through October in the Walkable Urban Districts.
- (f) **Planning Commission Authority.** The Planning Commission shall have the authority to waive the number of required off-street parking spaces, in addition to the reductions above, by up to 20%, with a finding that there is a special circumstance that particularly relates to the size of an existing parcel and building in combination, and/or character of the proposed use.

Sec. 122-693. Required Bicycle Parking. (838) (723)

Any development requiring vehicle parking spaces shall be required to provide bicycle parking. Off-street parking areas shall contain at least one (1) bicycle parking space for every five (5) spaces provided for motor vehicles, or fraction thereof, with a minimum of two (2) bicycle parking spaces provided. In the Center, Historic Corridor, and Neighborhood Corridor Districts, bicycle facilities provided in the public right-of-way may be used in parking calculations.

Sec. 122-694. Off-street stacking spaces for drive-through facilities. (840) (724)

- (a) **Drive-in or drive-through windows.** On the same premises with every building, structure, or part thereof, erected or occupied for the purpose of serving customers in their automobiles by means of a service window or similar arrangement, such as drive-in banks, restaurants, or cleaning establishments, there shall be provided two off-street stacking spaces for each service window or transaction station in compliance with subsection (c) of this section. Six off-street stacking spaces shall be provided for each drive-through transaction station of a restaurant.
- (b) **Automobile servicing.** Self-service automobile and car wash establishments shall provide three off-street stacking spaces for each washing stall. Quick oil change facilities shall provide three off-street stacking spaces per each oil change service bay. Automobile and car wash establishments, other than self-service, shall provide stacking spaces equal in number to four times the maximum capacity of the motor vehicle wash for automobiles awaiting entrance. The term "maximum capacity" shall mean the greatest number of possible automobiles undergoing some phase of washing at the same time.
- (c) **Stacking space dimensions.** Each stacking space shall be a minimum dimension of ten feet in width and 20 feet in length.

Sec. 122-695. Off-street loading space requirements. (841) (725)

With the exception of uses located within the Center district, there shall be provided and maintained on the same premises with every building, structure, or part thereof involving the receipt or distribution of vehicles or materials or merchandise, including but not limited to retail stores, wholesale stores, markets, hotels, hospitals, offices, and laundries, adequate space for standing, loading, and unloading in order to avoid undue interference with public use of dedicated rights-of-way and vehicular circulation on the site.

- (a) Such off-street loading spaces shall be provided as specified in the table below. The Planning Commission may modify these requirements upon making the determination that another standard would be more appropriate because of the number or type of deliveries experienced by a particular business or use.

Off-Street Loading Space Requirements			
Use	Gross Floor Area (In Square Feet)	Size and Quantity	
		10' X 25' Space	10' X 50' Space
Office	0--99,999	--	--
	100,000--149,000	--	1
	150,000 and over	--	2
Commercial, Industrial. or Institutional	0-- 1,999	--	--
	2,000-- 4,999	1	--
	5,000--19,999	--	1
	20,000--49,999	--	2
	50,000--79,999	--	3
	80,000--99,999	--	4
	100,000--149,999	--	5
	150,000 and over	--	5, plus one additional space for each 50,000 square feet of floor area in excess of 150,000 square feet

- (b) All loading spaces shall be located within a nonrequired rear yard, or a nonrequired side yard which does not abut or lie across a street from a residential zoning district; but in no case shall loading spaces be permitted in a front yard. Loading spaces shall be subject to primary building setbacks.
- (c) No loading space shall be located closer than 50 feet to any R1, MD, CN-SF, CN-Mid, CN, or HHS district, unless located within a completely enclosed building or enclosed on all sides facing the district by a solid concrete or masonry wall not less than six feet in height.
- (d) Loading space areas shall be provided with a paved surface having an asphaltic or Portland cement binder so as to provide a permanent, durable and dustless surface. All loading spaces shall have a minimum 14-foot high clearance.
- (e) Loading areas shall not utilize any area required for the maneuvering of vehicles into parking spaces or block general vehicular circulation on a site.
- (f) A truck turning plan must be provided.

Sec. 122-696. Special assessment districts. (842) (726)

When a property is located within a special assessment district created for the purpose of constructing a municipal parking lot or structure, and an assessment has been levied against the entire building site, the owner of such property may petition the Planning Commission for approval of substituting such public parking for all or a portion of the required off-street parking spaces. The Planning Commission shall determine that the petitioner's property is adequately served by the public parking facility in such a way that the objectives and intent of this article shall be secured. To accomplish this end, the Planning Commission shall have the power to require such conditions as deemed appropriate. The Planning Commission shall consider the assessment of benefits in the special assessment district in determining the adequacy of service by the public facility.

Sec. 122-697. Fee in lieu of providing off-street parking. (843) (727)

- (a) Intent. The intent of the fee in lieu of providing off-street parking is to encourage the development of apartment units above ground floor commercial uses, in existing buildings, in the Center District. It is recognized that many structures in these business districts were constructed at zero lot lines, and often the structure covers the lot completely. Therefore, parking spaces on the lot or contiguous to the lot cannot be provided. For those building owners who cannot provide the amount of required parking pursuant to this chapter, and whose upper floor space has not been legally occupied within one year of their application for payment of such a fee in lieu

of parking, they shall be charged a fee according to the number of bedrooms in the residential units. Upon payment of this fee, the owner or applicant will be permitted to develop or rehabilitate these residential units without providing the parking required by this chapter. The fee will be held by the City for parking capital improvements, which will be used to provide increased parking and transportation infrastructure such as transit stops, bicycle facilities, and pedestrian pathways for the areas where these buildings are located.

- (b) Condition for allowing payment of fee in lieu of providing off-street parking. Property owners who meet all of the following requirements shall be entitled to apply for payment of fee in lieu of providing off-street parking:
 - (1) They are the owner, or have permission of the owner, of a building which can provide residential units above ground floor commercial uses.
 - (2) The building is located in the Center District within the City.
 - (3) The property, by virtue of its construction, cannot meet parking requirements in the district.
 - (4) The residential unit or units have not been legally occupied within one year prior to making application.
- (c) Application.
 - (1) An application for permission to use such payment in lieu of providing off-street parking shall be made as part of an application to the City Planner.
 - (2) The permit shall contain the following information:
 - (i) Name, address and phone number of property owner and name, address and phone number of applicant, if different than owner.
 - (ii) Address of property requiring fee in lieu of providing off-street parking.
 - (iii) Plan showing the layout of the proposed residential units, including size of rooms and identification of bedroom space.
 - (iv) Description of commercial use on ground floor level.
 - (v) A site plan which shall include:
 - (a) Dimensions and size of parcel.
 - (b) Location of structure on parcel.
 - (c) If any parking is available on the site, its location must be indicated, including access, stall size, etc.
 - (d) Description of location of parking to be used by tenants.
 - (3) Application fee. An application fee shall be paid at the time of submitting the application to the City Planner.
- (d) Approval procedures.
 - (1) The City Planner shall consider the following in making his/her determination:
 - (i) Whether the owner can provide on-site parking that meets ordinance standards.
 - (ii) Whether the owner can modify available parking space, or loading space, located on-site to meet ordinance standards.
 - (2) If the City Planner determines that the owner cannot provide on-site parking to meet ordinance standards, or can only provide partial on-site parking to meet ordinance standards, and the other requirements of this article are met, then he/she shall make a specific finding regarding the number of spaces which are required for the residential units, which shall allow the City Treasurer to compute the amount of fee in lieu of parking.
- (e) Condition. The off-street parking requirement satisfied by fee in lieu of parking shall run with the land. If any subsequent change in use should occur, which requires additional parking, then the owner shall make a new application to the City pursuant to this chapter for such additional parking. An additional application fee shall be paid when such application is submitted. An additional fee shall be due prior to the issuance of a building permit to allow the additional modifications.

Secs. 122-698 – 699. Reserved.

Article VII: Supplementary Regulations

Division 1: Planned Unit Development

Sec. 122-700. Description and purpose. (571) (750)

- (a) It is the purpose of this article to provide guidelines for development or redevelopment which is planned as a unit. Toward this end, it is the intent of these regulations to allow flexibility in the regulation of land development; encourage innovation in land use and variety in design, layout, and type of structures constructed; achieve economy and efficiency in the use of land, energy, public services, and utilities; encourage useful open space; provide better housing, employment, shopping opportunities, compatibility of design, and use between neighboring properties; facilitate the preservation and reuse of historic structures; and encourage development that is consistent with the City's master land use plan.
- (b) The approval of a planned unit development application requires an amendment to this chapter to revise the Zoning Map and designate the subject property as "PUD, planned unit development." An approval granted under this article, including all aspects of the final site development plan and conditions imposed on it, constitutes an inseparable part of this chapter.
- (c) The provisions of this article are not intended as a device for ignoring this chapter, the specific standards set forth in this chapter, or the planning upon which it has been based. Provisions of this article are intended to result in land development substantially consistent with the zoning standards generally applied to the proposed uses, allowing for modifications and departures from generally applicable standards in accordance with the guidelines of this article to insure appropriate, fair, and consistent decision-making.

Sec. 122-701. Permitted uses. (572) (751)

In a planned unit development, the principal uses which are permitted are based on the underlying zoning district. City Council may also consider, upon Planning Commission recommendation, the City of Ypsilanti Master Plan as a basis for principal uses permitted in a planned unit development.

Underlying Zoning District	Permitted Uses under Planned Unit Development
R1, CN-SF, P	Planned unit developments are not permitted in these districts, except as provided for under §122-703.
CN, CN-Mid, MD	Any combination of uses permitted in the CN, CN-Mid, and MD zoning districts. Limited commercial, service, and office uses may be permitted if in combination with and related to residential uses.
HHS, HC, NC, C	Any combination of uses permitted in the HHS, HC, NC, or C zoning districts.
GC	All uses permitted under GC, plus Unclassified Uses as defined in §122-431(c) . ORIGINAL: (changed to have as much flexibility in use as the underlying district- as intended- plus additional, if thought appropriate.) All commercial, service, and office uses or any combination of such uses may be permitted. Limited light industrial uses may be permitted if in combination with such commercial or office uses.
PMD	All industrial and office uses and any combination of such uses. Limited commercial and service uses may be permitted if in combination with industrial uses. Residential uses are not permitted.

Sec. 122-702. Requirements for planned unit developments. (573) (752)

The following requirements must apply to all planned unit developments:

- (a) Unified control. The proposed development must be under single ownership or control such that there is a single person or entity having responsibility for completing the project in conformity with this chapter. The applicant must provide legal documentation of a single ownership or control in the form of agreements, contracts, covenants, and deed restrictions which indicate that the development can be completed as shown on the plans, and further, that all portions of the development that are not to be maintained or operated at public expense will continue to be operated and maintained by the developers or their successors.
- (b) Minimum size. The minimum size of a planned unit development in the Walkable Urban Districts is one half-

acre of contiguous land. The minimum size of a planned unit development in the Use Based Districts is one acre of contiguous land.

- (c) Applicable base regulations. Unless waived or modified in accordance with the procedures and standards set forth in this article, the yard, bulk, parking, loading, landscaping, lighting, general provisions, and all other standards set forth in this chapter for the uses listed below must be applicable for uses proposed as part of a planned unit development:
 - (1) Multiple-family residential uses must comply with the regulations applicable in the MD multiple dwelling residential district.
 - (2) Commercial and office uses must comply with the regulations applicable in the C - Center district.
 - (3) Manufacturing uses must comply with the regulations applicable in the PMD - Production, Manufacturing, and Distribution district.
 - (4) Mixed uses must comply with the regulations applicable for each individual use, as outlined above, except that if conflicts exist between provisions, the regulations applicable to the most dominant use must apply.
 - (5) To encourage flexibility and creativity in development consistent with the planned development concept, departures from compliance with the base regulations may be granted by the City Council, upon recommendation of the Planning Commission, as a part of the approval of the planned development. For example, such departures may include modifications of lot dimensional standards, setback requirements, density standards, parking and landscaping requirements, and similar requirements. Such departures may be approved only on the condition that they will result in a higher quality of development than would be possible using conventional zoning standards.
- (d) Street access. Each lot, main building, and principal use within a planned development district must have vehicular access to a public street. Adequate provision must be made for dedications of land for streets and essential services.
- (e) Usable open space. The proposed development must contain at least as much open space as would otherwise be required by the existing underlying zoning.
- (f) Landscaping and maintenance of common areas. All required yards and common areas must be landscaped and adequately and permanently maintained by the property owner, tenant, or organization responsible for maintaining common areas. Through an irrevocable conveyance, such as deed restrictions or covenants that run with the land, the developer must assure that all yards and common areas will be developed in accordance to the site plan and not changed to another use.
- (g) Additional considerations. During review of a proposed planned development, the Planning Commission must take into account the following considerations which may be relevant to a particular project: perimeter setbacks and screening; thoroughfares, drainage, as provided for in best management practices as appropriate, and utility design; underground installation of utilities; insulating pedestrian circulation from vehicular thoroughfares and ways; achievement of an integrated development with respect to signage, lighting, landscaping and building materials; and noise reduction mechanisms, particularly in cases where nonresidential uses adjoin off-site residentially-zoned property.

Sec. 122-703. Planned adaptive reuse projects. (574) (753)

A planned unit development that involves adaptive reuse of an existing structure that is located in a residential zoning district, but that was originally constructed for non-residential use, may be reviewed as a planned adaptive reuse project at the request of the applicant. The following requirements must apply to a planned adaptive reuse project in addition to the requirements applied to all planned unit developments:

- (a) Eligibility. The project must involve the reuse of an existing structure that is located in a residential zoning district, that was constructed for non-residential use.
- (b) Minimum size. Notwithstanding §122-702(b), no minimum size is required for a planned adaptive reuse project.
- (c) Permitted uses. Notwithstanding §122-701, a planned adaptive reuse project may include any uses determined by the City Council, upon Planning Commission recommendation, to be appropriate for the site and compatible with adjacent uses and zoning districts, with the master plan, and with any subarea plans.

Sec. 122-704. Application requirements. (575) (754)

An application for a planned unit development must contain the following:

- (a) Cover letter signed by the applicant and owner holding an equitable interest in the property.
- (b) Legal description showing the location and acreage of the property.
- (c) General description of proposed development, including a timetable of development and a list of departures from the regulations of this chapter which will be required.
- (d) Site plan at a scale of one inch equals 50 feet or larger, prepared in accordance with §122-309. Additional information on the site plan must include:

- (1) A schedule of total land areas devoted to each type of use, useable floor areas, density calculations, number and types of units, and building ground coverage.
 - (2) Open space areas, indicating the proposed uses and improvements for such areas.
 - (3) Architectural sketches showing building heights, external wall finishes, location of building entry ways, lighting elements, and other architectural features.
 - (4) Copy of agreements, covenants, or deed restrictions which will assure that the development will be completed and maintained as shown on the plans by the developer and successive owners.
 - (5) Other information deemed pertinent to the proposed development by the Planning Commission or City Council.
- (e) A fee for the processing of the planned development application, as established by the City Council.

Sec. 122-705. Review procedures. (576) (755)

The review and approval process for planned unit developments must be as follows:

- (a) Preapplication conference.
 - (1) In order to facilitate review of a planned unit development proposal in a timely manner, the applicant may request an informal preapplication conference with City staff. The purpose of such a conference is to exchange information and provide guidance to the applicant that will assist in preparation of application materials.
 - (2) The applicant must present at such a conference, at a minimum, a concept plan of the proposed planned unit development (drawn to scale), a legal description of the property in question, the total land areas of the project, the approximate number of residential units to be constructed, the floor area of nonresidential uses, and areas to be designated as common areas or open space.
 - (3) No formal action must be taken at a preapplication conference. There must be no fee for a preapplication conference. Statements made at the preapplication conference must not be legally binding commitments.
- (b) Public hearing. After a formal application has been filed for a planned unit development, it must be reviewed by the City Planner and planning and development department for completeness and submitted to the Planning Commission. A public hearing on the proposed planned unit development must be scheduled. Notice of the public hearing must be published in a newspaper of general circulation in the City, and sent by mail or personal delivery to the owners of property for which approval is being considered, to all persons to whom real estate property is assessed within 300 feet of the boundary of the property in question, and to the occupants of all structures within 300 feet. Such notice must be given not less than 15 days before the public hearing scheduled. Such notification must contain the following information:
 - (1) Nature of the planned unit development project requested.
 - (2) Boundaries of the property which is the subject of the request.
 - (3) Date and time of the public hearing.
 - (4) Location and times that written comments will be received concerning the request.
- (c) Planning Commission recommendations. Within a reasonable time not to exceed 90 days following the public hearing, the Planning Commission must make its final consideration of the request, and must recommend to the City Council denial, approval, or approval with conditions, of the request. The Planning Commission must have prepared a report stating its conclusions, the basis for its recommendations, and any conditions relating to an affirmative recommendation.
- (d) City council action.
 - (1) The City Council must be provided with a copy of the Planning Commission's report, a summary of comments received at the public hearing, minutes of all proceedings, and all documents related to the planned unit development. Within a reasonable time, not to exceed 60 days, after the action of the Planning Commission, the City Council must deny, approve, or approve with conditions, the request.
 - (2) The City Council may require that a performance guarantee be deposited with the City to insure faithful completion of improvements, in accordance with [§122-317](#). Unapproved deviations or delays in construction may result in a loss of all or a portion of the performance guarantee.
 - (3) The City Council may also impose other conditions to ensure that a planned unit development is constructed in an orderly manner, consistent with the spirit and intent of this chapter; and that the planned unit approach is not used as a means of circumventing restrictions on the location or quantity of certain types of land uses.
- (e) Effect of approval.
 - (1) Approval of a planned unit development proposal must constitute an amendment to this chapter. All improvements to and use of the site must be in conformity with the approved planned unit development site plan and any conditions imposed.
 - (2) Within three business days of official approval of the application and site plan by the City Council, the City clerk must attest the planned unit development designation for the land in question on the Zoning Map.

- (3) Notice of the adoption of the planned unit development designation must be published in a newspaper of general circulation within the City within 15 days after approval in accordance with §122-361.
- (f) Recorded with register of deeds. The applicant must record with the county register of deeds within ten days of approval of the application the following: a legal description of the project site, the approved site plan and an affidavit declaring that all future improvements will be made in accordance with the approved planned unit development.

Sec. 122-706. Standards for approval. (577) (756)

In considering any application for a planned unit development, the Planning Commission and City Council must make their determinations based on the standards for site plan approval in §122-311 and the following standards:

- (a) Conformance with the planned development concept. The overall design and all uses proposed in connection with a planned unit development must be consistent with and promote the intent of this article, as well as with specific project design standards set forth in this chapter.
- (b) Recognizable benefits. The planned development will result in recognizable and substantial benefits to the ultimate users of the project and to the community in general where such benefits would otherwise be unfeasible or unlikely to be achieved.
- (c) Compatibility with adjacent uses. The proposed planned unit development must be designed with due regard to its relationship with development on surrounding properties and uses thereon, including building heights, setbacks, density, parking, circulation, landscaping, views, and other layout features. In particular, consideration must be given to the following:
 - (1) The bulk, placement, architecture, and types of materials used in construction of proposed structures.
 - (2) The location and screening of vehicular circulation and parking areas in relation to surrounding development.
 - (3) The location and screening of outdoor storage, outdoor activity or work areas, and mechanical equipment in relation to surrounding development.
 - (4) The hours of operation of the proposed uses.
 - (5) Landscaping, preservation of historic features, and other site amenities.
- (d) Impact of traffic. The planned development must be designed to minimize any adverse impact of traffic generated by the proposed development. Consideration must be given to the following:
 - (1) Estimated traffic to be generated by the proposed development.
 - (2) Access to major thoroughfares.
 - (3) Proximity and relation to intersections.
 - (4) Adequacy of driver sight distances.
 - (5) Location of and access to off-street parking.
 - (6) Required vehicular turning movements.
 - (7) Provisions for pedestrian traffic.
 - (8) Access to loading and unloading areas.
- (e) Public services. The proposed type and density of use must not result in a material increase in the need for public services, facilities, and utilities; including but not necessarily limited to water and sewer services, public roads, fire and police protection, and schools. The proposal must not place an undue burden upon the subject or surrounding land or property owners and occupants or the natural environment.
- (f) Compatibility with master plan and this chapter. The proposed development must be compatible with the adopted City master plan and with the spirit and intent of this chapter.
- (g) Economic impact. The proposed development must not result in an unreasonable negative economic impact upon surrounding properties.
- (h) Compliance with applicable regulations. The proposed development must be in compliance with all applicable federal, state, county, and local laws and regulations.
- (i) Phasing. Where a project is proposed for construction in phases, the project must be so designed that each phase, when completed, must be capable of standing on its own in terms of the presence of services, facilities, and open space; and must contain the necessary components to ensure protection of natural resources and the health, safety, and welfare of the users of the planned unit development and the occupants of the surrounding area.

Sec. 122-707. Expiration of approval. (578) (757)

- (a) Approval of the planned unit development must expire and be of no effect unless construction must have commenced within one year of the date of the approval. An extension for a specified period may be granted by the City Council upon good cause shown, if such request is made to the City Council prior to the expiration period.
- (b) In the event an approved planned unit development has expired, the City Council may rezone the property in

any reasonable manner following Planning Commission recommendation and a public hearing in accordance with [Article III, Division 4](#) of this chapter. If, at the discretion of the City Council, the property remains classified as a planned unit development, a new application is required and will be reviewed in light of the prevailing conditions, applicable laws, and ordinance provisions.

Sec. 122-708. Revision of approved plans. (579) (758)

- (a) General revisions. Approved final plans for a planned unit development may be revised in accordance with the procedures set forth in [§122-705](#). Major revisions would include, but must not be limited to, increases in scope or density of use, land area, or building size; the addition of uses not authorized by the original planned unit development approval; the rearrangement of lots or building tracts; changes in the character or function of drives; or changes in the concept of the development.
- (b) Minor changes. Notwithstanding subsection (a) of this section, minor changes may be permitted by the Planning Commission following normal site plan review procedures outlined in [Article III](#) of this chapter, subject to its finding of the following:
 - (1) Such changes will not adversely affect the initial basis for granting approval; and
 - (2) Such minor changes will comply with all applicable requirements of this chapter and other local, state, and federal laws; and will not adversely affect the overall planned unit development in light of the intent and purpose of such development as set forth in this article.

Sec. 122-709. Appeals and variances. (580) (759)

The Zoning Board of Appeals is without jurisdiction to accept appeals or grant variances with respect to an approved planned unit development.

Division 2: Site Condominium Subdivisions

Sec. 122-710. Purpose and scope. (601) (760)

Site condominium subdivisions are developments utilizing the technique of land division on the basis of condominium ownership. As such, site condominium subdivisions are not subject to the provisions of the land division act, Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101 et seq.), MSA 26.430(101) et seq.), as amended. This section requires the submittal and review of site condominium subdivision plans under this chapter to ensure that such developments are accomplished with the same results as if the improvements were being proposed pursuant to the land division act, including, without limitation, conformance with all requirements of the applicable regulations contained in this chapter. Site condominium subdivision projects may be approved in any zoning district as a special use under the provisions of [Article III, Division 2, Subdivision II](#) of this chapter, or where divergence from the use, height, area, and placement regulations of this chapter is desired, the provisions of [Article VII, Division 1](#) of this chapter.

Sec. 122-711. Zoning compliance. (603) (761)

All site condominium subdivisions and structures therein must comply with all the use, size, height, area, setback, sign, and all other regulations of the zoning district in which the subdivision is located unless modified through the provisions of [Article VII, Division 1](#) of this chapter regarding planned unit developments.

Sec. 122-712. Review and approval procedures. (604) (762)

Application for review and approval of site condominium subdivision projects shall be made pursuant to the provisions of [Article III, Division 2, Subdivision II](#) or [Article VI, Division 1](#) of this chapter.

Sec. 122-713. Effect of approval. (605) (763)

Approval of a site condominium subdivision project serves as authorization to proceed with the division of the land on the basis of condominium ownership and the construction of required improvements to the land. However, unless specifically addressed and authorized, site condominium subdivision approval does not serve as the authorization of land uses on individual lots within the subdivision. All uses are subject to the provisions of this chapter otherwise applicable to the specific zoning district and use in question.

Sec. 122-714. Site plans. (606) (764)

The site plan submitted for a site condominium subdivision must be consistent with the requirements outlined in [§122-309](#) showing the location, size, shape, area, and width of all lots, all general and limited common elements, and street and utility layout. In addition, the following must be included as part of the application for special land use approval:

- (a) The use and occupancy restrictions as will be contained in the master deed.
- (b) A "consent to submission of real property to condominium project," listing all parties which have ownership interest in the proposed site condominium subdivision, or evidence of authority or right that the developer has a legal option to purchase the subject property from the owner of record.

Sec. 122-715. Layout, design and required improvements. (607) (765)

Site condominium subdivision plans must conform to the design, layout, and improvement standards as may be promulgated by the City Council by ordinance. Any such standards and regulations are hereby incorporated by reference in this article.

- (a) Streets. If a site condominium subdivision is proposed to have public streets, the streets must be paved and developed to the minimum design, construction, inspection, approval, and maintenance requirements for public streets as adopted by the City.
- (b) Utilities. Extension and provision of utilities must be provided as may be required by the City as conditions of approval.
- (c) Drainage. Procedures and design criteria for drainage must be as provided in the rules of the county drain commissioner, pursuant to section 105(c) of Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101(c), MSA 26.430(101), (c)), as amended.

Sec. 122-716. Master deed contents. (608) (766)

All provisions of the site condominium plans which are approved by the City pursuant to this article must be incorporated, as approved, in the master deed for the site condominium subdivision. Any proposed changes to the

approved site condominium plans must be received and approved by the City pursuant to the procedure set forth in §122-712 for the approval of site condominium plans. A copy of the master deed as filed with the county register of deeds for recording must be provided to the City Clerk within ten days after such filing with the County.

Secs. 122-717 – 719. Reserved.

Division 3: Flood Damage Prevention

Sec. 122-720. Flood hazard findings. (911) (770)

The flood hazard areas of the City are subject to periodic inundation which may result in safety hazards, loss of life, property and health, disruption of commerce and governmental services, extraordinary public expenditures for flood protection and relief, and impairment of the tax base, all of which adversely affect the public health, safety and welfare. The flood losses are caused by the cumulative effects of obstructions in floodplains causing increased flood heights and velocities, and by the occupancy in flood hazard areas by uses vulnerable to floods or hazardous to other lands which are inadequately elevated, floodproofed or otherwise protected from flood damages.

Sec. 122-721. Purpose. (912) (771)

It is the purpose of this article to protect the general public and all land within the City subject to flood losses by provisions designed to do the following:

- (a) Restrict or prohibit uses which are dangerous to health, safety and property in times of flood or which cause excessive increases in flood flow heights or velocities.
- (b) Require that uses vulnerable to floods, including facilities which serve such uses, be protected against flood damage at the time of initial construction.
- (c) Control the alteration of natural floodplains, stream channels and natural protective barriers which are involved in the accommodation of floodwaters.
- (d) Control filling, grading, dredging and other development which may increase erosion or flood damage.
- (e) Prevent or regulate the construction of flood barriers which will unnaturally divert floodwaters or which may increase flood hazards to other lands.

Sec. 122-722. Scope. (913) (772)

This article shall apply to all flood hazard areas. The boundaries of the flood hazard areas shall coincide with the boundaries of the areas indicated as within the limits of the 100 year flood in the report entitled Flood Insurance Study, Washtenaw County (All Jurisdictions) Community Number 260216, dated April 3, 2012, with accompanying Flood Insurance Rate maps and Flood Boundary and Floodway maps. Within the flood hazard area zone, a regulatory floodway shall be designated. The boundaries of the regulatory floodway shall coincide with the floodway boundaries indicated on the flood boundary and floodway maps. The study and accompanying maps are adopted by reference, appended, and declared to be a part of this chapter. The term flood hazard area, as used in this chapter, shall mean flood hazard area zone and the term floodway, shall mean the designated regulatory floodway.

- (a) AGENCY DESIGNATED. Pursuant to the provisions of the state construction code, in accordance with Section 8b(6) of Act 230, of the Public Acts of 1972, as amended, the Building Official of the City of Ypsilanti is hereby designated as the enforcing agency to discharge the responsibility of the City of Ypsilanti under Act 230, of the Public Acts of 1972, as amended, State of Michigan. The City of Ypsilanti assumes responsibility for the administration and enforcement of said Act throughout the corporate limits of the community adopting this ordinance.
- (b) CODE APPENDIX ENFORCED. Pursuant to the provisions of the state construction code, in accordance with Section 8b(6) of Act 230, of the Public Acts of 1972, as amended, Appendix G of the Michigan Building Code shall be enforced by the enforcing agency within the City of Ypsilanti.
- (c) DESIGNATION OF REGULATED FLOOD PRONE HAZARD AREAS. The Federal Emergency Management Agency (FEMA) Flood Insurance Study (FIS) Entitled Washtenaw County, Michigan (All Jurisdictions) and dated April 3, 2012 and the Flood Insurance Rate Map(s) (FIRMS) panel number(s) of 26161C; 00269E, 0288E, 0407E, and 0426E dated April 3, 2012 are adopted by reference for the purposes of administration of the Michigan Construction Code, and declared to be a part of Section 1612.3 of the Michigan Building Code, and to provide the content of the "Flood Hazards" section of Table R301.2(1) of the Michigan Residential Code.

Sec. 122-723. Regulation of uses in floodplain areas. (914) (773)

Any proposed occupation, structure, excavation, fill, extraction, grading or scraping and any substantial improvement to an occupation, structure or area shall be reviewed and approved by the Planning Commission.

"Substantial improvement" means any repair, reconstruction or improvement of an occupation, structure or area, the cost of which equals or exceeds 50 percent of the market value of the structure either, (i) before the improvement or repair is started or (ii) if the occupation, structure or area has been damaged and is being restored, before the damage occurred. For the purpose of this definition, "substantial improvement" is considered to occur when the first alteration of any wall, ceiling, floor or other structural member commences, whether or not that alteration affects the

external dimensions of the structure or area. The term does not, however, include either (i) any project for improvement of a structure to comply with state or local health, sanitary or safety code specifications which are solely necessary to assure safe living conditions, or (ii) any alteration of a structure listed on the National Register of Historic Places or state register of historic places.

(a) Permitted uses. The following uses may be permitted in those portions of the floodplain which are not a floodway, to the extent that they are allowed uses within a given zoning district and subject to the construction standards of building code in effect for the City at the time of construction:

- (1) Residential and nonresidential structures provided that the building official certifies to the Planning Commission that the proposed provisions for flood resistant construction, flood proofing or elevation meet or exceed the standards set forth in the City's building code.
- (2) Recreational uses such as parks, swimming areas, picnic grounds, ball fields, hiking or biking trails, and wildlife and nature preserves.
- (3) Residential support uses such as lawns, gardens, play areas, and parking areas which do not result in the filling in of floodplain areas.
- (4) Industrial and commercial support uses which are open in nature such as loading areas or parking areas which do not result in the filling in of any floodplain areas.
- (5) Utility facilities such as power plants, transmission lines, pipelines not crossing a lake or waterway, lighting facilities, and navigational and drainage aids.
- (6) Piers, boat ramps, bridges, and other such water related uses subject to approval by the water resources commission of the state department of natural resources.
- (7) Fencing of any type, provided that such fencing shall not be located in that portion of the floodplain that is a floodway or other areas essential to the conveyance of floodwaters.
- (8) Sidewalks, driveways, patios, and similar structures when constructed at grade.
- (9) Fill or removal of topsoil, sand, and gravel or other extraction operations, in that portion of a floodplain which is not a floodway provided the following conditions are met:
 - (i) Proof that proper long term maintenance will be provided so that the flood-carrying capacity is not diminished.
 - (ii) Any fill or excavated area shall be protected from erosion during and after operations by rip-rap, vegetative cover, bulk-heading, or other approved means.
 - (iii) The proposed filling in of land, provided that material equal to 110 percent of the fill volume is removed elsewhere from such premises and adjusted to be capable of storing floodwaters. Structures and parking areas may be permitted on such filled land provided the elevation of the filled land is at least one foot above the base flood elevation. A permit issued by the state department of natural resources under the state's floodplain regulatory authority, Act No. 451 of the Public Acts of Michigan of 1994 (MCL 324.3101 et seq., MSA 13A.3101 et seq.), shall be obtained prior to the filling of land in the floodplain. A copy of the state department of natural resources permit shall be provided to the City building inspection division prior to the issuance of a building permit.
- (10) Streets, railroads, and other rights-of-way.
- (11) Pavilions, open amphitheaters, detached garages, raised patios and decks, and other accessory structures provided they are properly anchored and made flood resistant and are not located in a floodway or other area essential to the conveyance of floodwaters.
- (12) Facilities for the storage and detention/retention of stormwater.
- (13) Storage yards for heavy equipment, materials, or machinery.

(b) Prohibited uses. The following uses are not allowed in a floodplain area under any circumstances:

- (1) New residential construction or occupation, including mobile homes, manufactured homes or pre-manufactured homes, are specifically prohibited in that portion of the floodplain that is a floodway. Other types of construction and occupation may be allowed in that portion of the floodplain that is a floodway; however, a hydraulic analysis shall be required which demonstrates that occupation and resulting obstruction of the floodway will not restrict the flood carrying capacity of the watercourse.
- (2) A landfill, dump, junkyard, recycling center or hazardous waste storage or treatment facility are expressly prohibited in a floodplain area.
- (3) The storage or processing of materials which in time of flooding become buoyant, flammable, explosive or otherwise injurious to public health, is expressly prohibited within a floodplain area.
- (4) On-site sewage disposal systems shall be permitted within a floodplain area.
- (5) Any encroachment which would cause any increase in the base flood level.

Sec. 122-724. Review procedures. (915) (774)

(a) Site plan review. All development, construction, occupation or substantial improvement proposals located within a floodplain area shall be reviewed by the City Planner or Planning Commission in accordance with the

site plan review procedures of [Article III](#) of this chapter, and the "Rules of the Washtenaw County Water Resources Commissioner." The City Planner or Planning Commission, when reviewing an application for occupation, construction or substantial improvement in a floodplain, shall consider the following standards before rendering a decision:

- (1) Any possible danger to life and property as a result of increased flood heights or velocities caused by encroachments on the floodplain.
 - (2) The danger that materials may be swept to other lands or downstream to the injury or property loss of others.
 - (3) The susceptibility of the proposed development and its contents to flood damage.
 - (4) The importance of the services provided by the development to the community.
 - (5) The requirement of the proposed development for a waterfront location and the availability of alternate locations not subject to flooding.
 - (6) The compatibility of the proposed use with existing and anticipated development of the surrounding area and the floodplain management program of the area.
 - (7) The safety of access to the property in times of flood for ordinary and emergency vehicles.
 - (8) The measures taken to assure adequate drainage so as to reduce exposure to flood hazards.
 - (9) The Planning Commission may attach certain conditions to an approval such as limitations on period of use and operation; imposition of operational controls, deed restrictions, performance bonds, and covenants; or requirements for construction of dikes, levees, and other protection measures.
- (b) Building official's responsibility. Prior to site plans being submitted to the Planning Commission the building official shall:
- (1) Certify that the proposed construction, occupation or substantial improvement complies with the City building code adopted in [Chapter 18](#).
 - (2) Where permits are required by other state or federal agencies, a copy of the approved permit shall be provided, by the applicant, prior to review by the Planning Commission.
 - (3) Cause to be verified and recorded on the site plan and building plans, the actual elevation (in relation to mean sea level) of the lowest floor (including basement) of all new or substantially improved structures.
 - (4) Cause to be verified and recorded on the site plan and building plan, the actual elevation (in relation to mean sea level) to which the new or substantially improved structures have or will be floodproofed.
 - (5) Require that all site plans and building plans for occupation, construction or substantial improvement within the floodplain have been prepared under the supervision of a registered professional engineer or architect. All site plans and building plans shall be signed by the registered professional engineer or architect.
 - (6) Certify that notification has been made to adjacent communities and the state flood control coordinator of a proposed development, construction, occupation, substantial improvement alteration or relocation of a watercourse, and submit evidence of such notification to the Federal Insurance Administration and the Planning Commission.
 - (7) Be available at the meeting of the Planning Commission when such plans are reviewed to answer any questions relative to the floodplain or construction standards.

Sec. 122-725. Building permit requirements. (916) (775)

No occupation, building or structure within a floodplain area shall be erected, moved, repaired, altered, or razed until a building permit shall have been obtained from the building official in accordance with the customary building permit requirements under [Chapter 18](#). For structures located within a floodplain, the following additional information shall be included with the building permit, and shall become a condition of the permit. All plans, specifications and conditions approved by the Planning Commission. The plans shall include all of the information required by [§122-724](#).

Sec. 122-726. Appeals, variances. (917) (776)

The Zoning Board of Appeals shall hear and decide appeals and requests for variances from the requirements of this article, in accordance with the procedures and conditions set forth in this article. Prior to hearing of the appeal, the City Planner shall certify to the Zoning Board of Appeals that notices as required under this article have been made. Further, the City Planner shall certify to the Zoning Board of Appeals that the immediate downstream community's chief elected official and the state flood control coordinator have been notified of the request for appeals or variance and of the public hearing. Appeals or variances relating to the construction standards as set forth in the building code, shall be heard by the construction board of appeals as outlined in [Chapter 18](#). In addition, the following conditions shall be applied to variances granted from the floodplain regulations of this article:

- (a) Variances shall be issued upon a determination that the granting of a variance will not result in increased flood heights, additional threats to public safety, extraordinary public expense, public nuisances, or cause fraud on or victimization of the public.

- (b) Any applicant to whom a variance is granted shall be given a written notice specifying the difference between the base flood elevation and the elevation at which a structure is being built, and a statement that the cost of flood insurance will be commensurate with the increased risk resulting from the reduced lowest floor elevation.
- (c) All such variances to this article shall be maintained in a record and reported to the Federal Insurance Administration and the state flood control coordinator upon request.

Sec. 122-727. Disclaimer of liability. (918) (777)

The degree of flood protection required by this article is considered the minimum necessary and reasonable for regulatory purposes. Larger floods may occur at any time, and excessive floodwater heights may be experienced due to manmade and natural causes. This article does not imply that areas outside the special flood hazard areas, or uses permitted within such areas, shall remain free from flooding or flood damages. This article shall not create a liability on the part of the City or any officer or employee thereof for any flood damage that results from compliance with or reliance upon this article or any administrative decision lawfully made thereunder.

Secs. 122-728 – 999. Reserved.



ZONING ORDINANCE

City of Ypsilanti, Michigan

Approved by City Council 16 December 2014
Updated June 7, 2015
Updated April 14, 2016 (Parks District)

Chapter 122

ZONING

Article I. In General

Sec. 122-1	Intent
Sec. 122-2	Interpretation of language
Sec. 122-3	Definitions
Sec. 122-4	Interpretation and Conflict
Sec. 122-5	Rule of Construction
Sec. 122-6	Administrative Liability
Sec. 122-7	Vested right
Sec. 122-8	Violations and Penalties
Sec. 122-9 – 122-30	Reserved

Article II. Administration

Division 1.	Generally
Sec. 122-31	Establishment of administrative officers
Sec. 122-32	Duties and enforcement powers
Sec. 122-33	Building permits
Sec. 122-34	Certificate of occupancy
Sec. 122-35	Temporary use permits
Sec. 122-36 – 122-45	Reserved
Division 2.	Planning Commission
Sec. 122-46	Authority
Sec. 122-47	Purpose
Sec. 122-48	Establishment
Sec. 122-49	Reserved
Sec. 122-50	Zoning board of appeals member of the Planning Commission
Sec. 122-51	Procedures of the Planning Commission
Sec. 122-52	Meetings of the Planning Commission
Sec. 122-53	Duties and responsibilities of the Planning Commission
Sec. 122-54	Approval, ratification and reconfirmation
Sec. 122-55 -122-60	Reserved
Division 3.	Amendments
Sec. 122-61	General requirements
Sec. 122-62	Amendment procedures
Sec. 122-63	Standards for Amendments
Sec. 122-64	Protests
Sec 122-65	Resubmitted amendments
Sec. 122-66-122-90	Reserved

Article III. Zoning Board of Appeals

Sec. 122-91	Establishment and membership
Sec. 122-92	Powers and duties
Sec. 122-93	General procedures
Sec. 122-94	Variances
Sec. 122-95	Appeals
Sec. 122-96	Decisions final
Sec. 122-97	Time limitations
Sec. 122-98	Fees
Sec. 122-99 – 122-120	Reserved

Article IV. Site Plan Review

- Sec. 122-121 Purpose
- Sec. 122-122 Requirement for zoning compliance review
- Sec. 122-123 Requirement for and Authority to review site plans
- Sec. 122-124 Site plan review checklist
- Sec. 122-125 Application procedure; contents
- Sec. 122-126 Site plan content
- Sec. 122-127 Review procedure and authorization
- Sec. 122-128 Standards for site plan review
- Sec. 122-129 Issuance of building permit
- Sec. 122-130 Amendment of approved site plan
- Sec. 122-131 Modification of plan during construction
- Sec. 122-132 As-built drawings
- Sec. 122-133 Phasing of development
- Sec. 122-134 Performance guarantee
- Sec. 122-135 Fees
- Sec. 122-136 Record of approval
- Sec. 122-137 – 122-160 Reserved

Article V. Special Land Use Review

- Sec. 122-161 Statement of intent
- Sec. 122-162 Authority to grant permits
- Sec. 122-163 Application; contents
- Sec. 122-164 Public hearing
- Sec. 122-165 Standards for reviewing special use requests
- Sec. 122-166 Planning Commission action
- Sec. 122-167 Conditions of approval
- Sec. 122-168 Duration of special use approval
- Sec. 122-169 Amendments to special land uses
- Sec. 122-170 Revocation of special land use approval
- Sec. 122-171 Appeals
- Sec. 122-172 Reapplication
- Sec. 122-173 – 122-200 Reserved

Article VI. Nonconforming Uses, Buildings, Structures or Lots

- Sec. 122-201 Description and purpose
- Sec. 122-202 Authority to continue nonconforming uses and structures
- Sec. 122-203 Nonconforming lots
- Sec. 122-204 Nonconforming use of land
- Sec. 122-205 Nonconforming uses of buildings or structures
- Sec. 122-206 Nonconforming buildings or structures
- Sec. 122-207 Acquisition of nonconformities
- Sec. 122-208 Building or structure under construction on effective date of the ordinance from which this chapter is derived
- Sec. 122-209 Unlawful nonconformities
- Sec. 122-210 – 122-230 Reserved

Article VII. District Regulations

- Division 1. Generally
 - Sec. 122-231 Establishment of districts
 - Sec. 122-232 Zoning Map
 - Sec. 122-233 Application of chapter

Sec. 122-234 Interpretation of district boundaries
Sec. 122-235 Uses permitted as a right
Sec. 122-236 Uses permitted under special approval
Sec. 122-237 Zoning of vacated land
Sec. 122-238 Zoning of annexed land
Sec. 122-239 – 122-250 Reserved

Division 2 R1 Single-Family Residential District

Sec. 122-251 Description and purpose
Sec. 122-252 Permitted uses
Sec. 122-253 Schedule of Regulations
Sec. 122-254 – 122-260. Reserved

Division 3 MD Multiple Dwelling Residential Districts

Sec. 122-261 Description and purpose
Sec. 122-262 Permitted uses
Sec. 122-263 Schedule of Regulations
Sec. 122-264 – 122-270. Reserved

Division 4 Neighborhoods, Centers, Corridors and Health and Human Services Districts

Sec. 122-271 Description and purpose
Sec. 122-272 Permitted uses
Sec. 122-273 Circulation standards
Sec. 122-274 Building Types
Sec. 122-275 Reserved
Sec. 122-276 Number of detached accessory buildings
Sec. 122-277 Steps for Use of Regulations for CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts
Sec. 122-278 – 122-290. Reserved

Division 5 Production, Manufacturing and Distribution District

Sec. 122-291 Description and purpose
Sec. 122-292 Permitted uses
Sec. 122-293 Area regulations
Sec. 122-294 Performance Standards for PMD Districts
Sec. 122-295 – 122-300. Reserved

Division 6 Park District

Sec. 122-301 Description and purpose
Sec. 122-302 Permitted uses
Sec. 122-303 Area regulations
Sec. 122-304 – 122-320. Reserved

Article VIII. Reserved

Sec. 122-522 – 122-570 Reserved

Article IX. Planned Unit Development

Sec. 122-571 Description and purpose
Sec. 122-572 Permitted uses
Sec. 122-573 Requirements for planned unit developments
Sec. 122-574 Planned adaptive reuse projects
Sec. 122-575 Application requirements
Sec. 122-576 Review procedures
Sec. 122-577 Standards for approval
Sec. 122-578 Expiration of approval
Sec. 122-579 Revision of approved plans

Sec. 122-580 Appeals and variances
Sec. 122-581 – 122-600 Reserved

Article X. Site Condominium Subdivisions

Sec. 122-601 Purpose and scope
Sec. 122-602 Definitions
Sec. 122-603 Zoning compliance
Sec. 122-604 Review and approval procedures
Sec. 122-605 Effect of approval
Sec. 122-606 Site plans
Sec. 122-607 Layout, design and required improvements
Sec. 122-608 Master deed contents
Sec. 122-609 – 122-630 Reserved

Article XI. Supplementary District Regulations

Division 1 Generally

Sec. 122-631 Scope
Sec. 122-632 Control of heat, glare fumes, dust, noise, etc.
Sec. 122-633 Damaged or destroyed buildings
Sec. 122-634 Dumping on land prohibited
Sec. 122-635 Dwelling on rear of lot
Sec. 122-636 Easements
Sec. 122-637 Essential services
Sec. 122-638 Depositing or burying garbage; excavation or filling
Sec. 122-639 Grades; elevation differentials
Sec. 122-640 Steep slopes protection
Sec. 122-641 Outdoor lighting
Sec. 122-642 Direct access to major thoroughfares
Sec. 122-643 Moving of buildings or structures
Sec. 122-644 Porches, decks, balconies, fire escapes, and barrier-free access ramps
Sec. 122-645 Public service access
Sec. 122-646 Retaining walls
Sec. 122-647 Sidewalks
Sec. 122-648 Street frontage requirements
Sec. 122-649 Traffic visibility
Sec. 122-650 Trash receptacles and dumpsters
Sec. 122-651 Unclassified uses
Sec. 122-652 Voting place
Sec. 122-653 – 122-665 Reserved

Division 2 Accessory Structures and Uses

Sec. 122-666 Purpose and intent
Sec. 122-667 General standards for accessory structures
Sec. 122-668 Swimming pools
Sec. 122-669 Home occupations
Sec. 122-670 Garage sales, rummage sales, and owner-made craft sales
Sec. 122-671 – 122-680 Reserved

Division 3 Communication Devices

Sec. 122-681 Intent
Sec. 122-682 General standards
Sec. 122-683 Antenna systems
Sec. 122-684 Satellite dish stations
Sec. 122-685 Communication devices in residential districts
Sec. 122-686 Communication devices in C, O, HC, NC and GC districts
Sec. 122-687 Communication devices in the PMD zoning districts

Sec. 122-688 – 122-700 Reserved

Division 4 Landscaping, Greenbelts and Screening

- Sec. 122-701 Intent
- Sec. 122-702 Landscape plan requirements
- Sec. 122-703 Screening between land uses
- Sec. 122-704 Off-street parking area landscaping
- Sec. 122-705 Street trees
- Sec. 122-706 Front greenbelts
- Sec. 122-707 Foundation landscaping
- Sec. 122-708 Site landscaping
- Sec. 122-709 Residential development landscaping
- Sec. 122-710 Screening of exterior electrical equipment and transformers
- Sec. 122-711 Landscape elements
- Sec. 122-712 Installation, maintenance, and completion
- Sec. 122-713 Fences, hedges, walls, berms, and screening
- Sec. 122-714 Modifications or exceptions to requirements

Division 5 Reserved

Sec. 122-715 – 122-730 Reserved

Division 6 Storage of Vehicles

- Sec. 122-731 General prohibition
- Sec. 122-732 Commercial vehicles in residential areas
- Sec. 122-733 Recreational vehicles
- Sec. 122-734 Unlicensed, untitled, and inoperable motor vehicles, and disassembled parts of motor vehicles
- Sec. 122-735 Reserved
- Sec. 122-736 Responsibility for violations
- Sec. 122-737 – 122-750 Reserved

Division 7 Yard, Area and Lot Requirements

- Sec. 122-751 Altered land parcel
- Sec. 122-752 Area requirements
- Sec. 122-753 Corner lots
- Sec. 122-754 Lots adjoining alleys
- Sec. 122-755 Determinations by zoning board of appeals
- Sec. 122-756 Land division
- Sec. 122-757 – 122-770

Article XII. Specific Standards for Certain Uses

- Sec. 122-771 Purpose
- Sec. 122-772 Compliance with article
- Sec. 122-773 Adult foster care small and large group homes, adult foster care congregate facilities and foster family group homes
- Sec. 122-774 Adult regulated uses
- Sec. 122-775 Automobile service or repair
- Sec. 122-776 Automobile filling stations
- Sec. 122-777 Automobile or car wash establishments
- Sec. 122-778 Bed and breakfast lodgings and inns
- Sec. 122-779 Child care centers; child drop-off centers, and group day care homes
- Sec. 122-780 Religious Institutions and Services
- Sec. 122-781 Parking garages
- Sec. 122-782 Parking lot as principal use
- Sec. 122-783 Drive-in and drive-through restaurants
- Sec. 122-784 Drive-through facilities
- Sec. 122-785 Homeless Shelter
- Sec. 122-786 Express and passenger terminals

Sec. 122-787	Reserved
Sec. 122-788	Solar Collectors
Sec. 122-789	Reserved
Sec. 122-790	Junkyards
Sec. 122-791	Commercial kennels
Sec. 122-792	Reserved
Sec. 122-793	Medical clinics or neighborhood counseling centers
Sec. 122-794	Multiple-family dwellings containing seven or more units
Sec. 122-795	Municipal, county, regional and state service buildings and uses
Sec. 122-796	Nursing homes, convalescent homes and rest homes
Sec. 122-797	Offices and showrooms for skilled trade services
Sec. 122-798	Open-front or open-air businesses; Outdoor recreation/amusement facilities; Outdoor sales of new or used automobiles, trucks and tractors, boats, etc.
Sec. 122-799	Outdoor cafes, restaurants and beer gardens
Sec. 122-800	Outdoor retail sales of plant materials, lawn furniture, playground equipment, garden supplies, etc.
Sec. 122-801	Outdoor storage of raw materials, supplies and products
Sec. 122-802	Private noncommercial recreational areas or social facilities; Institutional or community recreational centers; Nonprofit swimming pool or tennis club
Sec. 122-803	Recycling centers
Sec. 122-804	Roominghouses & Group residences
Sec. 122-805	Primary, Secondary and Post-Secondary Schools (public & private)
Sec. 122-806	Self-storage facilities and vehicle storage facilities
Sec. 122-807	Enclosed storage of liquid and solid fuels
Sec. 122-808	Substance abuse treatment facilities
Sec. 122-809	Veterinary hospitals and clinics
Sec. 122-810	Printing services
Sec. 122-811	Supportive housing
Sec. 122-812	Auction house
Sec. 122-813	Medical Marijuana Dispensaries
Sec. 122-814	Medical Marijuana Growing/Manufacturing Facility
Sec. 122-815	Gardens/Community Gardens
Sec. 122-816 – 122-830	Reserved

Article XIII. Off-Street Parking and Loading Requirements

Sec. 122-831	Description and purpose
Sec. 122-832	Scope
Sec. 122-833	General requirements
Sec. 122-834	Parking dimensions
Sec. 122-835	Parking layout and construction
Sec. 122-836	Minimum and maximum number of parking spaces
Sec. 122-837	Reductions in Parking Requirements
Sec. 122-838	Required Bicycle Parking
Sec. 122-839	Off-street parking for physically handicapped persons
Sec. 122-840	Off-street stacking spaces for drive-through facilities
Sec. 122-841	Off-street loading space requirements
Sec. 122-842	Special assessment districts
Sec. 122-843	Fee in lieu of providing off-street parking
Sec. 122-844 – 122-860	Reserved

Article XIV. Signs

Sec. 122-861	Purpose
Sec. 122-862	General requirements
Sec. 122-863	Definitions
Sec. 122-864	Sign permit requirements
Sec. 122-865	Unsafe and prohibited signs
Sec. 122-866	Sign design standards

Sec. 122-867 Nonconforming signs
Sec. 122-868 Table of allowable signage
Sec. 122-869 – 122-910 Reserved

Article XV. Flood Damage Prevention

Sec. 122-911 Flood hazard findings
Sec. 122-912 Purpose
Sec. 122-913 Scope
Sec. 122-914 Regulation of uses in floodplain areas
Sec. 122-915 Review procedures
Sec. 122-916 Building permit requirements
Sec. 122-917 Appeals, variances
Sec. 122-918 Disclaimer of liability

ARTICLE I. IN GENERAL

Sec. 122-1. Intent

In the interpretation and application of this chapter, the provisions of this chapter shall be held to be minimum requirements for the promotion of the public health, safety and welfare. The provisions of this chapter are intended to create a safe and sustainable city; to meet the needs of the city's residents for food, fiber, energy and other natural resources; the location of places of residence, recreation, industry, trade, service and other uses of land; to ensure that uses of the land shall be situated in appropriate locations and relationships; to limit the inappropriate overcrowding of land and congestion of population and transportation systems and other public facilities; to facilitate adequate and efficient provision for transportation systems, sewage disposal, water energy, education, recreation and other public service and facility needs; and for those purposes, divide the City into districts and within those districts designate the uses for which buildings or structures may be erected or altered; what type of building may be erected, provide regulations for land uses, activities, or special uses which may be permitted subject to approval and regulation; establish the height and bulk of buildings, the area of yards, courts and other open spaces; restrict the maximum number of families which may be housed in dwellings; and impose regulations for land prone to flooding.

The intent and purpose of this Code is to enable, encourage and qualify the implementation of the following policies:

- (1) The block and the building
 - a. That buildings and landscaping should contribute to the physical definition of streets as civic places.
 - b. That development should create complete streets that adequately accommodate automobiles while respecting the pedestrian and the spatial form of public areas.
 - c. That the design of streets and buildings should reinforce safe environments, but not at the expense of accessibility.
 - d. That architecture and landscape design should grow from local climate, topography, history, and building practice.
 - e. That buildings should provide the community with a clear sense of geography and climate through energy efficient methods.
 - f. That Institutional Buildings and public gathering places should be provided as locations that reinforce community identity.
 - g. That Institutional Buildings should be distinctive and appropriate to a role more important than the other buildings that constitute the fabric of the city.

- h. That the preservation and renewal of historic buildings should be facilitated, to affirm the continuity and evolution of society.
 - i. That the harmonious and orderly evolution of urban areas should be secured through codes that regulate both building type and land use.

(2) The Districts

- a. That neighborhoods should provide meaningful choices in living arrangements as manifested by distinct physical environments.
 - b. That the District descriptions in Article VII shall constitute the intent of this Code with regard to the general character of each of these environments.

Sec. 122-2. Interpretation of language.

For the purpose of this chapter, the following rules of interpretation shall apply to the text of this chapter:

- (1) The particular shall control the general.
- (2) In the case of any difference of meaning or implication between the text of this chapter and any caption or illustration, the text shall control.
- (3) The word "shall" is always mandatory and not discretionary. The word "may" is permissive and discretionary.
- (4) Words used in the present tense shall include the future. Words used in the singular number shall include the plural, and the plural the singular, unless the context clearly indicates the contrary.
- (5) A "building" or "structure" includes any part thereof.
- (6) The phrase "used for" includes "arranged for," "designed for," "intended for," "maintained for," or "occupied for."
- (7) The word "person" includes an individual, a corporation, a partnership, a public utility, firm, an incorporated association, or any other similar entity.
- (8) Unless the context clearly indicates the contrary, or a regulation involves two or more items, conditions, provisions, or events connected by the conjunction "and," "or," "either . . . or," the conjunction shall be interpreted as follows:
 - a. "And" indicates that all the connected items, conditions, provisions, or events shall apply.

- b. "Or" indicates that the connected items, conditions, or provisions, or events may apply singly or in any combination.
- c. "Either . . . or" indicates that the connected items, conditions, or provisions, or events may apply singly or in any combination.

(9) Terms not defined in this chapter shall have the meaning customarily assigned to them.

Sec. 122-3. Definitions.

The following words, terms and phrases when used in this chapter shall have the meanings ascribed to them in this section, except where the context clearly indicates a different meaning:

Abandon means, in relation to nonconformities, to refer to uses, businesses, or establishments which have ceased to operate or exist; or to buildings, structures, or properties which have ceased to be occupied or used or for which no owner can be found, for a period of 365 consecutive days where there is an intent demonstrated by the property owner to abandon the nonconforming use by action consistent with §122-204(5) or 122-205(5).

Accessory dwelling unit means Living or sleeping quarters, temporary or permanent, in an accessory building. Accessory dwelling units are prohibited in travel trailers, motor homes or other recreation vehicle, auto chassis, boat or portable building.

Accessory use, building or structure means a use, building, or structure which is clearly incidental to, customarily found in connection with, subordinate to, and is located on the same zoning lot as the principal use or structure to which it is exclusively related.

Adjacent. See "Lot, adjacent."

Administrative officer means an employee of the City who is charged with administering a department or major function of the city, such as City Manager, City Clerk, City Treasurer, City Assessor, Police Chief, Fire Chief, City Planner, Community and Economic Development Director, Building Inspection Supervisor.

Adult drop-in center means a facility offering counseling, recreation, supervision, education or a place to pass the day to physically, mentally, or emotionally impaired adult individuals who may stop at any time and stay an unspecified period of time during its business hours.

Adult foster care facility. A governmental or nongovernmental establishment having as its principle function the receiving of adults, 18 years of age or older, for foster care in accordance with Act No. 218 of the Public Acts of Michigan of 1979, and the adult foster care administrative

rules as administered by the state department of social services. It includes facilities and foster care family homes for adults who are aged, emotionally disturbed, developmentally disabled, or physically handicapped who require continuous supervision on an ongoing basis but who do not require continuous nursing care. The following four types of adult foster care homes are provided for by these rules:

- (1) *Adult foster care family home.* A private residence with the approved capacity to receive not more than six adults who shall be provided foster care for five or more days a week and for two or more consecutive weeks. The adult foster care family home licensee shall be a member of the household and an occupant of the residence.
- (2) *Adult foster care small group home.* An adult foster care facility with the approved capacity of not more than 12 adults who shall be provided foster care. Conformance to local zoning is required only if seven or more residents will live in the home.
- (3) *Adult foster care large group home.* An adult foster care facility with the approved capacity to receive at least 13 but not more than 20 adults who shall be provided foster care. Conformance to local zoning is required.
- (4) *Adult foster care congregate facility.* An adult foster care facility with the approved capacity to receive more than 20 adults who shall be provided foster care. Conformance to local zoning is required.

Adult regulated uses. The following definitions shall apply to adult uses as regulated in section 122-774:

- (1) *Adult book or supply store* means an establishment having 20 percent or more of its stock in trade or its sales devoted to the distribution, display, or storage of books, magazines, and other periodicals and/or photographs, drawings, slides, films, video tapes, recording tapes, and/or novelty items which are distinguished or characterized by their emphasis on matters depicting, describing, or relating to specified sexual activities or specified anatomical areas. Such establishment or the segment or section devoted to the sale or display of such material in an establishment is customarily not open to the public generally but only to one or more classes of the public, excluding any minor by reason of age.
- (2) *Adult mini-motion picture theater* means an enclosed building with a capacity for less than 50 persons used for presenting material

distinguished or characterized by an emphasis on matter depicting, describing or relating to specified sexual activities or specified anatomical areas, for observation by patrons therein. Such establishment is customarily not open to the public generally, but only to one or more classes of the public, excluding any minor by reason of age.

- (3) *Adult motel/hotel* means a building in which lodging is provided or offered to the public for compensation and which is open to transient guests where the room charge is made by the hour, and/or in which books, magazines and other periodicals or materials which are distinguished or characterized by their emphasis on matter depicting, describing or relating to specified sexual activities or specified anatomical areas, may be sold or rented, or where motion pictures or video tapes with an emphasis on specified sexual activities or specified anatomical areas are available for viewing on an in-room viewing screen or television monitor.
- (4) *Adult motion picture theater or adult live stage performing theater* means an enclosed building with a capacity of 50 or more persons used for presenting material distinguished or characterized by an emphasis on matter depicting, describing or relating to specified sexual activities or specified anatomical areas for observation by patrons therein. Such establishment is customarily not open to the public generally, but only to one or more classes of the public, excluding any minor by reason of age.
- (5) *Cabaret* means an establishment which features any of the following: topless dancers and/or bottomless dancers, strippers, or topless and/or bottomless waitpersons or employees or any other form of nude or partially nude service or entertainment.
- (6) *Massage parlor or massage establishment* means a place where manipulated massage or manipulated exercises are practiced for pay upon the human body by anyone using mechanical, therapeutic, or bathing devices or techniques, other than the following: a duly licensed massage therapist, physician, osteopath, or chiropractor; a registered or practical nurse operating under a physician's directions; or, registered physical or occupational therapists or speech pathologists who treat patients referred by a licensed physician and operate only under such physician's direction. A massage establishment may include, but is not limited to, establishments commonly known as massage

parlors, health spas, sauna baths, turkish bathhouses, and steam baths. Massage establishments shall not include properly-licensed hospitals, offices of a duly licensed massage therapist, medical clinics, or nursing homes, or beauty salons or barbershops in which massages are administered only to the scalp, the face, the neck or the shoulders; or other establishments that offer massages performed by a duly licensed massage therapist.

- (7) *Specified anatomical areas* means portions of the human body defined as follows:
 - a. Less than completely and opaquely covered human genitals, pubic region, buttocks, or female breast below the point immediately above the top of the areola; and
 - b. Human male genitals in a discernibly turgid state, even if completely and opaquely covered.
- (8) *Specified sexual activities* means the explicit display of one or more of the following:
 - a. Human genitals in a state of sexual stimulation or arousal.
 - b. Acts of human masturbation, sexual intercourse, or sodomy.
 - c. Fondling or other erotic touching of human genitals, pubic region, buttocks, or female breast.

Alley means a public right-of-way which affords only a secondary means of access to abutting property and not intended for general traffic circulation.

Alteration means any change, addition or modification in construction or type of occupancy; any change in the structural members of a building, such as walls, partitions, stairways, columns, beams, girders; any change in the width or number of exits; any substantial changes in the roof or exterior walls; any change in the location of a building; any change in the number of off-street parking spaces or loading areas or means of egress and ingress to the site; or any change which may be referred to as "altered" or "reconstructed" or "change of use."

Alternative paving means alternatives to traditional impervious asphalt or concrete paving techniques that save energy, decrease the heat island effect, and/or increase stormwater infiltration. This includes pervious paving and pavers and geogrid installations, but does not include loose gravel.

Antenna means the arrangement of wires or metal rods used in the sending and receiving of electromagnetic waves.

Antenna support structure means any mast, pole, tripod, tower, or similar structure used to support an antenna.

Antenna system means the combination of an antenna and antenna support structure.

Arts and crafts studios means facilities that are used as work space for an artist or crafter or an instruction place for the study of an art or craft. Arts uses shall include, but are not limited to, the fine arts such as music, dance, film (except for adult regulated uses), and photography. Craft uses include the handmade production of articles other than food, such as pottery, glass items, neon sculpture, jewelry, silk screening, needle work, stone and wood work, metalworking or casting, and similar items.

Auction house means a permanent facility where items of merchandise are sold and physically conveyed to the highest bidder in an enclosed facility. This does not include on-line auction activities or temporary auctions.

Automobile means, unless specifically indicated otherwise, any vehicle including cars, trucks, pickups, vans, commercial vehicles, motorcycles, and the like.

Automobile repair means repair of automobiles including engine tune-ups and servicing of brakes, air conditioning, exhaust systems; oil change or lubrication; wheel alignment or balancing; or similar servicing, engine and transmission rebuilding, reconditioning or general repairs; collision service such as body, frame or fender straightening or repair; steam cleaning, undercoating and rustproofing; painting and similar exterior detailing; machining; and similar servicing, rebuilding or repairs.

Automobile filling station means any building, structure or land used for the retail sale of fuels, lubricants, and automobile accessories and the making of minor repairs to vehicles or parts thereof totally enclosed within a building. An automobile filling station shall not include engine and transmission rebuilding, reconditioning or general repairs; collision service such as body, frame or fender straightening or repair; steam cleaning, undercoating and rustproofing; painting and similar exterior detailing; machining; and similar servicing, rebuilding or repairs that normally require significant disassembly or storing the automobiles on the premises overnight.

Automobile Share Organization means a membership-based car-share service to the public and manages, maintains and insures motor vehicles for shared use 24-hours a day by individual and group members. This definition does not include

automobile rental services where vehicles are leased by the day and vehicles are stored, washed and/or repaired in the same facility.

Automobile Share Parking means a parking space or spaces which it is located and dedicated for use by any automobile share organization through a deed restriction, condition of City approval, or license agreement.

Automobile or car wash means any building or premises or portions thereof used for washing and/or detailing automobiles and includes automatic, self-service and hand wash facilities.

Awning means a structure generally constructed so as to shade a window or door opening on a building, which is made of nonrigid materials stretched over a frame attached to a building and which may or may not be constructed so as to be raised or retracted to a position against the building when not in use.

Bar/lounge means an establishment which is operated primarily for the dispensing of alcoholic beverages, although the sale of prepared food or snacks may also be permitted. If an establishment includes a bar or lounge and a separate dining facility, the establishment shall be considered a bar/lounge if more than 50 percent of the usable floor area of the entire establishment is used for the bar/lounge. Brewpubs, as defined and licensed by the State of Michigan, shall be considered a bar/lounge.

Base flood means the flood having a one percent probability of being equaled or exceeded in any given year as determined by the Federal Insurance Administration and/or the U.S. Army Corps of Engineers; also referred to as the 100-year flood.

Base flood elevation means the height of the base flood in relation to the National Geodetic Vertical Datum of 1929.

Basement means that portion of a building wholly or partly below grade. Except that a basement shall be considered a story above grade where the finished surface of the floor above the basement is:

- (1) More than six feet (1,829 mm) above grade plane;
- (2) More than six feet (1,829 mm) above the finished ground level for more than 50 percent of the total building perimeter; or
- (3) More than 12 feet (3,658 mm) above the finished ground level at any point. (Refer to Figure 1.)

Bed and breakfast lodging means a structure which was constructed for and is used for single-family

residential purposes occupied by the owner but which may have as an accessory use a temporary lodging for travelers/guests where bedrooms are rented on a nightly basis with breakfast included in the price of the room, subject to the limitations outlined in this chapter.

Bedroom means any private room in a dwelling unit suitable for regular use for sleeping purposes, as defined in the housing code. Bedrooms can include rooms designated on development floor plans as dens, studies, or libraries but not living rooms, family rooms, dining rooms, kitchens, bathrooms, laundry rooms, and mud rooms. Any room designated as other than a bedroom but which in the judgment of the City Planner and the Building Official or Planning Commission could normally be usable for sleeping purposes shall be considered a bedroom. Any bedroom designed for occupation shall have minimum space requirements as established by the City Housing Code for existing structures or as established by the building code adopted by the this Code for new construction, additions or repairs.

Berm means a continuous, raised earthen mound with a flattened top and sloped sides, capable of supporting live landscaping materials, and with a height and width that complies with the requirements of this chapter.

Board of appeals means the zoning board of appeals of the city, created pursuant to the provisions of Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.), as amended.

Boardinghouse. See "Roominghouse."

BOCA Code means codes currently adopted by the City which are promulgated by the Building Officials and Code Administrators International, Incorporated.

Body art facility means any location that provides, as a principle function, tattooing, branding, body-piercing, or similar body modification for a non-medical purpose. Body art facilities shall be regulated as required by State of Michigan Act 149 of the Public Acts of 2007, as amended, and shall comply with all inspections, licensing, and other procedures required by that act or by regulations established by Washtenaw County.

Brewer/distiller/wine maker means a facility in which beer, wine or other alcoholic beverages are brewed, fermented, or distilled and then packaged and stored for distribution and, if allowed by licenses and zoning, consumption; and for possesses the appropriate license(s) from the State of Michigan and the federal government. Accessory uses to the facility, if allowed by the state license, such as direct to consumer sales,

tasting rooms and restaurants are regulated by zoning district.

Building means any temporary or permanent structure, having a roof or other covering, used or built for the support, enclosure, shelter, or protection of persons, animals, chattel or property of any kind, designed primarily for shelter rather than as a means of conveyance. A building shall not include such structures as signs, fences or smokestacks.

Building code means chapter 18, Article III of this Code.

Building, completely enclosed means a building separated on all sides from the adjacent open space or from other building or structures by a permanent roof and exterior walls having only window and normal entrance or exit doors.

Building height means the vertical distance from the established grade of the center of the front of the building to the highest point of the roof surface of a flat roof; to the deck line of mansard roof; to the mean height level between the eaves and ridge for a hip, gambrel or gabled roof; and 75 percent of the height of "A" frame. (Refer to Figure 3.) Chimneys, spires, antenna, and similar projections other than signs shall not be included in calculating building height.

Building line means a line parallel to the front lot line that separates all parts of a building from the open spaces adjacent thereto on the same lot. (Refer to Figure 4.) For the purposes of this chapter, a minimum building line is the same as a required front yard setback line.

Building, principal means a building or group of buildings in which is conducted the main or principal use of the lot on which the building is situated. See "Accessory use, building, or structure" and "Use, principal."

Building, temporary means a building which is not permanently affixed to the property, and is permitted to exist for a specific reason for a specific period of time. An example of temporary building is a trailer used on a construction site.

Bulk means a composite characteristic of a given building as located upon a given lot; not definable as a single quantity, but involving all of the following characteristics:

- (1) Size and height of the building;
- (2) Location of exterior walls at all levels in relation to lot lines, streets, or to other buildings;

- (3) Gross floor area of the building in relation to lot area;
- (4) All open spaces allocated to the building; and
- (5) Amount of lot area provided per dwelling unit.

Canopy means a roof-like structure, other than an awning, made of rigid and durable materials with frames attached to and made a part of the building and further supported by a frame to the ground or sidewalk; or in the case of an automobile filling station or automobile repair garage that sells fuels, a canopy is a roof-like structure that is supported mainly by vertical support beams and not walls, it may or may not be attached to the principal building, and is designed to shelter the fuel pumps.

Carport means a structure consisting of a roof supported by posts which is otherwise open to the elements on at least three sides, which is mainly used for storage of automobiles.

Change of Use constitutes the conversion of an existing structure from one permitted use to another. Such a change may not include exterior building alterations, but due to a use intensity, requires additional off-street parking and modification to interior circulation or landscaping.

Child care means the following:

- (1) *Family day care home* means a private home, licensed by the state, in which one but less than seven minor children are received for care and supervision for periods of less than 24 hours a day, unattended by a parent or legal guardian, except children related to an adult member of the family by blood, marriage, or adoption. Family day care home includes a home that gives care to an unrelated minor child for more than four weeks during a calendar year.
- (2) *Group day care home* means a private home, licensed by the state, in which more than six but not more than 12 minor children are given care and supervision for periods of less than 24 hours a day unattended by a parent or legal guardian, except children related to an adult member of the family by blood, marriage or adoption. Group day care home includes a home that gives care to an unrelated minor child for more than four weeks during a calendar year.

Child care center or day care center means a commercial facility, licensed by the state, receiving one or more children for care for periods of less than 24 hours a day, and where the parents or guardians are not immediately available to the child. Child

care center or day care center includes a facility which provides care for not less than two consecutive weeks, regardless of the number of hours of care per day. The facility is generally described as a child care center, day care center, day nursery, nursery school, parent cooperative preschool, play group, or drop-in center. Child care center or day care center does not include a Sunday school, a vacation Bible school, or a religious instructional class that is conducted by a religious organization where children are in attendance for not more than three hours per day for an indefinite period or not more than eight hours per day for a period not to exceed four weeks during a 12-month period, or a facility operated by a religious organization where children are cared for not more than three hours while persons responsible for the children are attending religious services. **State law reference(s)**--Child care organizations, defined, MCL 722.111, MSA 25.358(11).

Cisterns means storage containers that capture a larger volume of runoff stormwater than a rain barrel.

City means the City of Ypsilanti, Washtenaw County, Michigan.

City Council means the City Council of Ypsilanti, Washtenaw County, Michigan.

Club or lodge, private means a nonprofit association of persons who are bona fide dues paying members which owns or leases premises, the use of which is restricted to members and their guests. The facilities owned or used by such organization may be referred to as a "club" or "lodge" in this chapter.

Coin-operated amusement device means any mechanical or electrical device which provides amusement or entertainment which may be operated or set in motion upon the insertion of a coin or token, or payment of a fee. This definition shall not include juke boxes, music machines, telephone devices, machines which dispense merchandise or machines or devices that provide film or video tape presentations to a customer/user who is merely a passive spectator of such presentation. This exclusion shall not be deemed to exclude any machines or devices in which the customer/user is engaged in a form of competition against the machine or another customer/user.

Commercial vehicle means a truck or motor vehicle with cab and chassis and with a stake, rack, body, dump body, wrecker body, tanker body or any other body, the mounted height of which exceeds the height of the cab roof more than eight inches. Any truck or motor vehicle which has a commercial license plate and is designed to accommodate a body length in excess of nine feet. Commercial vehicles shall not include motor

homes or recreational vehicles, but shall include construction equipment such as backhoes, power shovels, bulldozers, earth moving equipment, semi trucks, tractors and trailers.

Commission means the Planning Commission of the City of Ypsilanti, Michigan.

Communication device means an apparatus such as an antenna system or satellite dish stations of which the principal function is to send or receive television, radio, or data microwave signals.

Condominium means ownership in common with others of a parcel of land and certain parts of a building thereon which would normally be used by all of the occupants, such as yards, foundations, basements, floors, walls, hallways, stairways, elevators and all other related common elements, together with individual ownership in fee of a particular dwelling unit in such building. Condominiums shall be subject to the regulations set forth in Act No. 59 of the Public Acts of Michigan of 1978 (MCL 559.101 et seq., MSA 26.50(101) et seq.), as amended.

Cooperative housing means a multiple dwelling owned by a corporation which leases its units to stockholders/shareholders on a proprietary lease arrangement.

Correctional facility means a place of confinement for persons who have broken the law, are awaiting trial, and/or have been convicted of criminal offenses.

Curb cut means the entrance to or exit from a property provided for vehicular traffic to or from a public or private thoroughfare.

Craft Manufacturing means establishments manufacturing and/or assembling products primarily by hand or with hand tools and/or domestic mechanical equipment. Items produced may include, but are not limited to, custom furniture and woodworking, ceramics and glass, items intended for consumption, personal care products, candle making, jewelry making, custom textile manufacturing and crafts production.

Department of community and economic development means the city department which reviews site plans, variance applications, proposed planned unit developments, and other applications associated with this chapter in order to provide information and recommendations that will assist the Planning Commission and zoning board of appeals in their determinations.

District means a portion of the city within which, on a uniform basis, certain uses of land and/or buildings are permitted and within which certain regulations and requirements apply under the provisions of this chapter, such as building type,

building height, building setback, and intensity of use.

Dormitory means those facilities used for housing students, which are owned and controlled by an educational institution and which are to be distinguished from hotels, motels, and boardinghouses. The terms "dormitory" and "residence hall" are to be used synonymously.

Drive-through service means a business activity so developed that its retail or service character provides a driveway approach and waiting spaces for motor vehicles so as to serve patrons while seated in their motor vehicle. An automatic teller machine or similar device shall not be included in this definition, provided that the device is not staffed and does not use any type of amplification device.

Dwelling means a building or portion thereof, containing sleeping, kitchen, and bathroom facilities designed for and occupied by one family, excluding hotels, motels, and inns. In no case shall a travel trailer, motor home, automobile, tent, or other portable building defined as a recreational vehicle be considered a dwelling. In the case of mixed occupancy where a building is occupied in part as a dwelling unit, the part so occupied shall be deemed a dwelling unit for the purposes of this chapter.

Dwelling, manufactured (also known as a "mobile home") means a vehicular, portable structure built on a chassis and designed to be used without a permanent foundation as a dwelling when connected to required utilities and which is, or is intended to be, attached to the ground, to another structure, or to a utility system on the same premises for more than 30 consecutive days. The unit shall be labeled as prescribed under the provisions of the Mobile Homes Construction Safety Standards as promulgated by the United States Department of Housing and Urban Development being 24 CFR 3280. Recreational vehicles as described and regulated shall not be considered "mobile homes" for the purpose of this chapter. Also refer to "Dwelling, one-family or single-family."

Dwelling, premanufactured means an assembly of materials or products intended to comprise all or part of a building or structure, and that is assembled, at other than the final location of the unit of the building or structure, by a repetitive process under circumstances intended to ensure uniformity of quality and material content. The unit shall be labeled as prescribed in R408.31137 of the Michigan Department of Labor, Construction Code Commission Administrative

Rules Part 11. See also "Dwelling, one-family or single-family."

Dwelling, multiple means a building designed for and occupied by three or more families living independently with separate housekeeping, cooking, and bathroom facilities for each. Multiple dwelling units include the following:

- (1) *Apartment*. An apartment is an attached dwelling unit with party walls, contained in a building with other apartment units which are reached from a common stair landing or walkway, or are accessed directly from the outside.
- (2) *Efficiency unit or studio apartment*. An efficiency unit or studio apartment is a type of multiple-family or apartment unit consisting of one principal room with sleeping facilities, plus bathroom and kitchen facilities, hallways, closets, and/or a dining alcove located directly off the principal room. Sleeping facilities may also be separated from the principal living space by dividers or lofts.

Dwelling, one-family or single-family means a detached building containing not more than one dwelling unit designed for residential use.

Dwelling, two-family or duplex means a detached building, designed exclusively to be occupied by two families living independently of each other, with separate housekeeping, cooking, and bathroom facilities for each.

Dwelling unit, single-family attached or townhouse means an attached single-family dwelling unit with party walls, designed as part of a series of three or more dwellings, with its own front door which opens to the outdoors at front level, and typically with its own basement utility connections, and front and rear yards. A townhouse may be located on its own lot, or may be located on land commonly owned by a condominium association or similar association. Townhouses are also commonly known as rowhouses.

Easement means a grant of one or more of the property rights by the property owner to and/or for the use by the public, a corporation, or another person or entity. The term "easement" often applies to public or private rights-of-way and to "utility easements" which give utility companies the right to use land for the construction and maintenance of utilities.

Encroachment means any construction, structure, filling grading, or deposition of materials in, upon, across or projecting into a floodplain, channel, or floodway.

Erected means built, constructed, reconstructed, moved upon, or any physical operations on land required for the building. Excavations, fill, drainage, and installation of utilities shall be considered part of erected.

Essential services means the erection, construction, alteration, or maintenance by public utilities or municipal departments or city licensed cable television companies or underground, surface, or overhead gas, steam, electrical, fuel or water systems for the purposes of transmission, distribution, collection, communication, supply or disposal; including towers, poles, boxes, wires, mains, drains, sewers, pipes, conduits, cables, fire alarm and police call boxes, traffic signals, hydrants, and similar equipment, which are necessary for the furnishing of adequate service by such utilities or municipal departments for the general health, safety, and welfare of the public. The location, size, and intensity of essential services shall be regulated by the standards of this chapter. Essential services shall also not include communication providers when there is more than one entity servicing a geographic area and which are not regulated by the state public service commission.

Excavation means the removal or movement of soil, sand, stone, gravel, or fill dirt, except for common household gardening, farming, and general ground care.

Family means:

- (1) One individual;
- (2) A group of two or more persons related by blood, marriage or adoption, together with foster children; together with:
 - a. No more than two domestic workers of the principal occupants;
 - b. No more than two additional unrelated persons occupying the unit as boarders, roomers, or guests;

All of whom are domiciled together as a common, domestic, household in a single dwelling unit;

- (3) A group of persons, none of whom are related to each other by blood, marriage, or adoption, who reside together in a single dwelling unit, provided that the total number of occupants in such group shall not exceed three, except in the MD district and in any permitted residential uses in any corridor district the total number of occupants in this group shall not exceed four, unless otherwise provided for in this chapter; or

- (4) A collective number of individuals living together in one dwelling unit, whose relationship is of a continuing, nontransient, domestic character, and who are cooking and living as a single, nonprofit housekeeping unit. This definition shall not include any society, club, fraternity, sorority, association, lodge, coterie, organization, or group of students or other individuals whose domestic relationship is of a transitory or seasonal nature or for an anticipated limited duration of a school term or terms or other similar determinable period.

Family day care home. See “Child Care.”

Farmers’ market means an indoor or outdoor market open to the public offering for sale at retail vegetables, produce, other farm products, and value-added food products, occurring in a pre-designated area, where the vendors are individuals who have grown or produced the food products or have taken the same on consignment for retail sale.

FBFM means the flood boundary and floodway map, used as a floodplain management map that depicts, based on detailed analyses, the boundaries of the 100-year and SOO-year floods and the 100-year floodway. For the purposes of this chapter, the FBFM is the map titled Flood Insurance Rate Map(s) (FIRMS) Washtenaw County (All Jurisdictions) panel number(s) of 26161C; 00269E, 0288E, 0407E, and 0426E dated 4/3/12.

Fence means a permanent or temporary unroofed barrier enclosing or bordering a plot of land or portion thereof composed of wood, shrubs or suitable manmade materials for the purpose of preventing or controlling entrance, confining within, screening, or marking a boundary.

Fill means the deposit or dumping of any matter onto or into the ground, except for common household gardening, farming, and general ground care.

FIRM means the flood insurance rate map titled Flood Insurance Rate Map(s) (FIRMS) Washtenaw County (All Jurisdictions) panel number(s) of 26161C; 00269E, 0288E, 0407E, and 0426E dated 4/3/12.

Flood means a temporary increase in the stage of a river or stream resulting in the inundation of lands not normally covered by water.

Flood insurance study means the engineering study performed by FEMA to identify flood-prone areas, insurance risk zones, and other flood data and contained in a document titled, Flood Insurance Study, Washtenaw County (All

Jurisdictions) Community Number 260216, dated April 3, 2012.

Floodplain means that area of land adjoining a river or stream which will be inundated by a 100-year flood.

Floodway means the channel of a river, stream, creek, or other watercourse and the adjacent land areas that must be reserved in order to discharge the base flood without cumulatively increasing the water surface elevation more than one foot. In the city, the floodway includes the Huron River and Paint Creek along with the adjoining land, as shown on the Federal Emergency Management Agency insurance maps.

Floor area, gross means the total area of a building measured by taking the outside dimensions of the building at each floor level intended for occupancy or storage, not including any uncovered or unenclosed porches, patios, or decks.

Floor area, usable nonresidential means the sum of the horizontal areas of each floor, measured from the interior faces of the exterior walls, including all areas used for, intended to be used for, and accessible for the sale of merchandise, provision of services, or service to patrons, clients or customers. Floor area which is used for or intended to be used for the storage or processing of merchandise, or for utilities shall be excluded from the computations of usable nonresidential floor area. If precise floor plans are not available for calculations, usable nonresidential floor area shall be 80 percent of gross nonresidential floor area.

Floor area, usable residential means the gross floor area minus area in basements, unfinished attics, attic floor area with less than five feet vertical distance from floor to finished ceiling, attached garages, uncovered or enclosed porches, patios, terraces, carports, breezeways, decks, or verandas.

Foster family home. A private residence, licensed by the state, that houses four or fewer foster children, up to age 19, under constant child care and supervision. Under Act No. 116 of the Public Acts of Michigan of 1973 (MCL 722.111 et seq., MSA 25.358(11) et seq.), a foster family home does not require local zoning approval before being licensed by the state department of social services.

Foster family group home. A private residence, licensed by the state, that houses five or six foster children, up to age 19, under constant care and supervision. Under Act No. 116 of the Public Acts of Michigan of 1973 (MCL 722.111 et seq., MSA 25.358(11) et seq.), a foster family group home shall be considered a residential use of property

for the purposes of zoning and permitted use in all residential zones and is not subject to a special use permit or procedure different from those required for other dwellings of similar density in the same zone.

Fraternity or sorority house means a building, rented, occupied or owned by a national or local chapter of some regularly organized college fraternity or sorority which is officially recognized by a college or university, or by or on its behalf by a building corporation or association composed of members of such fraternity or sorority, as a place of residence.

Garage means an accessory building or portion of a principal building used or designed to be used primarily for the storage of motor vehicles, boats, or trailers owned and used by the occupants of the building to which it is accessory. Private garages shall not have public repair facilities.

Garden/Community Garden means land used to grow and harvest food or non-food crops for personal or group use. The products of gardens/community gardens may or may not be for commercial purposes.

Gas station. See "Automobile service station/automobile filling station."

Geothermal Energy means power extracted from heat stored in the earth. Geothermal resources include: all products of geothermal processes embracing indigenous steam, hot water and hot brines; steam and other gases, hot water and brines resulting from water, other fluids or gas artificially introduced into geothermal formations; heat or other associated energy found in geothermal formations, including any artificial stimulation or induction thereof; and, any mineral or minerals, exclusive of fossil fuels and helium gas, which may be present in solution or in association with geothermal steam, water or brines.

Grade means the average level of the finished surface of the ground adjacent to the exterior walls of the building or structure.

Greenbelt means a strip of land of definite width and location reserved for the planting of a combination of shrubs, trees, and ground cover to serve as an obscuring screen or buffer for noise or visual enhancement, in accordance with the requirements of this chapter.

Greenhouse, commercial means a space, building, structure, or combination thereof, where live trees, shrubs, and other plants used in gardening and landscaping are propagated, stored, and/or offered for sale on the premises. If business is conducted primarily outdoors, see "Open air business."

Group residence means a building used as a residence by a group of persons who are not a family on a weekly or longer basis. Typical uses include cooperatives, sororities and fraternities. This definition does not include boarding houses, rooming houses or other group living more specifically defined in this Chapter, specifically any group living or care facility licensed by the State of Michigan.

Ground cover means low-growing plants that form a dense, extensive growth after one complete growing season, and tend to prevent weeds and soil erosion.

Hedge means a row of closely planted shrubs or low-growing trees which form a continuous visual screen, boundary, or fence.

Home occupation means an occupation or profession carried on by a member or members of the immediate family residing on the premises which use is clearly incidental and secondary to the use of the dwelling for dwelling purposes; does not change the character thereof; which does not endanger the health, safety, and welfare of any other persons residing in that area by reason of noise, noxious odors, unsanitary or unsightly conditions, fire hazards and the like; and which meets the requirements of section 122-669

Homeless Shelter means a facility which provides congregate style temporary lodging with or without meals and supportive services on the premises to primarily the homeless for more than four (4) weeks in any calendar year. A shelter does not provide such lodging to any individual (1) who is required because of age, mental disability or other reason to reside either in a public or private institution or (2) who is imprisoned or otherwise detained pursuant to either federal or state law. A shelter for the homeless shall be considered a different land use than adult foster care facilities, supportive housing, nursing homes, temporary emergency shelters, or warming centers.

Hospital means an institution which is licensed by the state department of health to provide in-patient and out-patient medical and major surgical services for the sick and injured, and which may include such related facilities as laboratories, medical testing services, central service facilities, and staff offices.

Hotel or motel means a building in which lodging is provided and offered to the public for compensation, which is open to transient guests generally on a per-day basis and not for long-term lodging, in distinction from a roominghouse, bed and breakfast lodging, or inn. Hotels or motels customarily provide services such as desk service,

maid service, laundering of linens, the use of furniture, etc. No kitchen or cooking facilities are to be provided, with the exception of units for use of the manager or caretaker; unless approved by the Planning Commission as a special use.

Housing code means Article V of chapter 18, as amended.

Ingress and egress means, and is generally used in reference to a driveway which allows vehicles to enter or leave a parcel of property, or to a sidewalk or entranceway which allows pedestrians to enter or leave a parcel of property, a building, or another location.

Indoor recreation means recreation uses occurring entirely inside a building including bowling alleys, gymnasiums or court sports facilities, tennis clubs, roller or ice skating rinks, recreation centers, personal fitness centers, and similar recreation use.

Inn means a structure, originally constructed for residential purposes and used as temporary lodging for travelers and guests where bedrooms are rented on a nightly basis and managed either by an owner/occupant or resident manager.

Junk means any motor vehicles, machinery, appliances, products or merchandise with parts missing, or other scrap materials that are damaged, deteriorated, or are in a condition which prevents their use for the purpose for which the product was manufactured.

Junkyard means an area where waste and used or secondhand materials are bought and sold, exchanged, stored, baled, packed, disassembled, or handled including, but not limited to: junk, scrap iron, metals, paper, rags, tires, bottles, and automobiles.

Kennel means any lot or premises on which four or more dogs, cats, or other domestic animals six months or older are kept, either permanently or temporarily, either for sale, breeding, boarding, training, hobby, protection, grooming or as pet; and may offer provision for minor medical treatment, including animal shelters.

Laboratory means a place devoted to experimental, routine, or basic study such as testing and analytical operations and in which the manufacturing of products, except prototypes, is not performed.

Landscaping means the treatment of the ground surface with live plant materials such as, but not limited to, grass, ground cover, trees, shrubs, vines, edible plants, and flowers. A landscape design may include other decorative manmade materials such as wood chips, crushed stone,

boulder, raised garden beds, or mulch. Structural features such as fountains, pools, statues, and benches may also be considered a part of landscaping, but only if provided in combination with live plant material. Artificial plant materials shall not be counted towards meeting the requirements for landscaping.

Loading space, off-street means an off-street space of definite size and dimensions in accordance with the requirements of this chapter, which is safely and conveniently located on the same lot as the building or buildings being served, for the temporary parking of delivery vehicles while loading and unloading merchandise and materials.

Lot (or zoning lot or parcel) means a piece of land under one ownership and control that is at least sufficient in size to meet the minimum requirements for use, coverage, area, setbacks, parking, and open space as required by this chapter. A lot shall have frontage on a street. A lot may consist of the following:

- (1) A single lot of record (See "Lot of record").
- (2) A portion of a lot of record.
- (3) A combination of complete lots of record, or portion thereof.
- (4) A piece of land described by metes and bounds.

Lot, abutting means lots which share a common interior lot line and which are not separated by a public or private right-of-way or easement.

Lot, adjacent means lots which adjoin each other or which are separated only by a public or private right-of-way or easement.

Lot, contiguous means lots adjoining each other.

Lot, corner means a lot of which at least two adjacent sides abut their full length upon a street, provided that such two sides intersect at an angle of not more than 135 degrees. Where a lot is on a curve, if the tangents through the extreme point of the street lines of such lot make an interior angle of not more than 135 degrees, it shall be considered a corner lot. In the case of a corner lot with a curved street line, the corner is that point on the street lot line nearest to the point of intersection of the tangents described above. Tangents are straight lines extended from the outer edges of a curve which intersect to form a corner. (Refer to Figure 7.)

Lot, double frontage means a lot other than a corner lot having frontage on two more or less parallel streets. Also called a through lot. In the case of a row of double frontage lots, one street shall be designated as the front street for all lots in the

plat. If there are existing buildings in the same block fronting on one or both of the streets, the required minimum front yard setback shall be observed on the street where buildings presently front.

Lot, interior means a lot other than a corner lot.

Lot area means the total horizontal area within the lot lines of a lot, exclusive of any abutting public street right-of-way or private road easements, or the area of any lake, except that any lot which abuts an alley, may include the area of half the width of such alley where it abuts the lot in determining the total area of that lot.

Lot coverage means the part or percent of the lot that is occupied by buildings or structures.

Lot depth means the horizontal distance between the front and rear lot lines, measured along the midpoint between the side lot lines.

Lot line means any line separating a parcel of land from another. Lot lines are further defined as follows:

- (1) *Front lot line* means, in the case of an interior lot abutting on one public or private street, the line separating the lot from such street right-of-way. In the case of a corner or double frontage lot, the front lot line shall be that line separating such lot from the street which is designated as the front street in the plat and/or in the request for a building permit.
- (2) *Rear lot line* means the lot line which is opposite and most distant from the front lot line. In the case of irregular, triangular, wedge shaped, or lots that are pointed in the rear, the rear lot line shall be an imaginary line parallel to the front lot line, not less than ten feet in length, lying farthest from the front lot line and wholly within the lot.
- (3) *Side lot line* means any lot line other than the front or rear lot lines. A side lot line separating a lot from a street is a street side lot line. A side lot line separating a lot from another lot or lots is an interior side lot line.
- (4) *Interior lot line* means any lot line which does not separate a lot from a street right-of-way. A lot line which separates a lot from an alley right-of-way shall be considered an interior lot line.

Lot of record means a lot or parcel of land, the deed of which has been recorded in the office of the registrar of deeds of the county.

Lot split or consolidation means the dividing or uniting of lots by virtue of changes in the deeds in

the office of the county registrar of deeds and/or the city treasurer.

Lot, through see lot, double-frontage.

Lot width means the straight line distance between the side lot lines, measured at the two points where the minimum front yard setback line intersects the side lot lines.

Massage parlor or massage establishment see “Adult Regulated Uses.”

Massage therapist means an office where massage is performed for financial compensation only by individuals who satisfy the requirements of the Massage Therapy Licensing Act (PA 471 of 2008) as amended.

Master plan means a document which is prepared under the guidance of the city Planning Commission and consists of graphic and written materials which indicate the general location for streets, parks, schools, public buildings, and all physical development of the city. The master plan is intended as a guide for all development within the city, and shall be used to guide the zoning board of appeals and the Planning Commission in all decisions before those bodies. The master plan is to be updated periodically.

Medical or dental clinic means an office of five or more physicians, dentists, massage therapists, or similar professionals or which is staffed on a rotational basis with personnel from an area hospital, where persons are examined or treated on an outpatient basis only, including outpatient surgery.

Medical or dental office means the office of not more than four physicians, dentists, massage therapists, or similar professionals, where persons are examined or treated on an outpatient basis only, including outpatient surgery.

Medical marijuana dispensary means a facility, including a membership club, where primary caregivers who are legally registered by the Michigan Department of Community Health (MDCH) may lawfully assist qualifying patients to whom the primary caregiver is connected through the state registration process and who are also legally registered by the MDCH with the medical use of marijuana in accordance with the Michigan Medical Marijuana Act, as amended. A use which purports to have engaged in the medical use of marijuana either prior to enactment of said Act, or after enactment of said Act but without being legally registered by the MDCH, shall be deemed to not be a legally established use, and therefore not entitled to legal nonconforming status under the provisions of this Ordinance and/or State Law.

(State Law reference(s))--Michigan Medical Marihuana Act, Initiated Law 1 of 2008, MCL §333.264 et seq)

Medical Marijuana Growing/Manufacturing Facility.

A facility for the cultivation and processing of medical marijuana into a usable form by primary caregivers who are legally registered by the Michigan Department of Community Health (MDCH) in accordance with the Michigan Medical Marijuana Act, as amended. A use which purports to have engaged in the cultivation and processing of medical marijuana into a usable form either prior to enactment of said Act, or after enactment of said Act but without being legally registered by the MDCH, shall be deemed to not be a legally established use, and therefore not entitled to legal nonconforming status under the provisions of this Ordinance and/or State Law. A maximum of five (5) primary caregivers may operate at a medical marijuana growing/manufacturing facility, provided all applicable zoning ordinance standards can be met.

(State Law reference(s))--Michigan Medical Marihuana Act, Initiated Law 1 of 2008, MCL §333.264 et seq)

Medical Marijuana Home Occupation means the cultivation of medical marijuana by a registered primary caregiver as defined in Sec. 3 of the Act, MCL §333.26423(g), in compliance with the General Rules of the Michigan Department of Community Health, the Michigan Medical Marijuana Act, Initiated Law 1 of 2008, MCL §333.26423(e), within a single family dwelling that is the registered primary caregiver's primary residence and which cultivation is in conformity with the restrictions and regulations contained in the Act and in the State Regulations developed by the Michigan Department of Community Health (MCDH). Medical Marijuana Home Use does not include any multi-family dwelling.

(State Law reference(s))--Michigan Medical Marihuana Act, Initiated Law 1 of 2008, MCL §333.264 et seq)

Mezzanine means an intermediate level or levels between the floor and ceiling of any story with an aggregate floor area of not more than one-third of the floor area of the story in which the level or levels are located. A mezzanine shall be deemed a full story if the vertical distance from the next floor below the mezzanine to the next floor above is 24 feet or more. (Refer to Figure 2.)

Microbrewer/small distiller/small wine maker means a facility in which a limited amount beer, wine or other alcoholic beverages, defined by the State of Michigan Liquor Control Commission, are brewed, fermented, or distilled and then packaged

and stored for distribution and, if allowed by licenses and zoning, consumption; and possesses the appropriate license(s) from the State of Michigan and the federal government. Accessory uses to the facility, if allowed by the state license, such as direct to consumer sales, tasting rooms and restaurants are regulated by zoning district.

Motel. See "Hotel or motel."

Motor home means a motorized vehicular unit primarily designed for travel and/or recreational usage, which may also contain facilities for overnight lodging. This term does not apply to mobile homes.

Municipality means the city.

Nonconforming lot means a lot which was lawfully in existence at the effective date of the ordinance from which this chapter is derived, or amendments thereto, and which does not now conform to the lot size, lot width, or other provisions of this chapter for the zoning district in which it is located.

Nonconforming structure means a building or structure which was lawful on the effective date of adoption or amendment of this chapter, but which does not conform to the new chapter regulations for lot area, lot area per dwelling unit, lot width, lot coverage, floor area, height, greenbelts or screening, off-street parking, loading space, yard, or other requirements of the zoning district in which it is located.

Nonconforming use means a use which was lawfully in existence at the effective date of the ordinance from which this chapter is derived, or amendment thereto, and which does not now conform to the use regulations of this chapter for the zoning district in which it is now located. A nonconforming use may include a use that requires a Special Use Permit under current regulations contained in this chapter, where under previous regulations a Special Use Permit was not required or granted.

Nuisance means any offensive, annoying, or disturbing practice or object, which prevents the free use of one's property, or which renders its ordinary use or physical occupation uncomfortable. A nuisance commonly involves continuous or recurrent acts which give offense to the senses, violate the laws of decency, obstruct reasonable and comfortable use of property, or endanger life and health.

Nursery, day nursery, or nursery school. See "Child care center."

Nursing home, convalescent home, or rest home means a home for the care of the aged, infirm, or

those suffering from physical or mental disorders, wherein two or more persons are housed or lodged and furnished with nursing care. Such facilities are licensed in accordance with Act No. 368 of the Public Acts of Michigan of 1978 (MCL 333.20101 et seq., MSA 14.15(20101) et seq.), as amended.

Occupancy, change of means an abandonment of an existing use and the substitution of a use of a different kind or class, or the expansion of a use.

Occupied means used in any way at the time in question.

Open air business means any business that is conducted primarily out-of-doors. Unless otherwise specified, open air businesses shall include, but are not limited to:

- (1) Retail sales of garden supplies and equipment, including but not limited to: trees, shrubbery, plants, flowers, seed, topsoil, trellises, and lawn furniture.
- (2) Roadside stands for the sale of agricultural products, including fruits, vegetables, and Christmas trees.
- (3) Outdoor display and sale of model garages, swimming pools, playground equipment, and similar uses.

Open space means that part of a lot, including courts and/or yards, which is open and unobstructed from its lowest level to the sky, and is accessible to all occupants upon the zoning lot.

Ownership, change in means whenever the title to the property is transferred to another person, including purchase by land contract.

Parcel. See "Lot."

Parking garage means a building for the storage only of noncommercial vehicles of occupants in the same block or abutting blocks and providing no service to vehicles stored therein.

Parking lot, community means a parking lot on public or privately-owned property which provides parking with or without compensation for uses located in the general area in which it is situated.

Parking, off-street means an area not located within a public right-of-way which provides vehicular parking spaces along with adequate drives and aisles for maneuvering so as to provide for safe and convenient ingress and egress to the parking area, in accordance with the provisions of Article XIII of this chapter.

Parking space means an area, enclosed or unenclosed, of definite length and width as designated in this chapter, to store one automobile or other vehicle

which is fully accessible by a driveway connecting the parking space with a street, road or alley and permitting ingress and egress of an automobile. The term "parking space" is exclusive of the access drives and aisles thereto.

Party wall means a wall starting from the foundation and extending continuously through all stories to or above the roof that separates one building from another and that is in joint use by each building.

Passive solar structure is a building that collects, stores, and distributes solar energy to grow plants; it does not have a foundation or electrical utilities. It may also be called a hoophouse.

Performance standard means a criteria or limit relating to nuisance elements which a particular use or operation may not exceed. Performance standards are typically established to control noise, odor, smoke, toxic or noxious matter, vibration, fire and explosive hazards, glare, heat, or other effects.

Person means an individual, trustee, executor, fiduciary, corporation, firm, partnership, association, organization, sole proprietor, or other legal entity acting as a unit.

Planned unit development (PUD) means an area of minimum contiguous size, as specified in Article IX of this chapter, to be planned and developed as a single entity containing one or more residential clusters or planned unit residential developments or one or more public, quasi-public, commercial or industrial areas.

Planning Commission means the city Planning Commission, created pursuant to the provision of Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.).

Porous paving means systems that allow water to pass freely through interstitial space ingrained throughout the paving matrix, thereby transforming traditionally impervious surfaces such as pervious concrete and asphalt, interlocking pavers, reinforced gravel and grass paving.

Principal use. See "Use, principal."

Private street or road. See "Street."

Public utility means any persons, firm, corporation, municipal department, or board, duly authorized through government rate regulation (such as by the state public utilities commission or the city) to furnish to the public under government regulations any of the following: electricity, gas, steam, communications services, cable television services, transportation services, water, sewer service, or sewage treatment.

Premises means a lot or property together with all buildings or structures thereon.

Rain-gardens mean landscaped depressions that can be built to any size or shape. Also known as ‘bio-retention cells’, they are designed to allow water to settle and infiltrate into the soil.

Recreational vehicle means a boat, snowmobile, off-road vehicle, camper travel trailer, motor home, pick-up camper, trailer which is designed for private recreational or recreational travel use. Any trailer which is principally used for transporting any of the above shall also be considered a recreational vehicle.

Recycling center means an enclosed area or storage facility where area residents can drop off recyclable household wastes such as newspapers, cans, bottles, plastics, and cardboard which may be sorted and stored for short periods of time on the site until hauled away to another location for processing, reuse, or safe disposal.

Religious Institution means any structure wherein persons regularly assemble for religious activity or worship, including such uses normally accessory thereto, such as a fellowship hall, Sunday School classrooms, parsonages or rectories, and offices. Where a group of persons, who are affiliated with a religious organization, reside together within a dwelling which is the principal building on a site, such dwelling shall not be considered a religious institution.

Refuse means the miscellaneous waste materials resulting from housekeeping, mercantile enterprises, trades, manufacturing and office, including other waste matter such as slag, stone, broken concrete, fly ash, sashes, tin cans, glass, scrap metal, rubber, paper, rags, chemicals, or any similar or related combinations thereof.

Research use means facilities for scientific research, and the design, development and testing of electrical, electronic, magnetic, optical and computer and telecommunications components in advance of product manufacturing, and the assembly of related products from parts produced offsite, where the manufacturing activity is secondary to the research and development activities, and includes pharmaceutical, chemical, and biotechnology research and development.

Restaurant means any establishment whose principal business is the sale of food and beverages to the customer in a ready-to-consume state, and whose method of operation is characteristic of a carry-out, drive-in, drive-through, fast food, or sit-down restaurant, as defined below. Any restaurant which combines elements of two or more of the following types of restaurants shall be subject to

the regulations of the most restrictive restaurant type employed:

- (1) *Restaurant, carry-out.* A restaurant whose method of operation involves the sale of food, beverages, and/or frozen desserts in disposable or edible containers or wrappers in a ready-to-consume state for consumption off the premises, typically from a counter or window inside the building. Indoor seating for consumption on the premises is not permitted.
- (2) *Restaurant, drive-in.* A restaurant whose method of operation involves delivery of prepared food so as to allow its consumption in a motor vehicle or elsewhere on the premises, but outside of an enclosed building.
- (3) *Restaurant, drive-through.* A restaurant whose method of operation involves the delivery of the prepared food to the customer in a motor vehicle, typically through a drive-through window, for consumption off the premises. Indoor seating for consumption on the premises is not permitted.
- (4) *Restaurant, fast food.* A restaurant whose method of operation involves minimum waiting for delivery of ready-to-consume food to the customer at a counter for consumption at tables, booths, or stands inside the structure or out, or for consumption off the premises, but not in a motor vehicle at the site.
- (5) *Restaurant, sit-down.* A restaurant whose method of operation involves either:
 - a. The delivery of prepared food by servers (waitpersons) to customers seated at tables within a completely enclosed building; or
 - b. The prepared food is acquired by customers at a cafeteria line or ordering counter and is subsequently consumed by the customers at tables within a completely enclosed building.

Right-of-way means a right-of-way dedicated to or owned by a public body and available for use by the general public. In the case of public streets, the right-of-way often includes curbs, lawn strips (also referred to as the margin or parkway), sidewalks, and lighting and drainage facilities.

Room, is for the purpose of determining lot area requirements, and density in a multi-family district, means a living room, dining room, or bedroom, and any other room equal to at least eighty (80) square feet in area. A room shall not

include the area in kitchen, sanitary facilities, utility provisions, corridors, hallways and storage.

Roominghouse means a building, other than a hotel or motel, bed and breakfast lodging, or inn, where for compensation or by prearrangement for definite periods of time, lodging or lodging and meals are provided for three or more unrelated persons, not living as group or household. The term "unit" as it refers to a roominghouse shall mean sleeping room, or a room which may be used as a sleeping room. (See "Sleeping room.") A boardinghouse or lodgishouse shall be deemed a roominghouse for the purposes of this chapter.

Satellite antenna means an accessory structure which at its widest dimension is in excess of 36 inches, capable of receiving signals from orbiting satellites and other extraterrestrial sources, together with other equipment related to such purposes.

Screen or screening means a wall, non-wire fence, or combination of plantings of sufficient height, length, and opacity to form a visual barrier

Self-storage facility means a building or group of buildings in a controlled access compound that contains individual compartmentalized and controlled access stalls or lockers of no more than 500 square feet each for the dead storage of customers' goods or wares in enclosed buildings.

Setback means the distance between a front, side, or rear lot line and the nearest supporting member of a structure on the lot. The "minimum required setback" is the minimum distance between a front, side, or rear lot line and the nearest supporting member of a structure (including, but not limited to, the foundation, bay windows or similar architectural features at the ground floor level supported by the building or the ground, and porches which are enclosed) in order to conform to the required yard setback provisions of this chapter.

Shrub means a self-supporting, deciduous or evergreen woody plant, normally branched near the base, bushy, and less than 15 feet in height.

Sign means any visual or graphic device designed through the use of words, number, characters, or symbols to inform or attract attention and which is designed to be visible from outside any building or structure in which, upon which, or attached to which it may be located. Various types of signs and sign related terms are defined in section 122-863.

Site plan means a plan showing all features of a proposed development as required in Article IV of this chapter so that it may be evaluated to

determine whether it meets the provisions of this chapter.

Sleeping room means a single room within a roominghouse which is usually individually rented and the entry door to the room is individually locked requiring the use of a key to gain access, and which is primarily used for sleeping purposes. The occupants may have direct access within the building to sanitary facilities, kitchen facilities and dining facilities or may share these facilities in common with other residents. See "Roominghouse."

Solar Collector means a device, substance, or element that relies upon sunshine to absorb and transform direct solar radiation through a medium to generate energy that can be used to heat or cool a building, heat or pump water, or generate electricity or other application that would otherwise require the use of a non-renewable energy source.

Solar Farm means large areas of land with several photovoltaic modules and inverters, or parabolic troughs placed on them for large scale energy generation.

Solar Roof Paneling means roof paneling that uses the sun's light to create electricity directly through photovoltaic cells.

Sorority house. See "Fraternity or sorority house."

Special use means a use that would be detrimental to other uses permitted in the same zoning district unless carefully controlled as to the number, area, size, exterior design, location, or relation to the adjacent properties and to the neighborhood or city as a whole and may be permitted if the proper safeguards are taken. Such uses may be permitted in a zoning district after a public hearing and approval by the Planning Commission, if specific provision is made in this chapter. Formerly called conditional use.

State equalized valuation means the value shown on the city assessment roll as equalized through the process of state and county equalization.

Story means that portion of a building included between the upper surface of any floor and the upper surface of the next floor above it, or any portion of a building between the topmost floor and the roof having a usable floor area which exceeds two-thirds of the usable floor area of the floor immediately below it. (See Figure 2.) Mezzanines and basements shall be deemed full stories as specified within their definitions.

- (1) A mezzanine shall be deemed a full story when it covers more than one-third of the area of the story underneath such mezzanine,

or if the vertical distance from the floor next below the mezzanine to the floor next above it is 24 feet or more.

- (2) A basement shall be considered a story above grade where the finished surface of the floor above the basement is:
- More than six feet (1,829 mm) above grade plane;
 - More than six feet (1,829 mm) above the finished ground level for more than 50 percent of the total building perimeter; or
 - More than 12 feet (3,658 mm) above the finished ground level at any point.

Story, first means the lowest story of the ground story of any building that is not a basement (see Figure 2) except that any basement or cellar used for residential purposes shall be deemed the first story.

Story, half means a partial story under a gable, hip or gambrel roof, the usable floor area which does not exceed two-thirds of the floor area of the uppermost full story.

Street means a public or private street, road, or thoroughfare intended primarily to provide vehicular circulation and access to abutting property. Various types of streets are defined as follows:

- (1) *Collector street* means a street whose principal function is to carry traffic between local or minor streets and major streets but may also provide direct access to abutting properties.
- (2) *Cul-de-sac* means a street that terminates in a vehicular turnaround.
- (3) *Local or minor street* means a street whose function is to provide access to abutting properties.
- (4) *Major thoroughfare* means a street that carries high volumes of traffic and serves as a main avenue through or around the city. Major thoroughfares may also be referred to as major streets or arterial streets. For the purposes of this chapter, major thoroughfares shall include those streets designated as "state trunkline," "county primary," or "major street" on the most recently approved City of Ypsilanti Act 51 map (P.A. 1951).

Street line means a dividing line between a street and a lot, also known as the right-of-way line.

Street, private means a street or road under private ownership which has been constructed for the purposes of providing access to adjoining

property and which is normally open to the public so that persons other than the occupants of adjoining property may travel thereon, but which has not been accepted for maintenance by the city, county, state, or federal government.

Street, public means a street or road, the right-of-way and improvements of which have been accepted for maintenance by the city, county, state or federal government.

Structure means anything constructed or erected in, on, over or below the ground. All buildings are structures, however, not all structures are buildings. Structures include, but are not limited to, principal and accessory buildings, tower, decks, fences, privacy screens, wall, antennae, swimming pools, and sign structures.

Structure, accessory. See "Accessory use, building, or structure."

Subdivision plat means the division of a tract of land into two or more lots, building sites, or other divisions for the purpose of sale or building development, in accordance with the land division act, Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101 et seq., MSA 26.430(101) et seq.), as amended.

Substance abuse treatment facility means:

- (1) *Boarding.* Any facility providing substance abuse treatment or preventive or addictive counseling, including the dispensing of or distribution of drugs as part of the treatment, where individuals receiving the treatment live on the premises for a period of time, including overnight stays.
- (2) *Walk-in.* Any facility providing substance abuse treatment or preventive or addictive counseling, including the dispensing or distribution of drugs as part of the treatment plan, where no one resides on the premises overnight.

Supportive Housing means a facility that provides housing for twenty-four (24) hours per day and supportive services designed to assist residents with improving daily living skills, securing employment, rehabilitation, or obtaining permanent, independent housing. Supportive housing is not intended for short-term, emergency housing and care, but rather longer periods ranging from a few months to a few years. Supportive housing is distinguished from a hospital or other health care environment, and facilities regulated by the State of Michigan as State licensed residential facilities. This definition shall not include fraternities, sororities, dormitories, adult foster care facilities, group homes, nursing homes, substance abuse treatment

facilities, emergency shelters, individuals utilizing tenant-based or homeownership-based voucher funding through the U.S. Department of Housing and Urban Development, community correctional facilities, and housing for the rehabilitation of former occupants of correctional facilities.

Supportive Services are services provided to residents of supportive housing for the purpose of facilitating the independence of residents, and may be provided on the premises, or off-site. Some examples are case management, medical or psychological counseling and supervision, child care, transportation, and job training.

Swale, vegetated/rock means a densely vegetated or rock lined drainage ways with low-pitched side slopes that detain, evaporate, and/or infiltrate the runoff associated with a storm event.

Swale, biofiltration means a shallow drainage ways that employ landscaping to stabilize the soil while providing water quality treatment. They are designed to remove silt and sediment-associated pollutants before discharging to storm sewers and to reduce volume if soils allow for infiltration.

Swimming pool means any structure or container located either above or below grade designed to hold water to a depth of greater than two feet when filled, and intended for swimming, bathing, or aquatic recreation. A swimming pool does not include plastic, canvas, or rubber portable pools temporarily erected upon the ground holding less than 300 gallons of water nor decorative pools with less than two feet of water depth.

Temporary use or building. See "Building, temporary" or "Use, temporary."

Theater means an enclosed building used for presenting performances or motion pictures which are observed by paying patrons from seats situated within the building.

Townhouse. See "Dwelling unit, single-family attached or townhouse."

Toxic or hazardous waste means waste or a combination of waste and other discarded material including solid, liquid, semi-solid or contained gaseous material which because of its quantity, concentration, or physical, chemical, or infectious characteristics may cause or significantly contribute to the following if improperly treated, stored, transported, disposed of, or otherwise managed:

- (1) An increase in mortality;
 - (2) An increase in serious irreversible illness;
 - (3) Serious incapacitating, but reversible illness;
- or

- (4) Substantial present or potential hazard to human health or the environment.

Tree means a self-supporting woody, deciduous or evergreen plant with a well-defined central stem which normally grows to a mature height of 15 feet or more in the county.

a. *Deciduous tree* means a variety of tree that has foliage that is shed at the end of the growing season.

b. *Evergreen tree* means a variety of tree that has foliage that persists and remains green throughout the year.

Unclassified use means a use permitted only after review of an application by the Planning Commission, such review being necessary because the provisions of this chapter do not specifically or implicitly address a particular use due to emerging technologies or omissions within this chapter. Such uses are so differentiated from uses or categories specified in this chapter that the standards of this chapter cannot be reasonably applied to them. Eligibility of a particular use for an unclassified use shall be determined by the Planning Commission. Such uses shall be allowed only after a public hearing and approval by the Planning Commission, subject to the standards in section 122-651.

Use means the purpose for which land, lots, or building thereon is designed, arranged, or intended, or for which it is occupied, maintained, or leased.

Use, accessory. See "Accessory use, building, or structure."

Use, nonconforming. See "Nonconforming use."

Use, permitted means a use which may be lawfully established in a particular district or districts provided it conforms with all requirements, regulations, and standards of such district.

Use, principal means the principal use is the main use of land and buildings and the main purpose for which land and buildings exist.

Use, special. See "Special use."

Use, temporary means a use permitted to exist during a specified period of time under conditions and procedures as provided in this chapter.

Variance means a modification of the literal provisions of this chapter in accordance with the provisions of this chapter in cases where strict enforcement would cause undue hardship as a result of special circumstances affecting an individual property that do not generally affect other properties in the same zoning district.

Vehicle storage facility means a building or portion thereof or an outdoor controlled-access compound, designed or used exclusively for long-term or seasonal storage of four or more automobiles, trucks, tractors, boats, mobile homes, recreational vehicles and trailers, and other types of vehicles. A vehicle storage facility may be combined with a self-storage facility.

Vegetated roof means the roof of a building that is partially or completely covered with vegetation, including for food production, and a growing medium, planted over a waterproofing membrane.

Veterinary clinic or hospital means a place for the care, diagnosis, and treatment of sick or injured animals, or those in need of medical or minor surgical attention. A veterinary clinic or hospital may include customary pens, animal runs, or cages enclosed within the walls of the clinic building.

Warehouse means an enclosed building used for the storage of commercial goods or wares which are intended for sale, transfer or processing.

Yard means an open space between a building and the adjoining lot lines, unoccupied and unobstructed by any portion of a structure from the ground upward, except as otherwise provided in this chapter. The minimum required setback is the minimum depth of a front, rear, or side yard necessary to conform to the required yard setback provision of this chapter. (See Figure 5.)

(1) *Yard, front* means a yard extending across the front of a lot and being the minimum horizontal distance between the street line and the principal building or any projections thereof other than projection of uncovered steps, unenclosed balconies or unenclosed porches.


(2) *Yard, rear* means a yard extending across the full width of the lot between the rear lot line and the nearest point of the principal building. On all lots, the rear yard shall be opposite the front yard.

(3) *Yard, side* means a yard between a principal building and the side lot line, extending from the front yard to the rear yard, the width of which shall be the horizontal distance from the nearest point of the side lot line to the nearest point on the principal building.

(4) *Yard, street side* means a yard between the principal building and the street side lot line on a corner lot, extending from the front yard rearward to the rear lot line, the width of which shall be the horizontal distance of the side lot line to the nearest point on the principal building.

Zoning Map means the Zoning Map of the city together with all amendments subsequently adopted.


Figure 2



basic structural terms

Definitions


Figure 3



building height requirements

H: height of building

Figure 4



yard terms

Definitions





Figure 5

building line


Figure 6



lot width and setbacks

Definitions

Figure 7




corner lots

floor area

FLOOR AREA OF
COMMERCIAL, OFFICE AND SIMILAR NON-RESIDENTIAL USES

Figure 10



Sec. 122-4. Interpretation and conflict.

- (a) In interpreting and applying the provisions of this chapter, such provisions shall be held to be the minimum requirements adopted for the promotion of the public health, morals, safety, comfort, convenience, prosperity, and general welfare.
- (b) It is not intended by this chapter to repeal, abrogate, annul or in any way to impair or interfere with any existing provision of any law or ordinance other than the above described zoning ordinance, or with any rules, regulations, or permits previously adopted or issued or which shall be adopted or issued pursuant to the law relating to the use of the buildings or premises; provided, however, that where this chapter imposes a greater restriction than is required by an existing ordinance or by rules, regulations or permits, the provisions of this chapter shall control.

Sec. 122-5. Rule of construction.

The rule that a penalty statute is to be strictly construed shall not apply to this chapter or any of the provisions thereof. All provisions of this chapter shall be construed according to the fair import of their terms, to promote justice, and to effect the objectives of this chapter.

Sec. 122-6. Administrative liability.

No officer, agent, employee, or member of the city council, Planning Commission, or zoning board of appeals shall render himself personally liable for any damage that may accrue to any person as the result of any act, decision, or other consequence or occurrence arising out of the discharge of his duties and responsibilities pursuant to this chapter.

Sec. 122-7. Vested right.

It is hereby expressly declared that nothing in this chapter shall be interpreted or construed to give or grant to any person, firm or corporation any vested right, license, or privilege in the continuation of any particular use, zoning classification or any permissible activities therein. Such provisions are hereby declared to be subject to subsequent amendment, change or modification as may be necessary for the preservation or protection of public health, safety and welfare.

Sec. 122-8. Violations and penalties.

- (a) *Public nuisance.* Any building or structure which is erected, altered, converted, or used, or any use of premises or land which is begun or changed subsequent to the passage of this chapter and in violation of any of the provisions of this chapter is hereby declared to be a public nuisance per se, and may be abated by order of the city council,

subject to appeal to any court of competent jurisdiction.

- (b) *Municipal civil infraction.* A person who violates any provision of this chapter is responsible for a municipal civil infraction, subject to payment of a civil fine as set forth in section 70-38. Repeat offenses under this article shall be subject to increased fines as set forth in section 70-38.
- (c) *Owner responsibility.* The owner of any building, structure or premises or part thereof, where any condition in violation of this chapter shall exist or shall be created, and who has assisted knowingly in the commission of such violation, shall be guilty of a separate offense and upon conviction thereof shall be liable for the fines provided in this chapter.
- (d) *Each day separate offense.* Each and every day during which a violation of this chapter shall exist shall constitute a separate offense.
- (e) *Rights and remedies are cumulative.* The rights and remedies provided in this chapter are cumulative and are in addition to any other remedies provided by law.
- (f) *Rights and remedies preserved, no waiver.* Any failure or omission to enforce the provisions of this chapter, and any failure or omission to prosecute any violations of this chapter, shall not constitute a waiver of any rights and remedies provided by this chapter or by law, and shall not constitute a waiver of nor prevent any further prosecution of violations of this chapter.
- (g) *Money received from penalties.* All money received from penalties assessed shall be placed in the city's general fund.

Sec. 122-9. Eligibility for zoning authorization.

- (a) If a person is delinquent in paying a civil fine, costs, or a justice system assessment imposed by the City of Ypsilanti's Administrative Hearings Bureau, that person is not eligible to apply for any zoning authorization under the City of Ypsilanti's Zoning Ordinance, including but not limited to, the following zoning authorizations:
 - (1) A zoning amendment under Article II "Administration," Division 3 "Amendments."
 - (2) A variance under Section 122-94 "Variances."
 - (3) Site plan review or amendment to an approved site plan under Article IV "Site Plan Review."
 - (4) A special use permit or to amend a special land use under Article V "Special Land Use Review."

- (5) A planned unit development under Article IX "Planned Unit Development."
 - (6) A site condominium subdivision project under Article X "Site Condominium Subdivisions."
 - (7) An application for occupation, construction or substantial improvement in a floodplain under Article XV "Flood Damage Prevention."
- (b) Subsection (a) above does not apply if:
- (1) If the applicant for zoning authorization became the owner of the property by foreclosure or by taking a deed in lieu of foreclosure and is one (1) of the following:
 - (i) A government-sponsored enterprise. As used in this subsection, "government-sponsored enterprise" means the term as defined in 2 USC 622(8), or the Michigan state housing development authority created under the state housing development authority act of 1966, 1966 PA 346, MCL 125.1401 to 125.1499c.
 - (ii) A financial institution. As used in this subsection, "financial institution" means that term as defined in section 4(c) of the Michigan strategic fund act, 1984 PA 270, MCL 125.2004.
 - (iii) A mortgage servicer. As used in this subsection, "mortgage servicer" means that term as defined in section 1a of the mortgage brokers, lenders, and servicers licensing act, 1987 PA 173, MCL 445.1651a, that is subject to the mortgage brokers, lenders, and servicers licensing act, 1987 PA 173, MCL 445.1651 to 445.1684.
 - (iv) A credit union service organization that is organized under the laws of this state or the United States.
 - (2) If the application for zoning authorization will correct, in whole or in part, the blight violation that was the subject of the delinquent payment referred to in subsection (a).

Secs. 122-10--122-30. Reserved.

ARTICLE II. ADMINISTRATION*

*Cross reference(s)--Administration, ch. 2.

DIVISION 1. GENERALLY

Sec. 122-31. Establishment of administrative officers.

The provisions of this chapter shall be administered and enforced by the city manager or by such person or persons, such as the city planner or building inspector, that the city manager may delegate to enforce the provisions of this chapter. All departments, officials and public employees of the city vested with the duty or authority to issue permits or licenses, shall conform to the provisions of this chapter.

Sec. 122-32. Duties and enforcement powers.

Typical duties and powers of the city manager, or such person or persons the city manager may delegate to act as building inspector, city planner or other agents to enforce this chapter, shall include, but not be limited, to the following:

- (1) The building inspector, or such person or persons as the city manager may delegate, shall have the power to:
 - a. Make inspections of buildings and premises necessary to carry out the duties of enforcement of this chapter.
 - b. Issue building permits.
 - c. Issue certificates of occupancy.
 - d. Conduct surveillance and issue notices of violation pursuant to this chapter.
- (2) Adequate records of permits and applications issued, inspections, violations, nonconformities, variances, construction plans, fees collected, etc., shall be maintained. Public notices shall be published as necessary.
- (3) Persons who have zoning questions shall be assisted, and when applicable, such questions shall be brought before the Planning Commission or zoning board of appeals.
- (4) Advice may be provided to the city council, Planning Commission or zoning board of appeals on petitions and applications that come before these bodies.
- (5) It shall be unlawful for the city manager, or his delegate to approve any permits or certificates of occupancy for any excavation or development proposal until such plans have been inspected in detail and found to conform with this chapter, or when applicable, site plan approval has been obtained.

- (6) Under no circumstances shall the city manager or his delegate be permitted to make changes to this chapter nor vary the terms of this chapter in carrying out duties in administering and enforcing this chapter.
- (7) The city manager or his delegate shall not refuse to issue a permit when the conditions imposed by this chapter are complied with by the applicant, despite violations of any contract such as covenants or private agreements which may occur upon granting of such permit.

Sec. 122-33. Building permits.

- (a) *Permit requirement.* No building or structure within the city shall hereafter be erected, moved, repaired, altered or razed, nor shall any work be started to erect, move, repair, alter, or raze until a building permit has been issued in accordance with the building regulations of this Code. No building permit shall be issued unless it is in conformity with the provisions of this chapter and all amendments hereto.
- (b) *Application requirements.* All applications for building permits shall be submitted to the building department. The application shall be accompanied by a site plan approved by the Planning Commission (or city planner) when required under Article IV of this chapter.
- (c) *Cancellation of permits.* The building department shall have the power to revoke and cancel any permit in the event of failure or neglect to comply with all of the terms and provisions of this chapter.
- (d) *Expiration of permit.* All building permits shall expire six months from their date of issuance if construction has not been begun and diligently pursued. The building department may, upon a showing of due cause, extend the permit for one additional time as the building department determines to be reasonably necessary for completion. Thereafter, the applicant shall file a new building permit application, accompanied by the required fee.

Sec. 122-34. Certificate of occupancy.

- (a) *Certificate required.* No dwelling, building, structure or land shall be occupied or used until a certificate of occupancy has been issued for such occupancy or use, which occupancy or use shall be in compliance with this chapter (including

approved site plans as applicable). No structure or land shall be occupied by a changed use or occupancy until a certificate of occupancy for the changed use has been issued.

- (b) *Temporary certificate of occupancy.* If the applicant can show prior substantial compliance with this chapter and can demonstrate need, the building department may issue a temporary certificate of occupancy for a period of not more than six months.

Sec. 122-35. Temporary use permits.

The building department may issue temporary use permits for the uses listed below, after determining that such uses will meet the standards under subsection (9) of this section and review standards for that specific use included in this section. A second temporary use permit may be issued by the building department at the end of such time limit for good cause shown. A third temporary special use permit may only be authorized by the Planning Commission as a special use under the procedures of Article V of this chapter. The building department, at its discretion, may refer any request for a temporary use permit to the Planning Commission.

- (1) *Temporary dwellings.* An individual mobile home, private garage, basement, or other temporary structure may be used as temporary living quarters for up to 60 days while a dwelling or structure is being constructed on the same premises. A temporary use permit must be issued prior to any such use.
- (2) *Construction buildings.* Temporary buildings for uses incidental to construction work may be authorized for a period of up to 12 months. Such buildings shall be removed within 15 days after completion or abandonment of construction work.
- (3) *Signs and supplies.* The storage of building supplies and machinery; temporary storage buildings; the assembly of materials and customary trade; and contractor, architect, and identification signs in connection with a construction project may be authorized by the building department for a period of up to 12 months. All signs shall meet the provisions under Article XIV of this chapter.
- (4) *Seasonal uses.* The building department may authorize a temporary special permit for up to 30 days for seasonal or unusual nonrecurrent temporary uses and signs.
- (5) *Parking areas.* Temporary special permits may be issued by the building department for the use of unimproved parking areas for a period of up to 30 days.
- (6) *Sales office for subdivision.* Temporary special

permits may be issued by the building department for a period of up to six months for a temporary office which is both incidental and necessary for the sale or rental of property in a new subdivision or housing project.

- (7) *Food Concession Sales.* The provisions of this section are intended to allow food vending opportunities that can add vitality to vacant parking lots and underutilized sites and provide food access, employment and entrepreneurship opportunities while preventing predatory practices on brick-and-mortar restaurants. These provisions shall apply to businesses engaged in the cooking, preparation, and distribution of food or beverage on properties located outside of the public right-of-way. This section does not apply to mobile vendors that move from place to place and are stationary in the same location for no more than thirty (30) minutes at a time or special event vendors. Temporary concession sales, including those conducted outdoors, or in stands, trailers, wagons, or vehicles shall be permitted subject to the following requirements:

- a. *Districts Allowed.* Food concessions are only allowed as temporary uses in the following districts: Center, Parks, General Corridor, Neighborhood Corridor, and Health and Human Services.
- b. *Principal Use.* Concession sales as a principal use on a vacant lot or as part of a group of retail business buildings approved under a single approved plan shall be subject to Special Land Use approval in the Center, General Corridor, and Health and Human Services Districts.
- c. *Accessory Use.* Temporary concession sales may be permitted as an accessory use to the principal permitted use and business on the lot, approved by the City Planner per item s of this sub-section.
- d. *Co-Location.* Where concession sales have been approved on a lot as a principal use, the Planning Commission may allow locating additional concession sales on the same lot with a sketch plan meeting the requirements of item q of this sub-section.
- e. *Approvals.* In addition to satisfying the requirements of this section, evidence of approval from the Washtenaw County Health Department and/or Michigan Department of Agriculture and Rural Development, as applicable, shall be provided for all concession sales. A Transient Merchant License or a Special Peddler's license must also be obtained from the Office of the City Clerk, as applicable.

- f. Outdoor Cooking. With the exception of the Center District, outdoor food preparation and cooking is prohibited within two hundred (200) feet of a first-floor residential use.
- g. Active Use. Any stand, trailer, wagon, or vehicle that is located on a property for the purposes of concession sales shall maintain regular business hours at least two days a week so long as the premises is occupied. If the business closes, ceases to operate, or fails to keep regular business hours then the temporary use permit may be revoked and the stand, trailer, wagon or vehicle shall be immediately removed from the property.
- h. Maximum Duration. Permits may be issued for no more than two hundred (200) consecutive days over a period of twelve (12) calendar months. Permits will be issued annually upon application.
- i. Placement. Concession sales shall be located within the building envelope for the district in which it is located.
- j. Parking Area. The area occupied by accessory concession sales shall be no more than twenty (20) percent of any required parking spaces or area. Sufficient on-site or district parking shall be provided for each stand, trailer, wagon, or vehicle on a lot; this shall be in addition to any other required parking for retail business buildings located on the same parcel.
- k. Pedestrian Space. A minimum pedestrian clear space of five (5) feet is required along all public walkways
- l. Traffic Visibility. Concession sales shall not be located in the public right-of-way or on public property unless otherwise approved, and shall be outside of traffic visibility areas in compliance with Section 122-649.
- m. Outdoor Seating: If provided, all outdoor seating must be in compliance with Section 122-799. Outdoor cafes, restaurants and beer gardens.
- n. Sanitary Facilities. Sanitary facilities shall be provided if seating is present for the convenience of guests. The City Planner may waive this requirement if alternative arrangements are made and documentation is provided.
- o. Hours of Operation. Operating hours shall be no later than 10 p.m. Sunday through Thursday and 11:00 p.m. on Friday and Saturday, unless otherwise approved by the Planning Commission.
- p. Sound. No outdoor amplified music, sound, or noise shall be permitted. Outdoor generators that provide power shall be identified; such generators may be prohibited if it is anticipated that such an operation will create a nuisance to neighbors due to noise, exhaust or vibration.
- q. Required Site Information. A sketch plan shall be submitted that includes:
 - i. location and dimensions of any stand, trailer, wagon or vehicle, and any other outdoor activity associated with concession sales;
 - ii. site dimensions of any existing buildings on the lot including building setbacks;
 - iii. existing public improvements, such as fire hydrants, bus shelters, trees and tree grates and parking meters;
 - iv. surface type of the lot (e.g. unimproved/paved);
 - v. a parking plan, including traffic circulation patterns;
 - vi. location of trash receptacles;
 - vii. location of on-site water, generator, and/or electric utilities that will serve concession vendor(s);
 - viii. location of sanitary facilities;
 - ix. map identifying existing restaurants located within buildings, as well as other concession sales locations within three-hundred (300) feet;
 - x. Photographs of the area
 - xi. Required Concession Sales Facilities Information. A narrative with elevation drawings shall be submitted that describe/show: the nature of proposed concession sales, include food and/or beverage types; vehicle or structure type; site signage; duration that sales will occur on the site; and hours of operation.
- r. Food Concession Sales Permit Required. A temporary use permit shall be obtained by each concession sales vendor on a property. The vendor shall adhere to all regulations and requirements of this section and any conditions imposed by the Planning Commission. The Planning Director shall apply the Review Standards of this section to insure that the proposed concession sales will

not be in conflict with these standards in the issuance of a temporary use permit.

- s. Permit Approval and Administration. The City Planner will review and approve food concession sales permits if all requirements of this sub-section and Section 122-35(9) are met.
- t. Review Standards. The following considerations shall be used by the Planning Commission and the City Planner in the deliberation and approval of a concession sales request for the site and/or vendor(s):
 - i. Will the use contribute to the vitality and experience of the surrounding area?
 - ii. Will the use support or draw new attention to existing brick and mortar establishments?
 - iii. Is there an appropriate separation distance between temporary and permanent uses so as to not impair the long-term viability of nearby businesses?
 - iv. Will the use add variety to the types of food or beverage offerings in the district?
 - v. Will the proposed stand, trailer, wagon or vehicle contribute to the general aesthetic of the business district?

(8) *Temporary Businesses in Vacant Storefronts:* In the Center, General Corridor and Neighborhood Corridor Districts, the City Planner may authorize a temporary use permit for a business to occupy a vacant storefront for less than 3 months if the following standards are met:

- a. The proposed use is a permitted use in that district. Special uses shall not be given temporary use permits.
- b. All building and fire code requirements are met.
- c. The standards in Section 122-35(9) are met.

(9) *Standards.* No temporary use permit shall be authorized until the following standards are met:

- a. The location and erection of any temporary structure shall conform to all of the regulations of the zoning district in which it is situated and all other applicable regulations of this chapter.
- b. The location of such use shall not be injurious to adjacent properties or the surrounding neighborhood.
- c. The water supply and sanitary facilities of any temporary dwelling shall conform to all applicable requirements of the state health department, the county health department and city codes and other regulations.
- d. The following shall be taken into consideration:
 - 1. The reasons and necessity for the temporary use or structure.
 - 2. The nature of the use or structure.
 - 3. The proposed location of the use or structure.
- e. If not required above, the building department, City Planner or Planning Commission may request a plot plan, drawn to scale no smaller than one inch equals 50 feet, showing the location of the temporary use in relation to the lot lines and other structures.
- f. Reasonable conditions may be required with the approval of a temporary special permit by the building department or Planning Commission. The conditions may include, but are not limited to, conditions necessary to ensure that public services and facilities are not adversely affected, to protect the natural environment and conserve natural resources and energy, to ensure compatibility with adjacent uses of land, and to promote the use of land in a socially and economically desirable manner.

(10) A fee for a temporary use permit shall be paid in accordance with a fee schedule established by the City Council.

Secs. 122-36--122-45. Reserved.

DIVISION 2. PLANNING COMMISSION*

*Cross reference(s)--Boards and commissions, § 2-111 et seq.

State law reference(s)--Municipal planning, MCL 125.31 et seq., MCL 125.38 et seq.

Sec. 122-46. Authority.

This ordinance is adopted pursuant to the authority granted the City Council under the Michigan Planning Enabling Act, Public Act 33 of 2008, MCL 125.3801 *et seq.*, and the Michigan Zoning Enabling Act, Public Act 110 of 2006, MCL 125.3101 *et seq.*, as amended, to establish a Planning Commission with the powers, duties and limitations provided by those Acts.

Sec. 122-47. Purpose.

The purpose of this ordinance is for the City Council to confirm the establishment, under the Michigan Planning Enabling Act, Public Act 33 of 2008, MCL 125.3801 *et seq.*, of the city Planning Commission, formerly established under the Municipal Planning Act, MCL 125.31 *et seq.*, to establish the appointments, terms, and membership of the Planning Commission; to identify the officers and the minimum number of meetings per year of the Planning Commission; and to prescribe the authority, powers and duties of the Planning Commission as provided in and subject to the terms and conditions of this ordinance.

Sec. 122-48. Establishment.

There shall be a city Planning Commission in accordance with the Michigan Planning Enabling Act, Public Act 33 of 2008, as amended, with the powers and duties as therein set forth and as hereinafter provided.

Sec. 122-49. Reserved

Sec. 122-50. Zoning board of appeals member of the Planning Commission.

As provided in the Michigan Zoning Enabling Act, MCL 125.3601, one member of the Planning Commission may be appointed by the City Council to serve on the zoning board of appeals, with the term of that appointment to correspondence to that member's term as a Planning Commission member.

Sec. 122-51. Procedures of the Planning Commission.

- (a) The Planning Commission shall adopt bylaws for the transaction of business and shall keep a public record of its resolutions, transactions, findings, and determinations.
- (b) The Planning Commission's procedures shall be in conformity with applicable ordinances, resolutions and policies adopted by the City Council.

Sec. 122-52. Meetings of the Planning Commission.

- (a) The Planning Commission shall hold not less than four (4) regular meetings each year. At its first meeting of the calendar year, the Planning Commission shall adopt and provide notice of its regular meetings for the ensuing year in accordance with the Open Meeting Act, Public Act 267 of 1976, as amended; provided, however, that a meeting need not be held if pending matters do not warrant a meeting.
- (b) Special meetings may be called by the chairperson or upon written request to the secretary by at least two members of the Planning Commission. Unless the Planning Commission bylaws provide otherwise, the secretary shall send written notice of a special meeting to Planning Commission members not less than 48 hours before the meeting. All costs of special meetings held to consider requests of applicants for approvals under the zoning ordinance (or for such other purposes as may be necessary) shall be paid by the applicant for such requests.
- (c) The business that the Planning Commission may perform shall be conducted at a public meeting held in compliance with the Open Meetings Act, Public Act 267 of 1976, as amended.

Sec. 122-53. Duties and responsibilities of the Planning Commission.

The members of the Planning Commission shall have the following principal duties and responsibilities, among others:

- (a) Prepare, review and update a master plan as a guide for development within the city's planning jurisdiction.
- (b) Take such action on petitions, staff proposals and City Council requests for amendments to the zoning ordinance as required.
- (c) In accordance with the Michigan Planning Enabling Act, Public Act 33 of 2008, as amended, consider, no less frequently than every five (5) years, whether a revision of the master plan or updated amendments in the master plan are needed and prepare, consider and approve any such revisions or amendments.
- (d) Take such actions as are required by the Michigan Zoning Enabling Act, Public Act 110 of 2006, as amended, and the Michigan Planning Enabling Act, Public Act 33 of 2008, as amended.

- (e) Review subdivision and condominium proposals and recommend appropriate actions to the City Council.
- (f) Prepare special studies and plans, as deemed necessary by the Planning Commission or City Council for which appropriations of funds have been approved by the City Council, as needed.
- (g) Prepare an annual written report to the City Council concerning its operations and the status of planning activities, including recommendations regarding actions by the City Council related to planning and development, with the report to be presented within 90 days of the beginning of each calendar year.
- (h) Promote understanding of and interest in the master plan and the city zoning ordinance.
- (i) The Commission shall review and advise upon plans for capital improvements, such as construction, expansion, removal, or vacating of public lands, buildings, or right-of-ways. This review should focus on consistency with adopted plans of the City and other governmental units.

This may be done by an annual review of the City's Capital Improvement Plan prior to adoption by City Council, rather than of each project individually.

- (i) Carry out other duties and responsibilities as set forth in the Michigan Planning Enabling Act, Public Act 33 of 2008.

Sec. 122-54. Approval, ratification and reconfirmation.

All official actions taken by the city Planning Commission preceding the Planning Commission established by this ordinance are hereby approved, ratified, and reconfirmed. Any project, review, or process taking place at the effective date of this ordinance shall continue with the Planning Commission created by this ordinance, subject to other requirements of this ordinance, and shall be deemed a continuation of any previous city Planning Commission. This ordinance shall be in full force and effect from and after its adoption and publication.

Secs. 122-55--122-60. Reserved.

DIVISION 3. AMENDMENTS*

*State law reference(s)--Amendment of zoning ordinance, MCL 125.584, MSA 5.2934.

Sec. 122-61. General requirements.

- (a) The City Council shall have authority to amend, supplement, or change zoning district boundaries or the provisions and regulations of this chapter, pursuant to the authority and procedures set forth in Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.), as amended.
- (b) Text amendments to this chapter may be initiated by a motion of the City Council or the Planning Commission, or by the filing of an application by any interested person or organization. Changes in district boundaries may be initiated by a motion of the City Council or the Planning Commission, or by the filing of an application by any person having a freehold interest in the subject property or by such person's designated agent.
- (c) The owner of land who has filed an application for changes in district boundaries may voluntarily offer with conditions relating to the use and/or development of land, either at the time the application is filed or may be made at a later time during the approval process. The City Council may establish a period of time during which the conditions apply to the land. No employee or official of the City of Ypsilanti shall not require an owner to offer conditions as a requirement for rezoning. The lack of an offer of conditions shall not affect an owner's rights under this Ordinance.
- (d) All proposed amendments shall be referred to the Planning Commission for a public hearing, review and recommendation, before action may be taken thereon by the City Council.

Sec. 122-62. Amendment procedures.

- (a) *Application.* Applications for amendments to this chapter shall be filed with the city planner's office on an appropriate form provided by the city and accompanied by the required fee. No fee shall be required if a proposed amendment was initiated by the City Council or Planning Commission. All applications for amendments to this chapter shall, at a minimum, include the following:
 - (1) The applicant's name, address, and interest in the application; and the name, address, and interest of every person having a legal or equitable interest in any land which is to be rezoned. The application shall be signed by both the landowner and the applicant, if not the same.
 - (2) The nature and effect of the proposed amendment.

- (3) If the proposed amendment would require a change in the Zoning Map, a boundary change and/or a change in building type allowed on a site designated on the Zoning Map, a fully dimensioned map showing the boundaries of land which would be affected by the proposed amendment, a legal description of the entire land area, a legal description of each subarea owned by a different person or organization, the present zoning of the land, the zoning of all adjacent lands, existing uses and structures on the subject property and adjacent properties, and all public and private rights-of-way and easements bounding or intersecting the land to be rezoned.
- (4) If the proposed Zoning Map amendment includes voluntary conditions set forth by the owner of the property, a written statement of those voluntary conditions shall be included. The "Statement of Conditions" shall:
 - (a) Be in a form recordable with the Washtenaw County Register of Deeds or, in the alternative, be accompanied by a recordable Affidavit or Memorandum prepared and signed by the owner giving notice of the "Statement of Conditions" in a manner acceptable to the City Attorney.
 - (b) Contain a legal description of the land to which it pertains.
 - (c) Contain a statement acknowledging that the "Statement of Conditions" runs with the land and is binding upon successor owners of the land.
 - (d) Incorporate by attachment or reference any site plan, diagram, or other documents submitted or approved by the owner that are necessary to illustrate the implementation of the "Statement of Conditions". If any such documents are incorporated by reference, the reference shall specify where the document may be examined.
 - (e) Contain a statement acknowledging that the "Statement of Conditions" or an Affidavit or Memorandum giving notice thereof may be recorded by the Township with the Washtenaw County Register of Deeds.
 - (f) Contain the notarized signatures of all of

the owners of the subject land preceded by a statement attesting to the fact that they voluntarily offer and consent to the provisions contained within the "Statement of Conditions".

- (5) If the application is for an amendment to this chapter text, a description of the proposed change, with a detailed explanation as to why the proposed amendment is needed.
- (6) All other circumstances, factors, and reasons which the petitioner offers in support of the proposed amendment.

(b) *Public hearing.*

- (1) At least one public hearing on a proposed amendment shall be held by the Planning Commission. Notice of such public hearing shall be published at least once in a newspaper of general circulation in the city, not less than 15 days prior to the date set for the public hearing. The contents of the notice shall include the following.
- (2) Time and place of the public hearing.
- (3) A description of the proposed amendment.
- (4) The street address and legal description of any property for which a zoning change is requested, the present zoning of that property, and the proposed new zoning designation. If 11 or more adjacent properties are proposed for rezoning, individual addresses and legal descriptions are not required.
- (5) Not less than 15 days' notice of the public hearing shall be given by mail to each public utility company and railroad company owning or operating any public utility or railroad within the zoning district affected by the proposed amendment that registers its name and address with the city for the purpose of receiving such notice.
- (6) If an individual property or up to 10 adjacent properties are proposed for rezoning, written notice of the public hearing shall be given the owner of the property in question, and to all owners of real property and occupants of structures within 300 feet of the property in question. The notice shall be mailed or delivered not less than 15 days before the public hearing.
- (7) Any notices served by mail require an affidavit of mailing to be filed with the Planning Commission prior to the public hearing.

(c) *Planning Commission recommendation.* Following the public hearing, the Planning

Commission shall prepare a report of its recommendations regarding the proposed amendment, and transmit such report to the City Council. The Planning Commission may recommend changes in the amendment in order to reflect objections raised at the hearing or to correct typographical or grammatical errors. The Planning Commission may reduce the area of land to be rezoned as described in the public hearing notice, but may not enlarge the area of land to be rezoned.

- (d) *City Council action.* After the Planning Commission has held a public hearing and has made a written report to the City Council indicating their recommendation on the proposed amendment, the City Council may adopt the proposed amendment, decline to adopt the proposed amendment, or may adopt it in whole or part with or without additional changes. The City Council may also hold a public hearing on the proposed amendment or refer the proposed amendment back to the Planning Commission for further study and review or for additional public hearings. Upon the presentation of a protest petition meeting the requirements of section-4 403 of Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.) an amendment to this chapter or Zoning Map which is the object of such petition shall be passed by an affirmative vote of not less than two-thirds members of the City Council.

- (e) *Publication.* Following adoption of an amendment to this chapter by the City Council, a notice of adoption shall be published in a newspaper of general circulation in the city within 15 days after adoption. The notice shall include the following information:

- (1) Either a summary of the regulatory effect of the amendment including the geographic area affected, or the text of the amendment.
- (2) The effective date of the amendment.
- (3) The place and time where a copy of the amendment may be purchased or inspected.

Sec. 122-63. Standards for Amendments

- (a) *Text Amendment.* For a change to the text of the Zoning Ordinance, the Planning Commission shall consider and the City Council may consider, whether the proposed amendment meets the following standards:
 - (1) The proposed amendment is consistent with the guiding values of the Master Plan; and
 - (2) The rezoning is consistent with description and purpose of the proposed district, and.
 - (3) The proposed amendment consistent with the

- intent of this Zoning Ordinance; and
- (4) The proposed amendment will enhance the functionality, transportation network or character of the future development in the City; and
 - (5) The proposed amendment will preserve the historic nature of the surrounding area and of the City; and
 - (6) The proposed amendment will enhance the natural features and environmental sustainability of the City; and
 - (7) The proposed amendment will protect the health, safety, and general welfare of the public; or
 - (8) The proposed amendment is needed to correct an error or omission in the original text; or
 - (9) The proposed amendment will address a community need in physical or economic conditions or development practices; and
 - (10) The proposed amendment will not result in the creation of significant nonconformities in the City.
- (b) *Zoning Map Amendment.* For a change in the Zoning Map, the Planning Commission shall consider and the City Council may consider, whether the proposed rezoning meets the following standards:
- (1) The rezoning is consistent with the policies, guiding values and City Framework (Future Land Use Map) of the Master Plan, including any subarea or corridor studies. If conditions have changed since the current Master Plan was adopted, the consistency with recent development trends in the area.
 - (2) The rezoning sustains the site's physical, geological, hydrological and other environmental features with the potential uses allowed in the proposed zoning district.
 - (3) The property proposed to be re-zoned can accommodate the requirements of the proposed zoning district.
 - (4) All the potential uses and building types allowed in the proposed zoning district are compatible with surrounding uses, buildings, and zoning in terms of land suitability, impacts on the environment, impacts on the transportation network, density, nature of use, aesthetics, infrastructure and potential influence on property values.
 - (5) The capacity of City infrastructure and services sufficient to accommodate the uses permitted in the requested district without compromising the health, safety, sustainability and welfare of the City.
 - (6) The rezoning will not be detrimental to the financial stability and economic welfare of the City.
 - (7) The rezoning not would negatively impact the condition of any nearby parcels considering existing vacancy rates, current per-square-foot lease or sale rates, and other impacts.
 - (8) The rezoning is consistent with the trend of development in the neighborhood or surrounding area.
 - (9) The property in question was improperly zoned or classified when this Chapter was adopted or amended.
 - (10) Where a rezoning is reasonable given the above criteria, a determination shall be made that the requested zoning district is more appropriate than another district or than amending the list of permitted or special land uses within a district.
- (c) *Building Type Designation on Zoning Map.* For a change in building type designation on the Zoning Map, the Planning Commission shall consider and the City Council may consider, whether the proposed amendment meets the following conditions:
- (1) The building type change is consistent with the policies, guiding values and City Framework (Future Land Use Map) of the Master Plan, including any subarea or corridor studies. If conditions have changed since the current Master Plan was adopted, the building type change is consistent with recent development trends in the area.
 - (2) The building type sustains the site's physical, geological, hydrological and other environmental features with the potential uses allowed on the proposed property and surrounding property.
 - (3) The building type change is consistent with the size, scale and character desired within the zoning district.
 - (4) The property can accommodate the requirements of the proposed building type change.
 - (5) The building type change is compatible with surrounding uses, buildings, and zoning in terms of land suitability, impacts on the environment, impacts on the transportation network, density, nature of use, aesthetics, infrastructure and potential influence on

property values.

- (6) The capacity of City infrastructure and services sufficient to accommodate the building type change on the property in question without compromising the health, safety, sustainability and welfare of the City.
 - (7) The building type change will not be detrimental to the financial stability and economic welfare of the City.
 - (8) The building type change will not would negatively impact the condition of any nearby parcels considering existing vacancy rates, current per-square-foot lease or sale rates, and other impacts.
 - (9) The building type change is consistent with the trend of development in the neighborhood or surrounding area.
 - (10) The building type change on the property in question is consistent with the description and purpose of the district of the property.
 - (11) In cases where requested building type is designed to accommodate commercial uses on the first floor in Neighborhood district, the parcel must be located on a corner.
- (d) *Conditional Zoning Map Amendment.* For a change in the Zoning Map with a conditional site plan, the Planning Commission shall consider and the City Council may consider, whether the proposed rezoning and voluntary conditions meet the following conditions:
- (1) The rezoning and voluntary conditions are consistent with the policies, guiding values and City Framework (Future Land Use Map) of the Master Plan, including any subarea or corridor studies. If conditions have changed since the current Master Plan was adopted, the consistency with recent development trends in the area.
 - (2) The rezoning and voluntary conditions are consistent with the description and purpose of the district of the property.
 - (3) The rezoning and voluntary conditions sustains the site's physical, geological, hydrological and other environmental features with the potential uses allowed in the proposed zoning district.
 - (4) The property proposed to be re-zoned can accommodate the requirements of the proposed zoning district and voluntary conditions.
 - (5) All the potential uses and building types allowed in the proposed zoning district under the voluntary conditions are compatible with

surrounding uses, buildings, and zoning in terms of land suitability, impacts on the environment, impacts on the transportation network, density, nature of use, aesthetics, infrastructure and potential influence on property values.

- (6) The capacity of City infrastructure and services are sufficient to accommodate the uses permitted in the requested district under the voluntary conditions without compromising the health, safety, sustainability and welfare of the City.
- (7) The rezoning and voluntary conditions will not be detrimental to the financial stability and economic welfare of the City.
- (8) The rezoning and voluntary conditions will not negatively impact the condition of any nearby parcels considering existing vacancy rates, current per-square-foot lease or sale rates, and other impacts.
- (9) The rezoning and voluntary conditions are consistent with the trend of development in the neighborhood or surrounding area.
- (10) The voluntary conditions bear a reasonable and rational relationship to the property for which rezoning is requested.

Sec. 122-64. Protests.

- (a) In case a protest against a proposed rezoning is presented, duly signed by the owners, or part owners, of 20 percent of the area of land proposed to be altered, or by the owners of at least 20 percent of the area of land included with the area extending outward 100 feet from any point on the boundary of the land included in the proposed change, such amendment shall not be passed except by a two-thirds vote of the City Council. The protest petition shall be presented to the City Council before final City Council action on the amendment.
- (b) For purposes of the protest, publicly-owned land shall be excluded in calculating the 20 percent land area requirement.

Sec. 122-65. Conditional Zoning Map Amendment Administration.

- (a) *Zoning Map.* Upon a conditional Zoning Map amendment taking effect, the Zoning Map shall be amended to reflect the new zoning classification along with a designation that the land was rezoned with a "Statement of Conditions". The Planning Department shall maintain a listing of all lands rezoned with a "Statement of Conditions".
- (b) *Statement of Conditions.* The approved "Statement of Conditions" shall be approved by

the City Attorney and then filed by the City of Ypsilanti with the Washtenaw County Register of Deeds. If a time period for compliance with conditions has been required by City Council, the time period must be included in the document approved and filed with the Washtenaw County Registrar of Deeds. The City Council shall have authority to waive this requirement if it determines that, given the nature of the conditions and/or the time frame within which the conditions are to be satisfied, the recording of such a document would be of no material benefit to the City or to any subsequent owner of the land.

- (c) *Compliance with Conditions.* Upon a conditional Zoning Map amendment taking effect, the use of the land shall conform thereafter to all of the requirements regulating use and development within the new zoning district as modified by any more restrictive provisions contained in the “Statement of Conditions”. Any person who establishes a development or commences a use upon land that has been rezoned with conditions shall continuously operate and maintain the development or use in compliance with all of the conditions set forth in the “Statement of Conditions”. Any failure to comply with a condition contained within the “Statement of

Conditions” shall constitute a violation of this Ordinance. Additionally, any such violation shall be deemed a nuisance per se and subject to judicial abatement as provided by law. No permit or approval shall be granted under this Ordinance for any use or development that is contrary to an applicable “Statement of Conditions”.

- (d) *Time period for conditions.* If approved with a time period for conditions, the City of Ypsilanti shall not add or alter the conditions during that time period. The landowner may request an extension of the time period from the City Council. Except if an extension is granted, the land shall revert to its former zoning classification if conditions are not satisfied within the approved time period.

Sec. 122-66. Resubmitted amendments.

No petition for an amendment which has been disapproved by the City Council shall be resubmitted for a period of one year from the date of disapproval, except as may be permitted by the Planning Commission after new and significant facts or conditions have been offered which might result in favorable action upon resubmission.

Secs. 122-67--122-90. Reserved.

ARTICLE III. ZONING BOARD OF APPEALS*

*Cross reference(s)--Boards and commissions, § 2-111 et seq.

State law reference(s)--Board of appeals, MCL 125.585 et seq., MSA 5.2935 et seq.

Sec. 122-91. Establishment and membership.

- (a) *Established.* There is hereby established a zoning board of appeals, which shall perform its duties and powers in accordance with Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.), as amended, and in such a way that the objectives of this chapter shall be observed, public safety secured, and substantial justice done.
- (b) *Membership.* The zoning board of appeals shall consist of five members appointed by the mayor with the City Council's consent. The members of the zoning board of appeals shall be residents of the city. No employee or contractor of the City Council may sit on the zoning board of appeals. One member of the zoning board of appeals shall also sit on the city Planning Commission. Each member of the zoning board of appeals shall hold office for a term of three years. Terms shall be staggered to provide for as nearly as possible the appointment of an equal number of members each year. Those persons now serving as members of the zoning board of appeals shall serve the balance of the terms for which they were appointed. All vacancies for unexpired terms shall be filled for the remainder of the term.
- (c) *Officers.* The zoning board of appeals shall annually elect its own chairperson and vice-chairperson. The terms of the chairperson and vice-chairperson shall be for a period of one year.
- (d) *Alternate members.* The mayor, with the City Council's consent, shall appoint two alternate members for the zoning board of appeals to sit as regular members of the zoning board of appeals in the absence of a regular member. If a regular member is absent from or unable to attend one or more consecutive meetings of the zoning board of appeals or for a period of more than 30 consecutive days, then alternate members may be called on a rotating basis to serve in the place of a regular member. For the purpose of reaching a decision on a case in which the regular member has abstained for reasons of conflict of interest, an alternate member may also be called. The alternate member having been appointed shall serve in the case until a final decision has been made. The alternate member shall have the same voting rights as a regular member of the zoning board of appeals.
- (e) *Meetings.* All meetings of the zoning board of appeals shall be held at the call of the chairperson and at such times as the zoning board of appeals

may determine. All hearings conducted by the zoning board of appeals shall be open to the public. Minutes shall be kept of each meeting and the zoning board of appeals shall record into the minutes all findings, conditions of approval, facts, and other relevant factors, and all its official actions. The vote of each member upon a question, or absence or abstention, shall be recorded into the minutes of the meeting.

- (f) *Rules and procedures.* The zoning board of appeals shall adopt general rules and regulations governing its procedure and may make rules for the filing of appeals and other matters requiring its attention which shall not cause reasonable delays in the transaction of its business.
- (g) *Abstention.* A member of the zoning board of appeals shall abstain from voting on any question on which he has a conflict of interest. Failure of a member to abstain in such cases shall constitute misconduct of office.
- (h) *Resignations.* When zoning board of appeals members propose to resign, if reasonably feasible, they shall give notice of their intent in writing to the chairperson, and make the date of resignation effective in such a manner as to allow time for appointment of replacements. Failure to attend three consecutive regular meetings, or three of seven consecutive meetings, without recorded consent of the chairperson shall be construed as resignation from the zoning board of appeals by absence. When a member dies or resigns (including resignation by absence), the chairperson shall promptly notify the mayor that a vacancy exists.

Sec. 122-92. Powers and duties.

- (a) The board of appeals shall hear and decide all questions and decisions regarding the following:
 - (1) Interpretation of the official Zoning Map, including the interpretation of the location of zoning district boundaries when in doubt.
 - (2) The interpretation of the language of this chapter when its meaning is unclear, or when there is uncertainty as to whether the language applies to a particular situation.
 - (3) The hearing of requests for nonuse variances from the strict application of the provisions of this chapter in accordance with section 122-94.
 - (4) The hearing of requests for appeals from any order, requirement, decisions, or

determination made by an administrative body or official charged with the enforcement of this chapter in accordance with section 122-95.

- (5) Hear and decide on any other matters referred to the zoning board of appeals or upon which the zoning board of appeals is required to pass under the terms of this chapter.
- (b) The zoning board of appeals shall not change the zoning district classification of any property or make any change in the terms of this chapter, and shall not take any action which would, as a result, make legislative changes in or negate any provisions of this chapter.
- (c) The zoning board of appeals shall not have authority to hear appeals on decisions made by the Planning Commission or City Council regarding planned unit developments.
- (d) The zoning board of appeals shall not have the authority to grant a use variance.

Sec. 122-93. General procedures.

- (a) *Hearings.* The zoning board of appeals shall hold a public hearing on each question submitted to it for decision. Such hearing shall be set within a reasonable time, not to exceed 45 days from the filing date of an appeal or variance request. Written notice of such hearing including the date, time, and place of the public hearing; the nature of the appeal; and a description of any property in question; shall be given to the appellant, if different than owner(s) of the property, to persons to whom real property is assessed within 300 feet of the boundary of the property subject to the request, regardless of whether the property or occupant is located within the boundaries of the City of Ypsilanti, and to the occupants of all structures within 300 feet of the premises. The notice shall be delivered personally or by mail, addressed to the respective owners and tenants at the address given in the last assessment roll. If a tenant's name is not known, the term "occupant" may be used. Notification need not be given to more than one (1) occupant of a structure, except that if a structure contains more than one (1) dwelling unit or spatial area owned or leased by different individuals, partnerships, businesses, or organizations, one (1) occupant of each unit or spatial area shall receive notice. In the case of a single structure containing more than four (4) dwelling units or other distinct spatial areas owned or leased by different individuals, partnerships, businesses or organizations, notice may be given to the manager or owner of the structure who shall be requested to post the notice at the primary entrance to the structure. The notice shall also be published in a newspaper of general

circulation in the city. All notices shall be given at least 15 days prior to the public hearing. An affidavit of mailing shall be filed with the zoning board of appeals prior to the public hearing. The zoning board of appeals may recess a hearing to gather additional information, to make site inspections, or to engage in other activities as may be necessary to make a proper decision. The zoning board of appeals shall reconvene the hearing within 35 days of the original hearing date. The reconvened hearing date shall be announced at the original hearing and this announcement shall constitute proper public notification.

- (b) *Decisions by the board of appeals.* The concurring vote of a majority of the entire membership of the zoning board of appeals (three votes) shall be necessary to reverse any order, requirement, or decision of any administrative official; to effect any variance in the non-use terms of this chapter; or to decide any matter upon which the zoning board of appeals is required to pass by this chapter. The concurring vote of two-thirds of the entire membership of the zoning board of appeals (four votes) shall be necessary to effect any variance from uses of the land permitted in this chapter.
- (c) *Time limit.* The zoning board of appeals shall decide upon all matters within 90 days from the filing date. The time limit may be extended by written agreement between the applicant or appellant and the zoning board of appeals.
- (d) *Representation.* Any person may appear on his own behalf at a hearing or may be represented by an agent or attorney.
- (e) *Conditions of approval.* The zoning board of appeals may attach conditions to any affirmative action as it deems reasonable to minimize any detrimental effects of its decisions and to promote the purposes of this chapter. Such conditions shall be in accordance with section 122-167 and Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.), as amended. A performance guarantee may be required as a condition of an affirmative action when in accordance with section 122-134.
- (f) *Official record.* The decisions and orders of the zoning board of appeals in disposing of an appeal or a request for a variance, along with any conditions attached, shall be entered into the official record for each case. Such record shall include the reasons for a determination, a summary of the evidence introduced, and the reasons for any conditions imposed.

Sec. 122-94. Variances.

- (a) *Application.* An application for a variance to the provisions of this chapter shall be filed with the city planner's office by the record owner of the property in question or by a person authorized to act on the record owner's behalf. The application shall consist of a completed application form, fee, and the following information:
- (1) Name, address, and telephone number of the applicant and property owner; and the interest of the applicant in the property.
 - (2) Legal description, address, and tax parcel number of the subject property.
 - (3) An accurate, scaled drawing of the property, showing all property lines and dimensions correlated with the legal description; the location and dimensions of all existing and proposed structures and uses on the property; any roads, alleys, easements, drains, or waterways which traverse or abut the property; and the lot area and setback dimensions necessary to show compliance with the regulations of this chapter. In most cases, a site plan or sketch plan will meet this requirement (see Section 122-126 for site plan requirements and subsection 122-126(19) for sketch plan).
 - (4) Other reasonable information deemed necessary by the zoning board of appeals in order to make a proper decision.
- (b) *Standards for variances.* A variance from the literal enforcement of this chapter may be granted by the zoning board of appeals only if all of the following standards are met:
- (1) Literal enforcement of this chapter will pose practical difficulties to the applicant because of special conditions or circumstances which are unique to the specific property such as: exceptional shallowness or shape of the property, exceptional topographic conditions, extraordinary situation of a building or structure, use or development of an adjacent property, or difficulties relating to construction or structural changes on the site. Mere inconvenience or a desire to attain higher financial return shall not itself be deemed sufficient to warrant a variance.
 - (2) Such variance is necessary for the preservation and enjoyment of a substantial property right enjoyed by other property owners in the same district under the terms of this chapter. Granting of the variance shall not confer upon the applicant any special privilege that is denied by this chapter to other lands, structures, or buildings in the same district.
 - (3) The alleged practical difficulties on which the variance request is based have not been created by any person presently having an interest in the property.
 - (4) The granting of the variance will not be detrimental to the public welfare or injurious to other property or improvements in the neighborhood in which the property is located.
 - (5) The allowance of the variance will result in substantial justice being done, considering the public benefits intended to be secured by this chapter, the individual hardships that will be suffered by a failure of the zoning board of appeals to grant the variance, and the rights of others whose property would be affected by the allowance of the variance.
 - (6) A variance granted shall be the minimum variance that will make possible a reasonable use of the land, buildings, or structure.
- (c) *Variances; reapplication.* An application for a variance which has been denied wholly or in part by the zoning board of appeals shall not be resubmitted for a period of one year from the date of denial, except on grounds of new evidence of changed conditions found by the zoning board of appeals to be valid. The zoning board of appeals shall review any subsequent application for a variance on the conditions and circumstances which exist at the time of the subsequent application.
- (d) *Variance to run with land.* A variance shall run with the land and shall not become void if property is sold to a new owner. However, a variance shall become null and void if no building permit or no construction is started within one year of the approval date of the variance (see section 122-97).

Sec. 122-95. Appeals.

- (a) *Questions first go to administrative official.* All questions concerning administrative decisions under this chapter shall first be presented to the applicable city official or agency. Such questions shall be presented to the zoning board of appeals only on appeal from the decisions of the applicable city official or agency.
- (b) *Filing appeal.* Appeals may be commenced by a person aggrieved or by any officer, department, board, agency, or bureau of the city, county, state, or federal governments by filing a notice of appeal with the City Planner's office. The notice of appeal shall be signed, shall specify the requirement or decision from which the appeal is made, and shall state the specific grounds on which the appeal is based. The applicable fee shall

be submitted with the notice of appeal; such fee shall be nonrefundable. Appeals shall be filed within 60 days of the decision in question.

- (c) *Stay of action.* An appeal stays all proceedings in the furtherance of the action appealed from unless the building department certifies to the zoning board of appeals after the notice is filed that, by reason of facts stated in the certificate, a stay would cause imminent peril to life or property. In such case, proceedings shall not be stayed other than by a restraining order which may be granted by the Zoning Board of Appeals or by circuit court, following written request, notice to the officer or body from whom the appeal is taken, and due cause shown.
- (d) *Power to subpoena.* The zoning board of appeals shall have the power to subpoena witnesses; administer oaths; compel testimony; and require the production of reports, papers, files, and other evidence pertinent to the matters before it.
- (e) *Decisions regarding appeals.* The zoning board of appeals may, so long as such action is in conformity with the terms of this chapter, reverse or affirm, wholly or partly, or may modify the order, requirement, decision, or determination from which an appeal is sought. To that end, the zoning board of appeals shall have the powers of the public official or body from whom the appeal is taken.

Sec. 122-96. Decisions final.

All decisions of the zoning board of appeals are final. However, a person having an interest aggrieved by a decision may appeal to the circuit courts, as provided in Act No. 110 of the Public Acts of Michigan of 2006 (MCL 125.3101 et seq.), as amended. Such an appeal must be filed within 30 days after the zoning board of appeals certifies its decision in writing or approves the minutes of its decision.

Sec. 122-97. Time limitations.

If a variance or other requested action is granted or authorized, the necessary permits shall be obtained and any authorized actions shall be begun within one year following the date of such variance or authorization and shall be completed as authorized by the permit or elsewhere in this chapter. Should the applicant/appellant fail to obtain such permits or fail to commence work within such subsequent period, it shall be presumed that the applicant/appellant has waived, withdrawn, or abandoned his appeal; and all permissions, authorizations, variances, and permits shall be deemed to be rescinded.

Sec. 122-98. Fees.

The City Council may prescribe and amend by resolution a reasonable schedule of fees to be charged to applicants for appeals or variances requested from zoning board of appeals. Fees shall be paid at the time of application and shall be nonrefundable. Fees shall be placed in the general revenue fund of the city.

Secs. 122-99--122-120. Reserved.

ARTICLE IV. SITE PLAN REVIEW*

*State law reference(s)--City may require the submission and approval of a site plan before authorization of a land use or activity regulated by a zoning ordinance, MCL 125.584d, MSA 5.2934(4).

Sec. 122-121. Purpose.

- (a) The purposes of site plan review are as follows:
- (1) To determine compliance with the provisions of this chapter;
 - (2) To promote the orderly development of the city, to prevent the depreciation of land values through uses or structures which do not give proper attention to site or area protection; and
 - (3) To provide consultation and cooperation between the applicant and the city in order to accomplish the developers objectives in harmony with the spirit and intent of this chapter.
- (b) The site plan review procedures and standards in this article are intended to provide a consistent and uniform method of review of proposed development plans. Through the application of these regulations, the attainment of the city master plan will be assured, and the city will develop (or redevelop) in an orderly fashion.

Sec. 122-122. Requirement for Zoning Compliance Review

- (a) Zoning compliance review shall be required for the activities or uses listed in the table below. Zoning compliance is required for certain site or building activities not complicated enough to warrant site plan review. Zoning compliance review shall be approved by the city planner or designee.

Activity/Use	Regulations
New Construction	
Building permit for single & 2 family dwelling on individual lot, except if limited building type	Zoning district regulations
Building permit for accessory dwelling unit	Zoning district regulations
Expansion/Modification to Existing Principal or Residential Buildings	
Building permit for building expansion of single or two family dwelling on individual lot	Zoning district regulations
Building permit for building expansion of accessory dwelling unit	Zoning district regulations
Change in Use	
Reuse of an existing building where no building expansion is proposed and the City Planner determines the new use is similar or less intense in terms of parking, traffic generation, drainage, utility needs, noise, aesthetics and other external effects	Zoning district regulations
Temporary uses, buildings & structures	Section 122-35
Accessory Structures & Site Improvements	
Accessory buildings, structures, and off-street parking for single- and two-family dwelling units on individual lots	Zoning district regulations
Accessory buildings less than 250 square feet	Zoning district regulations
Expand/modify parking lot with existing or proposed ten (10) or less spaces that does not result in drainage alterations, changes in circulation patterns or access, or addition or replacement of base or subgrade with no requests for exceptions allowed in this Chapter	Article XIII
Community Garden	Section 122-815
Infrastructure and paving improvements including sidewalks, bicycle facilities and pathways	Section 122-647
Construction, relocation or erections of signs, screening walls, trash receptacles, fences, walls, lights, poles, cooling/heating or other mechanical equipment	Signs must comply with Article XIV; screening wall, fences and walls with Section 122-713; trash receptacles with Section 122-650
Swimming pools	Section 122-668

Sec. 122-123. Requirement for and Authority to Review Site Plans

- (a) Site plan review shall be required for the activities or uses listed in the table below. The city planner, Planning Commission or City Council shall have the authority to review and to approve, approve with conditions, or deny site plan applications as provided in this Ordinance, when an “X” is in the table below. Any decision made by the City Council shall be based upon recommendation by the Planning Commission.

Activities or uses	City Council	Planning Commission	City Planner
New Construction			
Site plan for essential services, electrical substations, private utilities and similar uses			X
New construction with no requests for exceptions allowed by this Chapter and not a limited building type			X
Site plan for new construction where the building encroaches into the required setback from a planned easement for a street		X	
Site plan for new construction with request for exceptions allowed by the Chapter		X	
Site plan for new construction of limited building types in a zoning district		X	
Special Land Use		X	
Subdivisions (site condominiums & plats)	X	Recommend	
Conditional Rezoning	X	Recommend	
Planned Unit Development (PUDs)	X	Recommend	
Expansion / Modification to Existing Principal or Residential Buildings			
Site plan for building expansion with no requests for exceptions allowed by the Chapter			X
Site plan for building expansion where the building encroaches into the required setback from a planned easement for a street		X	
Site plan for building expansion with request for exception allowed by this Chapter		X	
Expansion/intensification of a special land use		X	
Change in Use			
Reuse of an existing building where no building expansion is proposed and the City Planner determines the new use is similar or less intense in terms of parking, traffic generation, drainage, utility needs, noise, aesthetics and other external effects			X
Change of land or building to a more intensive use, as determined by the City Planner that may involve substantial change in parking, traffic flow, hours of operation, public services, effluent discharge, or substantial alteration of the physical character of the site and no requests for exceptions under this Chapter			X
Change of land or building to a more intensive use, as determined by the City Planner that may involve substantial change in parking, traffic flow, hours of operation, public services, effluent discharge, or substantial alteration of the physical character of the site, with request for exception allowed by this Chapter		X	
Change in use to special land use		X	
Accessory Structures & Site Improvements			
Accessory buildings, except for those uses noted above, 250 square feet or more			X
New parking lot and/or garage with no requests for exceptions allowed in this Chapter			X
Modify parking lot that results drainage alterations, changes in circulation patterns or access, or addition or replacement of base or subgrade with no requests for exceptions allowed in this Chapter			X
Expand/modify parking lot to with existing or proposed 11spaces or more with no requests for exceptions allowed in this Chapter			X
New parking lot and or garage, or expand/modify existing parking lot with requests for exceptions allowed in this Chapter		X	

- (b) *Deferral to Planning Commission.* The city planner may defer approval of any site plan to the Planning Commission.
- (c) *Planning Commission review.* The Planning Commission in its entirety may review and approve site plans, or the Planning Commission may designate a subcommittee of no less than three of its members to review and/or approve site plans.

Sec. 122-124. Site Plan Review Checklist

- (a) *Site Plan Review Checklist Development.* The city planner shall draft a site plan review checklist, which shall be reviewed and approved by the Planning Commission. The city planner shall update the site plan review checklist at least once every three (3) years or earlier, if deemed necessary. All changes shall be approved by the Planning Commission.
- (b) *Transmission to Planning Commission.* The review checklist for all site plans shall be transmitted to the Planning Commission, no matter which body is the approving authority, in accordance the process procedure in Section 122-125.

Sec. 122-125. Application procedure; contents.

- (a) An application for site plan review shall be made to the city planner along with a fee as required by the City Council. The application shall, at a minimum, contain the following information:
 - (1) The applicant's name, address and phone number.
 - (2) Proof that the applicant is the owner of the property or has a legal or financial interest in the property, such as a purchase agreement.
 - (3) The name, address and phone number of the owner of record if different from the applicant.
 - (4) The address and/or parcel number of the property.
 - (5) Brief project description, including number of structures and dwelling units, square footage of each building, number of parking spaces, estimated number of employees, and any unique features of the site or proposed development.
 - (6) Area of the parcel in acres, excluding street rights-of-way.
 - (7) A site plan for the project containing all of the information listed in section 122-126.

See item b of this sub-section for type and number of copies.

- (b) For all site plan submittals, four (4) paper copies drawn at a minimum scale of one inch equals 200 feet and one (1) electronic copy of the site plan shall be submitted. If the site plan will go to the Planning Commission for review, the city planner may require that up to 12 paper copies at a smaller scale than required above on a minimum size of 11 inch by 17 of the site plan be provided by the applicant.
- (c) The city planner shall review all application materials. If such materials are incomplete, they shall be returned to the applicant.

Sec. 122-126. Site plan content.

Each site plan submitted for review under this chapter shall be drawn at a minimum scale of one inch equals 200 feet and shall contain the following information:

- (1) Name of development, scale, north arrow, date of original drawing and any revisions, and general location map showing major thoroughfares and site location.
- (2) Name, address and phone number of the site owner, developer and plan designer, and the professional seal of the designer.
- (3) The area of the site in square feet and acres, excluding all existing and proposed rights-of-way. Property lines, dimensions, and building setback distances and dimensions of all structures and lot lines within 50 feet of the site shall also be indicated. If the parcel is a part of a larger parcel, boundaries of the total land holding shall be shown.
- (4) Existing zoning of the site and all adjacent properties.
- (5) Direction of stormwater drainage, ground elevations of all existing buildings, drives and parking lots, and any unusual surface conditions shall be provided. Indicate any areas located within floodplains.
- (6) Location of existing and proposed buildings; their intended use; the length, width and height of each building; and the square footage of each building. The location and dimensions of any open air uses shall also be provided, such as recreational fields, outdoor cafes, or open air sales areas.
- (7) Location of abutting streets, existing and proposed rights-of-way, service drives, curb cuts, and access easements serving the site, as well as driveways opposite the site and all

driveways within 100 feet of the site. The centerline of road rights-of-way shall be shown.

- (8) Proposed parking areas and access drives, showing the number and size of spaces, aisles, loading areas, and handicapped access ramps. Also, the proposed method of surfacing such areas shall be noted.
- (9) Building floor plans and architectural wall elevations. The height of all buildings or structures shall be indicated.
- (10) Landscape plan in accordance with Article XI, division 4, of this chapter, which indicates type and size of all plant material, including all areas to be sod or seeded for grass. Cross sections of all proposed berms shall be provided. Existing vegetation which is to be retained on the site shall be illustrated.
- (11) Location of all proposed accessory structures, including fences or walls, outdoor lighting fixtures (including photometric study to demonstrate compliance with section 122-641), outdoor communication devices, flagpoles, storage sheds, transformers, dumpsters or trash removal areas, and signs. Also show the location of all sidewalks or pathways, fire hydrants, existing and proposed utility poles, utility easements, and drainways.
- (12) Location of all outdoor storage areas for materials and the manner in which materials shall be screened and/or covered.
- (13) Location and specifications for any existing or proposed above or below ground storage facilities for any chemicals, salts, flammable materials, or hazardous materials as well as any containment structures or clear zones required by this chapter or other state or federal agencies.
- (14) If phased construction is to be used, each phase must be noted and each phase must stand on its own.
- (15) Notation of any variances or special use permits which are required, any legal nonconforming uses or structures, and any state or federal permits which have been secured or may be necessary to secure.
- (16) Locations of all planned easements for non-motorized pathways in the City of Ypsilanti's Non-Motorized Plan, a 50 to 100 foot conservation and /or access easement along any Huron River frontage and any planned road easement expansions approved by City Council.
- (17) For proposals in the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, the following information shall be provided:
 - a) *Circulation Plan Requirements.* For proposed development less than three acres in size, a circulation plan shall be submitted which identifies potential cross- and joint-access to adjacent parcels, the existing block layout. The block shall be defined as lots and/or all contiguous lots shall be considered to be part of a block for this purpose. Pedestrian accommodations and alternative transportation modes shall be reflected in the submitted circulation plan, as required by Section 122-647. The street trees, as required by Section 122-704 will also be required to be applied to existing streets.
 - b) *Block Plan Requirements.* When a proposed development is three acres or greater, a block plan shall be submitted. The block plan must show the street layout, proposed parking areas and access drives, showing the number and size of spaces, aisles, loading areas, and handicapped access ramps. The proposed method of surfacing such areas shall be noted.
 - c) the building type
 - d) the building lot configuration
 - e) the parking location
- (18) Other data which the Planning Commission, city planner, or consulting engineer may deem reasonably necessary for adequate review.
- (19) The approving body, Planning Commission or city planner, may grant waivers of data requirements when specific data is deemed unnecessary in determining compliance of a site plan with the regulations or standards of this chapter. For zoning compliance reviews or site plans approved by the City Planner, the City Planner may allow a sketch plan, defined as a scaled drawing based on a legal survey containing less information than a site plan; drawn in compliance with this Ordinance but not required to be prepared by a licensed professional. Sketch plans shall contain the following information:
 - a) Name of development, scale, north arrow, date of original drawing and any revisions.
 - b) Name, address and phone number of the site owner, developer and/or plan designer.
 - c) The area of the site in square feet or acres.
 - d) Existing zoning of the site and all adjacent properties.

- e) Location and setbacks of existing and proposed buildings; their intended use; the length, width and height of each building; and the square footage of each building. The location and dimensions of any open air uses shall also be provided, such as recreational fields, outdoor cafes, or open air sales areas.
- f) Location of abutting streets, existing rights-of-way, service drives, curb cuts, and access easements serving the site, as well as driveways opposite the site.
- g) Parking areas and access drives, showing the number and size of spaces, aisles, loading areas, and handicapped access ramps.
- h) Landscape plan in accordance with Article XI, division 4, of this chapter, which indicates type and size of all plant material, including all areas to be sod or seeded for grass. Existing vegetation which is to be retained on the site shall be illustrated.
- i) Location of all proposed and existing accessory structures, including fences or walls, outdoor lighting fixtures, outdoor communication devices, flagpoles, storage sheds, transformers, dumpsters or trash removal areas, and signs. Also show the location of all sidewalks or pathways, fire hydrants, and utility poles.
- j) Location of all outdoor storage areas for materials and the manner in which materials shall be screened and/or covered.
- k) Notation of any variances or special use permits which are required, any legal nonconforming uses or structures, and any state or federal permits which have been secured or may be necessary to secure.
- l) For proposals in the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, the following information shall be provided:
 - 1) *Circulation Plan Requirements.* For proposed development less than three acres in size, a circulation plan shall be submitted which identifies potential cross-and joint-access to adjacent parcels, the existing block layout. The block shall be defined as lots and/or all contiguous lots shall be considered to be part of a block for this purpose. Pedestrian accommodations and alternative transportation modes shall be reflected in the submitted circulation plan, as required by Section 122-

647. The street trees, as required by Section 122-704, will also be required to be applied to existing streets.

- 2) the building type
- 3) the building lot configuration
- 4) the parking location

m) Other data which the Planning Commission, city planner, or consulting engineer may deem reasonably necessary for adequate review.

Sec. 122-127. Review procedure and authorization.

All site plans required under this article shall be subject to review as follows:

- (1) *Pre-application conference required for new construction.* For any new construction, the applicant/property owner must attend a pre-application conference to be coordinated by the city planner. This meeting may include the building official, city attorney, city engineer, fire inspector, police chief, city manager, economic development official, Planning Commission member(s) and City Council member(s) and any other government official deemed applicable. The city planner may consult with any of the above offices and share input at the conference. The applicant shall not be bound by the plan reviewed in a pre-application conference, nor shall the any approving authority be bound by any such conference.
- (2) *Distribution of plans/department of community and economic development.* Upon submission of all required application materials, the site plan proposal shall, when applicable, be placed on the Planning Commission agenda for review. Before the Planning Commission meeting, the site plan and application shall be reviewed for comment by the city department of community and economic development and any other city officials deemed necessary. The plan may also be submitted to the city engineer or city attorney for review.
- (3) *Authorization.* The city planner, or when applicable the Planning Commission (as per section 122-123), shall have the power to approve, approve subject to conditions, or deny any site plan submitted to it under this chapter. The Planning Commission may also table consideration of a site plan until a later meeting. The applicant shall be advised of any action in writing. A building permit shall not be issued until a site plan has been approved as required in this chapter.

- (4) *Review period.* The city planner or Planning Commission shall render a decision on a site plan within 65 days of its initial review of the site plan, unless an extension of time is agreed to by the city planner or Planning Commission and the applicant.
- (5) *Review standards.* The city planner or Planning Commission shall review each site plan according to the standards for site plan review as contained in section 122-128 and any other applicable regulations of this chapter. In addition, the city planner or Planning Commission shall consider the findings and recommendations of the department of community and economic development, and is empowered to seek the review and recommendation of appropriate county, state or federal agencies, or other professionals, consultants, or agencies deemed necessary to assist in the review.
- (6) *Signature of approval.* Upon approval of a site plan, three paper copies of the plan and one electronic copy shall be signed and dated by the city planner or the chair of the Planning Commission. If approval is subject to conditions, such conditions shall also be written on each of the site plans. One paper copy of the plan shall be retained by the applicant, one paper copy of the plan shall be retained by the city planner's office, and one paper and one electronic copy of the plan shall be submitted to the building department as part of the building permit review process.
- (7) *Effect of approval.* Approval of a site plan authorizes issuance of a certificate of zoning compliance and issuance of a building permit, provided all other requirements for a building permit have been met. In the case of uses without buildings or structures, approval of a final site plan authorizes issuance of a certificate of zoning compliance and issuance of a certificate of occupancy, provided all other requirements for such certificates have been met.
- (8) *Expiration of approval.* Approval of a site plan shall expire and be of no effect unless a building permit shall have been issued within one (1) year of the date of the site plan approval. Approval of a site plan shall expire and be of no effect two years following the date of approval unless construction has begun on the property and is diligently pursued to completion in conformance with the approved site plan.

Sec. 122-128. Standards for site plan review.

Site plans shall be reviewed for compliance with the following general standards:

- (1) The applicant is eligible to legally apply for site plan review, and all required information has been provided.
- (2) The proposed site plan conforms with all the provisions and requirements, as well as the spirit and intent of this chapter and the Master Plan. The proposed development will meet all the regulations of the zoning district in which it is located.
- (3) All elements of the site plan shall be harmoniously and efficiently organized in relation to the character of the proposed use, the size and type of lot, the size and type of buildings, and the character of the adjoining property. The site shall be so developed as not to impede the normal and orderly development or improvement of surrounding property for uses permitted in this chapter.
- (4) With respect to vehicular and pedestrian circulation on the site, including walkways, interior drives, and parking; circulation shall to the extent possible create potential cross-and joint-access to adjacent parcels and the existing block layout. Special attention shall be given to the location, number and spacing of ingress and egress points; general interior circulation including turnaround areas; adequate provisions for delivery of services (trash removal, school buses, mail and parcel delivery); separation of pedestrian and vehicular traffic; avoidance of building corners next to access drives; identification of addresses; storage of plowed snow; and arrangement of parking areas that are safe and convenient, and insofar as practicable, do not detract from the design of the proposed buildings and structures, neighboring properties, pedestrian and bicyclist safety, access to transit and flow of traffic on adjacent streets. All buildings or groups of buildings shall be so arranged as to permit adequate access by emergency vehicles as required by the city building code.
- (5) Streets are designed in context with the urban form and continue the established pattern of the surrounding area.
- (6) Adequate services and utilities including sanitary sewers shall be available or provided, with sufficient capacity to properly serve the development. Appropriate measures will be taken to ensure that site drainage will not adversely affect adjoining properties or the capacity of the public storm drainage system, or

nearby bodies of water. Provisions shall be made to accommodate stormwater and prevent soil erosion. All stormwater management facilities, including but not limited to storm sewers and detention/retention facilities, shall be designed in accordance with the "Rules of the Washtenaw County Water Resources Commissioner," together with any special provisions established by the city.

- (7) Natural resources will be protected to the maximum feasible extent. The proposed development will not cause soil erosion or sedimentation problems, and will respect floodways or floodplains on or in the vicinity of the subject property.
- (8) The site plan shall provide reasonable visual and sound privacy for all dwelling units on or adjacent to the property. Fences, walks, barriers, and landscaping shall be used, as appropriate, for protection and enhancement of the property. All outdoor storage of materials, loading and unloading areas, and refuse containers shall be screened or located so as not to be a nuisance. Outdoor lighting shall be shielded so as to not adversely affect neighboring properties or traffic on adjacent streets.
- (9) Separate phases of development shall be in logical sequence, and each phase shall stand alone so that no one phase will depend upon a subsequent phase for adequate access, public utility services, drainage, or other improvements.
- (10) Site plans shall conform to all applicable requirements of state and federal statutes, including health and pollution laws, fire or explosion hazards, toxic and hazardous materials, and barrier-free requirements. Site plan approval may be conditioned on the applicant receiving necessary county, state, or federal permits before a local building permit or occupancy permit is granted.
- (11) An objective of site plan review shall be to protect and promote public health, safety, sustainability and general welfare. It is also the intent of site plan review to improve the quality of existing developments as they are expanded, contracted, or redeveloped in keeping with sound site development standards of this chapter and city master plan.

Sec. 122-129. Issuance of building permit.

The building department shall, upon receipt of notice of approval from the Planning Commission or city planner and upon application by the applicant, issue a building permit provided all other applicable city regulations have been met.

Sec. 122-130. Amendment of approved site plan.

- (a) A site plan may be amended upon application and in accordance with the procedures and requirements provided in section 122-125.
- (b) Minor changes to a site plan may be made without following the procedures of section 122-125 at the discretion of the city planner. The original approving body shall have the authority to determine if a proposed change is minor or major and if such change requires an amendment to an approved site plan. A sketch plan, meeting the requirements of Section 122-126(19), may be allowed by the original approving body for submission for review for a minor or major revision.
- (c) Major revisions would include, but not be limited to, increases in scope or density of use, land area, or building size; the addition of uses not authorized by the original site plan approval; the rearrangement or relocation of buildings or structures; changes in the character or function of drives, parking areas, and landscaping; or changes in the concept of the development.
- (d) A record of such determinations and reasons for allowing any minor amendment shall be recorded in writing. In the case of minor changes to an approved site plan, two paper copies and one electronic copy of the revised site plan or sketch plan drawing shall be submitted by the applicant showing such minor changes for purposes of city record.

Sec. 122-131. Modification of plan during construction.

All site improvements shall conform to the approved site plan. If the applicant makes any changes during construction in the development in relation to the approved site plan, such changes shall be made at the applicant's risk, without any assurance that the Planning Commission or city planner will approve the changes. It shall be the responsibility of the applicant to notify the city building department and the city planner of any changes. The building department, the city planner, or the Planning Commission, whichever is applicable, may require the applicant to correct the changes so as to conform to the approved site plan.

Sec. 122-132. As-built drawings.

Upon completion of the installation of required improvements as shown on an approved site plan, the property owner shall submit to the building department an electronic and paper "as-built" site plan, certified by an engineer or architect, at least one week prior to the anticipated occupancy of any building. A certificate of occupancy shall be withheld by the building department in any case where the site plan and major conditions as approved by the Planning Commission or city planner have not been complied with and a performance guarantee has not been issued for incomplete improvements in accordance with 122-134.

Sec. 122-133. Phasing of development.

- (a) The applicant may divide the proposed development into two or more phases. In such case, the site plan shall show the entire property involved and shall clearly indicate the location, size, and character of each phase. However, complete site plans for all phases of a project need not be provided at once. Subsequent site plans may be submitted for review and approval for each phase as the project proceeds.
- (b) Each phase of a project shall stand on its own. No phase shall rely on the completion of any subsequent phases of the project for parking, utilities, landscaping, or any other element required by this chapter.

Sec. 122-134. Performance guarantee.

- (a) *Purpose.* To ensure faithful compliance with the provisions of this chapter and any conditions imposed thereunder, a performance guarantee may be required by city staff, the Planning Commission, or when appropriate the City Council to be deposited with the city. Improvements for which a performance guarantee may be required include, but are not limited to, landscaping, berms, screening, lighting, surfacing of drives, parking, traffic control devices, water or sewer line expansions, sidewalks, drainage, and other improvements.
- (b) *General requirements.* A performance guarantee may be in the form of a bond, irrevocable bank

letter of credit, cash deposit, or other form of security. Such guarantee shall be provided to the city clerk, and shall be provided any time after a site plan has been approved.

- (c) *Amount.* The amount of the performance guarantee shall be 100% of the cost of the improvements associated with the performance guarantee. Accordingly, the applicant shall provide an itemized cost estimate of the improvements, and such estimate shall be verified by the building department. The form of the guarantee shall be approved by the city attorney.
- (d) *Failure to complete improvements.* If the applicant should fail to provide any of the site improvements according to the approved site plans within the time period specified in the guarantee, the performance guarantee shall be forfeited. The city shall rebate a proportional share of cash deposits only when requested by the depositor, based on the percent of improvements completed, as attested to by the depositor and verified by the building department. In cases where the provisions of this article have not been met, the amount of the aforementioned performance guarantee shall be used by the city to complete the required improvements and the balance, if any, shall be returned to the applicant.

Sec. 122-135. Fees.

Fees for the review of site plans and inspections as required by this article shall be established and may be amended by resolution of the City Council.

Sec. 122-136. Record of approval.

An approved site plan shall become part of the record of approval, and subsequent action relating to a site in question shall be consistent with the approved site plan, unless the city planner (or Planning Commission, as applicable) agrees to such changes as provided in this article. Any violation of the provisions of this article, including any improvement not in conformance with the approved final site plan, shall be deemed a violation of this chapter and shall be subject to all penalties therein.

Secs. 122-137--122-160. Reserved.

ARTICLE V. SPECIAL LAND USE REVIEW*

*State law reference(s)--Special land uses, MCL 125.584a, MSA 5.2934(1).

Sec. 122-161. Statement of intent.

- (a) The formulation and execution of this chapter is based upon the division of the city into districts, within each of which certain specified, mutually compatible uses are permitted by right, and the bulk and location of buildings and structures are substantially uniform. It is recognized, however, that there are certain uses which, because of their unique characteristics, cannot be properly classified in any particular district without special consideration. Such uses are essential or desirable for the welfare of the community and are essentially appropriate and not incompatible with the uses permitted by right in a zoning district; but not at every location therein, or without restrictions or conditions being imposed by reason of special problems presented by the use or its particular location in relation to neighboring properties.
- (b) This article requires special approval of such uses. The procedures and standards in this article are intended to provide a consistent and uniform method for review of proposed plans for special land uses.

Sec. 122-162. Authority to grant permits.

The city Planning Commission shall have the authority to approve special uses and to attach conditions to any approved special use. Only those uses specifically listed as special uses in this chapter shall be considered for special use review and approval, except as provided for unclassified uses in Section 122-651.

Sec. 122-163. Application; contents.

- (a) An application for a special use permit shall be made by filing an application form, containing the required information, and fee with the city planner's office. The fee shall be set by resolution of the City Council. No part of the fee shall be returnable to the applicant. An application for a special use permit shall contain the following information:
 - (1) The applicant's name, address, and telephone number; and the names and addresses of all record owners and proof of ownership.
 - (2) The applicant's interest in the property and, if not the fee simple owner, a signed authorization from the owner for the application.
 - (3) Legal description and address of the property.
 - (4) Reference to the section of this chapter under which the special land use permit is sought.

- (5) A description of the proposed use of the property.

- (6) A site plan, which shall include all of the information required by this chapter in section 122-126. For special land uses to occupy an existing building with no building additions, the City Planner may allow a sketch plan, defined as a scaled drawing based on a legal survey containing less information than a site plan; drawn in compliance with this Ordinance but not required to be prepared by a licensed professional with the minimum requirements in as defined in Section 122-126(19).

- (b) A public hearing by the Planning Commission shall be scheduled for within 65 days of the filing date of an application for a special use permit. The applicant or designated representative shall be present at the public hearing and any other scheduled review meetings on the proposal. Otherwise, consideration of the proposal may be tabled due to lack of representation.

Sec. 122-164. Public hearing.

- (a) *Notification requirements.* A notice of a public hearing shall be published in a newspaper of general circulation in the city and shall be sent by mail or personal delivery to the owners of property for which approval is being considered, to all persons to whom real property is assessed within 300 feet of the boundary of the property in question, and to the occupants of all structures within 300 feet. The notice shall be given not less than 15 days before the date of the public hearing. If the name of an occupant is not known, the term "occupant" may be used in making notification. Notification need not be given to more than one occupant of a structure, except if a structure contains more than one dwelling unit or spatial area owned or leased by different individuals, partnerships, businesses, or organizations, one occupant of each unit or spatial area shall receive notice. In case of a single structure containing more than four dwelling units or other distinct spatial areas owned or leased by different individuals, partnerships, businesses, or organization, notice may be given to the manager or owner of the structure who shall be requested to post the notice at the primary entrance to the structure.
- (b) *Contents of notification.* The notice shall include the following:

- (1) Description of the nature of the special use request.
- (2) A legal description or address of the property which is the subject of the special use request.
- (3) Statement of when and where the public hearing will be held.
- (4) Statement of when and where comments will be received concerning the request.

Sec. 122-165. Standards for reviewing special use requests.

- (a) Following the public hearing, the Planning Commission shall review the application for the special land use proposal, together with the public hearing findings and any reports or recommendations of the city planner, department of community and economic development, city attorney, city building inspector, or other reviewing agencies.
- (b) Approval of a special land use permit shall be based on the determination that the following standards are met:
 - (1) The proposed use conforms with all the provisions and requirements of this chapter, including site plan review standards (section 122-128) and the applicable site development standards for the specific use, as well as the spirit and intent of this chapter and the Master Plan. The location, scale, and intensity of the proposed use shall be compatible with adjacent uses and the zoning of the land. Height, location and size of buildings shall be compatible with uses and buildings on adjacent properties. The intensity of the proposed use, such as volume, frequency and times of operation, and its compatibility shall be considered.
 - (2) The proposed use shall promote the use of land in a socially and economically sustainable manner and shall not be detrimental, hazardous, or disturbing to existing or future neighboring uses, persons, property or public welfare. Noise, odor, smoke and potential contamination of air, soil and water and its potential effect on neighboring uses, persons and property, as well as public welfare, shall be considered.
 - (3) The proposed special land use shall be designed, constructed, operated and maintained to assure long-term compatibility with surrounding land uses. Consideration shall be given to the placement, bulk, and height of structures; materials used in construction; location and screening of

parking areas, driveways, outdoor storage areas, outdoor activity areas, and mechanical equipment; nature of landscaping and fencing; and hours of operation.

- (4) The proposed special land use shall not present unreasonable adverse impacts on the transportation system. Consideration shall be given to the estimated pedestrian, bicycle and vehicular traffic generated by such use, access to transit, proximity to major thoroughfares, proximity to intersections, required vehicular turning movements, and provisions for pedestrian and bicycle traffic.
- (5) The proposed use shall not create additional requirements at public cost for public facilities and services that will be detrimental to the economic sustainability of the community.
- (6) Within the MD district, the proposed special land use will help to allow residents to access everyday needs by foot, if a similar service is not currently provided within a quarter mile walking distance.

Sec. 122-166. Planning Commission action.

The Planning Commission must approve, approve with conditions, or deny a special use permit application. The Planning Commission's decision, the basis for the decision, and all conditions imposed, must be described in a written statement which must be made a part of the record of the meeting.

Sec. 122-167. Conditions of approval.

- (a) Reasonable conditions may be required in conjunction with an approval. The conditions may include conditions necessary to ensure that public services and facilities affected by a proposed land use or activity will be capable of accommodating increased service and facility loads caused by the land use or activity, to conserve natural resources and energy, to ensure compatibility with adjacent uses of land, and to promote the use of land in a socially and economically desirable manner. Conditions imposed must do all of the following:
 - (1) Be designed to protect natural resources, the health, safety, and welfare, as well as the social and economic well-being.
 - (2) Be related to the valid exercise of police power and purposes which are affected by the proposed use or activity.
 - (3) Be necessary to meet the intent and purposes of this chapter, be related to standards established in this chapter, and be necessary to ensure compliance with those standards.

- (b) Failure by an applicant to comply with any such conditions must be considered a violation of this chapter and grounds for Special Use Permit revocation. Conditions of approval must remain unchanged except upon mutual consent of the city Planning Commission and the landowner. Any such changes must be recorded in the minutes of the City Planning Commission meeting at which the action occurred.

Sec. 122-168. Duration of special use approval.

- (a) Approval of a Special Use Permit must expire and be of no effect unless a building permit has been issued within six months of the date of approval, and unless construction has begun within two years of the date of approval and diligently pursued to completion in conformance with all approved plans and conditions attached thereto. Expiration of a special use permit may be extended one time by the Planning Commission for a period of six months; otherwise, a new application for an expired special use permit must be filed.
- (b) Once a special use is established, special use permits must run with the land and must not be issued for specified periods, unless the use is clearly temporary or time-related in nature. Special Use Permits may be revoked by the Planning Commission in accordance with Section 122-170.

Sec. 122-169. Amendments to special land uses.

When an application is received to expand the use, change the traffic pattern, or otherwise alter elements of a special land use, the application must be subject to the same procedures followed for an original special approval of land use.

Sec. 122-170. Revocation of special land use approval.

Approval of a special land use permit may be revoked by the Planning Commission if construction is not in conformance with the approved plans, or if compliance with Special Use Permit conditions has not been consistently demonstrated. In such case, the issue must be placed on the agenda of the Planning Commission for consideration. Written notice must be given to the applicant not less than ten days prior to the meeting. The applicant must be given the opportunity to present information to the Planning Commission and answer questions. The Planning Commission may revoke the special use permit if it finds that a site plan or special use permit violation exists and has not been remedied prior to the meeting.

Sec. 122-171. Appeals.

Any decision of the Planning Commission regarding a special use permit must not be appealed to the city zoning board of appeals. Such appeals must be taken to the circuit court.

Sec. 122-172. Reapplication.

No application for a Special Use Permit which has been denied wholly or in part by the Planning Commission shall not be resubmitted for a period of 365 days from the date of such denial, except on grounds of new evidence or proof of changed conditions found by the Planning Commission to be valid.

Secs. 122-173--122-200. Reserved.

ARTICLE VI.

NONCONFORMING USES, BUILDINGS, STRUCTURES OR LOTS*

*State law reference(s)--Nonconforming uses and structures, MCL 125.583a, MSA 5.2933(1).

Sec. 122-201. Description and purpose.

It is recognized that there exists within the districts established by this chapter uses of land which were lawful before this chapter was passed or amended, but which would be prohibited or restricted under the terms of this chapter.

It is the intent of this chapter to permit these nonconformities to continue until they are removed, abandoned, or brought into compliance with this chapter but not to encourage their survival. Such uses are declared by this chapter to be incompatible with permitted uses in the districts. It is further the intent of this chapter that nonconforming buildings, structures, or lots shall not be enlarged upon, expanded or extended, nor be used as grounds for adding other structures or uses prohibited in the district.

It is further recognized that certain nonconforming uses are not necessarily contrary to the public health, safety and welfare and that such uses were lawful at the time of their inception, and that no useful purpose would be served by the strict application of the elimination of lawful nonconforming use status. Therefore, two classes of nonconforming uses are designated, being class A and class B. All nonconforming uses are classified as class B nonconforming uses unless designated class A nonconforming uses.

Sec. 122-202. Authority to continue class B nonconforming.

Any class B nonconforming use which existed lawfully at the time of the adoption of the ordinance from which this chapter derives and which remains nonconforming and any such use which becomes nonconforming upon the adoption of this article, or of any subsequent amendments thereto, may be continued, subject to the regulations in this article.

Sec. 122-203.-Nonconforming lots.

A nonconforming lot is a lot of record or a lot described in a deed or land contract existing at the effective date of the ordinance from which this chapter derives that does not meet the minimum area or lot dimensional requirements of the district in which the lot is located. The following regulations must apply to any nonconforming lot:

- (1) *Use of nonconforming lot.* Any nonconforming lot must be used only for a use permitted in the district in which it is located.
- (2) *Single lot of record.* A principal structure and customary accessory structures may be erected on

any single lot of record at the effective date of adoption or amendment of this chapter, notwithstanding limitations imposed by other provisions of this chapter. Such lot must be in separate ownership and not of continuous frontage with other lots in the same ownership. This provision must apply even though such lot fails to meet the requirements for area or width or both, that are generally applicable in the district, provided that yard setback dimensions and requirements other than those applying to area or width of the lot must conform to the regulations for the district in which such lot is located. However, no more than one dwelling unit must occupy any lot except in conformance with the provisions of this chapter for required lot area for each dwelling unit.

- (3) *Variance from yard or other requirements.* If the use of a legal nonconforming lot requires a variation from any yard or other requirements, other than lot area or width, then such variance must be obtained from the Zoning Board of Appeals.
- (4) *Contiguous lots in same ownership.* When two or more contiguous nonconforming lots or parts of nonconforming lots are in a single ownership at the time of, or subsequent to the adoption or amendment of this chapter, such lots must be considered to be a single lot for the purposes of this chapter, and no portion of such lot must be used, occupied, divided, or sold in any manner which would diminish compliance with minimum lot width and area requirements of this chapter.

Sec. 122-204. Nonconforming use of land.

A nonconforming use of land occurs when property is used for a purpose or in a manner which was lawfully in existence before this chapter was adopted, but has become nonconforming under the terms of this chapter or its amendments.

- (1) The nonconforming use of land not involving a building or structure, or in connection with which any building or structure thereon is incidental or accessory to the principal use of the land, may be continued subject to the regulations which follow:
 - (a) *Change.* The nonconforming use of land must not be changed to any other use except to a use permitted in the district in which the land is located.
 - (b) *Expansion.* A nonconforming use of land must not be expanded or extended beyond the area it occupies.

(c) *Moving.* No such nonconforming use must be moved in whole or in part to any other portion of the lot or parcel occupied by such use at the effective date of adoption or amendment of this chapter.

(d) *Change in occupancy or ownership.* A change in occupancy or ownership shall not constitute a change in use.

(e) *Abandonment.* If the nonconforming use of land is discontinued for a period of 365 consecutive days, where there is an intent demonstrated by the property owner to abandon the nonconforming use, such use shall not be renewed, and any subsequent use of the land must conform to the regulations of the district in which the land is located. A nonconforming use may be determined to be abandoned if the use has ceased and one (1) or more of the following conditions exist, that said condition(s) demonstrating intent on the part of the property owner to abandon the nonconforming use:

(i.) One (1) or more utility meters, such as water, gas and electricity to the property, have been removed;

(ii.) The property, buildings and/or grounds are unsafe or unsanitary, as described in Chapter 18, Article V;

(iii.) Cessation of business operations;

(iv.) Receipt of a written declaration by the property owner.

(v.) Signs or other indications of the existence of the nonconforming use have been removed;

(vi.) Removal of equipment or fixtures that are necessary for the operation of the nonconforming use;

(vii.) Failure to maintain current licenses, certificates, permits, registrations or other appropriate documentation for the nonconforming use;

(viii.) Bank or tax foreclosure;

(ix.) Operation or maintenance of a permitted or different use at the property; or

(x.) Other actions or omissions, which in the opinion of the Planning or Building Department(s), evidence an intention of the part of the property owner to abandon the nonconforming use.

(2) A nonconforming use of land is not eligible for class A nonconforming designation.

Sec. 122-205. Class B nonconforming uses of buildings.

All nonconforming uses of buildings not designated class A shall be class B nonconforming uses of buildings. Class B nonconforming uses of buildings shall comply with all the provisions of this article relative to nonconforming uses of buildings. The class B nonconforming use of a building, or building and lot in combination, may be continued subject to the following provisions:

(1) *Change in use.* The nonconforming use of a building may not be changed to a different use unless the new use is permitted in that same district. Any building, or building and lot in combination, in or on which a nonconforming use is replaced by a permitted use, must thereafter conform to the regulations of the district in which it is located and the nonconforming use may thereafter not be resumed.

(a) A building or structure used for residential purposes which is nonconforming due to the number of dwelling units contained therein may only be changed so that the number of dwelling units is decreased, or so that the use is brought into conformity with this chapter.

(b) Notwithstanding the above, a nonconforming use of a building or structure may be changed to another nonconforming use so that the degree of nonconformity is lessened when authorized by the planning commission after a public notice and hearing in accordance with section 122-164. In considering such authorization, the planning commission must consider the following:

(i.) Whether the proposed use is equally or more appropriate than the present nonconforming zoning district in which the building, structure or land is located. No change to a less appropriate use may be authorized by the planning commission.

(ii.) Whether the proposed use will interfere to a lesser extent with the use of adjoining lands or other properties in the surrounding neighborhood for the uses for which they have been zoned pursuant to the provisions of this chapter.

(iii.) The effect of the proposed use on adjoining lands and the surrounding neighborhood.

(iv.) In permitting such change, the planning commission may require appropriate conditions and safeguards in accord with the purpose and intent of this chapter.

- (v.) Where a nonconforming use of a structure, or structure and land, is hereafter changed to a more conforming use, it must not thereafter be changed to a less conforming use.

(2) *Expansion of class B nonconforming use.*

- (a) The nonconforming use of any part of a building or structure must not be expanded or extended into any other portion of such building or structure.
 - (b) No visible structural alteration must be made to the building or structure devoted to a nonconforming use, except repairs and maintenance work which are required to keep such building in sound condition or as required by law.
 - (c) An existing structure containing a nonconforming use shall not be enlarged, constructed, reconstructed, moved or structurally altered or extended, unless the use is changed to a use which is permitted in the district in which the structure is located.
- (3) *Change in occupancy or ownership.* A change of occupancy or ownership shall not constitute a change in use.
- (4) *Removal or destruction.* If a building or structure in which a nonconforming use is being conducted is removed, destroyed, or severely damaged to the extent that the cost of restoration of the structure exceeds 100 percent of the state equalized value (SEV) or 50 percent of a higher value established by the most recent appraisal of the structure exclusive of the foundation and land, the nonconforming use shall not be renewed, and any subsequent use of the premises must conform to the use regulations of the district in which the premises are located. Single-family homes on individual lots that are considered a nonconforming use in the NC, Neighborhood Corridor Zoning District, shall be allowed to be rebuilt regardless of the amount of damage done to the structure so long as the rebuilt building is not enlarged or expanded. Single-family and two-family homes on individual lots that are considered a nonconforming use in the PMD, Production, Manufacturing, and Distribution Zoning District, shall be allowed to be rebuilt regardless of the amount of damage done to the structure so long as the rebuilt building is not enlarged or expanded.

For the purpose of calculating a fair and equitable cost of restoration regulated by this section, the average of two bid estimates from licensed contractors must be used. All work requiring permits under state and local regulations, and

materials necessary to bring the structure up to current code must be included. Clean up costs, demolition, furnishings, appliances, and site work, i.e. landscaping, fencing, paving, shall not be included. The actual repair and reconstruction may be done by the owner or contractor of his or her choice.

- (5) *Abandonment.* If the nonconforming use of land is discontinued for a period of 365 consecutive days, where there is an intent demonstrated by the property owner to abandon the nonconforming use, it must not thereafter be renewed, and any subsequent use of the land must conform to the regulations of the district in which the land is located. A nonconforming use must be determined to be abandoned if the use has ceased and one (1) or more of the following conditions exist, that said condition(s) being deemed to demonstrate intent on the part of the property owner to abandon the nonconforming use:
- (a) One (1) or more utility meters, such as water, gas and electricity to the property, have been removed;
 - (b) The property, buildings and/or grounds are unsafe or unsanitary, as described in Chapter 18, Article V;
 - (c) Cessation of business operations;
 - (d) Receipt of a written declaration by the property owner.
 - (e) Signs or other indications of the existence of the nonconforming use have been removed;
 - (f) Removal of equipment or fixtures that are necessary for the operation of the nonconforming use;
 - (g) Failure to maintain current licenses, certificates, permits, registrations or other appropriate documentation for the nonconforming use;
 - (h) Bank or tax foreclosure;
 - (i) Operation or maintenance of a permitted use or different use at the property; or
 - (j) Other actions or omissions, which in the opinion of the Planning or Building Department(s), evidence an intention of the part of the property owner to abandon the nonconforming use.

Sec. 122-206. Class A nonconforming uses of buildings.

Nonconforming uses of buildings shall be designated class A provided that the Planning Commission finds all of the following exists with respect to the use or structure:

- (1) The use of structure was lawful at its inception.
- (2) The decision to continue the nonconforming use, if granted, will not alter the essential character of the area or neighborhood.
- (3) Continuance of the use or structure would not be contrary to the public health, safety, or welfare or the spirit of the chapter.
- (4) No useful purpose would be served by strict application of the provisions of this chapter with which the use or structure does not conform.
- (5) Nonconforming uses of buildings are subject to the following restrictions:

- (a) *Change in use.* The nonconforming use of a building may not be changed to a different use unless the new use is permitted in that same district. Any building, or building and lot in combination, in or on which a nonconforming use is replaced by a permitted use, must thereafter conform to the regulations of the district in which it is located and the nonconforming use may thereafter not be resumed.

- (b) A building or structure used for residential purposes which is nonconforming due to the number of dwelling units contained therein may only be changed so that the number of dwelling units is decreased, or so that the use is brought into conformity with this chapter.

- (c) Notwithstanding the above, a nonconforming use of a building or structure may be changed to another nonconforming use so that the degree of nonconformity is lessened when authorized by the planning commission after a public notice and hearing in accordance with section 122-164. In considering such authorization, the planning commission must consider the following:

- (i.) Whether the proposed use is equally or more appropriate than the present nonconforming zoning district in which the building, structure or land is located. No change to a less appropriate use may be authorized by the planning commission.

- (ii.) Whether the proposed use will interfere to a lesser extent with the use of adjoining lands or other properties in the surrounding neighborhood for the uses for which they have been zoned pursuant to the provisions of this chapter.

- (iii.) The effect of the proposed use on adjoining lands and the surrounding neighborhood.

- (iv.) In permitting such change, the planning commission may require appropriate conditions and safeguards in accord with the purpose and intent of this chapter.

- (v.) Where a nonconforming use of a structure, or structure and land, is hereafter changed to a more conforming use, it must not thereafter be changed to a less conforming use.

- (6) *Removal or destruction.* If a class A nonconforming structure is destroyed, or severely damaged, it may be restored in conformance with the plans submitted when the status was conferred.

- (7) This designation shall run with the land.

Sec. 122-207. Class A Conditions.

The decision to grant a class A designation shall be made by the Planning Commission in writing, setting forth its findings of fact and basis for the designation. Only multiple family dwellings and/or group residence uses in R1 and CN-Mid shall be eligible for this designation. For changes or improvements to a class A use, site plans shall be required.

- (1) *Application.* An application for class A nonconforming status shall be filed with the city planner's office by the record owner of the property in question or by a person authorized to act on the record owner's behalf. The application shall consist of a completed application form, fee, and the following information:

- (a) Name, address, and telephone number of the applicant and property owner; and the interest of the applicant in the property.

- (b) Legal description, address, and tax parcel number of the subject property.

- (c) An accurate, scaled drawing of the property, showing all property lines and dimensions correlated with the legal description; the location and dimensions of all existing and proposed structures and uses on the property; any roads, alleys, easements, drains, or waterways which traverse or abut the property; and the lot area and setback dimensions necessary to show compliance with the regulations of this chapter. In most cases, a site plan or survey will meet this requirement.

- (d) The applicant shall show compliance with all applicable conditions of the City of Ypsilanti Code of Ordinances, and all applicable conditions of the International Property Maintenance Code, as adopted under Chapter 18 of

the City of Ypsilanti Code of Ordinances.

- (e) Other reasonable information deemed necessary by the Planning Commission in order to make a proper decision.
 - (f) No application for Class A designation shall be accepted after such time as the building has been destroyed as described in §122-205(4) or the use abandoned as described in §122-205(5).
- (2) *Conditions.* The Planning Commission may condition its approval on the following:
- (a) Screening and landscaping in keeping with community standards to ensure compatibility with adjacent uses.
 - (b) Restrictions on lighting, noise, odor, or visual impact.
 - (c) Signage must comply with current zoning district requirements. Existing nonconforming signs may be required to be eliminated or reduced in size and number.
 - (d) Replacement of a building must not create a more nonconforming yard setback condition which would impact on conforming properties in the immediate vicinity.
 - (e) Other reasonable safeguards and improvements may be imposed by the Planning Commission to protect conforming uses in the surrounding area.
- (3) *Procedure.* By the following procedure, the Planning Commission shall assure the public health, safety and welfare, and the spirit and purpose of this chapter:
- (a) A class A designation shall be deemed temporary until the Planning Commission has received written verification from the building official that the party requesting the class A designation has complied with all of the conditions set forth by the Planning Commission.
 - (b) Once the Planning Commission has received written verification from the building director that the party requesting the class A designation has complied with said conditions, the class A designation shall become final, subject to other provisions of this chapter as hereafter prescribed.
 - (c) No class A nonconforming use shall be resumed if it has been abandoned as defined in section §122-205(5). No class A nonconforming use shall be used, altered, or enlarged in violation of any conditions imposed in its designation.
 - (d) A temporary class A nonconforming use designation shall be void after six months if

any conditions imposed by the designation remain outstanding, unless the Planning Commission grants a written request for an extension of six months. No more than two extensions may be granted.

- (4) *Revocation.* Approval of a Class A designation may be revoked by the Planning Commission if the use and building is not in conformance with the approved plans, or if compliance with conditions has not been consistently demonstrated. In such case, the issue must be placed on the agenda of the Planning Commission for consideration. Written notice must be given to the applicant not less than ten days prior to the meeting. The applicant must be given the opportunity to present information to the Planning Commission and answer questions. The Planning Commission may revoke the Class A designation if it finds that a violation of the conditions set forth by the Planning Commission in their initial decision exists and has not been remedied prior to the meeting.

Sec. 122-208. Nonconforming structures.

- (1) A nonconforming building or structure is a structure which was lawful on the effective date of adoption or amendment of this chapter, but which does not conform to the new chapter regulations for building type, lot area, lot area per dwelling unit, lot width, lot coverage, floor area, height, screening, off-street parking, loading space, yard, or other requirements of the zoning district in which it is located.
- (2) Nonconforming buildings and structures may be re-used and occupied by new owners or tenants if all requirements of this Chapter are met and the restrictions below are met.
- (3) Nonconforming buildings and structures are subject to the following restrictions:
 - a. *Expansion.* Nonconforming structures may be expanded only in compliance with the following regulations:
 - i. All nonconforming structures, in any zoning district, may only be expanded in such a way that does not increase a non-conforming characteristic.
 - ii. All expansions must meet all requirements of the zoning district in which it is located, including lot coverage, heights, yard requirements, and off-street parking.
 - iii. A non-conforming building type may not be expanded.
 - b. *Alterations.* A nonconforming structure may be altered to decrease its nonconformity.

- c. *Moving.* A nonconforming structure which is moved within a site or to another site must conform to the regulations of the district in which it is located.
- d. *Damage and removal.* A nonconforming structure which is damaged by any means may be restored to its original conditions and location prior to such damage, provided such construction is completed within 18 months of the date of damage and is diligently pursued to completion. Failure to complete reconstruction must result in the loss of legal, nonconforming status.
- e. *Restoration or repair.*
 - i. All repairs and maintenance work required to keep a nonconforming building in sound condition may be made, but such structure must not be structurally altered in a way inconsistent with the description and purpose of this article.
 - ii. If a nonconforming structure or a structure housing a nonconforming use becomes physically unsafe or unlawful or poses a threat to the public health, safety, and welfare due to a lack of repairs or maintenance, the structure must be declared by the building department to be unsafe or unlawful by reason of physical condition. Such structure must not thereafter be restored, repaired, or rebuilt except in conformity with the provisions of this chapter.

(4) *Restoration of Historic Structures.* Restoration may be permitted of a legal nonconforming structure, designated as historic by the Ypsilanti Historic District Commission, which has been destroyed or abandoned (as defined in §122-205) provided the Planning Commission finds all of the following provisions are met:

- a. The approved design of the restored building maintains the same design and historical character it had prior to the destruction or abandonment; or, in the case of a building that had been altered prior to destruction or abandonment, that the restored building more closely parallels the design of the original historic structure.
- b. All reasonable attempts at eliminating or reducing the nonconforming nature of the structure have been considered and are implemented in the restoration project.

Sec. 122-209. Acquisition of nonconformities.

The city may acquire private property to remove a nonconformity, as provided in Act No. 207 of the Public Acts of Michigan of 1921 (MCL 125.581 et seq., MSA 5.2931 et seq.), as amended.

Sec. 122-210. Building or structure under construction on effective date of the ordinance from which this chapter is derived.

Any building or structure must be considered existing and lawful for the purposes of this article if, on the effective date of the ordinance from which this chapter is derived, a building permit has been obtained therefore, if required; or if no building permit is required, a substantial start has been made toward construction and construction is thereafter pursued diligently to conclusion.

Sec. 122-211. Unlawful nonconformities.

- (1) No nonconformity shall be permitted to continue in existence if it was unlawful at the time it was established.
- (2) The city shall maintain records of nonconforming uses and structures as accurate as is feasible for determining legal nonconforming uses and structures in existence on the effective date of the ordinance from which this chapter is derived. However, failure on the part of a property owner to provide the city with necessary information to determine legal nonconforming status may result in denial of a required or requested permit.

Secs. 122-212--122-230. Reserved.

ARTICLE VII. DISTRICT REGULATIONS

DIVISION 1. GENERALLY

Sec. 122-231. Establishment of districts.

Ypsilanti's Master Plan classified the City into neighborhoods, corridors, centers, and special districts. These classifications are the basis for the regulation of these areas. Outlying neighborhoods (outlying residential and multiple-family) and special districts (parks and production, manufacturing and distribution) are areas where regulation by use and intensity remain appropriate. Core neighborhoods, corridors, and centers were classified as walkable urban places, where the regulations must go beyond use or intensity to reinforce the context of the built environment through form and scale. The office district as laid out in the Master Plan, has been included as a Form Based Code area because it is surrounded by Neighborhoods, Centers, and Corridors and has an underlying street network and mixture of uses.

For the purposes of this chapter, the city is hereby divided into the following zoning districts having the names and symbols here shown:

R1 Single-family residential district

MD Multiple dwelling residential district

Neighborhoods, Centers, Corridors and Health and Human Services Districts:

CN Core Neighborhood

CN-SF Core Neighborhood Single Family

CN-Mid Core Neighborhood Mid

C Center

HC Historic Corridor

NC Neighborhood Corridor

GC General Corridor

HHS Health and Human Services

P Parks

PMD Production, Manufacturing and Distribution

Sec. 122-232. Zoning Map.

- (a) The locations and boundaries of the zoning districts are hereby established as shown on a map adopted by the City Council. The map must be entitled the "Zoning Map, City of Ypsilanti, Washtenaw County, Michigan," and must bear the date adopted or amended. It must be the duty of the city mayor and clerk to authenticate such records by placing their official signatures thereon. Such map with all accompanying explanatory matter is hereby made a part of this chapter as if the matters and information set forth thereon were all fully described in this chapter.
- (b) In Neighborhoods, Centers, Corridors, and Health and Human Services Districts, the Zoning Map must contain notations on property where building types noted in Section 122-274 are allowed in certain areas and required street construction or connections.
- (b) A copy of the Zoning Map must be available for sale or distribution to the public. The Zoning Map must be updated regularly.

Sec. 122-233. Application of chapter.

- (a) Land uses are permitted specifically in the various zoning districts of this chapter. Where not specifically permitted, uses are thereby specifically prohibited unless construed to be similar to a use expressly permitted.
- (b) Except as otherwise provided in this chapter, erection of buildings and uses of land must conform to the specific provisions for the zoning districts involved. No land must be redeveloped or a use commenced, expanded or continued within the city except as specifically, or by necessary implication, authorized by this chapter.
- (c) Lawful nonconforming structures and uses existing at the time of passage of this chapter are specifically governed by Article VI of this chapter and generally governed by this chapter.

Sec. 122-234. Interpretation of district boundaries.

Where uncertainty exists with respect to the boundaries of the various districts as shown on the Zoning Map, the following rules must apply:

- (1) Boundaries indicated as approximately following lot lines, the centerlines of streets or alleys, and city limits must be construed as following such lines.
- (2) Boundaries indicated as parallel to or extension of features indicated in subsection (1) of this section must be so construed. Distances not specifically indicated on the official Zoning Map must be determined by the scale of the map.
- (3) Where physical or natural features existing on the ground are at variance with those shown on the Zoning Map, or in other circumstances not covered above, the zoning board of appeals must interpret the district boundaries.
- (4) Where one parcel is divided into two or more portions by reason of different zoning district classifications, each of these portions must be used independently of the others in respective zoning classifications; and for the purposes of applying the regulations of this chapter, each such portion must be considered as if in separate and different ownership. However, if the zoning board of appeals finds that any portion of a lot so divided is inadequate in area for a viable use, such portion may be combined with an adjacent lot and/or rezoned as appropriate.

Sec. 122-235. Uses permitted as a right.

Permitted uses, as identified in the divisions covering each district, are recognized as uses of land and buildings in certain districts which are harmonious with other such uses which may lawfully exist within the same district. A permitted use is subject to the general provisions, parking regulations, district intent, permit, certificate and site plan requirements found elsewhere in this chapter, but otherwise is considered to be a lawful use not requiring special or extraordinary controls or conditions, unless otherwise indicated in this chapter.

Sec. 122-236. Uses permitted under special approval.

The uses identified as special uses in divisions covering each district are recognized as possessing characteristics of such unique and special nature (relative to location, off-site impacts, design, size, public service and utilities needs, and other similar characteristics) as necessitating individual standards and conditions in order to safeguard the general health, safety and welfare of the community. Article V of this chapter, regarding procedure and requirements for special uses, must apply to these uses.

Sec. 122-237. Zoning of vacated land.

Vacated streets or alleys, or the divided portions thereof, must automatically be given the same zoning classification as the private property to which they are attached upon vacation.

Sec. 122-238. Zoning of annexed land.

Property duly annexed to the city will be zoned R1, single-family residential, upon annexation. However, the City Council may, in the annexation ordinance, designate an appropriate zoning designation upon annexation, based upon existing use of the property, the city's adopted master plan, or the use of surrounding properties.

Secs. 122-239--122-250. Reserved.

DIVISION 2.
R1 SINGLE-FAMILY RESIDENTIAL DISTRICTS

Sec. 122-251. Description and purpose.

The R1 single-family district is designed to provide an environment of predominantly low-density, single-family detached dwellings, along with other related facilities such as schools and religious institutions. The purpose of the R1 single-family district to encourage the preservation and the continuation of the long-standing residential fabric in existing neighborhoods of predominantly single-family dwellings. Multiple-family, business, or industrial uses which would substantially interfere with the development or continuation of single-family dwellings in the district are prohibited.

Sec. 122-252. Permitted uses.

The following uses are allowed in the R1 single-family residential district.

P=Principal, A=Accessory, S=Special Land Use

USES R1 NOTES & OTHER REGULATIONS FOR USE		
RESIDENTIAL		
Single-Family Detached Dwelling	P	Manufactured and premanufactured dwellings may be located and installed according to same standards that would apply to a site-built single-family dwelling on the same lot.
Home Occupation	A	Section 122-669
Family Child Care Home	A	1-6 children, day care and 24 hour care Section 122-779
Adult foster care family homes	A	1-6 adults, day care and 24 hour care, excludes facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities. Section 122-773
Group Child Care Home	S	6-12 children, day care only Section 122-779
RECREATION, EDUCATION & PUBLIC ASSEMBLY		
Park	P	
Primary & Secondary Schools (public & private)	S	Section 122-805
Post-secondary educational institutions (public & private)	S	Section 122-805
Religious institution	S	Section 122-780
Municipal, county, regional & state service uses	S	Section 122-795
SERVICES		
Bed & Breakfast or Inn	S	Section 122-778
Farmers' Market	A	When accessory to a nonresidential use.
INFRASTRUCTURE		
Essential Services	P	Section 122-637
Communication Devices	A	Article XI, division 3
Alternative Energy	A	Section 122-788
Stormwater Control	A	Section 122-789
GARDENS / COMMUNITY GARDENS		
Community Gardens	P	Exempt from area regulations in Section 122-253, subject to Section 122-815
Toolhouses, sheds and other similar buildings for the storage of domestic supplies	A	Must meet accessory structure regulations for lot coverage and maximum floor area. Rear or side yard only.
Passive solar structure (greenhouse, hoophouse, etc.)	A	Must meet accessory structure regulations for lot coverage. Rear or side yard only. Structure must meet regulations in Section 122-253, with an exception for an up to 200 sq ft passive solar structure if floor area of existing detached accessory structures are less than 200 sq ft or equal to the gross floor area of the ground floor of the principal structure. Maximum square footage is 800 sq ft.

Sec. 122-253. Schedule of Regulations.

- (a) All principal structures and attached accessory structures must comply with the following regulations in the R-1 single-family residential zoning district:

REGULATIONS		R1	NOTES
Minimum Lot Width			
Lot width for all buildings	45 ft.		
Minimum Lot Size			
Single-family detached dwelling	5,000 sq. ft.		
Minimum Setbacks (Residential Uses)			
Front yard	25 feet	Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must not be less than the average depth of the front yards of the existing buildings on each side.	
Side yard	4 feet		
Side yards (combined)	12 feet		
Street Side yard	8 feet		
Rear yard	25 feet		
Minimum Setbacks (Non-Residential Uses)			
Front yard	25 feet	Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must not be less than the average depth of the front yards of the existing buildings on each side.	
Side yard	8 feet		
Side yards (combined)	Equal to the height of the structure or the setbacks required for residential uses, whichever is greater.		
Street side yard	8 feet		
Rear yard	25 feet		
Parking Setbacks (other than single-family dwellings)			
Front & side street yard	Not allowed		
Side and rear yards	10 feet		
Height			
Maximum height	30 feet or 2.5 stories	Chimneys, flagpoles, church spires, belfries, cupolas, domes, or other similar architectural embellishments; roof mounted communication antennas; water towers, observation towers, power transmission towers, radio towers, masts, smokestacks, ventilators, skylights, derricks, conveyors, cooling towers, and other similar and necessary mechanical appurtenance pertaining to the permitted uses; provided that they do not exceed the maximum height by more than ten feet.	
Minimum Floor Area			
Dwelling unit	500 sq. ft.		
Maximum Lot Coverage			
Residential Uses	35%		
Non-residential Uses	50%		

(c) All detached accessory structures must meet the following standards:

Regulations	R1	Notes
Minimum Setbacks (Accessory to Residential Uses)		
Front yard	Not allowed	
Side yard	3 feet	1 foot if lot line abuts an alley
Street Side yard	8 feet	
Rear yard	3 feet	1 foot if lot line abuts an alley, 12 feet for a through lot
Distance from principal structure	7 feet	Minimum distance to comply with fire regulations and/or building code, if greater than minimum listed. An attached enclosure or roof over a pathway between structures on a lot, such as a breezeway, is exempt from this setback provided it is 8 feet or less in width and 15 feet or less in height.
Minimum Setbacks (Accessory to Non-Residential Uses)		
Front yard	Not allowed	
Side yard	3 feet	1 foot if lot line abuts an alley
Street Side yard	8 feet	
Rear yard	3 feet	1 foot if lot line abuts an alley, 12 feet for a through lot
Distance from principal structure	5 feet	Minimum distance to comply with fire regulations and building code, if greater than setback listed.
Height		
Maximum height	15 feet	
Size of Accessory Buildings		
Maximum Floor Area	Floor area of all accessory buildings must not exceed gross floor area of the ground floor of the principal structure and must not cause lot coverage regulations for all buildings and paved surfaces on-site to be exceeded.	

Secs. 122-254--122-260. Reserved.

DIVISION 3.
MD MULTIPLE DWELLING RESIDENTIAL DISTRICTS

Sec. 122-261. Description and purpose.

The MD multiple-family residential district is designed to allow a multiple-family residential development, rental or owner-occupied, designed specifically for apartments, townhouses, and/or other housing types. The multiple-family residential district is located adjacent to high traffic generators and major thoroughfares and corridors, and can serve as zones of transition between nonresidential districts and neighborhoods. The multiple-family residential district is designed to insure sound development policies for areas having a concentration of multifamily units, while assuring an adequate supply of multiple-family living units in the housing mix of the city overall. Recreation, services and retail uses are allowed as special land uses to allow residents to access everyday needs by foot, if they are not already within walking distance on a corridor or in a center.

Sec. 122-262. Permitted uses.

The following uses are allowed in the MD multiple-family residential district.

P=Principal, A=Accessory, S=Special Land Use

USES	MD	NOTES & OTHER REGULATIONS FOR USE
RESIDENTIAL		
Two-Family Dwelling	P	Manufactured and premanufactured dwellings may be located and installed according to same standards that would apply to a site-built two-family dwelling on the same lot.
Multiple Family Dwellings, maximum of 6 units per building	P	Includes senior housing, student housing, and co-housing. Responsible party for management must be on file with the City.
Multiple Family Dwellings, more than 6 units per building	S	Includes senior housing, student housing, and co-housing. Responsible party for management must be on file with the City.
Home Occupation	A	Section 122-669
Family Child Care Home	A	1-6 children, day care and 24 hour care Section 122-779
Adult foster care family homes	A	1-6 adults, day care and 24 hour care, excludes facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities. Section 122-773
Group Child Care Home	S	6-12 children, day care only Section 122-779
GROUP LIVING		
Group living with support staff, not licensed by State of Michigan	S	Includes supportive housing, rehabilitation housing, or dormitories.
Adult foster care small & group homes, adult congregate facilities	S	7 or more adults, licensed by State of Michigan Section 122-773
Adult foster care facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities.	S	

(continued on following page)

RECREATION, EDUCATION & PUBLIC ASSEMBLY		
Park	P	
Outdoor recreation areas	A	Section 122-802
Social facility for multiple dwelling residents and their guests	A	Subject to detached accessory structure regulations.
Primary & Secondary Schools (public & private)	S	Section 122-805
Post-secondary educational institutions (public & private)	S	Section 122-805
Religious institution	S	Section 122-780
Municipal, county, regional & state service uses	S	Section 122-795
SERVICES		
Bed & Breakfast or Inn	S	Section 122-778
Child care centers and day care centers	S	Section 122-779
Nursing homes	S	Section 122-796
Medical or Dental Offices	S	
Financial services, including banks	S	Drive through facilities are not allowed in MD
Personal service establishments	A	
COMMERCIAL		
Food stores, excluding sale of alcohol, less than 15,000 square feet	S	
Farmers' Market	A	
RESTAURANTS		
Carry-out and/or delivery restaurant	S	Drive through facilities are not allowed in MD
Café or coffee shop	S	Drive through facilities are not allowed in MD
INFRASTRUCTURE		
Essential Services	P	Section 122-637
Communication Devices	A	Article XI, division 3
Alternative Energy	A	Section 122-788
Stormwater Control	A	Section 122-789
Automobile Share Parking	A	
GARDENS/COMMUNITY GARDENS		
Community Gardens	P	Exempt from area regulations in 122-263, subject to 122-815
Toolhouses, sheds and other similar buildings for the storage of domestic supplies	A	Must meet accessory structure regulations for lot coverage and maximum floor area. Rear or side yard only.
Passive solar structure (greenhouse, hoophouse, etc.)	A	Must meet accessory structure regulations for lot coverage and maximum floor area. Rear or side yard only. Maximum square footage is 800 square feet.

Sec. 122-263. Schedule of Regulations.

(a) All principal structures must comply with the following regulations in the MD multiple-family residential district:

REGULATIONS	MD	NOTES								
Minimum Lot Width										
Lot width for all buildings	45 ft.									
Minimum Lot Size										
Two-family dwelling	6,000 sq. ft.									
Group living	6,000 sq. ft.									
Multiple-family	8,000 sq. ft.									
Ratio of Lot Sizes to Number of Units										
		The total number of rooms in a multiple apartment dwelling structure must not be more than the area of the parcel in square feet divided by 1,400 square feet. The required minimum floor area per unit type is as follows: <table><tr><td>Unit Type</td><td>Required Min. Square Footage</td></tr><tr><td>1 Bedroom</td><td>600</td></tr><tr><td>2 Bedroom</td><td>800</td></tr><tr><td>3+ Bedroom</td><td>1,000</td></tr></table>	Unit Type	Required Min. Square Footage	1 Bedroom	600	2 Bedroom	800	3+ Bedroom	1,000
Unit Type	Required Min. Square Footage									
1 Bedroom	600									
2 Bedroom	800									
3+ Bedroom	1,000									
Minimum Setbacks (Residential Uses)										
Front yard	25 feet	Where an existing front yard setback line has been established by existing residential dwellings occupying 50 percent or more of the frontage within the same block on the same side of the street, the depth of the front yard must not be less than the average depth of the front yards of the existing buildings on each side								
Side yard	4 feet	For buildings with more than 4 units, 6 feet or, if lot directly abuts R1 district, 25 feet.								
Side yards (combined)	12 feet	For buildings with more than 4 units, 14 feet								
Street Side yard	8 feet	For buildings with more than 4 units, 15 feet								
Rear yard	25 feet									
Distance between buildings	20 feet									
Minimum Setbacks (Non-Residential Uses)										
Front yard	25 feet									
Side yard	6 feet									
Side yards (combined)	14 feet									
Street side yard	15 feet									
Rear yard	25 feet									
Parking Setbacks (other than single-family dwellings)										
Front & side street yard	Not allowed									
Side and rear yards	10 feet									
Height										
Maximum height	65 feet or 6 stories	Chimneys, flagpoles, church spires, belfries, cupolas, domes, or other similar architectural embellishments; roof mounted communication antennas; water towers, observation towers, power transmission towers, radio towers, masts, smokestacks, ventilators, skylights, derricks, conveyors, cooling towers, and other similar and necessary mechanical appurtenance pertaining to the permitted uses; provided that they do not exceed the maximum height by more than ten feet								

REGULATIONS	MD	NOTES
Minimum Floor Area		
Dwelling unit	See Section 122-794	
Outdoor Space		
A total of one hundred thirty (130) square feet of outdoor living space must be provided for each bedroom or studio/efficiency unit. Porches, balconies and improved roof areas may count toward the required outdoor living space, provided no such area is less than five (5) feet in width. Such outdoor areas must be buffered from streets and parking lots. Off-street parking areas, driveways, and accessory uses must not be counted as required open space.		

(b) All detached accessory structures must meet the following standards:

REGULATIONS	MD	NOTES
Minimum Setbacks (Accessory to Residential Uses)		
Front yard	Not allowed	
Side yard	3 feet	1 foot if lot line abuts an alley
Street Side yard	8 feet	
Rear yard	3 feet	1 foot if lot line abuts an alley, 12 feet for a through lot
Distance from principal structure	7 feet	Minimum distance to comply with fire regulations and/or building code, if greater than 7 feet. An attached enclosure or roof over a pathway between structures on a lot, such as a breezeway, is exempt from this setback provided it is 8 feet or less in width and 15 feet or less in height.
Minimum Setbacks (Accessory to Non-Residential Uses)		
Front yard	Not allowed	
Side yard	3 feet	1 foot if lot line abuts an alley
Street Side yard	8 feet	
Rear yard	3 feet	1 foot if lot line abuts an alley, 12 feet for a through lot
Distance from principal structure	5 feet	Minimum distance to comply with fire regulations, if greater than 7 feet
Height		
Maximum height	15 feet	
Size of Accessory Buildings		
Maximum Floor Area	No limitations other than maximum impervious surface lot coverage.	

(c) All structures (principal and accessory) and paved surfaces must meet the following standards:

REGULATIONS	MD
Maximum Impervious Surface Lot Coverage	
Residential Uses	45%
Non-residential Uses	50%

Secs 122-264-122-270. Reserved

DIVISION 4.

NEIGHBORHOODS, CENTERS, CORRIDORS AND HEALTH AND HUMAN SERVICES DISTRICTS

Sec. 122-271. Description and purpose.

In Ypsilanti's Master Plan, core neighborhoods, corridors, and centers were classified as walkable urban places, where the regulations must go beyond use or intensity to reinforce the context of the built environment through form and scale. The Health and Human Services district is included due to its location and character.

These districts are places where a person can walk, bike or ride transit to work and to fulfill most shopping and recreation needs. These environments allow for the use of automobiles but do not require the use of a vehicle to accommodate most daily needs.

These districts were primarily developed prior to the 1940's. Such places were developed in a pattern where a person could live with limited reliance on the automobile and were conducive to destination walking and cycling. They are largely supported through a network of interconnected, tree-lined streets, a diversity of housing choices and a mix of appropriate commercial and residential uses in a compact form. These areas also support public transit due to their compact nature.

(a) *Core Neighborhoods.* Core neighborhoods are built on a grid street network connected to the adjacent business districts. They border center districts or other core neighborhoods. These neighborhoods have a range of residential building types, with religious institutions, schools, stores and automobile filling stations intermixed. There are three types of core neighborhoods:

- (1) *CN Core Neighborhoods.* These neighborhoods directly border center districts and have a variety of housing types, ranging from cottages to group living to apartment buildings. This district also affords opportunities for accessibly-placed walkable, neighborhood businesses.
- (2) *CN-Mid Core Neighborhood Mid.* These neighborhoods generally abut the Core Neighborhoods, and offer a less dense and less intense residential area with opportunities for accessibly-placed low-intensity walkable, neighborhood businesses. Housing types range from mansions to cottages, with multiple-family and single-family uses. This zoning may also be used as a transition zone between single-family districts and mixed use districts.
- (3) *CN-SF Core Neighborhood Single Family.* These neighborhoods are east of Depot Town

and north of Michigan Avenue, known as the historic eastside. Housing types include mansions, estates, houses, and cottages. Residential uses are restricted to single-family; neighborhood businesses are limited.

- (b) *C Center.* These are mixed-use areas with historic buildings. These are the places where people shop, go to school, live, come to work, visit, drop by City Hall, eat, gather and have fun. They host events that bring thousands of visitors each year and bring the City together as a community. The intent of the zoning district is preserve the urban form, walkable nature and vibrant mix of uses in these areas.
- (c) *Corridors.* Corridors are mixed-use and commercial areas located along the arteries of the City, such as Washtenaw, Huron, Hamilton, Michigan, Harriet, and River.
 - (1) *HC Historic Corridor.* Historic corridors are located entirely in the Historic District and are on Cross Street, Huron Street, Hamilton Street, and River Street. These corridors are lined with historic buildings and are integrated into the adjacent neighborhoods and centers. The intent of this district is to preserve the walkability, character and historic nature of these streets, while allowing for adaptive re-use of historic buildings ranging from single-family to multiple-dwelling to office uses.
 - (2) *NC Neighborhood Corridor.* Neighborhood corridors have a linear land pattern and are adjacent to residential neighborhoods. The size, form and scale of buildings and the type and intensity of uses should be complementary to abutting single-family or core neighborhoods, including less intense multiple-family residential building types and uses.
 - (3) *GC General Corridor.* General corridors are located along roads with heavy traffic and have commercial establishments, restaurants, offices, and other businesses that are geared toward automobile traffic. Multiple-family residential building types and uses are appropriate in this district.
- (d) *HHS Health and Human Services.* The Health and Human Services district is located on either side of Towner between Prospect and Arnet Streets. A cluster of office, health and human service uses are in this district. The intent of the district is to provide regulations to require a more urban form through redevelopment of parking lots and reconnecting the street grid and circulation system.

Sec. 122-272. Permitted uses.

a) Core Neighborhoods

The following uses are allowed in CN, CN-Mid, and CN-SF districts:

P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted

USES	CN	CN-MID	CN-SF	NOTES & OTHER REGULATIONS FOR USES
RESIDENTIAL				
Single-Family Detached Dwelling	P	P	P	
Accessory Dwelling Unit	A	A	--	
Two-family dwelling units	P	P	--	
Multiple Family Dwellings, maximum of 4 units per building	P	S	--	
Multiple Family Dwellings, more than 4 units per building	S	--	--	
Apartments located above ground floor of permitted nonresidential uses	P	--	--	
Home Occupation	A	A	A	Section 122-669
Family Child Care Home	A	A	A	1-6 children, day care and 24 hour care Section 122-779
Adult foster care family homes	A	A	A	1-6 adults, day care and 24 hour care Section 122-773
Group Child Care Home	S	S	S	6-12 children, day care only Section 122-779
GROUP LIVING				
Group residence	S	--	--	Responsible party for management must be on file with the City. Section 122-804
Group living with support staff, not licensed by State of Michigan	S	--	--	Includes supportive housing, rehabilitation housing or dormitories.
Roominghouse	S	--	--	Section 122-804
Adult foster care small & group homes, adult congregate facilities	S	S	--	Licensed by State of Michigan for 7 or more adults. Section 122-773
Adult foster care facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities.	S	--	--	
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES				
Park	P	P	P	
Outdoor recreation	A	--	--	Section 122-802
Primary & Secondary Schools (public & private)	S	S	S	Section 122-805
Post-secondary educational institutions (public & private)	S	S	S	Section 122-805
Religious institution	S	S	S	Section 122-780
Private assembly, banquet hall allowed	S	--	--	

P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted

				NOTES & OTHER REGULATIONS FOR
USES	CN	CN-MID	CN-SF	USES
Municipal, county, regional, & state service uses	S	S	S	Section 122-795
Public Art	A	A	A	
SERVICES				
Bed & Breakfast or Inn	S	S	S	Section 122-778
Funeral Homes	S	S	--	
Nursing Homes	S	S	--	Section 122-796
Medical or Dental Offices	S	S	--	
COMMERCIAL				
Arts & crafts studios	S	--	--	
Food stores, excluding sale of alcohol, less than 15,000 square feet	S	S	S	
Farmers' Market	A	A	A	When accessory to a non-residential use.
RESTAURANTS				
Carry-out and/or delivery restaurant	S	--	--	
Café or coffee shop	S	--	--	
AUTO-ORIENTED				
Automobile Filling Station - no repair	S	S	S	Section 122-776
Automobile Share Parking	A	--	--	
INFRASTRUCTURE				
Essential Services	P	P	P	Section 122-637
Communication Devices	A	A	A	Article XI, division 3
Alternative Energy	A	A	A	Section 122-788
Stormwater Control	A	A	A	Section 122-789
GARDENS / COMMUNITY GARDENS				
Community gardens	P	P	P	Section 122-815
Passive solar structure (hoophouse, greenhouse, etc.)	A	A	A	Must meet accessory building regulations for building type. Maximum square footage is 800 square feet.
Toolhouses, sheds and other similar buildings for the storage of domestic supplies	A	A	A	Must meet accessory building regulations for building type.

b) Corridors

The following uses are allowed in the HC, NC and GC districts:

P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted

USES	HC	NC	GC	NOTES & OTHER REGULATIONS FOR USES
RESIDENTIAL				
Single-Family Detached Dwelling	P	--	--	
Accessory Dwelling Unit	A	--	--	
Two-family dwelling units	P	P	P	
Multiple Family Dwellings, maximum of 4 units per building	P	P	P	
Multiple Family Dwellings, more than 4 units per building	S	S	P	Section 122-794
Apartments located above ground floor of permitted nonresidential uses	P	P	P	
Home Occupation	A	A	A	Section 122-669
Family Child Care Home	A	A	A	1-6 children, day care and 24 hour care Section 122-779
Adult foster care family homes	A	A	A	1-6 adults, day care and 24 hour care Section 122-773
Group Child Care Home	A	A	A	6-12 children, day care only Section 122-779
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES				
Parks	P	P	P	
Outdoor recreation	--	S	P	Section 122-802
Museums & libraries, less than 15,000 square feet	P	P	--	
Museums & libraries 15,000 square feet or more	S	S	--	
Primary & Secondary Schools (public & private)	S	S	--	Section 122-805
Post-secondary educational institutions (public & private)	S	S	--	Section 122-805
Religious institution	S	S	--	Section 122-780
Private assembly, banquet hall allowed	S	S	--	
Indoor recreation less than 15,000 square feet	--	P	P	
Indoor recreation 15,000 square feet or more	--	--	P	
Municipal, county, regional & state service uses	S	P	P	Section 122-795
Public Art	A	A	A	
SERVICES				
Business and professional offices less than 15,000 square feet	P	P	P	
Business and professional offices, 15,000 square feet or more	--	S	P	
Financial services, including banks, less than 15,000 square feet	P	P	P	Drive through or drive-up facilities require special land use

P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted

USES	HC	NC	GC	NOTES & OTHER REGULATIONS FOR USES
Financial services, including banks, 15,000 square feet or more	--	S	P	Drive through or drive-up facilities require special land use.
Homeless Shelter	--	--	P	Section 122-785
Personal service establishments, less than 15,000 square feet	P	P	P	
Personal service establishments, 15,000 square feet or more	--	--	P	
Body art facilities	--	--	P	
Offices for skilled trade services including but not limited to plumbing, electric, heating, and painting establishments	--	S	P	Section 122-797
Printing services, including but not limited to: publishing, engraving, photo development, lithographing, silk screening and three-dimensional printing	--	S	S	Section 122-810
Bed & Breakfast or Inn	P	S	--	Section 122-778
Hotels & motels	--	--	P	
Child Care Centers	S	P	P	Section 122-779
Funeral homes	S	S	S	
Laundromats and dry cleaners, less than 15,000 square feet	--	P	P	No dry cleaning on premises.
Laundromats and dry cleaners, 15,000 square feet or more	--	--	P	No dry cleaning on premises.
Nursing Homes	S	--	S	Section 122-796
Medical or dental offices	P	P	P	No more than 4 practitioners.
Medical or dental clinics	S	S	P	5 or more practitioners.
Veterinary hospitals and clinics	--	S	S	Section 122-809
Kennels, commercial	--	--	S	Section 122-791
Substance abuse treatment facilities	--	--	S	Section 122-808
Catering services, less than 15,000 square feet	P	P	P	
Catering services, 15,000 square feet or more	--	--	P	
Self-storage	--	--	P	Section 122-806
COMMERCIAL				
Retail stores, less than 15,000 square feet	S	P	P	
Retail stores, greater than 15,000 square feet	--	--	P	
Resale stores	--	P	P	
Arts & crafts studios	P	P	P	
Food stores, excluding sale of alcohol, less than 15,000 square feet	S	P	P	
Food stores, with sale of alcohol, less than 15,000 square feet	--	S	P	
Food stores greater than 15,000 square feet with or without sale of alcohol	--	--	P	

P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted

USES	HC	NC	GC	NOTES & OTHER REGULATIONS FOR USES
Commercial Greenhouse			P	
Farmers' market and other organized markets	--	P	P	
Outdoor retail sales	--	S	S	Section 122-800
RESTAURANTS				
Carry-out and/or delivery restaurant	--	P	P	
Café or coffee shop	P	P	P	
Sit-down, with seating limit of 50 seats	P	P	P	
Sit-down, no seating limit	--	--	P	
Bar/Lounge	--	S	P	
Tasting room and accessory to microbrewer/ small distiller/ small wine maker	--	S	P	Carry-out sales allowed with proper licenses.
Fast Food	--	S	P	Must be located on major thoroughfare. Drive through or drive-up facilities require special land use.
Drive through restaurant of any type	--	--	S	Section 122-783
Outdoor cafes	A	A	A	Section 122-799
AUTO-ORIENTED				
Parking lot (as primary use)	--	--	S	Section 122-782
Parking Garage	--	--	S	Section 122-781
Automobile Sales	--	--	S	
Automobile Filling Station - no repair	--	S	S	Section 122-776
Automobile Filling Station with repair	--	--	S	Sections 122-775 and 122-776
Automobile Wash & Detailing	--	--	S	
Automobile Repair	--	--	S	Section 122-775
Automobile Share Parking	A	A	A	
Automobile rental or share organization (parking, storage, wash & repair)	--	--	S	
Vehicle, Recreational Vehicle, Storage and Towing	--	--	S	
RESEARCH				
Laboratories	--	--	S	
Research & Development	--	--	S	
PRODUCTION, MANUFACTURING & DISTRIBUTION				
Craft production, clothing production or food production, less than 16,000 square feet	--	P	P	
Craft production, clothing production or food production, 16,000 square feet or greater	--	--	S	
Microbrewer/ small distiller /small wine maker, less than 16,000 square feet	--	P	P	

P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted

USES	HC	NC	GC	NOTES & OTHER REGULATIONS FOR USES
Microbrewer/ small distiller /small wine maker, 16,000 square feet or greater	--	--	S	Carry-out sales allowed with proper licenses.
Wholesale or distribution facility with total gross floor area of less than 16,000 square feet	S	S	P	
Wholesale or distribution facility with total gross floor area 16,000 square feet or greater	--	--	S	
Medical Marijuana Growing/Manufacturing Facility	--	--	S	
TEMPORARY USES				
Temporary permitted use in vacant storefront	--	P	P	Section 122-35 (8)
Food concession sales	--	P	P	Section 122-35 (7)
INFRASTRUCTURE				
Essential Services	P	P	P	Section 122-637
Communication Devices	A	A	A	Article XI, division 3
Alternative Energy	A	A	A	Section 122-788
Stormwater Control	A	A	A	Section 122-789
GARDENS/COMMUNITY GARDENS				
Passive solar structure (greenhouse, hoophouse, etc.)	A	A	A	Must meet accessory structure regulations for building type. Maximum square footage is 800 square feet in the HC zoning district.
Community gardens	--	A	A	Section 122-815
PERFORMANCE OR STRUCTURES REQUIRING SPECIAL LAND USE				
Operation between 2 a.m. and 6 a.m. during any 24-hour period	--	S	S	
Drive through facilities	--	S	S	Section 122-784
Ongoing outdoor retail sales or display	--	S	S	Section 122-800
Outdoor storage	--	S	S	Section 122-801

- (a) Centers
The following uses are allowed in C districts:

P=Principal, A=Accessory, S=Special Land Use

USES	C	NOTES & OTHER REGULATIONS FOR USES
RESIDENTIAL		
Multiple Family Dwellings	P	
Apartments located above ground floor of permitted nonresidential uses	P	
Home Occupation	A	Section 122-669
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES		
Museums & libraries	P	
Parks	P	
Public Art	A	
Indoor recreation	P	
Performance venues/theaters	P	
Municipal, county, regional & state service uses	P	Section 122-795
Post-secondary educational institutions (public & private)	P	Section 122-805
INFRASTRUCTURE		
Essential Services	P	Section 122-637
Communication Devices	A	Article XI, division 3
Alternative Energy	A	Section 122-788
Stormwater Control	A	Section 122-789
Public & Private Transportation Passenger Terminals	S	Section 122-786
SERVICES		
Business and professional offices and services	P	
Financial services, including banks	P	No drive through or drive-up facilities are permitted in C.
Personal service establishments	P	
Body Art Facilities	P	
Printing services, including but not limited to: publishing, engraving, photo development, lithographing, silk screening and three-dimensional printing	S	
Hotels & motels	P	
Child Care Centers	P	Section 122-779
Laundromats and dry cleaners	P	No dry cleaning on premises.
Medical or dental offices	P	No more than 4 practitioners.
Medical or dental clinics	P	5 or more practitioners.

P=Principal, A=Accessory, S=Special Land Use

USES			C	NOTES & OTHER REGULATIONS FOR USES
Medical Marijuana Dispensary		P		Section 122-813
Catering services		A		
Self-storage		S		Section 122-806
COMMERCIAL				
Retail stores		P		
Resale stores		P		
Arts & crafts studios		P		
Food stores, excluding sale of alcohol		P		
Food stores less than 15,000 square feet, with sale of alcohol		S		
Food stores greater than 15,000 square feet with sale of alcohol		P		
Farmers' market and other organized markets		P		
Auction houses		P		Section 122-812
RESTAURANTS				
Carry-out and/or delivery restaurant		P		
Café or coffee shop		P		
Sit-down		P		
Bar/Lounge		P		
Tasting room and/or restaurant		A		Carry-out sales allowed with proper licenses.
Outdoor cafes		A		Section 122-799
Fast Food		P		No drive through or drive-up facilities are permitted in C.
AUTO-ORIENTED				
Parking lot (as principal use)		S		Section 122-782
Parking Garage		S		Section 122-781
Automobile Share Parking		A		
PRODUCTION, MANUFACTURING & DISTRIBUTION				
Microbrewer/ small distiller /small wine maker		P		Carry-out sales allowed with proper licenses.
TEMPORARY USES				
Temporary permitted use in vacant storefront		P		Section 122-35 (8)
Food concession sales		P		Section 122-35 (7)
PERFORMANCE OR STRUCTURES REQUIRING SPECIAL LAND USE				
Operation between 2 a.m. and 6 a.m. during any 24-hour period		P		
Sale of alcoholic beverages for consumption off the premises		S		

- (b) Health and Human Services
The following uses are allowed in the HHS district:

P=Principal, A=Accessory, S=Special Land Use

USES	HHS	NOTES & OTHER REGULATIONS FOR USES
RESIDENTIAL		
Two-family dwelling	P	
Multiple Family Dwellings, maximum of 6 units per building	P	
Multiple Family Dwellings, more than 6 units per building	S	Section 122-794
Apartments located above ground floor of permitted nonresidential uses	P	
Home Occupation	A	Section 122-669
Group living with support staff, not licensed by State of Michigan	P	Includes supportive housing (see Section 122-811), rehabilitation housing or dormitories.
Family Child Care Home*	A	1-6 children, day care and 24 hour care Section 122-779
Adult foster care family homes*	A	1-6 adults, day care and 24 hour care, excludes facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities. Section 122-773
Group Child Care Home*	A	6-12 children, day care only Section 122-779
GROUP LIVING		
Group residence, maximum of 6 residents	P	Responsible party for management must be on file with the City. Section 122-804
Group residence with 7 or more residents	S	Responsible party for management must be on file with the City. Section 122-804
Roominghouse	S	Section 122-804
Adult foster care small & group homes, adult congregate facilities	P	7 or more adults, licensed by State of Michigan Section 122-773
Adult foster care facilities licensed by a state agency for care and treatment of persons released from or assigned to adult correctional facilities.	S	
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES		
Parks	P	
Public Art	A	
Indoor recreation	P	
Municipal, county, regional & state service uses	P	Section 122-795
Post-secondary educational institutions (public & private)	S	Section 122-805
Outdoor recreation	A	Section 122-802
INFRASTRUCTURE		
Essential Services	P	Section 122-637
Communication Devices	A	Article XI, division 3
Alternative Energy	A	Section 122-788
Stormwater Control	A	Section 122-789

P=Principal, A=Accessory, S=Special Land Use

USES	HHS	NOTES & OTHER REGULATIONS FOR USES
SERVICES		
Business and professional offices and services	P	
Financial services, including banks	P	Drive through or drive-up facilities require special land use
Adult drop-in center	P	Section 122-793
Homeless Shelter	P	Section 122-785
Personal service establishments	P	
Child Care Centers	P	Section 122-779
Funeral homes	S	
Nursing Homes	P	Section 122-796
Medical or dental offices	P	No more than 4 practitioners
Medical or dental clinics	P	5 or more practitioners
Hospitals	P	
Substance abuse treatment facilities	S	Section 122-808
Catering services	P	
COMMERCIAL		
Retail stores less than 15,000 square feet	P	
Food stores, excluding sale of alcohol	P	
Farmers' market and other organized markets	P	
RESTAURANTS		
Carry-out and/or delivery restaurant	P	
Café or coffee shop	P	
Cafeteria	A	
AUTO-ORIENTED		
Parking Garage	S	Section 122-781
Automobile Share Parking	A	
RESEARCH		
Laboratories	P	
TEMPORARY USES		
Food concession sales	P	Section 122-35 (7)
URBAN AGRICULTURE		
Community gardens	A	Exempt from area regulations in 122-274, subject to 122-815
Toolhouses, sheds and other similar buildings for the storage of domestic supplies	A	Must meet accessory structure regulations for building type.
Passive solar structure (greenhouse, hoop house, etc.)	A	Must meet accessory structure regulations for building type.
PERFORMANCE OR STRUCTURES REQUIRING SPECIAL LAND USE		
Operation between 2 a.m. and 6 a.m. during any 24-hour period	S	

Sec. 122-273. Circulation Standards.

Circulation Standards will apply to redevelopment and new development of parcels within the walkable urban districts.

(a) General

1. Streets are intended for use by vehicular and pedestrian traffic and to provide access to lots and open spaces.
2. Streets must generally consist of vehicular lanes and public frontages.
3. Streets must be designed in context with the urban form and desired design speed of the districts through which they pass. The public frontages of streets that pass from one district to another must be adjusted accordingly or, alternatively, the district may follow the alignment of the street to the depth of one lot, retaining a single public frontage throughout its trajectory.
4. Within all the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS Districts, pedestrian comfort must be a primary consideration of the street. Design conflict between vehicular and pedestrian movement generally must be decided in favor of the pedestrian.
5. The street network must be designed to define blocks as established by district. The perimeter must be measured as the sum of lot frontage lines. Block perimeter at the edge of the development parcel must be subject to approval by the Planning Commission.
6. All streets must terminate at other streets, forming a network. Internal streets must connect wherever possible to those on adjacent sites. Cul-de-sacs must be subject to approval by the Planning Commission to accommodate specific site conditions only.
7. Each lot must front a street, pedestrian passage, and/or civic space, such as a park. An entrance to the building with required frontage must face the street or, if a street is not present, the Planning Commission may approve an entrance on the pedestrian passage or civic space.
8. All circulation and block plans must include the easements for non-motorized pathways in the City of Ypsilanti's Non-Motorized Plan, the ReImagine Washtenaw Corridor Improvement Study and any planned road easement expansions approved by City Council.

- (b) *Circulation plan required with site plan for proposal less than 3 acres.* For proposed development that is less than three acres in size, a circulation plan must be submitted which identifies potential cross-and joint-access to adjacent parcels, the existing Block Layout. The Block must be defined as lots and/or all contiguous lots must be considered to be part of a block for this purpose. Pedestrian accommodations and alternative transportation modes must be reflected in the submitted circulation plan. The streetside zone parameters, as outlined Article XI, Division 4 of this Ordinance will also be required to be applied to existing streets. The measurement of the streetside zone, must be from the edge of curb.
- (c) *Block plan required with site plan for proposal greater than 3 acres.* When a proposed development is three acres or greater, a block plan must be required as part of the proposed development which requires the proposed development to construct a block assembly as part of the development as outlined in sub-section d of this Section: Circulation standards for new streets. An applicant must submit the block length, block perimeter and the street type that will be constructed for the development. Streets must be designed to allow for adjacent parcels to connect to existing streets.
- (d) *Circulation standards.*
 1. Streets are intended for use by vehicular and pedestrian traffic and to provide access to lots and open spaces.
 2. Circulation standards must generally consist of vehicular lanes, parking, bicycle lanes, landscape, sidewalks, and outdoor seating.
 3. Streets must be designed in context with the urban form and desired design speed of the districts through which they pass. Circulation that pass from one districts to another must be adjusted accordingly or, alternatively, the district may follow the alignment of the street to the depth of one lot, retaining a single public frontage throughout its trajectory.
 4. Within all the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, pedestrian comfort must be a primary consideration of the street. Design conflict between vehicular and pedestrian movement generally must be decided in favor of the pedestrian.
 5. *Block Perimeter and Block Size.* The street network must be designed around a series of blocks. In order to create a system of land subdivision and development which links one area to another, land should be organized by development blocks to the maximum extent

feasible given the topography and physical characteristics of each individual site. A block perimeter must be measured as the sum of lot frontages. Each district is regulated by a varying block size and perimeter:

- a. Centers and Core Neighborhoods (C, CN, CN-SF, CN-Mid): Block perimeter must not exceed a total length of 1600 feet and the maximum block length must generally be 400 feet.
 - b. Corridors and Health and Human Services (HC, NC, GC, HHS): Block perimeter must not exceed a total length of 2,000 feet and the maximum block length must generally be 500 feet.
6. All Streets must terminate at other streets, in order to form a network. Internal streets must connect wherever possible to those on adjacent sites. Cul-de-sacs must be subject to approval by the Planning Commission to accommodate specific site conditions only.
 7. Each lot must front a street, pedestrian passage, or civic space.
 8. A continuous network of rear and side alleys or lanes, must serve as the primary means of vehicular ingress to individual lots, when possible within Center Districts. Alley or lane entrances should generally align so as to provide ease of ingress for service vehicles.
- (e) *Vehicular access for infill and new development.* New development and redevelopment for joint use driveways and cross access easements. A system of joint use driveways and cross access easements must be established wherever feasible and the building site must incorporate the following:
1. A continuous service drive or cross access extending the entire length of each parcel served to provide for driveway separation consistent with access management classification system and standards.
 2. Stub-outs and other design features to make it visually obvious that the butting properties may be tied in to provide cross access via a service drive;
 3. A unified access and circulation system plan that includes coordinated or shared parking areas is encouraged wherever feasible.

(f) *Access for outparcels and phased development plans*

1. In the interest of promoting unified access and circulation systems, development sites under the same ownership or consolidated for the purposes of development and comprised of more than one building site must not be considered separate properties in relation to the access standards of this code. The number of connections permitted must be the minimum number necessary to provide reasonable access to these properties, not the maximum permitted for that frontage. All necessary easements, agreements, and stipulations required under joint use driveways and cross access easements must be met. This must also apply to phased development plans.
2. All access to outparcels must be internalized using the shared circulation system of the principal development. Access to outparcels must be designed to avoid excessive movement across parking aisles and queuing across surrounding parking and driving aisles

Sec. 122-274. Building Types.

Building types are permitted by Core Neighborhoods, Centers, Corridors and Health and Human Services District(s) as identified in Sec. 122-271 when any new and/or redevelopment occurs on any parcel within these Districts. The building typologies are consistent with the size, scale and character desired within each Neighborhoods, Centers, Corridors and Health and Human Services District.

- (a) *Building Types by Neighborhoods, Centers, Corridors and Health and Human Services District.* The following building types are allowed in Neighborhoods, Centers, Corridors and Health and Human Services districts as shown in the table below. “P” stands for permitted building types, “L” stands for building types allowed in special locations shown on the Zoning Map.

BUILDING TYPE		CN	CN-MID	CN-SF	C	HHS	HC	NC	GC
MA	Mansion	L	L	L	--	--	L	--	--
ES	Estate	P	P	P	--	--	P	P	--
HS	House	P	P	P	--	P	P	P	--
CO	Cottage	P	P	P	--	--	--	--	--
TH	Townhouse	P	P	--	L	--	--	P	--
AH	Apartment House	P	P	--	P	P	P	P	--
CA	Courtyard Apartment	P	--	--	L	--	P	P	P
AB	Apartment Building	P	--	--	L	--	L	P	P
CS	Commercial/Mixed-Use Small	L	--	--	P	--	P	P	P
CM	Commercial/Mixed Use Medium	--	--	--	P	--	P	P	P
CL	Commercial/Mixed Use Large	--	--	--	P	P	--	--	P
SC	Single Story Commercial Building	L	L	L	--	--	L	P	P
LS	Large Single Story Commercial Building	--	--	--	--	P	--	--	P
MB	Multiple Story	--	--	--	P	P	--	--	P
IT	Institutional	P	P	P	P	P	P	P	P

- (b) *New Construction of Limited Building Types requires Site Plan Approval by Planning Commission.* All new construction of limited building types must be subject to site plan review with approval by the Planning Commission per Section 122-123.
- (c) *Categories for Building Types.* The following categories are included in the table provided for each building type. Each standard is labeled by a letter (A, example) which directly relates to the table provided on each building type. The categories are described as follows:
1. Lot requirements. Provisions for minimum and maximums; lot depth, lot size and the permitted lot coverage.
 2. Building envelope. Provisions for the minimum and maximum setbacks permitted by front, side, and rear yards. There are minimum and maximum setback for each lot type. The maximum and minimum frontage refers to the proportion of the lot width along which the primary building façade must be within the minimum and maximum front setback.
 3. Accessory Structure Envelope. Provides the setbacks and maximum building footprints permitted for accessory structures.
 4. Building height: Provisions for permitted heights in stories. The minimum height for all first floors is twelve

(12) feet. The maximum height for first floor residential development must be fourteen (14) feet and twenty (20) feet for nonresidential. Institutional building types may receive a waiver from the Planning Commission (see IT institutional building type and Section 122-780). The minimum height for second story and higher is ten (10) feet. The maximum height for second story and higher must not exceed twelve (12) feet. Each building lot typology provides the range of height appropriate for the building type. Height must be measured from finished floor.

5. Parking provisions: The amount of parking must be determined by Article XIII of this Chapter. Parking provisions provide zones where parking is permitted. The parking zone refers to any uncovered parking area located on the parcel. Driveways are permitted in any zone provided the frontage requirements have been met as required by provided the frontage requirements have been met as required by building type. The diagram illustrates a Primary and Secondary street.


Primary streets are streets that are addressed to the parcel of land. Secondary streets may or may not have access to the parcel. Zones are defined and illustrated by the lot area between the principal building frontage and:

Zone 1: the right-of-way of any primary street.

Zone 2: any common interior lot line.

Zone 3: any rear lot line.

Zone 4: the right-of-way of any secondary street.



6. Private frontages, refers to the area that is attached or integrated into the primary building. The building types are either required or preferred. If there are multiple frontages provided in the table, the applicant may choose what private frontage to provide per building. The private frontage area may count towards the calculation of the frontage build out requirement under the “Building Envelope” category.

- (d) *Building Type Parameters.* The diagrams and text that follow provide the building parameters by building type. Building types must be consistently applied by District and not permitted a variance or waiver to increase in lot size.

1. Lot Size determines Building Types. The size of the lot determines what type of building may be placed on a lot. For instance, a cottage or a house building type may be constructed on 5,000 square foot lot, since all of the those building types fit within the allowed lot size for those building types, but an estate building type is not allowed. Maximum lot depth and width do not determine building types, but all building types must meet the minimum lot width, depth and size.
2. Infill and Redevelopment. Additions, renovations and new buildings on existing built parcels, will require the assembly of building types. The building types are outlined by lot size and will not necessarily need to be replatted or divided to meet the standards. For instance, an addition to an existing building that meets the setbacks in the following table but is on a lot larger than the maximum size does not need to adjust lot lines.
3. Lot Requirements For New And Infill Development. Lot requirements for parcels that may fit more than one building type or several buildings of the same type are permitted. There is no requirement to plat or divide land to create lots on the existing parcel site. However, the building type’s lot requirements as outlined in the table below must be met. For example, a multiple-story building and a commercial mixed use building can be built on the same parcel, without any changes to the lot line locations or a lot split, as long as the other lot requirements for the district can be met. In terms of buildings of a single type, two rows of rental townhouses can be built on a single parcel, without changes or splits of the lot, as long as the width of each unit met the lot requirements and the distance between the two buildings met the side or rear yard setback for both buildings, whichever is applicable.

In the event an existing building exceeds the lot requirements, the Planning Director must determine if a waiver can be granted or require a review by the Planning Commission. A waiver can be issued if the existing and or proposed additions do not exceed the District’s block area and perimeter defined in subsection 122-273(d)5.

4. If the proposed additions to an existing building exceed the block requirements, the applicant may be subject to review by the Planning Commission.

5. *Exceptions to Setbacks.* The following exceptions apply to setbacks for all building types:
- (a) *Historic Structure Front and Rear Yard.* With Planning Commission approval, a structure, if deemed historic by the Ypsilanti Historic District Commission, may encroach up to within five feet of a required front or rear yard or within three feet within a side yard in order to allow the re-use of an existing historic structure or to enhance the authenticity of an historic site; provided that no part of any structure is located on or over any adjacent property.
 - (b) *Accessory Structure Adjacent to Alley or Railroad.* Any setback for an accessory structure adjacent to an alley or railroad right-of-way is one foot.
6. *Double Frontage Lots.* In the case of a row of double frontage lots, one street must be designated as the front street for all lots in the row, with rear setbacks applying to the yards fronting the other street. If there are existing buildings in the same block fronting on one or both of the streets, the required minimum front yard setback must be observed on the street where buildings presently front.

MA

MANSION

Very large buildings originally built as residences, they are located on very large lots that distinguish the building from others nearby with expansive yards. They generally have a single primary entrance. This building type is only permitted by the Planning Commission.

LOT REQUIREMENTS	MIN	MAX
A - Lot Width (ft)	120	--
B - Lot Depth (ft)	120	--
C - Lot Size (sf)	14,440	--
D - Lot Coverage (%)	--	30
BUILDING ENVELOPE	MIN	MAX
E - Street Setback (ft)	30 ⁽¹⁾	--
F - Side Setback (ft)	25	--
G - Rear Setback (ft)	40	--
H - Frontage Buildout (%)	--	--
ACCESSORY BUILDING ENVELOPE	MIN	MAX
I - Street Setback (ft)	30	--
J - Side Setback (ft)	5	--
K - Rear Setback (ft)	5	--
L - Building Footprint (sf)	--	1,200
Note: There is a maximum of two accessory buildings.		
BUILDING HEIGHT	MIN	MAX
M - Principal Building (st)	1	3
N - Accessory Structure(s) (ft)	--	15
PARKING PROVISIONS		


Location Front, Side, street-side yard, and rear yards

⁽¹⁾ The street setback will be determined by the average of the front yards of existing buildings on the same street side and block in which the new building is being proposed.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY STRUCTURE ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



Large buildings, built as residences, they are located on large lots that accommodate large yards. They generally have distinguishing architectural features and one primary entrance.

LOT REQUIREMENTS	MIN	MAX
A - Lot Width (ft)	80	120
B - Lot Depth (ft)	120	--
C - Lot Size (sf)	9,600	21,780
D - Lot Coverage (%)	--	30
BUILDING ENVELOPE	MIN	MAX
E - Street Setback (ft)	20 ⁽¹⁾	--
F - Side Setback (ft)	10	--
G - Rear Setback (ft)	25	--
H - Frontage Buildout (%)	--	80
ACCESSORY BUILDING ENVELOPE	MIN	MAX
I - Street Setback (ft)	30	--
J - Side Setback (ft)	5	--
K - Rear Setback (ft)	5	--
L - Building Footprint (sf)	--	950

Note: There is a maximum of two accessory buildings.

BUILDING HEIGHT	MIN	MAX
M - Principal Building (st)	1	3
N - Accessory Structure(s) (ft)	--	15

PARKING PROVISIONS
Location
Side, street-side yard, and rear yards


PRIVATE FRONTAGES	Required:
-------------------	-----------

⁽¹⁾ The street setback will be determined by the average of the front yards of existing buildings on the same street side and block in which the new building is being proposed in residential districts only.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY STRUCTURE ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



HS

HOUSE

Detached residential buildings built for a single dwelling unit. They are located on lots that accommodate a detached primary building with small side yards and relatively large rear or front yards. They generally have one primary entrance.


LOT REQUIREMENTS	MIN	MAX
A - Lot Width (ft)	35	80
B - Lot Depth (ft)	100	--
C - Lot Size (sf)	4,000	12,000
D - Lot Coverage (%)	--	60
BUILDING ENVELOPE	MIN	MAX
E - Street Setback (ft)	15 ⁽¹⁾	25
F - Side Setback (ft)	5	--
G - Rear Setback (ft)	20	--
H - Frontage Buildout (%)	60	80
ACCESSORY BUILDING ENVELOPE	MIN	MAX
I - Street Setback (ft)	30	--
J - Side Setback (ft)	5	--
K - Rear Setback (ft)	5	--
L - Building Footprint (sf)	--	800
Note: There is a maximum of two accessory buildings		
BUILDING HEIGHT	MIN	MAX
M - Principal Building (st)	1	3
N - Accessory Structure(s) (ft)	--	15
PARKING PROVISIONS	Location	
	Side, street-side yard, and rear yards	
PRIVATE FRONTAGES	Required:	
	Porch or Stoop	

⁽¹⁾ The street setback will be determined by the average of the front yards of existing buildings on same street side and block in which the new building is being proposed in residential districts only.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY STRUCTURE ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



Small residential buildings, sized for a single dwelling. They are located on lots that accommodate a detached primary building with small yards. They are generally a single-story building or bungalow with a single primary entrance.


LOT REQUIREMENTS	MIN	MAX
A - Lot Width (ft)	25	35
B - Lot Depth (ft)	50	150
C - Lot Size (sf)	2,500	6,300
D - Lot Coverage (%)	--	70
BUILDING ENVELOPE	MIN	MAX
E - Street Setback (ft)	10 ⁽¹⁾	20
F - Side Setback (ft)	3	--
G - Rear Setback (ft)	10	--
H - Frontage Buildout (%)	70	90
ACCESSORY BUILDING ENVELOPE	MIN	MAX
I - Street Setback (ft)	30	--
J - Side Setback (ft)	3	--
K - Rear Setback (ft)	5	--
L - Building Footprint (sf)	--	500
Note: There is a maximum of two accessory buildings		
BUILDING HEIGHT	MIN	MAX
M - Principal Building (st)	1	2
N - Accessory Structure(s) (ft)	--	15
PARKING PROVISIONS	Location	
	Side, street-side yard, and rear yards	
PRIVATE FRONTAGES	Required:	

⁽¹⁾ The street setback will be determined by the average of the front yards of existing buildings on the same street side and block in which the new building is being proposed in residential districts only.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY STRUCTURE ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



A row of attached residential buildings. They are located on lots which accommodate a building of two or more units with party walls and a private back yard. Each dwelling has its own entrance to the street.

LOT REQUIREMENTS	MIN	MAX
A - Lot Width (ft)	15	25 ⁽²⁾
B - Lot Depth (ft)	80	120
C - Lot Size (sf)	1,200	3,000
D - Lot Coverage (%)	--	60
BUILDING ENVELOPE	MIN	MAX
E - Street Setback (ft)	10 ⁽¹⁾	20 ⁽¹⁾
F - Side Setback (ft)	0 ⁽²⁾	--
G - Rear Setback (ft)	15	--
H - Frontage Buildout (%)	90	100
Note: A maximum of 6 units may be provided in a row		
ACCESSORY BUILDING ENVELOPE	MIN	MAX
I - Street Setback (ft)	30	--
J - Side Setback (ft)	3	--
K - Rear Setback (ft)	5	--
L - Building Footprint (sf)	--	800
Note: There is a maximum of two accessory buildings.		
BUILDING HEIGHT	MIN	MAX
M - Principal Building (st)	1	3
N - Accessory Structure(s) (ft)	--	15
PARKING PROVISIONS		
Location	Rear Yard	
PRIVATE FRONTAGES	Required:	
	Porch or Stoop	


⁽¹⁾ If located on Washtenaw Avenue must build no more than 10 ft from future right-of-way line

⁽²⁾ End unit lot may be up to 10' larger.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY STRUCTURE ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



Detached residential buildings converted to contain two or more dwelling units. They are located on lots that accommodate the associated parking and outdoor living areas for several dwellings. Each may have its own entrance.

LOT REQUIREMENTS	MIN	MAX
A - Lot Width (ft)	40	120
B - Lot Depth (ft)	100	150
C - Lot Size (sf)	4,000	18,000
D - Lot Coverage (%)	--	50
BUILDING ENVELOPE	MIN	MAX
E - Street Setback (ft)	15 ⁽¹⁾⁽²⁾	25
F - Side Setback (ft)	5	--
G - Rear Setback (ft)	20	--
H - Frontage Buildout (%)	60	80
ACCESSORY BUILDING ENVELOPE	MIN	MAX
I - Street Setback (ft)	30 ⁽¹⁾	--
J - Side Setback (ft)	5	--
K - Rear Setback (ft)	5	--
L - Building Footprint (sf)	--	800
Note: There is a maximum of two accessory buildings.		
BUILDING HEIGHT	MIN	MAX
M - Principal Building (st)	1	3
N - Accessory Structure(s) (ft)	--	15
PARKING PROVISIONS	Location	
	Side, street-side yard, and rear yards	
PRIVATE FRONTAGES	Required:	
	Porch or Stoop	


⁽¹⁾ If located on Washtenaw Avenue must build no more than 10ft from future right-of-way line

⁽²⁾ The street setback will be determined by the average of the front yards of existing buildings on the same street side and block in which the new building is being proposed in residential districts only.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY STRUCTURE ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



CA

COURTYARD
APARTMENT

A grouping of buildings, containing multiple dwellings each, arranged around and fronting on a central courtyard that may be partially or wholly open to the street. The lot also accommodates the associated parking and outdoor living areas. Each dwelling may have its own entrance.


LOT REQUIREMENTS	MIN	MAX
A - Lot Width (ft)	80	200
B - Lot Depth (ft)	80	180
C - Lot Size (sf)	6,400	20,000
D - Lot Coverage (%)	--	80
BUILDING ENVELOPE	MIN	MAX
E - Street Setback (ft)	10 ⁽¹⁾	20
F - Side Setback (ft)	0	10
G - Rear Setback (ft)	10	--
H - Frontage Buildout (%)	50	75
ACCESSORY BUILDING ENVELOPE	MIN	MAX
I - Street Setback (ft)	30	
J - Side Setback (ft)	10	--
K - Rear Setback (ft)	10	--
L - Building Footprint (sf)	--	800
BUILDING HEIGHT	MIN	MAX
M - Principal Building (st)	2	4
N - Accessory Structure(s) (ft)	--	15
PARKING PROVISIONS		
Location	Side and Rear Yards	
PRIVATE FRONTAGES	Required:	
	Forecourt	

⁽¹⁾ If located on Washtenaw Avenue must build no more than 10ft from future right-of-way line




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY STRUCTURE ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



AB

APARTMENT BUILDING

Multiple-story buildings, designed for multifamily residential use. They are located on lots that may be as large as a city block and can accommodate two or more dwellings as well as the associated parking, waste disposal, and outdoor living areas.

LOT REQUIREMENTS	MIN	MAX
A - Lot Width (ft)	40	300
B - Lot Depth (ft)	100	300
C - Lot Size (sf)	4,000	90,000
D - Lot Coverage (%)	--	80
BUILDING ENVELOPE	MIN	MAX
E - Street Setback (ft)	10 ⁽¹⁾	25 ⁽¹⁾
F - Side Setback (ft)	5	--
G - Rear Setback (ft)	15 ⁽²⁾	--
H - Frontage Buildout (%)	60	80
ACCESSORY BUILDING ENVELOPE	MIN	MAX
I - Street Setback (ft)	30	--
J - Side Setback (ft)	10	--
K - Rear Setback (ft)	10	--
L - Building Footprint (sf)	--	800
BUILDING HEIGHT	MIN	MAX
M - Principal Building (st)	2	6
N - Accessory Structure(s) (ft)	--	15
PARKING PROVISIONS		
Location	Side and Rear Yards	
PRIVATE FRONTAGES	Required:	
	Porch, Forecourt or Stoop	


⁽¹⁾ If located on Washtenaw Avenue must build no more than 10 ft from future right-of-way line

⁽²⁾ When adjacent to existing single family residential detached homes, the rear setback shall be 25 ft.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY STRUCTURE ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



COMMERCIAL/ MIXED-USE - SMALL

Small multiple-story buildings, often designed for commercial or office uses on the ground floor and dwellings or offices above. They are located on lots that can accommodate a building that is less than 20% of a city block width.


LOT REQUIREMENTS	MIN	MAX
A - Lot Width (ft)	15	60
B - Lot Depth (ft)	80	120
C - Lot Size (sf)	1,800	7,200
D - Lot Coverage (%)	--	90
BUILDING ENVELOPE	MIN	MAX
E - Street Setback (ft)	0 ⁽¹⁾	15 ⁽¹⁾
F - Side Setback (ft)	0	--
G - Rear Setback (ft)	5	--
H - Frontage Buildout (%)	80	100
ACCESSORY BUILDING ENVELOPE	MIN	MAX
I - Street Setback (ft)	30	--
J - Side Setback (ft)	3	--
K - Rear Setback (ft)	10	--
L - Building Footprint (sf)	--	800
BUILDING HEIGHT	MIN	MAX
M - Principal Building (st)	2	4
N - Accessory Structure(s) (ft)	--	15
PARKING PROVISIONS		
Location	Side and Rear Yards	
PRIVATE FRONTAGES	Required:	
	Commercial	

⁽¹⁾ If located on Washtenaw Avenue must build no more than 10ft from future right-of-way line




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY STRUCTURE ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



Average-sized multiple-story buildings, often designed for commercial or office uses on the ground floor and dwellings or offices above. They are located on lots that can accommodate a building that spans 20-40% of a city block width.

LOT REQUIREMENTS	MIN	MAX
A - Lot Width (ft)	60	120
B - Lot Depth (ft)	--	500
C - Lot Size (sf)	--	60,000
D - Lot Coverage (%)	--	90
BUILDING ENVELOPE	MIN	MAX
E - Street Setback (ft)	0 ⁽¹⁾	15 ⁽¹⁾
F - Side Setback (ft)	0	--
G - Rear Setback (ft)	10 ⁽²⁾	--
H - Frontage Buildout (%)	90	100
ACCESSORY BUILDING ENVELOPE	MIN	MAX
I - Street Setback (ft)	30	--
J - Side Setback (ft)	10	--
K - Rear Setback (ft)	10	--
L - Building Footprint (sf)	--	800
BUILDING HEIGHT	MIN	MAX
M - Principal Building (st)	2	5
N - Accessory Structure(s) (ft)	--	15
PARKING PROVISIONS		
Location	Side and Rear Yards	
PRIVATE FRONTAGES	Required:	


⁽¹⁾ If located on Washtenaw Avenue must build no more than 10ft from future right-of-way line

⁽²⁾ When adjacent to existing single family residential detached homes, the rear setback shall be 25 ft.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY STRUCTURE ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



COMMERCIAL/ MIXED-USE - LARGE

Large multiple-story buildings, often designed for commercial or office uses on the ground floor and dwellings or offices above. They are located on lots that can accommodate a building that spans up to an entire city block width. .

LOT REQUIREMENTS	MIN	MAX
A - Lot Width (ft)	120	300
B - Lot Depth (ft)	--	500
C - Lot Size (sf)	--	150,000
D - Lot Coverage (%)	--	90
BUILDING ENVELOPE	MIN	MAX
E - Street Setback (ft)	0 ⁽¹⁾	15 ⁽¹⁾
F - Side Setback (ft)	0	--
G - Rear Setback (ft)	10 ⁽²⁾	--
H - Frontage Buildout (%)	90	100
ACCESSORY BUILDING ENVELOPE	MIN	MAX
I - Street Setback (ft)	30	--
J - Side Setback (ft)	10	--
K - Rear Setback (ft)	10	--
L - Building Footprint (sf)	--	800
BUILDING HEIGHT	MIN	MAX
M - Principal Building (st)	2	8
N - Accessory Structure(s) (ft)	--	15
PARKING PROVISIONS		
Location	Side and Rear Yards	
PRIVATE FRONTAGES	Required:	
	Commercial	


⁽¹⁾ If located on Washtenaw Avenue must build no more than 10ft from future right-of-way line

⁽²⁾ When adjacent to existing single family residential detached homes, the rear setback shall be 25 ft.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY STRUCTURE ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



SC

SINGLE STORY COMMERCIAL BUILDING

A single-story building, designed for non-residential use. They are located on lots that accommodate a detached primary building with the associated parking, loading, and waste disposal areas. A single use is generally located in each building.

LOT REQUIREMENTS		MIN	MAX
A - Lot Width (ft)		50	300
B - Lot Depth (ft)		100	300
C - Lot Size (sf)		7,500	90,000
D - Lot Coverage (%)		--	60
BUILDING ENVELOPE		MIN	MAX
E - Street Setback (ft)		5 ⁽¹⁾	15 ⁽¹⁾
F - Side Setback (ft)		0	--
G - Rear Setback (ft)		15 ⁽²⁾	--
H - Frontage Buildout (%)		50	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I - Street Setback (ft)		30 ^l	--
J - Side Setback (ft)		10	--
K - Rear Setback (ft)		10 ^l	--
L - Building Footprint (sf)		--	800
BUILDING HEIGHT		MIN	MAX
M - Principal Building (st)		1	1
N - Accessory Structure(s) (ft)		--	15
PARKING PROVISIONS			
Location	Side, Street-Side and Rear Yards		
PRIVATE FRONTAGES		Permitted:	


⁽¹⁾ If located on Washtenaw Avenue must build no more than 10ft from future right-of-way line

⁽²⁾ When adjacent to existing single family residential detached homes, the rear setback shall be 25 ft.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY STRUCTURE ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



LF

LARGE SINGLE STORY COMMERCIAL BUILDING

Large one-story buildings that contain one or more uses. They are located on lots that accommodate the building and its associated parking, loading, and waste disposal areas. Each unit may have its own entrance to the street.

LOT REQUIREMENTS	MIN	MAX
A - Lot Width (ft)	300	Block
B - Lot Depth (ft)	300	Block
C - Lot Size (sf)	90,000	--
D - Lot Coverage (%)	45	80
BUILDING ENVELOPE	MIN	MAX
E - Street Setback (ft)	5 ⁽¹⁾	15 ⁽¹⁾
F - Side Setback (ft)	0	--
G - Rear Setback (ft)	10 ⁽²⁾	--
H - Frontage Buildout (%)	50	100
ACCESSORY BUILDING ENVELOPE	MIN	MAX
I - Street Setback (ft)	30	--
J - Side Setback (ft)	10	--
K - Rear Setback (ft)	10	--
L - Building Footprint (sf)	--	800
BUILDING HEIGHT	MIN	MAX
M - Principal Building (st)	1	1
N - Accessory Structure(s) (ft)	--	15
PARKING PROVISIONS		
Location	Side and Street-Side and Rear Yards	
PRIVATE FRONTAGES	Permitted:	
	Commercial	


⁽¹⁾ If located on Washtenaw Avenue must build no more than 10ft from future right-of-way line

⁽²⁾ When adjacent to existing single family residential detached homes, the rear setback shall be 25 ft.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY STRUCTURE ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



MB

MULTIPLE STORY BUILDING

Large multiple-story buildings, designed for a single type of commercial use, such as office. They are located on lots that can accommodate a building that spans up to an entire city block width.

LOT REQUIREMENTS	MIN	MAX
A - Lot Width (ft)	120	310
B - Lot Depth (ft)	--	500
C - Lot Size (sf)	--	150,000
D - Lot Coverage (%)	--	90
BUILDING ENVELOPE	MIN	MAX
E - Front Setback (ft)	5 ⁽¹⁾	25 ⁽¹⁾
F - Side Setback (ft)	0	--
G - Rear Setback (ft)	10 ⁽²⁾	--
H - Frontage Buildout (%)	50	100
ACCESSORY BUILDING ENVELOPE	MIN	MAX
I - Street Setback (ft)	30	--
J - Side Setback (ft)	10	--
K - Rear Setback (ft)	10	--
L - Building Footprint (sf)	--	800
BUILDING HEIGHT	MIN	MAX
M - Principal Building (st)	2	6
N - Accessory Structure(s) (ft)	--	15
PARKING PROVISIONS	Location	
	Side, Street-Side and Rear Yards	
PRIVATE FRONTAGES	Permitted:	
	Commercial	


⁽¹⁾ If located on Washtenaw Avenue must build no more than 10ft from future right-of-way line

⁽²⁾ When adjacent to existing single family residential detached homes, the rear setback shall be 25 ft.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY STRUCTURE ENVELOPE



BUILDING HEIGHT



PARKING LOCATION



Buildings originally designed to house government, assembly, or institutional uses. They are located on lots that can accommodate the primary building, associated parking, loading, waste disposal areas, and outdoor living areas, as applicable.

LOT REQUIREMENTS		MIN	MAX
A - Lot Width (ft)		50	Block Max
B - Lot Depth (ft)		100	Block Max
C - Lot Size (sf)		5,000	--
D - Lot Coverage (%)		--	60
BUILDING ENVELOPE		MIN	MAX
E - Street Setback (ft)		15 ⁽¹⁾	--
F - Side Setback (ft)		0	--
G - Rear Setback (ft)		15	--
H - Frontage Buildout (%)		50	100
ACCESSORY BUILDING ENVELOPE		MIN	MAX
I - Street Setback (ft)		30	
J - Side Setback (ft)		10	--
K - Rear Setback (ft)		10	--
L - Building Footprint (sf)		--	800
BUILDING HEIGHT		MIN	MAX
M - Principal Building (st)		1	4 ⁽²⁾
N - Accessory Structure(s) (ft)		--	15
PARKING PROVISIONS			
Location	Side, Street Side and Rear Yards,		
PRIVATE FRONTAGES		Required:	
		No specific frontage required	


⁽¹⁾ If located on Washtenaw Avenue must build no more than 10ft from future right-of-way line

⁽²⁾ Additional height may be granted by the Planning Commission if the Commission finds the additional height to be consistent within that district.




EXAMPLE


LOT REQUIREMENTS AND BUILDING ENVELOPE




ACCESSORY STRUCTURE ENVELOPE



BUILDING HEIGHT



PARKING LOCATION




P

PORCH

The façade is set back from the front lot line per applicable street setback requirements. The façade includes an attached front porch structure. A wide variety of porch designs are possible.

FRONTAGE ZONE (FZ)	MIN	MAX
Porch structure requirements:		
A - Width (clear) (ft)	10	--
B - Depth (clear) (ft)	5	--
C - Height (clear) (ft)	7	--
INTERFACE ZONE (IZ)		
Landscape with path (3' wide min) from sidewalk to structure		
OTHER REQUIREMENTS		
Refer to Historic Guidelines when developing within the Historic District.		

FRONTAGE ZONE AND INTERFACE ZONE DIMENSIONS




S

STOOP

The façade is set back from the front lot line per applicable street setback requirements. The façade includes an attached entry stoop (an elevated landing with stairs) that is placed at or near the front lot line. The ground floor is elevated to provide privacy. The stoop may include a roof.

FRONTAGE ZONE (FZ)	MIN	MAX
Stoop structure requirements:		
A - Width (clear) (ft)	5	8
B - Depth (clear) (ft)	3	8
C - Height (clear) (ft)	7	--
INTERFACE ZONE (IZ)		
Landscape with path (3' wide min) from sidewalk to structure		
OTHER REQUIREMENTS		
Refer to Historic Guidelines when developing within the Historic District.		

FRONTAGE ZONE AND INTERFACE ZONE DIMENSIONS




F

FORECOURT

The façade is set back from the front lot line per applicable street setback requirements. A portion of the façade is recessed to form an uncovered court. The court is suitable for outdoor dining, gardens, vehicle drop-offs, formal entries etc.. A fence or wall may be used to define the private space of the court. The court may be elevated behind a retaining wall at or near the front lot line with entry steps to the court.

FRONTAGE ZONE (FZ)	MIN	MAX
Courtyard requirements:		
A - Width (clear) (ft)	12	--
B - Depth (clear) (ft)	12	50
INTERFACE ZONE (IZ)		
Landscape with path (6' wide min) from sidewalk to structure		
OTHER REQUIREMENTS		
Refer to Historic Guidelines when developing within the Historic District.		

FRONTAGE ZONE AND INTERFACE ZONE DIMENSIONS



C

COMMERCIAL

The façade is set back from the front lot line per applicable street setback requirements, typically at or near the front lot line with the entrance at sidewalk grade. The façade may include an awning, shed roof, or gallery (a lightweight colonnade with no habitable building space above it) that covers the sidewalk and may extend into the right-of-way. The façade has a substantial amount of glazing at the sidewalk level. Recessed entrances are acceptable.

FRONTAGE ZONE (FZ)	MIN	MAX
Building facade requirements:		
A - Distance between openings (ft)	--	2
B - Door recess (ft)	--	5
C - Ground floor transparency (%)	60	--
D - Height to bottom of window (ft)	--	2.5

INTERFACE ZONE (IZ)


Extended sidewalk from right-of-way edge to structure

OPTIONAL ELEMENTS	MIN	MAX
AWNING or GALLERY		
E - Setback from curb (ft)	2	--
F - Depth (clear) (ft) (Gallery min 8')	4	10
G - Height (clear) (ft)	8	--

OTHER REQUIREMENTS

Refer to Historic Guidelines when developing within the Historic District.

FRONTAGE ZONE AND INTERFACE ZONE DIMENSIONS



Sec. 122-275. Reserved.

Sec. 122-276. Number of detached accessory buildings

No more than two detached accessory buildings are permitted on a lot in the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts.

Sec. 122-277. Steps for Use of Regulations for CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts

The following illustrates the steps a user would follow for projects in the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts. This is illustrative only and is not intended to set forth the administration and procedures, which are set in Article IV.

Quick Code Guide CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS Districts – Projects 3 acres or more			
Step	Instructions	Section	Title
(1)	Find the district for your parcel	Sec. 122-232	Zoning Map
(2)	Confirm proposed use(s) is allowed in district	Sec. 122-272	Permitted Uses
(3)	Create a Block Plan that complies with the circulation standards of these districts	Sec. 122-126 17 (b)	Block Plan Requirements
		Sec. 122-273	Circulation Standards
(4)	If the project requires division of property, follow procedures and comply with the requirements for land division or site condominiums	Article X	Site Condominiums
		Sec. 122-756	Land Division
(5)	Comply with parking and landscaping requirements	Article XI, Division 4	Landscaping and Screening
		Article XIII	Off-Street Parking and Loading Requirements
(6)	Follow Procedures for Project 3 acres or less	See following table	

Quick Code Guide CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS Districts – Projects 3 acres or less			
Step	Instructions	Section	Title
(1)	Find the district for your parcel	Sec. 122-232	Zoning Map
(2)	Confirm proposed use(s) is allowed in district	Sec. 122-272	Permitted Uses
(3)	Determine if your site is within a Historic Designation. If so, see step	Chapter 54 of City Code of Ordinances	Historic District
(4)	Create circulation plan that complies with Circulation Standards	Sec. 122-273	Circulation Standards
(5)	Chose building type(s) for your site	Sec. 122-274	Building Lot Typologies
(6)	Comply with the Building Parameters by Building Type	Sec. 122-274	Building Lot Typologies
(7)	Comply with parking, landscaping and sign regulations	Article XI, Division 4	Landscaping and Screening
		Article XIII	Off-Street Parking and Loading Requirements
		Article XIV	Signs
(8)	Follow procedures and comply with the requirements for permit application		Article IV
(9)	If within Historic Designation, apply for Historic District Work Application	Chapter 54 of City Code of Ordinances	Historic District

Secs. 122-278-122-290. Reserved

DIVISION 5.
PRODUCTION, MANUFACTURING AND DISTRIBUTION DISTRICT

Sec. 122-291. Description and purpose.

The PMD Production, Manufacturing and Distribution district is designed to create and sustain jobs and industry producing, manufacturing, storing and distributing goods. These districts should be located where buildings can be on large plots of contiguous land, serviced by railroad lines or major thoroughfares, and adequately served by required utilities, and services. All operations must be fully contained within well-designed buildings, with adequate off-street parking and loading areas, and with property screening around outside storage areas. Uses are expected to generate waste, noise, odor and truck traffic. Principal uses should produce minimal external impacts that are detrimental in any way to other uses in the district or to properties in adjoining districts. Special uses are expected to produce external impacts and should, therefore, be located only where such impacts will not be detrimental to other uses in the PMD district or to properties in adjoining districts.

Sec. 122-292. Permitted uses.

The following uses are allowed in the PMD district. Any other use which must be determined by the City Council after recommendation from the Planning Commission, to be of the same general character as the below permitted or special uses. The City Council may impose any required setback and/or performance standards above and beyond the requirements of this chapter so as to insure public health, safety and general welfare.

*P=Principal; A=Accessory; S/Res= Special Land adjacent to R-1, CN, CN-Mid, CN-SF & MD zoning, otherwise permitted;
S=Special Land Use*

USES	PMD	NOTES
INFRASTRUCTURE		
Essential Services	P	Section 122-637
Communication Devices	A	Article XI, division 3
Radio & Television Studios or Stations	P	
Radio and television towers, public utility microwaves, and public utility television transmitting towers, mobile communications towers, cellular phone towers and their accessory facilities	S	Section 122-687
Utility buildings including electric and gas service buildings and yards, telephone exchange buildings, electrical transformer stations and substations, gas regulator stations, and water and propane tank holders.	S	
Railroad yards not including manufacture and repair	S/Res	
Energy, electricity and heat generation plants	S	Includes solar farms and geothermal plants; see Sec 122-788
Landfill	S	May include anaerobic digester.
Water or sewage treatment plant	S	
Biofiltration Facility	P	
Alternative Energy	A	Section 122-788
Stormwater Control	A	Section 122-789
SERVICES		
Business and professional offices and services, 15,000 square feet or greater	P	
Business and professional offices and showrooms ancillary to the primary use	P	These uses may not exceed 25% of the gross floor area.
Kennels, commercial	S/Res	Section 122-791
Offices for skilled trade services including but not limited to plumbing, electric, heating, and painting establishments	P	
Repair of appliances, machines or vehicles	P	

*P=Principal; A=Accessory; S/Res= Special Land adjacent to R-1, CN, CN-Mid, CN-SF & MD zoning, otherwise permitted;
S=Special Land Use*

USES	PMD	NOTES
Self-storage facilities	P	
Printing services, including but not limited to: publishing, engraving, photo development, lithographing, silk screening and three-dimensional printing	P	Section 122-810
Construction and Landscape Contractors, contractor's yards, equipment and materials storage	S	
Recycling centers	S	
AUTO-ORIENTED		
Automobile Wash & Detailing	P	
Automobile Share Parking	A	
Truck Wash	S	
Automobile Repair	P	Section 122-775
Automobile rental (parking, storage, wash & repair)	P	
Vehicle, Recreational Vehicle, Storage and Towing	S/Res	
Vehicle Wrecking, Salvage, Storage of Inoperable Vehicles	S	
RESEARCH		
Laboratories	S/Res	
Development & Research	S/Res	
PRODUCTION, MANUFACTURING & DISTRIBUTION		
Manufacture or processing of food products including brewing & distilling	P	
Craft manufacturing	P	
Medical Marijuana Growing/Manufacturing Facility	S	Section 122-814
Storage, warehousing and wholesale distribution	S/Res	Outdoor storage is a special land use subject to section 122-801
Junkyards	S	Section 122-790
Central dry cleaning plants	S	
Clothing production	P	
Software, film, music, television and radio, and video game development & physical production	S/Res	Adult regulated uses are special land uses.
Assembly and production, from prefabricated parts, of household appliances, electronic products, hardware products, and similar products	S/Res	
Processing or assembling of parts for production of finished equipment	S/Res	
Dry cleaning plants or laundries	S	
Manufacturing, Compounding, Processing, packing or treatment of such products as candy, cosmetics, drugs, perfumes, pharmaceuticals, and toiletries, except the rendering or refining of fats and oils	S/Res	
Manufacturing of alcohol; ammonia; bleaching powder or chlorine; asphalt, including refining; brick, tile or terra cotta; chemicals; concrete or cement products; lampblack; oil cloth or linoleum; paint, oil, shellac, turpentine, lacquer or varnish; petroleum products; plastics; soap; sodium compounds; tar distillation or tar products	S	

*P=Principal; A=Accessory; S/Res= Special Land adjacent to R-1, CN, CN-Mid, CN-SF & MD zoning, otherwise permitted;
S=Special Land Use*

USES	PMD	NOTES
Manufacturing of machine tools, machinery, vehicles of all types, machine or vehicle components or that requires metal plating or galvanizing, plastic extrusion or molding or similar process	S	
Metal Foundry or fabricating plant and heavyweight casting	S	
Manufacture of construction materials	S	
Manufacturing of textiles, rubber or synthetic treated products	S	
Manufacture and repair of train cars, locomotives and track	S	
Animal slaughter and processing	S	Except aquaculture and aquaponics.
Ethanol, petroleum and fuel production, refining and storage	S	
Passive solar structure (greenhouse, hoophouse, etc.)	P	
Hydroponics, aquaculture and aquaponics and similar raising of food	P	All activities must take place indoors.
PERFORMANCE OR STRUCTURES REQUIRING SPECIAL LAND USE		
Adult regulated uses	S	Section 122-774
Outdoor storage	S/Res	Section 122-801
Storage of liquid and solid fuels	S	Section 122-807
Any other use as determined by the City Council after recommendation from the Planning Commission, to be of the same general character as the above permitted or special uses. The City Council may impose any required setback and/or performance standards above and beyond the requirements of this chapter so as to insure public health, safety and general welfare.	S	

Sec. 122-293. Area Regulations.

All principal structures must comply with the following regulations in the special zoning districts:

REGULATIONS	PMD	NOTES
Minimum Lot Width		
Determined by the use and the required off-street parking, loading, screening and yard setbacks		
Minimum Lot Size		
Determined by the use and the required off-street parking, loading, screening and yard setbacks		
Minimum Setbacks		
Front yard	25 feet	Minimum setbacks must increase by one foot for each foot a building or structure exceeds 30 feet in height.
Side yard	15 feet	
Street Side yard	15 feet	
Rear yard	20 feet	
From adjacent R-1, CN-SF, CN-Mid, CN, MD, HHS districts	25 feet	Screen required per section 122-703.
Parking Setbacks		
Front & street side yard	10 feet	In PMD, greenbelt required per subsection 122-835(11)
Side and rear yards	10 feet	
From adjacent residential zoning district	15 feet	No storage is permitted in setback from residential zoning district
Height		
Maximum height	60 feet	Chimneys, flagpoles, church spires, belfries, cupolas, domes, or other similar architectural embellishments; roof mounted communication antennas; water towers, observation towers, power transmission towers, radio towers, masts, smokestacks, ventilators, skylights, derricks, conveyors, cooling towers, and other similar and necessary mechanical appurtenance pertaining to the permitted uses; provided that they do not exceed the maximum height by more than ten feet

Sec. 122-294. Performance Standards for PMD District.

- (a) *Deleterious operations.* No activity, operation, or use must be permitted on any property which by reason of the emission of odor, fumes, smoke, vibration, radiation, heat, glare, dust, soot, noise, or disposal of waste is deleterious to other permitted activities in the zoning district or is obnoxious or offensive to uses permitted in neighboring districts, or is harmful to the general health, safety, or welfare, of the community.
- (b) *Enclosed buildings.* All manufacturing, compounding, assembling, processing, packaging, or other industrial or business activity in must be conducted within a completely enclosed building, except as otherwise specified.

Sec. 122-295-300. Reserved.

DIVISION 6.
PARK DISTRICT

Sec. 122-301. Description and purpose.

The P Park district is designed to preserve publicly and privately owned green space, including parks and cemeteries. When embedded in R-1, CN-SF, CN-Mid, CN, MD and HHS districts, the district is intended to provide the essential green space for urban neighborhoods. When on the outskirts of the city, the district maintains large green spaces, such as cemeteries. Along the Huron River, the district provides recreation as well as environmental protections. Temporary uses may be allowed to encourage use and vitality of these areas.

Sec. 122-302. Permitted uses.

The following uses are allowed in the park districts.

P=Principal, A=Accessory, S=Special Land Use, -- = Not Permitted

USES	P	NOTES
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES		
Park	P	
Outdoor and indoor education areas	P	
Outdoor recreation areas such as swimming pools, tennis courts, and performance venues	P	Privately owned.
Conservation areas, wildlife preserves, forests preserves, arboreta, botanical or zoological gardens, public tree or plant nurseries	P	
Privately owned or operated uses accessory to City parks	S	Includes but is not limited to permanently affixed concession stands, canoe or bicycle liveries.
INFRASTRUCTURE		
Essential Services	P	Section 122-637
Solar Farms	S	Section 122-788
Alternative Energy	A	Section 122-788
Stormwater Control	A	Section 122-789
SERVICES		
Cemetery	P	
Crematory	S	All principal buildings must be set back at least 75 feet from all property lines.
TEMPORARY USES		
Food concession sales	P	Section 122-35 (7)
URBAN AGRICULTURE		
Community Gardens	P	Subject to 122-815
Passive solar structure (greenhouse, hoophouse, etc.)	P	

Sec. 122-303. Area Regulations.

All principal structures must comply with the following regulations in the special zoning districts:

REGULATIONS		P	NOTES
Minimum Lot Width			
Determined by the use and the required off-street parking, loading, screening, and yard setbacks.			
Minimum Lot Size			
Determined by the use and the required off-street parking, loading, screening, and yard setbacks.			
Minimum Setbacks			
Front yard	25 feet	Minimum setbacks must increase by one foot for each foot a building or structure exceeds 30 feet in height.	
Side yard	15 feet		
Street Side yard	25 feet		
Rear yard	20 feet		
Parking Setbacks			
Front & side street yard	10 feet		
Side and rear yards	10 feet		
Height			
Maximum height	Equal to that of adjacent zoning district or building type along the property line. If different heights abut, the largest setback is required.	Chimneys, flagpoles, church spires, belfries, cupolas, domes, or other similar architectural embellishments; roof mounted communication antennas; water towers, observation towers, power transmission towers, radio towers, masts, smokestacks, ventilators, skylights, derricks, conveyors, cooling towers, and other similar and necessary mechanical appurtenance pertaining to the permitted uses; provided that they do not exceed the maximum height by more than ten feet.	

Sec. 122-304--122-520. Reserved.

ARTICLE VIII. RESERVED

Sec. 122-521--122-570. Reserved.

ARTICLE IX. PLANNED UNIT DEVELOPMENT *

*State law reference(s)--Planned unit development, MCL 125.584b, MSA 5.2934(2).

Sec. 122-571. Description and purpose.

- (a) It is the purpose of this article to provide guidelines for development or redevelopment which is planned as a unit. Toward this end, it is the intent of these regulations to allow flexibility in the regulation of land development; encourage innovation in land use and variety in design, layout, and type of structures constructed; achieve economy and efficiency in the use of land, energy, public services, and utilities; encourage useful open space; provide better housing, employment, shopping opportunities, compatibility of design, and use between neighboring properties; facilitate the preservation and reuse of historic structures; and encourage development that is consistent with the city's master land use plan.
- (b) The approval of a planned unit development application requires an amendment to this chapter to revise the Zoning Map and designate the subject property as "PUD, planned unit development." An approval granted under this article, including all aspects of the final site development plan and conditions imposed on it, constitutes an inseparable part of this chapter.
- (c) The provisions of this article are not intended as a device for ignoring this chapter, the specific standards set forth in this chapter, or the planning upon which it has been based. Provisions of this article are intended to result in land development substantially consistent with the zoning standards generally applied to the proposed uses, allowing for modifications and departures from generally applicable standards in accordance with the guidelines of this article to insure appropriate, fair, and consistent decision-making.

Sec. 122-572. Permitted uses.

In a planned unit development, the principal uses which are permitted are based on the underlying zoning district. City Council may also consider, upon Planning Commission recommendation, the City of Ypsilanti Master Plan as a basis for principal uses permitted in a planned unit development.

Underlying Zoning District	Permitted Uses under Planned Unit Development
R1, CN-Mid, CN-SF, P	Planned unit developments, excepting adaptive reuse, are not permitted in these districts, except as provided for under 122-574.
CN, MD	Any combination of uses permitted in the CN and MD zoning districts. Limited commercial, service, and office uses must be permitted if in combination with and related to residential uses.
HHS, HC, NC, C	Any combination of uses permitted in the HHS, HC, NC or C zoning districts. Residential uses must be permitted only if in combination with such commercial or office uses.
GC	All commercial, service, and office uses or any combination of such uses must be permitted. Limited light industrial uses must be permitted if in combination with such commercial or office uses.
PMD	All industrial and office uses and any combination of such uses. Limited commercial and service uses must be permitted if in combination with industrial uses. Residential uses must not be permitted.

Sec. 122-573. Requirements for planned unit developments.

The following requirements must apply to all planned unit developments:

- (1) *Unified control.* The proposed development must be under single ownership or control such that there is a single person or entity having responsibility for completing the project in conformity with this chapter. The applicant must provide legal documentation of a single ownership or control in the form of agreements, contracts, covenants, and deed restrictions which indicate that the development can be completed as shown on the plans, and further, that all portions of the development that are not to be maintained or operated at public expense will continue to be operated and maintained by the developers or their successors.
- (2) *Minimum size.* The minimum size of a planned unit development must be 43,560 square feet (one acre) of contiguous land. The City Council may approve a planned unit development for a parcel as small as 21,780 square feet (one-half acre) if the proposal involves the preservation and/or adaptive reuse of a historically significant structure. The historical significance must be determined by the city historic district commission.
- (3) *Applicable base regulations.* Unless waived or modified in accordance with the procedures and standards set forth in this article, the yard, bulk, parking, loading, landscaping, lighting, general provisions, and all other standards set forth in this chapter for the uses listed below must be applicable for uses proposed as part of a planned unit development:
 - a. Multiple-family residential uses must comply with the regulations applicable in the MD multiple dwelling residential district.
 - b. Commercial and office uses must comply with the regulations applicable in the C - Center district.
 - c. Manufacturing uses must comply with the regulations applicable in the PMD - Production, Manufacturing, and Distribution district.
 - d. Mixed uses must comply with the regulations applicable for each individual use, as outlined above, except that if conflicts exist between provisions, the regulations applicable to the most dominant use must apply.
- e. To encourage flexibility and creativity in development consistent with the planned development concept, departures from compliance with the base regulations may be granted by the City Council, upon recommendation of the Planning Commission, as a part of the approval of the planned development. For example, such departures may include modifications of lot dimensional standards, setback requirements, density standards, parking and landscaping requirements, and similar requirements. Such departures may be approved only on the condition that they will result in a higher quality of development than would be possible using conventional zoning standards.
- (4) *Street access.* Each lot, main building, and principal use within a planned development district must have vehicular access to a public street. Adequate provision must be made for dedications of land for streets and essential services.
- (5) *Usable open space.* The proposed development must contain at least as much open space as would otherwise be required by the existing underlying zoning.
- (6) *Landscaping and maintenance of common areas.* All required yards and common areas must be landscaped and adequately and permanently maintained by the property owner, tenant, or organization responsible for maintaining common areas. Through an irrevocable conveyance, such as deed restrictions or covenants that run with the land, the developer must assure that all yards and common areas will be developed in accordance to the site plan and not changed to another use.
- (7) *Additional considerations.* During review of a proposed planned development, the Planning Commission must take into account the following considerations which may be relevant to a particular project: perimeter setbacks and screening; thoroughfares, drainage, as provided for in best management practices as appropriate, and utility design; underground installation of utilities; insulating pedestrian circulation from vehicular thoroughfares and ways; achievement of an integrated development with respect to signage, lighting, landscaping and building materials; and noise reduction mechanisms, particularly in cases where nonresidential uses adjoin off-site residentially-zoned property.

Sec. 122-574. Planned adaptive reuse projects.

A planned unit development that involves adaptive reuse of an existing structure that is located in a residential zoning district, but that was originally constructed for non-residential use, may be reviewed as a planned adaptive reuse project at the request of the applicant. The following requirements must apply to a planned adaptive reuse project in addition to the requirements applied to all planned unit developments:

- (1) *Eligibility.* The project must involve the reuse of an existing structure that is located in a residential zoning district, that was constructed for non-residential use.
- (2) *Minimum size.* Notwithstanding Sec. 122-573(2), no minimum size is required for a planned adaptive reuse project.
- (3) *Permitted uses.* Notwithstanding Sec. 122-572, a planned adaptive reuse project may include any uses determined by the City Council, upon Planning Commission recommendation, to be appropriate for the site and compatible with adjacent uses and zoning districts, with the master plan, and with any subarea plans.

Sec. 122-575. Application requirements.

An application for a planned unit development must contain the following:

- (1) Cover letter signed by the applicant and owner holding an equitable interest in the property.
- (2) Legal description showing the location and acreage of the property.
- (3) General description of proposed development, including a timetable of development and a list of departures from the regulations of this chapter which will be required.
- (4) Site plan at a scale of one inch equals 50 feet or larger, prepared in accordance with section 122-126. Additional information on the site plan must include:
 - a. A schedule of total land areas devoted to each type of use, useable floor areas, density calculations, number and types of units, and building ground coverage.
 - b. Open space areas, indicating the proposed uses and improvements for such areas.
 - c. Architectural sketches showing building heights, external wall finishes, location of building entry ways, lighting elements, and other architectural features.
 - d. Copy of agreements, covenants, or deed restrictions which will assure that the development will be completed and

maintained as shown on the plans by the developer and successive owners.

- e. Other information deemed pertinent to the proposed development by the Planning Commission or City Council.

- (5) A fee for the processing of the planned development application, as established by the City Council.

Sec. 122-576. Review procedures.

The review and approval process for planned unit developments must be as follows:

(1) Preapplication conference.

- a. In order to facilitate review of a planned unit development proposal in a timely manner, the applicant may request an informal preapplication conference with city staff. The purpose of such a conference is to exchange information and provide guidance to the applicant that will assist in preparation of application materials.
- b. The applicant must present at such a conference, at a minimum, a concept plan of the proposed planned unit development (drawn to scale), a legal description of the property in question, the total land areas of the project, the approximate number of residential units to be constructed, the floor area of nonresidential uses, and areas to be designated as common areas or open space.
- c. No formal action must be taken at a preapplication conference. There must be no fee for a preapplication conference. Statements made at the preapplication conference must not be legally binding commitments.

- (2) *Public hearing.* After a formal application has been filed for a planned unit development, it must be reviewed by the city planner and planning and development department for completeness and submitted to the Planning Commission. A public hearing on the proposed planned unit development must be scheduled. Notice of the public hearing must be published in a newspaper of general circulation in the city, and sent by mail or personal delivery to the owners of property for which approval is being considered, to all persons to whom real estate property is assessed within 300 feet of the boundary of the property in question, and to the occupants of all structures within 300 feet. Such notice must be given not less than 15 days before the public hearing scheduled. Such notification must contain the following information:

- a. Nature of the planned unit development project requested.
 - b. Boundaries of the property which is the subject of the request.
 - c. Date and time of the public hearing.
 - d. Location and times that written comments will be received concerning the request.
- (3) *Planning Commission recommendations.* Within a reasonable time not to exceed 90 days following the public hearing, the Planning Commission must make its final consideration of the request, and must recommend to the City Council denial, approval, or approval with conditions, of the request. The Planning Commission must have prepared a report stating its conclusions, the basis for its recommendations, and any conditions relating to an affirmative recommendation.
- (4) *City council action.*
- a. The City Council must be provided with a copy of the Planning Commission's report, a summary of comments received at the public hearing, minutes of all proceedings, and all documents related to the planned unit development. Within a reasonable time, not to exceed 60 days, after the action of the Planning Commission, the City Council must deny, approve, or approve with conditions, the request.
 - b. The City Council may require that a performance guarantee be deposited with the city to insure faithful completion of improvements, in accordance with section 122-134. Unapproved deviations or delays in construction may result in a loss of all or a portion of the performance guarantee.
 - c. The City Council may also impose other conditions to ensure that a planned unit development is constructed in an orderly manner, consistent with the spirit and intent of this chapter; and that the planned unit approach is not used as a means of circumventing restrictions on the location or quantity of certain types of land uses.
- (5) *Effect of approval.*
- a. Approval of a planned unit development proposal must constitute an amendment to this chapter. All improvements to and use of the site must be in conformity with the approved planned unit development site plan and any conditions imposed.
 - b. Within three business days of official approval of the application and site plan by

the City Council, the city clerk must attest the planned unit development designation for the land in question on the Zoning Map.

- c. Notice of the adoption of the planned unit development designation must be published in a newspaper of general circulation within the city within 15 days after approval in accordance with section 122-62.

- (6) *Recorded with register of deeds.* The applicant must record with the county register of deeds within ten days of approval of the application the following: a legal description of the project site, the approved site plan and an affidavit declaring that all future improvements will be made in accordance with the approved planned unit development.

Sec. 122-577. Standards for approval.

In considering any application for a planned unit development, the Planning Commission and City Council must make their determinations based on the standards for site plan approval in section 122-128 and the following standards:

- (1) *Conformance with the planned development concept.* The overall design and all uses proposed in connection with a planned unit development must be consistent with and promote the intent of this article, as well as with specific project design standards set forth in this chapter.
- (2) *Recognizable benefits.* The planned development will result in recognizable and substantial benefits to the ultimate users of the project and to the community in general where such benefits would otherwise be unfeasible or unlikely to be achieved.
- (3) *Compatibility with adjacent uses.* The proposed planned unit development must be designed with due regard to its relationship with development on surrounding properties and uses thereon, including building heights, setbacks, density, parking, circulation, landscaping, views, and other layout features. In particular, consideration must be given to the following:
 - a. The bulk, placement, architecture, and types of materials used in construction of proposed structures.
 - b. The location and screening of vehicular circulation and parking areas in relation to surrounding development.
 - c. The location and screening of outdoor storage, outdoor activity or work areas, and

- mechanical equipment in relation to surrounding development.
 - d. The hours of operation of the proposed uses.
 - e. Landscaping, preservation of historic features, and other site amenities.
- (4) *Impact of traffic.* The planned development must be designed to minimize any adverse impact of traffic generated by the proposed development. Consideration must be given to the following:
- a. Estimated traffic to be generated by the proposed development.
 - b. Access to major thoroughfares.
 - c. Proximity and relation to intersections.
 - d. Adequacy of driver sight distances.
 - e. Location of and access to off-street parking.
 - f. Required vehicular turning movements.
 - g. Provisions for pedestrian traffic.
 - h. Access to loading and unloading areas.
- (5) *Public services.* The proposed type and density of use must not result in a material increase in the need for public services, facilities, and utilities; including but not necessarily limited to water and sewer services, public roads, fire and police protection, and schools. The proposal must not place an undue burden upon the subject or surrounding land or property owners and occupants or the natural environment.
- (6) *Compatibility with master plan and this chapter.* The proposed development must be compatible with the adopted city master plan and with the spirit and intent of this chapter.
- (7) *Economic impact.* The proposed development must not result in an unreasonable negative economic impact upon surrounding properties.
- (8) *Compliance with applicable regulations.* The proposed development must be in compliance with all applicable federal, state, county, and local laws and regulations.
- (9) *Phasing.* Where a project is proposed for construction in phases, the project must be so designed that each phase, when completed, must be capable of standing on its own in terms of the presence of services, facilities, and open space; and must contain the necessary components to ensure protection of natural resources and the health, safety, and welfare of the users of the planned unit development and the occupants of the surrounding area.

Sec. 122-578. Expiration of approval.

- (a) Approval of the planned unit development must expire and be of no effect unless construction must have commenced within one year of the date of the approval. An extension for a specified period may be granted by the City Council upon good cause shown, if such request is made to the City Council prior to the expiration period.
- (b) In the event an approved planned unit development has expired, the City Council may rezone the property in any reasonable manner following Planning Commission recommendation and a public hearing in accordance with Article III of this chapter. If, at the discretion of the City Council, the property remains classified as a planned unit development, a new application must be required and must be reviewed in light of the prevailing conditions, applicable laws, and ordinance provisions.

Sec. 122-579. Revision of approved plans.

- (a) *General revisions.* Approved final plans for a planned unit development may be revised in accordance with the procedures set forth in section 122-576. Major revisions would include, but must not be limited to, increases in scope or density of use, land area, or building size; the addition of uses not authorized by the original planned unit development approval; the rearrangement of lots or building tracts; changes in the character or function of drives; or changes in the concept of the development.
- (b) *Minor changes.* Notwithstanding subsection (a) of this section, minor changes may be permitted by the Planning Commission following normal site plan review procedures outlined in Article IV of this chapter, subject to its finding of the following:
 - (1) Such changes will not adversely affect the initial basis for granting approval; and
 - (2) Such minor changes will comply with all applicable requirements of this chapter and other local, state, and federal laws; and will not adversely affect the overall planned unit development in light of the intent and purpose of such development as set forth in this article.

Sec. 122-580. Appeals and variances.

The zoning board of appeals is without jurisdiction to accept appeals or grant variances with respect to an approved planned unit development.

Secs. 122-581--122-600. Reserved.

ARTICLE X. SITE CONDOMINIUM SUBDIVISIONS*

*State law reference(s)--Condominium act, MCL 559.101 et seq., MSA 26.50(101) et seq.

Sec. 122-601. Purpose and scope.

Site condominium subdivisions are developments utilizing the technique of land division on the basis of condominium ownership. As such, site condominium subdivisions are not subject to the provisions of the land division act, Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101 et seq.), MSA 26.430(101) et seq., as amended. This section requires the submittal and review of site condominium subdivision plans under this chapter to ensure that such developments are accomplished with the same results as if the improvements were being proposed pursuant to the land division act, including, without limitation, conformance with all requirements of the applicable regulations contained in this chapter. Site condominium subdivision projects may be approved in any zoning district as a special use under the provisions of Article IV of this chapter, or where divergence from the use, height, area, and placement regulations of this chapter is desired, the provisions of Article IX of this chapter.

Sec. 122-602. Definitions.

The following terms are defined both in the context of the condominium act and in a manner intended to make comparison possible between the terms of this chapter and other current or future land subdivision and utility extension regulations adopted by the city.

Condominium act means Act No. 59 of the Public Acts of Michigan of 1978 (MCL 559.101 et seq., MSA 26.50(101) et seq.), as amended.

Condominium structure or *building envelope* means the principle building or structure intended for or constructed upon a lot or building site, together with any attached accessory structures. For example, in a residential development, the condominium structure or building envelope would refer to the house and any attached garage.

Condominium unit means that portion of the condominium project designed and intended for separate ownership and use, as described in the master deed, regardless of whether it is intended for residential, office, industrial, business, or recreational use as a time-share unit, or any other type of use.

Lot means the same as building site and is that portion of the condominium project designed and intended for separate ownership and/or exclusive use, as described in the master deed. Lot must be further defined as:

- (1) A condominium unit consisting of the area under a building envelope and the contiguous

area around the building envelope which, by itself, meets the minimum area and yard requirements for lots within each zoning district.

- (2) The contiguous limited common element under and surrounding a condominium unit that is or must be assigned to the owner of the condominium unit, for the owner exclusive use, and which, together with the condominium unit, meets the minimum area and yard requirements for lots within each zoning district.

Master deed means the legal document prepared and recorded pursuant to Act No. 59 of the Public Acts of Michigan of 1978 (MCL 559.101 et seq., MSA 26.50(101) et seq.), as amended, to which is attached as exhibits and incorporated by reference the approved bylaws for the project and the approved condominium subdivision plan for the project.

Mobile home condominium project means a condominium project in which mobile homes are intended to be located upon separate sites which constitute individual condominium units.

Setback, front, side and rear yard means the distance measured from the respective front, side, and rear yard area lines associated with the lot to the respective front, side, and rear of the condominium structure/building envelope.

Sec. 122-603. Zoning compliance.

All site condominium subdivisions and structures therein must comply with all the use, size, height, area, setback, sign, and all other regulations of the zoning district in which the subdivision is located unless modified through the provisions of Article IX of this chapter regarding planned unit developments.

Sec. 122-604. Review and approval procedures.

Application for review and approval of site condominium subdivision projects must be made pursuant to the provisions of Article V or Article IX of this chapter.

Sec. 122-605. Effect of approval.

Approval of a site condominium subdivision project must serve as authorization to proceed with the division of the land on the basis of condominium ownership and the construction of required improvements to the land. However, unless specifically addressed and authorized, site condominium subdivision approval must not serve as the authorization of land uses on individual lots within

the subdivision. All uses must be subject to the provisions of this chapter otherwise applicable to the specific zoning district and use in question.

Sec. 122-606. Site plans.

The site plan submitted for a site condominium subdivision must be consistent with the requirements outlined in section 122-126 showing the location, size, shape, area, and width of all lots, all general and limited common elements, and street and utility layout. In addition, the following must be included as part of the application for special land use approval:

- (1) The use and occupancy restrictions as will be contained in the master deed.
- (2) A "consent to submission of real property to condominium project" listing all parties which have ownership interest in the proposed site condominium subdivision, or evidence of authority or right that the developer has a legal option to purchase the subject property from the owner of record.

Sec. 122-607. Layout, design and required improvements.

Site condominium subdivision plans must conform to the design, layout, and improvement standards as may be promulgated by the City Council by ordinance. Any such standards and regulations are hereby incorporated by reference in this article.

- (1) *Streets.* If a site condominium subdivision is proposed to have public streets, the streets must be paved and developed to the minimum design, construction, inspection, approval, and maintenance requirements for public streets as adopted by the city.
- (2) *Utilities.* Extension and provision of utilities must be provided as may be required by the city as conditions of approval.
- (3) *Drainage.* Procedures and design criteria for drainage must be as provided in the rules of the county drain commissioner, pursuant to section 105(c) of Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101(c), MSA 26.430(101), (c)), as amended.

Sec. 122-608. Master deed contents.

All provisions of the site condominium plans which are approved by the city pursuant to this article must be incorporated, as approved, in the master deed for the site condominium subdivision. Any proposed changes to the approved site condominium plans must be received and approved by the city pursuant to the procedure set forth in section 122-604 for the approval of site condominium plans. A copy of the master deed as filed with the county register of deeds for recording must be provided to the city clerk within ten days after such filing with the county.

Secs. 122-609--122-630. Reserved.

ARTICLE XI. SUPPLEMENTARY DISTRICT REGULATIONS

DIVISION 1. GENERALLY

Sec. 122-631. Scope.

The provisions of this chapter must apply to all lots and parcels of land and to every building, structure, or use, and extends vertically. No lot, building, structure, or part thereof, must hereafter be located, erected, altered, occupied, or used except in conformity with the provisions of this chapter. The general provisions of this article must apply unless specifically stated otherwise.

Sec. 122-632. Control of heat, glare, fumes, dust, noise, etc.

Every use must be so conducted and operated that it is not obnoxious or dangerous by reason of heat, glare, fumes, dust, noise, radiation, vibration, or odors beyond the lot on which the use is located. Furthermore, it shall be unlawful for any person to create, assist in creating, permit, continue, or permit the continuance of any public nuisance as defined and regulated under Article II of chapter 42.

Sec. 122-633. Damaged or destroyed buildings.

- (a) The owner of any building or structure which has been damaged or destroyed by fire, windstorm, or other casualty must repair such damage within six months after its occurrence. However, nonconforming buildings and structures must only be repaired when in conformance with the subsection 122-206(c)(4).
- (b) In the event the building or structure is damaged beyond repair, or repairs are not permitted by the terms of this chapter, then any part left standing after such damage or destruction must be demolished within six months of its occurrence pursuant to a permit granted by the city building department.

Sec. 122-634. Dumping on land prohibited.

The use of land for the dumping or disposal of scrap metal, junk, junk cars, parts of automobiles, trucks, and boats, tires, garbage, rubbish, or other refuse or of ashes, slag or other wastes or by-products, must not be permitted in any zoning district.

Cross reference(s)--Solid waste, ch. 86.

Sec. 122-635. Dwelling on rear of lot.

- (a) No building on the same lot and in the rear of a principal building must be used as a dwelling, nor must any building be located in front of a building used as a dwelling on the same lot, except as provided by this chapter or within an approved planned unit development.
- (b) The only exceptions to this requirement are dormitories, rectories, convents, or similar living quarters operated and maintained in connection with a religious institution, school, hospital, or similar institution.

Sec. 122-636. Rights of Way and Easements.

- (a) *Construction of Permanent Structure Over Right of Way or Easement Unlawful.* It is unlawful for any person to install, erect, cause or permit the installation of a permanent structure (such as a garage, building, swimming pool, fence, or tree) on or across an easement of record which will prevent or interfere with the free right or opportunity to use or make accessible such easement for its proper use.
- (b) *Building Entrance must face Street.* No principal building can be placed on a lot unless the building is situated in such a manner that the front entry into the building faces the street to which the property is addressed.
- (c) *Planned Easements.* All site plans must show planned easements for non-motorized pathways in the City of Ypsilanti's Non-Motorized Plan, a 50 to 100 foot conservation and /or access easement along any Huron River frontage, the ReImagine Washtenaw Corridor Improvement Study and any planned road easement expansions approved by City Council. A proposed expansion of a structure or new building where the building or structure encroaches from the required setback from a planned easement for a street must be approved by the Planning Commission.

Sec. 122-637. Essential services.

- (a) *General provisions.* Essential services which are located underground or involve the customary placing of utility poles in public rights-of-way or public easements or the placing of utility boxes in the rear of private properties, and which are reasonably necessary for the furnishing of adequate services for the public health, safety, or welfare must be permitted as authorized and regulated by law and other ordinances of the city in any zoning district.
- (b) *Public utility buildings.* The Planning Commission may authorize the erection, maintenance, and use of a building, or an alteration or addition to an existing building by a public utility as a special use and after site plan review in any zoning district, including a building with a height greater than otherwise permitted in the zoning district; provided that the Planning Commission finds that such building is necessary at a selected location, will not be injurious to the surrounding neighborhood, and is not contrary to the spirit or purpose of this chapter. Where possible, such buildings must be located in a commercially or industrially zoned district rather than in residential districts.

Sec. 122-638. Depositing or burying garbage; excavation or filling.

- (a) The deposit or burying of garbage anywhere in the city is expressly prohibited.
- (b) The removal or filling of topsoil, sand, gravel or other material from or on the land is not permitted in any zoning district unless a site plan for such excavation or filling has first been approved by the Planning Commission and a permit is issued by the building department. Before approving such plan, the Planning Commission must determine that such removal will not cause standing water to collect or, at the expiration date of such permit, leave the surface of the land in an unsuitable condition or unfit for other land uses permitted in the district in which the removal or filling occurs; and that such fill or removal will not cause water or other materials to encroach on any public street, sidewalk, or adjacent property not owned by the applicant. When appropriate, the city may require that such fill or excavation areas are protected with fencing, rail guards, and warning signs.
- (c) This section must not apply to the normal removal or filling of soil for the construction of an approved building or structure when such plans have received site plan approval and a permit for such construction has been issued by the building department.

- (d) This section is also not intended to regulate common household gardening or general ground care.

Cross reference(s)--Solid waste, ch. 86.

Sec. 122-639. Grades; elevation differentials.

The grading of all building lots must be such as to divert water away from buildings and to prevent standing water and soil saturation detrimental to structures, lot use, and surrounding property.

Sec. 122-640. Steep slopes protection.

This section is intended to protect resources in environmentally sensitive areas to ensure that development does not result in erosion and in flooding during site preparation and the development process. All uses and activities established after the effective date of this Ordinance must comply with the following standards. Site alterations, re-grading, filling or the clearing of vegetation, or any other activity deemed detrimental to any environmentally sensitive area or resource prior to the submission of plans for subdivision or land development are a violation of this Ordinance.

- (a) *General Design Standards.* Structures must be designed in a manner that requires a minimum amount of alternation to the steep slope and that otherwise complies with the grading standards in item b of this section. Except where a geologic hazard investigation report recommends otherwise, multi-level building design and/or terracing must be used. Otherwise, structures must be sited on existing level areas of the site. Particular caution must be taken to prevent increases in the rate of stormwater runoff and erosion downslope of any steep slope development site.
- (b) *Specific Design Standards.* The following specific design standards must be met on sites with steep slopes:
 - 1. Any site disturbance of slopes exceeding twelve (12%) percent must be minimized.
 - 2. No site disturbance must be allowed on slopes exceeding fifteen (15%) percent, except under the following circumstances.
 - a. Grading for a portion of a driveway accessing a single family dwelling when it can be demonstrated that no other routing which avoids slopes exceeding fifteen (15%) percent is possible.
 - b. Upon submission of a report by a certified soil or geotechnical engineer indicating that the steep slope may be safely developed and execution of a provision agreeing to hold the City of Ypsilanti harmless from

any claims of damages due to approval of such development. If development is allowed to proceed under this subsection, no more than (15%) percent of such areas must be developed and/or re-graded or stripped of vegetation.

3. Finished slopes of all cuts and fills must not exceed three-to-one (3:1), unless the applicant can demonstrate that steeper slopes can be stabilized and maintained adequately.

Sec. 122-641. Outdoor lighting.

- (a) All outdoor lighting must be so designed and arranged so as not to shine on adjacent properties or occupied dwellings, or adversely impact vehicular or pedestrian traffic on nearby streets, drives, walkways, or general rights-of-way. Outdoor lighting originating on a site must not exceed one-half (0.5) footcandle at the lot line. Proposed light fixtures must be Dark Sky compliant. Lights may be required to be full cutoff where they may impact residential uses.
- (b) Outdoor lighting fixtures must not exceed 30 feet in height or the height of the principal building on the site, whichever is less. For development sites abutting lots used or zoned for one and two-family residential uses, lights must not exceed a height of 16 ft. The Planning Commission may modify the height restrictions in commercial and industrial districts, based on consideration of the following: the position and height of buildings, the character of the proposed use; and the character of surrounding land uses.
- (c) Where outdoor lighting is required by this chapter, the light intensity provided at ground level must be a minimum of one-third (0.3) footcandle anywhere in the area to be illuminated. Light intensity must average a minimum of one-half (0.5) footcandle over the entire area, measured five feet above the surface.

Cross reference(s)--Traffic and vehicles, ch. 102.

Sec. 122-642. Direct access to major thoroughfare.

Whenever this chapter requires that direct access to a major thoroughfare be provided, one of the following provisions must be met:

- (1) Direct driveway ingress and egress is provided from the site directly to a major thoroughfare.
- (2) Access to the site from a major thoroughfare does not traverse through or abut any land zoned R1, MD, CN-SF, CN-Mid, and CN.

Sec. 122-643. Moving of buildings or structures.

The moving of a building or structure to a different location must be considered as the erection of a new building and all provisions, regulations, and requirements relative to the erection of a new building must be applicable thereto. A performance guarantee may be required prior to such moving as provided in section 122-134.

Sec. 122-644. Porches, decks, balconies, fire escapes, and barrier-free access ramps.

(a) *Porches, decks, terraces and balconies.*

- (1) An open or unenclosed porch or terrace may project into a front yard for not more than ten feet, unless otherwise regulated within this chapter.
- (2) Open, unenclosed or uncovered porches, decks, terraces, and walkways over nine inches in height must meet all side and rear yard setback requirements.
- (3) Unenclosed balconies may project into a front yard for not more than ten feet, but must meet all side and rear yard requirements.
- (4) All enclosed porches, decks or balconies are an integral part of a building and must meet all yard setback requirements of that structure.

- (b) *Fire escapes.* No fire escape can be located within any front yard. All fire escapes must meet all side and rear yard setback requirements.

- (c) *Barrier-free access ramps.* Barrier-free access ramps may be located within any front, side or rear yard, provided that no portion of the ramp which exceeds over 36 inches in height is located within any required minimum yard setback area. This provision may be waived by the building department for a temporary barrier-free access ramp to a single-or two-family dwelling, provided that the building department finds that such proposed barrier-free ramp will not pose a fire or safety hazard, and will not obstruct traffic vision. A temporary barrier-free access ramp must be removed within 14 days after the person needing the ramp ceases to occupy a dwelling.

- (d) *Architectural features.* Window sills, cornices, eaves, bay windows, and other architectural features may project into a required side yard not more than two inches for each one foot of width of such side yard; and may extend into any front or rear yard not more than three feet.

Sec. 122-645. Public service access.

All buildings and structures must be provided with adequate access for fire, police, sanitation and public works vehicles. The Planning Commission may require paved turnaround areas to allow adequate maneuverability for public service vehicles on a site.

Sec. 122-646. Retaining walls.

Retaining walls in excess of one foot in height require a building permit. All retaining walls must be designed and built so as to safely resist lateral pressures of soil behind them and be safely supported by soil beneath them. Additionally, retaining walls must be maintained in structurally sound and safe repair and must not impair drainage or create negative impacts on any other lot.

Sec. 122-647. Sidewalks.

- (a) For all development projects, either a new public sidewalk or if necessary the reconstruction of existing sidewalks, must be provided along the perimeter of the lot which abuts any street. New or reconstructed sidewalks must be aligned with existing or proposed sidewalks and must be constructed to city standards and subject to Chapter 94 of the City Code of Ordinances.
- (b) This requirement may be modified by the Planning Commission as follows:
 - (1) A shared-use path may be provided in lieu of a sidewalk, upon a finding that any portion of the perimeter of a lot is planned to be part of an area-wide non-motorized network that requires such a facility.
 - (2) A fee in lieu of construction may be provided by the development in the amount of 100% of the construction cost, upon a finding that any portion of the perimeter of a lot is included in a transportation project programmed in the City's 5-year Capital Improvement Plan. Any fee paid for this purpose must be

reserved for non-motorized improvements as a part of the identified transportation project.

- (3) Any easement required for the construction, maintenance, or operation of a modified facility must be included on the site plan at the time the modification is requested.



Sec. 122-648. Street frontage requirements.

No lot can contain any building used in whole or in part for any purpose unless such lot abuts the minimum lot width of the building type or zoning district on at least one street; or unless it has an exclusive, unobstructed private easement of access or right-of-way of at least 50 feet wide to a street. There must not be more than one single-family dwelling or one nonresidential land use for such frontage or easement.

Sec. 122-649. Traffic visibility.

- (a) No structure, wall, fence, vehicle, shrubbery, or trees can be erected, parked, planted or maintained on any lot which will obstruct the view of the driver of a vehicle approaching an intersection or maneuvering from a driveway. Provided, shrubbery and low fences or walls not exceeding 30 inches in height above the curb level and branches of trees not less than eight (8) feet above the street level will be permitted.
- (b) This means, in the case of an intersection, that there must be provided an unobstructed triangular area formed by the street property lines and a line connecting them at points 25 feet from the intersection of the pavement edge lines, or in the case of a rounded corner, from the intersection of the street property lines extended. In the case of a driveway, there must be provided an unobstructed triangular area formed by the street right-of-way line, the edge of the driveway, and a line connecting them at points ten (10) feet from the intersection of the street right-of-way line and driveway edge. (Refer to the traffic visibility illustration on the next page.)

General Provisions



TRAFFIC VISIBILITY

Sec. 122-650. Trash receptacles and dumpsters.

Any new or altered commercial use, including residential uses with three or more units, which requires zoning compliance review or site plan review under Article IV of this chapter and has an outdoor trash storage area must comply with the following requirements:

- (1) No outdoor trash storage area may be located in any front yard or any required side yard setback which is adjacent to a street, unless there is no alternative as established by the city planner or the Planning Commission. In no instance may any trash receptacle or dumpster be located within or block a designated parking space.
- (2) Any outdoor trash storage area must be limited to normal refuse which is collected on a regular basis and must be maintained in a neat, orderly and sanitary condition. This maintenance is the responsibility of the owner of the premises on which the containers are placed.
- (3) Adequate vehicular access must be provided to such containers for truck pickup either via a public alley or vehicular access aisle which does not conflict with the use of off-street parking spaces or entrances to or exits from principal buildings nearby.
- (4) All trash storage areas must be located in a rear yard or be so located and arranged so as to minimize its visibility from adjacent streets and uses, on a concrete pad, and must be screened with an enclosure at least one (1) foot taller than the dumpster. The enclosure must be of a solid brick or masonry wall on three sides with an 80% opacity swing door on the fourth side.
- (5) At the discretion of Planning Commission, landscaping may be required around the perimeter of a refuse container in order to soften its appearance from adjacent residential uses.

Cross reference(s)--Solid waste, ch. 86.

Sec. 122-651. Unclassified uses.

Uses which have not been specifically mentioned within any district may be processed under the special use permit procedure, in accordance with Article V of this chapter. The Planning Commission must approve such special use permit only after it determines that it will have no adverse effect upon adjacent property, that the use is similar to other uses in the district in which it is proposed to be placed, and the spirit and intent of this chapter and master plan are not impaired by permitting such use at the proposed location.

Sec. 122-652. Voting place.

The provisions of this chapter must not be so construed as to interfere with the temporary use of any property as a voting place in connection with a public election. A temporary use permit must not be required for such voting place.

Secs. 122-653--122-665. Reserved.

DIVISION 2.

ACCESSORY STRUCTURES AND USES

Sec. 122-666. Purpose and intent.

The intent of this division is to regulate accessory structures and uses in order to preserve adequate open spaces and separation between uses which may impact adjacent properties. Accessory uses and structures are generally permitted uses in their respective zoning districts, subject to the provisions of the this division.

Sec. 122-667. General standards for accessory structures.

- (1) *Attached Accessory Structures.* Where an accessory structure is attached to and made a part of the principal building (excluding breezeways or canopies), such accessory structure must comply in all respects with the requirements of this chapter applicable to the principal building.
- (2) *Detached Accessory Structures.* The following standards, unless otherwise stated in this chapter, govern all detached accessory structures. A "detached accessory structure" is one which is not attached to the principal structure; however, a breezeway or other enclosed or roofed over connecting way may connect the principal structure to an accessory structure provided that such breezeway or connecting way does not exceed eight feet in width and does not exceed the height of the accessory structure. Detached accessory structures include, but are not limited to, garages, sheds, toolhouses, swimming pools, tennis or basketball courts or other recreational equipment.
 - a. *Building permit.* No accessory structure may be erected, moved, altered, or razed until a building permit has been obtained from the building department.
 - b. *Height.* The maximum height for a detached accessory structure must be 15 feet; except in the PMD district, in which accessory structures may be constructed equal to the permitted maximum height of structures in such district, subject to Planning Commission review and approval.
 - c. *Location.* All detached accessory structures must be located in rear yards or side yards. On corner lots, detached accessory structures must not be located in the required street side yard setback. In no instance may an accessory structure be located within a dedicated easement.
 - d. *Setback and ground coverage requirements.* All detached accessory structures must meet the setback and ground coverage regulations for the underlying zoning district and, if applicable, building type.
 - e. *Architecture/siding.* The architectural character of all accessory buildings must be compatible with that of the principal building. All accessory buildings in all zones except the PMD district, must be sided and roofed with materials which are compatible with the principal building and adjacent principal buildings.
 - f. *Sleeping quarters.* The use of any accessory building for the overnight housing of persons is prohibited, unless expressly permitted by this chapter or this Code.
 - g. *Mobile homes.* Mobile homes are not permitted as an accessory use to a permitted principal use.
 - h. *Subdivision of lots.* No parcel or lot may be subdivided unless and until all detached accessory buildings comply with this chapter with respect to allowable size and setback requirements for the proposed lot on which the buildings are to be located.

Sec. 122-668. Swimming pools.

Prior to the issuance of a building permit for the construction of an outdoor swimming pool in any zoning district, the following provisions must be satisfied:

- (1) An application for a building permit must be accompanied by a complete and detailed set of plans and specifications for the swimming pool, including type of construction, size, location on lot in relation to lot lines and buildings on the site, fencing, and related equipment, which show that the following minimum standards will be met.
- (2) The swimming pool must be located no closer than ten feet to any side or rear lot line, and no part of any pool may be constructed within a front yard or required side yard setback adjacent to a street.
- (3) Swimming pools must be located a minimum of four feet from any building on the same parcel and a minimum of 25 feet from any dwelling on an adjoining lot which is located within an R1, MD, CN-SF, CN-Mid or CN district.

- (4) All pool associated wiring and wiring in, around, over or under the pool must comply with the latest edition of the National Electrical Code as adopted by this Code.
- (5) All swimming pools must be enclosed by a fence of a type not readily climbed by children which must be at least five feet in height from the ground level. However, if the entire yard of the residence is enclosed, then this provision may be waived by the building department upon inspection and approval of the yard's enclosure; or if the pool is of a portable or above ground type, with a wall height of at least five feet above the surrounding ground surface, and of such construction as not to be readily climbed by children, then the ends of the fence may be attached to the pool structure and the fence need be erected only around the immediate area of the ladder and other means of access to the pool. Gates must be of self-closing latch type with the latch on the inside of the gate, not readily available for children to open. Gates must be securely locked when the pool is not in use. Pools must be enclosed by such fence before water is placed in pool. All fences must be subject to the requirements of Article XI, division 4 of this chapter.
- (6) Water retained in any pool regardless of depth must be maintained clean and sanitary as provided in the BOCA National Building Code, water treatment standards.
- (7) The building department has the right at any reasonable hour to inspect any swimming pool for the purpose of determining that all the provisions of this chapter are fulfilled and complied with. Any outdoor swimming pool installed, operated or maintained in violation of the provision of this section constitutes a nuisance, and the city may, in addition to the penalties set forth in section 122-8, maintain any proper action for the abatement of such nuisance.

Sec. 122-669. Home occupations.

- (a) *Prohibited home occupations.* The following are not permitted as home occupations: animal grooming establishments, barber shops or beauty parlors with more than one stylist or chair, clinics or hospitals, commercial stables, day care centers, kennels, real estate offices, restaurants, vehicle repair or painting, retail or wholesale sales of any items stocked on the premises, landscape installation and maintenance businesses, construction contractors, snow removal, funeral homes, nursing homes, antique shops, bed and breakfast establishments, private clubs, or trailer rentals, adult regulated uses, millinery and other apparel shops, veterinarian's office, clinic or hospital. However, this section is not intended to prohibit offices related to the administration of construction contracting, landscaping, maintenance, or snow removal businesses.
- (b) *Permitted home occupations.* Any home occupation that is not specifically prohibited by subsection (a) of this section must be permitted if it meets the following standards:
 - (1) All home occupations must obtain a business license from the City Assessor; if the occupant is not the owner of the premises then consent must be obtained from the property owner to ensure the owner's knowledge of the use.
 - (2) The home occupation must not change the outside appearance of the dwelling nor alter the residential character of the structure.
 - (3) The home occupation must not be visible from the street.
 - (4) The home occupation must be owned and operated only by a member or members of the immediate family residing on the premises.
 - (5) No more than one other person may be employed or involved with such activity on premises other than a member of the immediate family residing in the dwelling unit.
 - (6) All wholesale, jobbing or retail business must be conducted entirely by mail, telephone, electronically or by delivery.
 - (7) Services and transactions must be conducted by appointment only, walk-in trade is prohibited.
 - (8) The maximum area for home occupations must be calculated as 25 percent of the usable residential floor area of a dwelling unit or 300 feet whichever is less. Areas designated for home occupations may be located in any useable area of the home, the basement, or any accessory building.
 - (9) No motor power other than electrically operated motors may be utilized. No single electrical motor used in the home occupation may exceed one horsepower. All electrical motors and equipment used in the conduct of the home occupation must be shielded so as not to cause radio or television interference for adjoining properties.

- (10) A home occupation must not create noise, dust, vibration, smell, smoke, glare, electrical interference, fire hazards, or any other hazard or nuisance to any greater or more frequent extent than would normally be generated in the zoning district in which it is located.
 - (11) Signage must be limited to a nameplate which must not exceed one square foot in area.
 - (12) In no case may a home occupation be open to the public earlier than 7:00 a.m. nor later than 9:00 p.m.
 - (13) There must be no deliveries to or from the home occupation with a vehicle having more than two axles.
 - (14) No merchandise or articles for sale may be displayed on the lot used for the home occupation.
 - (15) The home occupation may increase vehicular traffic flow and parking by no more than two additional vehicles at a time.
- (c) **Medical Marijuana Home Occupation.** In addition to the requirements in Section 122-669(b), Medical marijuana home occupations must be subject to the following requirements:
- (1) The medical use of marijuana must comply at all times and in all circumstances with the Michigan Medical Marihuana Act and the General Rules of the Michigan Department of Community Health, as they may be amended from time to time.
 - (2) A registered primary caregiver operating a medical marijuana home occupation must not be located within 1,000 feet of a school, as measured from the outermost boundaries of the lot or parcel on which the home occupation and school is located.
 - (3) Not more than one (1) primary caregiver per parcel may be permitted to grow or cultivate medical marijuana.
 - (4) Not more than five (5) qualifying patients may be assisted with the medical use of marijuana within any given calendar week.
 - (5) All medical marijuana must be contained within an enclosed, locked facility inside a primary or accessory building.
 - (6) All necessary building, electrical, plumbing and mechanical permits must be obtained for any portion of the building in which electrical wiring, lighting and/or watering devices that support the cultivation, growing or harvesting of marijuana are located.
 - (7) If a room with windows is utilized as a growing location, any lighting methods that exceed usual residential periods between the hours of 11pm and 7am must employ shielding methods, without alteration to the exterior of the residence, to prevent ambient light spillage that may create a distraction for adjacent residential properties.
 - (8) That portion of the building where energy usage and heat exceeds typical residential use, such as grow room, and the storage of any chemicals such as herbicides, pesticides, and fertilizers must be subject to inspection and approval by the Ypsilanti Fire Department to insure compliance with the Michigan Fire Protection Code.
 - (9) The premises must be open for inspection upon request by the Building Official, the Fire Department and law enforcement officials for compliance with all applicable laws and rules, during the stated hours of operation/use and as such other times as anyone is present on the premises.

Cross reference(s)--Businesses, ch. 22.

Sec. 122-670. Garage sales, rummage sales, and owner-made craft sales.

- (a) *Duration.* Each occasion may not take place for a period of time longer than 12 hours per day for a maximum of three consecutive days.
- (b) *Number.* There must be no more than three occasions per year on any premises.
- (c) *Hours.* All articles or property that are offered for sale must be totally enclosed within a lawful structure or building between the hours of dusk to dawn.
- (d) *Removal of signs.* All signs that may have been used to advertise the sale must be removed upon completion of the sale.

Secs. 122-671--122-680. Reserved.

DIVISION 3. COMMUNICATION DEVICES*

*Cross reference(s)--Telecommunications, ch. 98.

Sec. 122-681. Intent.

It is the intent of this division to provide reasonable regulations for the mounting of private communication antennas. The objectives of this division are to promote safety and prevent injury to persons and property, to maintain and promote the aesthetic and architectural quality of properties, to preserve property values, to balance the city's authority and duty to regulate the placement of communication devices in relation to the right to construct and use communication devices without reasonable restrictions, and to conditionally exclude from regulation by this division certain VHF and UHF television antennas meeting the criteria of subsection 122-683(1).

Sec. 122-682. General standards.

- (a) *Permits.* All applicants proposing to erect any communication device in any zoning district, except as excluded under subsection 122-683(1), must be required to obtain a building permit and make payment of required fees.
- (b) *Plot plan and mounting detail.* Prior to issuance of a building permit for the erection of a communication device in any zoning district, the applicant must submit a plot plan showing to scale the precise proposed location of the communication device; its relative location to buildings on the site, adjoining properties, roads, landscaping, and natural features; the height and design of the structure; and foundation and/or mounting detail as appropriate for the building department to determine safety and building code compliance.
- (c) *Standards.* All communication devices must be installed, maintained, and grounded according to the standards as stated in the building code and must also meet wind and ice loads as specified in the building code.
- (d) *Restrictions.* All communication devices must be subject to the following restrictions:
 - (1) *Protrusion.* Communication devices must not protrude or overhang in any way over any public right-of-way or adjoining property.
 - (2) *Location.* Communication devices must not be located in front yards or in the street side yard of corner lots.
 - (3) *Advertising, symbols, lighting.* No portion of any communication device may display any advertising message or other graphic representation other than a manufacturer's logo or nameplate or warning signs; provided such logo or letters are of a size and character that is not legible from adjacent properties. Except as required by the Federal Communications Commission, no communication device may be illuminated by direct or indirect lighting.
 - (4) *Color and texture.* All communication devices must be of a color and texture so as not to be conspicuous and to promote its visual blending into the adjacent background.
 - (5) *Wood construction prohibited.* Communications devices must not be constructed of wood.
 - (6) *Ground mounted devices.* All communication devices not mounted on a principal or accessory building must be permanently anchored to a foundation located on the ground. No ground mounted device may be located closer to a property line than its height as measured from the ground elevation at the base of the antenna structure.
 - (7) *Roof mounted devices.* All communication devices mounted on the roof of a building must be located on that portion of the building located adjacent to the rear of the property, unless it can be demonstrated that an alternative location is as safe or safer, and the visibility of the antenna from the adjacent properties and by pedestrian or vehicular passers-by is reduced or equal in comparison to a rear yard orientation/location.

Sec. 122-683. Antenna systems.

In addition to the foregoing general standards of this division, the following standards must apply to antenna systems:

- (1) Conventional VHF and/or UHF television antennas which have width and height dimensions of not more than 135 inches and ten feet respectively, which are situated on the portion of the roof adjacent to the rear yard on the property, and which do not extend higher than ten feet above the ridge and/or peak of the roof, must be exempt from the requirements of applying for and receiving approval under this division. Exemption of such VHF and UHF television antennas from this division is based upon the following findings: there is relatively small concern for wind and snow load issues, there has been a long demonstrated safety record, there has

been an historical acceptance of such facilities from an architectural and aesthetic standpoint, and the cost of compliance with the procedure for application and review would be great in relation to the cost of purchasing and installing such antennas.

- (2) Antenna systems which do not meet the criteria and condition of subsection (1) of this section must be regulated as follows:
 - a. The antenna system must be located in a fenced or walled enclosure, so as to deter any person from climbing the tower, except for service or repair.
 - b. The antenna system must be of a self-supporting design.
 - c. Proof of liability insurance in the amount of \$100,000.00 must be submitted indicating protection of all adjacent property owners within a radius equal to 1½ times the height of the tower. This must include any city-owned property or right-of-way.
 - d. The antenna system must be used only for legal, amateur or commercial receiving and transmitting, as licensed by the Federal Communications Commission.

Sec. 122-684. Satellite dish stations.

In addition to the general standards of section 122-682, the following must apply to all satellite dish antennas:

- (1) Permit applications must contain the following additional information:
 - a. In the case of a satellite dish proposed to be mounted on a roof in a commercial or manufacturing district, a detailed plan showing the exact location of the antenna on the roof.
 - b. A picture, sketch, or catalog cut of the proposed installation, including the proposed coloration of the satellite dish.
 - c. Proof of liability insurance in a minimum amount of \$100,000.00.
 - d. Such other pertinent information as may be required by the building department.
- (2) No more than one satellite dish installation may be permitted on any single lot of record.
- (3) The satellite dish and all structural supports must be of noncombustible and corrosive resistant material.
- (4) Each satellite dish installation must be designed to withstand a wind force of 75 miles per hour without the use of any supporting guide wires.
- (5) Any driving motor must be limited to 100-volt maximum power design and be encased in protective guards. Any motor with operating voltage of more than 50-volt A.C. nominal must comply with Article 430 of the National Electrical Code.
- (6) A satellite dish antenna must be permanently mounted. A satellite dish antenna may only be on wheels or temporarily installed when used to demonstrate and/or test the feasibility of use.

Sec. 122-685. Communication devices in residential districts.

In addition to the foregoing provisions, the following requirements apply to all communication devices in the R1, MD, CN, CN-Mid, CN-SF and HHS zoning districts:

- (1) *Antenna systems.*
 - a. *Ground mounted restrictions.* Ground mounted antenna systems must not exceed a height of 75 feet, or a height equal to the distance from the base of the antenna system to the nearest property line whichever is less. There must be no more than one ground mounted antenna system on a single zoning lot.
 - b. *Roof mounted height restrictions.* Roof mounted antenna systems must not exceed in height the lesser of the height of the roof plus ten feet, or the distance from the base of the antenna tower system (at its connection point with the roof) to the nearest property line.
- (2) *Satellite dish stations.*
 - a. *Height.* No part of any satellite dish station may exceed 12 feet in height.
 - b. *Size.* The diameter or any exterior dimension of any satellite dish station must not exceed ten feet.

- c. *Location.* All satellite dish stations in residential districts must be located in a rear yard and comply with the minimum distance requirements for detached accessory structures, as stated in section 122-667, however, a satellite dish station may be located on the roof of a building under the following conditions:
 1. In the R1, CN-SF and CN-Mid zoning district, a satellite dish station may be located on the roof of a building associated with nonresidential use (i.e. school, religious institution or public service building), provided that the satellite dish station is located toward the rear of the building and is entirely screened from view from any public streets, pedestrian rights-of-way, or adjoining properties.
 2. In the MD, or CN zoning districts, a satellite dish station may be located on any roof; provided the satellite dish station is located toward the rear of the building, no portion of the dish station extends higher than four feet above the ridge or peak of the building's roof, and the dish station is entirely screened from view from any public street or pedestrian right-of-way.
- d. *Screening.* A greenbelt or fence must be installed around a ground mounted satellite dish antenna so as to reasonably conceal the view of the satellite dish antenna from adjacent public rights-of-way.

Sec. 122-686. Communication devices in C, HC, NC and GC districts.

The following requirements must apply to all communication devices in the C, HC, NC, and GC zoning district.

(1) *Antenna systems.*

- a. *Ground mounted height restrictions.* Ground mounted antenna systems must not exceed in height the lesser of 75 feet, or the distance from the base of the antenna system to the nearest property line.
- b. *Roof mounted height restrictions.* Roof mounted antenna systems must not exceed in height the lesser of the height of the roof plus 40 feet, or the distance from the base of the antenna tower system (at its connection point with the roof) to the nearest property line.

(2) *Satellite dish stations.*

- a. *Ground mounted height restrictions.* No part of any ground mounted satellite dish station may exceed 15 feet above ground level.
- b. *Roof mounted height restrictions.* Roof installations are permitted only on a building where the height of the roof surface where the satellite dish is to be mounted is at least 15 feet in height. No part of any satellite dish station may exceed higher than four feet above the ridge or peak of the building's roof, unless enclosed by an opaque screen not less in height than the satellite dish station. The design of the screening device must be compatible with the architectural design of the building upon which it is located.
- c. *Size.* The diameter or any exterior dimension of any satellite dish station must not exceed 15 feet.
- d. *Location.* All ground mounted satellite dish stations must be located in rear yards and comply with minimum distance requirements for accessory structures, as stated in section 122-667.
- e. *Screening.* A greenbelt or fence must be installed around a ground mounted satellite dish antenna so as to reasonably conceal the view of the satellite dish antenna from public rights-of-way.

Sec. 122-687. Communication devices in the PMD zoning district.

- (1) *Intent.* The intent of this Section is to permit the location of mobile communication facilities within the PMD zoning district and while protecting the safety and character of nearby residential areas and the City. It is further the intent of this Section to require co-location of transmission and receiving apparatus on existing structures or facilities, unless it can be demonstrated by the applicant that co-location is not technically feasible.

(2) *Definitions.*

- (a) ***Mobile Communication Facilities*** mean and include all structures and accessory facilities relating to the use of the radio frequency spectrum for the purpose of transmitting or receiving radio signals. This may include, but not be limited to, cellular telephone towers, radio towers, television towers, telephone devices and exchanges, micro-wave relay towers, telephone transmission equipment building and commercial mobile radio service facilities. Not included within this definition are: citizen band radio facilities; short wave facilities; ham, amateur radio facilities; satellite dishes; and, governmental facilities which are subject to state or federal law or regulations which preempt municipal regulatory authority.

- (b) **Attached Mobile Communications Facilities** means mobile communication Facilities that are affixed to existing structures, such as existing buildings, towers, water tanks, utility poles, and the like. A wireless communication support structure proposed to be newly established shall not be included within this definition.
- (d) **Mobile Communication Support Structures** means structures erected or modified to support wireless communication antennas. Support structures within this definition include, but not be limited to, monopoles, lattice towers, light poles, wood poles and guyed towers, or other structures which appear to be something other than a mere support structure.
- (e) **Co-location** means the location by two or more wireless communication providers of mobile communication towers on a common structure, tower, or building, with the view toward reducing the overall number of structures required to support wireless communication antennas within the community.

(3) Locational Factors.

- (a) The applicant must demonstrate the need for the proposed facility to be located as proposed based upon the presence of one or more of the following factors:
 - (i) Proximity to a major thoroughfare.
 - (ii) Areas of population concentration.
 - (iii) Concentration of commercial, industrial, and/or other business centers.
 - (iv) Areas where signal interference has occurred due to tall buildings, masses of trees, or other obstructions.
 - (v) Topography of the proposed facility location in relation to other facilities with which the proposed facility is to operate.
- (b) It is the policy of the City to minimize the overall number of newly established locations for mobile communication Facilities and encourage the use of existing structures.
 - (i) Co-location must be deemed to be "feasible" for purposes of this section where all of the following are met:
 - The wireless communication provider entity under consideration for co-location will undertake to pay market rent or other market compensation for co-location.
 - The site on which co-location is being considered, taking into consideration reasonable modification or replacement of a facility, is able to provide structural support.
 - The co-location being considered is technologically reasonable, e.g., the co-location will not result in unreasonable interference, given appropriate physical and other adjustment in relation to the structure, antennas, and the like.
 - The height of the structure necessary for co-location will not be increased beyond a point deemed to be permissible by the City, taking into consideration the standards set forth in this section.
 - (ii) Requirements for Co-location:
 - Approval for the construction and use of a new wireless communication facility must not be granted unless and until the applicant demonstrates that a feasible co-location is not available for the coverage area and capacity needs.
 - All new and modified mobile communication facilities must be designed and constructed so as to accommodate co-location.
 - If a party who owns or otherwise controls a facility fails or refuses to alter a structure so as to accommodate a proposed and otherwise feasible co-location, such facility will thereupon and thereafter be deemed to be a nonconforming structure and use, and must not be altered, expanded or extended in any respect.

(4) Application Requirements.

- (a) A site plan prepared in accordance with Article IV. The site plan must also include a detailed landscaping plan illustrating screening and aesthetic enhancement for the structure base, accessory buildings and enclosure.
- (b) The application must include a signed certification by a State of Michigan licensed professional engineer with regard to the manner in which the proposed structure will fall, which certification will be utilized, along with other criteria such as applicable regulations for the district in question, in determining the appropriate setback to be required for the structure and other facilities.
- (c) The application must include a description of security to be posted at the time of receiving a building permit for the facility to ensure removal of the facility when it has been abandoned or is no longer needed (see Section 122-687(6)). In this regard, the security must, at the election of the applicant, be in the form of: (1) cash; (2) surety bond; (3) letter of credit; or, (4) an agreement in a form approved by the City Attorney and recordable at the office of the Register of Deeds, establishing a promise of the applicant and owner of the property to timely remove the facility as required under this section of the ordinance, with the further provision that the applicant and owner must be responsible for the payment of any costs and attorneys' fees incurred by the City in securing removal.
- (d) The application must include a map showing existing and known proposed mobile communication facilities within the City, and further showing existing and known proposed mobile communication facilities within areas surrounding the borders of the City in the location, and in the area, which are relevant in terms of potential co-location or in demonstrating the need for the proposed facility. If and to the extent the information in question is on file with the community, the applicant is required only to update as needed. Any proprietary information may be submitted with a request for confidentiality in connection with the development of governmental policy, in accordance with MCL 15.243(1)G. This ordinance serves as the promise to maintain confidentiality to the extent permitted by law. The request for confidentiality must be prominently stated in order to bring it to the attention of the City.
- (e) The name, address and phone number of the person to contact for engineering, maintenance and other notice purposes. This information must be continuously updated during all times the facility is on the premises.

(5) General Regulations.

- (a) Towers must not exceed 140 feet in height when measured at grade level. This requirement may be waived in the sole discretion of the City based upon a consideration of the following standards.
 - (i) The tower is to be used by no less than one additional co-locator.
 - (ii) The topography of the site in relationship to the immediate surrounding area necessitates a tower of increased height.
 - (iii) The screening capabilities of the site provide adequate mitigation of the obtrusive visual effects of the tower.
 - (iv) The land use characteristics of the area surrounding the subject site are compatible with a tower of increased height.
 - (v) There is no feasible and prudent alternative to a tower of increased height based upon the opinion of an independent expert.
- (b) The accessory building contemplated to enclose switching equipment must be limited to fifteen (15) feet in height.
- (c) The setback of the support structure from any residential district must be no less than double the height of the structure. The setback of the support structure from an existing or proposed rights-of-way or other publicly traveled roads must be no less than the height of the structure.
- (d) Where the proposed support structure abuts a parcel of land zoned from other than residential purposes, the minimum setback of the structure and accessory structures must be in accordance with the required setbacks from the main or principal buildings as provided in the schedule of regulations for the zoning district in which the support structure is located.
- (e) There must be an unobstructed paved access drive to the support structure for operation, maintenance, repair and inspection purposes, which may be provided through or over an easement. This access drive must be a minimum of fourteen (14) feet in width.

- (f) Where a wireless communication facility is proposed on a roof of a building, the equipment enclosure is not permitted as a roof appliance or penthouse on the building. The equipment enclosure may be located within the principal building or may be an accessory building, providing that as an accessory building it conforms with all district requirements for principal buildings, including yard setback and building height.
- (g) The support structure must be constructed in accordance with all applicable building codes and must include the submission of a soils report from a soils engineer, licensed in the State of Michigan. This soils report must include soil borings and statements indicating the suitability of soil conditions for the proposed use. The clearance requirements of the Federal Aviation Administration and Federal Communications Commission must be noted.
- (h) No wireless communication tower may be located within three thousand (3,000) feet of another wireless communication tower. This requirement may be waived at the sole discretion of the City if one of the following conditions are met:
 - (i) The communication apparatus is located on an existing tower or other structure capable of accommodating such apparatus.
 - (ii) The tower/facility is of an exceptional design so as to create a positive architectural and/or environmental feature which is compatible with the character of the surrounding area and community.
 - (iii) The tower is intended to serve solely a governmental agency.
- (i) The tower and appurtenant apparatus building must be secured by fencing a minimum of six (6) feet in height. Landscape screening of the fencing and apparatus building must be provided in accordance with Article XI, Supplemental District Regulations, Division 4, Landscaping, Greenbelts and Screening.
- (j) The applicant must submit details of tower lighting approved by the Federal Aviation Administration.
- (k) A maintenance plan must be presented as part of the site plan for the proposed facility.
- (l) The name, address and phone number of the person to contact for engineering, maintenance and other notice purposes must be posted on the perimeter fencing, and must be continuously updated during all times the facility is on the premises.
- (m) The proposed tower or wireless communication facility must be located within 500 feet of the Interstate 94 right-of-way. This does not apply to collocation of wireless communication antenna on existing towers, buildings, or other existing structure.

(6) Removal.

- (a) The City reserves the right to request evidence of ongoing operation at any time after the construction of an approved tower.
- (b) A condition of every approval of a wireless communication facility must be adequate provision for removal of all or part of the facility by users and owners when the facility has not been used for 180 days or more.
- (c) The situations in which removal of the facility is required, the removal of antennas or other equipment from the facility, or the cessation of operations (transmission and/or reception of radio signals) must be considered as the beginning of a period of nonuse.
- (d) Upon the determination that a facility must be removed, the property owner or persons who had used the facility must immediately apply or secure the application for any required demolition or removal permits, and immediately proceed with and complete the demolition/removal, restoring the premises to an acceptable condition as reasonably determined by the Zoning Administrator.
- (e) If the required removal of a facility or a portion thereof has not been lawfully completed within sixty (60) days of the applicable deadline, and after at least thirty (30) days written notice, the City may remove or secure the removal of the facility or required portions thereof, with its actual cost and reasonable administrative charge to be drawn or collected from the security posted at the time application was made for establishing the facility.

Secs. 122-688--122-700. Reserved.

DIVISION 4.

LANDSCAPING AND SCREENING

Sec. 122-701. Intent.

The intent of this section is to:

- (1) Protect and preserve the appearance, character, and value of the community.
- (2) Minimize noise, air, soil, groundwater, surface water and visual pollution.
- (3) Minimize soil erosion and runoff, provide protection from wind and sun, mitigate the heat island effect and promote energy conservation.
- (4) Improve the overall aesthetics and appearance, divide the expanse of pavement, and define parking areas and vehicular circulation within off-street parking lots and other off-street parking facilities.
- (5) Buffer residential areas and lower-intensity land uses from more intense land uses.
- (6) Encourage an appropriate mixture of plant material, such as evergreen and deciduous trees and shrubs, to protect against disease infestation and produce a more aesthetic and cohesive design.
- (7) Encourage the integration of existing vegetation in landscape plans and preservation of specimen trees.

Sec. 122-702. Landscape plan requirements.

A separate detailed landscape/tree protection plan at a scale of not greater than 1"=50' must be submitted to the City as part of the site plan review or tentative preliminary plat review. The landscape/tree protection plan must demonstrate that all requirements of this Section are met and must include, but necessarily be limited to, the following items:

- (1) Location, spacing, size (caliper), root type (shallow or deep) and descriptions for each plant type (deciduous, conifer, annual, or perennial) to be planted.
- (2) Location, size (caliper), root type (shallow or deep), health and species name of all trees and plants to remain on the site. If trees or plants are proposed to be remain, information showing how these trees and plants will be protected during construction must be shown.
- (3) Typical straight cross section including slope, height, and width of berms.
- (4) Typical construction details to resolve specific site conditions, such as landscape walls and tree wells used to preserve existing trees or maintain natural grade.
- (5) Details in either text or drawing form to ensure proper installation and establishment of proposed plant materials as prescribed by the American Standard for Nursery Stock.
- (6) Identification and description of grass and other ground cover to be planted and method of planting (sod, plugs, sprigs or seeds).
- (7) Identification of landscape maintenance program in accordance with Section 122-712

Sec. 122-703. Screening between land uses.

- a. Upon any improvement for which a site plan is required, a visual screen at least six (6) feet in height must be constructed along all boundaries between land uses when required by this section. If the screen is composed of nonliving material, such material must be compatible with materials used in construction of the main building but in no case may include wire fencing. Such screen is required when:
 1. Required elsewhere in this Chapter;
 2. When a PMD zoning district abuts any other zoning district;
 3. When a HHS, HC, NC or GC zoning district abuts a R-1, CN-SF, CN-Mid, CN, MD zoning district;
 4. When a non-residential use abuts a property where a residential use occupies the first floor of the principal structure;
 5. Any multiple-dwelling use abuts an R-1, CN-SF, CN-Mid, or CN zoning district.

- b. *Screens* must be a wall, fence or landscape buffer. A wall or fence must be 80% opaque and may be constructed of face brick, poured-in-place simulated face brick, precast brick face panels having simulated face brick, stone or wood.

A landscape buffer must consist of evergreen trees and shrubbery to maintain a minimum opacity of at least eighty (80) percent and be no more than four (4) feet in width. To achieve effective screening, landscape materials must be planted in a staggered manner meeting the minimum opacity standard based upon reasonably anticipated growth over a period of three (3) years. The Planning Commission may approve a waiver when the design and placement of the screen meets the intent of the zoning district. A required screen must be located on the lot line except where underground utilities interfere and except in instances where this Zoning Ordinance requires conformity with front yard setback requirements; the Planning Commission may approve a waiver for an alternate location in such instances.

- c. *PMD district.* In the PMD zoning district, where there is a need to provide a greater noise or dust barrier or to screen more intense development, a solid wall or fence be required by the city planner or Planning Commission. The wall or fence must be constructed of face brick, poured-in-place simulated face brick, precast brick face panels having simulated face brick, stone or wood.

Sec. 122-704. Street Trees

The frontage of all public or private streets for any new or altered use which requires site plan review must be landscaped with street trees as follows:

- a. A minimum of one (1) tree for every thirty (30) lineal feet on of frontage (the frontage measurement includes proposed or existing access drives). Such street trees must meet the minimum size and spacing requirements set forth in 122-711(e). Existing trees in good health to be preserved may count towards the street tree requirements.
- b. The street trees must be centered between the sidewalk and the back of street curb.
- c. When potential tree planting site or sites within the right of way has been identified by the City, street trees must be planted in accordance with the Urban Forestry Plan. If additional street trees are required, the thirty foot measurement for other planting locations must be taken from the potential tree planting site(s).
- d. All street tree species must be listed on the Approved Trees List maintained by the City of Ypsilanti.

Sec. 122-705. Greenbelts

A greenbelt, where required, must be landscaped in accordance with the following requirements:

- a. The greenbelt must be landscaped with a minimum of one (1) tree for every thirty (30) lineal feet of frontage abutting a public road right-of-way.
- b. In addition to the required trees within the greenbelt, the remainder of the greenbelt must be landscaped in grass, ground cover, shrubs and other natural landscape materials.
- c. Access drives from public rights-of-way through required greenbelts must be permitted, but such drives may not be subtracted from the lineal dimension used to determine the minimum number of trees required.

Sec. 122-707. Foundation landscaping.

Foundation plantings must be provided in the MD and PMD zoning districts and the Single Story Commercial Building and Large Footprint Single Story Commercial Building building types. They must meet the following standards:

- a. *Location:* Foundation plantings must be provided along the front or sides of any buildings which face a public road and/or is adjacent to a parking lot or other area which provides access to the building(s) by the general public. Foundation planting areas must be integrated into the sidewalk system (between the front or sides of the building and the parking area and/or associated driveways) adjacent to the building.
- b. Foundation planting areas must contain a minimum of six (6) shrubs per thirty (30) lineal feet of applicable building frontage. Individual planting areas must be a minimum of six (6) feet in width.
- c. *Planting Area Width.* Individual planting areas must be a minimum of six (6) feet in width. At the discretion of the Planning Commission, the minimum width requirements may be reduced.

Sec. 122-708. Site landscaping.

Inclusive of any landscape greenbelt and/or off-street parking area landscaping required by this section, at least ten (10%) percent of the site area, excluding existing public rights-of-way, must be landscaped. Such site area landscaping may include a combination of the preservation of existing tree cover, planting of new trees and plant material, landscape plazas, gardens, vegetated roofs, and foundation landscaping beds. Site area landscaping must be provided to screen potentially objectionable site features such as, but not limited to, retention/detention ponds, transformer pads, air-conditioning units, storage and loading areas.

Sec. 122-709. Residential development landscaping.

Landscaping for residential development projects must be provided in accordance with the following requirements:

- a. **Street Trees.** The frontage of all internal public or private streets must be landscaped in compliance with Section 122-704.
- b. **Screening Between Land Uses.** The screening requirements set forth in Section 122-703 must be met.
- c. **Other Site Improvements.** A landscape plan for a subdivision or site condominium development must also include landscaping details of the entrance to the development, provisions for maintaining the natural water run-off, storm water retention and/or detention areas, community buildings and other recreational areas, and any other site improvement which would be enhanced through the addition of landscaping.

Sec. 122-710. Screening of exterior electrical equipment and transformers.

- a. Transformers that may be visible from any primary visual exposure area must be screened with either plantings or a durable non-combustible enclosure which are unified and harmonious with the overall architectural theme, and meet utility provider standards for location and maintenance.
- b. Exterior-mounted electrical equipment must be mounted on the interior of a building wherever possible, or must be located where it is substantially screened from public view.

Sec. 122-711. Landscape elements.

The following minimum standards must apply:

- a. **Quality.** Plant materials must be of generally acceptable varieties and species that are not invasive, free from insects and diseases, hardy to Washtenaw County, conform to the current minimum standard of the American Standard for Nursery Stock, and must have proof of any required governmental regulations and/or inspections.
- b. **Composition.** A mixture of plant material, such as evergreen deciduous trees and shrubs, is recommended as a protective measure against insect and disease infestation. A limited mixture of hardy species is recommended rather than a large quantity of different species to produce a more aesthetic, cohesive design and avoid a disorderly appearing arrangement.
- c. **Berms.** Berms must be constructed with slopes not to exceed a 1:3 gradient. Berm slopes must be protected with sod, seed, or other form of natural ground cover.
- d. **Credit for Existing Vegetation.** The preservation and incorporation of existing shrubs and trees is encouraged. Existing shrubs and trees may be used to satisfy the requirements of this section, if all of the following requirements apply:
 1. Paving, or other site improvements, must not encroach upon the drip line of the existing tree(s) to be preserved.
 2. If existing plant material is labeled "To Remain" on site plans by the applicant or required by the City, protective techniques, must be installed during construction. No vehicle or other construction equipment may be parked or stored within the drip line of any plant material intended to be saved.
 3. The shrubs and/or trees are in good health. In the event that healthy shrubs or trees which are used to meet the minimum requirements of this Ordinance or those labeled to remain are cut down, destroyed, damaged, or excavated at the drip line, as determined by the City, the contractor must replace them with trees which meet Ordinance requirements.
 4. The trees or shrubs proposed for credit are not a species that is invasive, brittle, susceptible to disease and insects, has a root structure that will interfere with underground utilities, drops excessive litter or other undesirable characteristics. Species include but are not limited to: Ash (*Fraxinus*), Black Locust

(Robinia spp.), Black Walnut (*Juglans nigra*), Siberian Elm (*Ulmus pumila*); Box Elder (*Acer negundo*), and Ginkgo Female (*Ginkgo biloba*).

5. The shrubs and/or trees meet the following minimum sizes and must receive credit based on size shown in the table below:

Shrub or Tree Type	Minimum Size	Size	Credit
Trees	2.5" in caliper	2.5"-8"	1
		8"-12"	2
		12"-20"	3
		Over 20"	5
Shrubs	24" in height	All sizes	1

- e. Minimum Size and Spacing Requirements. Where landscaping is required the following schedule sets forth minimum size and spacing requirements; for representative landscape materials:

	Small Trees	Medium Trees	Large Trees
Mature Height	10'-25'	25'-50'	> 50'
Growing Space	4'	6'-8'	8'+
Spacing Apart	20'	30'	40'
Distance from Existing Trees on Abutting Lots	30'	30'	30'
Distance from Street Corners	35'	35'	35'
Distance from Driveway Cuts and Alleys	15'	15'	15'
Distance from Overhead Utilities	None	20'-40'	40'+
Distance from Street Lights	15'	15'	15'

- f. Tree Species. All trees must be a species on the Approved Trees List maintained by the City of Ypsilanti, with the exception of fruit-bearing trees. Fruit-bearing trees are allowed in yard areas where they do not overhang sidewalks, walkways or parking lots. The Planning Commission may allow species not on the Approved Trees List, with a finding that the species is appropriate to the circumstance.

Sec. 122-712. Installation, maintenance, and completion.

- All landscaping required by this Ordinance must be planted before obtaining a Certificate of Occupancy or the appropriate financial guarantee, as set forth in Section 122-134, must be placed in escrow in the amount of the cost of landscaping to be released only after landscaping is completed.
- All landscaping and landscape elements must be planted, and earth moving or grading performed, in a sound workmanlike manner, according to accepted planting and grading procedures.
- All plant material must be maintained in good condition so as to present a healthy, neat and orderly appearance and must be trimmed or pruned in such a manner so as to not alter their natural growth potential.
- The owner of property required to be landscaped by this Ordinance must maintain such landscaping in a strong and healthy condition, free from physical damage or injury arising from lack of water, chemical damage insects, diseases, blight or other causes.

All materials used to satisfy the requirements of this Ordinance which become unhealthy or dead must be replaced within six (6) months of damage or death or the next appropriate planting period, whichever comes first.

- e. All landscaped areas must be provided with a readily available and acceptable water supply. Underground sprinkler systems may be installed, utilized and maintained in order to insure the proper watering of all plant materials on the sites.


Sec. 122-713. Fences, hedges, walls, berms, and screening.

Except as otherwise required by this Ordinance, the following regulations must apply:

- a. In a P, R-1, CN-SF, CN-Mid, CN, MD district, fences must not exceed six (6) feet in height. However, fences in the required front yard must not exceed four (4) feet in height and fifty (50%) percent opacity. Opacity is the degree to which a fence is impervious to rays of light. This condition is measured by the observation of any two (2) square yard area of fence between one (1) foot above the ground level and the top of the fence. The observation is from a direction perpendicular to the place of the fence.
- b. In a HHS, HC, NC, GC or PMD district, no fence, wall, or other screening structure shall exceed ten (10) feet in height, and must be constructed in the side or rear yard. Fences a maximum of six (6) feet in height may be permitted in the front yard, in accordance with corner visibility standards, when required by this chapter to screen residential used or zoned property. In such cases, the required front setback for the fence must be the same as for the structure or use which it is intended to buffer.
- c. The use of barbed wire, spikes, nails, or any other sharp point or instrument of any kind on top or on the sides of any fence is prohibited. Barbed wire cradles may be placed on top of fences enclosing public utility buildings or wherever deemed necessary in the interests of public safety.
- d. No fence may be constructed or maintained which is charged or connected with an electrical current.
- e. Retaining walls must be designed and constructed in accordance with applicable Building Code requirements.
- f. Temporary construction fences and fences required for protection around excavations must comply with the Building Code. Such fences must not remain in place for a period greater than a year.

Sec. 122-714. Modifications or exceptions to requirements.


- a. Buildings Abutting Property Lines. Required screening may be omitted along any lot line where a building wall exists immediately abutting the lot line.
- b. Location Adjustments. Where property line screening is required, the location may be adjusted at the discretion of the Planning Commission so that the screening may be constructed at or within the setback area, provided the areas between the screening and the property lines are landscaped or retain their natural vegetative state.
- c. Planning Commission Modifications. Any other requirements of this Section may be waived or modified through site plan approval, provided the Planning Commission first makes a finding:
 - i. That the topographic features or special characteristics of the site create conditions so that the strict application of the provisions of this Section will result in less effective screening and landscaping than alternative landscape designs.
 - ii. That the public benefit intended to be secured by this Section will exist with less than the required landscaping or screening.
 - iii. The historic district designation on the property precludes the ability to require any or all of the landscape requirements.



BERM OPTION

Sec. 122-_____. Standards

- * Minimum three (3) feet in height landscape berm along perimeter of those sides visible from a public road.



LANDSCAPE PLANTINGS / WALL OPTION


May 2000

- * Minimum distance of three (3) feet between backside of curb and proposed landscape plantings.
- * Minimum of five (5) feet minimum distance between backside of curb and the proposed landscape plantings where vehicles overhang.


OFF-STREET PARKING AREA LANDSCAPING- PERIMETER PARKING LOT

City of Ypsilanti, Michigan

Prepared By:
Carlisle / Wortman Associates, Inc.
Community Planners and Landscape Architects
Ann Arbor, Michigan



PLAN VIEW




ELEVATION

May 2000

REFUSE / RECYCLE CONTAINER SCREENING

City of Ypsilanti, Michigan


Prepared By:
Carlisle / Wortman Associates, Inc.
Community Planners and Landscape Architects
Ann Arbor, Michigan




May 2000


FOUNDATION LANDSCAPING **City of Ypsilanti, Michigan**

Prepared By:
Carlisle / Wortman Associates, Inc.
Community Planners and Landscape Architects
Ann Arbor, Michigan






TREES IN END ISLANDS



LANDSCAPE MEDIAN




LANDSCAPE ISLANDS

May 2000


DESIGN OPTIONS FOR OFF-STREET PARKING AREA LANDSCAPING- INTERIOR PARKING AREAS

City of Ypsilanti, Michigan


Prepared By:
Carlisle / Wortman Associates, Inc.
Community Planners and Landscape Architects
Ann Arbor, Michigan



PLAN VIEW



ELEVATION



SECTION

May 2000

SCREENING BETWEEN CONFLICTING LAND USES

City of Ypsilanti, Michigan

Prepared By:
Carlisle / Wortman Associates, Inc.
Community Planners and Landscape Architects
Ann Arbor, Michigan

DIVISION 5.
Reserved

Secs. 122-715—122-730. Reserved.

DIVISION 6.
STORAGE OF VEHICLES*

**Cross reference(s)--Traffic and vehicles, ch. 102.*

Sec. 122-731. General prohibition.

Except as otherwise provided in this chapter, no vehicles may be parked or stored on any residentially-zoned lot except for operable passenger automobiles, pickup trucks, vans, or motorcycles which are personally owned by the persons residing on the premises, or their guests.

Sec. 122-732. Commercial vehicles in residential areas.

The parking or storage of a commercial vehicle over a two ton capacity is prohibited on any residential lot. However, this section does not apply to commercial vehicles temporarily parked less than eight hours in a residential area in conjunction with maintenance or service to a residential property.

Sec. 122-733. Recreational vehicles.

- (a) The parking or storage of recreational vehicles, whether or not the recreational vehicle is mounted upon or hitched to another vehicle, including vacant mobile homes, antique or racing automobiles, or any other vehicles of a similar nature and related equipment, is prohibited on any lot in an R1, CN-SF, CN-Mid, CN, MD or HHS zoning district unless parked within a completely enclosed building or within a rear or side yard other than within a required yard setback area. Such vehicles stored in a side yard must be screened from view from the street and the adjacent property by an acceptable fence or landscaped screen, in accordance with Article XI, division 4 of this chapter. Notwithstanding the above, no recreational vehicle may be parked or stored on any indoor or outdoor parking space which is required to meet the minimum parking space requirement in an CN, MD or HHS district.
- (b) No more than two recreational vehicles per dwelling unit may be stored outdoors at one time. The size of recreational vehicles kept or stored outdoors may not exceed eight feet in width, ten feet in height, or 32 feet in length.
- (c) Trailer coaches, motor homes, and other vehicles or equipment designed or adaptable for sleeping purposes must remain unoccupied and must not be connected to sanitary sewer facilities, or to electricity, water, or gas.

Sec. 122-734. Unlicensed, untitled, and inoperable motor vehicles, and disassembled parts of motor vehicles.

No unlicensed, untitled, or inoperable motor vehicles, or disassembled parts of motor vehicles may be kept on any property within the city except as follows:

- (a) Contained entirely within a completely enclosed building so long as any indoor parking spaces, necessary for meeting minimum space requirements, must not be used for the storage of unlicensed or inoperable vehicles and so long as the storage is not otherwise prohibited.
- (b) The storage of vehicles as is specifically authorized in PMD and GC districts.
- (c) Minor repairs, such as changing flat tires, of vehicles where the repairs will be completed within 24 hours.

As used in this subsection:

“Enclosed building” means a garage or other permanent structure which has four walls, a roof, and a means of access for ingress and egress, i.e., doors large enough to accommodate ingress and egress, and is constructed in compliance with the applicable building codes. The placement of a tarpaulin or other covering over such vehicle does not meet the criteria for being within an enclosed building.

“Inoperable vehicle” means any motor vehicle which, by reason of dismantling, disrepair, or other causes, is incapable of being propelled under its own power or any motor vehicle which meets any of the three (3) of the following requirements:

- 1. Has any missing or broken windows
- 2. Has a missing hood.
- 3. Has a missing door.
- 4. Has missing or flat tires.
- 5. Has missing trunk lid.
- 6. Has a missing engine, or any substantial part thereof.
- 7. Is inoperable because of missing or defective steering mechanism.

8. Does not have any or all of the following:
operable head lights, parking lights, clearance
lights, tail lights, stop lights.

“*Motor vehicle*” means any wheeled vehicle which is
self-propelled or intended to be self-propelled.

“*Unlicensed vehicle*” means any motor vehicle that
does not have lawfully affixed to it a valid,
unexpired license plate.”

“*Untitled vehicle*” means any motor vehicle which has
not been titled in accordance with the law.

Sec. 122-735. Reserved

Sec. 122-736. Responsibility for violations.

In any proceeding for violation of any provision of this
division, both the person to whom a vehicle is registered as
determined from the registration plate displayed on such
motor vehicle, and the owner of the property on which the
vehicle is stored, will be presumed to be persons who
committed the violation charged. In the case of unlicensed
vehicles, the owner of the property on which the vehicle is
located will be considered to be the person responsible for
the violation charged.

Secs. 122-737--122-750. Reserved.

DIVISION 7.
YARD, AREA AND LOT REQUIREMENTS

Sec. 122-751. Altered land parcel.

No lot or parcel of land may be divided, altered or reduced by sale, gift, or other disposition so that the yards, parking area, or other open spaces, or the land area thereof is less than the minimum requirements of this chapter. No lot, parcel of land, parking area, or other open space may be reduced so as to increase its noncompliance with the minimum requirements of this chapter.

Sec. 122-752. Area requirements.

In determining lot, land, yard, parking area or other open space requirements, no area may serve to meet such requirements for more than one principal building or use, and no area necessary for compliance with the space requirements for one principal building or use be included in the calculation of the space requirements for any other building, structure, or use.

Sec. 122-753. Corner lots.

- (a) In the R-1 and MD districts, for corner lots platted or of record after August 8, 1984, the front yard regulations apply to each street side of the corner lot. The rear yard requirements for a corner lot apply to the open space which is opposite and most distant from the front lot line as designated in the plat and/or in the request for a building permit.
- (b) In the R-1 and MD districts, on corner lots platted or of record prior to August 8, 1984, the front yard regulations apply only along the front lot line as designated in the plat and/or in the request for a building permit. The yard along the second street must meet the requirements for side yards on corner lots as specified in the district regulations.

Sec. 122-754. Lots adjoining alleys.

In calculating the area of a lot that adjoins an alley for the purpose of applying lot area requirements of this chapter, one-half the width of such alley abutting the lot is considered as part of such lot.

Sec. 122-755. Determinations by zoning board of appeals.

When yard regulations cannot reasonably be complied with, or where their application cannot be determined on lots of peculiar shape, topography or due to architectural or site arrangement, such regulations may be modified or determined by the zoning board of appeals.

Sec. 122-756. Land division.

- (a) *Lot split or consolidation.* The division of lots must take place in accordance with the land division act, Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101 et seq., MSA 26.430(101) et seq.), as amended. Pursuant to the authority granted the city to regulate the division of a lot or parcel of land in a recorded plat, the division of a lot or other parcel of land in a recorded plat is prohibited unless first approved by the city assessor and city planner in accordance with the land division act, Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101 et seq., MSA 26.430(101) et seq.).
- (b) *Subdivision plats.* The subdivision of a tract of land into two or more lots, building sites, or other divisions for the purpose of sale or building development, must take place in accordance with the land division act, Act No. 288 of the Public Acts of Michigan of 1967 (MCL 560.101 et seq., MSA 26.430(101) et seq.), as amended.

Secs. 122-757--122-770. Reserved

ARTICLE XII. SPECIFIC STANDARDS FOR CERTAIN USES*

*Cross reference(s)--Businesses, ch. 22.

Sec. 122-771. Purpose.

It is recognized that there are certain uses that, due to size, location, use, or intensity, may adversely impact surrounding properties if not regulated. Such uses are generally listed within this chapter as special uses within specified zoning districts. This article states specific standards for approval of such uses in order to eliminate or mitigate any potential adverse impacts these uses may have on surrounding properties.

Sec. 122-772. Compliance with article.

The uses in sections 122-773--122-830, whether specifically allowed as permitted uses, permitted accessory uses, or special uses in any zoning district, may only be approved, established, operated, used, expanded or enlarged in accordance with the specific provisions listed in this article.

Sec. 122-773. Adult foster care small and large group homes, adult foster care congregate facilities and foster family group homes.

Adult foster care small and large group homes, adult foster care congregate facilities and foster family group homes must be permitted subject to the conditions hereinafter imposed:

- (1) All such facilities must be registered with or licensed by the state and must comply with the minimum state standards for such facilities and the city housing code.
- (2) For each adult cared for, the square footage of outdoor recreation or relaxation area required by the Building Code and licensing agency must be provided. Such outdoor space must be fenced and screened from any adjacent lot located within a residential district.
- (3) At least one off-street parking space must be provided for each caregiver working at the facility.
- (4) A resident manager must be employed or appointed if the owner does not live in the house.
- (5) Uses other than family day care homes, adult foster care family homes, foster family homes and foster family group homes, must not be located within 200 feet of property zoned R1 or CN-Mid and CN-SF.

Sec. 122-774. Adult regulated uses.

(a) In the development and execution of this section, it is recognized that there are certain uses, which by their very nature are recognized as having serious objectionable operational characteristics (particularly when several of them are concentrated in a small area), thereby having a deleterious effect on surrounding neighborhoods. Regulation of the location of these uses is necessary to ensure that the adverse effects of such businesses will not cause or contribute to the blighting or downgrading of the city's residential neighborhoods or commercial centers. It is the intent of this section to provide reasonable regulations for the establishment of adult regulated uses in a viable, accessible location where the adverse impact of their operations may be minimized. Uses subject to these regulations and the requirements of Article V of chapter 10 are as follows:

- (1) Adult: Adult book or supply store, adult hotels or motels, adult motion picture theater/adult live stage performing theater, and adult mini-motion picture theater.
 - (2) Cabarets.
 - (3) Massage parlors and massage establishments.
 - (4) Pawnshops.
- (b) No adult regulated use may be permitted within 1,000 feet of any other adult regulated use. Measurement of the 1,000-foot radius must be made from the outermost boundaries of the lot or parcel on which the adult regulated use is proposed. The Planning Commission may waive this requirement for pawnshops if the following findings are made that:
- (1) The proposed use will not be contrary to the public interest or injurious to nearby properties, and that the spirit and intent of this article is observed.
 - (2) The proposed regulated use will not enlarge or encourage the development of a "skid-row" or blighted area.
 - (3) The establishment of an additional adult regulated use in the area will not be contrary to any program of neighborhood conservation nor will it interfere with any program of urban revitalization.
 - (4) All applicable regulations of this chapter will be observed.

The Planning Commission may not waive this locational requirement for adult uses, cabarets, massage parlors, or massage establishments.

- (c) No adult regulated use may be permitted within 500 feet of any R1, HHS, P, MD, CN, CN-Mid and CN-SF district; nor may any adult regulated use be permitted

within 500 feet of any school, park, library, playground, movie theater, licensed child care facility, or any other area or use where minor children are likely to congregate; nor may any adult regulated use be permitted within 500 feet of any religious institution. Measurement must be from the outermost boundaries of the lot or parcel on which the adult regulated use is proposed to be located. This prohibition may be waived if the Planning Commission is presented with a validated petition requesting such waiver, signed by two-thirds of all persons owning, residing in, or doing business in the area within 500 feet of the proposed adult regulated use. The circulator of the petition must sign an affidavit attesting that the circulator personally witnessed the signatures and the signatures were affixed to the petition by the person whose name appears thereon. The signatures must be validated by the community economic development department. The Planning Commission cannot consider the waiver of the locational requirements until the required petition has been duly filed and verified. Pawnshops are not be subject to these locational requirements.

- (d) The building and premises must be designed and constructed so that material depicting, describing, or relating to specified sexual activities or specified anatomical areas, cannot be observed by pedestrians or from vehicles on any public right-of-way. This provision must apply to any display, decoration, sign, show window, or other opening.
- (e) No person may reside in or permit any person to reside in the premises of an adult regulated use.
- (f) Such uses must comply with all applicable federal, state, and local licensing regulations. Initial and annual proof of such compliance must be a condition of special use approval and the continuance thereof.
- (g) Upon finding that any condition, safeguard, or requirement has been breached, the building department can revoke any occupancy permit. All operations must cease 14 days following such notification of revocation by the building department, unless such violations are corrected. Also, if violations are not corrected within 14 days, reinstatement of a revoked permit must require a new special use application and approval thereof.

Sec. 122-775. Automobile service or repair.

Automobile service and repair are permitted subject to the conditions hereinafter imposed:

- (1) All lubrication equipment, hoists, and pits must be enclosed entirely within a building. All repair operations must take place within a completely enclosed building, and such building must not be located within 100 feet of any interior lot line abutting a residentially zoned district.
- (2) The entire lot, excluding areas occupied by landscaping and building, must be hard-surfaced with concrete or plant-mixed bituminous material. Curbs of at least six inches in height must be

installed around the perimeter of all surfaced areas. Drainage must be provided in accordance with subsection 122-835(6).

- (3) The storage, sale or rental of new or used automobiles, trucks, trailers, and any other vehicles on the premises is prohibited. Vehicles awaiting repair, or inoperable, wrecked, or partially dismantled vehicles, must not be stored or parked outside for a period exceeding seven days.
- (4) Quick oil change and similar facilities where permitted must provide off-street waiting spaces of at least three automobiles per bay, in addition to the required off-street parking spaces as provided in sections 122-836 and 122-838.

Sec. 122-776. Automobile filling stations.

Automobile filling stations where permitted are subject to the conditions hereinafter imposed:

- (1) The curb cuts are not permitted at such locations that will tend to create traffic hazards in the streets immediately adjacent thereto. Entrances must be no less than 25 feet from a street intersection (measured along the road right-of-way). Drives must be no less than 20 feet wide, nor wider than 30 feet at the right-of-way line. No more than one such drive or curb opening may be permitted for every 75 feet of frontage along any street or in accordance with county or state requirements, whichever is greater.
- (2) The entire lot, excluding areas occupied by landscaping and building, must be hard-surfaced with concrete or plant-mixed bituminous material. Curbs of at least six inches in height must be installed around the perimeter of all surfaced areas. Drainage must be provided in accordance with subsection 122-835(6).
- (3) All fuel pumps must be located not less than 15 feet from any lot line; provided however, that fuel pumps may not be located less than 40 feet from any interior lot line which abuts residentially zoned property, nor closer than 100 feet from any religious institution, theater, hall, or other place of public assembly.
- (4) A rigid canopy which covers the fuel dispensing area is permitted provided that the lowest edge of such canopy must be a minimum of 14 feet above grade. For service stations located within a NC zoning district, the nearest edge of any canopy must be set back a minimum of ten feet from any lot line. For service stations located within a GC zoning district, the nearest edge of any canopy must be set back a minimum of 15 feet from any lot line. All support structures for canopies must be located so as not to obscure the vision of motorists using any nearby streets, driveways, or maneuvering aisles.
- (5) The storage, sale, or rental of new or used automobiles, trucks, trailers, or any other vehicles on the premises is prohibited. Inoperable, wrecked

or partially dismantled vehicles must not be stored or parked outside for a period exceeding two days.

- (6) All outdoor lighting must comply with section 122-641.

Sec. 122-777. Automobile or car wash establishments.

Automobile or car wash establishments are permitted subject to the conditions hereinafter imposed:

- (1) All washing activities must be carried out within a building. Vacuuming activities may be permitted outdoors, provided such activities are located at least 50 feet from adjacent R1, P, MD, CN, CN-Mid and CN-SF districts or property with first-floor residential uses.
- (2) The entire lot, excluding areas occupied by landscaping and building, must be hard surfaced with concrete or plant-mixed bituminous material. Curbs of at least six inches in height must be installed around the perimeter of all surfaced areas. Drainage must be provided in accordance with subsection 122-835(6).
- (3) Sufficient space must be provided on the lot so that vehicles do not enter or exit the wash building directly from an adjacent street or alley. All maneuvering areas, stacking lanes, and exit aprons must be located on the car wash parcel itself. Streets and alleys may not be used for maneuvering or parking by vehicles to be serviced by the automobile wash.

Sec. 122-778. Bed and breakfast and inns.

Bed and breakfast lodgings and inns are permitted subject to the conditions hereinafter imposed:

- (1) The structure to be used as a bed and breakfast lodging must be the principal residence of the owner/operator and such owner/operator must live on the premises when the bed and breakfast lodging is in operation. In the case of an inn, the owner may reside elsewhere so long as a resident manager is employed and lives on the premises. A minimum of 450 square feet of living space must be preserved for the owner/operator's quarters.
- (2) Rooms used for sleeping must have a minimum of 100 square feet for two occupants, plus an additional 50 square feet for each additional occupant. Rooms must be designed to accommodate no more than four occupants.
- (3) Food may only be served to guests staying at the bed and breakfast lodging. There may not be separate cooking facilities for the bed and breakfast lodging other than those which serve the principal residence. An inn may operate a restaurant on the premises, provided that all requirements of this chapter related to restaurants, as well as any other applicable regulations, are met; and provided that no expansion of the residential building in order to accommodate a restaurant is permitted.

- (4) Two off-street parking spaces must be provided plus one additional space per room to be rented. An inn which operates a restaurant must also meet the parking requirements for the restaurant, in addition to the above requirement.

- (5) Changes to the building structure must not be made that would prevent the structure from being reverted in the future to any residential use permitted in the zoning district. Bed and breakfast lodgings or inns may not be converted to a roominghouse unless a special use permit is approved by the Planning Commission in accordance with Article V of this chapter.

- (6) Bed and breakfast lodgings and inns are subject to city licensing provisions, and must be inspected every two years for compliance with this chapter and the city building code.

Sec. 122-779. Child care centers; child drop-off centers, and group day care homes.

Child care centers, child drop-off centers or group day care homes (not including dormitories) are permitted subject to the conditions hereinafter imposed:

- (1) All child care centers, child drop-off centers and group day care homes must be registered with or licensed by the state department of social services and must comply with the minimum state standards for such facilities.
- (2) The square footage of outdoor recreation required by the Building Code and licensing agency must be provided and maintained. Such space must be fenced and screened from any adjoining lot in any residential district.
- (3) At least one off-street parking space for each care giver must be provided. Additional off-street or on-street spaces must be made available for the safe drop-off and pick-up of persons being cared for at the facility. Such drop-off-sites must not obstruct the flow of traffic along any public thoroughfare.
- (4) Child drop-off centers care for minor children for longer periods than four (4) hours.

Sec. 122-780. Religious Institutions and Services.

Religious institutions and services, including accessory offices, rectories or parsonages, meeting rooms, and classrooms for religious instruction only are permitted subject to the conditions hereinafter imposed:

- (1) For religious institutions located within the R-1 and MD districts, parking areas must be prohibited in the required front yard or street side yard setback areas. Parking areas which are located behind the required setback area adjacent to a street right-of-way must be screened in accordance with subsection 122-835(11).
- (2) Buildings of greater than the maximum height allowed in the zoning district may be permitted by exception approved by the Planning Commission provided that the front, side, and rear yards are

increased beyond the minimum required yards by one foot for each foot of building height that exceeds the maximum height allowed. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, the Planning Commission may grant exceptions based on maximum compliance possible with the IT institutional building type.

- (3) Related uses such as social centers, social service centers, child care centers, and rental banquet facilities are prohibited unless the Planning Commission finds that any adverse impacts on surrounding properties and traffic will be mitigated.

Sec. 122-781. Parking garages.

Parking garages are permitted subject to the conditions hereinafter imposed:

- (1) Such use must not be located within 100 feet of an R1, CN-Mid or CN-SF district.
- (2) The architectural style and facade of the structure must be in keeping with the character of surrounding residential and business uses.
- (3) All areas not used for parking or vehicular maneuvering must be landscaped and maintained in good condition.
- (4) The vehicle entrances to structured parking should be from side streets and/or access roads. No access from a major thoroughfare is permitted.
- (5) Direct pedestrian access from parking garages to any adjacent street must be provided.
- (6) The exterior facades of all parking garages fronting on any street must be designed to achieve an architectural unity with the block.
- (7) Parking garages must comply with all building design standards for building façade, scale, building features and lighting, compatibility, and placement on the site when located in the Historic District.
- (8) The parking garage must have sheltered bicycle and motorcycle parking areas within 25 feet of the vehicular entrance.
- (9) The City may approve other design alternatives, such as liner buildings around the outer edge of the garage.

Sec. 122-782. Parking lot as principal use.

A parking lot as a principal use is permitted subject to the conditions hereinafter imposed:

- (1) If the lot is located on or adjacent to a permitted or special use which it is intended to serve, the minimum number of parking spaces intended to serve that use must be provided.
- (2) A lighting plan must be submitted for lots which contain more than 20 spaces, which must be approved by the Planning Commission during site plan review.

- (3) Parking lots must meet all requirements for off-street parking in accordance with Article XIII of this chapter.

Sec. 122-783. Drive-in and drive-through restaurants.

Drive-in and drive-through restaurants, or any restaurant which provides a drive-through window, as defined under "restaurant" in section 122-3 are permitted subject to the conditions hereinafter imposed:

- (1) Principal and accessory buildings and structures must be located no closer than 60 feet from any residential district. Canopies and support structures or portions thereof must meet all yard setback requirements. The lowest edge of a canopy must be at least 12 feet above grade.
- (2) Drive-through windows or other facilities must be located no closer than 100 feet to a residential district. The sound from amplification equipment must not be audible beyond the boundaries of the site.
- (3) In addition to any required off-street parking for employees and sit-down restaurant facilities, stacking spaces for each drive-through window must be provided in accordance with section 122-840.
- (4) All drive-in and drive-through restaurants must have direct access to a major thoroughfare in accordance with section 122-642. No ingress or egress curb cuts may be located closer than 60 feet from the intersection of two streets.

Sec. 122-784. Drive-through facilities.

Drive-through facilities in combination with any kind of store, financial institution, or personal service business are permitted subject to the conditions hereinafter imposed:

- (1) Drive-through windows or other facilities and stacking spaces must not be located within 50 feet of a residentially-zoned district. Off-street stacking spaces must be provided in accordance with section 122-840. Canopies and support structures associated with drive-through facilities must meet all minimum yard setback requirements.
- (2) All drive-in facilities must have direct access to a major thoroughfare in accordance with section 122-642. Ingress and egress curb cuts to the site must be located at least 60 feet from the intersection of any two streets, measured along the nearest right-of-way line.
- (3) Devices for the transmission of voices must not be audible beyond the boundaries of the site.

Sec. 122-785. Homeless Shelter.

Emergency shelters for the homeless are permitted subject to the conditions hereinafter imposed:

- (1) The facility must be operated by a recognized human service agency, incorporated by the state and which is not for profit.
- (2) Resident manager and support services must be provided.
- (3) No such facility may be located within 1,000 feet of a similar facility.

Sec. 122-786. Express and passenger terminals.

Express and passenger terminals and express transfer facilities are permitted subject to the conditions hereinafter imposed:

- (1) All ticket booths, waiting areas, and other passenger facilities must be wholly contained within an enclosed building.
- (2) Stopping and stacking spaces for buses or taxis must not encumber traffic nor present a safety hazard for vehicles or pedestrians on public rights-of-way.
- (3) Curb cuts must not be permitted at such locations that will tend to create traffic hazards in the streets immediately thereto. No drives may be wider than 30 feet at the right-of-way line, and no more than one such drive or curb cut may be permitted for every 50 feet of frontage along any street.

Sec. 122-787. Reserved.

Sec. 122-788. Alternative Energy.

(1) Photovoltaic Production

- (a) Attached accessory photovoltaic structures are permitted in all zoning districts when meeting the following requirements:

- i. *Positioning.* All attached photovoltaic structures positioning and attachment must meet Building Department requirements for snow loads and wind loads.
- ii. *Height.* All attached photovoltaic structures must meet the following height regulations by type:
 - a. *Maximum.* The maximum height of photovoltaic roof paneling installed on a sloped roof or flat roof of a building is ten feet above the maximum building height allowed for that zoning district or building type . Photovoltaic panels attached to the side of a structure must not project vertically above the building height allowed for that zoning district or building type.

- (b) *Detached accessory photovoltaic structures,* when mounted top-of-pole for outdoor lights, are permitted in all zoning districts. In no

instance may such panels exceed 20 feet in height.

- (c) *Solar farms.* On sites where the primary use is photovoltaic energy production, all structures must meet the height requirement of the zoning district.

- i. *Abandonment.* Any freestanding *photovoltaic system* which is not used for six (6) months will be deemed to be abandoned. The applicant/permit holder will be so notified in writing by the municipality and requested to dismantle the site and return it to its original state. If there are mitigating circumstances as to why the site has not been used, the applicant/permit holder may contact the municipality and request a three-month extension. If a site has been deemed abandoned and no request for an extension is received, the applicant/permit holder will again be notified to dismantle the site and return it to its original state. If the applicant/permit holder does not do this, the municipality will have the removal and restoration done at the owner/applicant's expense. Removal will include removing posts, equipment, panels, foundations and other items so that the ground is restored to its preconstruction state and is ready for development as another land use.

- (2) *Solar water heating.* Attached accessory solar water heating systems are permitted in all zoning districts. Solar collectors installed on a sloped roof of a building must not project vertically above the peak of the roof. Solar collectors attached to a flat roof must not project vertically more than 10 feet above the roof. Solar panels attached to the side of a structure must not project vertically above the building height allowed for that zoning district or building type.

- (3) *Wind energy production.* Attached accessory wind energy production structures are permitted in all zoning districts, subject to height limitations.

- (4) *Geothermal energy production.* Attached accessory geothermal energy production systems are permitted in all zoning districts.

- (5) *Other methods.* Other methods of alternative energy production may be submitted to the City Planner and, at their discretion, may be approved, approved subject to another City department(s) review, approved subject to Planning Commission review, or denied.

Sec. 122-789. Attached or detached accessory stormwater control features

- (1) *Swales.* Both biofiltration and vegetated/rock swales as defined in 122-3 are permitted in all districts.
- (2) *Pervious paving.* Pervious paving is permitted in all districts subject to Article IV Site Plan Review, where required, and Section 122–835, Parking lot layout and construction.
- (3) *Rain gardens.* As defined in 122-3, rain gardens are permitted in all districts subject to Article IV Site Plan Review, where required. Rain gardens installed accessory to one- or two-family uses in the R-1 district or the Townhouse, Cottage, or House building types in the CN, CN-Mid, CN-SF districts do not require engineering review.
- (4) *Rain barrels or cisterns.* Rain barrels or cisterns are permitted in all districts subject to Article IV Site Plan Review, where required.
 - (a) Underground cisterns or rain barrels are subject to engineering review and constructed in accordance with the State Building Code.
 - (b) Aboveground rain barrel or cistern systems in excess of 250 gallons accessory to the Mansion, Estate, Apartment House, Courtyard Apartment, Apartment Building, Commercial/Mixed-Use Small, Commercial/Mixed-Use Medium, Commercial/Mixed-Use Large, Single-story Commercial Building, Large Footprint Single Story Commercial Building, Multiple Story, or Institutional building types; or in excess of 250 gallons and located in the R-1 district not accessory to a single-family use; or in excess of 250 gallons and located in the MD or PMD districts, must conform to the accessory building standards in place for those building types and be subject to engineering review and constructed in accordance with the State Building Code.
- (5) *Vegetated roofs.* Vegetated roof systems are permitted in all districts in accordance with the State Building Code.
- (6) *Other methods.* Other methods of onsite stormwater control may be submitted to the City Planner and, at their discretion, may be approved, approved subject to another City department(s) review, approved subject to Planning Commission review, or denied.

Sec. 122-790. Junkyards.

Junkyards are permitted subject to the conditions hereinafter imposed:

- (1) The minimum lot size must be one acre.
- (2) A minimum setback of 50 feet must be maintained between the front property line and the portion of the property on which junk materials are placed or stored. Outdoor storage areas must also conform to all other setback requirements for principal buildings. No junkyard may be located within 300 feet of a R1, HHS, P, MD, CN, CN-Mid and CN-SF district.
- (3) All outdoor storage areas for junkyards must be screened by a six-to eight-foot obscuring wall constructed of masonry, concrete or other similar material.
- (4) All roads, driveways, parking lots, and loading and unloading areas must be paved or treated in a manner approved by the city building department so as to confine any wind-borne dust to within the boundaries of the site.
- (5) Proper access to all parts of the storage areas must be provided for fire and emergency services, as required by the city building code and BOCA code.

Sec. 122-791. Commercial kennels.

Commercial kennels are permitted subject to the conditions hereinafter imposed:

- (1) Any such kennel must be subject to all permit and operational requirements established by city, county, and state regulatory agencies.
- (2) Buildings in which animals are kept, animal runs, and exercise areas must not be located in any required yard setback areas, and must be located at least 300 feet from any dwellings and 100 feet from any buildings used by the public.
- (3) All outdoor animal runs or exercise areas must be fenced and secured at all times so that no animal contained therein may escape such enclosure.

Sec. 122-792. Reserved.

Sec. 122-793. Adult drop-in centers or neighborhood counseling centers.

Adult drop-in centers or neighborhood counseling centers are permitted subject to the conditions hereinafter imposed:

- (1) Access to and from the site must be directly to a major street as defined in section 122-642, or to a major street through an HHS or a nonresidential district. In no event may access be through an R1, MD, CN, CN-Mid, or CN-SF district.
- (2) Social services, such as food and/or clothing distribution or other similar services, are permitted only if the Planning Commission should find that adequate ingress and egress, parking, and indoor waiting and storage areas are provided.

Sec. 122-794. Multiple-family dwellings containing seven or more units.

Multiple family dwellings containing seven (7) or more units:

- (1) Access to the site from a major thoroughfare must not traverse through or abut an R1, CN-SF or CN-Mid district, unless access is directly from a major thoroughfare.
- (2) Access drives, parking areas, and maneuvering lanes must be located to minimize their conflict with buildings and outdoor living areas and to encourage pedestrian and vehicular safety and convenience. Sidewalks for convenient pedestrian flow between buildings, parking areas, outdoor living areas, and public rights-of-way must be provided. In the Neighborhoods, Centers, Corridors and Health and Human Services zoning districts, all circulation standards must be met.
- (3) The required parking spaces must be as conveniently located in close proximity to the dwellings they are intended to serve as is practicable. In no case may any parking space be located further than three hundred (300) feet from the nearest entrance to the building.
- (4) All dwelling units must be readily accessible by fire and emergency vehicles. Fire lanes must be paved and posted as required in the Building Code adopted by the City of Ypsilanti. Emergency vehicle turn-around areas must be provided where there is no driveway outlet.
- (5) All parking areas, building entrances, and sidewalks must be illuminated for safety and security.
- (6) The following regulations apply to the MD district only:
 - a. A total of one hundred thirty (130) square feet of outdoor living space must be provided for each bedroom or studio/efficiency unit. Porches, balconies and improved roof areas may count toward the required outdoor living space, provided no such area is less than five (5) feet in width. Such outdoor areas must be buffered from streets and parking lots. Off-street parking areas, driveways, and accessory uses may not be counted as required open space.
 - b. The total number of rooms in a multiple apartment dwelling structure must not be more than the area of the parcel in square feet divided by 1,400 square feet. The required minimum floor area per unit type is as follows:

Unit Type	Required Min. Square Footage
1 Bedroom	600
2 Bedroom	800
3+ Bedroom	1,000

Sec. 122-795. Municipal, county, regional, and state service buildings and uses.

Municipal, county, regional, and state service buildings and uses are permitted subject to the conditions hereinafter imposed:

- (1) For such uses proposed to be located within an R1, MD, CN, CN-SF, CN-Mid district, operating requirements must necessitate that the facility be located within that district in order to serve the immediate vicinity. Where possible such facilities must be located in an HHS or a nonresidential district. Storage yards, sales or business offices, commercial buildings or activities, sanitary landfills, or water or sewage treatment plants are prohibited in the R1, MD, CN, CN-SF, and CN-Mid districts.
- (2) Public buildings and utility uses must not include any outdoor storage of materials or vehicles, unless as permitted within the PMD district.
- (3) The architecture and construction materials must be in character with the surrounding residential area.

Sec. 122-796. Nursing homes, convalescent homes and rest homes.

Nursing homes, convalescent homes, and rest homes are permitted subject to the conditions hereinafter imposed:

- (1) Such facilities must be constructed, maintained, and operated in conformance with applicable state and federal laws.
- (2) Off-street parking is prohibited in the front and street-side setback area. In case any off-street parking area abuts a lot in any residential district, screening must be provided as provided in section 122-703.
- (3) Such facility must provide the square footage of outdoor open space required by the Building Code and licensing agency. The open space must be landscaped, buffered from streets and parking lots, and include places for walking and sitting. Off-street parking areas, driveways, and accessory uses or areas may not be counted as required open space.

Sec. 122-797. Offices and showrooms for skilled trade services.

Offices and showrooms of a skilled trade service are permitted subject to the conditions hereinafter imposed:

- (1) Any fabrication, repair, cleaning or other processing of goods must conform to fire and building code.
- (2) Those areas of the ground floor which face upon or are visible from any adjacent streets must be used only for entrances, offices, sales, or display.
- (3) There must be no outside storage of materials or goods of any kind.
- (4) Storage of commercial and other vehicles inside the building is permitted, pursuant to building and fire code.

Sec. 122-798. Open-front or open-air businesses; outdoor recreation/amusement facilities; outdoor sales of new or used automobiles, trucks and tractors, boats, etc.

Open-front or open-air businesses; outdoor recreation/amusement facilities; and outdoor sales of new or used automobiles, trucks and tractors, boats, mobile homes, recreational vehicles and trailers are permitted subject to the conditions hereinafter imposed:

- (1) All loading and parking areas for open air businesses shall be confined within the boundaries of the site, and shall not be permitted to spill over onto adjacent public rights-of-way. Curbs or wheel stops shall separate parking areas from all sidewalks.
- (2) All areas of a front yard or street side yard which are not landscaped, shall be provided with a concrete or plant-mixed bituminous surface, and shall be graded and drained so as to dispose of all surface water accumulated within the area.
- (3) Driveway access to the outdoor business area shall be at least 50 feet from the intersection of any two streets.
- (4) The location, layout, design, or operation of the outdoor business shall not impair the continued enjoyment, use, and future development of nearby properties. The use shall not generate excessive noise, odors, dust, or other impacts. The Planning Commission may specify hours of operation and stricter screening mechanisms to assure compatibility with adjacent uses.
- (5) No major repair or major refinishing is permitted on the outdoor sales lot.
- (6) All lighting shall be shielded from adjacent residential properties and public rights-of-way.

Sec. 122-799. Outdoor cafes, restaurants and beer gardens.

Outdoor cafes, restaurants and beer gardens shall be permitted subject to the conditions hereinafter imposed:

- (1) All outdoor seating areas at grade level must be accessory to business which provides indoor seating or food concession. All storage, preparation and cooking of food and all vending machines shall be within an enclosed building or food concession.
- (2) The outdoor seating area shall be separated from all parking areas by means of a minimum three-foot high planting, wall or other architectural feature delineating the space.
- (3) The outdoor seating area shall not be located within 50 feet of any properties zoned R1, MD, CN, CN-Mid, or CN-SF.
- (4) All outdoor seating areas shall be kept clean and void of litter at all times.

(see also 94-192 for outdoor cafés in the ROW)

Sec. 122-800. Outdoor retail sales of plant materials, lawn furniture, playground equipment, garden supplies, etc.

Outdoor retail sales of plant materials, lawn furniture and decorations, playground equipment, and home and garden supplies shall be permitted subject to the conditions hereinafter imposed:

- (1) Plant storage and display areas shall comply with all minimum setback requirements for the zoning district.
- (2) The storage of soil, fertilizer, and similar loosely packaged materials shall be contained and covered to prevent it from blowing onto adjacent properties.

Sec. 122-801. Outdoor storage of raw materials, supplies and products.

Outdoor storage of raw materials and supplies or finished or semi-finished products shall be permitted subject to the conditions hereinafter imposed:

- (1) All such storage shall be located within a rear yard and screened with fencing in accordance with section 122-703. No material shall be stored above the height of the screening.
- (2) All storage areas shall conform to all district setback requirements for principal uses, but in no case shall outside storage be located closer than 50 feet to residentially zoned property.
- (3) Property access to all parts of the storage areas shall be provided for fire and emergency services as provided in the city building code.
- (4) All loosely packed materials such as sand, topsoil, dirt, etc., shall be covered and contained to prevent them from being blown or washed off of the site.
- (5) No materials which give off noxious odors shall be stored outdoors.

Sec. 122-802. Private noncommercial recreational areas or social facilities; institutional or community recreational centers; nonprofit swimming pool or tennis club.

Private noncommercial recreational areas or social facilities, institutional or community recreational centers, and nonprofit swimming pool or tennis club shall be permitted subject to the conditions hereinafter imposed:

- (1) If the proposed use would attract persons from, or is intended to serve areas beyond the immediate neighborhood, the site shall have direct access to a major thoroughfare in accordance with section 122-642.
- (2) Except in the Neighborhoods, Centers, Corridors and Health and Human Services districts, front, side, and rear yards shall be at least eight feet wide, and shall be landscaped in trees, shrubs, and grass. All such landscaping shall be maintained in a healthy condition. In the Neighborhoods, Centers, Corridors and Health and Human Services districts, any

buildings shall comply with the IT institutional building type.

- (3) The Planning Commission may reduce the number of off-street parking spaces required as specified in section 122-837 in those instances where it is specifically determined that the users will originate from the immediately adjacent areas and will therefore be pedestrian.

Sec. 122-803. Recycling centers.

Recycling centers for discarded items shall be permitted subject to the conditions hereinafter imposed:

- (1) Such use shall be located no closer than 300 feet to residentially zoned property.
- (2) All separation and storage areas shall conform to the setback requirements for buildings in the PMD district and screened with fencing in accordance with section 122-703.
- (3) Access to such site shall not be through or abut residentially-zoned property.
- (4) Proper access to all parts of the storage areas shall be provided for fire and emergency access as provided by the city building code.
- (5) Recycling drop-off centers shall not occupy more than 6,000 square feet of area; shall not handle vegetative yard wastes (grass clippings, leaves, brush, etc.) or industrial, toxic, or liquid wastes; and shall not be involved in the compounding, washing or cleaning, treating, or composting of any materials.

Sec. 122-804. Roominghouses and Group Residences.

Roominghouses and group residences are permitted subject to the following conditions:

- (1) A roominghouse or group residence permitted as a special use shall not be located within 200 feet of an R1 or CN-SF district.
- (2) The minimum usable floor area of the structure, size of common interior living space, and kitchen facilities must comply with the applicable Building Codes and Fire Codes adopted by the City of Ypsilanti. Kitchen facilities shall be provided on the premises for the residents therein.
- (3) Rooms for sleeping shall have a minimum square footage as required by the housing code adopted by this Code.
- (4) If the owner of the property does not reside on the premises, the owner must appoint a resident manager, who must reside on the premises. The property owner must provide the name and contact information of this person upon request by the City.
- (5) For rooming houses or group residences permitted as a special land use access to and from the site shall be directly to a major street or to a major street through a CN, CN-M or nonresidential district. In no event shall access be through an R1 or CN-SF district.

Sec. 122-805. Primary, Secondary and Post-Secondary Schools (public & private).

Elementary, junior, senior high, and post-secondary schools, public and private schools (but not regulating home schooling as defined by the state department of education) shall be permitted subject to the conditions hereinafter imposed:

- (1) Staff and curriculum must meet the educational qualifications established by the state.
- (2) All buildings must meet the building and fire safety qualifications as established by the state.
- (3) Except in the CN, CN-SF, CN-Mid, C, HC, NC, GC, and HHS districts, the minimum lot area shall be 13,000 square feet. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, and HHS districts, the minimum lot area is determined by the IT institutional building type.
- (4) The site shall have direct access to a major thoroughfare, as provided in section 122-642.
- (5) Except in the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, buildings of greater than the maximum height allowed within a given zoning district may be allowed provided that the front, side, and rear yards are increased above the minimum required yards by one foot for each foot of building height that exceeds the maximum height allowed. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, the maximum height is determined by the IT institutional building type.
- (6) Except in the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, off-street parking shall be prohibited in the required front yard setback area. In the CN, CN-SF, CN-Mid, C, HC, NC, GC, HHS districts, parking location is determined by the IT institutional building type. In the case any off-street parking area abuts a lot in any residential district, screening must be provided as provided in section 122-703.
- (7) For primary and secondary schools, the developer of the site shall document that a minimum of two off-street or on-street parking spaces shall be available for drop-off and pick-up of children, plus one additional drop-off/pick-up space for each 100 children that the facility has in attendance.
- (8) If bus transportation is to be provided, documentation that adequate ingress and egress for bus traffic to the site shall be provided. If public bus transportation is utilized, a bus drop-off point within 250 feet of the school shall be available.
- (9) Athletic fields and playgrounds accessory to educational facilities shall be shown on the approved site plan shared with the city.

Sec. 122-806. Self-storage facilities and vehicle storage facilities.

Self-storage facilities and vehicle storage facilities shall be permitted subject to the conditions hereinafter imposed:

- (1) In the C, NC and GC districts, self-storage and vehicle storage facilities must comply with the regulations for building types. In all other districts, the facility shall be surrounded by a six-foot high solid obscuring fence, except for entrance gates. Required fencing near ingress and egress driveways may be lowered to permit adequate sight distances for vehicles entering and exiting the facility.
- (2) No single storage space shall exceed 500 square feet, except for vehicle storage facilities.
- (3) Only vehicles may be stored in vehicle storage facilities.
- (4) Adequate security shall be provided and maintained.
- (5) A single residential unit, to be occupied only by a residential manager and his family, with a floor area not exceeding 1,500 square feet, is permitted.

Sec. 122-807. Enclosed storage of liquid and solid fuels.

Storage within enclosures of liquid and solid fuels shall be permitted subject to the conditions hereinafter imposed:

- (1) All storage tanks and the handling of all flammable liquids shall be in compliance with the building code as adopted by this Code.
- (2) Below-ground storage tanks shall be located no closer than 50 feet from any property line and, when required, shall be registered with the state fire marshal.

Sec. 122-808. Substance abuse treatment facilities.

Substance abuse treatment facilities shall be permitted subject to the conditions hereinafter imposed:

- (1) Such facilities shall have direct access to a major thoroughfare, in accordance with section 122-642.
- (2) Such uses shall not be located within 1,000 feet of an R1, CN-Mid, or CN-SF district or of another such facility.

Sec. 122-809. Veterinary hospitals and clinics.

Veterinary hospitals and clinics shall be permitted subject to the conditions hereinafter imposed:

- (1) All principal use activities, including animal boarding, shall be conducted within a totally enclosed building.
- (2) Buildings used for such purposes within 500 feet of a residential zoning district shall construct those indoor areas used for animal boarding an exercise in accordance with the soundproofing guidelines for dwelling units set forth in Section 1207.2 of the Michigan Building Code (2006).

- (3) A veterinary hospital or clinic shall be subject to the requirements, limitations, and regulations listed in Sec 14-132.

Sec. 122-810. Printing services.

Printing services shall be permitted subject to the conditions hereinafter imposed:

- (1) All principal use activities, including storage of equipment and chemicals, shall be conducted within a totally enclosed building.
- (2) No exterior windows shall be oriented towards single-family residential uses.
- (3) Such uses shall not create a nuisance to adjacent residences through excessive noises or the smell of chemicals.

Sec. 122-811. Supportive Housing.

Supportive Housing where listed in residential districts shall be permitted after Special Use review and approval, and shall be subject to the conditions hereinafter imposed:

- (1) Supportive Housing shall be located at least 750 feet from all existing supportive housing, measured in a radius from the outermost boundaries of the lot or parcel on which the use is proposed, as well as all of the following uses:
 - a. State licensed residential facility, not including all home-based facilities serving 6 or fewer individuals and Day Care Group Homes serving 12 or fewer individuals.
 - b. Nursing homes
 - c. Substance Abuse Treatment Facility
 - d. Homeless Shelter
 - e. Drop-in center
 - f. Correctional facility
- (2) Site Plan Review in accordance with Article IV shall be required.
- (3) A minimum lot area of 8,000 square feet shall be provided.
- (4) The maximum number of persons served per the facility shall not exceed 8.
- (5) On-site services shall be for residents of the facility only.
- (6) All new construction or additions to existing buildings shall be compatible with the scale and character of the surroundings, and exterior building materials shall be harmonious with other buildings in the neighborhood.
- (7) Screening in accordance with 122-703 shall be provided along all boundaries between the proposed use and property either zoned or used for single-family and two-family purposes.

Sec. 122-812. Auction House.

- (a) The applicant shall provide a use statement with the following information:
 - 1. The maximum capacity of the facility
 - 2. Number and frequency of the auctions
 - 3. Method for providing parking during auctions
- (b) Any outdoor activities are subject to the requirements for open-front or open-air businesses (section 122-798) and are only permitted in those districts that permit open-front businesses as a permitted or special use subject to the standards for those districts.

Sec. 122-813. Medical Marijuana Dispensaries

The intent of the Zoning Ordinance is to regulate medical marijuana dispensaries and growing/manufacturing facilities by providing for regulations and fees in a manner that promotes and protects the public health, safety and welfare, mitigates potential impacts on surrounding properties and persons, and that conforms with the policies and requirements of the Michigan Medical Marijuana Act, MCL 333.26421, et seq (hereinafter "Act"). Nothing in this Chapter, or in any companion regulatory provision adopted in any other provision of this Code, is intended to grant, nor shall they be construed as granting, immunity from criminal prosecution for growing, sale, consumption, use, distribution, or possession of marijuana not in strict compliance with the Act or the General Rules. Also, since Federal law is not affected by the Act or the General Rules, nothing in this Chapter, or in any companion regulatory provision adopted in any other provision of this Code, is intended to grant, nor shall they be construed as granting, immunity from criminal prosecution under Federal law. The Act does not protect users, caregivers or the owners of properties on which the medical use of marijuana is occurring from Federal Prosecution, or from having their property seized by Federal authorities under the Federal Control Substances Act.

The following Standards for Medical Marijuana Dispensaries

- (1) The medical use of marijuana shall comply at all times and in all circumstances with the Michigan Medical Marijuana Act and the General Rules of the Michigan Department of Community Health, as they may be amended from time to time;
- (2) The dispensary shall not be located within one thousand (1,000) feet of a school, as measured from the outermost boundaries of the lot or parcel on which the dispensary and school are located;
- (3) The dispensary shall not be located within a five hundred (500) feet of a lawfully existing medical marijuana dispensary or growing/manufacturing facility as measured from the outermost boundaries of the lot or parcel on which the proposed dispensary and lawfully existing dispensary or growing/manufacturing facility is located;

- (4) Smoking and/or use of medical marijuana shall be prohibited at the dispensary;
- (5) All activity related to the dispensary shall be done indoors;
- (6) The premises shall be open for inspection upon request by the Building Official the Fire Department and law enforcement officials for compliance with all applicable laws and rules, during the stated hours of operation/use and as such other times as anyone is present on the premises.
- (7) Quarterly inspections may be made by the City Official's designee to confirm the dispensary or growing/manufacturing facility is operating in accordance with applicable laws including, but not limited to, State Law and City Ordinances;
- (8) Any medical marijuana dispensary shall maintain a log book and/or database identifying by date the amount of medical marijuana on the premises for each qualifying patient/caregiver, keeping the qualifying patient and caregiver information confidential. This log shall be available to law enforcement personnel to confirm that the medical marijuana dispensary does not have more medical marijuana than authorized at the location and shall not be used to disclose more information than is reasonably necessary to verify the lawful amount of medical marijuana at the facility. The facility shall maintain the confidentiality of qualifying patients in compliance with the Michigan Medical Marijuana Act, as amended.
- (9) If the dispensary ceases operation for a length of time of sixty (60) days or greater, the permit shall expire;
- (10) Dispensary drive-through facilities shall be prohibited;
- (11) All medical marijuana shall be contained within the main building in an enclosed, locked facility in accordance with the Michigan Medical Marijuana Act, as amended;
- (12) Application for a Medical Marijuana Dispensary License shall be made to the City Clerk upon application forms provided by the Clerk for Medical Marijuana Dispensary and signed by the applicant verifying the truth and accuracy of all information and representations in the application. Applications including information and documentation provided pursuant to an application shall be subject to the confidentiality rules under the Act. In addition to information and submittals, the application shall include payment of application fee in an amount set by the City Council;
- (13) The police department shall review the proposed application to operate a dispensary regarding public health, safety, and welfare concerns of the proposal;
- (14) Growing or cultivation of medical marijuana in a dispensary is prohibited;

Sec. 122-814. Medical Marijuana Growing/Manufacturing Facility

The intent of the Zoning Ordinance is to regulate medical marijuana dispensaries and growing/manufacturing facilities by providing for regulations and fees in a manner that promotes and protects the public health, safety and welfare, mitigates potential impacts on surrounding properties and persons, and that conforms with the policies and requirements of the Michigan Medical Marijuana Act, MCL 333.26421, et seq (hereinafter "Act"). Nothing in this Chapter, or in any companion regulatory provision adopted in any other provision of this Code, is intended to grant, nor shall they be construed as granting, immunity from criminal prosecution for growing, sale, consumption, use, distribution, or possession of marijuana not in strict compliance with the Act or the General Rules,. Also, since Federal law is not affected by the Act or the General Rules, nothing in this Chapter, or in any companion regulatory provision adopted in any other provision of this Code, is intended to grant, nor shall they be construed as granting, immunity from criminal prosecution under Federal law. The Act does not protect users, caregivers or the owners of properties on which the medical use of marijuana is occurring from Federal Prosecution, or from having their property seized by Federal authorities under the Federal Control Substances Act.

A. The following Standards for Medical Marijuana Growing/Manufacturing Facilities Shall Apply:

- (1) The medical use of marijuana shall comply at all times and in all circumstances with the Michigan Medical Marijuana Act and the General Rules of the Michigan Department of Community Health, as they may be amended from time to time;
- (2) The growing/manufacturing facility site shall not be located within one thousand (1,000) feet of a school, as measured from the outermost boundaries of the lot or parcel on which the growing/manufacturing facility and school are located;
- (3) The growing/manufacturing facility site shall not be located within a five hundred (500) feet of a lawfully existing medical marijuana dispensary and/or lawfully existing growing/manufacturing facility as measured from the outermost boundaries of the lot or parcel on which the proposed growing/manufacturing facility and lawfully existing dispensary or growing/manufacturing facility is located;
- (4) Smoking and/or use of medical marijuana shall be prohibited at the growing/manufacturing facility;
- (5) All activity related to the growing/manufacturing facility shall be done indoors;
- (6) The premises shall be open for inspection upon request by the Building Official the Fire Department and law enforcement officials for compliance with all applicable laws and rules,

during the stated hours of operation/use and as such other times as anyone is present on the premises.

- (7) Quarterly inspections may be made by the City Official's designee to confirm the growing/manufacturing facility is operating in accordance with applicable laws including, but not limited to, State Law and City Ordinances;
- (8) Any medical marijuana growing/manufacturing facility shall maintain a log book and/or database identifying by date the amount of medical marijuana on the premises for each qualifying patient/caregiver, keeping the qualifying patient and caregiver information confidential. This log shall be available to law enforcement personnel to confirm that the medical marijuana dispensary or growing/manufacturing facility does not have more medical marijuana than authorized at the location and shall not be used to disclose more information than is reasonably necessary to verify the lawful amount of medical marijuana at the facility. The facility shall maintain the confidentiality of qualifying patients in compliance with the Michigan Medical Marijuana Act, as amended.
- (9) If the growing/manufacturing facility ceases operation for a length of time of sixty (60) days or greater, the permit shall expire;
- (10) Growing/manufacturing facility drive-through facilities shall be prohibited;
- (11) All medical marijuana shall be contained within the main building in an enclosed, locked facility in accordance with the Michigan Medical Marijuana Act, as amended;
- (12) All necessary building, electrical, plumbing and mechanical permits shall be obtained for any portion of the structure in which electrical wiring, lighting and/or watering devices that support the cultivation, growing or harvesting of marijuana are located;
- (13) That portion of the structure where the storage of any chemicals such as herbicides, pesticides, and fertilizers shall be subject to inspection and approval by the Ypsilanti Fire Department to insure compliance with the Michigan Fire Protection Code;
- (14) Application for a Medical Marijuana Growing/Manufacturing Facility License shall be made to the City Clerk upon application forms provided by the Clerk for Medical Marijuana Growing/Manufacturing Facility License and signed by the applicant verifying the truth and accuracy of all information and representations in the application. Applications including information and documentation provided pursuant to an application shall be subject to the confidentiality rules under the Act. In addition to information and submittals, the application

shall include payment of application fee in an amount set by the City Council;

- (15) The police department shall review the proposed application to operate a dispensary or growing/manufacturing facility regarding public health, safety, and welfare concerns of the proposal;
- (16) The dispensing of medical marijuana at the medical marijuana growing/manufacturing facility shall be prohibited.
- (17) There shall be no other accessory uses permitted within the same building.

Sec. 122-815. Gardens/Community Gardens

The goal of this standard is to clarify within existing districts that gardening is allowed as an accessory use and to allow for interim or long term low-intensity gardens and/or community gardens on vacant lots in R1, CN, CN-Mid, and CN-SF districts as long as the use provides minimal impacts to residential character, and minimal increase in traffic in and around related parcels.

Furthermore, the City of Ypsilanti is an urban environment, and while these provisions are intended to support the local food system, it is not the intent of these standards to create agricultural districts within the City. Additionally, if any gardening or related use invokes the State Right-to-Farm Act, then this section and related sections in this division are to become null and void.

- (1) All principal use gardens/community gardens in R1, CN, CN-Mid, and CN-SF districts must maintain a 3 foot setback on street frontages as

well as meet traffic visibility regulations detailed in Sec 122-649. Further, they shall not encroach onto adjacent parcels or sights-of-way.

- (2) Sale of goods grown in a garden/community garden is prohibited on garden sites in residential districts. Sales of goods from greenhouse in business or other districts are subject to underlying district requirements.
- (3) The property shall be maintained in an orderly and neat condition and shall not be detrimental to the physical environment or to public health and general welfare, and remains subject to compliance with the property maintenance code, noise ordinance, and related ordinances.
- (4) The property shall be maintained so as to prevent the free flow of storm water, irrigation water, chemicals, dirt, or mud across or onto adjacent lots, properties, public streets, or alleys.
- (5) Motorized equipment within a residential zoning district or residential planned unit development district shall be restricted to hours beginning at 8:00 a.m. and ending at 8:00 p.m.
- (6) Compost piles may only be used for waste generated on site, and are subject to setbacks.
- (7) Gardens shall utilize integrated pest management techniques and best practices in accordance with Chapter 110, Act II of this Ordinance.

Secs. 122-816--122-830. Reserved

ARTICLE XIII.

OFF-STREET PARKING AND LOADING REQUIREMENTS*

*Cross reference(s)--Traffic and vehicles, ch. 102.

Sec. 122-831. Description and purpose.

The purpose of this article is to recognize that motor vehicles, while part of the social and economic well-being of the community, can cause conditions and problems of parking and storage which can have a negative impact on the safety, appearance, health and welfare of the community. It is the intent of this article to provide standards for the parking and storage of motor vehicles in order to ensure that off-street parking facilities are in harmony with the use of surrounding properties and all modes of transportation; maintain barrier-free pedestrian access, ensure adequate accessibility to the off-street parking facilities from city street; and to set standards for design and construction of parking facilities compatible with the health, safety and general welfare of the community.

Sec. 122-832. Scope.

The conditions and requirements of this article applies to all zoning districts. In all zoning districts, off-street parking facilities shall be provided for the storage and parking of motor vehicles and bicycles for the use of occupants, employees, and patrons of all buildings, structures, residences, businesses, or establishments erected, altered, constructed, changed in use, or commenced after the effective date of the ordinance from which this chapter derives. Such space (or spaces) shall be maintained and not be encroached upon, unless an equivalent number of such spaces are provided elsewhere, in conformance with this chapter.

- (1) *New or altered buildings.* No building or structure shall hereafter be erected, and no existing structure may be so altered that it is increased in size or intensity of use, unless adequate parking space, as required by the provisions of this article, is provided for the entire building or structure as erected or altered.
- (2) *Change in use.* The use of any building or structure shall not be changed if additional parking space would be required as a result of the change in use, unless the minimum parking space as required by the provisions of this article is provided for the entire building.
- (3) *Areas excepted.* The provisions of this article shall not apply to uses and structures in the C zoning district, except those spaces required for upper-story dwellings. A fee in lieu of providing off-street parking for upper-story units in the C zoning district is permitted in accordance with section 122-843.

Sec. 122-833. General requirements.

Any person, organization, or establishment who has any ownership interest in or the control of any real estate within the city is required to provide and maintain in a usable condition off-street parking spaces as follows:

- (1) *Off-street parking for one- and two-family dwellings.* Off-street parking facilities required for one- and two-family dwellings shall consist of a parking strip, apron, driveway, garage, carport, or combination thereof and shall be located on the premises they are intended to serve subject to the provisions of section 122-667. Further, parking areas serving one- and two-family dwellings shall be subject to the following:
 - a. *Driveways.* On lots used for one-family or two-family residential purposes, maneuvering or backing of vehicles into a street or alley is permitted. Driveways may cross the required front yard, or the required street side yard on a corner lot, provided that the total area of the driveway do not exceed 30 percent of the area of such required yard.
 - b. *Ingress and egress.* No individual curb cut to a street or alley for a single driveway shall exceed 20 feet in width. The total width of all curb cuts shall not exceed 35 feet on all property lines. On lots with a lot width of 60 feet or less, no more than one curb cut to a single street is permitted. All curb cuts accessing Washtenaw Avenue (M-17) must comply with the Michigan Department of Transportation M-17 Access Management Plan.
 - c. *Surfacing.* Parking areas and driveways shall be surfaced with crushed limestone or similar gravel material, or shall be hard surfaced with asphalt, concrete, or similar bonded material. Porous paving is also allowed. However, parking areas which are designed for five or more spaces must meet the requirements of subsection 122-835(5). That portion of the driveway between the lot line and the public way, shall be paved with concrete a minimum of six inches thick for residential occupancies and eight inches thick for commercial occupancies. Curb cuts along state trunk lines shall comply with the requirements of the state department of transportation. All other curb cuts shall comply with adopted standards of the Department of Public Works.
 - d. *Parking in yards.* No parking shall be permitted in the required front yard, or in the required street side yard on a corner lot, except on a driveway which leads to a parking area that is beyond the front line of the structure and the space is in compliance with section 122-834.
- (2) *Off-street parking for multiple-family and nonresidential uses.* Off-street parking facilities required for multiple-family and nonresidential uses shall be located on the same lot or parcel as the

building or use they are intended to serve, or within 300 feet of such building or use, measured from the nearest point of the building to the nearest point of the off-street parking lot. A shared parking agreement or use easement for the land intended for shared parking must be on file with the county register of deeds, in order for the shared parking spaces to satisfy requirement parking.

- (3) *Setback from street.* Parking lot setbacks are required by the setbacks and building types of the zoning district in which they are located. An allowed exception are circular drives, which may be located in a required minimum front yard or street side yard, provided that such drives shall be designed so that no parking space is located closer than 25 feet to any street right-of-way line.
- (4) *Designated parking areas.* Any area once designated as required off-street parking may not be changed to any other use, unless or until equal facilities are provided elsewhere.
- (5) *Collective off-street parking.* Two or more buildings or uses, or mixed uses in the same building, may collectively provide the required off-street parking.
- (6) *Nonoverlapping operating hours.* In the instance of land uses requiring off-street parking spaces where operating hours of the uses do not overlap, the City Planner may grant exception to the individual parking requirements of section 122-836.
- (7) *Use of parking lots for storage.*
 - a. Except as provided under subsection (7)b of this section, a parking lot may not be used for the storage or parking of trailers, mobile homes, travel trailers, boats, boat trailers, or junked or wrecked vehicles of any type; for the storage of merchandise or industrial equipment or materials; or as a dump for refuse of any description.
 - b. The parking out-of-doors of motor vehicles which are used as part of a permitted commercial or industrial use, including automobiles, trucks, or trailers, are permitted on off-street parking lots outside normal business hours of such commercial or industrial use; provided no more than a total of five automobiles and three commercial trucks or trailers each weighing less than 10,000 pounds shall be permitted. The outdoor storage of more than five automobiles and three trucks or trailers shall be permitted only after special use approval by the Planning Commission in accordance to the provisions of Article V of this chapter.

- (8) *Repair prohibited.* No repairs or service to vehicles shall be permitted on areas designated as required off-street parking.
- (9) *Display of vehicles for sale.* The parking of motor vehicles, recreational vehicles, and trailers which are possessed expressly and solely for sale by persons or businesses licensed by the state for such sales are permitted only when in accordance with the requirements of each respective zoning district and the specific provisions of section 122-798 regarding the outdoor sales of vehicles. Otherwise, the display of vehicles for sale in designated off-street parking areas is prohibited.
- (10) *Use of loading space.* Loading spaces, as required under section 122-841, shall not be counted or used for required parking.
- (11) *Usable floor area and gross floor area.* For the purpose of computing the number of parking spaces required, the definitions for "usable floor area" and "gross floor area" in section 122-3 shall apply.
- (12) *Fractional requirements.* When units or measurements determining number of required parking spaces result in requirement of a fractional space, any fraction up to one-half shall be disregarded and fractions including and over one-half shall require one parking space.
- (13) *Uses not specified.* For those uses not specifically mentioned under section 122-836, the requirements for off-street parking facilities shall be in accord with a use which the City Planner considers similar in type.

Sec. 122-834. Parking dimensions.

All off-street parking facilities required by this chapter shall be of adequate size and design to provide safe and reasonably direct ingress and egress from an alley or street. All parking spaces shall be adequate for parking a motor vehicle with room for opening doors on both sides.

- (1) Parking spaces required by this article shall be at least 9 feet wide and 18 feet long (16 feet long if 2 feet of overhang is provided when parking against a curb). Spaces directly adjacent to a fence, wall or enclosure shall be increased by 1 foot in width. Barrier free parking spaces must be designated as required by and in conformity with state law.
- (2) Up to 20% of the parking spaces may be designated as small car spaces, which shall be at least 8 feet wide and 16 feet long and clearly signed for "compact cars."
- (3) Up to 10% of the parking spaces may be designated as motorcycle spaces, which shall be at least 5 feet wide and clearly signed for "motorcycles."

- (4) Minimum Standards. The minimum standards for parking spaces and aisles are indicated in the table below (refer to parking layout diagram):

Standard Vehicle Parking Dimensions:

Parking Patterns (Degrees)	Parking Space Width (Feet)	Parking Space Length (Feet)	Maneuvering Lane Width (Feet)	Total Width of One Tier of Spaces Plus Maneuvering Lane (Feet)	Total Width of Two Tiers of Spaces Plus Maneuvering Lane (Feet)
0 (parallel)	9	22	12	20 one-way 32 two-way	28 one-way 40 two-way
30 to 53	9	18	13	36	53
54 to 74	9	18	16	38	59
75 to 90	9	18	22	42	62

Compact Vehicle Parking Dimensions

Parking Patterns (Degrees)	Parking Space Width (Feet)	Parking Space Length (Feet)	Maneuvering Lane Width (Feet)	Total Width of One Tier of Spaces Plus Maneuvering Lane (Feet)	Total Width of Two Tiers of Spaces Plus Maneuvering Lane (Feet)
0 (parallel)	8	18	12	20 one-way 32 two-way	28 one-way 40 two-way
30 to 53	8	17	13	36	53
54 to 74	8	17' 5"	16	38	59
75 to 90	8	16	22	42	62

Motorcycle Vehicle Parking Dimensions

All motorcycle parking spaces shall be a minimum of five feet by eight feet.

Sec. 122-835. Parking layout and construction.

Off-street parking facilities shall be designed, constructed, and maintained in accordance with the following requirements.

- (1) *Review and approval requirements.* Except for off-street parking accessory to single-or two-family dwelling units, review and approval is required for off-street parking areas in accordance with Article IV of this chapter.
 - a. Plans for parking lots shall be drawn at scale, showing existing and proposed grades, drainage, sewers, type of surfacing, proposed parking layout, striping, signage, and related landscaping or screening.
 - b. Upon completion of construction, a parking lot must be inspected and approved before a certificate of occupancy can be issued for the parking lot or for the building or use for which the parking is intended to serve.

- c. In the event that required parking cannot be constructed because of cold or inclement weather, a temporary certificate of occupancy may be issued by the building department, provided the applicant first deposits a performance guarantee with the city in accordance with section 122-134.
- (2) *Access.* All parking spaces shall be provided adequate access by pedestrians and vehicles:
 - a. *Walkways in Parking Lots.* Paved walkways a minimum of 5 feet in width shall be provided for access to adjacent parks, commercial areas, transit stops, anticipated walkways and institutions. Pedestrian movement shall be accommodated within parking lots through raised walkways, marked crosswalks or similar methods.
 - b. *Vehicular Access.* All parking spaces must be accessible to vehicles by means of maneuvering aisles. Except for one-and two-family uses, maneuvering or backing from a parking space

directly onto a street or walkway shall be prohibited, and all parking spaces shall be designed so that any motor vehicle may be parked or unparked without moving another vehicle.

- (3) *Ingress and egress.* For parking lots containing five or more spaces, adequate ingress and egress to such parking lot shall be provided by means of clearly defined and limited drives having a minimum width of 20 feet, with a maximum of 30 feet. All such drives shall be located so as to minimize traffic congestion. All curb cuts and approaches to such parking lots shall comply with adopted city standards for curb cuts. Ingress and egress for the parking area in an area zoned CN-Mid, CN, HC, NC, GC, C, HHS, PMD shall not cross land zoned for P, R1 or CN-SF. Parking lot driveways shall be situated so as to minimize vehicle headlights from shining on residential dwellings. Where possible, curb cuts shall be located across from any existing curb cuts on the opposite side of the street, or shall be offset from any opposite-side curb cuts by at least 25 feet. No curb cut for a parking lot may be closer than 50 feet to the intersection of any two streets as measured along the street right-of-way line. However, the Planning Commission may allow a curb cut for a parking lot situated on a small land parcel located no closer than 20 feet to the intersection of any two streets, upon finding no other access points in compliance with City Ordinances is possible due to the size of the parcel.
- (4) *Internal maneuvering drives.* Each driveway providing access to an off-street parking lot containing five or more parking spaces shall be a minimum of ten feet in width. Where a turning radius is necessary, it shall be an arc that allows unobstructed vehicle flow.
- (5) *Surfacing.* All parking and loading facilities and access drives shall be paved with a durable bonded material in accordance with accepted engineering standards. Alternative surfacing materials may be considered in order to minimize impervious surface and stormwater runoff, employ environmental and other best practices, and achieve low impact design. Use of pervious alternative surfaces is encouraged in proximity to the Huron River. Paving materials proposed to improve aesthetics may also be considered by the City Planner and the Planning Commission. Alternative surfaces proposed shall be reviewed by the City's consulting engineer. Consideration of alternative surfacing in accordance with best management practices will be given by the Planning Commission for off-street parking lots of five to ten parking spaces serving residential uses. In R-1, CN-SF, CN-Mid, and CN, paving shall not be required for off-street parking areas of four spaces or less, in which case the spaces shall be surfaced with gravel or similar material and so laid out as to clearly indicate that the spaces are reserved for parking of motor vehicles.
- (6) *Drainage.* All off-street parking and loading areas shall be graded and drained to public storm sewers. As an alternative, if in the opinion of the City's consulting engineer, the soils are of a type which will allow for efficient drainage, the use of drywells, infiltration trenches, swales, bio-retention or other best management practices for controlling urban runoff quality are permitted. No surface water shall be permitted to drain onto adjoining properties, unless there is a common engineered drainage system shared with the adjoining property or an appropriate watershed easement has been obtained. No surface water drainage from an off-street parking lot shall be permitted to drain across a public sidewalk.
- (7) *Striping.* For parking lots containing five or more spaces, all spaces shall be outlined with three-inch wide strips of white or yellow paint, except that barrier-free spaces shall be blue, with a symbol of compliance in blue. An exception to this requirement are parking lots which are surfaced with gravel for historic preservation purposes in accordance with Article VIII, division 2, of this chapter.
- (8) *Wheel stops.* For parking lots containing five or more spaces, wheel stops or curbing shall be provided for all parking spaces to prevent any vehicle from projecting beyond the parking lot area, bumping any wall or fence, or encroaching upon any landscaping. In all cases where parking lots abut public or private sidewalks, continuous concrete curbing or bumper stops, at least six inches high, shall be placed so that a motor vehicle cannot be driven or parked on, or hang over, any part of any sidewalk.
- (9) *Lighting.* With the exception of facilities for one- and two-family dwellings and for multiple-family dwellings on individual lots containing no more than four units, parking and loading facilities utilized during night-time hours shall be artificially illuminated. All such outdoor lighting shall meet the requirements of section 122-641.
- (10) *Signs.* Accessory directional signs shall be permitted in parking areas in accordance to Article XIV of this chapter
- (11) *Screening and landscaping.*
 - a. Intent. Separate landscape areas shall be provided within parking lots so as to break up the broad expanse of pavement, mitigate heat island effect, support storm water management, and guide the circulation of vehicular and pedestrian traffic.
 - b. Required landscaping within off-street parking areas. Separate landscape areas shall be provided within off-street parking areas in accordance with the following requirements:
 1. There shall be a minimum of one (1) tree for every eight (8) parking spaces, provided that

- a landscape island shall be provided for no more than sixteen (16) continuous spaces.
2. Landscape islands must meet the following size requirements:
 - (a) Landscape islands containing a tree shall be a minimum of 160 square feet and a minimum of nine (9) feet wide.
 - (b) Landscape islands containing a pedestrian pathway shall be a minimum of eleven (11) feet wide, with a pathway of a minimum width of five (5) feet and minimum three (3) feet wide landscape area on both sides.
 - (c) If landscaped islands are not used for storm water infiltration, the islands must be raised and curbed.
 3. The ends of all parking isles and corners shall be protected with a curbed island.
 4. A minimum distance of three (3) feet from the backside of the curb and the proposed landscape plantings shall be provided. Where vehicles overhang a landscape island or strip, a minimum distance of five (5) feet from the backside of the curb and the proposed landscape plantings shall be provided.
 5. Shrubs and/or ground covers which will not impede vehicular visibility in accordance with this Ordinance may also be included.
- c. Required Landscaping at the Perimeter of Off-Street Parking Areas. Separate landscape areas shall be provided at the perimeter of off-street parking areas in accordance with the following requirements:
1. Off-street parking areas in the side and rear yard which abut a R-1, MD, CN, CN-Mid, CN-SF zoning district must be screened in accordance with Section 122-703. Landscaped berms may also be used in lieu of the screening, if approved by the Planning Commission.
 2. All off-street parking areas shall be screened from view with a solid wall or landscape planting achieving at least 80% opacity year-round at least three (3) feet in height but no more than four (4) feet in height along the perimeter of those sides which are visible from a public road. The Planning Commission, at their discretion, may approve landscape berm or vegetated swale.
 3. All land between a parking lot and any street right-of-way shall be kept free from refuse and debris and must be landscaped. The ground area shall be planted in lawn or other live ground covering. All such landscaping and plantings shall be maintained in a healthy, growing condition, neat and orderly in appearance.
 - d. Landscaped areas, walls, structures, and walks shall be properly protected from vehicular encroachment or overhang through appropriate wheel stops or curbs.
- (12) *Maintenance.* All off-street parking areas, including striping, shall be maintained in good usable condition, and when necessary shall be treated to prevent dust or other nuisances. Such parking areas and drives shall also be kept free of litter, debris, and refuse.
- (13) *Additional requirements.* In addition to the above requirements, parking areas shall comply with additional requirements or conditions which may be deemed as reasonably necessary by the Planning Commission for the protection of abutting lots.

Sec. 122-836. Minimum and maximum number of parking spaces.

- (1) *Minimum.* The minimum number of off-street parking spaces by type of use in all zoning district shall be determined in accordance with the following schedule.

USE	SPACES PER UNIT OF MEASURE
RESIDENTIAL:	
Single-family detached dwellings and two-family dwellings	1 space per unit Garage and driveways may meet this requirement.
Multiple-family dwellings, including townhouses	1.5 for each dwelling unit, plus 1 for each 10 dwelling units for guest parking.
Upper-story residential units in C, HC, NC, GC, and HHS districts	1 for each dwelling unit.
Group living with support staff, not licensed by State of Michigan	1 for each 3 beds, plus 1 per employee on an average employment shift.
Group residence & roominghouse	1 for each bedroom or sleeping room, plus 1 for each employee or the largest employment shift.
Adult Foster Care	1 for each 3 beds, plus 1 for each employee an average employment shift.
Accessory Dwelling Unit	1 for each dwelling unit Garage and driveways may meet this requirement.
Family Child Care Home	Minimum of 1 and a maximum of 3 child-care drop off spaces, plus 1 for the principal dwelling unit.
RECREATION, EDUCATION & PUBLIC ASSEMBLY USES	
Religious institutions	1 for each 5 seats or 10 feet of linear pew space, based on the maximum seating capacity in the main unit of worship
Hospitals	1 for each 4 patient beds, plus 1 for every 200 square feet of out-patient service area
Primary Schools (public and private)	1 for each teacher, employee or administrator, plus 1 for each 10 students.
Secondary Schools (public and private)	1 for each teacher, employee or administrator and 1 for each 10 students, in addition to the requirements for the auditorium and stadium, if provided.
Post-secondary educational institutions (public & private)	1 for each teacher, employee or administrator and 1 for each 5 students.
Private assembly	1 for each 3 persons allowed within the maximum occupancy load as established by local, county, or state fire, building, or health codes, whichever is greater.
Arts & crafts studios	1 per 1,000 square feet plus 1 per classroom.
Performance venues/Theaters	1 for each 5 seats or 10 linear feet of bench space, plus 1 for each 2 employees on an average employment shift.
Libraries, museums, cultural centers, community centers or similar facilities	1 for each 400 square feet of usable floor area, excluding area devoted to storage including stacks.
Municipal, county, regional & state service uses	1 for each 1,000 square feet of usable floor area.
Child care centers	1 off-street parking space per caregiver required to staff facility at the state-licensed capacity, plus 1 space for every 20 children the facility is licensed to care for.
Outdoor recreation and fields	1 for each 1,000 square feet of recreation space.
Indoor recreation	1 for each 3 persons who may be legally admitted at one time based on the occupancy load established by local, county, or state fire, building, or health codes, plus 1 for each employee on an average employment shift.
Stadiums, sports arenas, or similar places of outdoor assembly	1 for each 4 seats or 8 feet of linear bench space.
Swimming pools	1 for each 4 persons who may be legally admitted at one time based on occupancy load established by local codes.

USE		SPACES PER UNIT OF MEASURE
INFRASTRUCTURE		
Radio & Television Studios or Stations		1 per each 500 square feet of gross floor area.
Utility buildings		1 for each employee on an average employment shift.
Energy, electricity and heat generation or sewage plants		1 for each employee on an average employment shift.
SERVICES		
Bed & Breakfasts or Inns		1 per occupancy unit plus 1 per employee on an average employment shift.
Motels, hotels or other commercial lodging establishments		1 per occupancy unit plus 1 per employee on an average employment shift; plus extra spaces for dining rooms, ballrooms, or meeting rooms as required.
Business or professional offices		1 per 300 square feet of usable floor area.
Funeral homes		1 per 50 square feet of assembly room, parlor and slumber room.
Laundromats		1 per 3 washing machines.
Financial service, including banks		1 per 300 square feet of usable floor area, plus 2 stacking spaces for each drive-in or drive-through transaction station.
Nursing Homes		1 per 3 beds.
Medical or dental offices or clinics, substance abuse treatment facilities		1 for each 300 square feet of usable floor area in waiting rooms, plus 1 for each examining room, dental chair, or similar use area.
Personal service establishments		2 spaces for each of the first 2 beauty or barber chairs, and 1½ spaces for each additional chair, or 1 for each 300 square feet of useable floor area whichever is greater.
Self-storage facilities		1 per 200 storage units, plus 1 per 300 square feet of usable floor area of office space, plus 1 for residence, if provided.
Catering service		1 per 600 square feet of usable floor area.
All other service uses not elsewhere specified		1 for each 300 square feet of gross floor area.
COMMERCIAL		
Furniture and appliances, household equipment; repair shops; showrooms of a plumber, decorator, electrician or similar trade; and other similar uses		1 for each 600 square feet of usable floor area.
Open air businesses		1 for each 600 square feet of lot area used for open air business, plus extra spaces for indoor sales or office space as required.
Shopping centers or clustered commercial centers over 100,000 square feet in gross floor area		1 for each 300 square feet of gross floor area.
All other retail uses not elsewhere specified		1 for each 250 square feet of gross floor area.
RESTAURANTS		
Café, coffee shop, restaurants, tasting rooms or bar/lounge, and other establishments where food, beverages, or refreshments are sold primarily for consumption on the premises		1 for each 100 square feet of usable floor area, or 1 for each 3 persons allowed within the maximum occupancy load as established by local, county, or state fire, building or health codes; whichever is greater.
Restaurant, fast food, drive-in or drive-through		1 for each 50 square feet of customer waiting and eating areas, plus 1 for each employee in the largest employment shift, plus 8 stacking spaces for each drive-in or drive-through transaction station.
AUTO-ORIENTED		
Automobile filling stations		1 for each employee, plus spaces required for other uses within the station, such as the retail floor area, carryout restaurants, subtracted by one half space for each automobile fueling position.
Automobile repair		1 for each employee in the largest employment shift, plus 1 space for each auto service stall. In addition, stacking spaces for automobiles awaiting entrance to a service stall shall be provided as required by section 122-840.
Automobile or truck wash (automatic and self-serve) and detailing		1 for each employee in the largest employment shift. In addition, stacking spaces for automobiles awaiting entrance to the wash facility must be provided as required by section 122-840.
Motor vehicle sales and service establishments, trailer sales and rental, and boat showrooms		1 for each 500 square feet of usable floor space of sales room, plus 1 for every 500 square feet of outdoor sales area, plus 1 for each 1
Automobile rental (parking, storage, wash & repair)		auto service stall in service areas, plus 1 space per employee on the largest employment shift.

USE	SPACES PER UNIT OF MEASURE
Vehicle, Recreational Vehicle, Storage and Towing	1 for 300 square feet of office space, plus 1 space per employee on the largest employment shift.
RESEARCH	
Laboratories or research establishments	5 plus 1 for every 1.5 employees in the largest working shift; or 1 space per each 1,000 square feet of gross floor area for storage areas, and 1 space per 300 square feet of office area; whichever is greater.
PRODUCTION, MANUFACTURING & DISTRIBUTION	
Craft production	1 per 1,000 square feet
Wholesale or distribution facility	5 plus 1 for every employee in the largest working shift; or 1 for every 1,700 square feet of gross floor area, plus 1 for each 300 square feet of office area. Spaces shall also be provided for any retail or service area in addition to the above.
Assembly, processing or manufacturing	5 plus 1 for every 1½ employees in the largest working shift; or 1 space per each 1,000 square feet of gross floor area for assembly, processing and manufacturing and storage areas, and 1 space per 300 square feet of office area.
URBAN AGRICULTURE	
Community garden	None
Hydroponics, aquaculture and aquaponics and similar raising of food	5 plus 1 for every employee in the largest working shift; or 1 for every 1,700 square feet of gross floor area, plus 1 for each 300 square feet of office area. Spaces shall also be provided for any retail or service area shall be in addition to the above

- (2) *Maximum.* The number of off-street parking spaces must not exceed one hundred and twenty percent of the required parking spaces. The Planning Commission may grant an exception based on a special circumstance that particularly relates to the size of an existing parcel and building in combination, and/or character of the proposed use.

Sec. 122-837. Reductions in Parking Requirements

Off-street parking requirements may be reduced based the following regulations:

- (a) *Transit.* Parking requirements may be reduced by up to 20 percent for buildings, structures or uses, within three hundred (300) feet of a commuter rail station or bus transit center or within one hundred (100) feet of a transit stop. A traffic study may be required to demonstrate that a sufficient number of vehicle drivers would immediately opt for transit, and therefore would not result in adverse parking impacts on surrounding properties. The Ride shall verify that the transit station or transit stop is in a is not scheduled to move in the 5-year plan for the Ride.
- (b) *Alternative Vehicles.* Parking spaces reserved, signed, and enforced for car-sharing services, may count as four (4) regular parking spaces. Electric car spaces shall include a power outlet for use by the parked car. Such spaces should be closest to the main entrance (exclusive of barrier-free spaces). Parking spaces reserved, signed, and enforced for carpooling or vanpooling services may count as two (2) regular parking spaces.
- (c) *Bicycle.* Parking requirements may be reduced by one (1) space for every four (4) covered, secure bicycle parking spaces are provided on site. Parking requirements may be further reduced by four (4)

spaces where free showers are available for employee use within the building.

- (d) *Planning Commission Authority.* The Planning Commission shall have the authority to reduce the number of required off-street parking spaces, inclusive of the reductions above, by up to 20% of those required. Such an action must be based on a special circumstance that particularly relates to the size of an existing parcel and building in combination, and/or character of the proposed use.

Sec. 122-838. Required Bicycle Parking

Any development requiring vehicle parking spaces shall be required to provide bicycle parking. Off-street parking areas shall contain at least one (1) bicycle parking space for every five (5) spaces provided for motor vehicles, or fraction thereof, with a minimum of two (2) bicycle parking spaces provided. Bicycle facilities provided in the public right-of-way may be used in parking calculations.

Sec. 122-839. Barrier-free parking spaces.

Off-street parking facilities as required under this chapter shall include parking spaces which are reserved for physically handicapped persons in accordance with the state barrier free design requirement of the state building code.

Sec. 122-840. Off-street stacking spaces for drive-through facilities.

(a) *Drive-in or drive-through windows.* On the same premises with every building, structure, or part thereof, erected or occupied for the purpose of serving customers in their automobiles by means of a service window or similar arrangement, such as drive-in banks, restaurants, or cleaning establishments, there shall be provided four off-street stacking spaces for each service window or transaction station in compliance with subsection (c) of this section. Eight off-street stacking spaces shall be provided for each drive-through transaction station of a restaurant.

(b) *Automobile servicing.* Self-service automobile and car wash establishments shall provide three off-street stacking spaces for each washing stall. Quick oil change facilities shall provide three off-street stacking spaces per each oil change service bay. Automobile and car wash establishments, other than self-service, shall provide stacking spaces equal in number to four times the maximum capacity of the motor vehicle wash for automobiles awaiting entrance. The term "maximum capacity" shall mean the greatest number of possible automobiles undergoing some phase of washing at the same time.

(c) *Stacking space dimensions.* Each stacking space shall be a minimum dimension of ten feet in width and 20 feet in length.

Sec. 122-841. Off-street loading space requirements.

With the exception of uses located within the C Center district, there shall be provided and maintained on the same premises with every building, structure, or part thereof involving the receipt or distribution of vehicles or materials or merchandise, including but not limited to retail stores, wholesale stores, markets, hotels, hospitals, offices, and laundries, adequate space for standing, loading, and unloading in order to avoid undue interference with public use of dedicated rights-of-way and vehicular circulation on the site.

- (1) Such off-street loading spaces shall be provided as specified in the table below. The Planning Commission may modify these requirements upon making the determination that another standard would be more appropriate because of the number or type of deliveries experienced by a particular business or use.

	Gross Floor Area (In Square Feet)	Loading and Unloading Spaces	
		10' X 25' Space	10' X 50' Space
Office	0--99,999	--	--
	100,000--149,000	--	1
	150,000 and over	--	2
Commercial/Industrial/ Institutional	0--1,999	--	--
	2,000--4,999	1	--
	5,000--19,999	--	1
	20,000--49,999	--	2
	50,000--79,999	--	3
	80,000--99,999	--	4
	100,000--149,999	--	5
	150,000 and over	--	5*

**One additional space for each 50,000 square feet of floor area in excess of 150,000 square feet.*

- (2) All loading spaces shall be located within a nonrequired rear yard, or a nonrequired side yard which does not abut or lie across a street from a residential zoning district; but in no case shall loading spaces be permitted in a front yard. All minimum side and rear yard setback requirements shall be met.
- (3) No loading space shall be located closer than 50 feet to any R1, MD, CN-SF, CN-Mid, CN or HHS district, unless located within a completely enclosed building or enclosed on all sides facing the district by a solid concrete or masonry wall not less than six feet in height.
- (4) Loading space areas shall be provided with a paved surface having an asphaltic or Portland cement binder so as to provide a permanent, durable and dustless surface. All loading spaces shall have a minimum 14-foot high clearance.
- (5) Loading areas shall not utilize any area required for the maneuvering of vehicles into parking spaces or block general vehicular circulation on a site.

Sec. 122-842. Special assessment districts.

When a property is located within a special assessment district created for the purpose of constructing a municipal parking lot or structure, and an assessment has been levied against the entire building site, the owner of such property may petition the Planning Commission for approval of substituting such public parking for all or a portion of the required off-street parking spaces. The Planning Commission shall determine that the petitioner's property is adequately served by the public parking facility in such a way that the objectives and intent of this article shall be secured. To accomplish this end, the Planning Commission shall have the power to require such conditions as deemed appropriate. The Planning Commission shall consider the assessment of benefits in the special assessment district in determining the adequacy of service by the public facility.

Sec. 122-843. Fee in lieu of providing off-street parking.

- (a) *Intent.* The intent of the fee in lieu of providing off-street parking is to encourage the development of apartment units above ground floor commercial uses, in existing buildings, in the C-Center District. It is recognized that many structures in these business districts were constructed at zero lot lines. Often the structure covers the lot completely. Therefore parking on the lot or contiguous to the lot cannot be provided. For those building owners who cannot provide parking, pursuant to this chapter and whose upper floor space has not been legally occupied within one year of their application for payment of such a fee in lieu of parking, they shall be charged a fee according to the number of bedrooms in the residential units. Upon payment of this fee, the owner or applicant will be permitted to develop or rehabilitate these residential units without providing the parking required by this chapter. The fee will be held by the city for parking capital improvements, which will be used to provide increased parking and transportation infrastructure such as transit stops, bicycle facilities and pedestrian pathways for the areas where these buildings are located.
- (b) *Condition for allowing payment of fee in lieu of providing off-street parking.* Property owners who meet all of the following requirements shall be entitled to apply for payment of fee in lieu of providing off-street parking:
- (1) They are the owner, or have permission of the owner, of a building which can provide residential units above ground floor commercial uses.

- (2) The building is located in a C-Center District within the city.
- (3) The property, by virtue of its construction, cannot meet parking requirements in the district.
- (4) The residential unit or units have not been legally occupied within one year prior to making application.

(c) *Application.*

- (1) An application for permission to use such payment in lieu of providing off-street parking shall be made as part of an application to the City Planner.
- (2) The permit shall contain the following information:
 - a. Name, address and phone number of property owner and name, address and phone number of applicant, if different than owner.
 - b. Address of property requiring fee in lieu of providing off-street parking.
 - c. Plan showing the layout of the proposed residential units, including size of rooms and identification of bedroom space.
 - d. Description of commercial use on ground floor level.
 - e. A site plan which shall include:
 1. Dimensions and size of parcel.
 2. Location of structure on parcel.
 3. If any parking is available on the site, its location must be indicated, including access, stall size, etc.
 4. Surrounding land use and zoning.
 5. Description of location of parking to be used by tenants.
- (3) Application fee. An application fee shall be paid at the time of submitting the application to the city planner.


(d) *Approval procedures.*

- (1) The City Planner shall consider the following in making his/her determination:
 - a. Whether the owner can provide on-site parking that meets ordinance standards.
 - b. Whether the owner can modify available parking space, or loading space, located on-site to meet ordinance standards.


- (2) If the City Planner determines that the owner cannot provide on-site parking to meet ordinance standards, or can only provide partial on-site parking to meet ordinance standards, and the other requirements of this article are met, then he/she shall make a specific finding regarding the number of spaces which are required for the residential units, which shall allow the City Treasurer to compute the amount of fee in lieu of parking.
- (e) *Condition.* The off-street parking requirement satisfied by fee in lieu of parking shall run with the land. If any subsequent change in use should occur, which requires additional parking, then the owner shall make a new application to the city pursuant to this chapter for such additional parking. An additional application fee shall be paid when such application is submitted. An additional fee shall be due prior to the issuance of a building permit to allow the additional modifications.
- (f) *Penalty for violation.* Violation of this section shall be deemed a misdemeanor which is punishable by a maximum of 90 days in jail and/or a fine of \$500.00, in the discretion of the court.

Off-Street Parking and Loading Requirements


75 to 90
degree




54 to 74
degree



30 to 53
degree



parallel



parking layout

ARTICLE XIV. SIGNS*

*Cross reference(s)--Businesses, ch. 22.

Sec. 122-861. Purpose.

The purpose of this article shall be to permit such signs as will not, by reason of their size, location, construction or manner of display, endanger life or limb, confuse or mislead traffic, obstruct vision necessary for traffic safety or otherwise endanger the public morals, health or safety.

It is further the intent of this article to:

- (a) Maintain and enhance the aesthetic value of the City.
- (b) Encourage free expression of ideas and dissemination of messages, regardless of content, using signs that are compatible with their surroundings and legible under the circumstances in which they are seen.
- (c) Enhance pedestrian and vehicular traffic safety.
- (d) Minimize the adverse effects of signs on nearby public and private property.
- (e) Minimize driver distraction.
- (f) Protect and enhance economic vitality by assuring aesthetic appeal for residents and visitors.
- (g) Preserve property values.
- (h) Enhance the effectiveness of permitted signs and directional and warning signs.
- (i) Seek the removal of illegal signs and encourage the replacement or removal of nonconforming signs that are incompatible with the purpose of this article.

Sec. 122-862. General Requirements.

- (a) *Building Permit Required.* Except as provided in this, Article XIV, no sign shall be constructed or erected prior to the issuance of a permit by the building department, and approval from other applicable reviewing bodies.
- (b) *Historic District Approval.* Signs to be located in the Historic District need approval by the Historic District Commission, excluding temporary signs.
- (c) *Accessory to Principal Use.* All signs shall be accessory to the primary use of the lot where the sign is located and shall comply with the applicable design standards set forth herein, with the exception of any sign specifically permitted by Section 122-866(d)(2).
- (d) *Public Rights-of-Way.* Signs shall be expressly prohibited from locating in all public rights-of-way and dedicated public easements except as otherwise provided for in this ordinance, and as follows:
 - (1) Signs erected by the City or other governmental entities for public purposes are permitted.
 - (2) Building mounted signs may project over a public right-of-way or easement provided they comply with the applicable design standards for the specific type of sign and that they maintain a minimum clearance of eight feet.
 - (3) Overhead banners
 - (4) Sidewalk signs
- (e) *Construction requirements.*
 - (1) All signs shall conform to the city building code unless more stringent requirements are specified in this article. Signs and sign structures shall be designed and constructed to resist wind and seismic forces as specified in this section. All bracing systems shall be designed and constructed to transfer lateral forces to the foundation. For signs on building the dead and lateral loads shall be transmitted through the structural frame of the building to the ground in such a manner as not to overstress any of the elements thereof.
 - (2) The overturning movement produced from lateral forces shall in no case exceed two-thirds of the deadload resisting movement. Uplift due to overturning shall be adequately resisted by proper anchorage to the ground or the structural frame of the building. The weight of earth imposed over footings may be used in

determining the dead-load resisting movement. Such earth shall be carefully placed and thoroughly compacted.

- (3) *Wind loads.* For the purpose of design, wind pressure shall be taken upon the gross area of the vertical projection of all signs and sign structures at not less than 20 pounds per square foot for those portions less than 60 feet above the ground.
- (4) *Allowable stresses.* The design of wood, concrete or steel members shall conform to the requirements of the most recently adopted version of the Michigan Building Code, and loads, vertical and horizontal, exerted on the soil shall not produce stresses exceeding those specified therein. The working stresses of wire rope and its fastenings shall not exceed 25 percent of the ultimate strength of the rope or fasteners. Working stresses for wind or seismic loads combined with deadloads may be increased as specified in the Michigan Building Code.
- (5) *Supports.* The supports for all signs or sign structures shall be placed in or upon private property and shall be securely built, constructed and erected in conformance with the requirements of this chapter.
- (6) *Fastenings.* Signs attached to masonry, concrete or steel shall be safely and securely fastened thereto by means of metal anchors, bolts, or approved expansion screws of sufficient size and anchorage to support safely the loads applied. Anchors which attach signs to masonry surfaces shall be inserted into mortar joints.
- (f) *Traffic and Pedestrian Hazards.* The placement, size, content, coloring or manner of illumination of signs shall not create traffic or pedestrian hazards. No sign shall make use of the words “stop,” “look,” “danger” or other word, phrase or symbol in a manner that is confusing or misleading. No sign or flashing light shall be erected or maintained in any manner which, by reason of its size, location, context, coloring or manner of illumination, shall constitute a traffic hazard or which shall interfere with the visibility of any traffic control device.
- (g) *Substitution.* Notwithstanding anything herein to the contrary, noncommercial copy may be substituted for commercial copy on any lawful sign structure, and any sign permitted by this article may contain a non-commercial message.
- (h) *Obstruction Prohibited.* No sign shall be placed so as to obstruct any fire escape, required exitway, window, or door opening used as a means of passage or as access for firefighting purposes.
- (i) *Obstruction to ventilation.* A sign shall not be attached in any form, shape or manner which will interfere with any opening required for ventilation by the building code; except that such signs may be erected in front of and may cover transom windows when not in violation of the provisions of this chapter.
- (j) *Maintenance.* All signs, sign frames, sign copy area, panels, structural elements, lamps and electrical hardware shall be maintained in good repair and working order, so as to present a neat and orderly appearance. Non-galvanized or corrosion-resistant materials shall be painted when necessary to prevent corrosion.
- (k) *Authorized sign contractors.* Every person before engaging or continuing in the business of constructing, repairing or dismantling signs, poster boards or other display signs in the city, shall first furnish the city a public liability insurance policy, approved by the city attorney, with minimum limits of \$300,000.00 combined single limit bodily injury and/or property damage, and the contractor agrees to indemnify the city from all damage suits or actions of every nature brought or claimed against the contractor for or on account of injuries to persons or damages to property received or sustained by any person or person through any act of omission or negligence of such erector, agents or employees in the erection, repair or dismantling of any sign, poster board or other display sign. Such policy shall contain a clause whereby such policy cannot be canceled until after a written notice of intention to cancel has been filed with the city clerk at least 30 days prior to the date of cancellation.
- (l) *Master Sign Plan* in HHS, HC, NC, GC, C, PMD, and P districts and for non-residential uses in R1, CN-SF, CN-Mid, CN, MD districts.

All non-residential buildings shall submit a master sign plan as part of their sign permit application. The master sign plan shall identify size, location, and lighting of all existing and proposed signs located or to be located on the building.

- (m) *Modification of standards:* Upon receipt by of an application for a permit that includes a request to modify any of the standards in this Chapter, the Planning Commission may, at any regular meeting or any special meeting duly called for that purpose, consider whether the proposed sign, if erected, will achieve the purposes of this Chapter. The applicant shall demonstrate the following to the satisfaction of the Planning Commission:

- (1) Whether the structure, dimensions and placement of the proposed sign generally conform to the character of signs in the neighborhood or business district;
- (2) Whether the proposed sign achieves the purposes of this Chapter as described in Section 122-861;
- (3) Whether the proposed sign achieves another public purpose consistent with the purpose of this Chapter or the City's Master Plan;
- (4) Whether the proposed sign achieves innovation and variety in design and compatibility;
- (5) The proposed sign shall be designed, constructed, operated and maintained to assure long-term compatibility with surrounding uses, buildings, and signs. Consideration shall be given to the placement, bulk, height and materials used in construction.
- (6) The proposed sign shall promote the use of signage in a socially and economically desirable manner and not be detrimental, hazardous, or disturbing to existing or future neighboring uses, persons, property or public welfare.
- (7) Appeals from the decision of the Planning Commission shall be heard by the zoning board of appeals.

Sec. 122-863. Definitions.

The following words, terms and phrases when used in this article shall have the meanings ascribed to them in this section, except where the context clearly indicates a different meaning:

Abandoned sign means a sign which directs attention to an object, product, place, activity, person, institution, organization or business which is no longer currently existing and is not maintained in accordance with the standards set forth in this chapter and contains or exhibits broken panels, visible rust, visible rot, damaged support structures, missing letters or which is otherwise dilapidated, unsightly, unkempt and for which the business or property owner is not accepting maintenance responsibility where such acts evidence an intent to abandon. Signs of local historical significance may not be considered abandoned

Building frontage means the outside perimeter measurements of the building wall on which wall the sign shall be placed.

Clearance. The vertical distance between the surface grade beneath the sign and the lowest point of the sign, including framework and embellishments.

Damaged sign means a sign or supporting structure which is torn, defaced, dented, smashed, broken, vandalized or destroyed.

Display surface means the sign area measured in square feet. Superficial ornamentation, trim or simple type appendages of non-message-bearing character shall not be included in determining display surfaces so long as they do not exceed 20 percent of sign area. The square footage of a two-, three- or four-faced sign shall mean the square footage of the largest face of the sign.

Flag means a flag bearing the official design of a nation, state, municipality, educational institution or organization.

Mechanical Sign means any signs that have any visible moving parts, mechanical movement or other apparent visible movement achieved by electrical or mechanical means or action of normal wind currents.

Mural means a design or representation painted, drawn, or otherwise attached to the exterior surface of a structure that does not advertise a business, product, service or commercial activity.

Nameplate means a sign identifying only the name, occupation, or profession and address of the business or occupant of the lot where the sign is placed.


Nonconforming sign means a sign which complied with the provisions of the chapter in effect at the time that it was erected but which does not conform to this article.

Seasonal display means decorations that do not convey a commercial message. These shall not be considered signage, and shall not require a permit.


Sign means a name, identification, description, announcement, display, illustration or insignia which is affixed to or painted or represented directly or indirectly upon a building, structure or piece of land, which directs attention to an object, product, place, authority, person, institution, organization or business and which is visible from any public street, right-of-way, sidewalk, alley, park or other places open to the public.

- (1) *Address sign* means a numerical address with numbers no greater than eight inches in height.


- (2) *Animated sign* means a sign that uses light emitting elements including but not limited to light bulbs, fixtures, LEDs, fiber optic lighting to create a continuously scrolling, flashing, or animated effect on any sign visible from the exterior of the building.
- (3) *Awning sign* means a sign that is painted on, attached to, or an integral part of an awning or canopy.
- (4) *Banner* means a sign, including inflatables, consisting of a large piece of cloth or similar flexible material, in public view, in front of a building or entranceway.
- (5) *Banner, overhead*, means a sign consisting of a large piece of cloth or similar flexible material suspended by wires in public view across a street or other public space.
- (6) *Billboard* means an off-premises sign.
- (7) *Building directory* means a sign identifying multiple tenants in a single building located above the street level façade (such as a multiple-story office or commercial building).
- (8) *Building-Mounted Sign* means a display sign that is painted on, adjacent to or attached to a building wall, door, window or related architectural feature. Such signs include, but are not limited to awning, projecting, wall and window signs.
- (9) *Directional sign* means a sign not exceeding two square feet which contain only noncommercial messages including designation of restrooms, telephone locations, restrictions on smoking, door openings, private control on premises vehicle or bicycle traffic and parking.
- (10) *Election sign* means a sign advocating or opposing a candidate for public office or a position on an issue to be determined at an election, but does not advertise any products, goods, services or businesses.
- (11) *Electronically illuminated message sign* means a sign with a message displayed on a surface with an electronically illuminated changeable copy area (often composed of LEDs).
- (12) *Ground sign* means any freestanding sign, not attached to a building, including monument or pole signs.
- (13) *Hanging sign* means a sign suspended under an awning, canopy, or marquee.
- (14) *Historical sign* means a sign designating a building as a historical structure, names of buildings, dates of construction, and other historic information.
- (15) *Illuminated sign* means a sign that provides artificial light directly or through transparent or translucent material from a source connected to or within such a sign, on which is illuminated by a light so shielded as to prevent direct rays from being visible from the public right-of-way.
- (16) *Inflatable sign* means a temporary sign that is intended to be expanded by air or other gas for its proper display or support.
- (17) *Marquee sign* means a projecting sign that accommodates changeable copy.
- (18) *Monument sign* means a freestanding sign supported by a pedestal or base, with permanent attachment to the ground.



- (19) *Off-premises sign* means a sign not relating to the premises on which such sign is located.
- (20) *On-premises sign* means a sign related to the premises on which such sign is located.
- (21) *Opinion sign* means a sign advocating or opposing an opinion or point of view, but does not advertise any products, goods, services or businesses.
- (22) *Pole sign* means a sign which is erected on a single freestanding mast or pole, not attached to a building.




- (23) *Portable sign* means a sign of a temporary nature, not securely anchored to the ground or to a building or structure, excluding sidewalk signs.
- (24) *Projecting sign* means a sign which is attached directly to the building wall, and which extends more than 18 inches from the face of the wall. A projecting sign shall project not more than four feet from the wall of a building and shall not project above the front wall of the building.




- (25) *Public signs* means a traffic or other governmentally erected notices, railroad crossing, danger and other temporary emergency signs, location of transit line, a railroad station or other public carrier or other non-advertising signs.
- (26) *Residential entry feature or sign* means an architectural feature with signage at each entrance to a residential subdivision, neighborhood, apartment community, condominium development, or mobile home condominium project.
- (27) *Roof sign* means a sign which is constructed and maintained upon or above the roof of a building, marquee, or parapet wall and which is wholly or partially supported by such building.
- (28) *Sidewalk sign* means a temporary sign placed within the right-of-way. These types of signs may include "A" Frame, "T" Frame or other temporary styles, which are not permanently affixed to the ground.
- (29) *Special Event Sign* means banners, pennants, balloons or festoons associated with a specific event and displayed for a specified and limited period of time, including commercial store sales, etc.
- (30) *Temporary Sign* means display signs, banners, balloons, festoons or other advertising devices constructed of cloth, canvas, fabric, plastic or other light temporary material, with or without a structural frame, or any other sign intended for a limited period of display, but not including decorative displays for holidays or public demonstration.
- (31) *Wall sign* means a sign which is painted on or attached directly to the surface of masonry, concrete, frame or other approved building walls, and which extends not more than 18 inches from the face of the wall and which does not extend above the parapet, eaves or building facade.

(32) *Window sign* means any sign within a building placed within 12 inches of a window or upon a window pane and that is visible from the exterior of the building not including merchandise located in a window.

Sign Area. The gross surface area within a single continuous perimeter enclosing the extreme limits of all sign copy or surface of any internally-illuminated sign, awning or canopy. Such perimeter shall not include any structural or framing elements lying outside the limits of such sign and not forming an integral part of the display. Where a sign has two (2) or more faces, the sign area shall equal the total area of all sign faces, except where two (2) faces are placed back to back and are at no point more than three feet (3') apart, the sign area shall equal the area of the larger single sign face.



Sign Height. The vertical distance measured from the average grade at the sign location to the highest point of the sign.



Sign Structure. Anything constructed or erected for the purpose of supporting a sign, the use of which requires permanent location on the ground or attachment to something having permanent location on the ground.

Sec. 122-864. Sign permit requirements.

a. Schedule of sign permit requirements

It shall be unlawful for any persons to erect, alter or relocate within the city any sign or other advertising structure without first obtaining a permit as indicated in the following schedule:

Type of Sign*	Permit Required	Sign Standards
Animated	Prohibited	---
Barber Pole	N	---
Building Mounted Signs		122-866 (b)
• Address Number/Nameplate	N	---
• Awning, Canopy	Y	122-866(b)(6)
• Building Directory	Y	122-866(b)(9)
• Menu	Y	122-866 (b)(8)
• Projecting	Y	122-866(b)(7)
• Wall	Y	122-866(b)(5)

Type of Sign*	Permit Required	Sign Standards
• Window	N	122-866(b)(10)
Directional	N	122-866(a)(6)
Flags	N	---
Ground (pole and monument)	Y	122-865(a)
• Billboards	Y	122-866(d)(2)
• Residential Entry Sign	Y	122-866(a)(8)
Historic Designation	N	---
Mural	Y	--
Opinion	N	122-866(c)(6)
Off-premises signs (except billboard)	Prohibited	---
Portable (except sidewalk signs)	Prohibited	---
Public	N	---
Roof	Prohibited	---
Temporary Signs		122-866(c)
• Banner	Y	122-866(c)(3)
• Overhead Banner	Y	122-866(c)(4)
• Construction – R1, MD, CN-SF, CN-Mid, CN and HHS	N	122-866(c)(1)
• Construction – All other districts	Y	122-866(c)(1)
• Election Sign	N	122-866(c)(5)
• For Sale, For Lease – Non-Residential	N	122-866(c)(1)
• For Sale, For Lease - Residential	N	122-866(c)(1)
• Garage Sale	N	---
• Inflatables	Y	122-866(c)(3)
• Special Events	Y	122-866(c)(1)
Sidewalk	Y	122-866(d)(3)
Traffic Control	N	---
Vehicle	N	---

(b) **Application for permits; contents.**

- (1) Application for sign permits shall be made upon forms provided by the building department.
- (2) Applications for signs other than overhead banners shall contain or have attached thereto the following information:
 - a. Name, telephone number and address of applicant.
 - b. Name, address and telephone number of owner or lessee of the premises upon which the sign is to be erected.
 - c. A written statement signed by the owner or lessee of the premises upon which the sign is to be erected, indicating his consent thereto, or the signed contract between the parties.
 - d. The address of the premises upon which the sign is to be attached or erected.
 - e. One set of plans showing the dimensions, materials, height and method of anchorage of the sign.
 - f. Position of the sign in relation to nearby buildings, structures and property lines.
 - g. Insurance policy or proof of financial security as required in section 122-862(k).
 - h. On electrical signs, certification by Underwriters Laboratory or some other recognized testing laboratory. Electrical sign installations shall comply with Article 600 of the National Electrical Code.
 - i. Such other information as deemed necessary to show compliance with this article.
- (3) Application for overhead banners shall contain or have attached thereto, the following information:
 - a. The name of organization or group sponsoring the banner.
 - b. A statement as to purpose of the banner.
 - c. Phrase on the banner, and/or sketch of the content
 - d. Location where banner is to be erected.

- e. The dates the banner will be hung.
- f. The name, address and telephone number of the applicant.
- g. Insurance policy or proof of financial security as required in section 122-862 (k).
- h. Such other information as deemed necessary to show compliance with this article and with Act No. 200 of the Public Acts of Michigan of 1969 (MCL 247.321 et seq., MSA 9.140(21) et seq.), and R247.271--R247.279 of the Michigan Administrative Code, 1979.

(4) Application for sidewalk signs shall include a sidewalk occupancy permit application.

Sec. 122-865. Unsafe and Prohibited signs

The following signs are prohibited in all zoning districts:

- (a) Notice of unsafe and prohibited signs. When any sign or sign structure becomes insecure, in danger of falling, or otherwise unsafe, or if any sign or sign structure shall be unlawfully installed, erected, or maintained in violation of any of the provisions of this chapter, or prohibited signs, it shall be considered a nuisance per se. The owner or lessee shall, upon receipt of written notice of the building official, immediately in the case of an unsafe sign, and in any case within not more than ten days, make such sign conform to the provisions of this article or shall remove it. If, after ten days, the notice is not complied with, the building official may remove such sign at the expense of the owner or lessee after having obtained an order from the administrative hearings bureau. The cost, including actual attorney fees, shall be assessed against the property as provided in Article VIII of the City Charter.
- (b) *Prohibited signs.*
 - (1) *Abandoned signs.*
 - (2) *Signs not complying with sign schedules.* Signs not complying with the requirements as set forth in schedules or tables contained in sections 122-866 and 122-868 respectively.
 - (3) *Signs not specifically permitted.* Signs which are not specifically permitted under the sections of this chapter.
 - (4) *Signs located near overhead electrical conductors.* Signs located with less than six feet horizontal clearance or 12 feet vertical clearance from overhead electrical conductors which are energized in excess of 250 volts.
 - (5) *Animated signs.*
 - (6) *Portable signs, not including sidewalk signs.*
 - (7) *Roof signs.*
 - (8) *Obscene Material.* Display of obscene material upon any sign is prohibited.
 - (9) *Mechanical Signs.*
 - (10) *Electronically illuminated message sign.*

Sec. 122-866. Sign Design Standards.

(a) Ground Signs

Zoning District	Maximum		Sign Setback Requirements
	Sign Area	Sign Height	
R1 ¹ , CN-SF ¹	16 sq. ft	6 ft.	Front yard – at least 3 feet from front property line. 10 feet from side or rear lot lines.
CN-Mid ¹ , CN ¹	16 sq. ft	8 ft.	Front yard – at least 3 feet from front property line. 10 feet from side or rear lot lines.
MD ¹ , HHS, HC	32 sq. ft	8 ft.	Front yard – at least 3 feet from front property line. 10 feet from side or rear lot lines.
NC	40 sq. ft	10 ft.	Front yard – at least 3 feet from front property line. 10 feet from side or rear lot lines.
GC	100 sq. ft	10 ft.	Front yard – at least 3 feet from front property line. 10 feet from side or rear lot lines.
C	Prohibited	Prohibited	--
P, PMD	100 sq. ft	35 ft	Front yard – at least 3 feet from front property line. 10 feet from side or rear lot lines

¹ For non-residential uses only

- (1.) *Number of Signs.* If permitted in a district, one monument or pole sign shall be allowed per lot or parcel. Lots that have more than 100 feet of frontage on two or more public streets shall be permitted one ground sign for each street frontage. A second ground signs shall have a maximum area of 50% of that otherwise permitted for a ground sign in the district .
 - (2.) *Height requirement* – no monument sign shall exceed 10 feet in height.
 - (3.) *Corner Clearance.* Signs shall be located outside of any corner clearance area as described in Section 122-649 of this Ordinance.
 - (4.) *Materials.* Ground or pole signs shall be constructed out of decorative materials that complement the design of principal buildings within the development. Natural materials such as stone, decorative masonry, wood, or metal are preferred sign construction materials.
 - (5.) *Landscaping.* Low level landscaping shall be provided around the base of the ground sign, but shall not obscure any part of the sign message.
 - (6.) *Directional Signs.* Shall not exceed 2 square feet of sign area.
 - (7.) *Drive-Through Signs.* Any use that includes a drive-through is permitted to have signs that relate to the drive-through facility, such as menu order board signs or information signs. The drive-through signs may have a maximum height of six feet and a maximum area of 32 sq. ft. per drive-through use, and shall not be included in the computation of total sign area for the parcel unless such signs are legible from a point of observation off the premises.
 - (8.) Residential entry signs shall be subject to the following standards;
 - a. Maximum of one (1) sign on each side of the entrance from a major street.
 - b. May not exceed the maximum area permitted for a ground sign in the applicable district.
- (b) *Building Mounted Signs.* Building mounted signs, including wall, awning, projecting and window signs shall comply with the following requirements:
- (1.) *Location.*
 - a. Building mounted signs may be located on any façade that faces a street, parking area, or vehicle circulation area that provides access to more than one parcel, or on a façade where a public entrance is located.
 - b. Upper story tenants may only have window signs, except as allowed for in subpart d.
 - c. Illuminated building mounted signs may not be located on a façade that faces a property line that abuts a residential zoning district unless the sign is set back at least 200 feet from the property line or

screening is provided that will completely obscure the view of the sign from the adjacent residential district.

- d. In the case of a building that contains two or more businesses each business that is directly accessible from the exterior of the building may have a building mounted sign on the façade where the primary or main customer entrance is located. For the purposes of calculating sign area in such multi-tenant buildings, the frontage controlled by each tenant on the façade where the entrance is located shall be used to calculate linear frontage.
- (2.) *Sign Area.*
- a. The total area of all building mounted signs, including wall, awning, projecting and window signs, shall not exceed three square feet for each one linear foot of building frontage on the side of the building the sign(s) are located on.
- (3.) *Minimum Height.* Awning and projecting signs shall maintain a minimum clearance of 8 feet between the grade level below the sign and the lowest part of the sign (including sign support devices).
- (4.) *Materials.*
- a. Building mounted signs shall incorporate exterior materials, finishes and colors that are the same, similar, or complementary to those used on the principal building.
 - b. Building mounted signs shall be professionally constructed using high-quality materials such as metal, stone, hard wood, or brass. The use of exposed neon tubing in conjunction with other types of materials to emphasize the business name or logo is permitted; however, neon tubing outlining windows or other architectural features is prohibited.
 - c. Internally lit box signs are prohibited.
 - d. External illumination of signs shall be limited to fully-shielded light fixtures with a maximum of 900 lumens. Such fixtures shall be mounted above the sign face with all light directed downward and concentrated on the area of the sign to prevent glare upon the street or adjacent property.
 - e. To minimize damage to masonry, all mounting and supports should be inserted into mortar joints and not into the face of the masonry.
- (5.) *Wall Signs.*
- a. No surface of a wall sign may project beyond or overhang any wall or permanent architectural feature by more than eighteen inches.
 - b. In non-residential districts wall signs cannot exceed 1 square foot for each linear foot of building frontage, or 100 square feet, whichever is less.
 - c. In residential districts, residential uses including multiple family dwelling containing 3 or more units, sorority, or fraternity houses, wall signs cannot exceed .5 square feet for each linear foot of building frontage, or 12 square feet.
 - d. In residential districts, for non-residential uses, wall signs cannot exceed 1 square foot for each linear foot of building frontage or 100 square feet whichever is less.
- (6.) *Awning Signs.*
- a. Sign lettering or logos may comprise up to 35% of the total exterior surface of an awning.
 - b. A minimum vertical clearance of 8 feet shall be provided between the lowest point of the awning and the sidewalk.
 - c. Internal illumination of awning signs is permitted where the permitted awning sign area is illuminated through semi-opaque material and the remainder of the awning consists of opaque material.
- (7.) *Projecting Signs.*
- a. Projecting signs shall be secured to the building by metal anchors, bolts, supports, rods or braces.
 - b. Projecting signs are limited to 24 square feet of sign area per sign face.
 - c. A minimum vertical clearance of eight feet shall be provided between the lowest point of the sign and the sidewalk.

(8.) *Menu Signs.* Menu signs shall be located in a permanently mounted display box on the surface of the building adjacent to the entry, and may have a maximum area of 3 square feet.

(9.) *Building Directory Signs.*

- a. The building directory sign shall be separate from any permitted signs accessory to the uses occupying the street level façade.
- b. The maximum sign area of the building directory sign shall be equal to five percent (5%) of the total permitted building mounted sign area.

(10.) *Window Signs.* May not occupy more than twenty-five percent (25 %) of the total transparent area of any individual window.

(c) *Temporary Signs.*

(1.) Schedule of regulations for temporary signs:

<i>Temporary Signs</i>	<i>Maximum Size (Square Feet)</i>	<i>Maximum Duration</i>
Banners	122-866(c)(3)	Two (2) permits allowed per calendar year. Each permit expires after 30 days.
Overhead Banners	122-866(c)(4)	30 days
Construction signs, residential and office properties R1, CN-SF, CN-Mid, CN, MD and HHS	12	The earliest of the following: to issuance of certificate of occupancy, final inspection of permit, or 7 days after completion of work.
Construction all other zones	64	Within 7 days after completion of construction
Special Event signs -	6	Three (3) permits allowed per calendar year. Each permit expires after 3 days.
For sale, for rent, for lease, pertaining to real estate, residential properties (no permit required)	12	3 days after purpose of sign fulfilled
For sale, for rent, for lease, signs relating to real estate, nonresidential zones	64	10 days after purpose of sign fulfilled
Election signs (no permit required)	Maximum size allowed by district by sign type	10 days after final election

(2.) *Temporary signs general.* Temporary signs may be constructed of materials other than those specified in the chapter, with or without structural frames. Temporary signs not regulated by the Schedule contained in section 122-866 (above) or which are listed in Schedule and exceed 20 square feet in total size must conform to all standards that apply to permanent signs in the zoning district which the temporary sign is erected with the exception of the material specifications.

- a. The permit shall specify the time period for which the temporary sign is authorized.
- b. Sizes of temporary signs shall conform to specifications in the Schedule (c) (1) above.
- c. The advertising message or copy contained on any permitted temporary sign shall pertain only to the business being currently conducted, or to be conducted on or within the premises on which such sign is erected or maintained. This provision does not apply to signs of a civic nature.

(3.) *Banners.* Banner requirements shall be as follows:

- a. The banner must be made of nonflammable material that will not shred and has adequate air holes. For banners hanging overhead across a street, roadway or highway the banner must contain at least three air holes for every 40 feet.
- b. The building department shall be permitted to inspect the banner or a sample of material prior to it being erected.
- c. The banner must be securely attached, sufficient to withstand storms, including strong gusts of wind and continuous pounding by the elements. The manner of attachment shall first be submitted to the building department.
- d. If a banner becomes partially unsecured, it shall be immediately reattached or removed by the entity which erected it.
- e. If a banner begins to shred, it shall be immediately repaired or removed by the entity which erected it.
- f. If the entity which erected the banner fails to comply with the standards of section(c) or fails to remove the banner by the time the permit expires, the city shall remove the banner and shall charge the cost thereof to the entity erecting the banner.
- g. Any banner permit may be canceled by the city if the installation becomes dangerous to motorists or pedestrians, unduly interferes with free movement of traffic or otherwise endangers the health, safety or welfare of persons in the city.
- h. No banners shall be erected unless a permit having a maximum duration of 30 days is first obtained from the building department. Only two permits may be issued per year.
- i. Banners or inflatables shall be attached to the premises to which the message contained thereon pertains.
- j. Banners or inflatables may not be strung overhead across roads, streets or highways.
- k. A banner shall not have displayed thereon any legion or symbol which is or purports to be an imitation of or resembles, or which may be mistaken for a traffic control device or which attempts to direct the movement of traffic.
- l. Banners or inflatables may not exceed 32 square feet.

(4.) *Overhead banners.* Requirements for overhead banners shall be as follows:

- a. An overhead banner shall be permitted for city approved events or other city or governmental sponsored messages
- b. The design, method of installation, and location of overhead banners shall not endanger persons using roads, streets or highways or unduly interfere with the free movement of traffic.
- c. An overhead banner shall have a minimum bottom height of 18 feet above the pavement, and shall not be placed closer than ten feet on either side of traffic signals, and shall not be placed so as to obstruct a clear view of traffic signals or other traffic control devices.
- d. An overhead banner shall:
 1. Not exceed 2.5 feet in height.
 2. Contain a snap top to permit a one-fourth-inch cable to run across the top.
- e. There shall be no more than two overhead banners placed at any time on a public road, street or highway with the exact location of such banners to be approved by the city building department, police department and the department of public works. When the banner shall be hung over a state trunkline, prior approval from the state department of transportation must be obtained.
- f. All overhead banners permits shall have a maximum duration of 30 days.

(5.) Election signs shall be subject to the following requirements;

- a. At polling places, on Election Day only, erected no less than 100 feet from the entrance of the polling place. Such signs may be located on the city right-of-way (margin).

- b. Such signs shall not be located on any city right-of-way except as permitted in subsection (5) of this section.

(d) *Other Signs.*

(1) *Billboards.* Outdoor advertising billboards may be erected in PMD zoning district adjacent to and visible from I-94, subject to the following regulations:

- a. Billboards are permitted in the adjacent area along I-94 as defined by the Highway Advertising Act of 1972, and may be the principal or primary use on the parcel in which it is located, notwithstanding Sec 122-862 (c).
- b. Billboards must be located and oriented in such a fashion as to be visible from I-94.
- c. New billboard permits will be issued only in the following cases:
 - 1. For non-digital billboards, when one non-conforming billboard is removed
 - 2. For digital billboards, when two non-conforming billboards are removed.
- d. Digital billboards - The message displayed on electronic message billboards may change a maximum of once every 6 seconds (an exemption from Sec. 122-866 (d) (1).
- e. Billboard structures shall not exceed 65 feet in height. All billboards must provide a setback from any adjacent residential zoning district equal to the height of the billboard.
- f. Billboard structures which have two or more panels stacked, one above the other, are not permitted.
- g. Double-faced billboard structures (two panels mounted on the same structure back-to-back) are permitted.
- h. Spacing between billboards shall be 1,000 feet as provided in the Highway Advertising Act of 1972, as amended.
- i. No more than the 672 square feet billboard shall be permitted regardless of land use zone, except when adjacent to a limited access highway and permitted by applicable state law.
- j. All billboard structures shall be of steel. No wood or other combustible material shall be permitted to support such signs.
- k. Billboards supported or maintained on the roof of a building are prohibited.
- l. Billboard structures shall be restricted to and used only with respect to interstate highways, freeways or primary highways as set forth in the Highway Advertising Act, Act No. 106 of the Public Acts of Michigan of 1972 (MCL 252.301 et seq., MSA 9.391(101) et seq.).

(2.) *Sidewalk Signs.*

- a. Sidewalk Signs may have a maximum area of 6 square feet per side.
- b. Sidewalk signs may be located on the sidewalk adjacent to the use to which they are accessory. Sidewalk signs shall be located such that they will not impede pedestrian traffic on the sidewalk, and such that they will not present a hazard to vehicular traffic.
- c. Sidewalk signs may not be permanently affixed to any object, structure, or the ground.
- d. Sidewalk signs may only be displayed during business hours and shall be removed when the business to which the sign is accessory is closed.
- e. Each business may have a maximum of one sidewalk sign.
- f. Sidewalk signs shall be made of durable materials with a finished appearance.
- g. Sidewalk signs made of decorative wood or decorative metal, that are architecturally compatible with the style, composition, materials, colors and details of the building may be increased to a maximum of 8 square feet.

Sec. 122-867. Nonconforming signs.

- (a) Nonconforming signs shall be permitted to continue as such until removed or altered, provided that such signs are maintained in accordance with the following requirements:
 - (1.) Expansion or relocation prohibited. Nonconforming signs shall not be expanded or relocated.
 - (2.) Servicing. Painting, servicing, cleaning, minor repairs, or changes in sign copy panel area (sign face changes) to a nonconforming sign structure shall be permitted, provided that the sign is restored to its original design and all work is in compliance with applicable structural and electrical codes and the requirements for all signs specified above.
 - (3.) Alterations. Alterations or changes to the sign structure of a nonconforming sign shall be subject to the following conditions:
 - a. The sign shall be brought into compliance with the requirements for all signs specified above.
 - b. The sign shall be brought into compliance with all applicable sign height and sign area standards for the type of sign, as specified above.
 - c. Nonconformities caused by inadequate ground sign setback at a ground sign's current location may be permitted to continue so that the existing support structure and wiring may be re-used, provided that permitted alterations will not increase this nonconformity, and provided that the ground sign is located entirely outside of all street rights-of-way and corner clearance areas.
 - d. Approval of appropriate permits by the Building Official.
- (b) *Signs of local historical significance.* Non-conforming signs located in the Historic District may be repaired, reconstructed, or relocated. For the purpose of this section, the applicant shall be required to provide the information under Section 122-864 for review by the Planning Commission.
 - (1.) The City Council may approve and or amend a list of existing non-conforming signs deemed to be of local historical significance by the Historic District Commission. Signs deemed historically significant may be repaired, reconstructed, or relocated, subject to review by the Building Official.
- (c) *Repair of signs.* This section shall not be construed to prevent the repair or restoration to a safe condition of any part of any existing, conforming or nonconforming sign when damaged by storm or other accidental emergency. Such repair or restoration shall be affected within 60 days of the event which causes the damage, unless an extension has been obtained in advance from the building department.
- (d) *Relocating signs.* Any sign that is moved to another location on the same or other premises shall be considered a new sign, and a permit shall be secured for any work performed in connection therewith when required by this article.

Sec. 122-868. Table of allowable signage

Type of Sign	Zoning Districts	Area	Height
Animated	Prohibited	--	---
Billboards	PMD	--	35 ft
Building Mounted		3sf/1lf of building frontage	
• Awning / Canopy	HHS, HC, NC, GC, C, P, PMD	35% of canopy/awning area	8 ft. min clearance
• Address Number/ Nameplate	All	2 sf	---
• Building Directory	HHS, HC, NC, GC, C, P, PMD	5% of building mounted sign area	---
• Menu	HHS, HC, NC, GC, C, P, PMD	3 sf	---
• Projecting	HHS, HC, NC, GC, C, P, PMD	24 sf per sign face	8 ft. min clearance
• Wall – residential	Residential	.5 sf/lf of building frontage or 12 sf	---
• Wall – non-residential	HHS, HC, NC, GC, C, P, PMD	1 sf/lf or 100 sf	---
• Window	HHS, HC, NC, GC, C, P, PMD	25% of individual window area	--
Changeable Copy	HHS, HC, NC, GC, C, P, PMD	part of sign area	--
Directional	All	2	4
Election	All	Maximum size allowed in district by sign type	
Flags	All	--	--
Ground			
	R1, CN-SF	16 sf	6 ft
	CN-Mid, CN	16 sf	8 ft
	MD, HHS	32 sf	8 ft
	HC, NC	40 sf	10 ft
	GC	100 sf	10 ft
	C	Not Permitted	---
	P, PMD	100 sf	35 ft
Historic	All	--	--
Opinion	All	Maximum size allowed in district by sign type	
Public	All	--	--
Portable	Prohibited	--	--
Residential Entry Sign	R1, CN-SF	16 sf	6 ft
	CN-Mid, CN	16 sf	8 ft
	MD, HHS	32 sf	8 ft
Roof	Prohibited	--	--
Temporary Sign	All	122-866(c)(1)	
Traffic Control	All	--	--

Secs. 122-869--122-910. Reserved.

ARTICLE XV. FLOOD DAMAGE PREVENTION*

*Cross reference(s)--Businesses, ch. 22; vehicles for hire, ch. 114.

Ord 1170-A, adopted 15 May 2012

Sec. 122-911. Flood hazard findings.

The flood hazard areas of the city are subject to periodic inundation which may result in safety hazards, loss of life, property and health, disruption of commerce and governmental services, extraordinary public expenditures for flood protection and relief, and impairment of the tax base, all of which adversely affect the public health, safety and welfare. The flood losses are caused by the cumulative effects of obstructions in floodplains causing increased flood heights and velocities, and by the occupancy in flood hazard areas by uses vulnerable to floods or hazardous to other lands which are inadequately elevated, floodproofed or otherwise protected from flood damages.

Sec. 122-912. Purpose.

It is the purpose of this article to protect the general public and all land within the city subject to flood losses by provisions designed to do the following:

- (1) Restrict or prohibit uses which are dangerous to health, safety and property in times of flood or which cause excessive increases in flood flow heights or velocities.
- (2) Require that uses vulnerable to floods, including facilities which serve such uses, be protected against flood damage at the time of initial construction.
- (3) Control the alteration of natural floodplains, stream channels and natural protective barriers which are involved in the accommodation of floodwaters.
- (4) Control filling, grading, dredging and other development which may increase erosion or flood damage.
- (5) Prevent or regulate the construction of flood barriers which will unnaturally divert floodwaters or which may increase flood hazards to other lands.

Sec. 122-913. Scope.

This article shall apply to all flood hazard areas. The boundaries of the flood hazard areas shall coincide with the boundaries of the areas indicated as within the limits of the 100 year flood in the report entitled *Flood Insurance Study*, Washtenaw County (All Jurisdictions) Community Number 260216, dated April 3, 2012, with accompanying Flood Insurance Rate maps and Flood Boundary and Floodway maps.

Within the flood hazard area zone, a regulatory floodway shall be designated. The boundaries of the regulatory floodway shall coincide with the floodway boundaries indicated on the flood boundary and floodway maps. The study and accompanying maps are adopted by reference, appended, and declared to be a part of this chapter. The term flood hazard area, as used in this chapter, shall mean flood hazard area zone and the term floodway, shall mean the designated regulatory floodway.

- (1) AGENCY DESIGNATED. Pursuant to the provisions of the state construction code, in accordance with Section 8b(6) of Act 230, of the Public Acts of 1972, as amended, the Building Official of the City of Ypsilanti is hereby designated as the enforcing agency to discharge the responsibility of the City of Ypsilanti under Act 230, of the Public Acts of 1972, as amended, State of Michigan. The City of Ypsilanti assumes responsibility for the administration and enforcement of said Act throughout the corporate limits of the community adopting this ordinance.
- (2) CODE APPENDIX ENFORCED. Pursuant to the provisions of the state construction code, in accordance with Section 8b(6) of Act 230, of the Public Acts of 1972, as amended, Appendix G of the Michigan Building Code shall be enforced by the enforcing agency within the City of Ypsilanti.
- (3) DESIGNATION OF REGULATED FLOOD PRONE HAZARD AREAS. The Federal Emergency Management Agency (FEMA) Flood Insurance Study (FIS) Entitled Washtenaw County, Michigan (All Jurisdictions) and dated April 3, 2012 and the Flood Insurance Rate Map(s) (FIRMS) panel number(s) of 26161C; 00269E, 0288E, 0407E, and 0426E dated April 3, 2012 are adopted by reference for the purposes of administration of the Michigan Construction Code, and declared to be a part of Section 1612.3 of the Michigan Building Code, and to provide the content of the "Flood Hazards" section of Table R301.2(1) of the Michigan Residential Code.

Sec. 122-914. Regulation of uses in floodplain areas.

Any proposed occupation, structure, excavation, fill, extraction, grading or scraping and any substantial improvement to an occupation, structure or area shall be reviewed and approved by the Planning Commission. "Substantial improvement" means any repair, reconstruction or improvement of an occupation, structure or area, the cost of which equals or exceeds 50 percent of the market value of the structure either, (i) before the improvement or repair is started or (ii) if the occupation, structure or area has been damaged and is being restored, before the damage occurred. For the purpose of this definition, "substantial improvement" is considered to occur when the first alteration of any wall, ceiling, floor or other structural member commences, whether or not that alteration affects the external dimensions of the structure or area. The term does not, however, include either (i) any project for improvement of a structure to comply with state or local health, sanitary or safety code specifications which are solely necessary to assure safe living conditions, or (ii) any alteration of a structure listed on the National Register of Historic Places or state register of historic places.

(1) *Permitted uses.* The following uses may be permitted in those portions of the floodplain which are not a floodway, to the extent that they are allowed uses within a given zoning district and subject to the construction standards of building code in effect for the city at the time of construction:

- a. Residential and nonresidential structures provided that the building official certifies to the Planning Commission that the proposed provisions for flood resistant construction, flood proofing or elevation meet or exceed the standards set forth in the city's building code.
- b. Recreational uses such as parks, swimming areas, picnic grounds, ball fields, hiking or biking trails, and wildlife and nature preserves.
- c. Residential support uses such as lawns, gardens, play areas, and parking areas which do not result in the filling in of floodplain areas.
- d. Industrial and commercial support uses which are open in nature such as loading areas or parking areas which do not result in the filling in of any floodplain areas.
- e. Utility facilities such as power plants, transmission lines, pipelines not crossing a lake or waterway, lighting facilities, and navigational and drainage aids.
- f. Piers, boat ramps, bridges, and other such water related uses subject to approval by the water resources commission of the state department of natural resources.
- g. Fencing of any type, provided that such fencing shall not be located in that portion of the floodplain that is a floodway or other areas essential to the conveyance of floodwaters.
- h. Sidewalks, driveways, patios, and similar structures when constructed at grade.
- i. Fill or removal of topsoil, sand, and gravel or other extraction operations, in that portion of a floodplain which is not a floodway provided the following conditions are met:
 1. Proof that proper long term maintenance will be provided so that the flood-carrying capacity is not diminished.
 2. Any fill or excavated area shall be protected from erosion during and after operations by rip-rap, vegetative cover, bulk-heading, or other approved means.
 3. The proposed filling in of land, provided that material equal to 110 percent of the fill volume is removed elsewhere from such premises and adjusted to be capable of storing floodwaters. Structures and parking areas may be permitted on such filled land provided the elevation of the filled land is at least one foot above the base flood elevation. A permit issued by the state department of natural resources under the state's floodplain regulatory authority, Act No. 451 of the Public Acts of Michigan of 1994 (MCL 324.3101 et seq., MSA 13A.3101 et seq.), shall be obtained prior to the filling of land in the floodplain. A copy of the state department of natural resources permit shall be provided to the city building inspection division prior to the issuance of a building permit..
- j. Streets, railroads, and other rights-of-way.
- k. Pavilions, open amphitheatres, detached garages, raised patios and decks, and other accessory structures provided they are properly anchored and made flood resistant and are not located in a floodway or other area essential to the conveyance of floodwaters.
- l. Facilities for the storage and detention/retention of stormwater.

- m. Storage yards for heavy equipment, materials, or machinery.
- (2) *Prohibited uses.* The following uses are not allowed in a floodplain area under any circumstances:
 - a. New residential construction or occupation, including mobile homes, manufactured homes or pre-manufactured homes, are specifically prohibited in that portion of the floodplain that is a floodway. Other types of construction and occupation may be allowed in that portion of the floodplain that is a floodway; however, a hydraulic analysis shall be required which demonstrates that occupation and resulting obstruction of the floodway will not restrict the flood carrying capacity of the watercourse.
 - b. A landfill, dump, junkyard, recycling center or hazardous waste storage or treatment facility are expressly prohibited in a floodplain area.
 - c. The storage or processing of materials which in time of flooding become buoyant, flammable, explosive or otherwise injurious to public health, is expressly prohibited within a floodplain area.
 - d. On-site sewage disposal systems shall be permitted within a floodplain area.
 - e. Any encroachment which would cause any increase in the base flood level.
- (4) The importance of the services provided by the development to the community.
- (5) The requirement of the proposed development for a waterfront location and the availability of alternate locations not subject to flooding.
- (6) The compatibility of the proposed use with existing and anticipated development of the surrounding area and the floodplain management program of the area.
- (7) The safety of access to the property in times of flood for ordinary and emergency vehicles.
- (8) The measures taken to assure adequate drainage so as to reduce exposure to flood hazards.
- (9) The Planning Commission may attach certain conditions to an approval such as limitations on period of use and operation; imposition of operational controls, deed restrictions, performance bonds, and covenants; or requirements for construction of dikes, levees, and other protection measures.
- (b) *Building official's responsibility.* Prior to site plans being submitted to the Planning Commission the building official shall:
 - (1) Certify that the proposed construction, occupation or substantial improvement complies with the city building code adopted in chapter 18.
 - (2) Where permits are required by other state or federal agencies, a copy of the approved permit shall be provided, by the applicant, prior to review by the Planning Commission.
 - (3) Cause to be verified and recorded on the site plan and building plans, the actual elevation (in relation to mean sea level) of the lowest floor (including basement) of all new or substantially improved structures.
 - (4) Cause to be verified and recorded on the site plan and building plan, the actual elevation (in relation to mean sea level) to which the new or substantially improved structures have or will be floodproofed.
 - (5) Require that all site plans and building plans for occupation, construction or substantial improvement within the floodplain have been prepared under the supervision of a registered professional engineer or architect. All site plans and building plans shall be signed by the registered professional engineer or architect.
 - (6) Certify that notification has been made to adjacent communities and the state flood control coordinator of a proposed development, construction, occupation, substantial improvement alteration or relocation of a

Sec. 122-915. Review procedures.

- (a) *Site plan review.* All development, construction, occupation or substantial improvement proposals located within a floodplain area shall be reviewed by the City Planner or Planning Commission in accordance with the site plan review procedures of Article IV of this chapter, and the "Rules of the Washtenaw County Water Resources Commissioner." The City Planner or Planning Commission, when reviewing an application for occupation, construction or substantial improvement in a floodplain, shall consider the following standards before rendering a decision:
 - (1) Any possible danger to life and property as a result of increased flood heights or velocities caused by encroachments on the floodplain.
 - (2) The danger that materials may be swept to other lands or downstream to the injury or property loss of others.
 - (3) The susceptibility of the proposed development and its contents to flood damage.

watercourse, and submit evidence of such notification to the Federal Insurance Administration and the Planning Commission.

- (7) Be available at the meeting of the Planning Commission when such plans are reviewed to answer any questions relative to the floodplain or construction standards.

Sec. 122-916. Building permit requirements.

No occupation, building or structure within a floodplain area shall be erected, moved, repaired, altered, or razed until a building permit shall have been obtained from the building official in accordance with the customary building permit requirements under chapter 18. For structures located within a floodplain, the following additional information shall be included with the building permit, and shall become a condition of the permit. All plans, specifications and conditions approved by the Planning Commission. The plans shall include all of the information required by section 122-915.

Sec. 122-917. Appeals, variances.

The zoning board of appeals shall hear and decide appeals and requests for variances from the requirements of this article, In accordance with the procedures and conditions set forth in this article. Prior to hearing of the appeal, the city planner shall certify to the zoning board of appeals that notices as required under this article have been made. Further, the city planner shall certify to the zoning board of appeals that the immediate downstream community's chief elected official and the state flood control coordinator have been notified of the request for appeals or variance and of the public hearing. Appeals or variances relating to the construction standards as set forth in the building code, shall be heard by the construction board of appeals as outlined in chapter 18. In addition, the following conditions shall be applied to variances granted from the floodplain regulations of this article:

- (1) Variances shall be issued upon a determination that the granting of a variance will not result in increased flood heights, additional threats to public safety, extraordinary public expense, public nuisances, or cause fraud on or victimization of the public.
- (2) Any applicant to whom a variance is granted shall be given a written notice specifying the difference between the base flood elevation and the elevation at which a structure is being built, and a statement that the cost of flood insurance will be commensurate with the increased risk resulting from the reduced lowest floor elevation.
- (3) All such variances to this article shall be maintained in a record and reported to the

Federal Insurance Administration and the state flood control coordinator upon request.

Sec. 122-918. Disclaimer of liability.

The degree of flood protection required by this article is considered the minimum necessary and reasonable for regulatory purposes. Larger floods may occur at any time, and excessive floodwater heights may be experienced due to manmade and natural causes. This article does not imply that areas outside the special flood hazard areas, or uses permitted within such areas, shall remain free from flooding or flood damages. This article shall not create a liability on the part of the city or any officer or employee thereof for any flood damage that results from compliance with or reliance upon this article or any administrative decision lawfully made thereunder.

Zoning Map

City of Ypsilanti

Washtenaw County, Michigan

Zoning Districts

Planned Unit Developments

 PUD: Planned Unit Development


Limited Building Types


-  AB: Apartment Building
-  CS: Commercial Mixed-Use Small
-  MA: Mansion
-  SC: Single-story Commercial
-  SC, CS: Single-story Commercial, Small Mixed-Use
-  TH, AB, CA: Townhouse, Apt Bldg, Courtyard Apt
-  TH, AH, AB: Townhouse, Apt House, Apt Bldg



Districts

-  P - Park
-  R-1 - Single-Family Residential
-  MD - Multi-Dwelling
-  PMD - Production, Manufacturing, Distribution
-  CN-SF - Core Neighborhood Single-Family
-  CN-Mid - Core Neighborhood Mid
-  CN - Core Neighborhood
-  C - Center
-  NC - Neighborhood Corridor
-  HC - Historic Corridor
-  GC - General Corridor
-  HHS - Health and Human Services
-  Eastern Michigan University

Adopted 15 December 2014
Revised 01 September 2015
Revised 03 November 2016


MAYOR SIGNATURE


CLERK SIGNATURE





ACTION MINUTES

CITY OF YPSILANTI
REGULAR COUNCIL MEETING
CITY COUNCIL CHAMBERS – ONE SOUTH HURON ST.
YPSILANTI, MI 48197
TUESDAY, MARCH 21, 2017
7:00 p.m.

I. CALL TO ORDER –

The meeting was called to order at 7:06 p.m.

II. ROLL CALL –

Council Member Bashert	Present	Council Member Robb	Present
Mayor Pro-Tem Brown	Present	Council Member Vogt	Present
Council Member Murdock	Present	Mayor Edmonds	Present
Council Member Richardson	Absent		

III. INVOCATION –

IV. PLEDGE OF ALLEGIANCE –

"I pledge allegiance to the flag, of the United States of America, and to the Republic for which it stands, one nation, under God, indivisible, with liberty and justice for all."

V. AGENDA APPROVAL –

The agenda was approved as amended

Change: Move Resolution No. 2017-063 from Section XI, Consent Agenda, to Section XII, Resolutions/Motions/Discussions.

VI. INTRODUCTIONS –

VII. PRESENTATIONS -

Medical Marijuana – City Planner Bonnie Wessler and Assistant City Attorney Dan DuChene

Resolution No. 2017-055, supporting the display of the Transgender Pride flag.

Offered By: Council Member Bashert; Seconded By: Council Member Murdock

Approved: Yes – 6; No – 0; Absent – 1 (Richardson)

VIII. AUDIENCE PARTICIPATION –

IX. REMARKS BY THE MAYOR –

X. ORDINANCES – FIRST READING –

Ordinance No. 1285

1. An ordinance to amend Section 58-32 of the Ypsilanti City Code to add two youth non-voting members to the Human Relations Commission.
 - A. Resolution No. 2017-060, determination
Offered By: Council Member Murdock; Seconded By: Mayor Pro-Tem Brown
Approved: Yes – 6; No – 0; Absent – 1 (Richardson)
 - B. Open public hearing
 - C. Resolution No. 2017-061, close public hearing
Offered By: Council Member Murdock; Seconded By: Council Member Bashert
Approved: Yes – 6; No – 0; Absent – 1 (Richardson)

XI. CONSENT AGENDA –

Resolution No. 2017 – 062

- ~~1. Resolution No. 2017-063, opposing elimination and reduction of US Department of Housing and Urban Development programs which are vital to Washtenaw County residents.~~ **(Moved and Heard during Section XII, Resolutions/Motions/Discussions)**
2. Resolution No. 2017-064, approving appointments to Boards and Commissions.
Offered By: Mayor Pro-Tem Brown; Seconded By: Council Member Bashert
Approved: Yes – 6; No – 0; Absent – 1 (Richardson)
3. Resolution No. 2017-065, approving appointments to Boards and Commissions (non-residents).
Offered By: Mayor Pro-Tem Brown; Seconded By: Council Member Bashert
Approved: Yes – 6; No – 0; Absent – 1 (Richardson)
4. Resolution No. 2017-066, approving minutes of January 24 and January 31, 2017.
Offered By: Mayor Pro-Tem Brown; Seconded By: Council Member Bashert
Approved: Yes – 6; No – 0; Absent – 1 (Richardson)

XII. RESOLUTIONS/MOTIONS/DISCUSSIONS –

1. Resolution No. 2017-067, approving budget amendments changing loan to a fund transfer for the uncollected reimbursement from MNRTF of \$328,490.00.
Offered By: Council Member Robb; Seconded By: Council Member Vogt
Approved: Yes – 6; No – 0; Absent – 1 (Richardson)
2. Resolution No. 2017-068, approving Ordinance 1284, to amend Chapter 122 (Zoning ordinance) of the City's Code of Ordinances. ***(Second Reading)***
Offered By: Council Member Vogt; Seconded By: Mayor Pro-Tem Brown
Approved as Amended: Yes – 6; No – 0; Absent – 1 (Richardson)
3. Resolution No, 2017-069, adopting a five-year road funding plan.
Offered By: Mayor Pro-Tem Brown; Seconded By: Council Member Bashert
Approved: Yes – 6; No – 0; Absent – 1 (Richardson)
4. Resolution No. 2017-070, approving City Manager MERS Defined Compensation Plan.
Offered By: Council Member Vogt; Seconded By: Mayor Pro-Tem Brown
Approved: Yes – 6; No – 0; Absent – 1 (Richardson)

5. Resolution No. 2017-071, scheduling a work session for the purpose of discussing and approving a list of priorities and expectations for the City Manager.
Offered By: Mayor Pro-Tem Brown; Seconded By: Council Member Murdock
Tabled: Yes – 6; No – 0; Absent – 1 (Richardson)
6. Resolution No. 2017-073, opposing oil transport through the Enbridge Energy Line 5 pipeline.
(added 3/20/17)
Offered By: Council Member Bashert; Seconded By: Council Member Murdock
Approved: Yes – 6; No – 0; Absent – 1 (Richardson)
7. Resolution No. 2017-063, opposing elimination and reduction of US Department of Housing and Urban Development programs which are vital to Washtenaw County residents.
Offered By: Mayor Pro-Tem Brown; Seconded By: Council Member Murdock
Approved: Yes – 6; No – 0; Absent – 1 (Richardson)

XIII. LIASON REPORTS –

- A. SEMCOG Update
- B. Washtenaw Area Transportation Study
- C. Urban County
- D. Ypsilanti Downtown Development Authority
- E. Eastern Washtenaw Safety Alliance
- F. Police-Community Relations/Black Lives Matter Joint Task Force
- G. Friends of Rutherford Pool
- H. Housing Equity Leadership Team
- I. Economic Development Coordinating Committee

XIII. COUNCIL PROPOSED BUSINESS –

XIV. COMMUNICATIONS FROM THE MAYOR –

XV. COMMUNICATIONS FROM THE CITY MANAGER –

XVI. COMMUNICATIONS –

XVII. AUDIENCE PARTICIPATION –

XVIII. REMARKS FROM THE MAYOR –

XIX. CLOSED SESSION –

Closed Session to discuss attorney-client privileged communication - OMA 15.267, Section 8(h)

Adjourned to Closed Session:

Offered By: Council Member Vogt; Seconded By: Mayor Pro-Tem Brown
Approved: Yes – 5; No – 1 (Murdock); Absent – 1 (Richardson)

Reconvene to Open Session:

Offered By: Council Member Vogt; Seconded By: Mayor Pro-Tem Brown
Approved: Yes – 5; No – 1 (Robb); Absent – 1 (Richardson)

XX. ADJOURNMENT -

Resolution No. 2017-072, adjourning the City Council meeting.
The meeting adjourned at 10:11 p.m